

*Murray's*

HAND-BOOK

FRANCE

FILE COPY

# MURRAY'S HAND-BOOKS FOR TRAVELLERS.

---

- HAND-BOOK OF TRAVEL-TALK. Being Conversations in English, German, French, and Italian. 18mo, 5s.
- NORTH GERMANY. THE RHINE, HOLLAND, BELGIUM, and PRUSSIA. Map. Post 8vo, 12s.
- PANORAMA OF THE RHINE, from SCHAFFHAUSEN to the NORTH SEA. 8vo, 10s. 6d.
- SOUTH GERMANY. The TYROL—BAVARIA—AUSTRIA—SALZBURG. The AUSTRIAN and BAVARIAN ALPS, the DANUBE, from ULM to the BLACK SEA. Map. Post 8vo.
- HISTORY OF GERMANY. Woodcuts. 12mo, 7s. 6d.
- MAPS AND PLANS OF CITIES AND TOWNS IN GERMANY AND SWITZERLAND. - Post 8vo.
- PAINTING.—GERMAN AND DUTCH SCHOOLS. From the German. Edited by SIR EDMUND HEAD. Post 8vo, 12s.
- SWITZERLAND, the ALPS of SAVOY, and PIEDMONT. Map. Post 8vo, 10s.
- NORTHERN ITALY. FLORENCE, SARDINIA, GENOA, THE RIVIERA, VENICE, LOMBARDY, and TUSCANY. Maps. Post 8vo, 12s.
- CENTRAL ITALY. ROME, the PAPAL STATES, and the CITIES of ETRURIA. Maps. Post 8vo.
- PAINTING.—ITALIAN SCHOOLS. From the German. Edited by C. L. EASTLAKE, R.A. Woodcuts. Post 8vo.
- DICTIONARY OF GREEK & ROMAN ANTIQUITIES, Woodcuts. Post 8vo, 10s. 6d.
- MALTA, the IONIAN ISLANDS, TURKEY, ASIA MINOR, and CONSTANTINOPLE. Maps. Post 8vo, 15s.
- EGYPT, THEBES, the NILE, ALEXANDRIA, CAIRO, the PYRAMIDS, MOUNT SINAI, the OASES, &c. Map. Post 8vo, 15s.
- FRANCE, NORMANDY, BRITTANY, the RIVER LOIRE, SEINE, RHONE, and GARONNE; the FRENCH ALPS, DAUPHINE, PROVENCE, and the PYRENEES. Maps. Post 8vo, 12s.
- SPAIN, ANDALUSIA, RONDA, GRANADA, VALENCIA, CATALONIA, GALLICIA, THE ASTURIAS, CASTILES, AND BASQUE PROVINCES, ARRAGON, AND NAVARRE. Maps. Post 8vo, 16s.
- PAINTING.—FRENCH AND SPANISH SCHOOLS. By SIR EDMUND HEAD, BART. Post 8vo, 12s.
- NORTHERN EUROPE, DENMARK, NORWAY, SWEDEN, RUSSIA, FINLAND, and ICELAND. Maps. 2 vols. post 8vo, 24s.
- LONDON. PAST AND PRESENT. Post 8vo, 16s.
- ENGLAND AND WALES. Map. Post 8vo. (*nearly ready*).
- LONDON GALLERIES OF ART. Post 8vo, 10s.
- WINDSOR AND WESTMINSTER. 16mo, 2s. 6d. each.



# BOOKS FOR TRAVELLERS.

---

THE SANATIVE INFLUENCE OF CLIMATE. With an Account of the best Places of Resort for Invalids. By SIR JAMES CLARK, Bart., M.D. Post 8vo, 10s. 6d.

LORD BYRON'S CHILDE HAROLD. With Illustrations of Places visited in SPAIN, PORTUGAL, ITALY, HOLLAND, &c. Vignettes. 8vo, 21s.

SIR DAVID WILKIE'S LIFE, LETTERS, AND CRITICAL REMARKS ON WORKS OF ART IN FRANCE, the NETHERLANDS, ITALY, SPAIN, EGYPT, and the HOLY LAND. BY ALLAN CUNNINGHAM. Portrait. 3 vols. 8vo, 42s.

A MANUAL OF SCIENTIFIC ENQUIRY; For the use of Travellers. Edited by SIR J. HERSCHELL, Bart. Maps. Post 8vo, 10s. 6d.

HUMBOLDT'S COSMOS. A Physical Description of the Universe. Translated by Mrs. SABINE. 2 vols. Post 8vo, 5s.

HUMBOLDT'S ASPECTS OF NATURE IN DIFFERENT LANDS AND IN DIFFERENT CLIMATES. Translated by Mrs. SABINE. 2 vols. Post 8vo, 5s.

PHYSICAL GEOGRAPHY. By MRS. SOMERVILLE. Portrait. 2 vols. 12mo, 12s.

CONNEXION OF THE PHYSICAL SCIENCES. By MRS. SOMERVILLE. Plates. Fcap. 8vo, 10s. 6d.

PRINCIPLES OF GEOLOGY. By SIR CHARLES LYELL. Woodcuts. 8vo, 18s.

LORD BYRON'S LIFE, LETTERS, AND JOURNALS. Edited, with Notes, by THOMAS MOORE. Portraits. Royal 8vo, 15s.

LORD BYRON'S POETICAL WORKS. Collected and arranged, with all the Notes, &c. Portrait. Royal 8vo, 15s.

BOSWELL'S LIFE OF DR. JOHNSON. Edited, with Notes, by MR. CROKER. Portraits. Royal 8vo, 18s.

SPECIMENS OF THE BRITISH POETS. With Biographical and Critical Notices. By THOMAS CAMPBELL. Portrait. Royal 8vo, 15s.

REV. GEORGE CRABBE'S LIFE AND POETICAL WORKS. Edited by his Son. Portrait. Royal 8vo, 15s.

OUTLINES OF ENGLISH LITERATURE. By T. B. SHAW. 12mo, 12s.

HORACE. A NEW EDITION OF THE TEXT. Illustrated by Gems, Statues, Vases, &c., chiefly from the Antique. Vignettes. 8vo, 42s.

CONSOLATIONS IN TRAVEL; or, the Last Days of a Philosopher. By SIR HUMPHRY DAVY. With Illustrations. Fcap. 8vo.

SALMONIA, OR DAYS OF FLY FISHING. By SIR HUMPHRY DAVY. With Illustrations. Fcap. 8vo.

SPECIMENS OF THE TABLE TALK OF S. T. COLERIDGE. Fcap. 8vo.

THE INTELLECTUAL POWERS AND THE INVESTIGATION OF TRUTH. By JOHN ABERCROMBIE, M.D. Fcap. 8vo, 6s. 6d.

PHILOSOPHY OF THE MORAL FEELINGS. By JOHN ABERCROMBIE, M.D. Fcap. 8vo, 4s.

JOHN MURRAY, ALBEMARLE STREET.

June, 1850.

I found all the Miss  
notes in the notes

have been incorporated

whenever 1864

~~in the notes~~

J.P.

280  
280



*Notes by J H Parker  
revised Oxford*

A

H A N D - B O O K

FOR

TRAVELLERS IN FRANCE.

## NOTICE TO THIS EDITION.

THE Editor of the 'Hand-book for Travellers in France' requests that travellers who may, in the use of the Work, detect any faults or omissions which they can correct *from personal knowledge*, will have the kindness to mark them down on the spot and communicate to him a notice of the same, favouring him at the same time with their names—addressed to the care of Mr. Murray, Albemarle Street. They may be reminded that by such communications they are not merely furnishing the means of improving the Hand-book, but are contributing to the benefit, information, and comfort of future travellers in general.

\* \* No attention can be paid to letters from innkeepers in praise of their own houses; and the postage of them is so onerous that they cannot be received.

CAUTION TO TRAVELLERS.—By a recent Act of Parliament the introduction into England of *foreign pirated Editions* of the works of British authors, in which the copyright subsists, *is totally prohibited*. Travellers will therefore bear in mind that even a single copy is contraband, and is liable to seizure at the English Custom-house.

CAUTION TO INNKEEPERS AND OTHERS.—The Editor of the Hand-books has learned from various quarters that a person or persons have of late been extorting money from innkeepers, tradespeople, artists, and others, on the Continent, under pretext of procuring recommendations and favourable notices of them and their establishments in the Hand-books for Travellers. The Editor, therefore, thinks proper to warn all whom it may concern, that recommendations in the Hand-books are not to be obtained by purchase, and that the persons alluded to are not only unauthorised by him, but are totally unknown to him. All those, therefore, who put confidence in such promises may rest assured that they will be defrauded of their money without attaining their object. English travellers are requested to explain this to Innkeepers in remote situations, who are liable to become victims to such impositions. Notices to this effect have been inserted by the Editor in the principal English and Foreign newspapers.—1847.



# H A N D - B O O K

FOR

## TRAVELLERS IN FRANCE:

BEING

### A GUIDE

TO

NORMANDY, BRITTANY;

THE RIVERS LOIRE, SEINE, RHÔNE, AND GARONNE;

THE FRENCH ALPS, DAUPHINÉ, PROVENCE,  
AND THE PYRENEES:

WITH

DESCRIPTIONS OF THE PRINCIPAL ROUTES, *RAILWAYS*, THE APPROACHES  
TO ITALY, THE CHIEF WATERING PLACES, ETC.

WITH FIVE TRAVELLING MAPS.

*Third Edition, Revised.*

L O N D O N :

JOHN MURRAY, ALBEMARLE STREET.

A. & W. GALIGNANI & CO., STASSIN & XAVIER, PARIS;  
LONGMAN, LEIPZIG.

---

1848.

THE ENGLISH EDITIONS OF THE HAND-BOOKS FOR TRAVELLERS ARE  
PUBLISHED

*In France, at*

AMIENS	BY CARON.
AVRANCHES	— LANSARD DESJARDINS.
BAYONNE	— JAYMEBON.
BORDEAUX	— CHAMAS; LAWALLE.
BOULOGNE	— WATEL & MERRIDEW.
BREST	— HEBERT.
CAEN	— AVONDE; MANCEL.
CALAIS	— LEROY.
DIEPPE	— MARAIS.
DINANT	— COSTE.
DUNKERQUE	— LEYSCHOCHART.
GRENOBLE	— VELLOTT & COMP.
HAVRE	— COCHARD.
LILLE	— VANACKERE.
LYONS	— BOHAIRE.
MARSEILLE	— TERRIS.
MASVERT	— CHAIX.

METZ	BY WARION.
MONTPELLIER	— LEVALLE.
NANCY	— GONET.
NANTES	— GUE'RAUD.
ORLEANS	— GATINEAU, <del>RESTY.</del>
PARIS	— GALIGNANI; STASSIN ET XAVIER.
PAU	— MARKAM.
PERPIGNAN	— JULIA, FRÈRES.
REIMS	— BRISSART BINET.
ROUEN	— LEBRUMENT.
ST. MALO	— HUE.
STRASBOURG	— LEVRAULT; LAGIER.
TOULON	— MONGE ET VILLAMUS.
TOULOUSE	— GALLON; H. LEBON.
TOURS	— AIGRE; BONTE'.
TROYES	— LALOY.

*In Germany, Holland, and Belgium, at*

AIX-LA- CHAPELLE	} BY I. D. MAYER; L. KOHNEN.
AMSTERDAM	
ANTWERP	— J. MULLER.
BADEN-BADEN	— MAX. KORNICKER.
BERLIN	— D. R. MARX.
BRUSSELS	— A. DUNCKER.
	— C. MUQUARDT; KIESS- LING & CO.; A. DECQ; W. TODD.
CARLSRUHE	— A. BIELEFELD.
COBLENTZ	— BAEDEKER.
COLOGNE	— L. KOHNEN; A. BAEDEKER.
DRESDEN	— ARNOLD.
FRANKFURT	— C. JÜGEL; F. WILMANS.
GRÄTZ	— DAMIAN & SORGE.
HAMBURG	— PERTHES, BESSER, & MAUKE.
HEIDELBERG	— J. C. B. MOHR.

LEIPZIG	BY T. O. WEIGEL.
MANNHEIM	— ARTARIA & FONTAINE.
MILAN	— ARTERIA, JOS. VALLARDI.
MÜNICH	— LITERARISCH-ARTISTISCHE ANSTALT & I. PALM.
NÜRNBERG	— CAMPE.
PESTH	— HARTLEBEN & G. HECKEN- AST.
PRAGUE	— CALVE.
ROTTERDAM	— A. BAEDEKER; MRS. KRAP.
STUTTGART	— P. NEFF.
TURIN	— GIANNINI & FIORE; J. BOCCA; MARIETTI.
VIENNA	— BRAUMÜLLER & SEIDEL; C. GEROLD; P. ROHR- MAN; SCHAÜMBURG & CO.

*In Italy, at*

ANCONA	BY
BOLOGNA	— M. RUSCONI, FRÈRES.
BERGAMO	—
BRFSCIA	—
FLORENCE	— JOS. MOLINI.
GENOA	— ANTOINE BEUF.
LEGHORN	— ROLANDI.
LUCCA	— F. BARON.
MALTA	— MUIR.
MANTUA	— MM. NEGRETTI, FRÈRES.
MILAN	— ARTARIA F. FUSI, MM. DU- MOLARD & FILS; MO- LINARI.
MODENA	— VINCENZI & ROSSI.

NICE	BY SOCIÉTÉ TYPOGRAPHIQUE; VISCONTI.
NAPLES	— CARLO BATELLI & CO.
PALERMO	— CHARLES BEUF.
PARMA	— J. ZANGHIERI.
PISA	— NISIRI, FRÈRES; JOS. VAN- NUCCHI.
PERUGIA	— VINCENZ. BARTELLI.
ROME	— VENANZIO MONALDINI, GAL- LERINI.
SIENNA	— ONORATO TORRI.
TURIN	— GIANNINI & FIORE; J. BOCCA; MARIETTI.
VENICE	— HERMANN FR. MÜNSTER, Piazza San Marco, 72, 73.

*In Switzerland, at*

AARAU	BY SAUERLAENDER.
DASLE	— SCHREIBER & WATZ.
BERN	— HUBER & CO.
CONSTANCE	— GLÜCKER.
FREIBURG	— HERDER.
ST. GALLEN	— HUBER.
GENEVA	— P. G. LE DOUBLE; LA LIBRAIRIE DESROGIS; MONROE.

LAUSANNE	BY GERS.
LUCERNE	— MEYER.
MÜHLHAUSEN	— ENGELMANN.
ROTWEIL	— HERDER.
SCHAFFHAUSEN	— HURTER.
SOLEURE	— REUTER.
THUN	— GRUBENMANN.
WINTERTHUR	— STEINER.
ZÜRICH	— H. FÜSSELI & CO.



## P R E F A C E.

---

THE Hand-book for France is the result of four or five journeys undertaken at different times between 1830 and 1841 ; and the Editor has covered the ground with a network of routes, described from personal observation, extending from Dunkirk to St. Jean de Luz ; from Toulon and Hyères to Brest ; from Grenoble and the Grande Chartreuse through Aubenas and Aurillac to the Port de Venasque ; and from Cherbourg and Mont St. Michel to Briançon and Embrun, and including the almost entire circuit of France. But in so vast a field many interstices have been left to be filled up by the best printed information ; and that so meagre in some respects, so abundant and scattered in others, that the collecting and arranging of the materials has been a work of very serious labour. The materials, indeed, for describing a large part of France are far more scanty than those which present themselves for Germany and Switzerland ; and the writer may fairly say, that he has, in the following pages, laid down routes of which no account is to be found in French Guides. It would be unjust to omit to mention the admirable Guides of Vaysse de Villiers, from which he has derived essential information ; but though they extend to nearly twenty volumes, they comprise only a small part of France, and only portions of their contents are calculated to interest English travellers. For their use this volume is compiled ; and if any French readers think fit to take it up, they must not be surprised to find many details well known to them, and doubtless many errors, not a few of which will be equally discernible by the Editor's own countrymen. He trusts that in the statement of

facts he has avoided invidious comparisons—that he has set down nought in such a light as to cause prejudice against the French, or to encourage or perpetuate estrangement between the two nations.

The chapters into which the book is divided are arranged according to the ancient Provinces, as being less minute, more historical, and better understood by English than the more intricate subdivisions of Departments. Though the latter are universally used by the French themselves, some centuries must elapse before *Champagne* and *Burgundy* cease to be remembered for their wines, *Périgord* for its pies, and *Provence* for its oil; nor will it be easy to obliterate the recollection of William of *Normandy*, Margaret of *Anjou*, and Henri of *Navarre*.

This volume contains no description of Paris, because to have included the capital would have extended this book to nearly double its present size, and because the ‘Paris Guide of Galignanis’ is a very good one, and renders the preparation of another, for the present at least, unnecessary.

June, 1843.



# CONTENTS.

---

INTRODUCTORY INFORMATION . . . . .	PAGE ix
------------------------------------	------------

## SECTION I.

### PICARDY.—ILE DE FRANCE.—NORMANDY.

Introductory Information . . . . .	1
Routes . . . . .	

## SECT. II.

### BRITTANY.

Introductory Information . . . . .	106
Routes . . . . .	113

## SECT. III.

### ORLÉANOIS.—TOURAINE.—RIVER LOIRE.—LA VENDÉE.— POITOU.—SAINTONGE.

Introductory Sketch of the Country . . . . .	172
Routes . . . . .	174

## SECT. IV.

### LIMOUSIN.—GASCONY.—GUIENNE.—THE PYRENEES.— NAVARRE.—BÉARN.—LANGUEDOC.—ROUSSILLON.

Preliminary Information . . . . .	234
Routes . . . . .	246

## SECT. V.

### CENTRAL FRANCE. — BERRI. — AUVERGNE. — VIVARAIS. — ARDÈCHE.—CANTAL.—BOURBONNAIS.—LYONNAIS.—THE CÉVENNES.

General View of the Country . . . . .	352
Routes . . . . .	356

## SECTION VI.

## PROVENCE AND LANGUEDOC.

	PAGE
General View of the Country . . . . .	436
Routes . . . . .	440

## SECT. VII.

## DAUPHINÉ.

Introduction.—Sketch of the Country . . . . .	501
Routes . . . . .	502

## SECT. VIII.

## BURGUNDY.—FRANCHE COMTÉ.

Routes . . . . .	523
------------------	-----

## SECT. IX.

CHAMPAGNE.—LORRAINE.—ALSACE.—THE VOSGES  
MOUNTAINS.

Routes . . . . .	545
------------------	-----

## SECT. X.

## ILE DE FRANCE.—FLANDERS.—ARTOIS.

Routes . . . . .	583
INDEX . . . . .	598

---



# HAND-BOOK

FOR

## TRAVELLERS IN FRANCE.

### INTRODUCTORY INFORMATION.

#### CONTENTS.

	PAGE
<i>a.</i> MONEY — TABLE OF FRENCH FRANCS REDUCED TO £. s. <i>d.</i>	x
<i>b.</i> TABLES OF WEIGHTS AND MEASURES . . . . .	xii
,, FRENCH FEET REDUCED TO ENGLISH FEET . . . . .	xiii
,, MÈTRES — Do. . . . .	xiv
,, KILOMÈTRES . . . . .	} — { ENGLISH MILES } AND FURLONGS
,, MYRIAMÈTRES . . . . .	
,, LIEUES DE POSTE — Do. . . . .	xv
,, TOISES — ENGLISH FEET . . . . .	xv
,, KILOGRAMMES — ENGLISH POUNDS . . . . .	xvi
,, POUNDS — Do. . . . .	xvi
,, HECTARES — ENGLISH ACRES . . . . .	xvi
,, AUNES DE PARIS — ENGLISH YARDS . . . . .	xvi
<i>c.</i> PASSPORTS AND POLICE . . . . .	xvi
<i>d.</i> THE DIFFERENT ROUTES BETWEEN LONDON AND PARIS COMPARED . . . . .	xix
<i>e.</i> MODES OF TRAVELLING— POSTING AND TRAVELLING CARRIAGE . . . . .	xx
<i>f.</i> MALLES POSTES . . . . .	xxiii
<i>g.</i> DILIGENCES . . . . .	xxv
<i>h.</i> RAILROADS . . . . .	xxvii
<i>i.</i> STEAM-BOATS . . . . .	xxviii
<i>k.</i> INNS—TABLES-D'HÔTE, ETC. . . . .	xxix
<i>l.</i> CAFÉS . . . . .	xxxi
<i>m.</i> A TRAVELLER'S GENERAL VIEW OF FRANCE — POINTS OF INTEREST—SCENERY—ARCHITECTURE . . . . .	xxxi
<i>n.</i> LIST OF THE 86 DEPARTMENTS INTO WHICH FRANCE IS DIVIDED, AND OF THE 33 ANCIENT PROVINCES COM- POSING THEM . . . . .	xxxvi
<i>o.</i> THE ENGLISH ABROAD . . . . .	xxxvii
<i>p.</i> SKELETON TOUR THROUGH FRANCE . . . . .	xxxix
<i>q.</i> ROUTE AND TIME FROM LONDON TO MARSEILLES . . . . .	xxxix

## a. MONEY.

In France, accounts are kept in *francs* and *centimes* (or hundred parts), the coinage being arranged on the decimal system. 1 franc contains 10 *décimes* (or double sous), and each *décime* 10 *centimes*.

## FRENCH MONEY.

*Silver Coins:—*

	£	s.	d.
1 franc = 100 centimes = 20 sous =	0	0	9½ to 10 <i>d.</i> English.
$\frac{1}{4}$ ditto = 25 ditto - =	0	0	2¼ $\frac{1}{8}$
$\frac{1}{2}$ ditto = 50 ditto - =	0	0	4¾
5 ditto = 500 ditto = 100 sous =	0	4	0

Worn pieces of money, like our old shillings, but composed of silver and copper, are also current, and bear the value of 75 centimes (15 sous), and 1 franc 50 centimes (30 sous), but they will soon be called in.

*Gold Coins:—*

	£	s.	d.
Louis d'or = 24 fr. . . . .	=	0	19 0 English.
Napoleon, or 20-franc piece . . . . .	=	0	15 10
Double Napoleon, or 40-franc piece . . . . .	=	1	11 8

*Copper Coins:—*

Décime, or 2-sous piece . . . . .	=	0	0 1
5 centimes = 1 sous . . . . .	=	0	0 0½
1 centime . . . . .	=	0	0 0 $\frac{1}{10}$

*N.B.* To find the value of centimes, remember that the *Tens* are all pennies, and the *Fives* halfpennies: thus 75*c.* = 7½*d.* : 25*c.* = 2½*d.* — 15*c.* = 1½*d.* within a fraction, but near enough for all practical purposes.

To reduce French francs to English money for common purposes, where minute exactness is not required, it is only necessary to divide the amount of francs by 25, or to substitute 4 for 100, thus:—

<i>Francs.</i>	£
100 =	4
1,000 =	40
10,000 =	400
100,000 =	4,000
1,000,000 =	40,000

The Bank of France issues *notes*, but for no sum under 500 fr., and they are difficult to change out of Paris, not being received in the provinces without paying an *agio*.

## FOREIGN COINS REDUCED TO THEIR VALUE IN FRENCH CURRENCY.

	<i>fr. c.</i>
English sovereign . . . . .	= 25 50 to 25 fr. 20 c. at par.
crown . . . . .	= 6 25
shilling . . . . .	= 1 25
Dutch Willem = 10 guilders . . . . .	= 21 30
guilder . . . . .	= 2 15
Prussian dollar . . . . .	= 9 75
Frederick d'or . . . . .	= 21 0
Bavarian florin = 20 pence English . . . . .	= 2 15
Kron thaler . . . . .	= 5 81
Austrian florin = 2 shillings English . . . . .	= 2 57

FRENCH FRANCS AND CENTIMES REDUCED TO THEIR VALUE IN ENGLISH  
POUNDS, SHILLINGS, AND PENCE.

	£.	s.	d.		£.	s.	d.
5 cents.	0	0	$0\frac{1}{4}\frac{9}{10}$	10 francs	0	7	11
10	0	0	$0\frac{3}{4}\frac{8}{10}$	11	0	8	$8\frac{1}{2}$
15	0	0	$1\frac{1}{4}\frac{7}{10}$	12	0	9	6
20	0	0	$1\frac{3}{4}\frac{6}{10}$	13	0	10	$3\frac{3}{4}$
25	0	0	$2\frac{1}{4}\frac{5}{10}$	14	0	11	$1\frac{1}{4}$
30	0	0	$2\frac{3}{4}\frac{4}{10}$	15	0	11	$10\frac{3}{4}$
35	0	0	$3\frac{1}{4}\frac{3}{10}$	16	0	12	$8\frac{1}{4}$
40	0	0	$3\frac{3}{4}\frac{2}{10}$	17	0	13	$5\frac{3}{4}$
45	0	0	$4\frac{1}{4}\frac{1}{10}$	18	0	14	$3\frac{1}{4}$
50	0	0	$4\frac{3}{4}$	19	0	15	$0\frac{3}{4}$
55	0	0	$5-\frac{9}{10}$	20	0	15	$10\frac{1}{4}$
60	0	0	$5\frac{1}{2}-\frac{8}{10}$	30	1	3	$9\frac{1}{2}$
65	0	0	$6-\frac{7}{10}$	40	1	11	$8\frac{3}{4}$
70	0	0	$6\frac{1}{2}-\frac{6}{10}$	50	1	19	8
75	0	0	$7-\frac{5}{10}$	60	2	7	7
80	0	0	$7\frac{1}{2}-\frac{4}{10}$	70	2	15	$6\frac{1}{4}$
85	0	0	$8-\frac{3}{10}$	80	3	3	$5\frac{1}{2}$
90	0	0	$8\frac{1}{2}-\frac{2}{10}$	90	3	11	$4\frac{3}{4}$
95	0	0	$9-\frac{1}{10}$	100	3	19	4
1 franc	0	0	$9\frac{1}{2}$	200	7	18	8
2	0	1	7	300	11	18	0
3	0	2	$4\frac{1}{2}$	400	15	17	4
4	0	3	2	500	19	16	8
5	0	3	$11\frac{1}{2}$	750	29	15	0
6	0	4	9	1,000	39	13	4
7	0	5	$6\frac{1}{2}$	5,000	198	6	8
8	0	6	4	10,000	396	13	4
9	0	7	$1\frac{1}{2}$				

ENGLISH MONEY REDUCED TO ITS VALUE IN FRENCH FRANCS AND CENTIMES.

	Fr.	Cts.		Fr.	Cts.		Fr.	Cts.
1 penny	0	$10\frac{1}{2}$	12 shillings	15	12	15 £ sterl.	378	0
2	0	21	13	16	38	16	403	20
3	0	$31\frac{1}{2}$	14	17	64	17	428	40
4	0	42	15	18	90	18	453	60
5	0	$52\frac{1}{2}$	16	20	16	19	478	80
6	0	63	17	21	42	20	504	0
7	0	$73\frac{1}{2}$	18	22	68	30	756	0
8	0	84	19	23	94	40	1008	0
9	0	$94\frac{1}{2}$	1 £ sterl.	25	20	50	1260	0
10	1	5	2	50	40	60	1512	0
11	1	15	3	75	60	70	1764	0
1 shilling	1	26	4	100	80	80	2016	0
2	2	52	5	126	0	90	2268	0
3	3	78	6	151	20	100	2520	0
4	5	4	7	176	40	200	5040	0
5	6	30	8	201	60	300	7560	0
6	7	56	9	226	80	400	10,080	0
7	8	82	10	252	0	500	12,600	0
8	10	8	11	277	20	1000	25,200	0
9	11	34	12	302	40	5000	126,000	0
10	12	60	13	327	60	10,000	252,000	0
11	13	86	14	352	80			



## b. WEIGHTS AND MEASURES.

A uniform decimal system of coins, weights, and measures was introduced into France in 1790, and since 1840 takes the place of all others.

In this new system all the measures of length, superficies, and solidity, the unit of weight, and the unit of money, are connected together, and are derived from one fundamental unit, deduced from the size of the earth, by means of geometrical and physical data, and each is capable of being verified at all times and in all places. This fundamental unit is called *MÈTRE*, and is equal to the ten-millionth part (0·0000001) of the distance from the pole to the equator.

The prefixes which express multiples are Greek :—

	MYRIA	KILO	HECTO	DECA,
represented by the capital letters	M	K	H	D,
expressing the numbers	10,000	1,000	100	10

The prefixes which express sub-multiples are Latin :—

	Deci	Centi	Milli	Deci-milli	Cent-milli,
represented by	d	c	m	d-m	c-m,
expressing the fractions	0·1	0·01	0·001	0·0001	0·00001.

By means of this system, with a small number of words, the division can be carried almost *ad infinitum*.

The measures of length are all either decimal multiples, or sub-multiples of the *mètre*, thus :—

Myria-	—	M.-m.	=	10,000	Mètres.
Kilo-	—	K.-m.	=	1,000	,,
Hecto-	—	H.-m.	=	100	,,
Deca-	—	D.-m.	=	10	,,
		m.	=	1	Mètre.
Deci-	—	d.-m.	=	0·1	,,
Centi-	—	c.-m.	=	0·01	,,
Milli-	—	m.-m.	=	0·001	,,

One great advantage of the decimal system of subdivision is, that, by the simple movement of a point, any one number of units is transformed into an equivalent number of superior and inferior units, thus :— $m489\cdot365 = Dm\ 48\cdot9365 = Mm\ 0\cdot489365 = cm\ 48936\cdot5$ .

## TABLES OF FRENCH MEASURES AND WEIGHTS.

TABLE A.—FRENCH FEET REDUCED TO ENGLISH FEET.\*

French Feet.	English Feet and Decimal Parts.	French Feet.	English Feet and Decimal Parts.	French Feet.	English Feet and Decimal Parts.
1	1·066	40	42·631	79	84·195
2	2·132	41	43·696	80	85·261
3	3·197	42	44·762	81	86·327
4	4·263	43	45·828	82	87·393
5	5·329	44	46·894	83	88·459
6	6·395	45	47·959	84	89·524
7	7·460	46	49·025	85	90·590
8	8·526	47	50·091	86	91·656
9	9·592	48	51·157	87	92·722
10	10·658	49	52·222	88	93·787
11	11·723	50	53·288	89	94·853
12	12·789	51	54·354	90	95·919
13	13·855	52	55·420	91	96·985
14	14·921	53	56·486	92	98·050
15	15·986	54	57·551	93	99·116
16	17·052	55	58·617	94	100·182
17	18·118	56	59·683	95	101·248
18	19·184	57	60·749	96	102·313
19	20·250	58	61·814	97	103·379
20	21·315	59	62·880	98	104·445
21	22·381	60	63·946	99	105·511
22	23·447	61	65·012	100	106·577
23	24·513	62	66·077	150	159·865
24	25·578	63	67·143	200	213·153
25	26·644	64	68·209	250	266·441
26	27·710	65	69·275	300	319·730
27	28·776	66	70·341	350	373·018
28	29·841	67	71·406	400	426·306
29	30·907	68	72·472	450	479·594
30	31·973	69	73·538	500	532·883
31	33·039	70	74·604	550	586·171
32	34·104	71	75·669	600	639·460
33	35·170	72	76·735	650	692·747
34	36·236	73	77·801	700	746·036
35	37·302	74	78·867	750	799·324
36	38·368	75	79·932	800	852·612
37	39·433	76	80·998	850	905·901
38	40·499	77	82·064	900	959·189
39	41·565	78	83·130	1000	1065·765

1 French Foot = 1·06576543 English Foot.

1 English Foot = 0·93829277 French Foot.

\* Tables A, B, and E are abridged from Lieut. Becher's accurate work on Foreign Linear Measures.

TABLE B.—FRENCH MÈTRES REDUCED TO ENGLISH FEET.

Mètres.	English Feet and Decimal Parts.	Mètres.	English Feet and Decimal Parts.	Mètres.	English Feet and Decimal Parts.
1	3·281	38	124·674	75	246·067
2	6·562	39	127·955	76	249·348
3	9·843	40	131·236	77	252·629
4	13·123	41	134·517	78	255·910
5	16·404	42	137·798	79	259·191
6	19·685	43	141·079	80	262·472
7	22·966	44	144·359	81	265·753
8	26·247	45	147·640	82	269·034
9	29·528	46	150·921	83	272·315
10	32·809	47	154·202	84	275·595
11	36·090	48	157·483	85	278·876
12	39·371	49	160·764	86	282·157
13	42·652	50	164·045	87	285·438
14	45·932	51	167·326	88	288·719
15	49·213	52	170·607	89	292·000
16	52·494	53	173·888	90	295·281
17	55·775	54	177·168	91	298·562
18	59·056	55	180·449	92	301·843
19	62·337	56	183·730	93	305·124
20	65·618	57	187·011	94	308·404
21	68·899	58	190·292	95	311·685
22	72·180	59	193·573	96	314·966
23	75·461	60	196·854	97	318·247
24	78·741	61	200·135	98	321·528
25	82·022	62	203·416	99	324·809
26	85·303	63	206·697	100	328·090
27	88·584	64	209·977	200	656·180
28	91·865	65	213·258	300	984·270
29	95·146	66	216·539	400	1312·360
30	98·427	67	219·820	500	1640·450
31	101·708	68	223·101	600	1968·539
32	104·989	69	226·382	700	2296·629
33	108·270	70	229·663	800	2624·719
34	111·550	71	232·944	900	2952·809
35	114·831	72	236·225	1000	3280·899
36	118·112	73	239·506		
37	121·393	74	242·786		

1 French mètre = 3·2808992 English feet.

TABLE C.—FRENCH KILOMÈTRES AND MYRIAMÈTRES INTO ENGLISH MILES, ETC.

Kilom.	Eng. Miles.	Fur- longs.	Yds.	Ft.	In.	Kilom.	Eng. Miles.	Fur- longs.	Yds.	Ft.	In.
1	0	4	213	1	11	8	4	7	169	0	4
2	1	1	207	0	10	9	5	4	162	2	3
3	1	6	200	2	9	1 myria.	6	1	156	1	2
4	2	3	194	1	8	2	12	3	92	2	4
5	3	0	188	0	7	3	18	5	29	0	6
6	3	5	181	2	6	4	24	6	185	1	8
7	4	2	175	1	5	5	31	0	121	2	10



TABLE D.—FRENCH LIEUES DE POSTE INTO ENGLISH MILES AND YARDS.

L. Mls.	Yds.	L. Mls.	Yds.	L. Mls.	Yds.	L. Mls.	Yds.
1 2	743·061	11 26	1,133·671	30 72	1,171·832	400	968 1,544·428
2 4	1,486·122	12 29	116·732	40 96	1,562·443	500	1,211 170·535
3 7	469·183	13 31	859·794	50 121	193·053	600	1,453 556·642
4 9	1,212·244	14 33	1,602·855	60 145	583·664	700	1,695 942·749
5 12	195·305	15 36	585·916	70 169	974·275	800	1,937 1,328·856
6 14	938·366	16 38	1,328·977	80 193	1,364·886	900	2,179 1,714·963
7 16	1,681·427	17 41	312·038	90 217	1,755·496	1,000	2,422 341·070
8 19	664·488	18 43	1,055·099	100 242	386·107	2,000	4,844 682·140
9 21	1,407·549	19 46	38·160	200 484	772·214	3,000	7,266 1,023·210
10 24	390·610	20 48	781·221	330 726	1,158·321	5,000	12,110 1,705·350

TABLE E.—FRENCH TOISES REDUCED TO ENGLISH FEET.

Toises.	English Feet and Decimal Parts.	Toises.	English Feet and Decimal Parts.	Toises.	English Feet and Decimal Parts.
1	6·395	38	243·095	74	473·200
2	12·789	39	249·389	75	479·594
3	19·184	40	255·784	76	485·989
4	25·578	41	262·178	77	492·384
5	31·973	42	268·573	78	498·778
6	38·368	43	274·967	79	505·173
7	44·762	44	281·362	80	511·567
8	51·157	45	287·757	81	517·962
9	57·551	46	294·151	82	524·357
10	63·946	47	300·546	83	530·751
11	70·340	48	306·940	84	537·146
12	76·735	49	313·335	85	543·540
13	83·130	50	319·730	86	549·935
14	89·524	51	326·124	87	556·830
15	95·919	52	332·519	88	562·724
16	102·313	53	338·913	89	569·119
17	108·708	54	345·308	90	575·513
18	115·103	55	351·703	91	581·903
19	112·497	56	358·097	92	588·308
20	127·892	57	364·492	93	594·697
21	134·286	58	370·886	94	601·092
22	140·681	59	377·281	95	607·486
23	147·076	60	383·676	96	613·881
24	153·470	61	390·070	97	620·275
25	159·865	62	396·465	98	626·670
26	166·259	63	402·859	99	633·065
27	172·654	64	409·254	100	639·459
28	179·049	65	415·649	200	1278·918
29	185·443	66	422·043	300	1918·378
30	191·838	67	428·438	400	2557·837
31	198·232	68	434·832	500	3197·296
32	204·627	69	441·227	600	3836·756
33	211·022	70	447·621	700	4476·215
34	217·416	71	454·016	800	5115·674
35	223·811	72	460·411	900	5755·133
36	230·205	73	466·805	1000	6394·593
37	236·600				

1 French toise = 6·39459259 English feet.

1 English foot = 0·15638212 French toise.

TABLE F.—FRENCH KILOGRAMMES INTO ENGLISH POUNDS (AVOIRDUPOIS).

Kil.	E. Pds.	Kil.	E. Pds.	Kil.	E. Pds.	Kil.	E. Pds.	Kil.	E. Pds.
1	2·206	14	30·880	27	59·554	40	88·228	300	761·714
2	4·411	15	33·086	28	61·760	41	90·434	400	882·286
3	6·617	16	35·291	29	63·996	42	92·640	500	1,102·857
4	8·823	17	37·497	30	66·171	43	94·846	1,000	2,205·714
5	11·028	18	39·703	31	68·377	44	97·051	2,000	4,411·429
6	13·234	19	41·908	32	70·583	45	99·257	3,000	6,617·143
7	15·440	20	44·114	33	72·788	46	101·463	4,000	8,822·857
8	17·646	21	46·320	34	74·994	47	103·668	5,000	11,028·471
9	19·851	22	48·526	35	77·200	48	105·874	10,000	22,057·143
10	22·057	23	50·731	36	79·405	49	108·080	20,000	44,114·286
11	24·263	24	52·937	37	81·611	50	110·286	30,000	66,171·429
12	26·468	25	55·143	38	83·817	100	220·571	40,000	88,228·572
13	28·674	26	57·348	39	86·023	200	441·143	50,000	110,285·715

TABLE G.—FRENCH POUNDS INTO ENGLISH POUNDS (AVOIRDUPOIS).

Fr. Pds.	Eng. Pds.	Fr. Pds.	Eng. Pds.	Fr. Pds.	Eng. Pds.	Fr. Pds.	Eng. Pds.	Fr. Pds.	Eng. Pds.
1	1·080	14	15·116	27	29·152	40	43·188	300	323·913
2	2·159	15	16·196	28	30·232	41	44·268	400	431·884
3	3·239	16	17·275	29	31·312	42	45·348	500	539·855
4	4·319	17	18·355	30	32·391	43	46·427	1,000	1,079·710
5	5·398	18	19·435	31	33·471	44	47·507	2,000	2,159·420
6	6·478	19	20·514	32	34·551	45	48·587	3,000	3,239·130
7	7·558	20	21·594	33	35·630	46	49·666	4,000	4,318·840
8	8·638	21	22·674	34	36·710	47	50·746	5,000	5,398·550
9	9·717	22	23·754	35	37·790	48	51·826	10,000	10,797·100
10	10·797	23	24·833	36	38·869	49	52·906	20,000	21,594·200
11	11·877	24	25·913	37	39·949	50	53·985	30,000	32,391·300
12	12·956	25	26·993	38	41·029	100	107·971	40,000	43,188·400
13	14·036	26	28·072	39	42·109	200	215·942	50,000	53,985·500

TABLE H.—FRENCH HECTARES INTO ENGLISH ACRES.

Hect.	Acres.	Hect.	Acres.	Hect.	Acres.	Hect.	Acres.	Hect.	Acres.
1	2·471	8	19·769	15	37·067	40	98·846	200	494·229
2	4·942	9	22·240	16	39·538	50	123·557	300	741·343
3	7·413	10	24·711	17	42·009	60	148·268	400	988·457
4	9·884	11	27·182	18	44·480	70	172·980	500	1,235·571
5	12·356	12	29·654	19	46·952	80	197·691	1,000	2,471·143
6	14·827	13	32·125	20	49·423	90	222·403	2,000	4,942·286
7	17·298	14	34·596	30	74·134	100	247·114	5,000	12,355·751

TABLE I.—FRENCH “AUNES DE PARIS” INTO ENGLISH YARDS.

Aun.	Yds.	Aun.	Yds.	Aun.	Yds.	Aun.	Yds.	Aun.	Yds.
1	1·300	7	9·098	13	16·896	19	24·695	70	90·981
2	2·599	8	10·398	14	18·196	20	25·994	80	103·978
3	3·899	9	11·697	15	19·496	30	38·992	90	116·975
4	5·199	10	12·997	16	20·795	40	51·989	100	129·972
5	6·499	11	14·297	17	22·095	50	64·986	200	259·945
6	7·799	12	15·597	18	23·395	60	77·983	500	649·862

## C. PASSPORTS AND POLICE.

A passport is indispensable to enable a stranger to travel in France. It may be procured *gratis* in London, at the French Passport Office, 6, Poland Street, open from 1 to 3 daily. It is necessary to apply for it verbally, or by letter, a day or two in advance (one day will suffice), when a printed form is delivered to the applicant to be filled up with his name, age, profession, &c. *Rentier*, or independent man, is a convenient designation for those who travel for recreation. On returning this paper



personally to the office, the passport is at once made out from it; and after a description of the person of the bearer has been inserted in it, and his own signature (which should be written legibly) has been attached to it, will be delivered to him. The description of his person, or *signalement*, *should on no account* be omitted in any passport for France: the want of it may, in remote parts of the country, lead to the bearer's detention or arrest; and it is the more necessary to dwell on this point, because the officials of English ministers abroad, in making out passports for their countrymen, are apt to slur it over to save trouble.

Passports may be also obtained on payment of 4s. 6d. from British consuls in France, or from French consuls residing at British sea-ports. The virtue of a Foreign Office passport, which costs 2l. 7s., appears to be dubious: it is liable to be taken away at the French frontier like any other.

In *cases of hasty* departure from England, when a traveller has not time to apply one day in advance, he may obtain a passport at any place in France where an English Consul resides. A British Consular passport is preferable to a foreign Consul's.

The passport which a traveller brings with him into France is not valid for travelling through the country, nor for quitting it, until it has received the signature of the Minister of the Interior. It is therefore taken away from the traveller at the sea-port where he lands, or the frontier town where he enters France, and is forwarded by the police to Paris, while a temporary passport, *Passe Provisoire*, is given him to carry him on to Paris, and 2 francs must be paid for it.

Until the traveller reaches Paris, the *Passe Provisoire* will carry him through all parts of France, but not out of the country. He cannot depart until he has exchanged it either for his original passport, visé by the Minister of the Interior, or for the passport of the British minister or consul.

The first care of the traveller after landing at a French sea-port, if he does not wish to be detained there, should be to obtain his *passe provisoire*, which is often a tedious business, owing to the number of applicants all eager to secure their papers in time to start by diligences, railroads, or steam-boats. If he be desirous of passing rapidly through France, *viâ Paris*, on his way to another country, such as Italy, India, &c., and does not wish to *stop* in Paris, he ought to impress this upon the agent at the passport office, and request him to forward the original passport to Paris by the same day's post, in order that it may arrive as soon as its owner. When this is neglected, an annoying delay of several days is often caused. In cases of urgent haste, where the traveller cannot wait for the arrival in Paris of his original passport, the British ambassador will give him one in exchange for the *Passe Provisoire*.

On reaching Paris, the "*Passe Provisoire*" must be taken or sent to the Préfecture of police, where the original will be given in exchange for it. It is better to send a valet de place or commissionnaire for it than to go for it: the commissionnaire being known to the officials is more likely to be attended to than a stranger, speaking French perhaps scarcely intelligible. The commissionnaire may, it is true, play false, and declare that the passport is not arrived, in the hope of detaining the traveller at his hotel; and the best way to prevent this is to promise him an extra



douceur in the event of his securing the passport at once. The traveller must give his signature, and his personal attendance at the police-office is not required.

To secure personally the necessary *visas* of French and foreign ministers to a passport, to enable the bearer to enter Austria or Italy, is not to be done under two days. The stranger who undertakes to do this for himself will find it a very disagreeable and tiresome business, the passport offices being open only at fixed hours, being situated in distant parts of the town, and being beset by crowds of applicants. In all the respectable Paris hotels (Meurice, Bristol, &c.), a commissionnaire is appointed to attend to the passports, for which a fixed charge (4 or 5 francs) is made, and this saves the traveller a couple of days' running about from office to office. The signature of the Papal nuncio is essential for travellers going to Rome, and can be obtained only at Paris.

If the stranger is not going to Paris, but only to cross a part of France, on his way to another country, for instance, from Calais to Lille, on his way to Belgium, the passport which he brings with him is visé at the frontier and returned to him. If he wishes merely to make a short stay at the place where he has landed (Boulogne for instance), or in a contiguous department, and the period of his stay do not exceed one month, the local authorities deliver to him a limited passport, retaining the original in their hands.

The traveller may have his original passport sent after him to any town in France where there is a préfecture or sous-préfecture; but if there is danger of delay in transmitting it to the capital, there is greater in sending it to a provincial place.

In France, more than in any other country in Europe\* at the present time, the passport is liable to be demanded at all times and places, and should *always be carried about the person*. The gendarmes are authorized to call for it not only in frontier and fortified towns, but in remote villages: they may stop you on the highway, or waylay you as you descend from the diligence—may force themselves into the *salle à manger*, or enter your bed-room, to demand a sight of this precious document. It is needless to expatiate on this restraint, so inconsistent with the freedom which an Englishman enjoys at home, or to show that the police are a pest to the harmless and well conducted, without being a terror to evil doers; it is the custom of the country, and the stranger must conform, or has no business to set his foot in it. It must be allowed that the police perform their duty with civility, so as to render it as little vexatious as possible. They cannot enter a private house without a warrant.

Those who lose their passports, leave them behind, or do not take care to have them "*en règle*," are liable to be marched off to the *juge de paix* or *préfet*, often a distance of 10, 15, or 20 miles, on foot, unless they choose to pay for a carriage for their escort as well as themselves; and if no satisfactory explanation can be given, may at last be deposited in prison.

*Before embarking at a French port*, a *permis d'embarquement* must be obtained; it is given gratis at all hours on exhibiting the passport en

\* Even in France the strictness regarding passports seems to have been relaxed since the introduction of railroads—1848.

règle or properly visé, and is received by an officer of police as the traveller goes on board the packet.

The duties of rural police are performed by

*Gendarmes*, a fine body of men, chosen from the line, handsomely dressed, better mounted than any other French cavalry corps. Being settled in their native country, and not moved from place to place, they know everybody and all the localities. Their salary amounts to 80*l.* a-year, out of which they have to provide their horse and uniform.

## d. THE DIFFERENT ROUTES BETWEEN LONDON AND PARIS COMPARED.

## By FOLKESTONE AND BOULOGNE.

London to Folkestone (Express)	. . . . rail	. 82 miles	. 2 $\frac{1}{4}$ hours*
Folkestone to Boulogne	. . . . steam	. 27 „	. 2 „
Boulogne to Abbeville	. . . . rail	. 44 „	. 3 $\frac{3}{4}$ „
Abbeville to Paris	. . . . rail	. 119 „	. 6 „
TOTAL		. 272	14

## By DOVER AND BOULOGNE.

London to Dover (Express)	. . . . rail	. 88 „	. 2 $\frac{3}{4}$ „
Dover to Boulogne	. . . . steam	. 26 „	. 2 „
Boulogne to Abbeville	. . . . rail	. 44 „	. 3 $\frac{3}{4}$ „
Abbeville to Paris	. . . . rail	. 119 „	. 6 „
TOTAL		. 277	14 $\frac{1}{2}$

## By DOVER AND CALAIS.

London to Dover (Express)	. . . . rail	. 88 „	. 2 $\frac{3}{4}$ „
Dover to Calais	. . . . steam	. 22 $\frac{1}{2}$ „	. 2 „
Calais to Arras	. . . . diligence	. 69 „	. 11 „
Arras to Paris	. . . . rail	. 133 „	. 6 „
TOTAL		. 312 $\frac{1}{2}$	21 $\frac{3}{4}$

## By BRIGHTON AND DIEPPE (the shortest).

London to Brighton (Shoreham Harbour)	. rail	. 56 $\frac{1}{2}$ „	. 2 $\frac{1}{2}$ „
Brighton to Dieppe	. . . . steam	. 74 „	. 8 „
Dieppe to Rouen	. . . . diligence	. 35 „	. 4 „
Rouen to Paris	. . . . rail	. 85 „	. 4 „
TOTAL		. 250 $\frac{1}{2}$	18 $\frac{1}{2}$

## By BRIGHTON AND HAVRE.

London to Brighton (Shoreham Harbour)	. rail	. 56 $\frac{1}{2}$ „	. 2 $\frac{1}{2}$ „
Brighton to Havre	. . . . steam	. 94 „	. 9 „
Havre to Paris	. . . . rail	. 142 „	. 6 $\frac{1}{2}$ „
TOTAL		. 292 $\frac{1}{2}$	18

\* By common trains in 4 hours.

*Fast Steam-boats* run in 2 hours between Folkestone and Boulogne twice each way every day (every tide). The Hotel (Vantini's) at Folkestone is an excellent one ;—the charges there are regulated by the Railway Company. There are ten trains daily between London and Folkestone and Dover.

By crossing from Dover or Folkestone to Boulogne, instead of Calais, 22 m. of land journey between Calais and Boulogne are saved.

LONDON TO PARIS BY THE THAMES TO BOULOGNE.

	Miles.	Hours.	Fares.	
			s.	d.
London to Boulogne (per Steamer) . . . . .	110	12	15	0
Boulogne to Paris (per Railway) . . . . .	156	10	23	0
Total . . . . .	266	22	38	0

This route is very economical, and least fatiguing, the sea part of the voyage in general not exceeding 5 hours.

RECAPITULATION.

	Miles.	Hours.
<i>Viâ</i> Folkestone and Boulogne . . . . .	272	14
— Brighton and Dieppe . . . . .	250½	18½
— Brighton and Havre . . . . .	292½	18
— London and Havre, by Steam . . . . .	—	39
— Dover and Calais . . . . .	312	20
— Southampton and Havre . . . . .	332	22½

e. POSTING.—PRIVATE CARRIAGE.

The French Post Book (*Livre de Poste*), published under the authority of the Government, is indispensable for persons travelling post, as it contains the exact distances from post to post, and the extra dues on entering and quitting towns (*postes de faveur*), *which are constantly changing*. It may be had in all towns, and even at the post-houses.

By a law enforced throughout France since the 1st Jan. 1840, distances are no longer calculated by “postes,” but by *kilomètres* and *myriamètres*. 1 *kilomètre* (*i. e.* 1000 *mètres*) = nearly 5 furlongs or  $\frac{5}{8}$ ths of an English mile ; 1 *myriamètre* = 10 *kilom.* = nearly  $6\frac{1}{4}$  Eng. m. (or 6 m. 1 fur. 156 yds.). See table, page xiv.

The postmaster's authorised charge is,  
For each horse, 2 francs or 40 sous per *myriamètre*, or 20 centimes per *kilom.*



The *Postilion* is entitled by the law to demand only 1 franc per myriamètre or 10 centimes per kilom. ; but it is customary to pay him 2 francs per myriam., or at the rate of a horse, unless he has misconducted himself, when he may be punished by limiting his pay to the tariff. He is bound by the law to drive the myriamètre within 46 and 58 minutes. The English, who generally want to go faster, are too often in the habit of giving him 50 sous per myriam., or 5 per kilom., which is at the rate of more than 4*d.* an English mile ; *i. e.* more than a postboy in England gets. In fact, French postboys are not satisfied with 4 sous, but well contented with 5.

This extravagant remuneration is contrary to the express injunction of the French “*Livre de Poste*,” which says, p. 42, “*Les voyageurs conservent donc la faculté de restreindre le prix des guides à 1 franc, à titre de punition ; et ils seront invités par les maîtres de poste, et dans l'intérêt du service, à ne jamais dépasser la rétribution de 2 fr. par myriamètre.*”

The *cost of posting* with 3 persons, in a calèche, through France, may be calculated at 8 francs par myriamètre, or 80 centimes par kilomètre. For 2 persons, with 2 horses and postboy, the rate is about 6 francs, or nearly 9*d.* per English mile.

The average speed of posting does not much exceed a myriamètre per hour, including stoppages.

In fixing the number of horses to be attached, the postmaster takes into account the nature, size, and weight of the carriage, and the quantity of luggage : a landau or berlin always requires 3 horses at least, generally 4 ; a chariot will require 3, while a britzka holding the same number of persons will need only 2.

To facilitate this, carriages are divided into 3 classes :—

1. Cabriolets and light calèches without a front seat, or having one narrower than the back seat, must have 2 horses.
2. Limonières, heavier carriages, chariots (*coupées*) ; to these the postmaster may attach 3 horses, even when they contain only 2 persons.
3. The heaviest kind of carriages, berlines, landaus, barouches, whether closed or not, but having a front seat as wide as the back, 4 horses.

The posting regulations allot one horse to each person in a carriage ; but allow the traveller, at his option, and provided the postmaster agrees, either to take the full complement of horses, at the rate of 40 sous each, or to take 2 or 3 at 40 sous, and to pay for the rest at 30 sous, without taking them. Thus a party of 4 persons in a light britzka may be drawn by 2 horses, paying 30 sous each for a third and fourth horse, which they are liable to take, or 3 francs extra for the 2 persons above the number of horses, thus compounding with the postmasters along the whole line of road. Where the carriage is so light as not to require as many horses as there are passengers, it is, of course, a saving of 10 sous a myriam. for each horse, to dispense with them. Postmasters in France are too apt to withhold the 3rd horse, even in cases where the weight of the carriage and state of the roads require it to be put to. No one ought to submit to this when *first attempted* ; it will cause much loss of time on hilly roads.

The limitation of the number of horses on first setting out on a journey is of importance, because you are obliged to take on from every post station



(except in the case of supplemental horses) the same number of horses that brought you to the relay.

One postilion may drive 4 horses, “aux grandes guides;”—where 3 horses are required, they may be harnessed one in front of the others, or “à l’arbalète.” Formerly, in France, 3 horses required to be yoked abreast; and for this purpose, shafts must be put to the carriage; but this rule is not now enforced, and there is no difficulty in travelling with 3 horses and a pole, as in Belgium and Germany.

On certain hilly stages one or more extra horses (*chevaux de supplément*) are required to be attached to carriages, and at the entry into and departure from certain large towns the postmaster is allowed to charge for a number of kilomètres exceeding the real distance of the stage, called “distances de faveur or supplémentaires,” formerly “postes royales.” For example, 8 kilomètres beyond the real distance are charged on entering and quitting Paris. These privileges are defined by the “*Livre de Poste*.” Those who merely pass through towns, changing horses but not stopping, are exempted from this extra charge.

The furnishing of post-horses does not, as in England, include a *post-chaise*, and those who mean to post in France must have a carriage of their own. It is true the French postmasters are obliged to keep a cabriolet or small calèche for hire, but it is usually a rickety vehicle holding only 2 persons, with no room for baggage beyond a *sac de nuit*, and is therefore seldom resorted to. The charge for it is the same as for a single horse, *i. e.* 40 sous per myriam.

Postilions are not allowed to pass another carriage on the road, unless the one in advance be drawn by fewer horses, or has been stopped by some accident. Travellers are supplied with horses in the order in which they and their couriers arrive; the *malles postes* and Government *estafettes* alone having a right of precedence.

A register is kept at every posthouse, in which the traveller may enter complaints against the postmaster or his servants in that or the neighbouring relays. These registers are inspected at stated times by proper authorities, and the charges are investigated.

*Tariff charge of post-horses* for conveying a carriage from the Railway Termini in Paris—for 2 horses and 1 postilion, 6 francs; 3 horses and 1 postilion, 8 francs 30 centimes; 4 horses and 2 postilions, 12 francs.

### *Carriages.*

*Duty on English Carriages.*—English travellers, on entering France with a carriage not of French make, are called upon to deposit one-third of an *ad valorem* duty for it; a barouche or chariot is usually rated at 1000 frs. (sometimes you can get off for 600), and a landau or coach at 1500 frs. Travellers should be aware of this, in order that they may take with them ready money to meet this charge. A receipt, with an order upon the Bureau des Douanes, is given to the owner, entitling him to receive back  $\frac{2}{3}$ ths of this one-third, if the *same* carriage be taken out of France within 3 years. This order describes very particularly the carriage, and, on presenting it at the frontier, the money deposited is repaid, except  $\frac{1}{4}$ th (*i. e.*  $\frac{1}{12}$ th of the value of the carriage), which is all the duty paid.

Carriages landed in France, and *taken out of the country within six*

*days*, are exempted from the duty of a third of their value, formerly levied on all carriages without exception.\* This remission of duty, however, can only be obtained on condition that some respectable French householder will guarantee that the carriage shall quit France within the six days specified. The landlord of the inn at which the traveller puts up in Calais will effect this arrangement: but as he subjects himself to a penalty of a very large amount in case the above condition is not complied with, he requires the traveller to sign an undertaking to indemnify and hold him harmless in case of failure. An order to procure this remission of duty, issued by the French custom-house, and called "*acquit à caution*," costs 5 francs, and must be delivered up on passing the French frontier.

Owing to the inferiority of the post-chaises in France (alluded to above), those who intend to travel post, and are not furnished with a carriage of their own, must buy or hire one.

A travelling carriage, strong and tolerably good-looking, may be hired at Calais, or Paris, or Boulogne, from one of the innkeepers, for 350 or 400 fr. (16*l.*) for two months, and 8 fr. a-day after the expiration of that time; the owner to pay for all necessary repairs. Thus the expense of crossing and recrossing the Channel, of shipping and unshipping, is spared.

The hire of a carriage alone to go from Calais to Paris varies from 100 to 150 francs. "A good carriage (*calèche*, to hold 4) may be hired in Paris at the rate of 16*l.* for 2 months, and less for a longer term. It need not be brought back to Paris, but may be delivered to the owner's agent at the frontier towns—Calais, Boulogne, Strasburg, Marseilles. Care should be taken to ascertain, before setting out, that the harness, as well as the carriage, is sound, and the sabot new."—*W. M.*

#### *Hired Carriages—Voitures à volonté.*

It is difficult to fix a fair scale of prices to pay for the hire of a carriage and horses in different parts of France; the best guide is to calculate it at one-half or two-thirds the posting price for the same distance, exclusive of the carriage.

The carriage usually to be met with for hire is the *cabriolet*—a heavy, lumbering, and *jolting* vehicle: the charge for it is commonly 8 or 9 fr. a-day, exclusive of a *pourboire* of 2 or 3 fr. to the driver. It has neither the neatness nor the lightness of the gigs furnished at a country inn in England, but is necessarily clumsily built to stand the terrible cross-roads of France.

In out-of-the-way places often no other vehicle is to be found than a *patache*—a rustic cab, verging towards the covered cart, without its easy motion. He who rides in a *patache* must prepare to be jolted to pieces.

#### *f. MALLÉS POSTES,*

equivalent to the English mail-coaches, and kept up at the expense of Government, travel along the following great roads of France to carry the mail, and are allowed to take 2 or 3 passengers.

\* It is said that no duty is levied on carriages entering *by land*.



## MALLES POSTES (FROM PARIS).

Starting every day at 6 p. m. from the Hôtel des Postes, Rue Jean Jacques Rousseau.

—	Places for Passengers.	Distance.	Duration of Journey.	FARES.			
				fr.	c.	s.	d.
From Paris to—		Miles.	Hours.				
Brest by Dinan . . .	3	371	40	108	0	85	8
Calais . . . . .	2	202	15	49	0	38	11
Cherbourg by Caen . .	3	213	21	61	60	48	10
Clermont-Ferrand . .	3	250	..	..		..	
Forbach by Châlons . .	2	233	25	68	45	54	3
Geneva by Dijon . . .	2	307	34	89	45	70	4
Limoges by Vierzon . .	4	236	22	69	15	54	10
Lyons by Auxerre . . .	4	287	33	84	20	66	11
Sédan by Rheims. . .	3	160	19	47	10	37	4
Strasbourg by Nancy .	3	280	33	82	95	66	10
St. Etienne by Moulins	4	315	34	90	80	72	1
Troyes . . . . .	4	..	10	30	30	..	
From Bordeaux to—							
Bayonne . . . . .	3	139	17	40	45	32	1
Nantes . . . . .	2	215	22	61	85	49	1
Toulouse . . . . .	1	155	17	44	80	35	5
From Altkirch to—							
Mulhouse . . . . .	1	..	1 15	3	15	..	
From Limoges to—							
Pau . . . . .	2	254	26	72	45	57	6
Toulouse . . . . .	2	192	22	55	10	43	9
From Lyons to—							
Bordeaux . . . . .	2	337	38	97	10	77	0
Marseilles . . . . .	2	207	20	60	55	48	1
Mulhouse . . . . .	2	288	..	64	40	51	1
From Moulins to—							
Montpellier . . . . .	2	285	36	81	0	64	3
From St. Etienne to—							
Marseilles . . . . .	3	204	22	58	95	46	10
From Toulouse to—							
Bayonne . . . . .	2	182	19	52	10	41	4
Marseilles . . . . .	2	259	27	74	55	59	2
Perpignan. . . . .	2	121	13	34	30	27	3
From Tours to—							
Bordeaux . . . . .	3	..	21	59	70	..	
Nantes . . . . .	2	..	12	36	12	..	
Rennes . . . . .	2	..	11	41	15	..	
Troyes to Basle . . .	2	..	22	58	25	..	
Besançon . . . . .	2	..	15	40	60	..	

The French mails are on the whole very comfortable, though the inside passengers have not very much room, and he that sits by the side of the conductor in the cabriolet is liable to be annoyed at every post town by his companion's horn in his efforts to rouse the postmasters, and by his bustle in the delivery and receipt of the letter-bags.

The mails consist of a stoutly-built barouche which holds comfortably inside 2 or 3 passengers; painted of a light red colour, drawn by 4 horses with tolerable harness, with a seat in front for the postilion, and one behind for the conductor. Their rate of travelling exceeds that of the diligence on almost all the roads, equalling at least 9 or 10 Eng. m. an hour, sometimes 12 m.

The price of places is nearly double that of the diligence, being 1 fr. 75 cent. per myriam. = to nearly 3*d.* a-mile, the outside fare on an English mail.

The malles postes are very much resorted to, especially from Paris; and as they take so few passengers, the only chance of obtaining a place, generally speaking, is to secure it some days beforehand. Places are taken at the post-offices in Paris and in the provincial towns where the malle poste passes. The passport must be shown if required before the name can be entered, and half the fare must be paid at once, the remainder before starting.

*Baggage* of passengers is restricted in weight to 25 kilogram. or 55 lbs.; all above that weight must be paid for. No portmanteau, or sac de nuit, of dimensions exceeding the following measurement can be admitted into a malle poste:—

In length	. . 0 <sup>m</sup> , 70 décim.	= 26 pouces	= 27 English inches.
breadth	. . 0 <sup>m</sup> , 40	= 14	= 15
height	. . 0 <sup>m</sup> , 35	= 13	= 13

These regulations are strictly enforced, so that it is vain for those who travel with much baggage to think of availing themselves of the malle poste. There is room, however, for a writing-case or hat-box inside.

The chief inconvenience is the shortness of the stoppages on the road; only to change horses, which does not occupy 5 minutes, and to take in the bags, and once only in the 24 hours for about half an hour for dinner. It is therefore advisable to take a small store of cold provisions on a long journey, especially between Paris and Marseilles, and Bordeaux.

The fare includes all charges; nothing is to be given to the postilions: the conductor generally receives a small douceur, varying from 5 to 10 fr. according to the length of the journey, at the good will of the passenger.

Places cannot be *secured* except for three-fourths of the entire distance which the mail travels; nor are passengers taken for short distances unless they are without baggage.

#### g. DILIGENCES.

The French stage-coach or diligence is a huge, heavy, lofty, lumbering machine, something between an English stage and a broad-wheeled waggon. It is composed of three parts or bodies joined together: 1. the front division, called *Coupé*, shaped like a chariot or post-chaise, holding  
France. b



3 persons, quite distinct from the rest of the passengers, so that ladies may resort to it without inconvenience, and, by securing all 3 places to themselves, travel nearly as comfortably as in a private carriage. The fare is more expensive than in the other part of the vehicle.

2. Next to it comes the *Intérieur*, or inside, holding 6 persons, and oppressively warm in summer.

3. Behind this is attached the *Rotonde*, "the receptacle of dust, dirt, and bad company," the least desirable part of the diligence, and the cheapest except

The *Banquette*, or *Impériale*, an outside seat on the roof of the coupé, tolerably well protected from rain and cold by a hood or head, and leather apron, but somewhat difficult of access until you are accustomed to climb up into it. It affords a comfortable and roomy seat by the side of the conductor, with the advantages of fresh air and the best view of the country from its great elevation, and greater freedom from the dust than those enjoy who sit below. It is true you may sometimes meet rough and low-bred companions, for the French do not like to travel outside; and few persons of the better class resort to it, except English, and they for the most part prefer it to all others. It is not suited to females, owing to the difficulty of clambering up to it. The diligence is more roomy and easy, and therefore less fatiguing, than an English stage; but the *pace* is slow, rarely exceeding 6 or 7 m. an hour, and in bad weather, when roads are heavy, falling below that. Nevertheless, the diligences have undergone considerable improvement within the last 15 or 20 years; the horses are changed more rapidly; strips of hide have taken the place of rope harness; and, on one or two lines of road, the rate of travelling is accelerated to 8, or even 10 m. an hour.

The coach and its contents are placed in charge of the *Conducteur*, a sort of guard, who takes care of the passengers, the luggage, the way-bill, and the *mécanique*, that is, the break or leverage, by which the wheel is locked. He is paid by the administration, and expects nothing from the passengers, unless he obliges them by some extra service. He is generally an intelligent person, often an old soldier, and the traveller may pick up some information from him.

The large 1st class, three-bodied diligences carry 15 passengers inside, and 4 out, including the conductor, and weigh when loaded 11,000 lbs., or about 5 tons. They are drawn by 5 or 6 horses, driven by a post-boy from the box, instead of the saddle, as was formerly the case. Besides passengers, the diligence carries a great deal of heavy merchandise, such as in England would be sent by the waggon or canal-boat.

The *places* in the diligence are all numbered, and are given out to passengers in the order in which they book themselves, the corner seats first; and it comports very much with the traveller's comfort to secure one of them, especially in long journeys. Before starting, the passengers' names are called over, and to each is assigned his proper place. The average rate of the *fares* may be calculated at 45 or 50 centimes for 2 leagues, equivalent to  $1\frac{1}{2}d.$  a mile English, except for the coupé, which is somewhat higher. Never omit to ask for the receipt or bulletin for the fare paid, which constitutes your legal title to the place.

- The two chief Messageries are equally good, and, generally speaking, superior to any of the minor companies; indeed, they manage to keep down their rivals, by a mutual understanding with each other.

N.B. During the *month of August* the diligences on all the great roads are thronged with school-boys and collegians, with their parents and masters, in consequence of the breaking up of the establishments of education in Paris, all hurrying home at once into the provinces. It not unfrequently happens, that for a fortnight together every place in every coach is taken. The vacations at the public offices occur about the same time, and contribute largely to swell the crowd of travellers in August.

France has allowed herself to be outstripped by her neighbours, not only by England, but also by Belgium, Prussia, and Austria, in these means of extending national resources and civilisation, which the country more especially stands in need of. The only railroads as yet completed in France are,

*b 2*



The Livret or *Guide* of *Paul Chaix* contains the time-tables, fares, &c., of all the French railways; it is the "Bradshaw" of France, and will be a useful companion to travellers in that country.

The following lines of railway, ramifying in different directions through France, have been laid down: some will require many years to complete:—

Lille to Calais and Dunkerque—in progress.

Paris to the German frontier, by Naney, Strasburg,—Strasburg to Hommarting in progress.

Paris to the Mediterranean, by Lyons and Marseilles. Between Dijon and Châlons in progress (common to Mediterranean and Rhine line).

Paris to the Spanish frontier, Tours to Poitiers, Angoulême, Bordeaux, in progress.

Paris to the Atlantic, Tours to Nantes, in progress.

Paris to the centre of France, by Bourges, Nevers, and Clermont. From Orleans to Châteauroux, finished; in progress to Limoges and to Clermont.

Paris to Brest. In progress from Versailles to Chartres, and from Chartres to Rennes.

St. Dizier to Gray—in progress.

Mediterranean to the Rhine, by Lyons, Dijon, and Mühlhausen.

The journey from Paris to London, viâ Folkestone and Boulogne, may be performed, exclusive of stoppages, in 14 hours.

#### i. STEAM-BOATS.

The use of steam is now very general in France, all the great rivers being traversed by steamers.

##### *Inland Steam Navigation.*

*The Seine*, from Havre to Rouen, from Paris to Fontainebleau and Montereau.

*The Oise*, to Compiègne.

*The Loire*, from Nantes to Tours;—Orleans, to Gien, Nevers, and Digoin.

*The Allier*, to Moulins.

*The Aulne*, Brest to Châteaulin.

*The Charente*, Rochefort to Saintes and Angoulême.

*The Garonne*, Bordeaux to Agen.

*The Gironde*, Bordeaux to the sea.

*The Rhône*, from Arles to Lyons and Seyssel, and between Arles and Marseilles by merchant steamers.

*The Saône*, from Lyons to Châlons.

*The Moselle*, from Trèves to Thionville.

In almost all cases the engineers employed on these vessels are Englishmen: the French do not seem to have aptitude for this duty.

The rivers of France are more liable than those of Britain to rise and fall, and a sudden elevation caused by rains, or a want of water owing to

drought, has equally the effect of arresting the navigation ; the last by withdrawing the necessary depth of water, the first by filling the arches of the bridges so as to leave no room for the steamers to pass under them.

There are also a great number of coasting steamers ; but the traveller should be cautious in trusting himself to them, unless the character of the captains and engineers be well ascertained to be of tried experience, as accidents not unfrequently happen, and even the French themselves do not place unlimited confidence in coasting steamers.

#### k. INNS—TABLES-D'HÔTE, ETC.

On the whole, the inns of France are very inferior to those of Germany and Switzerland, in the want of general comfort, and above all of cleanliness—their greatest drawback. There is an exception to this, however, in the bed and table linen. Even the filthy cabaret, whose kitchen and salon are scarcely endurable to look at, commonly affords napkins and table-cloths clean, though coarse and rough, and beds with unsullied sheets and white draperies, together with well-stuffed mattresses and pillows, which put German cribs and feather-beds to shame. Many of the most *important essentials*, on the other hand, are utterly disregarded, and evince a state of grossness and barbarism hardly to be expected in a civilised country ; the provisions for personal ablution are very defective ; the washing of floors, whether of timber or tile, seems unknown. In the better hotels, indeed, the floors are polished as tables are in England, with brushes attached to the feet instead of hands ; but in most cases they are black with the accumulated filth of years, a little water being sprinkled on them from time to time to lay the dust and increase the dark crust of dirt.

French inns may be divided into two classes :—*a.* Those which make some pretension to study English tastes and habits (and a few of them have some claim to be considered comfortable), and, being frequented by Englishmen, are very exorbitant in their charges. Such are met with along the great roads to Paris, and thence to Geneva, Lyons, and Marseilles. *b.* Those in remote situations, not yet corrupted to exorbitance by the English and their couriers ; where the traveller who can conform with the customs of the country is treated fairly, and charged no higher than a Frenchman. The expense of living in these country inns is moderate, 6 francs a-day board and lodging, and 10 sous to the servants.

In one respect the inns of France are more accommodating than those of Germany, that they will furnish at almost any hour of the day, at 10 minutes or  $\frac{1}{4}$  hour's notice, a well-dressed *dinner* of 8 or 10 dishes, at a cost not greatly exceeding that of the table-d'hôte. When ordering dinner in private, the traveller should specify the price at which he chooses to be served, fixing the sum at 3, 5, or more francs, as he may please. In remote places and small inns, never order dinner at a higher price than 3 francs : the people have only the same food to present, even if they charged 10 francs. A capital dinner is usually furnished at 4 fr. a-head ; but the traveller who goes post in his own carriage will probably be charged 6, unless he specifies the price beforehand. The usual charge for a table-d'hôte dinner is 3 fr. (including wine in a wine country,



but not in the north), and ought never to exceed that except in large towns and first-rate inns.

Bargaining for rooms before you enter an inn, though usual, sometimes leads the landlord to suppose that you are going to beat him down (marchander), and he may therefore name a higher price than he is willing to take, and thus you may cause the exorbitance which you intend to prevent.

*Tables-d'hôte*, though very general throughout France, are *rarely* resorted to by the most respectable townspeople, or by ladies, as in Germany. The majority of the company almost invariably consists of "commis voyageurs," Anglicè bagmen, but of a stamp very inferior to those of the same class in England, who swarm in all the inns, and are consequently the most important personages. Without denying that there are exceptions among these gentry, it is impossible to have sojourned in France for any time without the conviction that a more selfish, depraved, and vulgar, if not brutal, set does not exist, and gentlemen will take good care not to encourage their approaches, and to keep at a distance from them. They commonly sit down to table with their hats on, and scramble for the dishes, so that the stranger who is not on the alert is likely to fare very ill; and if females be present, not only do not pay them that attention which is customary in all civilised countries at a dinner-table, and used at one time especially to distinguish the French, but, as Mrs. Trollope remarks, constantly "use language which no Englishman would dream of uttering in their presence," evincing an utter want of all sense of propriety and decency. English ladies, therefore, will be cautious of presenting themselves at a French table-d'hôte, except in first-rate hotels, where English guests form a considerable part of the company, and at the well-frequented watering-places. Even at Bagnères de Bigorre, Lady Chatterton relates, "We laughed a good deal at a scene we witnessed at the table-d'hôte yesterday, where a Frenchman, after helping himself to all the best pieces of the roast fowl, turned to the lady next him, and said, with a most insinuating smile, 'Madame ne mange pas de volaille.'"

There are no established *fees* for the *servants* at inns;  $\frac{1}{2}$  a franc a-day "pour le service," and something extra (5 or 6 sous) for boots, "le décrotteur," is enough. At Meurice's Hotel, in Paris, the house charge for servants is only 1 franc a-day.

#### *Average Charges at French Provincial Hotels.*

Bedroom, 1 fr. 50 c. to 2 fr. 5 c.

Salon, 3 fr. and upwards.

*Breakfast*, tea and coffee, with bread and butter, 1 fr. 50 c.; with meat, 2 fr.

*Dinner*, table-d'hôte, 3 fr.—Apart, 4 fr. to 5 fr. or upwards.

*Bottle of vin ordinaire*, 1 fr.—N.B. Included in the charge for dinner in wine-growing countries.

The better wines are sold in demi-bouteilles. When only a part of the bottle is consumed, the waiter puts it aside for the owner until another time.

*Coffee*, 1 fr. It is better to take it at a café, where it is always better, and costs only 8 or 10 sous.

*Bougies* (wax lights), 1 fr. ; where this charge is made, that for the bedroom ought not to exceed 1 fr. 50 c.

l. CAFÉS.

We have no equivalent in England for the Cafés in France, and the number and splendour of some of these establishments, everywhere seemingly out of proportion to the population and to other shops, not only in Paris, but in every provincial town, may well excite surprise. They are adapted to all classes of society, from the magnificent *salon*, resplendent with looking-glass, and glittering with gilding, the decorations of which have perhaps cost 4000*l.* or 5000*l.*, down to the low and confined *estaminets*, resorted to by carters, porters, and common labourers, which abound in the back streets of every town, and in every village, however small and remote. The latter sort occupy the place of the beer-shops of England, furnish beer and brandy, as well as coffee, and, though not so injurious to health and morals as the gin-palaces of London, are even more destructive of time : indeed, the dissipation of precious hours by almost all classes in France produces as bad an effect on the habits of the people.

It is only to the superior class of cafés that an English traveller is likely to resort, and they furnish some agreeable resources to a stranger in a strange place. In the morning he may there obtain a breakfast of coffee or tea, better and cheaper than in an hotel, and far better than he can procure it in England ; in the afternoon, a *demi-tasse* of coffee well prepared, and a *petit verre* of liqueur ; and in the evening, in summer, excellent ices, sorbettes, orgeats, limonade, and other cool drinks ; and in winter a very tolerable potation called “ punch,” but differing from its English prototype. They are always supplied with the journals of Paris and the provinces, including, in the principal cities, ‘ *Galignani’s Messenger*,’ and have usually billiard-tables attached to them.

In the evening they are most crowded, and even in the most respectable (except the first-rate Parisian cafés) the company is very mixed. Clerks, tradesmen, *commis voyageurs*, soldiers—officers as well as privates, and men in blouses, crowded about a multitude of little marble tables, wrangle over provincial or national politics, or over games of cards or dominoes, while others perspiring in their shirt-sleeves surround the billiard-table. The rattling of balls, the cries of waiters hurrying to and fro, the gingling of dominoes, and tinkling bell of the mistress who presides at the bar, alone prevail over the harsh din of many voices, while the splendour of mirrored walls and velvet seats is eclipsed behind a cloud of unfragrant tobacco-smoke. Such is the picture of a French café !

A large cup of coffee (*café au lait*), with bread and butter, and an egg for breakfast, costs about 20 or 24 sous. A *demi-tasse*, or small cup in the afternoon, 8 or 10 sous ; a *petit verre* de cognac, 5 sous. The waiter usually receives 2 sous.

m. A TRAVELLER’S GENERAL VIEW OF FRANCE.

It has been the custom of the English, who traverse France on their way to Italy or Switzerland, to complain of the tiresome and monotonous



features of the country, and to ridicule the epithet "*La belle France*," which the French, who, it must be confessed, have in general no true feeling for the beauties of nature, are wont to apply to it. By a "beautiful" country, a Frenchman generally understands one richly fertile and fully cultivated; and in this point of view the epithet is justly applied to France. It is also most fortunate in its climate. Many of its vineyards, the most valuable spots in the country, occupy tracts of poor, barren, and waste land, which in our climate would be absolutely unprofitable. But in truth our countrymen are unjust in forming their opinion from the routes between Calais and Paris, and thence to Lyons, Strasburg, and Dijon, perhaps the least varied part of the kingdom, and at least no fair sample of its beauties. To this district, and to a large part of the province of Champagne, the descriptions of "wearisome expanse of tillage, unvaried by hill or dale, and extent of corn-land or pasture, without enclosures, supremely tiresome," are almost exclusively applicable. Throughout nearly one half of France, especially in Lower Normandy, Brittany, a great part of the country S. of the Loire, the vicinity of the Pyrenees, Limousin, Auvergne, and Dauphiné, enclosures and hedges are almost as common as in England, and the variety of surface in some of these districts is far greater. Our own island, indeed, presents as it were a miniature of other lands—a concentration, within a small area, of scenery, varying from flat fen and rolling down to mountains and precipices. In France, the features of nature are broad and expanded, and you must often traverse 50 or 100 miles to encounter those pleasing changes which, in Britain, succeed one another almost every 10 miles. If the English had confined themselves less to the beaten track in their way from the Channel to the Mediterranean, they would have verified the truth of this assertion.

More than 50 years ago, Arthur Young advised those "who know no more of France than just once passing through it to Italy, that, if they would see some of the finest parts of the kingdom, they should land at Havre, follow the Seine up to Paris, then take the great road to Moulins, and there quit it for Auvergne, and so to the Rhône at Valence or Viviers: such a variation from the common road, though it demand more time, would repay them by the sight of a much finer and more singular country than the road by Dijon." The traveller may at present farther vary his route by going from Paris by railway to Orleans, and thence by Bourges either to Clermont in Auvergne, or to Nevers and Moulins on the high road from Paris to Lyons.

The districts of France which chiefly recommend themselves by their beauty and variety of scenery are, in the north, Normandy, the banks of the Seine (the finest of the great rivers of France), the valleys round Vire, Mortain, and Avranches, the wild coast scenery of Brittany, and the course of the Rance, and of other streams near Quimper; in the centre, the Loire below Tours, and parts of Limousin; Auvergne, the Cantal and Ardèche, the Rhône—by some preferred to the Rhine, on account of its more extended prospects; in the east, the hills of the Jura, the mountains and valleys of Dauphiné, especially the vale of the Gresivaudan, the gorge of the Grande Chartreuse, and the savage magnificence of peak and



glacier around Mont Pelvoux, a region which may be styled the Chamouny or Grindelwald of France. Among the Vosges and Ardennes are many soberly romantic scenes which have as yet attracted but little notice from travellers; in the south, Provence, with its sunny sky, is too arid to deserve general praise, excepting that favoured terrace at the foot of the Alps along the shore of the Mediterranean, intervening between Toulon and Nice. The Pyrenees, however, without doubt, include the finest scenery in France, and, except in the want of lakes, are scarcely inferior to the Alps of Switzerland and Savoy.

This slight enumeration of the chief points of interest is filled up in ampler details in the introductions to the different sections into which this Hand-book is divided, with the view of enabling the traveller to lay down for himself the plan of a tour, embracing as many of these points as his time or inclination will permit.

“Bretagne, Maine, and Anjou have the appearance of deserts. The fertile territories of Flanders, Artois, and Alsace are distinguished by their utility. Picardy is uninteresting. Champagne, in general, where I saw it, ugly, almost as much so as Poitou. Lorraine, Franche Comté, and Bourgogne are *sombre* in the wooded districts, and want cheerfulness in the open ones. Berri and La Manche may be ranked in the same class.”—*Arthur Young*.

On the other hand, these districts, which are not interesting in point of scenery, have a compensating recommendation in their architectural remains, and relics of antiquity. The heaths of Brittany are studded with extraordinary Celtic remains, and abound in most beautiful churches. Out of the midst of the monotonous plain of La Beauce rises the wondrous fabric of Chartres cathedral; that of Bourges (colossal pile) overlooks the dull plain of Berri, as the spire of Strasburg surmounts the flat valley of the Rhine. Rheims, Troyes, Laon, &c., give an interest to the otherwise tiresome journey through Champagne; the sight of Amiens, Beauvais, and Abbeville, makes one forget the length of the way through Picardy and Artois; and the Roman remains of Nismes, Arles, St. Remy, Orange, and Antibes, equal to almost any in Italy, would alone compensate for a journey to Provence, even had it no other claims to interest. France, however, is particularly rich in architectural remains, especially in Gothic architecture, of which it possesses some of the noblest specimens existing, viz. the cathedrals above enumerated; to which must be added those of Metz, and 3 churches at Rouen.

These glorious monuments of architectural skill and lavish devotion are far more stupendous in their proportions than the cathedrals of England, but have this peculiarity, that scarcely one of them is finished: thus, Beauvais has no nave, Amiens is incomplete in its towers, Abbeville has no choir, St. Ouen no front. It has been said that a perfect cathedral might be made of the portal of Rheims, the nave of Amiens, the choir of Beauvais, and the tower of Chartres.

The rose or wheel windows are both more frequent and of larger dimensions than in English cathedrals, and contribute greatly to the beauty of those of France, where it is not uncommon to find three in one church. The quantity, variety, and richness of the *painted glass* which the eccle-

siastical edifices still retain, in spite of Huguenot iconoclasts and Revolutionary destructives, is quite marvellous: we have nothing to compare with it in England.

The churches in the N. of France are closed from 12 to 6, except the cathedrals, which re-open at 4. In the S. they remain open all day. The choir, its aisles and side chapels, are usually closed by an iron grating, and to obtain admittance one must apply to the *suisse*, or beadle, who struts about in cocked hat, sword, and laced livery.

The finest provincial cities are Lyons, Rouen, Bordeaux, Marseilles, and Nantes, all more or less distinguished for commerce, manufactures, and fine edifices. The minor provincial towns have a certain number of features in common which will not fail to draw the traveller's observation: such are the formal walk near the entrance or on the outskirts, often a mere platform, planted with rows of stunted trees, and the resort of nursery-maids, washerwomen, and recruits undergoing drill, except on Sundays or fête-days, when the dusty and gritty platform is crowded with a gay throng, to whom the sight of bright ribbons, shawls, and new bonnets, compensates for the want of other prospect. A walk into the country and across the fields is never thought of by the French artisan or shopkeeper, nor indeed are there any field paths, green shady lanes, or pretty villas, or neat cottages with gardens, on the outskirts of the towns, to invite him to sally forth. The *high roads* in France have been greatly improved within the last 10 years; many are now macadamized—indeed the whole country shows unequivocal signs of great and increasing prosperity.

Every town of a certain size is surrounded with a wall or barrier for the purpose of levying the *octroi* or town duties on all articles for eating and drinking brought into it, and which go to the municipal caisse or corporation funds. All carts and carriages, public and private, are stopped at the gates in consequence, by douaniers, who search them and the baggage contained in them, to ascertain that no "comestibles" are concealed, in order to evade this tax. The space outside the gates usually swarms with low cabarets, guinguettes, &c., where the poor man may eat and drink at a cheaper rate than within the walls.

Arrived within the town, the traveller will commonly find narrow streets, with no pavement at the sides, but a huge gutter in the centre, neither clean nor sweet, lighted at night by lamps (*réverbères*), swinging from ropes attached to the houses on either side. After passing one or more barracks, the number of which and of soldiers is striking everywhere, the barrack being often a sequestered convent or church, he will reach the grande Place or square. On one side of it, or in some other conspicuous situation, appears a large white-washed building, graced probably with a portico in front, guarded by a sentinel, surmounted by a tricolor flag, and fenced round by a tall iron railing tipped with gilt spearheads. This is the *préfecture* or *sous-préfecture*.

There are many institutions and establishments in French towns deserving high commendation and general imitation in England: such are the Abattoirs, or slaughter-houses, always in the outskirts; the public Cemeteries, always removed beyond the walls; even the Public Walks



to be found in every French town, though not suited altogether to English ideas of recreation, yet show an attention to the health and enjoyment of the people which is worthy of imitation north of the Channel.

In all the larger towns there is a museum of natural history, and generally of paintings, which, although for the most part of inferior merit, are commendable as institutions for public recreation.

Still more commendable are the public libraries and reading-rooms, arranged in convenient apartments with salaried librarians, common in all French provincial towns. An amiable traveller observes, "I could not visit these libraries without wishing that similar institutions could be introduced into England, where the easy access to books in every part of the kingdom could not but prove at once agreeable and beneficial. The encouragement of such an object would be a wise application of the public money."—*Mr. Gally Knight's Tour in Normandy.*

There are three authors whose works should be perused before entering France: Cæsar, for its ancient history; Froissart, for its feudal history; and Arthur Young, for the picture of France before the Revolution: his vivid local descriptions hold good to the present day.

To those who would attain some insight into the French *character*, previously to any personal intercourse with the people, no more agreeable or useful work can be recommended than "A Comparative View of the Social Condition of England and France," by the Editor of *Madame du Deffand's Letters*, the author of which has studied the national character through the double medium of long personal intercourse with the highest classes of society, and of an intimate acquaintance with the history of the country.

---



*n.* LIST OF THE 86 DEPARTMENTS INTO WHICH FRANCE IS DIVIDED, AND OF THE 33 ANCIENT PROVINCES COMPOSING THEM.

<i>Provinces.</i>	<i>Départemens.</i>	<i>Chefs-Lieux.</i>
ILE DE FRANCE, WITH LA BRIE, &c.	Seine.	Paris.
	Seine-et-Oise.	Versailles.
	Seine-et-Marne.	Melun.
	Oise.	Beauvais.
PICARDIE.	Aisne.	Laon.
ARTOIS AND BOULONNAIS.	Somme.	Amiens.
FLANDRE AND HAINAUT FRANÇAIS.	Pas-de-Calais.	Arras.
NORMANDIE.	Nord.	Lille.
	Seine-Inférieure.	Rouen.
	Eure.	Evreux.
	Calvados.	Caen.
	Orne.	Alençon.
BRETAGNE.	Manche.	Saint-Lô.
	Ille-et-Vilaine.	Rennes.
	Côtes-du-Nord.	Saint-Brieux.
	Finisterre.	Quimper.
	Morbihan.	Vannes.
ORLÉANAIS.	Loire-Inférieure.	Nantes.
	Loiret.	Orléans.
	Loir-et-Cher.	Blois.
BEAUCE AND PAYS CHARTRAIN.	Eure-et-Loire.	Chartres.
MAINE.	Sarthe.	Le Mans.
ANJOU.	Mayenne.	Laval.
TOURAINÉ.	Maine-et-Loire.	Angers.
POITOU.	Indre-et-Loire.	Tours.
	Vendée.	Bourbon-Vendée.
	Deux-Sèvres.	Niort.
BERRI.	Vienne.	Poitiers.
	Indre.	Châteauroux.
	Cher.	Bourges.
MARCHE.	Creuze.	Gueret.
LIMOUSIN.	Haute-Vienne.	Limoges.
ANGOUMOIS.	Corrèze.	Tulle.
SAINTONGE AND AUNIS.	Charente.	Angoulême.
PÉRIGORD.	Charente-Inférieure.	La Rochelle.
GUYENNE.	Dordogne.	Périgueux.
	Gironde.	Bordeaux.
	Lot-et-Garonne.	Agen.
	Lot.	Cahors.
	Tarn-et-Garonne.	Montauban.
ARMAGNAC (PART OF GASCOGNE).	Aveyron.	Rhodes.
BIGORRE (PART OF GASCOGNE).	Gers.	Auch.
	Hautes-Pyrénées.	Tarbes.

<i>Provinces.</i>	<i>Départemens.</i>	<i>Chefs-Lieux.</i>
GASCOGNE.	Landes.	Mont-de-Marsan.
BÉARN AND FRENCH NA- VARRE.	Basses-Pyrénées.	Pau.
COMTÉ DE FOIX.	Arriège.	Foix.
ROUSSILLON.	Pyrénées-Orientales.	Perpignan.
	Haute-Garonne.	Toulouse.
	Tarn.	Alby.
LANGUEDOC.	Aude.	Carcassonne.
	Hérault.	Montpellier.
	Gard.	Nismes.
VIVARAIS.	Ardèche.	Privas.
GÉVAUDAN.	Lozère.	Mende.
VELAY.	Haute-Loire.	Le Puy.
COMTAT VENAISSIN, ORANGE, &c.	Vaucluse.	Avignon.
	Bouches-du-Rhône.	Marseille.
PROVENCE.	Var.	Draguignan.
	Basses-Alpes.	Digne.
	Isère.	Grenoble.
DAUPHINÉ.	Drôme.	Valence.
	Hautes-Alpes.	Gap.
LYONNAIS AND BEAUJOLAIS.	Rhône.	Lyon.
FOREZ.	Loire.	Montbrison.
AUVERGNE.	Puy-de-Dôme.	Clermont.
	Cantal.	Aurillac.
BOURBONNAIS.	Allier.	Moulins.
NIVERNAIS.	Nièvre.	Nevers.
BRESSE, BUGÉY, &c.	Ain.	Bourg.
	Saône-et-Loire.	Mâcon.
BOURGOGNE (DUCHE').	Côte d'Or.	Dijon.
	Yonne.	Auxerre.
	Doubs.	Besançon.
COMTÉ DE BOURGOGNE, OR FRANCHE-COMTÉ.	Jura.	Lons-le-Saulnier.
	Haute-Saône.	Vesoul.
	Aube.	Troyes.
CHAMPAGNE.	Marne.	Châlons-sur-Marne.
	Haute-Marne.	Chaumont.
	Ardennes.	Mézières.
	Meurthe.	Nancy.
LORRAINE.	Meuse.	Bar-le-Duc.
	Moselle.	Metz.
	Vosges.	Epinal.
ALSACE.	Bas-Rhin.	Strasbourg.
	Haut-Rhin.	Colmar.
CORSICA.	Corse.	Ajaccio.

## O. THE ENGLISH ABROAD.

It may not be amiss here briefly to consider the causes which render the English so unpopular on the Continent; as to the fact of their being so, it is to be feared there can be no doubt. In the first place, it arises from the number of ill-conditioned persons (*mauvais sujets*) who, not being in condition to face the world at home, scatter themselves over *France*.

foreign lands, and bring no little discredit upon their country. But in addition to these, there are many respectable and wealthy persons, who, through inattention, unguardedness, wanton expenditure in some cases, niggardly parsimony in others, but, above all, from an unwillingness to accommodate themselves to the feelings of the people they are among, contribute not a little to bring their own nation into disrepute. The Englishman abroad too often forgets that he is the representative of his country, and that his countrymen will be judged by his own conduct; that by affability, moderation, and being easily pleased, he will conciliate; whereas by caprice, extravagant squandering, or ill-timed niggardness, he affects the reception of the next comer.

There are many points, however, in which our character is misunderstood by foreigners. The morose sullenness attributed by them to the Englishman is, in perhaps nine cases out of ten, nothing more than involuntary silence, arising from his ignorance of foreign languages, or at least from his want of sufficient fluency to make himself readily understood, which thus prevents his enjoying society. If an Englishman were fully aware how much it increases the pleasure and profit of travelling to have made some progress in foreign languages before he sets foot on the Continent, no one would think of quitting home until he had devoted at least some months to hard labour with grammars and dictionaries.

Englishmen and Protestants, admitted into Roman Catholic churches, at times are often inconsiderate in talking loud, laughing, and stamping with their feet while the service is going on: a moment's reflection should point out to them that they should regard the feelings of those around them who are engaged in their devotions. Above all, they should avoid as much as possible turning their backs upon the altar. In a church ladies and gentlemen should not walk arm in arm—as that is contrary to the usual practice of the people and to their idea of good manners: they should avoid talking together during service.

Our countrymen have a reputation for pugnacity in France: let them therefore be especially cautious not to make use of their fists, however great the provocation, otherwise they will rue it. No French magistrate or judge will listen to any plea of provocation; fine and imprisonment are the offender's inevitable portion.

By official returns it appears that there are at present in France 66,000 English residents. Supposing the average expenditure of each to be 5 francs a-day, the sum total will amount to about 4,820,000*l.* per annum. In not fewer than 25 towns of France, places of worship for the performance of the *English Church Service* have been established, and at most of these there are resident English ministers, many of them having the licence of the Bishop of London. With few exceptions the stipends are very small, and English travellers availing themselves of the privilege and benefit afforded by these places of worship should remember that they are in duty bound to contribute, according to their means, to the support of the establishments and their ministers. For more detailed information consult "*Dr. Biber's English Churches on the Continent*," a very interesting and useful little work.



p. SKELETON TOUR THROUGH FRANCE, TO EMBRACE THE PRINCIPAL OBJECTS OF CURIOSITY, AND TO OCCUPY FIVE OR SIX MONTHS,

HAVRE—By land up the N. bank of the Seine, halting to explore its beauties and curiosities.  
Rouen (to Paris by railway).  
Andelys.  
Descend the Seine by steamer to Honfleur, or by railway to Havre.  
Caen.  
Bayeux (Cherbourg).  
Vire.  
Avranches and Mont St. Michel.  
St. Malo.  
Dinant (Brest and Quimper).  
Vannes and Carnac.  
Nantes—Clisson.  
Ascent of the Loire to Angers.  
Saumur.  
Chinon.  
Tours.  
Loches—Chénonceaux.  
Amboise.  
Blois—Chambord.  
Orleans.  
Bourges.  
Clermont—Puy de Dôme.  
Mont Dore.  
Cantal.  
Le Puy.  
St. Etienne.  
Lyons.  
Descent of Rhône—Valence.  
Montelimart—Aubenas—Ardèche.  
Viviers on the Rhône.  
Orange.  
Avignon—Pont du Gard.  
Nismes.  
Montpellier.  
Narbonne.

Toulouse.  
Descent of the Garonne.  
Bordeaux.  
Bayonne.  
Pau.  
Tour of the W. Pyrenees.  
St. Gaudens.  
Tour of the E. Pyrenees.  
Perpignan.  
Narbonne.  
Montpellier.  
Arles—Aix.  
Marseilles.  
Toulon.  
Cannes.  
Digne.  
Sisteron.  
Gap.  
Embrun—Val Queiras.  
Briançon.  
Pass of Lauteret—Mont Pelvoux.  
Bourg d'Oysans.  
Grenoble—Vale of Gresivaudan.  
Grande Chartreuse.  
Bourg.  
Châlons-sur-Saône.  
Dijon.  
Besançon.  
Colmar.  
Strasburg.  
Nancy.  
Troyes.  
Châlons-sur-Marne.  
Rheims.  
Soissons.  
Amiens.  
Boulogne.

q. ROUTE AND TIME FROM LONDON TO MARSEILLES TO MEET THE OVERLAND MAIL STEAMER AT MALTA, SECURING BEFOREHAND PLACES IN THE MALLE POSTE.

	Hours.
London to Folkestone or Dover (express) . . . . .	2½
Folkestone to Boulogne . . . . .	2
Boulogne to Abbeville . . . . .	3¾
Abbeville by Amiens to Paris, Rail . . . . .	6
Or,	
London to Brighton and Dieppe . . . . .	11
Dieppe to Paris by Railway . . . . .	10
(say 24 hours from London to Paris.)	
In Paris . . . . .	12 or 36
Paris to Marseilles (Malle poste), 3 nights, 2½ days . . . . .	66

An English Government steamer plies once a-month direct between Marseilles and Malta, where it meets the packet coming direct from England. The fare is 9*l.*, including board, for a 1st class passenger; that of the 2nd class being 5*l.* It leaves Marseilles on the 11th of every month, arriving at Malta early on the third day, or the 14th; and brings with it the London mail for India, which is made up on the 7th, unless it should happen to fall on a Sunday, when it is deferred till the following day. By this junction-steamer letters can be despatched from London three or four days later than by the packet that goes round by Gibraltar to Malta.

The arrangements of the Mediterranean steamers are frequently changing; and it is therefore advisable to refer to the Tariffs issued annually by the different companies.

You ought to reach Marseilles on the 10th or very early on the 11th of the month, in order to embark comfortably.

In order to be enabled to remain in England till the last moment, it is necessary to write to a correspondent at Paris to secure a place in the malle poste by payment a week beforehand, or even a fortnight, to make sure. Start from London on the evening of the 4th.

At Marseilles it is necessary to get the passport visé by the British consul, the local police (and the Neapolitan consul, if you intend to land at Naples); also a bill of health, and a permis d'embarquement.

Persons wishing to travel more leisurely, and to avoid fatigue, should start on the 1st of the month or earlier, take the diligence from Paris to Châlons, whence they may proceed by water down the Saône and Rhône to Avignon or Arles, within 50 m. of Marseilles. The railway from Avignon to Marseilles is nearly finished, and will shorten the journey by 4 hours.

A place in the coupé of the diligence from Paris to Marseilles costs 4*l.*

French Government steamers ply from Marseilles to Alexandria, Constantinople, and Beyrout, touching at Malta, 3 times a-month. Other French Government steamers run from Marseilles to Malta, touching on the way at Leghorn, Civita Vecchia, and Naples.

---

\*.\* You may go all the way from Marseilles to Paris by rail or water, excepting about 10 hours' drive, by ascending the Rhône to Lyons and the Saône to Mâcon, where take the diligence to Digoïn (p. 368), and the steamer thence to Orleans.

---

## ABBREVIATIONS, &amp;c., USED IN THE HAND-BOOK.

The points of the Compass are often marked simply by the letters N. S. E. W.

(*rt.*) right, (*l.*) left,—applied to the banks of a river. The right bank is that which lies on the right hand of a person whose back is turned towards the source, or the quarter from which the current descends.

kilom. for kilomètre.

Cent. for Century.

m. for English mile.

R. Rte. for Route.

Dept. for Department.

p. for page.

Inhab. for Inhabitants.

St. Stat. for Railway Station.

The names of Inns precede the description of every place (often in a parenthesis), because the first information needed by a traveller is where to lodge. The best Inns, as far as they can be determined, are placed first.

Instead of designating a town by the vague words “large” or “small,” the amount of the population, according to the latest census, is almost invariably stated, as presenting a more exact scale of the importance and size of the place.

Every Route has a number, corresponding with the figures attached to the Route on the General Map of France, which thus serves as an index to the Book, at the same time that it presents a *tolerably* exact view of the great high roads of France, and of the course of public conveyances.

---

 LIST OF MAPS.

Course of the Seine and Railways	.	To face page	43
————— Loire and Railways	.	.	172
The Pyrenees . . . . .	.	.	234
Course of the Rhône and Railways	.	.	440
General Map of France . . . .	.	At the end.	



## ADDITIONS AND CORRECTIONS.

- P. 193, 194. TOURS.—The Faisan is stated to be still the best inn here, better than the new one (Ly. E.).
- P. 246 and 356.—The RAILWAY was opened in 1847 from Vierzon to Châteauroux (7 hours from Paris) by Issoudun.
- P. 279. Route 76.—227 = 141 Eng. m., *not* 184.
- P. 289.—For “Willoughby” *read* “Stapleton Cotton.”
- P. 338. Route 91.—For 80 Eng. m. *read* 90.
- P. 346. Route 97.—For 59 Eng. m. *read* 50.
- P. 366.—Bignon is 15 m. from Nemours, on the way to Sens.—C. D.
- P. 371.—ROANNE. The Poste is the newly-furnished inn, and it is comfortable: there is no H. du Midi.
- P. 372.—Roanne—Diligence to Digoin (p. 368) in about 5 hours: Railway to St. Etienne in 5½ hours.
- P. 386. — Vermanton.—Inn, Etoile, comfortable and clean. *Lucy-le-Bois*, *no Inn*.
- P. 390.—Mâcon. Diligence to Digoin (p. 368) on the Loire, in about 10 hours. Steamer from Digoin to Orleans every other morning.
- P. 399.—ROYAT is 2 m. from Clermont, *not* 8.
- P. 408.—MONT DORE LES BAINS.—Inns, Chaboury le Jeune, best; H. de Paris (Chaboury l'Aîné) and H. Bellon are good; Baraduc's house is H. de Lyon, P!
- P. 440.—Col. 1, l. 18, *for* 135 Eng. m. *read* 163.
- P. 487.—Col. 1, l. 3 from bottom, *for* W. of port, *read* N.
- P. 515. Route 136.—Inns, At Grasse, Poste, very good, best between Nice and Grenoble. At Barrême (1750 inhab.), H. du Midi, tolerable. Between Grasse and St. Vallière the views are exquisite. From Castellane (Inn, H. du Levant, dirty and dear), pop. 2000, *Diligences* run daily to Grasse and to Digne.

*Blois*.—The restorations of the Castle are proceeding. The salamanders of Francis, the ermine of Claude, and other devices which ornamented the magnificent staircase, have been replaced.

The “Crème de St. Gervais” is a sort of whipped cream, not like Devonshire cream.

*Orléans*.—The collection of antiquities forming the Museum is now deposited in the antique Hôtel de Ville.

# HAND-BOOK

FOR

## TRAVELLERS IN FRANCE.

### SECTION I.

PICARDY.—ILE DE FRANCE.—NORMANDY.

#### INTRODUCTORY INFORMATION.

OBJECTS OF INTEREST.—COUNTRY OF NORMANDY.—ARCHITECTURAL REMAINS.—  
SKELETON TOUR.

#### ROUTES.

\* \* The names of places are printed in *italics* only in those Routes where the *places* are described.

ROUTE	PAGE	ROUTE	PAGE
1 Calais to Paris, by <i>St. Omer</i> , <i>Amiens</i> , and <i>Chantilly</i> . . .	3	<i>cherville</i> , <i>Jumièges</i> , <i>Caude-</i> <i>bec</i> , and <i>Lillebonne</i> . . .	56
2 Calais to Paris, by <i>Boulogne</i> , <i>Abbeville</i> , and <i>Beauvais</i> . . .	7	14 Rouen to <i>Havre</i> —RAILROAD, by <i>Yvetot</i> and <i>Bolbec</i> . . .	60
3 Boulogne to Paris, by <i>Abbe-</i> <i>ville</i> , <i>Amiens</i> , <i>Pontoise</i> , and <i>St. Denis</i> . (RAILROAD) . . .	18	18 Havre to Dieppe and <i>Ab-</i> <i>beville</i> , by <i>Fécamp</i> and <i>Eu</i> . . .	66
5 Dieppe to Paris, by <i>Gisors</i> . . .	24	21 Rouen to Alençon, by <i>Ber-</i> <i>nay</i> , <i>Broglie</i> , and <i>Sées</i> . . .	70
6 Dieppe to Rouen (RAIL- ROAD) . . . . .	28	23 Rouen to Caen, by <i>Brionne</i> or by <i>Honfleur</i> . . . . .	70
8 Paris to Rouen (RAILROAD) . . .	29	24 Havre to Caen . . . . .	72
9 Paris to Rouen. — <i>Lower</i> <i>Road</i> , by <i>St. Germain</i> and <i>Louviers</i> . . . . .	43	25 Paris to Caen, by <i>Evreux</i> and <i>Lisieux</i> . . . . .	73
10 Paris to Rouen. — <i>Upper</i> <i>Road</i> , by <i>Gisors</i> or by <i>Magny</i> . . . . .	47	26 Caen to <i>Cherbourg</i> , by <i>Bayeux</i> . . .	80
11 THE SEINE, A. — <i>St. Germain</i> to Rouen.— <i>Roche Guyon</i> . — <i>Château Gaillard</i> . . . . .	48	27 Cherbourg to <i>St. Malo</i> , by <i>Coutances</i> . — <i>Granville</i> . — <i>Avranches</i> .— <i>Mont St. Mi-</i> <i>chel</i> , and <i>Dol</i> . . . . .	90
12 THE SEINE, B. — Rouen to <i>Havre</i> . . . . .	53	29 Caen to Tours, by <i>Falaise</i> .— <i>Alençon</i> . . . . .	
13 Rouen to Havre. — <i>Lower</i> <i>Road</i> , by <i>St. George Bos-</i>		31 Caen to Rennes, by <i>Vire</i> , <i>Mortain</i> , and <i>Fougères</i> . . . . .	102
		32 Bayeux to <i>St. Lo</i> and <i>Av-</i> <i>ranches</i> . . . . .	104

PICARDY and Ile de France, through which lie the routes to Paris from Calais and Boulogne, present no attractions of picturesqueness, but some interesting historical associations to Englishmen, and a few fine examples of Gothic architecture, the chief of which are the Cathedrals of Amiens, Beauvais, Abbeville.

Normandy, on the other hand, is full of interest in many respects:—it is  
*France*.



remarkable for varied outline of swelling hills waving with corn; for beautiful valleys abounding in orchards, and in rich pasturages, on which large herds of cattle are reared, and traversed by winding rivers; for richness and careful cultivation; and above all, for remains of antiquity; venerable cities, the delight of the painter; noble cathedrals, abbeys and churches, not confined merely to the larger towns, but scattered over the country, so that every little village, in some parts, possesses a fine specimen of Gothic architecture. Normandy is decidedly among the most attractive portions of France. Parts of the upper country are certainly flat, bare, monotonous tableland; but in its joyous sunny slopes and winding dales, in its hedgerows, orchards, thatched cottages with gardens, in the general character of the landscape of La Basse Normandie, especially in its verdure, frequent village spires, and white chalk cliffs, an Englishman recognises with pleasure the features of his own Fatherland, which no other part of the Continent affords. He may also take pleasure in remembering that this was the cradle whence came the wise and hardy bands of conquerors from whose possession of England that country dates her rising prosperity and greatness.

To those who are fond of Gothic architecture, especially to the architect and antiquary, Normandy will afford a rich treat. Rouen, a city possessing much of the old Teutonic character in its edifices, and containing not only a magnificent cathedral, but, if possible, a still finer church, that of St. Ouen, is certainly one of the most interesting places in France, and will alone furnish occupation for many days.

Caen is also interesting, though in a less degree; but in its vicinity are a great number of curious village churches. The ruined abbeys, Boscherville, Jumièges, &c., on the N. bank of the Seine, are remarkable examples of genuine Norman architecture; and the scenery of the river on whose banks and peninsulas they lie—the great water highway connecting Paris with its port of Havre—is so very pleasing, that it deserves to be seen both from land and water. The cathedrals of Bayeux (famed for its tapestry) and of Coutances also are noble edifices.

Normandy abounds in old *castles*; of which the most interesting, both in an historical and picturesque point of view, are Château Gaillard, the favourite stronghold of Richard Cœur de Lion, Falaise, the birth-place of William the Conqueror, and many others, the cradles of our English noblesse, whence they derive their titles; and above all, Mont St. Michel, which possesses a triple interest as an historical fortress, a remarkable ecclesiastical edifice, and a most grand and striking object.

The *Roman theatre* at Lillebonne deserves mention as an interesting example of an edifice of the kind, and almost the only one existing in Northern Europe.

The most picturesque parts of Normandy are the banks of the Seine from St. Germain to Havre, and especially from Rouen to Havre, though its innumerable islands, planted with rows of poplars and willows, are often monotonous; the vicinity of Vire and of Avranches charmingly posted on a hill top, whence the view extends to the Mont St. Michel, rising out of the sea, is peculiarly attractive.

The *Dock-yard* and *Breakwater* of Cherbourg, at the extremity of the promontory called the Cotentin, which deserves to be explored for its geological peculiarities, and the Château d'Eu, the summer residence of H. M. Louis-Philippe, must not be omitted among the curiosities of Normandy.

\* \* \* In going from Paris to Rouen and Havre, and *vice versâ*, the *lower roads*, along the banks of the Seine, which are highly picturesque, are to be preferred to the upper roads, which, though shorter, are dull and tiresome.



*Skeleton Tour of 3 Weeks through Normandy.*

Southampton to	11 Bayeux.
1 Havre.	12 Valonges.
Tancarville.	13 Cherbourg.
3 Lillebonne.	14 Coutances.
Caudebec.	St. Lo.
Jumièges.	15 Vire.
4 St. George Boscherville.	Mortain.
7 Rouen.	16 Avranches.
Château Gaillard.	Mont St. Michel.
Descent of the Seine to Honfleur	17 Dol.
(or to Havre, and by another	18 Dinant.
steamer to)	19 St. Malo, and by steamer to
8 Caen.	21 Jersey and Southampton.
10 Falaise and back.	

The best account of the architectural remains of Normandy will be found in Mr. *Gally Knight's* "Tour in Normandy;" *Whewell's* "Notes on German and French Churches;" *Dawson Turner's* "Tour in Normandy," one of the earliest descriptions of the country published in England or France; *Cotman and Pugin's* "Illustrative Plates;" and *Caumont's* "Histoire Sommaire de l'Architecture du Moyen Age." E. Frère's "Guide de Voyageur en Normandie, 1845," which is, for the most part, a translation from the Handbook. Also Miss *Costello's* "Bocages and Vines."

## ROUTE 1.

### CALAIS TO PARIS BY ST. OMER AND AMIENS.

281 kilom. = 174 Eng. m.

A branch Railway is in progress, from Calais, by St. Omer and Hazebrouck, to join the *Chemin de Fer du Nord* at Arras. (Route 184.)

At present the quickest way from Calais to Paris is to take the diligence, or post, as far as Arras or Abbeville. (Route 2.) Stations on the Railway.

CALAIS, in R. 2, p. 7.

The country about Calais, and for some distance inland, is low and wet, intersected by scummy ditches, and traversed by rows of pollard willows. It is drained by the canal de St. Omer, which falls into the sea at Calais: the tides are kept out by embankments. The villages are composed chiefly of mud cottages. The peasants, men as well as women, are fre-

quently seen mounted on very high pattens to avoid the dirt. The road crosses the Pont Sans Pareil, thrown over the two canals from St. Omer to Calais, and from Ardres to Grave-lines, at the point where they cut each other at right angles, 3 m. before reaching

16 Ardres, a small fortress. The plain between this place and Guisnes, a little to the W. of the road, is the *Field of the Cloth of Gold*, the scene of the meeting between Henry VIII. and Francis I., 1520, called Le Champ du Drap d'Or, from the cloth of gold with which the tents and pavilions of the monarchs and their suites, of 5696 persons with 4325 horses, were covered.

8 La Recousse.

16 *St. Omer.*—*Inns:* L'Ancienne Poste; Grande Ste. Catherine.

This is a third-rate fortress, whose means of defence lie less in its actual

fortifications than in the marshes which surround it, and the facility afforded by the river Aa, on which it stands, of flooding the land round about, so as to leave only  $\frac{1}{4}$  of its circuit unprotected by the waters. Although it contains a population of 19,344 souls, it is a very dull place. There are, however, two ecclesiastical edifices worthy of notice.

The *Cathedral*, at the upper end of the Rue St. Bertin, is a fine building, showing the transition from the round to the pointed style. The E. end is a good example of the polygonal termination of churches, with projecting chapels, so common on the Continent. The interior is good;—the small Lady Chapel has been recently decorated.

At the opposite extremity of the same street stand the scanty remains of the famous *Abbey Church of St. Bertin*, at one time the noblest Gothic monument of French Flanders—in its present state a disgrace to the town, and a reproach to the government. For be it known that its destruction has been perpetrated since 1830! At the outbreak of the great Revolution the monastery was suppressed; the Convention spared it; and though under the Directory it was sold for the materials, unroofed, and stripped of its woodwork and metal, yet its walls remained comparatively uninjured until the magistrates, a few years ago, barbarously pulled it down to afford employment to some labourers out of work! The fragment remaining consists of a stately tower built in the 15th century (1431—1461), displaying the ornaments of the florid Gothic in the mutilated panelling on its walls, and bits of tracery in its windows; a small portion of the nave remains attached to it. The tower, threatening to fall, has been propped by an ugly, ill-contrived buttress of masonry; there is some talk of converting it into a museum. The town is well seen from its top, but there is nothing else of interest in the view. Within the walls of the Abbey of St. Bertin the feeble Childeric III., the

last king of the first race, ended his days; here also Becket sought refuge when a fugitive from England.

A *Seminary* for the education of English and Irish Catholics exists here: it has succeeded the celebrated *Jesuits' College* founded by Father Parsons for the education of young Englishmen. Daniel O'Connell was brought up here for the priesthood; and several of the conspirators engaged in the Gunpowder Plot were pupils of the same school. There are not more than 15 or 20 students at present. About 400 English reside here. *English Chapel*, Rue du Bon Pasteur, Sunday, 11 and 3.

The road to Lille and Brussels (Route 188) turns off here. Diligences *daily* thither and to Boulogne.

18 Aire, another small fortress of the third class, contains a Gothic *Church*, *St. Paul's*, and a belfry built in the 18th century, rising above the public square. Mallebranche was born here.

13 Lillers.

11 Pernes.

13 St. Pol.

15 m. N. W. of this, and 2 m. S. of the post station, Fruges, is *Azincour* (1415), a village of dirty farms and poor cottages, uninteresting but for its *battle-field*. Only the foundations remain of the castle mentioned by Shakspeare "that stands hard by." Azincour lies on the l. of the high road from St. Omer to Abbeville, which passes through the village of Ruisseauville, mentioned in all the accounts of the battle. The hottest of the fight raged between Azincour and the commune of Tramecour, where a wood still exists corresponding with that in which Henry posted his archers, who contributed so much to the victory, each armed with an iron-pointed stake, to fix in the ground before him and to serve the purpose of the modern bayonet.

Henry, like his great-grandfather Edward III., previous to Crecy, had marched, with a force of only 9000 men at the utmost, through a hostile country, from Harfleur on his way to



Calais. On reaching the Somme below Abbeville he found the ford, by which Edward had crossed, staked, and was obliged to continue up the l. bank, finding every passage fortified and every bridge broken, until he arrived above Amiens, where he gained the rt. bank by a ford which had been left open. The French army, though more than six times the number of the English, retreated before him beyond St. Pol, and there drew up across the road to Calais to dispute his passage. There is thus a considerable similarity in the events attending the victories of Crecy and Azincour, and these two famous battle-fields are not more than 20 miles apart (see p. 14).

13 Frevent.

15 Doullens, chef-lieu of an arrondissement in the Dépt. of the Somme, has a *Citadel* built by Vauban, now a state prison. *St. Martin's Church* is said to be remarkable for the lightness of the pillars which support it.

14 Talmas.

16 AMIENS, on the Railway—see Route 3.

19 Flers.

13 Breteuil.—*Inn*: H. d'Ange et d'Angleterre, not good (p. 21).

The *Abbey of Ste. Marie* is an ancient Gothic building.

A road stretches hence through Noiremont, 12 k., to Beauvais (p. 15), (16 k.).

18 St. Just.

The park and château, formerly the property of the Duc de Fitzjames, are passed on the r., shortly before reaching

16 Clermont-sur-Oise—Route 3.

10 Laigneville.

The river is crossed at Creil, Route 3.

A monotonously straight road through an avenue of trees, partly skirting the forest, leads to

12 *Chantilly* (*Inns*: H. de la Pelouze, tolerably comfortable; H. d'Angleterre), a town of 2524 inhabitants. The splendid *château* built by the grandson of the Grand Condé, in the reign of Louis XV., was level-

led by the mob at the Revolution. The Great Condé here spent his latter years, after retiring from military life, in the society of Racine, Boileau, Bossuet, and the other literary men of his age. The *Stables* remain—a splendid pile, capable of lodging 180 horses, but unfinished.

Condé took great pride in this beautiful retreat, and pleasure in embellishing it; and when Louis XIV., who had a claim on it, indicated a desire to obtain possession, he said, "Vous êtes le maître: mais j'ai une grâce à demander à V. M., c'est de me laisser à Chantilly comme votre concierge;" and the king had the moderation not to interfere. Condé's affairs were never in a more desperate condition than at the moment when he was honoured by a visit from his cousin and sovereign, 1671; nevertheless, nothing could exceed the magnificence of the entertainment, rendered memorable by the suicide of Vatel, the cook, who ran himself through with his sword in despair because the fish did not arrive in time for dinner.\*

Chantilly, one of the most beautiful spots in the vicinity of Paris, abounds in interest and in souvenirs of its most distinguished owner. A noble author,† who visited it in 1841, has touchingly described its vast natural forest, its limpid and purling streams, its green Arbele poplars, which have taken root in the ruins of the Grand Château, and now quite overshadow them, its green turf drives, and its hedges of hawthorn. *Le Petit Château*, built by the Montmorencys, is one of the most charming monuments of the style of the Renaissance in France. It is surrounded by water, and consequently the lower story is scarce habitable; but in the state rooms and gallery are the Battles of the Grand Condé, painted by Van der Meulen.

The *Jardin Anglais*, laid out before the Revolution, is very curious; the French garden is in bad taste.

\* See Mad. de Sévigné.

† Lord Mahon:—Life of Condé.



The *Chapel* contains a rich altar screen in the style of the Renaissance, brought from Ecouen: here also is some fine painted glass representing the story of Psyche. Since the mysterious death of its late owner, the Duc de Bourbon, the last of the line of Condé, Chantilly has become the property of the Duc d'Aumale. *Le Petit Château* is allowed to be shown during the absence of the princes, and ought to be visited. An *Hospital*, built and endowed by the deceased Prince de Condé, remains a monument of his munificence to the town.

The park and grounds are very beautiful, and are readily shown to strangers. The forest adjoining them has an extent of 6700 acres. *Races* are held here in May and October.

The body of the aged Admiral Coligny, the noblest victim of the massacre of St. Bartholomew, after having been hung up by the heels on the gallows of Montfaucon, was secretly brought hither by Montmorency, and buried in the *parish church* without the head, which was conveyed to Catherine de Medicis.

Chantilly is famed for its silk lace (*blonde*, so called from the light colour), made here to a less extent in the town itself than in the 20 or 30 neighbouring communes, the artificers being women and children. The manufacture was originally established 1710, by M. Moreau. There are now 7 large establishments; but they only give out the patterns and materials: the work is executed at the homes of the lace-makers.

In the midst of the forest of Chantilly, on the dam at the margin of the Etangs de Comelle, is a pretty little Gothic building, flanked by 4 towers at the corners, called *Château de la Loge de Viarmes*, said to be built by Queen Blanche of Castille, mother of St. Louis. Its carved ornaments of snakes, frogs, lizards, snails, intermixed with foliage composed of water plants, are appropriate to the aquatic site. From the style of Gothic it appears to date from the 15th cen-

tury, and was probably erected by the Montmorencys for a hunting or fishing house. It was restored carefully in 1826. Three avenues traverse the ponds; and here grand stag-hunts are held by the royal princes. Not far from this is the ruined Cistercian Abbey of Royaumont, founded by St. Louis, 1230, who often retired hither from the world, tending the sick and eating with the monks. A wall and turret of the church, with bits of the refectory and cloister, alone remain, and are now converted into a cotton-mill. The valley of the Oise in this vicinity is very rich and fine.

10 Luzarches has an interesting church of the end of the 12th or beginning of the 13th century: its portal is ornamented with curious sculptures of martyred saints; and remains of an ancient castle of the French kings exist here on the top of the hill: they consist of a fragment of a square donjon, and a chapel.

11 Ecouen. The chief building is the *château* of the Montmorency family, built in the reign of Francis I., now the property of the Duc d'Aumale. It was converted by Napoleon into a seminary for the education of the daughters of members of the Legion of Honour, and placed under the direction of Madame Campan. It is now subordinate to the chief establishment of the order of St. Denis. The principal front was destroyed at the Revolution, the other 3 are well preserved. Within are traces of frescoes, of the 16th century, which were whitewashed by Madame Campan. The elegant *chapel*, ornamented with carvings in wood and a richly decorated chimney-piece, is a *chef-d'œuvre* of the style of the Renaissance.

Soon after leaving Ecouen, a fine view of Paris presents itself. Champlatreux, the seat of M. Molé, is visible.

10 *St. Denis*, (Stat. on the Railroad,) in Route 3.

9 PARIS. See Galignani's Guide to Paris, and p. 17

## ROUTE 2.

CALAIS TO PARIS BY BOULOGNE, ABBEVILLE, BEAUVAIS, AND ST. DENIS.

272 kilom. = 168 Eng. m.

*Diligences* daily from Calais to Boulogne. *Railway* thence to Paris in 9 hours.

CALAIS.—*Inns*: H. Dessin; very good. The bed-room in which the author of the 'Sentimental Journey' slept is still marked Sterne's Room; and that occupied by Sir Walter Scott is also ticketed with his respected name. Quillac's Hotel; very good, and an obliging landlord. — G. T. Hôtel Meurice; no connection with the house of the same name at Paris, but tolerably good and clean. The preference generally given to Boulogne has diminished the custom of the hotel-keepers; and this circumstance leads them to seek to indemnify themselves by an increase of prices. 10 francs is the common charge for landing or shipping a 4-wheeled carriage.

For useful information on landing in France, see INTRODUCTION.

Calais has 12,508 inhab.; it is a fortress of the 2nd class, situated in a most barren and unpicturesque district, with sandhills raised by the wind and sea on the one side, and morasses on the other, contributing considerably to its military strength, but by no means to the beauty of its position. Within a few years it has been refortified, and the strength of its works greatly increased, especially to seaward. An English traveller of the time of James I. described it as "a beggarly, extorting town; monstrous dear and sluttish." In the opinion of many, this description holds good down to the present time.

The *harbour*, lately improved and lengthened by 282 yards since 1830, is not so deep as that of Boulogne. Passengers must sometimes land in boats and wait for their baggage until the steamer can enter.

Except to an Englishman setting his foot for the first time on the Con-

continent, to whom everything is novel, Calais has little that is remarkable to show. After an hour or two it becomes tiresome, and a traveller will do well to quit it as soon as he has cleared his baggage from the custom-house, and procured the signature of the police to his passport, which, if he be pressed for time, will be done almost at any hour of the day or night, so as not to delay his departure. It is necessary to be aware of this, as the commissionaires of the hotels will sometimes endeavour to detain a stranger, under pretence of not being able to get his passport signed. The owner of the passport must repair to the police-office himself to have it visé. Travellers not intending to go to Paris, but merely passing through the country, on the way to Ostend, Brussels, or Marseilles, are not compelled to exchange their passport for a passe provisoire. See *Passports: Introduction*. Persons unprovided with a passport may procure one from the British Consul for 4s. 6d.

Calais has of late become a manufacturing town; the bobbin-net (tulle) trade flourishes in rivalry of that of England; numerous *mills* have sprung up; steam-engines are multiplying; and the inner ramparts have been removed, to make way for factories. The gates remain open all night. Water is scarce here, and throughout Artois. 55 millions of eggs are exported hence to England annually.

The *Pier of Calais* is an agreeable promenade, nearly  $\frac{3}{4}$  m. long. It is decorated with a pillar, raised to commemorate the return of Louis XVIII. to France, which originally bore this inscription:—

"Le 24 Avril, 1814, S. M. Louis XVIII. débarqua vis-à-vis de cette colonne, et fut enfin rendu à l'amour des Français; pour en perpétuer le souvenir, la ville de Calais a élevé ce monument." "As an additional means of perpetuating this remembrance, a brazen plate had been let into the pavement, upon the precise spot where his foot first touched the soil. It was



the left; and an English traveller noticed it in his journal as a sinistrous omen, that, when Louis le Désiré, after his exile, stepped on France, he did not put the right foot foremost."

*Quarterly Review.* At the Revolution of July both inscription and footmark were at once obliterated by the mob; and the pillar now stands a monument merely of the mutability of French opinions and dynasties, corresponding with the return of Charles II. and the expulsion of James II. in English history.

The principal *gate* leading from the sea-side into the town is that introduced by Hogarth into his well-known picture. It was built by Cardinal Richelieu, 1685.

No one needs to be reminded of the interesting incidents of the Siege of Calais by Edward III., which lasted 11 months, and of the heroic devotion of Eustace de St. Pierre and his 5 companions. Few, perhaps, are aware that the heroes of Calais not only went unrewarded by their own king and countrymen, but were compelled to beg their bread in misery through France. Calais remained in the hands of the English more than 200 years, from 1347 to 1558, when it was taken by the Duc de Guise. It was the last relic of the Gallic dominions of the Plantagenets, which, at one time, comprehended the half of France. Calais was dear to the English as the prize of the valour of their forefathers, rather than from any real value which it possessed.

The English traveller should look at the *Hôtel de Guise*, originally the guildhall of the mayor and aldermen of the "staple of wool," established here by Edward III., 1363. It has many vestiges of English Tudor architecture. Henry VIII. used to lodge in it.

In the Great Market Place stands the *Hôtel de Ville* (Town Hall). In it are situated the police-offices. In front of it are placed busts of St. Pierre; of the Duc de Guise, named le Balafré, who conquered the town

from the English; and of the Cardinal de Richelieu, who built the Citadel on the W. of the town: above it rises a belfry, containing the chimes. In the same square is a tower, which serves as a landmark by day and a lighthouse by night, to point out to sailors the entrance of the harbour.

The principal *Church* was built at the time when the English were masters of Calais. It is handsome, and surmounted by a stately tower and short steeple, which merit notice.

Lady Hamilton (Nelson's Emma) died here in great misery. Her remains, refused a resting-place in consecrated ground, were interred in a timber-yard, about 20 yards beyond the Porte de Calais, on the l. of the road to Boulogne. A pillar set up by Mr. R. Barton marks the spot.

The *walls* round the town, and the *pier* jutting out nearly  $\frac{3}{4}$  m. from the shore, are admirable promenades, and command a distinct view of the white cliffs of England,—a tantalizing sight to the English exiles, fugitives from creditors, or *compelled* from other causes to leave their homes: a numerous class both here and at Boulogne. There are many of our countrymen besides, who reside merely for the purpose of economising; so that the place is half Anglicised, and our language is generally spoken. The number amounts at present to 4800 English residents in and around Calais. There is an *English Chapel*, Rue des Prêtres: Service on Sundays, 11 a. m., 3 p. m.

There is a small *theatre* here.

Calais is one of those places where the fraternity of *Couriers* have a station. Travellers should be cautioned not to engage one unless the landlord of an hotel, or some other respectable and responsible person, give him a character derived from *personal* knowledge; as many of these couriers remain at Calais only because some previous act of misconduct prevents them showing their faces on the opposite side of the Channel. The inns are generally well stocked with carriages to be let or sold; they are



mostly old and rickety vehicles, and the hire demanded for them nearly equals that for which an excellent carriage may be obtained in London.

*Steam-boats 2 every day to Dover.* The new English steamers usually make the voyage in a little more than 2 hours. The French steamers are very bad, and ought to be avoided. Fare, 10s. 6d. Carriages, 2l. 2s. Steamers go direct to London several times a week, in 10½ or 12 hours.

*Diligence daily to St. Omer and Arras*, where it meets the Railway (Routes 184 & 3), and is conveyed on it to Paris—to Boulogne—to Lille, to meet the Belgian Railway—to Dunkirk.

*Railways* are projected from Calais to Boulogne and to Arras.

To the flat land immediately about Calais succeeds a hilly tract, unenclosed and uninteresting, which continues as far as Boulogne.

13 Haut Buisson.

The poor village Ouessant, or Witsand, on the sea shore, about 4 m. N. of this, is supposed to be the *Portus Itius* of the Romans, the spot where Julius Cæsar embarked for the conquest of Great Britain. Roman remains are found in the neighbourhood. The harbour has long since been blocked up with sand; yet it was for centuries the landing-place for passengers from England.

9 Marquise, a town of 2000 inhab., having in its neighbourhood mines of coal and iron of no great importance, and quarries of a coarse grey marble.

Ambleteuse, another poor village on the coast, deserves mention only as the spot where James II. disembarked, Jan. 5, 1689. In the churchyard of Wimille, at the road side, 3 m. from Boulogne, the two unfortunate aeronauts Pilâtre de Rosier and Romain are buried; the balloon in which they had ascended from Boulogne (1785), intending to cross the Channel, caught fire at an elevation of 3,600 ft., and they were miserably

dashed to pieces. An obelisk has been erected to their memory.

The road, previous to descending from the open high ground, passes close to a fort thrown up by Napoleon in 1804; beyond which, about 200 yards on the rt., rises the Napoleon Column. (See p. 13.)

A rapid descent leads under the walls of the old town into the lower or new town of

13 BOULOGNE. — *Inns*: Hôtel des Bains, situated close to the port, comfortable; a good cuisine and table d'hôte at 4 fr. H. du Nord, also good. Barry's Marine Hotel, opposite the baths and steamers. H. d'Angleterre, moderate. H. de Londres.

Boulogne-sur-Mer is a sea-port in the Channel or Pas de Calais, on the estuary of a small stream, the Liane, which forms a tide harbour, flanked on either side by wooden piers stretching out as far as low-water mark. It was the Roman GESSORIANACUM. The old town occupies the summit of a hill, on which it was built for security in ancient times, and it is still encircled by its feudal ramparts, and entered by cavernous gateways. The new, or Basse Ville, stretching down the slopes of the hills which border the harbour, and under the brown cliffs which partly line it, is the chief seat of commerce, and contains the best hotels, streets, and shops.

The number of inhabitants is 29,145, among whom are at least 7000 permanent English residents; indeed Boulogne, having the advantage of being within 8 hours of London, has become, since the peace, one of the chief British colonies abroad; and, by a singular reciprocity, on the very spot whence Napoleon proposed the invasion of our shores, his intended victims have quietly taken possession and settled themselves down. The town is enriched by English money; warmed, lighted, and smoked by English coal; English signs and advertisements de-

corate every other shop door, inn, tavern, and lodging-house; and almost every third person you meet is either a countryman or speaking our language; while the outskirts of the town are enlivened by villas and country-houses, somewhat in the style and taste of those on the opposite side of the Channel. There are at least 120 boarding-schools (*pensionnats*) for youth of both sexes, many of them under English managers.

*Le Port.* The margin of the harbour concentrates the chief bustle and business; here is the landing place of the packets, and the *Douane*, whither passengers are first conveyed on their arrival to deliver their passports, and to be visited by the custom-house officers. *New Quays* have been built; a backwater with sluices for scouring the harbour mouth is planned. The tide rises from 18 to 27 ft. here.

The present entrance to the harbour was formed 1829, somewhat to the W. of the old, and allows the packets to enter  $1\frac{1}{2}$  hour earlier and later than in the old. It is flanked on either side by wooden piers, that which projects from the end of the quay forming a pleasant walk when the tide is in. The number of persons who disembark here annually amounts to 56,000 or 60,000, and hence the chief source of the prosperity of Boulogne.

On one side of the harbour, on the margin of a fine sandy beach, is the *Etablissement des Bains*, a showy building, fronted with colonnades, containing subscription, ball, and reading rooms. In front is drawn up in long array a number of genuine bathing machines (*voitures baignoires*), the only ones of the sort to be found in France. Boulogne is much resorted to in summer as a watering-place, both by the Parisians and English, on account of sea-bathing, for which it is well adapted, having a fine sandy beach.

On the opposite (l.) side of the harbour is a semicircular basin, dug out of the sand by Napoleon, to contain the celebrated flotilla of flat-bottomed

boats intended by him to transport an invading French army to the coasts of England, but happily not destined to reach our shores.

Almost all the 1300 vessels belonging to Boulogne are engaged in fishery, and the arrival and departure of the boats collects a crowd of fishermen and fisherwives in their singular and picturesque costume, such as the pencils of Prout and Stanfield are wont to portray. These people occupy a distinct quarter of the town on the N. side of the harbour, the streets of which are draped with nets hung out from the fronts of the houses to dry, and in dress and manners they are distinct from the rest of the inhabitants, speaking a peculiar patois, and rarely intermarrying with the other townsfolk. They are an industrious and very hard-working race, especially the women, and very religious: the perils and vicissitudes of their hard life reminding them more nearly than other classes of their dependence on Providence. The Boulogne fishing boats are the largest and best worked in the Channel. A great number repair annually to the coast of Scotland for the herring fishery, and some go as far as Shetland and Iceland.

The Rue de l'Ecu, running parallel with the Liane, and the Grande Rue, ascending the hill towards the upper town, contain some of the best shops. About half-way up the Grande Rue is the *Museum* (in what was the Grande Séminaire). A sum has been voted for a new building expressly designed for it. It deservedly ranks amongst the best provincial collections in France, is highly creditable to the town, and owes a large part of its contents to private donations. The series of arms, dresses, implements, weapons, &c. of various nations, including the full dress of a Lapland lady given by Admiral Rosamel, is very extensive. Here is an imaginary model of the Tower of Caligula, which stood on the heights above the town: also engravings of the siege of Boulogne under Henry



VIII.; a curfew of earthenware; some curious fragments of sculpture of the 15th and 16th centuries from churches, &c.; a Last Judgment, a bas-relief carved in wood very elaborately; an extensive series of medals, —among them that celebrated one, which took too much for granted, struck by Napoleon 1804, and bearing the inscription “*Descente en Angleterre*,” “*Frappé à Londres*,” of which 3 or 4 impressions alone are said to exist, the die having been destroyed. The quantity of Roman antiquities, of pottery, glass, bronzes, coins, utensils of various kinds, found in and about the town by excavations, is very remarkable, as well as their good preservation. In digging the foundations of the *Abattoir* on the road to Paris, a multitude of vases and other objects, with more than 1300 medals, relics of the Roman *Bononia* or *Gessoriacum*, came to light, and have been deposited here. A collection of siege pieces, or coins struck in haste in besieged towns, is curious, as well as a series of French *Assignats*, or paper money issued at the Revolution. The museum possesses a mummy pronounced by Champollion one of the finest in Europe, for the number and brilliancy of its paintings, &c.; it was brought from *Biban el Molouk* by *Denon*.

Persons interested in *natural history* will find collections in all departments, by no means contemptible in extent or preservation. The geology of the district is illustrated by a large series of specimens, including the ironstone of the *Boulonnois*, the marble of *Marquise* (lower oolite), and the coal. Of the *Picture Gallery* much cannot be said, but there are one or two tolerable modern paintings; a good sea piece by *Delacroix*.

The museum is open to the public Thursday, Saturday, and Sunday, from 10 to 4; strangers may obtain admission on other days by giving a small fee to the concierge. Under the same roof is the *Public Library*, containing 22,000 volumes and 3,000

*MSS.*, many of them rare and richly illuminated, including the oldest copy extant of *Bede's 'Homilies,'* from *St. Bertin*.

The *Old Town* of Boulogne, on the summit of the hill, retains its three arched gateways, and the ancient ramparts which defended it in the 15th century, but offered a vain resistance to the assaults and cannonading of the army of *Henry VIII.* The town was restored, however, to *Henri II.* of France by the English (1550), in the reign of *Edward VI.*, by treaty, upon payment of 40,000 livres. In consideration of this a bronze bust of *Henri* (by *David d'Angers*) decorates the esplanade outside the gate *Des Dunes*. The *Remparts* form an airy and agreeable walk, running uninterruptedly round the town, and commanding views in all directions, over the sea and port, and over the high ground to the E., occupied in turn by the camps of *Caligula*, *Henry VIII.*, and *Napoleon*, and along the roads to *Calais* and *Paris*. In one corner of the walls is the old *Citadelle*, flanked by high round towers, and divided from the town by a fosse, but now much modernised externally, and converted into a barrack. In the midst of the old town, behind the *Hôtel de Ville*, rises the antique tower of the *Beffroi*.

The *Cathedral*, a large modern building of Grecian architecture, has been in progress since 1827, being built by subscription, on the site of a Gothic one pulled down at the Revolution. Two ranges of curious stunted pillars, dating probably from the 11th century, which belonged to a crypt under the old church, have been discovered beneath the new one.

There are several *Nunneries* in the old town; that of the *Ursulines* is at No. 2, *Rue de la Paille*. The sisters, 40 or 50 in number, instruct a pension for young ladies. The *Sœurs de Bon Secours* (*Rue St. Martin*, No. 20) devote themselves to attend on the sick, and their services are much esteemed by the poor. The con-



vent of the "Dames de la Visitation," about  $\frac{3}{4}$  m. out of the town, near the St. Omer road, is the largest, and has a fine chapel, open on Sundays.

Le Sage, the *author of Gil Blas*, who repaired to Boulogne in the latter years of his life to stay with his son, a canon of the cathedral, died 1747, in a house, No. 3, Rue du Château, as an inscription over the door points out. The existing building, however, is of much more recent date, and only occupies the site of the original house. Churchill the poet also died at Boulogne, whither he had come on a visit to John Wilkes, then a voluntary exile from England. Attempts made by the priests to obtain access to the dying man, in order to convert him to popery, were stoutly repelled by Wilkes.

There are 2 *English Chapels* here: one in the Rue du Temple, built by subscription of the English (1828), is capable of containing 1,000 persons—service at 11 and 3 on Sundays: the other in the Rue St. Martin in the Haute Ville.

The *Poste aux Lettres* is at No. 28, Rue des Vieillards; it is open from 8 A. M. to 8 P. M. The British Consul resides in Rue des Vieillards.

In the *Cemetery* of the upper town is the grave of 82 female convicts from England, drowned in the wreck of the 'Amphitrite,' 1833, and others who perished in the Indiaman 'Conqueror,' 1843.

At *Capecure* a large flax-mill has been built with 2 steam-engines, 6,000 spindles, employing 1,000 people.

Stubbs, Rue de l'Ecu, has an *English reading room* and circulating library. Merridew has another.

The *Office for passports* is open from 9 to 2; but passports are countersigned at later hours, in case of urgency. See Introduction, c.

On the very edge of the cliff, just above the sea-baths, a little to the E. of the port, are the scanty remains of sold brick walls known as *La Tour d'Ordre* (Turris Ardens, i.e. light

tower), supposed to be the foundations of a tower built by Caligula the Roman emperor, A.D. 40, when he marched to the shore of the Channel with an army of 100,000 men, boasting that he intended to invade the opposite coast of Britain, but contenting himself with gathering a few shells, which he called the spoils of the ocean. The tower is supposed to have been intended for a lighthouse, but the remains are very scanty, and from the falling of the cliff even these are likely soon to disappear.

On the same heights, 18 centuries later, another emperor—Napoleon—encamped an army of more than 180,000 men, designed to invade England, and placed under the command of Soult, Ney, Davoust, and Victor. Buonaparte himself, during his visits to the camp, occupied a temporary baraque, which was raised within a few yards of the Roman tower. Thence he could survey his flotilla of 2400 transports and flat-bottomed boats, and the shore on either side of the town, both under the cliff and upon the heights, bristling with batteries of cannon and mortars; while, in the distance, the vigilant fleets of England hovered incessantly. In one instance Nelson approached near enough to bombard the town and sink two of the floating batteries. "Boulogne," he writes, "was certainly not a pleasant place that morning; but it is not my wish to injure the poor inhabitants, and the town is spared as much as the service will admit." It is stated, however, that most of the bombs fell short, and that in excavating the new harbour many tons of them were dug out. He afterwards made an unsuccessful attempt with the boats of his squadron to cut out the flotilla in the teeth of the batteries, and burn it. Another attempt, in 1804, to burn the flotilla with fire-ships, made by Lord Keith, was attended with no better result.

The flotilla of Boulogne formed only part of the deeply laid scheme

of Napoleon for the destruction of England. He designed to collect together the combined fleets of France, Spain, and Holland, which for years previously he had been constructing in the harbours of Antwerp, Brest, Cadiz, and the Mediterranean, and with a squadron of 70 ships of the line to sweep the Channel of the British. Under cover of this vast armament he intended to have crossed over with the army of Boulogne, expecting to reach London in 5 days, where he designed to have proclaimed parliamentary reform, abolishing the monarchy and the House of Peers, and substituting a republic!! The troops of the Boulogne expedition were so nicely drilled, and every man so accurately informed of the boat which was to transport him, that at a preliminary review, in  $10\frac{1}{2}$  minutes 25,000 were embarked; and re-landed and drawn up on the shore again in 13 minutes more. The whole of these projects and combinations, however, were scattered to the winds; the fleet of England, under Sir Robert Calder, prevented the junction of those of the enemy, and Nelson finally annihilated them at Trafalgar.

A conspicuous memorial of this projected but unaccomplished invasion exists at the distance of nearly a mile from the town in the *Colonne Napoléon*, which surmounts the heights traversed by the road to Calais. It was begun by the grand army assembled for the invasion of England, as a monument to their leader and emperor. The first stone was laid by Marshal Soult, 1804; but its construction was discontinued after the departure of the troops, and the withdrawal of the subscriptions which they contributed out of their pay. Under Louis XVIII. it was resumed, with the ostensible design of commemorating the restoration of the Bourbons. In consequence, however, of the revolution of July it has resumed its original destination; and having been purged

of carved fleurs-de-lis and royalist inscriptions, was dedicated, 1841, as a monument to Buonaparte, and surmounted by a bronze statue of him in his coronation robes by *Bosio*, and one of that sculptor's best works, while bronze bas-reliefs decorate the base. The pillar is of the Doric order, and 50 mètres = 164 ft. high, exclusive of the statue, 16 ft., and is constructed of marble from the quarries of Marquise. A winding stair leads up to the top, whence a view may be had of the white cliffs of England.

$\frac{3}{4}$  m. further, on the coast, a monument of marble commemorates the distribution of the Order of the Legion of Honour by Buonaparte to his troops, during one of his visits to the camp. Nearer at hand, attached to a small hamlet or group of houses down in the hollow, is the chapel of *Jésus Flagellé*; curious, because it exhibits an instance of the practice so common in the Romish church of making votive offerings. It is resorted to by the fishermen of Boulogne and their families before they go out to sea; and they have lined its walls with votive pictures, even with lithographs, and hung its roof with models of their barks, each to commemorate some rescue from the perils of the great deep. The chapel, a humble modern edifice, is about  $1\frac{1}{2}$  m. distant from Boulogne.

*Railway* from Boulogne to Paris, by Etaples and Abbeville. (Route 3.)

*Steamers.* To Dovor daily in 2 hours. The passage is very little longer than from Calais to Dovor, and 24 m. of tedious land journey are saved. To Folkestone every tide in 2 hours. To London: in summer almost daily; in winter 2 or 3 times a-week, in 10 or 12 hours.

*Diligences.* To the railway at Neuchâtel (9 m.) 6 times daily, by which Paris may be reached in 10 hours;—to Beauvais;—to St. Omer, 2; to Calais; to Samer; to Lille and Arras.

*Landing and embarking at Bou-*



*logne* (see INTRODUCTION). The porter's tariff for conveying luggage from the steam-boat to the custom-house, and thence to the hotel, or to the owner's residence, is fixed according to weight.

Fr. Cents.

0 70 for 15 kilos (= 33 lbs.) or under.

1 0 for 15 to 100 kilos (= 220 lbs.)

1 50 for 100 kilos and upwards.

For excursions in the neighbourhood of jackasses (*baudets*) are much in vogue.

The high road to Paris is nearly deserted by travellers now that the railway is open to Paris. It is destitute of interest, if we except the churches at Abbeville and Beauvais. These two towns are the best resting places.

On quitting Boulogne the road commands, from an eminence which it ascends, a view into the valley of the Liane—thenceforth it is monotonous and dull. The railway to Abbeville (Route 3) is carried a little to the W. of the post-road; nearer to the sea.

15 Samer (ruins of an abbey near this). *Inn*: Tête de Bœuf.

9 Cormont.

13 Montreuil-sur-Mer. *Inns*: H. de la Cour de France, et de l'Europe; —H. de France, et de l'Angleterre.

An ugly town and 2nd-rate fortress, on a hill rising out of the marshy valley of the Cache. It has a tall flamboyant church, with a fine W. doorway under the towers.

14 Nampont is situated within the Dépt. de la Somme, which anciently formed the province of Picardy.

9 Bernay.—La Poste, comfortable. The little seaport St. Valery is visible from the heights traversed by the road.

The wood seen on the l., at a little distance from the road, is a part of the forest of *Crecy*, the name of a village 12 m. from Abbeville; obscure in itself, but renowned for a victory gained in its precincts, Aug. 26th, 1346, by Edward III. and his

40,000 men over the French army of Philip of Valois 100,000 strong, commanded by the Count d'Alençon, which still, after the lapse of ages, remains one of the most brilliant in English annals. Here, upon that memorable day, to the winning of which the cannon, used, according to some, for the first time, contributed less than the cloth-yard shafts of the English yeomen, there fell on the side of the French, the Kings of Bohemia and Majorca, the Duke of Lorraine, the Count d'Alençon, the king's brother, with 1200 knights, 1500 gentlemen, 5000 men at arms, and 30,000 infantry. Here it was that the Black Prince gained his spurs, and the feathers which the princes of Wales bear to this day.

7 Nouvion. An extensive manufactory of beet-root sugar is seen on the l., 2 m. before reaching Abbeville.

The most pleasing view on the whole road is that of Abbeville, and of the fertile vale of the Somme, in which it is situated, from the summit of the long and steep descent which leads down to it.

13 Abbeville. See Route 3. The Railway is completed hence to Paris.

About 6 m. E. of Abbeville (bad road) is the *Abbey Church of St. Riquier*, a very splendid and interesting Gothic edifice, well preserved, having a beautiful flamboyant W. front, in the centre of which rises an elegant tower; while beneath it opens the main portal, having statues in its top and sides. "The details of the front are exquisite, well arranged, and well executed." The interior is also very fine; the nave flamboyant, the choir apparently earlier. On the walls of the treasury are curious and ancient frescoes; one in the style of the "Dance of Death." It is well worth a visit.

The post-road crosses the Somme by two bridges on quitting Abbeville.

19 Airaines.

10 Camps.

13 Poix (Amiennois), which gives



the title to the chief of the Noailles family. The road from Amiens to Rouen passes through this place.

14 Grandvilliers. H. d'Angleterre.

10 Marseille (Oise). During this stage the scenery is rather more interesting. Vineyards first appear a little to the N. of

19 *Beauvais.*—*Inns:* Hôtel d'Angleterre; Ecu de France.

This is the chief town of the Dépt. de l'Oise: it has 13,082 inhab. The central portion (la Cité) is very ancient, still in part enclosed by its old walls, which on the E. side have given place to airy boulevards planted with trees, and many of the houses are of wood; the more modern quarter is surrounded by a boulevard planted with trees, occupying the site of former fortifications. The most conspicuous edifice, and the principal object of curiosity here, is the *Cathedral*. At a distance it appears a heavy and uncouth mass, overtopping the rest of the town with its prominent roof, which is supported by 3 rows of flying buttresses, surmounted by double ranges of pinnacles rising from broad buttress walls. It was commenced 1225, and the design of its founders and architects, excited to emulation by the splendour of Amiens, which had been begun 5 years earlier, seems to have been to surpass in vastness and magnificence all other Gothic edifices. They miscalculated, however, the resources both of their art and their treasury, and the result was repeated failure and final defeat; for the progress of the edifice was arrested when it was only half finished, and it remains a mere gigantic choir with transepts. As it is, however, this choir is the loftiest in the world, the elevation of the roof above the pavement being 153 ft.—13 ft. higher than that of Amiens; but though more extraordinary, it is less pleasing than it. "The extension of its dimensions upward is carried to a degree which strikes the spectator as exaggeration. Amiens is a giant in repose; Beauvais

a colossus on tiptoe."—*W.* To increase the wonder of the building, the architect designed to support it on half the number of piers employed at present; but in spite of the iron braces used to hold the piers in their places, the walls bulged out, and the roof fell twice. The only means, then, of maintaining it was by inserting intermediate piers in the wide spaces left between the original ones. The transepts, begun 1500, under the Bishop Villiers de l'Île Adam (who, as well as his brother the Grand Master of St. John of Jerusalem, was a Beauvoisin), by the architects Jean Waast and Martin Cambiches, and finished 1555, are a fine example of the flamboyant style.

One compartment of the nave was actually begun when the architects (moved, it is said, by a vain ambition to rival the height of St. Peter's dome, and M. Angelo's masterpiece) abandoned it to raise a tower 455 ft. high, which lasted only 5 years, having tumbled down 1573. The choir, "though raised to a loftiness that strikes the beholder with awe and astonishment, displays the space between the tall and slender pillars so entirely filled with glass, that the whole range of windows only appears like a single zone of light, supported and separated by nothing but narrow mullions situated at wide intervals."—*Hope.*

In the interior the effect of the admirable painted glass, executed in the best period of the art, is very rich. That in the N. and S. rose windows is attributed to Nicholas Lepot, and that in some of the side chapels to Augrand Leprince, both celebrated as artists in this line in the 16th century. In the choir are hung 8 of the *tapestries* for the manufacture of which Beauvais was celebrated, and which preceded by 3 years that of Gobelins. The monument, in the N. aisle of the choir, of Cardinal Forbin de Janson surmounted by his kneeling effigy, is by Nicholas Coustou, and of good workmanship.

The entrances to the Cathedral are by the transepts: the portal at the extremity of the S. transept is loaded with flamboyant decorations, though, from the fury of iconoclasts, it has lost the statues which filled the niches. It is surmounted by a noble rose window, of very rich tracery. The façade of the N. transept has very much the character of English perpendicular Gothic; its portal, deeply recessed, with feathered mouldings to the arches, retains its original carved doors, which are surmounted by a bas-relief, in the tympanum, of a genealogical tree; the escutcheons suspended from the branches.

One of the best views of the cathedral is obtained in the marketplace from the side of a corner house, conspicuously distinguished by the three curiously carved stone pillars, probably of the 11th or 12th century, which support it.

A ruinous building, called the *Basse Œuvre*, on the W. of the cathedral, occupying part of the space which the nave, if carried out, would have covered, is curious as one of the most ancient buildings in France (8th or 9th century). The lower part of the outer walls displays masonry with bonds of tiles, and tiled arches in the manner of Roman edifices. The superstructure served as a church in the 10th century; in its interior square piers support plain round arches. It seems never to have had a stone roof.

*St. Stephen's Church.* The nave exhibits the transition from Romanesque to Gothic; it is very plain, with round pier arches, and round-headed clerestory windows. The W. front resembles a plain early English front of our own country. The painted glass is very excellent. The *Bishop's Palace*, rebuilt in the 15th century, has externally the aspect of a castle, surrounded by walls, and its entrance flanked by 2 large round towers.

Cæsar thus mentions the Bellovaci, the ancient inhabitants of the Beau-

vais: "Plurimum inter Belgas Bellovacos et virtute et auctoritate, et hominum numero valere."

The most remarkable event in the annals of Beauvais is its *Siege* by Charles the Bold in 1472, when, being destitute of garrison, it might have fallen by a *coup de main*, had not its citizens boldly closed their gates in the face of an army of 80,000 Burgundians, and maintained an obstinate resistance until succour arrived from Paris. The peculiar feature in this defence was the part which the wives and daughters of the townsfolk took in it, guarding the walls, and sharing in all the perils of the men. The chief heroine, Jeanne Hachette, appeared upon the breach at the moment of the fiercest assaults, seized a Burgundian standard which a soldier was endeavouring to plant on the walls, and hurling the bearer to the bottom bore it off in triumph into the town. Louis XI. rewarded the valour of the citizens by releasing them from taxes, and complimented the ladies by an ordonnance authorising them to take precedence of the men in the procession of St. Angadrème, instituted to commemorate the raising of the siege. This procession is still kept up, on the Sunday nearest the 14th October; the females lead the way, carrying the banner so valourously acquired by Jeanne Hachette, which is preserved in the *H. de Ville*.

At an earlier period (1357) Beauvais was the centre of the revolt of the serfs against their tyrannic lords, called *Jacquerie*, from Jacques Bonhomme (Goodman James), the familiar sobriquet of the peasantry. It extended over several provinces before it was put down by the armed force of the seigneurs banded together, and with fearful cruelty. Froissart thus describes an instance of wholesale vengeance performed upon the rebellious peasants by the Duke of Orleans, the Count of Foix, and the Captal de Buch:—"They set fire to the town and burned it clean, and all



the villagers of the town that they could close therein."

15 Noailles.

13 Puisseux.

10 Beaumont-sur-Oise (Hôtel du Paon), prettily situated on the l. bank of the Oise. Here vineyards first appear. Railway Stat.

Before reaching Moisselles, a paved road, bordered with trees, strikes off to Viarmes, the Abbey of Royaumont, and Chantilly. (See p. 6.)

12 Moisselles. Rt. lie the forest of Montmorency, and that of Ecouen, with its immense château. (See p. 6.)

The road is carried through one of the *Fort*s forming part of the out-works of the new Fortifications of Paris, before entering.

13 *St. Denis*. (See Route 3.)

Travellers bound for the W. end of Paris turn to the rt. on quitting *St. Denis*, pass one of the new barracks for the garrison attached to the fortifications, and, leaving Montmartre on the l., traverse the *Faubourg des Batignolles*, up to the *Barrière de Clichy*. The route followed by the diligences is drawn in a perfectly straight line from *St. Denis* to the *Barrière St. Denis*, keeping the heights of Montmartre on the rt. It crosses the canal which unites the Seine at *St. Denis* with the *Canal de l'Ourcq*, and cuts off a bend of the Seine. Further to the rt., and near the Seine, is the villa of the *Prince de Craon*, where *Louis XVIII.* signed the Charter in 1814.

9 PARIS. *Galignani's Paris Guide* appears so good as to relieve the Editor of this work from the necessity of entering into any description at present of the French Capital. The following information, however, may not be unacceptable to strangers.

*Inns*:—Hôtel Bristol, *Place Vendôme*, is the *Mivart's* or *Clarendon* of Paris; excellent, perfectly comfortable (*W. M.*), and not expensive: capital cuisine. *H. des Princes*, *Rue de Richelieu*; a capital table-d'hôte, very well served at 6 fr.; expensive. *H. Wagram*, *Rue Rivoli*, excellent; safely to be recommended.—*L. F.*

*H. Brighton*, *Rue Rivoli*; quiet and good. *H. Mirabeau*, *Rue de la Paix*; a good suite of 4 apartments 7 to 10 fr. and higher a-night. *Hôtel Meurice*, *Rue Rivoli*; a comfortable and well-managed house, much frequented by Americans: bed 3 fr. per day; breakfast, tea and coffee, with eggs, 2 fr.; dinner at table-d'hôte, without wine, 4½ fr.; lacquais-de-place 5 fr.; carriage 25 fr.; servants all round 1 fr. a-day, but less in proportion for family. *Lawson's Hotel*, moderate in charges.

*Boarding House*—*Madame Guilhom's Pension*, 5, *Rue des Champs Elisées*; a very respectable establishment.

*Galignani's Reading Room*, *Rue Vivienne*, in a court, is a great resource to the Englishman in Paris: here he will find all the best newspapers of all the world; here he will meet with his friends, a list of his countrymen visiting or residing in Paris being kept here, and may supply himself with books, or subscribe to the circulating library. *Galignani's Messenger* is a capital paper, condensing all the news of the English papers without reference to politics. It is a comfort to have it sent after the traveller from place to place as he moves about France, which *MM. G.* will undertake to do.

Public and private carriages are stopped at the outer gate or barrier of Paris by the officers of the *Octroi*, whose duty it is to levy a tax upon all provisions, wines, &c. Baggage is liable to be searched by them; and one of them accompanies the diligence to the coach-office, where passengers are obliged to open their baggage before him, as at a custom-house.

### ROUTE 3.

BOULOGNE TO PARIS.—RAILWAY, BY ABBEVILLE, AMIENS, CLERMONT, AND PONTOISE.—CHEMIN DE FER DU NORD.

About 275 kilom. = 170 Eng. m.

*Trains*. 3 or 4 daily; in about

9 hours. [At present, 1847, the first stage, from Boulogne to Neuchâtel, 10 m., being incomplete, must be travelled in omnibus.]

There is a tunnel of 200 yards, through the forest of Hadelot.

15 Neuchâtel Stat., a small village in a wooded hollow.

13 Etaples Stat. There is a viaduct over the Cauche, more than 900 ft. long.

11 Montreuil Stat. (Route 2, p. 14.)

16 Rue (Stat.), a poor and hitherto "out-of-the-way" town, with a curious old *Ch.*

10 Noyelle St. The railway runs near the N. bank of the Somme.

At Blanchetaque Edward III. crossed the Somme with his army before the battle of Crecy, by a ford passable only at low water. The tide, rising immediately after, arrested the pursuit of the French forces, and compelled them to ascend the l. bank, while the English pursued their way up the rt.

St. Valery, at the mouth of the Somme, 12 m. below Abbeville, was the port whence the fleet of William the Conqueror set sail to invade England. It is partially resorted to as a watering-place. The Somme is crossed by a bridge of 2 arches before reaching

15 Abbeville (Stat.)—*Inns*: H. de l'Europe, table-d'hôte, 3 fr., very good; Tête de Bœuf.

This is an industrious manufacturing town, of 17,582 inhab., which, from its situation on the Somme, here a wide river, is accessible for vessels of 150 tons. Those who will penetrate into its narrow and filthy streets will find some quaint specimens of ancient domestic architecture, timber houses, &c., but the chief object of interest, which really ought to be seen, is

The *Cathedral* of St. Wolfram. The W. front, and 5 first arches of the nave, are a portion of a magnificent design, never carried out, commenced in the reign of Louis XII., under the Cardinal George d'Amboise. The façade is a splendid example of the flamboyant style, con-

sisting of three gorgeous portals, surmounted by a pediment, and flanked by two towers; the whole covered with the richest flowing tracery, or panelling; the niches being filled with statues. The central door is curiously carved. The remainder of the church is a mean continuation of the first plan.

*Diligences* to Eu and Dieppe (R. 18); to Rouen; 6 to Boulogne; to Beauvais; to St. Valery.

RAILWAY. 4 trains to Paris, daily, in 6 $\frac{3}{4}$  hours. From Abbeville to Amiens the line is carried up the valley of the Somme along its l. bank.

8 Pont-Remy Stat. The village is on the rt. bank of the Somme. 6 $\frac{1}{2}$  m. off lies Ailly le Haut Clocher, so called from the lofty steeple of its fine *Church*, in a style resembling Early English Gothic.

8 Longpré Stat.

7 Hangeat Stat.

7 Picquigny Stat. The ruined *castle*, close to the *Ch.*, with its terraces, mentioned in Mde. de Sévigné's "Letters," was built at the end of the 15th cent. This place gives its name to a Treaty signed 1475, between Edward IV. and Louis XI., who met on the bridge; but so distrustful of each other, that a barrier of stont palisades and wooden bars, "such as the cages of lions are made of," says De Comines, was raised to divide them, leaving space between the bars only wide enough to allow them to shake hands.

5 Ailly Stat.

10 AMIENS STAT.—*Inns*: H. de France et d'Angleterre; H. de Paris; H. des Postes—good, S.A.

Amiens is an industrious manufacturing town of 46,129 inhab., formerly capital of Picardy, now chef-lieu of the Dépt. de la Somme, and situated on that river, which passes through the town split into eleven branches, and renders essential service in turning the water-wheels of many of the numerous manufactories, whose tall chimneys are seen rising above the other buildings, and are



clustered around the outskirts. The weaving of cotton velvets, chiefly for Spanish consumption, and the spinning of cotton and woollen yarn, are the principal branches of industry. Amiens is the cradle of the cotton manufacture of France, which dates no farther back than 1773.

The object which deservedly concentrates the attention of travellers at Amiens is the *Cathedral*, one of the noblest gothic edifices in Europe. It was begun 1220, only two years later than Salisbury, though in a much more mature style than that edifice. It was designed and begun by the architect Robert de Luzarches, but continued and completed, 1269, by Thomas and Regnault de Cormont, except the W. front, not finished until the end of the 14th century. Three vast and deeply recessed portals lead into it; the arches supported by a long array of statues in niches instead of pillars, while rows of statuettes supply the place of mouldings, so that the whole forms one mass of sculpture; an arrangement of constant occurrence in French Gothic, though rare in English. The sculpture of these porches merits attention; over the centre door the bas-relief represents the Last Judgment; the statues are those of the 12 Apostles. Over the rt. hand porch are the Death and Assumption of the Virgin; over that on the l. is the legend of St. Firmin, the apostle of Picardy. Above the portals runs a colossal line of French kings, behind which appears a noble wheel-window; and the whole is flanked by two stately but unfinished towers.

"The interior is one of the most magnificent spectacles that architectural skill can ever have produced. The mind is filled and elevated by its enormous height (140 ft.), its lofty and many-coloured clerestory, its grand proportions, its noble simplicity. The proportion of height to breadth is almost double that to which we are accustomed in English cathedrals; the lofty, solid piers,

which bear up this height, are far more massive in their plan than the light and graceful clusters of our English churches, each of them being a cylinder with 4 engaged columns. The polygonal E. apse is a feature which we seldom see, and nowhere so exhibited, and on such a scale; and the peculiar French arrangement which puts the walls at the outside edge of the buttresses, and thus forms interior chapels all round, in addition to the aisles, gives a vast multiplicity of perspective below, which fills out the idea produced by the gigantic height of the centre. Such terms will not be considered extravagant when it is recollected that the vault is half as high again as the roof of Westminster Abbey." — *Whewell*.

The entire length is 442 ft. The general character of the architecture is that of the early English, except the geometric tracery of the windows. The triforium is glazed, which gives great lightness to the interior. Just within the central porch are two fine brass effigies of bishops; that on the l. as you enter is Evrard de Fouilly, who laid the first stone of the church; that on the rt. Geoffroy d'Eu, "learned," as his epitaph tells us "in medicine as well as theology." The splendid pulpit, the work of an artist of Amiens, Dupuis, is supported by statues of Faith, Hope, and Charity.

Placed at the crossing of the transept, the spectator may admire the three magnificent rose windows, all of elaborate tracery and varied patterns, filled with rich stained glass, each nearly 100 ft. in circumference, which form a great ornament to this church, and surpass everything of the sort which England can show. The font in the N. transept is a oblong trough of stone, probably of the 10th or 11th century.

Round the wall which separates the choir from its aisles runs a low screen of stone, enclosing a series of curious sculptures, in high relief, represent-

ing on the S. side the legend of St. Firmin, and on the N. the acts and death of John the Baptist. They date from the end of the 15th century.

The head of St. John the Baptist, brought from Constantinople at the time of the Crusades, has always been considered, and still remains, the most valuable relic possessed by this church. It is deposited in the side chapel dedicated to St. John. Several other heads of St. John existed before the Revolution in other churches of France, and one, indeed, in the neighbouring abbey of St. Acheul; but this, it was maintained, was the genuine one. Since the Revolution, the skull has been reduced to the frontal bone and upper jaw.

Attached to a monument of Canon Lucas, at the back of the high altar, and facing the Lady Chapel, is a weeping angel, which has received more praise than it seems to deserve on the score of art; it is known as "l'enfant pleureur." Blasset is the sculptor's name.

The *choir*, terminating in a semi-circular E. end, the elegantly groined roof resting on compressed lancet-pointed arches, yields in beauty to no part of the church. It is also especially distinguished for the elaborately carved woodwork of its 116 stalls: in variety of invention and delicacy of execution there is nothing finer of the kind in Europe. The intricate details of the tabernacles and lace-like parapets, the bold drawing, and effective, though coarse expression in the bas-reliefs, representing subjects from Holy Writ, the Life of the Virgin, &c., and the close imitation of nature in the twining tendrils and playful foliage of the vine and other plants, deserve minute attention. The carvers were Arnoult Boullin and Alex. Huet, menuisiers of Amiens: the work was finished in 1520. The diapering of fleurs-de-lis at the back of the seats was effaced by order of the government in 1830. To appreciate the vast proportions and examine the details of this cathe-

dral, the visitor ought to ascend to the triforium gallery; thence he may mount the tower and enjoy the view over the vale of the Somme, remarking in his ascent the turret with the stone table, where Henri IV. posted himself to watch the retreat of the Spaniards in 1597. The roof is a wonderful piece of carpentry, 46 feet high; a forest of oak and chestnut must be contained in it.

Within the cathedral of Amiens, Edward III. did homage for Guienne to Philippe of Valois, 1329; and here, in 1385, Isabel of Bavaria was married to the idiot king Charles VI. The best description of Amiens Cathedral is that of M. Gilbert.

The other buildings in the town possess comparatively slight interest. The deserted *Church of St. Remi*, now a stable, was a rich specimen of the latest florid Gothic, the beauty of which is destroyed by mutilations. Within it is a sculptured monument to the family Lannay. In the *Hôtel de Ville*, a building of 1600, the treaty of "the Peace of Amiens" was signed, 1802, by the plenipotentiaries, Joseph Buonaparte for France, Lord Cornwallis for England, Chevalier Azara for Spain, and M. Schimmelpenninck for Holland. The hall is hung with pictures of the modern French school, of slight merit. There is a *Museum*, containing some antiquities, paintings, &c.

A Boulevard surrounds the town, occupying the site of the ancient ramparts, and, being planted with trees, forms an agreeable promenade. A *Citadel*, however, remains, built on the rt. bank of the Somme by Henri IV., and strengthened by modern works. The Spaniards, in 1597, gained the city, which had claimed the privilege of exemption from a military garrison, through the stratagem of one Hernando Tello de Porto Carrero, Spanish governor of Doullens, who, disguising himself and a band of companions as peasants, entered the town at early dawn, along with the market folk, driving



a waggon laden with fruit, which he halted under the gateway. In passing the gate it was contrived that a sack of walnuts should burst; and while the unsuspecting guards were occupied on all-fours scrambling for its scattered contents, the Spaniards fell on them and put them to the sword. In vain the portcullis was hastily lowered: the waggon had been drawn up so as to catch it as it fell, leaving a passage by which a party of armed Spaniards, in ambush outside, gained easy admittance.

Henri IV., not yet firmly fixed in his throne, felt the loss of Amiens as a severe blow, and hastened to recover it. He was aided in the siege and capture of the town, 1598, by a body of 4000 Englishmen, under Sir Arthur Savage, furnished by Queen Elizabeth.

Amiens was the *Samarobriva* of the Romans; and the *Ambiani*, the Gallic inhabitants of the district (whence the name Amiens), are mentioned by Cæsar. Here Merovée was proclaimed king by being raised on the shield of his victorious soldiers.

The following eminent persons were born in the town or its vicinity:—Peter the Hermit, preacher of the first crusade; Gabrielle d'Estrées, the cherished mistress of Henri IV.; Ducange, author of the "Glossarium ad Scriptores mediæ et infimæ Latinitates;" Gresset the poet, author of "Vertvert;" Delambre, the astronomer.

Amiens is celebrated among gourmands for its *pâtés de canard*.

Railways from Amiens—to Paris, —to Lille (Rte. 184), and to Abbeville.

Diligences daily to Beauvais (see p. 15).

The *Abbey of St. Acheul*, on the outskirts of the town, was converted into a Jesuits' college under the Restoration. The crypt under the church contains some ancient tombs and bas-reliefs. At Amiens our route enters upon the Great Trunk Railway from Paris to Lille and Brussels, called *Chemin de Fer du Nord*. R. 184.

9 Boves Stat.

10 Ailly-sur-Noye Stat.

17 Breteuil Stat.—The town lies about 4 m. on the W.

Diligence to Beauvais, 17 m., and to St. Quentin.

15 St. Just Stat.

14 Clermont Stat.

Clermont-sur-Oise (*Inn*: Croissant, tolerable), a prettily situated town on the slopes of a hill, surmounted by the *Castle*, which is now converted into a Penitentiary for women, and so augmented by modern constructions that its antiquity would scarcely be suspected. It was, however, an important fortress from the 10th to the 16th century; taken by the English, 1359 and 1434, and by Henri IV. from the troops of the League, 1595. The elder Condé, disgusted with the Court, retired hither, 1615, and fortified himself against attacks.

From the agreeable promenade *du Chatellier*, which surrounds its walls, jutting out over the valley, a beautiful view of its winding stream is obtained. Cassini, the astronomer and geographer, was a native of Clermont.

8 Liancourt Stat.

7 Creil Stat., a town of 1500 inhab., on the l. bank of the Oise. Only the foundations of a tower remain of the old *Castle* in which Charles VI. was shut up during his madness. It stood on the island below the bridge, but was destroyed at the Revolution.

There is a large delft manufactory at or near Creil.

Diligence to Compiègne (Rte. 183).

The railroad, hitherto carried along the high land of Picardy (chalk in part), now descends the valley of the Oise.

7 St. Leu Stat.

Diligence hence to Chantilly (Rte. 1, p. 5), and to Senlis.

8 Boran Stat.

6 Beaumont-sur-Oise Stat., a town of 2000 inhab., surrounded by a ruined tower, part of its old castle.

From Beaumont the distance by rail is double the direct road to Paris.

7 Ile-Adam Stat.

6 Auvers Stat.

5 Pontoise Stat.

Pontoise (*Inns*: Grand Cerf; H. des Messageries), a town of 5400 inhab., occupies a steep slope on the river Oise, here traversed by a *bridge*, whence its name. It is famous for calves and flour, and supplies Paris with these two articles. The Vienne, which here joins the Oise, turns 30 corn-mills.

The *Church of St. Maclose* is an interesting edifice presenting various styles; there is some painted glass in a chapel near the principal entrance. The *Palais de Justice* is a Gothic building.

Pontoise is a place of some historical notoriety. St. Louis, attacked by a violent illness, was here warned by a voice from heaven to assume the cross — 1244. During the hard winter of 1437, when the ground was covered with snow, the English took the town by surprise, through the ingenious *ruse* of Talbot, who clothed his soldiers in white, under cover of which, in the obscurity of the night, they reached the foot of the walls unobserved by the garrison.

Coaches to Gisors and Chaumont.

8 Herblay Stat.

3 Franconville Stat.

3 Ermont Stat.

3 Enghien Stat. *Enghien les Bains* is a very pretty village on the borders of the Etang de Montmorency, with a *Bathing Establishment* supplied with medicinal waters from a sulphureous spring. Not only on this account, but for the extreme beauty of its situation and environs, it is much frequented by the Parisians as a sort of French Richmond. The walks in the Parc de St. Gratien are pleasant.

Enghien is about  $1\frac{1}{4}$  m. from *Montmorency*, whose beauties are much exaggerated by the Parisians. A road strikes off through Epinay-sur-Seine to *St. Leu*, celebrated for its château and park, which, before the Revolution, belonged to the Duc d'Orléans, and was the favourite re-

sidence of Madame de Genlis. In the time of Napoleon it was given to Hortense, the Queen of Holland, and after the Restoration became the property of the Duc de Bourbon, who ended his days there miserably and mysteriously, being found hanging to the window-bolt (*espagnolette*) of his bed-room.

Montmorency is a dirty little town 14 miles distant from Paris. Its fine *Gothic Ch.*, of the 15th century, contains some good painted glass.

The house called *L'Ermitage*, about  $\frac{1}{2}$  a mile off, has attained celebrity because Rousseau resided in it, 1756-58, and wrote there his "*Nouvelle Héloïse*." It was then the property of Madame d'Epinay, and really a peasant's cottage. It was afterwards occupied by Grétry the composer, who died here 1813. It still exists, but incorporated into a large and more modern mansion, in which are preserved Rousseau's bed, table, &c.

The line is carried past one of the detached forts which surround Paris, and skirts (rt.) the margin of the Seine shortly before reaching

5 *St. Denis Stat.*

The Abbey of *St. Denis* was one of the most important and wealthy religious foundations in France: its abbots were powerful potentates; Turpin was chancellor to Charlemagne, and Suger prime minister to St. Louis.

The *Abbey Church* has been the burial-place of the kings of France from the time of Dagobert (580), and is a building of great interest, in spite of the wanton dilapidations of revolutionary violence, which the restorations carried on under Napoleon, the Bourbons, and Louis-Philippe have not yet entirely repaired, and can never atone for. The W. front, flanked and surmounted by 2 towers, is in the simple early pointed style, having been raised by Abbot Suger, 1134. It was in the porch of St. Denis that Henri IV. abjured the Protestant faith. Over the central portal, which is semicircular, is a



bas-relief of the Last Judgment. A vestibule, crowded with piers to support the towers, leads into the nave, which was built 1281, and is of remarkable width, considering that the roof is of stone. The choir, dating from the earlier period of Abbot Suger, is, like that of Canterbury, much narrower than the nave.

On the l., as you enter the nave, is the monument of Dagobert, a singular Gothic structure, raised to his memory by St. Louis. The bas-reliefs on it represent the pretended vision of a hermit, who reported that he had seen Dagobert in a boat pursued and scourged by devils, but defended by St. Denis, St. Martin, and St. Maurice. On the same side are the splendid monuments, in the style of the Renaissance, of Louis XII. and Anne of Brittany, whose recumbent effigies in marble are surrounded by 12 small statues, in niches, of the Apostles, admirable for design, attitude, and execution. The bas-reliefs round the base represent the battle of Agnadel and the entry of Louis into Milan. This monument is the work of Paulo Poncio. That beside it, of Henri II. and Catherine of Medicis his queen, is said to have been designed by Philip Delorme and executed by Germain Pilon. The royal effigies are repeated twice; below recumbent as dead, above kneeling: at the four corners are the Cardinal Virtues in bronze!

On the S. side of the nave is the cenotaph of Francis I. and Claude his queen, erected 1550, from designs of Primaticcio. The recumbent effigies are by the skilful hand of *Jean Goujon*, as well as the elegant arabesques which decorate the canopy. The frieze running round the base of the monument represents, in a series of marble bas-reliefs of good execution, the battles of Cerisol and of Marignano. The canopy is surmounted by duplicate statues of Francis and his queen, with their three children.

In the N. transept are placed mo-

numental columns to Henri III., assassinated by Jacques Clement 1589, and to Francis II., husband of Mary Queen of Scots, its base surrounded by weeping angels. In the S. transept is a pillar in memory of Henri IV. The effigy of the Breton knight Du Guesclin, whose valour and renown procured him burial in the company of kings, but availed not to save his ashes from sacrilegious dispersion by the republicans, is remarkable for its diminutive size. The choir and its side chapels, elevated considerably above the nave, glow with modern decoration in painting and gilding, which rival heraldic blazonry in gaudy colours, laid on much too indiscriminately, and not in good taste. There is no lack of modern painted glass, a very small portion of the old having escaped the fury of the Revolution. Some fragments of that with which Abbot Suger decorated the building in 1140, still preserved in the apsidal chapels behind the choir, are regarded as the oldest in France. A red flag suspended behind the altar supplies the place of the once-venerated *Oriflamme*, the standard of the realm of France, but not used in battle since the time of Charles VII. It was originally the church flag of the Abbey of St. Denis, which was delivered by the abbot to the military guardian of the church whenever he went forth to fight its battles, and was supposed to secure victory to those who bore it. It supplanted St. Martin's cloak, which had previously served as the royal standard of France.

A flight of steps on either side of the choir leads down into the *crypt* beneath it. Here, along the aisle, are arranged chronologically the monuments of the kings of France from the time of Clovis. The statues called Clovis, king of the Franks, and his queen Clothilda, were brought from the portal of the church at Corbeil on the Seine at the Revolution. They are supposed to be works of the 11th or 12th century, and are curious specimens of royal costume: the fil-

leting of the queen's long hair is worth notice. Those of kings preceding the 13th century consist of rudely-sculptured effigies executed by order of St. Louis. His own bust and that of his queen, with statues of his two sons, painted and gilt, follow next in a separate chapel. The more modern statues of the sovereigns of the house of Valois and Bourbon are of white marble. The series is closed with those of Louis XVI., Marie Antoinette, the Duc de Berri, &c., executed for the Monument Expiatoire destined for the spot where the Duc de Berri was assassinated, but removed to the darkest corner of the crypt in consequence of the July revolution: in conception and execution they appear nearly the worst of the whole.

This long range of Royal tombs is now quite empty, in consequence of a decree of the Convention of 1793 ordering the destruction of the tombs of the *ci-devant* kings at St. Denis. In the course of 3 days 51 tombs were opened, rifled, and demolished; and the bodies of kings, queens, and princes, in every stage of decay, cast out in one indiscriminate heap into two trenches, hastily dug without the walls of the church, after being subjected to every species of brutal indignity. A soldier with his sabre cut the beard from the nearly perfect corpse of Henri IV. to wear it as a moustache on his own lip; and the valiant Turenne's body, so little injured by time that the likeness to his portrait was still recognised, was stuck into a glass case, and made a show to gratify idle curiosity. The broken monuments were conveyed, along with relics of saints and church-plate, to Paris, and owe their preservation and restoration to the praiseworthy zeal and care of M. le Noir, founder of the Musée des Petits Augustins. For 12 years after this sacrilege the Abbey Church of St. Denis, stripped of its lead to furnish bullets, remained roofless; having first been offered for sale for

the value of the building-materials, and next used as a market-house. Napoleon, however, undertook its restoration, and caused the desecrated sepulchral vaults of the Bourbons to be fitted up as a mausoleum for his own family! His design, however, was frustrated by the Restoration. At present the central vaults below the high altar contain the confused mass of royal bones, withdrawn by order of Louis XVIII. from the ditch into which they had been cast, together with the burnt remains of Louis XVI. and Marie Antoinette, the coffins of Louis XVIII. and others of his family. In an obscure corner lies the last Condé, father of the Duc d'Enghien, who died so miserably at St. Leu.

PARIS.—*Terminus*, Clos St. Lazare (see p. 17 and *e.* Charge for post-horses).

#### ROUTE 5.

##### DIEPPE TO PARIS BY GISORS.

168 kilom. = 104 Eng. m.

Steam-boats in summer from Brighton or Shoreham, Mon., Wed., Thurs., and Sat., and from Dieppe 4 days, making the passage in 8 hours.

See "Hints on Landing in France." (§ *c.* *Introduction.*)

*Dieppe.*—*Inns*: H. Royal; H. Royal, near the Quai—very good, W.S.G., C.O.; Roi d'Angleterre; H. des Bains, next the Custom-house, on the Quai; de Londres; Taylor's Hotel.

The sea-port town of Dieppe (17,000 inhab.) is situated in a depression, between two high ranges of the chalk cliffs which here line the coast, as white and nearly as tall as those of England. Through this gap the small river Arques flows into the sea, making an abrupt bend round the tongue of flat land upon which a part of the town is built, and forming a tolerable tide harbour fit for vessels of 500 tons, which is lined with quays, and cleared from mud by sluices. Dieppe is one of the chief fishing ports in France, equipping annually 60 vessels of 9000 tons for the cod fishery, and many more for that of the herring. It is much



frequented as a sea-bathing place in summer.

The streets of Dieppe are regular, and display few specimens of antiquity, in consequence of the bombardment of the town by the English, who, returning from an unsuccessful attack on Brest, 1694, revenged themselves by laying this town in ruins,—a reckless and inglorious exploit. The principal street runs parallel with the sea from the harbour to the castle, and contains some tolerable shops. The market-place, especially on market-day, will display samples of the picturesque dresses and strange high caps of Normandy; perhaps one of those towering, helmet-like head-dresses, once the common head-gear of the women of the Pays de Caux (cauchoise), may present itself. The *Faubourg de Pollet*, however, on the W., inhabited almost exclusively by fishermen, is that in which the most character and peculiarity of costume is observable; and it includes a few old houses. This quarter can be reached now only by making the circuit of the harbour, the old bridge across it having been pulled down in order not to check the force of the waters discharged from the bassin de retenue behind.

In the town itself there is little to merit the stranger's attention.

The *Church of St. Jacques*, in the square a little to the W. of the harbour, is worth a visit. The body of the building is much hidden behind the flying buttresses, some of them consisting of open screen-work tracery with 8 mullions. The anti-Gothic slated cupola, however, above the cross, does not add to its beauty. The interior also is disfigured by yellow wash and wooden screens. The transepts are the oldest part, built in the 13th century, as well as perhaps the arches of the choir: the nave is a little later, and the roof and many of the side chapels are not older than the 15th. The screens and curious carvings in the side aisles, especially that before the

*France.*

sacristy or trésor—a confusion of the Gothic and Italian styles—and that in the chapel of St. Yves, deserve notice as examples of French florid Gothic of the 15th and 16th centuries. “The Lady Chapel is a late specimen of Gothic art. The bosses of the groined roof are of delicate filagree work, and the vaulting is ornamented with knots pendent from the ribs.” Here is one of those strange representations of the Holy Sepulchre surrounded by figures of the three Mariæ and other holy personages, so common in Romish churches abroad, executed in a very inferior style.

The *Castle*, rising on the tall cliff at the W. end of the town, built in the 15th century, is now a barrack, and much modernised, so that it contains nothing remarkable. It is, however, a picturesque object, with its group of quaint cone-headed towers, its high bridge and draw-bridge spanning a chasm which runs down to the sea; it commands a fine view, and it possesses historical associations of great interest. Within these walls Henri IV., retreating before the army of the League, found shelter among his “bons Dieppois,” as he called them, who had been the first to acknowledge his right to the throne, before the battle of Arques. He made choice of Dieppe from the attachment of its inhabitants, the fidelity of its governor, and the advantage of an open communication by sea with England. While here he received from Queen Elizabeth a reinforcement of 1000 Scotch and 4500 English soldiers.

In 1650, the famous Duchesse de Longueville, so prominent among the leaders of the party of the Fronde, defying the royal authority, was compelled to take refuge in the castle; but being pursued even hither by the vengeance of Mazarin and Anne of Austria, she with difficulty at length escaped hence by night, and making her way amidst storm and tempest, after innumerable escapes and adven-

tures, embarked alone from the coast in an English vessel, dressed as a man, and at length succeeded in reaching Rotterdam.

Dieppe at present, in its nearly empty port and lifeless streets, gives little token of its former celebrity and prosperity. Yet 3 centuries ago it was the most flourishing seaport of France, and one of the first in Europe. The fleets of its adventurous merchants traversed every sea: one of them, indeed (Ango), riding in the Tagus with his merchant squadron, bearded the king of Portugal in his own capital; another captured the Canaries. Its skilful and hardy sailors distinguished themselves by their geographical discoveries and early settlements in the 15th and 16th centuries. Claims are put forth for their having found out the passage round the Cape of Good Hope before the Portuguese. If it were so, they certainly kept the secret so close that they have lost the credit of it. They were among the first visitors of the New World, explored Florida, opening the fur trade in Canada, and establishing the earliest European colony in Senegal; whence, as well as from the East Indies, they drew the costliest gums, gems, precious stones, metals and tissues, with which they for a long time exclusively supplied their luxurious countrymen. The importation of elephants' teeth from Africa is said to have given rise to the pretty *Manufacture of carved ivory*, which still exists here, and is almost peculiar to Dieppe. The rivalry of the Port of Havre, and its superior advantages in internal communication up the Seine, were the ruin of Dieppe. The revocation of the Edict of Nantes, and the English bombardment, inflicted severe blows in addition; and although the extensive equipment of vessels for the fisheries of cod in Newfoundland, and of the herring, has long contributed largely to the support of the town, yet they are much fallen off at present, and are insufficient to revive its pristine importance.

Dieppe, however, is much frequented as a watering-place in summer. The *Etablissement des Bains* is situated on the beach, nearly under the castle. There are no proper bathing-machines; and the bottom is a mass of flint shingle, without sand. A series of little huts are erected at the sea-side, from which ladies issue in robes resembling those of nuns, and gentlemen in wide trousers, and thus bathe in public. Ladies are assisted by male dippers appointed for this service, if they require their aid. There are also *hot baths* near the beach.

*English Ch. service*, Sunday at 1 p.m. Old Carmelite convent chapel.

*Diligences*—to Paris twice a-day by Rouen and the Railway in 10 hours (R. 6), to Havre and to Abbeville (R. 18).

The *Environs of Dieppe* present several interesting excursions. About 2 m. to the E., on the cliffs above the sea, is a camp capable of holding many thousand men, once attributed to Cæsar, but now supposed to be Gallic, and called *la Cité des Limes*. It is triangular in form, defended on the land-side by a rampart in places more than 50 ft. high. It is near the road to *Eu* (R. 18), 18 $\frac{3}{4}$  m. distant, where the *Château* of Louis-Philippe and the *Church* deserve a visit.

The most delightful walk, however, in the neighbourhood of Dieppe is to the ruins of the *Castle of Arques*, which are far more interesting than the *Cité des Limes*. They are situated in the valley of the Bethune, at its junction with the Arques, less than 4 m. S.E. of Dieppe, and are celebrated for the momentous victory gained beneath the walls by Henri IV. and his devoted band of 4000 Protestants over the army of the League, 30,000 strong, under the Duc de Mayenne, which decided the fate of the Béarnais prince. The artillery from its walls contributed not a little to the result of that day. "Il en fut tirée," says Sully in his *Memoirs*, "une volée de quatre pièces, qui fit



quatre belles rues dans leurs escadrons et bataillons." Three or four more discharges not only checked their advance, but drove them behind a bend of the valley to shelter themselves from the cannonade, and from this check they never recovered. The king, expecting the Leaguers to débouche down the valley to attack him, had disposed and intrenched his little band accordingly, when he suddenly found the advanced guard of the Duc de Mayenne in his rear, pushing forward to cut him off from his stronghold, Dieppe. Henri, with great quickness and dexterity, changed his front, threw up fresh ramparts to protect his flanks, and managed still to keep up his communication with Dieppe. Among the heroic traits of Henri on that anxious and hard-fought day, are his words to M. de Belin, an officer of the League, who scornfully inquired where Henri's forces were, to oppose so large an army: "Vous ne les voyez pas toutes, car vous ne comptez pas Dieu et le bon droit, qui m'assistent." A rude *obelisk*, raised on the brow of the hill, marks the spot where the deadliest struggle occurred.

The *Castle*, a fine object at a distance, occupies a commanding position on a tongue of high land between two valleys, and covers a large area with its ruins; but its shattered condition, arising less from the hazards of war and the effects of time than the dilapidations of man, has robbed it of much of its picturesqueness. For a series of years, down to the end of the last century, the government allowed it to be pulled to pieces as a mere quarry of building materials. It is difficult to fix the age of its shapeless walls, deprived of their casing of masonry; but it is probable that the oldest parts, viz., the *Donjon* and its enclosure, date from the time of our Henry II., who rebuilt the castle at the end of the 12th century; other portions are not older than the 16th century. The English,

under Talbot and Warwick, again obtained possession of it in 1419, and kept it for 30 years, down to the capitulation of Rouen, by which it was yielded to Charles VII.

The main entrance remains flanked by 2 massive towers of immense size; and portions of the piers of the drawbridge which led to it are still standing, but "the 3 successive arches of the gateway are torn into nearly shapeless rents."—*D. T.*

Within a pleasant walk from Dieppe, at the pretty but scattered village of *Varengewille*, stands *le Manoir d'Ango*, the château of the celebrated Dieppois merchant Ango,—the host and friend of Francis I. Though now converted into a farmhouse, so little of its external form is defaced that the eye can readily trace all the richness of decoration which distinguished the style of the Renaissance, when it was built.

"The walls are principally constructed of black hewn flint, which, alternating with a white stone, produce a very beautiful mosaic. They retain all the sharpness of their original construction; and the sculptures with which they are enriched are of the most classical and graceful form. A number of large medallions above the grand entrance, and along the façade of the principal corps de bâtiment, are remarkable: among them the portraits of Francis I. and Diane de Poitiers. In the interior are some finely sculptured fire-places and the remains of a large fresco; but they are only to be discovered by groping amongst the greniers, into which the apartments once so splendid have been changed."—*Miss Costello.*

The following direct road from Dieppe to Paris by Gisors, leaving Rouen altogether on one side, is shorter by 8 or 10 miles, but few would omit visiting that highly interesting city. (Routes 6 and 9.) Besides, the railway now renders the route by Rouen the quickest of the two. Diligences have in consequence ceased to run this way. The Gisors

road strikes off to the l., 3 m. beyond Dieppe.

12 Bois Robert.

17 Pommeréval.

4 or 5 m. on the l. of our road lies Neufchâtel, famed for its excellent cylindrical cream - cheeses, called Bondes.

24 Forges les Eaux. A village and watering-place, possessing chalybeate springs once of some repute, but neglected at present. They are three in number—*La Reinette*, *La Royale*, and *Cardinale*; the two last named from Louis XIII. and Cardinal Richelieu, who visited Forges to drink the waters in 1632, the period of their highest celebrity, in consequence of Anne of Austria, after living childless for 18 years, here becoming enceinte with Louis XIV.;—an event which was attributed to a course of these waters.

21 Gournay, famed for its butter, is situated in the district anciently called Pays de Bray.

The *Church of St. Hildebert* was begun in the 11th century, but not finished until the 13th, and its W. front, with pointed arches, is perhaps of the latter date. In the interior, very massive round piers support semicircular arches inclining to the horse-shoe form. The sculptured ornaments of the capitals are very remarkable for variety of pattern. Herring-bone masonry occurs in the E. end. About 5 m. from Gournay is the *Abbey Church of St. Germer*, as grand and large as a cathedral, of the 13th century.

12 Talmoutiers.

14 Gisors. — *Inn*: H. de l'Ecu. An ancient town of 3500 inhab., prettily situated on the Epte. Its venerable ramparts are converted into agreeable promenades, whose plantations encircle the ruins of its commanding *Castle*, once the bulwark of Normandy on the side of France, and still retaining many interesting characteristics of a feudal fortress of the middle ages. The octagonal Donjon especially, and its enclosure, crown-

ing the top of a high artificial conical mound, are of the most solid construction, and are works of the 12th century, built by our Henry II. The walls of a dungeon under one of the towers have been curiously carved with a nail by some unfortunate prisoner. At an interview which took place here between Henry and Louis VII., the two monarchs agreed to assume the cross for the recovery of Jerusalem.

The *Parish Church*, dedicated to Sts. Gervais and Protais, presents a singular combination of styles, and an abundance of uncouth sculptures: it has a choir built in the 13th century by Blanche of Castille (it is said); the nave and remainder of the church are of a later period. The sculpture of the portal, richly carved, is of the latest style of French florid Gothic, and much overladen with ornament. The organ-loft, and an emaciated monumental effigy, both attributed to Jean Goujon, merit notice, and there is some fine painted glass in the windows. In the S. aisle is a singular twisted column, surrounded by spiral bands of tracery.

Gisors is on the high road from Paris to Rouen (R. 10).

19 Chars.

18 Pontoise (in Route 3).

10 Herblay. Here the road bifurcates: the l.-hand branch leads to Paris by St. Denis (see Route 3); that on the rt. proceeds by Besons, where it crosses the Seine, and by

12 Courbevoie, to the Barrière de Neuilly, entering

9 PARIS by the Arc de l'Etoile. See GALIGNANI'S GUIDE, and p. 17.

## ROUTE 6.

### DIEPPE TO ROUEN.

57 kilom. = 35 Eng. m.

A *Railway* is in progress.

*Diligences* go twice a day in 5 hrs., at 9 a.m. and 12, to catch the 3 and 6 o'clock trains from Rouen to Paris.

In the outskirts of Dieppe, we leave on the rt. the road to Havre



(Route 18), and 3 m. farther, on the l., that to Paris direct (Route 5). Our road lies through a country pleasing when it enters the valleys, but bare and monotonous as long as it lies along the high table-land of the Pays de Caux. The land produces abundant crops of corn, and from the number of hedges is not unlike parts of England. "During the whole ride there is not one object to excite curiosity." The way is enlivened here and there at long intervals by villas or châteaux, without any claim to beauty.

#### 15 Omonville.

The numerous orchards are one of the characteristic features of Normandy, which is a cider, not wine-drinking, province.

13 Tôtes. (Cygne, a small but clean country Inn.) The spinning and weaving of cotton already begin to furnish employment to the inhabitants; mills and factories increase in number as we approach Rouen, the great centre of the cotton manufacture in France.

12 Cambres. We now enter the pretty, industrious, and populous vale of the Cailly, a stream which furnishes motive power to the numerous mills, and has given rise to a chain of populous villages along its banks.

The line of houses, factories, and chimneys, interspersed with villas, orchards, and gardens, almost uninterrupted, from Malaunay to Rouen, may remind an Englishman of the clothing district of the W. of England. In 1845 (Aug. 19) a terrific whirlwind swept down part of this valley, and in the course of 1½ minute demolished 3 factories, crumbling them like houses of cards, and all within them, people and machinery. 60 lives were lost, 100 were wounded, many were buried in the ruins.

At Malaunay the Dieppe Railway falls into the line from Rouen to Havre. (Route 14.)

Before reaching the barrier, a pretty view is obtained of the blue hills which border the Seine; nor is

the atmosphere thickened with so dense an envelope of smoke as hovers over the great manufacturing centres of England. A great part of the coal here used comes from England; the Dépt. du Nord furnishes also its supplies.

#### 17 ROUEN (in Route 8).

### ROUTE 8.

#### PARIS TO ROUEN—RAILROAD.

137 kilom.=84 Eng. m.

*Trains* 6 times a day, in about 5 hours. *Terminus* in Paris, Rue d'Amsterdam. Fares, 16, 13, and 10 francs.

This railroad was commenced in 1841, and opened May 1843. Its engineer is Mr. Locke, who executed the London and Southampton Railway; many of the shareholders are English capitalists of Lancashire; and even most of the workmen were English. A considerable number of experienced "navigators," having been transported across the Channel, worked on it harmoniously with their French brethren, showing them the mode of operation. The rails are of French iron, which is much dearer than English; but the locomotives, though made in France (at Rouen), are executed by an English company, established there expressly to supply this railroad. The minute subdivision of property in France, and the great number of landholders with whom the company had to deal, occasioned some difficulty in obtaining the land over which the railway passes, and caused the number of contracts to be multiplied enormously; but the demands of the proprietors were by no means so exorbitant as in England.

The first part of the line is the same as that to St. Germain (Rte. 9). The railway, after passing on a bridge over the Rue de Stockholm, and through 2 tunnels under the Place d'Europe and other streets, quits Paris by Les Batignolles. The village of Clichy is passed on the rt,

hand, and the Seine is crossed by a bridge of 5 arches before reaching the village.

$4\frac{1}{2}$  Asnières (stat.), on the l. bank of the Seine, here crossed by another bridge, below that of the Chemin de Fer. The Versailles Railroad (rive droite) and the St. Germain Railroad here branch off to the l.

At Colombes, a small village, Henrietta Maria, widow of Charles I. and daughter of Henri IV., died in great poverty, 1669. The château which she inhabited no longer exists.

At Bezons it crosses the Seine by a bridge of 9 flat timber arches, each 100 feet span, supported on stone piers. From this an embankment extends nearly a mile to a cutting at Houille, which is also about a mile. Beyond this the embankment continues to the Seine, which is traversed for the second time by a bridge like the former, conducting to

17 Maisons (stat. at the end of the avenue leading to M. Lafitte's villa). (*Inns*: Hôtel Talma, so called because once the residence of the actor; good. Le Petit Havre.) The *Château*, now the property of M. Jacques Lafitte, was built by François Mansard, 1658, for the Surintendant des Finances René de Longueil, and is a handsome edifice of Italian architecture. Voltaire wrote "Zaire" here; and he was here attacked with smallpox, which nearly carried him off. Before the Revolution it belonged to the Comte d'Artois, and was afterwards given by Napoleon to Marshal Lannes. The park has been cut into building lots, sold piecemeal, and studded over with villas, in the manner of the Regent's Park. Access is given to the new colony by the bridge of wood resting on stone piers. The distance hence to Paris is only 12 m. by land.

The railway proceeds, hence in a cutting, across the forest of St. Germain, and follows the l. bank of the Seine by

9 Poissy (stat.) (H. de Rouen), a small town on the l. bank of the

Seine, the birth-place of St. Louis (1215), who was wont to sign himself by the modest style of Louis of Poissy. The font at which he was baptized is still shown in the *Parish Church*, a Gothic building of the 13th century.

The *Conference of Poissy* was held 1561, with the hope of adjusting differences between the Popish and Calvinistic churches; Beza with a train of doctors appearing for the one party, and the papal legate Cardinal Ippolito d'Este for the other; and Charles IX. attended the first meeting with his mother Catherine de Medicis. But the controversialists soon separated without having approached to a reconciliation, each side believing it had the best of the argument.

A dirty and inconveniently narrow street leads to the long bridge of Poissy over the Seine, of 37 arches of different sizes, including the approaches, built, it is said, by St. Louis. The 3 central arches, now supplied by timber, were blown up in 1815 to prevent the passage of the allies; or, as some say, so long ago as in 1589, by Mayenne, the general of the League, to secure a safe retreat for his army from the pursuit of Maréchal de Biron, who had sacked Poissy because it refused to deliver its keys to the kings Henri III. and IV.

The greatest cattle market in France is held here every Thursday for the supply of Paris with meat.

8 Triel (stat.) In the church is an Adoration of the Shepherds, said to be an original, by *Poussin*, and some good painted glass. Here and at Vaux are extensive plaster quarries.

6 Meulan (stat.) This town, on the rt. bank of the Seine, is partly built on the slope of the hill, partly on an island in the middle of the river joined to the banks by an old stone bridge in two divisions.

8 Epone (stat.) has a fine *Church*, 12th century.

The scenery of the valley is very pleasing, though the chalky white of the rocks is an eyesore. The banks



of the river are enlivened with country houses. The post road runs at some distance from the river until it reaches Limay, the faubourg of Mantes, where it crosses from the rt. to the l. bank by the bridge. The railway runs in a cutting to the W. of the town of

7 Mantes (stat.)—*Inns*: Cheval Blanc;—Grand Cerf. This town is prettily situated on the margin of the Seine, whence it has gained the epithet *La Jolie*.

The chief building is the *Church of Notre Dame*, standing a little way above the bridge, and conspicuous by reason of its 2 towers from a long distance. It is a fine Gothic building; the body supported by flying buttresses, the roof covered with coloured tiles. The portals are pointed; the sculpture which adorns them is sadly mutilated. The interior, in the early pointed style, is very pleasing; its most remarkable feature being the height of the triforium gallery formed of triple arches, which being carried quite round the E. end, and lighted by windows behind, gives a cheerful character to the church. The towers at the W. end open into the nave. It was built for Blanche of Castille and her son St. Louis by the architect Eudes de Montreuil.

The solitary *Tower of St. Maclou* is the sole remnant of another church, built in 1344 with the toll dues exacted for leave to tow barges through the bridge on Sundays and holydays. It is deservedly preserved as a fine light Gothic structure.

It was among the glowing embers of the houses and monasteries of Mantes, which he had remorselessly caused to be burnt, that William the Conqueror received the injury in his corpulent person, caused by his horse starting, which proved mortal a few days after at Rouen. The castle of the French kings, where Henri IV. held the conferences with the Romish clergy which preceded his abjuration of the Protestant faith, was destroyed by the Regent Duke of Orleans.

*Coaches* daily to St. Germain by the road on the left bank of the Seine.

About half way between Mantes and Bonnières we pass on the rt. *Rosny*, a dirty little village, contiguous to which, between it and the Seine, stands the *Château*, the birth-place of Sully, where he was frequently visited by his friend and master Henri IV., who slept here the night after his victory at Ivry. The king, having overtaken Sully on the road desperately wounded carried on a litter, accompanied by his squires in a like plight, fell on his neck and affectionately embraced him. The château is a plain, solid building of red brick, with stone quoins and a high tent roof, surrounded by a deep ditch; it was rebuilt by Sully at the beginning of the 17th century. It is destitute of architectural beauty externally, and within has been modernised, although one room is still called *Chambre de Sully*. From 1818 down to the Revolution of 1830, Rosny was the favourite residence of the Duchesse de Berri, who erected here a chapel to contain the heart of her husband. The château has since changed hands repeatedly, and its present proprietor has pulled down the wings, which were modern, and added by the duchess. The grounds extend for some distance along the margin of the river, to which they owe their sole charm, the ground being perfectly flat, and traversed by long formal avenues.

In skirting the forest of Rosny, contiguous to the village, we are reminded of the sacrifice made by Sully, in felling in it at one time timber to the amount of 100,000 francs to pay his master's debts.

A great projecting buttress of chalk now intervenes, over which the high road is carried by a steep ascent and descent, and round which the Seine winds in a widely circuitous curve. The railway pierces this by a *Tunnel* about 2480 yards long—driven through the chalk and a flinty

conglomerate very hard to penetrate, commencing at Rolleboise, about 5 miles from Mantes, and terminating on the W. at a short distance from

13 Bonnières (stat.), the railway having been previously carried over the high road by a bridge. Bonnières is the station nearest to Evreux (R. 25), on the road to Caen and Cherbourg. Hence the railroad runs under the high ground close to the river as far as

10 Vernon (stat.).—*Inn*: Grand Cerf. This town (pop. 5300), which, like many others in Normandy, gives a name to a noble English family, is prettily situated, and its interior retains a venerable air of antiquity in its timber-framed houses; but its narrow streets, however picturesque, are by no means convenient on a great highway of traffic. There is preserved an ancient tower, tall and massive; and a Gothic church, the choir of the 13th, the nave of the 16th century, in which one monument only among many escaped the Revolution,—that of a lady of the family Maignard,—consisting of a kneeling effigy in marble (date 1610). Vernon possesses a hospital founded by St. Louis, an artillery barrack, and vast quarries of building stone on the opposite side of the Seine.

The *Château de Bizy*, one of the finest seats in Normandy, the property of the Counts of Eu, and afterwards of the Duc de Penthièvre, was destroyed at the Revolution, and is now replaced by a plain country house belonging to Louis-Philippe, approached by a fine avenue, on the outskirts of the town. *Coaches* to Evreux, Dreux, and Chartres.

13 Gaillon (stat.). A huge *penitentiary* occupies the place, and in part the remains, of the *Château* of the archbishops of Rouen. It was built 1515 for the Cardinal d'Amboise, out of the tribute levied on the Genoese, conceded to him by Louis XII., by the architects Jean Joconde and Androuet du Cerceau, and was adorned by the sculptor Jean-Juste

de Tours. It was demolished at the Revolution, except the entrance portal flanked by 4 turrets, and covered with inscriptions and bas-reliefs, the clock tower, and the chapel tower. The gateway between the 1st and 2nd courts, a splendid example of the style of the Renaissance, was rescued by M. Lenoir and transported to Paris, where it has been reconstructed in front of the Ecole des Beaux Arts. Its architect was Pierre Fain, date 1509.

In the distance is seen the imposing ruin of Château Gaillard, the pet castle of Richard Cœur de Lion (Route 11), rising on a lofty rock washed by the Seine, but 5 or 6 m. N. of our road; so great is the circuit which the river here again makes.

Gaillon is the station nearest to Auteuil and the town of Andelys (omnibus runs thither), and hence an excursion may be made to the interesting castle of Château Gaillard (p. 50). Near le Grand Villers, two *Tunnels* are driven through the mass of a projecting promontory of chalk hill. The first or easternmost of *Le Rule* is a mile long, and the second of *Venables* 470 yards long.

13 St. Pierre de Vauvray (stat.) The manufacturing town of Louviers is about 5 miles or 8 kilom. W. of this station (p. 46). Post horses are kept here.

The Seine is traversed obliquely for the 3d time by a bridge at Le Manoir just above the confluence of the Eure, and the railway proceeds along the rt. bank of the Seine for a short distance to

12½ Pont de l'Arche, stat. at the extremity of the bridge leading to that town. Pont de l'Arche is a small town whose main street is a narrow and inconvenient lane leading to the bridge of 22 arches, by which the Seine is crossed by the post road, a little below the junction of the Eure. The view from it is pretty; on the right is seen the Côte des Deux Amants (see Route 11). The tide ascends to this point.



The Gothic Church contains some curious painted windows: in one of them the inhabitants of the town, male and female, in the costume of the 16th century, are seen towing barges through the central arch of the bridge. *Coaches* to Elbœuf (p. 52).

The railway next passes through the hill of Tourville by a short *Tunnel* of about 500 yards, and crosses the Seine, here divided into two arms, for the 4th time, by a bridge resting on the Ile des Bœufs, to

5 Tourville, the station for the populous and industrious town of Elbœuf (p. 52). Hence it proceeds onwards along the l. bank of the Seine through St. Etienne de Louvray and Sotteville to its termination in the Faubourg St. Sever of the great city of

12 ROUEN, Terminus, Cours la Reine. *Postmaster's charge* 1 fr. 50 c. for each horse and each postilion in conveying a carriage from the railway to any part of Rouen.

ROUEN.—*Inns*: Hôtel de Rouen, on the Quai du Havre, close to the landing-place of the steamer; room 3 fr.; table d'hôte 3 fr.;—H. d'Angleterre;—H. d'Albion, on the Quai;—H. de Normandie, good and reasonable;—Hôtel Vatel, Rue des Carmes.

Rouen, anciently *Rotomagus*, the capital of ancient Normandy, and the chief town at present of the department of the Seine Inférieure, is agreeably seated on the Seine, and yields to no provincial city of France in its majestic and venerable aspect, in historic associations, and in magnificent buildings; the triumph of the ecclesiastical and civil architecture of the middle ages. It has this advantage also over most other ancient towns, that it is not a mere heap of dry bones, destitute of life and abandoned by commerce: its narrow streets of gable-faced, timber-fronted mansions, swarm like an ant-hill with busy crowds passing to and fro; it is a focus of trade, and the chief seat of the cotton manufacture in France.

It may be called, indeed, the French Manchester. It contains 92,083 inhab., and is surpassed in population by only 4 other cities in France.

The situation of Rouen on a river which affords ready access on the one hand to the sea at Havre (103 m. distant by the windings of the stream), and with the capital on the other, tends highly to promote its industry and commerce. The Seine, here more than 1000 ft. broad, forms a convenient port, accessible for vessels of 250 tons; and though the number of vessels is small, they add both to the picturesqueness and animation of the scene. Its banks are formed into five broad *Quais*, and these are lined with handsome modern buildings, which have sprung up within the last 10 or 15 years, and serve as a screen to hide a rear rank of tottering timber houses, such as form the bulk of the city, and which previously extended down to the river side. Modern improvements and additions, indeed, have of late greatly detracted from the venerable and picturesque appearance of Rouen; but the changes are skin-deep, confined to its exterior, and the stranger has only to plunge into its almost inextricable labyrinth of streets to find enough of antiquity to satiate the artist or the most ardent lover of by-gone times: although a law having been passed prohibiting the rebuilding of houses in wood, their number must diminish every year.

A *Boulevard*, occupying the place of the old fortifications which resisted Henry V. of England and Henri IV. of France, runs round the old town nearly in a semicircle, touching the Seine at its two extremities. This line includes within it all the most interesting public monuments and objects worth notice; outside of it spreads a supplement of populous faubourgs, occupied chiefly by the weavers and working classes, who also form the bulk of the population in the suburb St. Sever, on the l. bank of the Seine, having wider, but not cleaner streets than the inner town, interspersed at

intervals by tall smoking chimneys and lavishly glazed spinning mills.

A walk through the town in the following order will carry the pedestrian to the things best worth observation; but if he wishes to see them thoroughly, he will find one or even two days not enough. The distances from one quarter of the town to another are considerable, to say nothing of the want of pavement, the dirt, and the bad smells which he will have to encounter. The Rue Grand Port, which runs up from the quai opposite the suspension-bridge, and which is at once the chief thoroughfare and includes the best shops, will bring you to the Cathedral; a little in the rear of it, to the E., is the church of St. Maclou, from the door of which, the Rue Damiette running due N. will bring you to St. Ouen, the noblest church in Rouen. Close beside it, in the H. de Ville, is the gallery of pictures; but more worthy of attention is the Museum of Antiquities, Rue de Beauvoisin, near the Boulevard. Hence you must thread your way back to the river, visiting in turn the Palais de Justice, Tour de la Grosse Horloge, Place de la Pucelle (where Joan of Arc was burnt), and Hôtel de Bourghtheroude. As the churches are closed from 12 to 3, except on Saturday and Sunday, they should be visited in the early part of the day.

The *Cathedral* of Notre Dame occupies with its W. front one side of the fruit and flower market. The vast proportions of this grand Gothic façade, its elaborate and profuse decorations, and its stone screens of open tracery, impress one, at first glance, with wonder and admiration; diminished, however, though not destroyed, by a closer examination, which shows a confusion of ornament and a certain corruption of taste. "It is viciously florid, and looks like a piece of rock-work, rough and encrusted with images and tabernacles, and ornamented from top to bottom."—*G. Knight*. The projecting central porch

and the whole of the upper part were the work of Cardinal d'Amboise (1509—1530); the lateral ones are of an earlier period (13th century) and chaster style; and the sculpture adorning them deserves attention. Above the central door is carved the genealogy of Jesse. Over the l. hand (N.W.) door is the Death of St. John Baptist,—in it may be seen Herodias's daughter dancing, or rather tumbling, before Herod: over this, on the rt., much mutilated, the Virgin with Saints. Of the two stately flanking towers, that of St. Romain, on the N., rests on walls older than any other part of the building (12th century): it may be profitably ascended, on account of the view. The rt. hand, or S. W. tower, called *Tour de Beurre*, because built (between 1485 and 1507) with the money paid for indulgences to eat butter in Lent, is a far more beautiful structure, surmounted with an elegant circlet of stone filagree. It contained the famous bell, named George d'Amboise, melted at the Revolution; it is now gutted. Of the central spire the less that is said the better; it is a cage of cast-iron bars intended to replace a spire of wood burnt by lightning, 1822; and judging from its shape and size, seen at a distance, might be taken for the parent of all the factory chimneys in and about the town. When finished, it will reach to a height of 436 ft. It is quite out of character with the rest of the building, and is intended to be gilt. A corkscrew or geometrical staircase of iron worms itself up the centre to a dizzy height.

The N. and S. fronts are in a style resembling the decorated of England, with geometric tracery. The very beautiful N. door, called *Portail des Libraires*, from the book stalls which once occupied the court before it, was not finished until 1478. The opposite one leading to the S. transept, called *Portail de la Calende*, and nearly of the same age and style, is ornamented with bas-reliefs from the



history of Joseph. The figure hanging, vulgarly supposed to represent a corn merchant who suffered for using false measures, while his property was confiscated to build this entrance, is otherwise, and more accurately, explained to be Pharaoh's chief butler. The N. transept is flanked on either side by open towers of great beauty, and of such proportions as would fit them for the W. front of an English cathedral.

The *interior* measures 435 ft. in length, and the height of the nave is 89½ ft. It is in the early pointed style: above the main arches of the nave runs a second tier, smaller, but opening also into the aisles; an arrangement not uncommon in Normandy, but of which England presents only one instance, in Waltham Abbey. The three rose windows, in the nave and transepts, are very fine in size and decoration. In the end chapel, on the S. side of the nave, is the tomb and effigy of Rollo, first duke of Normandy, and opposite to it that of his son William Long Epée: but the figures are not older probably than the 13th century.

The *choir*, separated from the nave by a modern Grecian screen, was built between 1280 and 1300. The carving of the stalls, executed 1467, is extremely curious. The finest and oldest painted glass is to be found in the chapels of the choir aisles; it is of the 13th century. Small lozenge-shaped tablets of marble, let into the pavement of the choir, mark the spots where the heart of Richard Cœur de Lion, and the bodies of his brother Henry (died 1183), of William son of Geoffroy Plantagenet, their uncle, and of John Duke of Bedford, regent (prorex Normanniæ) under Henry VI. (1435), were interred. Their monuments, much injured by the outrages of the Huguenots in 1663, when all parts of the church suffered more or less, were removed, and lost until 1838, when the *effigy of Richard I.*, a rude statue 6½ ft. long, was dug up from under the pavement on the l.

of the high altar. His "lion heart" was also found still perfect, but shrunk in size, enveloped in a sort of greenish taffeta enclosed in a case of lead, and is now deposited in the sacristy. His body was interred at Fontevault; but he bequeathed his heart to Rouen, on account of the great affection which he bore to the Normans. The effigy of limestone, much mutilated, represents him crowned, and in the royal robes, and is now placed in the *Lady Chapel* behind the high altar, which contains two other splendid and highly interesting monuments. On the rt. hand is that of Cardinal George d'Amboise, archbishop of Rouen and minister of Louis XII., and his brother, a magnificent structure of black and white marble, in the style of the Renaissance, executed in 1525. The marble statues of the two cardinals, uncle and nephew, kneel below a covered canopy richly ornamented and gilt; behind is a bas-relief of St. George and the Dragon; above, in niches arranged two by two, are statues of the 12 Apostles; below are the Cardinal Virtues. The pilasters and intervening spaces are adorned with rich and fanciful arabesques. The bodies of the Cardinals d'Amboise were torn from the grave by the Revolutionists of 1793, the lead of the coffins melted, and the contents scattered.

On the l. side of the chapel is the monument of the Duc de Brézé, grand seneschal of Normandy; but more remarkable as husband of the celebrated Diana of Poitiers, mistress of Henry II., by whom it was erected. The effigy of the distressed widow kneels at the head of an emaciated corpse representing her husband after death, stretched on a sarcophagus of black marble. She is in a mourning attitude corresponding with the words of the epitaph which she caused to be engraved on the tomb:—

"Indivulsa tibi quondam, et fidissima conjux,  
Ut fuit in thalamo sic erit in tumulo."

A sentiment, however, which must

be taken in an ironical sense; it is quite certain that she was not buried with him, but at her château of Anet, and it is probable that she was as true to her word in one respect as in the other. Above, in an arched recess, is the statue of the duke in full armour on horseback. This tomb is a splendid work of the age of Francis I.; and is attributed to Jean Goujon, or Jean Cousin.

A rich florid Gothic niche at the side, surmounted by a stone canopy of open work and intervening stems, was erected at an earlier period (1465) to Pierre de Brézé, grandfather of the preceding. Neither statue nor inscription remains.

The elaborately carved screen in front of the sacristy, executed in the latter part of the 15th century, and its wrought-iron door, must not be passed without notice.

Passing the *Archevêché*, contiguous to the cathedral on its N. and E. side, we come to the

*Church of St. Maclou*, which ranks third among the churches of Rouen in beauty. Its grandest feature is its triple porch; it is a fine specimen of the florid architecture of the 15th century, and the sculpture adorning it is of exquisite taste and beauty of execution. The traveller should pay attention to the wooden doors (including that on the N. side) beautifully carved with Scripture subjects, in bas-relief, by Jean Goujon, it is said, and to the elaborate winding stair of stone near the W. entrance, leading to the organ-loft. There is much painted glass in the windows. The *Cemetery* of St. Maclou is said to be very curious.

The *Church of St. Ouen* surpasses the cathedral in size, purity of style, masterly execution, and splendid but judicious decoration, and is inferior only as regards historic monuments. It is beyond doubt one of the noblest and most perfect Gothic edifices in the world. Although it suffered considerably from the Huguenots (1562), who made 3 bonfires within the

building to burn the stalls, pulpit, organ, and priests' robes; and from the republicans, who turned it into an armourer's shop, and raised a smith's forge in its interior, by the smoke of which the windows were blackened until they ceased to be transparent, it has escaped in a remarkable degree; and judicious restorations, at present carrying on, leave little to desire touching its state of repair.

The first stone of the existing edifice (for 4 other churches had preceded it) was laid 1318 by Abbot Jean Roussel; the choir, the chapels, and nearly all the transept were completed in 21 years, and the nave and tower finished by the end of the 15th century. Thus, one plan being followed to the termination, the most perfect harmony of style prevails throughout. "The W. front was to have been flanked by 2 steeples, between which a curved portico of 3 arches was proposed; but it is unfinished."—*D. T.*

Above the cross rises the central tower, 260 ft. high, which, whether examined close at hand (as it ought to be) or seen at a distance rising above the town, is a model of grace and delicacy. "It is wholly composed of open arches and tracery, and terminates with an octangular crown of fleurs-de-lis"—(*D. T.*), which ancient royal symbol is also discovered in the pattern of the tracery of the windows, and in the painted glass.

The S. portal, called *des Marmouzets* from the figures of animals carved on it, deserves attentive examination, as a gem of Gothic work scarcely to be surpassed. It is surrounded by a fringe of open trefoil arches; while 2 groined pendants, 6 ft. long, drop from its vault. The bas-relief over the door represents the Death and Assumption of the Virgin: the whole has been restored.

The interior (443 ft. long, and 106½ ft. high), notwithstanding its size, is peculiarly light and graceful; the front pillars of its richly moulded



piers run up uninterruptedly to the roof as ribs, the side ones bend under the arches. The clerestory, being very large, increases the effect of lightness; "the windows seem to have absorbed all the solid wall," and the roof is maintained in its place by the support of pillars and buttresses alone. All the glass is painted, and there are 3 noble rose windows filled with it. The stranger should look into the holy water basin (*bénitier*) close to the W. door; he will find the beauties of the interior all mirrored on the surface of the water. The master mason under and by whom this noble church was reared is buried in St. Agnes' chapel, the 2nd on the l. in the N. choir aisle. His name was Alexander Berneval; and, according to tradition, he murdered his apprentice through envy, because the youth had surpassed in the execution of the rose window in the N. transept, into the tracery of which the pentalpha is introduced, that which his master had constructed in the S. transept. Though the mason paid the penalty of his crime, the monks, out of gratitude for his skill, interred his body within the church which he had contributed so much to ornament.

The whole of the transept, choir, and lower part of the tower are decorated in character, passing into the *flamboyant* in the upper story of the tower and in the nave.

The material used in the structure of St. Ouen is a limestone approaching to chalk, and containing flints, which have been often patiently cut through in the delicate carving and tracery. But the details of the building should be studied on the roof, upon the tower, and in the internal galleries. It will well repay the trouble of the ascent.

A very pretty *Garden*, whose great ornament, however, is the adjacent church, extends along the N. side of St. Ouen, behind the *Hôtel de Ville*; it was originally the convent garden. Within it, attached to the church, stands a very perfect *Norman tower*,

with round-headed windows, in the style of the 11th century; it probably formed part of a previously existing church. It is called "*La Chambre aux Cleres.*"

St. Ouen was archbishop of Rouen, and died 678.

The *Hôtel de Ville*, a handsome building of Italian architecture, attached to the N. transept of the church, formed part of the monastery of St. Ouen, to which a modern front, with Corinthian colonnade, has been added so as to give the building an official, civic air. Besides the public offices, it contains the *Public Library*, and *Le Musée des Tableaux*, a collection in which the good paintings bear a very small proportion to the bad. There is an ancient and curious picture, attributed to *Van Eyck*, of the Virgin and Child amidst Angels and Saints, "a delicious painting, and pronounced on good authority to be original;"—(*E. o. S.*); the predella of an altar piece, by *Perugino*, brought from Perugia; a copy of Raphael's *Madonna di San Sisto*; St. Francis in ecstasy, by *Ann. Caracci*; the Plague at Milan, by *Lemomnière of Rouen*; and an *Ecce Homo*, by *Mignard*.

The *Bibliothèque Publique* is a valuable collection of 33,000 volumes, very accessible, being open every day from 11 to 4, and from 6 to 9, except Sunday and Thursday. Among the 1,200 MSS., many richly ornamented with paintings, are the *History of the Normans*, by William of Junières, 11th cent.; a *Benedictionary*, which belonged to an archbishop of Canterbury; and a missal book of the 12th cent.; the *Gradual* of Daniel d'Aubonne, 17th cent., containing about 200 vignettes and initials, is very beautiful.

*Le Musée des Antiquités*, in the suppressed convent de Ste. Marie, Rue Beauvoisin, from the number and rarity of the curiosities deposited in it, consisting for the most part of voluntary donations, is one of the most interesting sights in the town, and

highly creditable to the administration of the department, by whom it was founded, 1833-4; no stranger should omit to visit it. The following enumeration will give an idea of the nature of the objects preserved here:—The door of the house in which Corneille was born; many Roman and Gallic tombstones, coffins, &c., dug up at Rouen and other places in the Dépt. de la Seine Inférieure; many fragments of Roman sculpture; specimens of pottery, glass, mosaics; inscriptions; together with a draped female statue of good work, but wanting the head, from the Roman théâtre, Lillebonne.

It is chiefly, however, for works of art and antiquities of the Middle Ages, and the following period down to the 17th cent., that this museum is entitled to attention.

The windows, 15 in number, by which the gallery is lighted, are all filled with painted glass derived from suppressed convents, churches, &c., forming a chronological series from the 13th to the 17th cent.; very valuable and interesting, as showing the progress of the art. The most remarkable are those from the church of St. Eloi, Rouen, 16th cent.; the miracle of St. Nicholas from St. Godard (first half of 16th cent.), very fine. There is no collection of glass painting equal to this in France or England.

In glazed frames against the wall are hung *charters* and other ancient MSS. containing autographs of remarkable persons. Among them William the Conqueror's mark, a cross (he could not write); and the signatures of our other Norman dukes and kings, among which those of Henry I. and Richard Cœur de Lion may be observed.

The shrine of St. Sever, which once contained the relics of that saint, formerly placed in the cathedral, is in the shape of a Gothic chapel, with silver statues of saints in niches round its sides. It is of oak, covered with copper plates gilt and silvered,

and is an elegant piece of workmanship of the end of the 12th century: it has been restored. A crucifix carved in stone, 16th cent.: at the foot of the cross the holy women; on the opposite side the Virgin and Child. Many other specimens of sculpture of the 15th, 16th, and 17th centuries, in stone and wood, from religious edifices: 5 bas-reliefs of the Last Judgment in marble from the church of St. Denis-sur-Scie; in one, Christ is rescuing souls from the jaws (literally) of hell. Many capitals of Gothic columns richly sculptured.

An extensive collection of coins and medals; Roman, Gallo-Roman, French Norman, &c.

Casts from the bas-reliefs of the Hôtel de Bourgtheroude (p. 40), representing the interview of the Field of the Cloth of Gold between Henry VIII. and Francis I. A small collection of arms and armour—among them will be found the coat of mail of Enguerrand de Marigny from the church of Ecouis (p. 48); also several early cannon and wall pieces, ancient furniture, cabinets.

A fragment of the famous bell George d'Amboise (see p. 34), which was melted into cannons and sous pieces at the Revolution.

This *Museum* is open Sunday and fête days from 11 to 4, and Tuesday and Thursday from 12 to 3.

In an adjoining building is a very respectable *Museum of Natural History*.

The amateur of stained glass should not omit to visit the churches of *St. Godard*, containing two windows 32 ft. high and 12 wide, and *St. Patrice*, where there are many more of still greater beauty executed in the 16th cent. The architecture of these two churches is not remarkable; they are very late in the Gothic style.

The *Church of St. Vincent* has an exquisite Gothic porch, and very fine painted glass likewise.

Another church, *St. Gervais*, situated in the very remote faubourg Cauchois, is reputed the oldest struc-



ture in Rouen, and one of the earliest Christian monuments in France. The church itself is low, humble, and not remarkable; but below it is a *crypt* even more simple and unadorned, but exhibiting to the eye of the antiquary marks of construction as old probably as the 4th century, in the courses of Roman tiles between the layers of rough masonry. It has an apsidal termination: in the side walls are holes for the *cancelli* or rails, to which the curtain was hung to separate the *chancel* from the rest of the church: the altar slab is marked with 5 + +. The two low arched recesses in the walls are said to have been the graves of St. Mello and St. Avitien, the first archbishop of Rouen.

The circular E. end of the church itself, which rests upon this crypt, is in the earliest Norman style: and some of the pillars let into the wall, but too short to support the roof, have classic capitals. The Roman road to Lillebonne passed close to St. Gervais. William the Conqueror, tortured by the wound he had received at the cruel sack and burning of Mantes (p. 31), repaired to the retired monastery of St. Gervais to die. His death-bed exhibited a melancholy example of the vanity of earthly grandeur. Deserted by his own sons, when the breath was scarce out of his body, forsaken by friends and courtiers, and plundered by his servants, his body remained stripped and deserted, until the pity and charity of an unknown knight in the neighbourhood provided the funds necessary for the funeral; and he himself escorted the body to its last resting-place at Caen. There are 7 suppressed churches in Rouen, most of them converted into warehouses.

The *Palais de Justice* is a very interesting specimen of civic Gothic architecture, which may vie with some of the town halls of the Low Countries. Reared at a time when the style had become fantastic in its forms, and exuberant in its adornments, it yet displays so much ori-

ginality of invention, beauty, and gorgeous magnificence, that it is hard to condemn it for a want of taste and purity.

It lines three sides of a square; the wing on the l. is the *Salle des Procureurs*, built 1493, as a sort of exchange for merchants, native and foreign, to meet in. It is a large and handsome hall, with an open roof, like a ship's hull reversed, 160 ft. long and 50 ft. high, a sort of Westminster Hall in miniature, and now serving the same purposes. The body of the building in the centre was raised six years later by Louis XII. for the *Cour d'Echiquier* of Normandy, the ancient supreme tribunal of the duchy, at least as old as the time of William the Conqueror, for which the name of parliament was substituted in 1515 by Francis I. This façade is decorated with all the ornament which the fertile resources of the architect afforded; the square-headed windows are set within the most delicate garlands of stone; the buttresses are studded with niches and crowned by pinnacles; and the lofty dormer windows rising against the high pitched roof are surmounted by canopies of the most delicate open work, with pinnacles and statues, many of them executed by first-rate artists at Paris, and are connected by a pierced battlement of arches and tracery. For many years past this front has been undergoing a careful restoration; it is only a pity that it makes so slow a progress.

The chamber in which the parliament of Normandy met is now the *Salle d'Assises*. It has a fine roof of black oak, set off with gold; but the elegant pendants which hung from it have been removed, and the wainscoting, painted over with arabesques and old mottoes, reminding judges of their duties, has been taken down or effaced by whitewash.

The large building behind the Palais, once the residence of the president of the parliament, is now the *Cour Royale*.

La *Rue de la Grosse Horloge*, not far from the Palais, one of the narrowest and most picturesque in Rouen, is so called from the antique clock gate-house, built 1527, by which it is spanned, adjoining the tower of the Beffroi, whence the curfew is still tolled every evening. In this street are several ancient houses. Nos. 115 and 129 deserve notice.

The *Place de la Pucelle*, known also by the vulgar name *Marché aux Veaux*, serves to record the fate of the heroic and unfortunate Jeanne d'Arc, the deliverer of her country, and the terror of the English, who was burned alive here as a sorceress 1431, on the spot marked by the contemptible modern statue placed upon a pump, which bears her name, but the outward aspect of Bellona! Her ashes were collected by the hangman, and cast into the Seine, by order of the Cardinal of Winchester. He and other prelates were spectators of her execution; and some of them, unmoved by her sufferings, even interrupted the priest who was confessing her, by their impatience, exclaiming, "Now, priest, do you mean to make us dine here?" After she was bound to the stake, and while the flames were rising around her, she begged her confessor to hold aloft the cross, that she might still behold the sacred emblem above the smoke; and she died expressing her conviction of the truth of her mission, and calling on the name of Jesus. The cruelty exercised upon this simple and gentle maiden (for in all her battles she never killed an enemy, and was always intent on preventing the effusion of blood) is a disgrace to the annals of England. In prison she was subjected to insult, insidious treachery, and even outrage; at her trial in the chapel of the castle, she stood alone without counsel or adviser, browbeaten by her inhuman and bloodthirsty judges, yet baffling their cunning and sophistry by her plain straightforward answers.

But one of the saddest circumstances connected with the death of the forlorn maiden of Domremy was the treatment she met with from her own countrymen: the Bishop of Beauvais, her unjust judge, her accuser, and the false priest who was introduced into her cell on the pretence of friendship as a spy to betray her secrets, were all Frenchmen. Her own countrymen allowed her to be made prisoner at Compiègne without an attempt to defend or rescue her; it was they who sold her to the English; and Charles VII., her king, who owed his country and throne to her enthusiasm, appears neither to have cared for nor remembered the heroine of Orleans, from the hour when she fell into the hands of the English. He certainly neither attempted to ransom her, nor did he *protest* against her trial.\*

It was not until 24 years from her death that a papal bull proclaimed her innocence; and a cross was raised by her own countrymen, once more become masters of Rouen, on the spot where she had been bound to the stake.

The great tower of the old castle in which she was imprisoned was demolished 1780. She was shut up in a cage of iron, and her feet were fettered,—yet her spirit remained unbroken; and when some English nobles came to insult her, she answered, "*Je sais bien que les Anglais me feront mourir, croyant après ma mort gagner le royaume de France; mais fussent-ils cent mille Goddams de plus qu'à présent, ils n'auront pas ce royaume.*"

On one side of the market-place, within a short distance of the statue, is an ancient mansion, which the common people call *Maison de la Pucelle*, but properly *l'Hôtel de Bourgtheroude*, constructed at the end of the 15th and beginning of the 16th cent., by Wil-

\* From a masterly and most interesting account of Jeanne d'Arc in the *Quarterly Review*, vol. lxxix.



liam le Roux, seigneur of Bourgthe-roude, nearly at the same period as the Palais de Justice. It is built round a court-yard, and its inner wall is ornamented with a series of bas-reliefs on tablets of marble, representing the interview of the Cloth of Gold, and the procession of the two kings Henry VIII. and Francis I., attended by their suite, among whom Cardinal Wolsey is conspicuous. Above these are other sculptures of allegorical figures, and the elegant hexagonal tower is decorated with pastoral subjects.

The *Convent of St. Amand*, recently pulled down, was a building of the same age: a few curious fragments alone remain in the Rue St. Amand.

There are several Gothic fountains in various parts of the city; the most curious are those of *La Croix de Pierre*, resembling in form Waltham Cross, but erected 1500 by the Cardinal d'Amboise; it stands in the Carrefour St. Vivien. *La Fontaine de la Crosse* is a low Gothic structure of the 15th century, elegantly adorned with tracery.

The house in which the grand Corneille (Pierre) was born, the most illustrious of the natives of Rouen, exists in Rue de la Pie, No. 4; a statue of him has been erected by his fellow-citizens on the stone bridge. Fontenelle, his nephew, author of the "Plurality of Worlds," resided in the Rue des Bons Enfants, No. 132—134. The composer Boieldieu was also born here, and the town has raised a statue to him on the quay facing the Bourse.

The edifice called *Les Halles*, situated between the cathedral and the stone bridge, appropriated to the purpose of a cloth hall for the sale of the manufactures of Rouen, occupies the site of the ancient palace and Vieille Tour, in which King John Lackland is said to have imprisoned and finally murdered his nephew Prince Arthur.

The structure called *Monument de St. Romain*, opposite the cloth hall

(date 1542), was the spot where, by virtue of an ancient privilege conceded by King Dagobert, the chapter of the cathedral were entitled to claim, on Ascension-day, the release of a condemned criminal, how great soever his crime. This custom was intended to commemorate the circumstance of a sentenced malefactor having been the only person willing to accompany St. Romain in his dangerous encounter with the dragon (gargouille) which infested the neighbourhood of Rouen. The monster, as it turned out, did not give much trouble; it was rendered powerless by the simple act of the saint making the sign of the cross over it, and with his stole tied round its neck, allowed itself to be led quietly into the town. The privilege was maintained down to the time of the Revolution, though latterly under considerable modifications. In the front of the house at the corner of the Rue St. Romain and Rue la Croix de Fer, a curious bas-relief of the 16th century, representing a school, is inserted.

*Bridges.*—The first bridge over the Seine here was built (1167) by Queen Matilda, daughter of Henry I.; it lasted till the middle of the 15th century, when it was destroyed, and a bridge of boats substituted for it. In 1829 the upper bridge of stone was completed, and in 1836 the boats were finally replaced, by *the existing suspension bridge*. An opening is left in the centre of this, between the supporting piers, under a lofty cast-iron arch rising 82 ft. above the river, to allow masted vessels to pass.

The *cotton manufactures* of Rouen are of such extent and importance as to render it the Manchester of France; they are greatly promoted by 3 small streams,—the Robec, the Aubitte, and the Reuelle. A particular kind of striped and chequed stuff is called *Rouennerie* (toiles peintes, rayées, et à carreaux), because originally and more especially fabri-

cated here. Spinning and weaving mills, dye works, especially of Turkey red, printing and bleaching works, are most plentifully distributed, not only through town and suburbs, but over the adjacent country in a circuit of many miles, employing, on a moderate computation, 50,000 persons.

The *English church service* is performed here on Sundays at 11 A.M. and 6 P.M. in the Ch. of Ste. Marie la Petite, Rue des Bons Enfants. There are 800 English residents here.

At the *shop of Lebrument, late Frère, bookseller*, Quai de Paris, the traveller may provide himself with many interesting works relating to the antiquities of Normandy, with views and maps.

The *Poste aux Lettres* is on the Quai du Havre, near the Custom House; open from 8 A.M. to 8 P.M.

*British Consul's* address, Rue d'Orléans, 34.

*Malleposte* daily to Tours by Le Mans.

The *Messageries Royales* in the Rue de Bec, 10. *Messag. Lafitte and Co.* Rue Thouret, 15.

*Railroads* — to Paris. 6 trains daily. Terminus in the Faubourg St. Sever. (Route 8.)—To Havre (Route 14); to Dieppe in progress.

*Diligences* to Caen daily, morning and evening; to Gournay and Beauvais daily; to Elbœuf and Lisieux; to Evreux and Orléans; to Pont Audemer and Honfleur; to Dieppe twice a day. (R. 6.)

*Steamboats* daily; to Havre in 8 hours; and to Elbœuf: start from the Quai du Havre (R. 12).

### *Walks and Excursions.*

The *Mont St. Catherine*, the escarped chalk hill on the l. of the city, rising above the Seine and the road to Paris, affords the best distant and panoramic view of Rouen, and will well repay the labour to those who are not afraid to face a steep ascent, 380 ft. high, which may be mastered in half an hour, starting

from the extremity of the Cours Dauphin. The entire mass of the town is spread out below you, surmounted by engine chimneys mixed with spires, sending out its long lines of houses and factories up the hill sides and into the neighbouring industrious valleys, uniting it with distant villages; the noble spires of the cathedral and of St. Ouen rising out of the midst, the winding and sparkling river Seine, spanned by its 2 bridges, and crowded with shipping, the railway pursuing its mole-like course, half above, half under ground, give a pleasing variety to the landscape. The marks of active industry are everywhere apparent, the bleach-fields strewn with white webs, the stream courses marked by rows of factories and tall chimneys, the nooks in the hill sides choked with villages.


All along the top of the mount are traces of ditches and brick foundations of bastions, part of the strong *Fort* occupied by the Marquis Villars and the soldiers of the League during the siege of 1591, which were captured by Henri IV., and dismantled by him in compliance with the request of the citizens, with the memorable words, that "he desired no fortress but the hearts of his subjects." This post was taken by assault, chiefly through the bravery of Henri's English allies under the Earl of Essex, who challenged Villars to maintain, in single combat, on horse or foot, in armour or doublet, that his cause was the better and his mistress the fairer.

Not far from St. Catherine's is Blosseville Bonsecours, with a modern Gothic church and painted windows, built 1846, to contain a figure of the Virgin, much resorted to by pilgrims.


It is worth while to drive out to the château of *Canteleu*, on the road to Caudebec (R. 13), on account of its beautiful view, even if you go no farther.

A more distant excursion, which











will occupy one day very agreeably, is to *Château Gaillard*, near Andelys (Route 11). The post road thither lies through Le Forge Féret (11 kilom.), Pont St. Pierre (10 kilom.), Les Andelys (19 kilom.), making the whole distance  $24\frac{3}{4}$  Eng. m. The Paris Railway passes within 3 m. of Andelys, and is the quickest way.

There are many interesting monuments of architecture in the vicinity of Rouen, among them the Chapelle de St. Julien, 3 or 4 m. S.W. of Rouen, on the l. bank of the Seine (R. 12). St. George Boscherville, 9 m. off, on the road to Havre (R. 13).

## ROUTE 9.

PARIS TO ROUEN (LOWER ROAD), BY  
ST. GERMAIN AND LOUVIERS.

137 kilom.=85 English miles.

Only one *Diligence*, in 10 or 12 hours; the rest are superseded by the railway. (Route 8.)

This road to Rouen is far more generally interesting and more picturesque in scenery than the upper one, through Gisors, but is nearly 7 miles longer than it. It is carried down the valley of the Seine, quitting the bank of the river only to avoid its excessive windings. The high road from Paris to St. Germain commences at the "star," or radiation of routes which gives a name to the *Arc de Triomphe de l'Etoile*, the largest triumphal arch in the world, and the finest entrance into the French capital. Yet the eye scarcely appreciates its vastness: few would suspect that it is nearly as wide and lofty as the façade of Nôtre Dame, or that the aperture of the arch equalled that of its nave. The road skirts on the l. the Bois de Boulogne, famous for promenades, duels, and suicides—now shorn of its proportions to form a glacis for the new fortifications.

A cross road, called Chemin de la Révolte, leading from Neuilly to St. Denis, branches off on the rt.: near the entrance of it occurred the melancholy death of the Duc d'Orléans,

heir to the throne, who was killed in jumping out of his carriage, of which the horses had run away. An elegant Byzantine *Chapel* has been built on the site of the house in which he breathed his last: it is dedicated to St. Ferdinand, and is in the form of a Greek cross. It contains a monumental cenotaph; the effigy of the prince in his uniform reclining on a bed, by M. Eriquetty. On a pedestal to the rt. is an angel kneeling in prayer, one of the last works of his sister the Princess Marie. The painted windows were executed at Sèvres, from Ingre's designs.

The road next passes on the rt. the *Château de Neuilly*, the most frequented residence of King Louis-Philippe, and beyond that village crosses the Seine by the celebrated bridge of 5 arches, each of 120 ft. span, the masterpiece of the architect Perronet, built 1772. Henri IV. and his queen were dragged into the water here in their cumbrous state coach, and narrowly escaped drowning: an accident which caused the ferry to be superseded by a bridge of wood. The park of Neuilly extends for some distance down the rt. bank of the Seine, and into the islands which here divide its stream. On the l. bank is seen the village and large barrack of

9 Courbevoie. A little beyond the post house, our road, a perfectly straight line hitherto, separating from the Route d'en haut (Route 10), bends to the l. and passes the Versailles Railroad (rive droite).

*Mont Valérien*, on the l., recently converted into the *citadel* of the fortifications of Paris, is not more than  $1\frac{1}{2}$  m. distant from the château of Neuilly. The *Church* on this height, founded on the débris of one destroyed by Napoleon, contains numerous relics: among them a fragment of the true Cross (!) and the Calvary attached to it has attracted pious pilgrims for several centuries. Madame de Genlis, the preceptress of the present king, was buried in the cemetery. The

aqueduct of Marly and château of St. Germain are now seen in the distance.

At Ruel the Cardinal Richelieu had a magnificent residence. The large barrack on the l. of the road was occupied in the time of the elder Bourbons by the Swiss guard. In the little church of the village, built 1584, and decorated with a portico at the cost of Cardinal Richelieu, from the designs of Lemercier, is buried the Empress Josephine. A simple monument bearing her statue kneeling, by Cartallier, has been erected by her children, Prince Eugène (Duc of Leuchtenberg), and Hortense Beauharnois (ex-queen of Holland), who has since been buried here herself. Josephine died, May 1814, at her favourite villa, hard by Ruel, *Malmaison*. Her pleasure grounds have been cut up to be sold in lots; her conservatory and menageries, in which she took much delight, and the Swiss dairy and Merino farm, are swept away. The spot seems to have owed its charms chiefly to art; the soil is very sterile. Buonaparte spent 5 days here in June 1815, between his second abdication and his final departure for Rochefort, having been sent out of Paris by Fouché and the provisional government.

The Château has been purchased by Queen Christina of Spain.

The road skirts the enclosing wall of Malmaison for some distance, and soon after reaching the l. bank of the Seine, passes La Chaussée, where La Belle Gabrielle had a house, and *Marly la Machine*, so called from the cumbrous pile of wooden scaffolding and wheels constructed to raise the water of the Seine 300 ft. to supply Versailles, but now partly replaced by a steam engine. The *Aqueduct* of 36 arches, the loftiest 70 ft. high, by which the water is conveyed, is a conspicuous and fine object rising against the hill. The *Château de Marly*, built by Mansard for Louis XIV., was destroyed at the Revolution, having been purchased by specu-

lators who pulled it down to sell the materials, and nothing now remains to mark that scene of a monarch's extravagance and magnificence. St. Simon, describing its construction, relates that whole forests of full-grown trees were brought from Compiègne,  $\frac{3}{4}$ ths of which died and were replaced by others; large tracts of wood were suddenly converted into sheets of water, and back again to shady groves; and all to adorn a small villa in a contracted valley without view, in which Louis might pass 3 or 4 nights in the course of the year.

The pavilion of *Luciennes*, on the brow of the hill above Marly, was the last residence of the notorious Madame du Barry, mistress of Louis XV.

Le Pecq is a suburb of St. Germain, stretching down the hill, on whose summit that town is built, to the margin of the Seine.

14 St. Germain-en-Laye (see below).

---

RAILROAD—*Paris to St. Germain*. The length of the line to Pecq is 18½ kilom.=11 Eng. m. The distance is performed in less than 30 minutes. Trains (convois) go every hour: but see the printed bills. The Terminus (Embarcadère) in Paris is in Rue St. Lazare, No. 120.

The first part of this line as far as 4½ Asnières (stat.) is the same as the Rouen Railway (p. 29).

Colombes stat. (p. 30).

The high road from Paris to Rouen is crossed within a short distance of

7 Nanterre (stat.), a village celebrated as the birth-place of St. Geneviève, the patron saint of Paris, who preserved it by her prayers, according to the legend, from the invasion of Attila. The chapel of the saint at which Anne of Austria came to pray for an heir, 1636, who was born 2 years after, no longer exists. Nanterre is famed for cakes.

Ruel station (p. 43).

The Seine is crossed for the second time shortly before arriving at the station of



$3\frac{1}{2}$  Chatou, by 2 bridges resting on an island which here divides the river. The village of Chatou lies on the rt. hand of the railway and rt. bank of the Seine. An atmospheric branch railway has been constructed hence to St. Germain.

$3\frac{1}{2}$  Le Pecq (stat.), opposite the village of Le Pecq, which is a suburb of St. Germain, and is connected with it by a bridge of stone, erected 1835, in the place of one of wood by which, in 1815, the Prussian army under Blücher crossed the river on its march upon Paris.

The Railway is carried, on the atmospheric principle, across the Seine and up the steep slope to the centre of the *Terrace de St. Germain*,  $\frac{1}{2}$  a mile. The steep ascent, from the bridge up to the town, is surmounted also by a broad road in zigzag, while a flight of stone steps affords access for the pedestrian to the *Terrace* which runs along the brow of the hill.

*St. Germain-en-Laye.* — *Inns:* H. d'Angleterre — de Toulouse — de la Chasse Royale. There is a Restaurant on the slope of the hill, au Pavillon de Henri IV.; the best, but all dear. This deserted residence of kings is interesting from historical recollections, and pleasing from the grandeur of its site; but although it contains 12,000 inhab., it has a melancholy air of abandonment, in its grass-grown streets and straggling edifices. The huge gloomy pile of the *Royal Château* itself, the favourite residence of Marguerite de Valois, Henri II, Henri IV., Francis I., and the birth-place of Charles IX. and of Louis XIV., having been gutted at the Revolution, has nothing but its souvenirs to recommend it. It looks like a prison, and is actually converted into a military penitentiary, and surrounded by a wall for security. Those who will take the trouble to seek an order of admission from the commandant (which is not readily granted) may see the chapel, the oldest part and the least impaired, the hall of Francis I., the bed-chamber of Madame de la

Vallière, and the trap-door by which the youthful Louis gained entrance into it after his mother had caused the door of the backstair to be walled up; also the Oratory of James II., and the chamber in which he died, 1701. This palace was assigned to him as a residence by his host Louis XIV., who was tired of the place himself, having taken an aversion to it, because it commanded a view of his destined resting-place St. Denis. James resided here 12 years, holding the semblance of a court. Part of his body, "une portion de la chair et des parties nobles du corps," was buried in the *parish church*, recently rebuilt and faced with a Doric portico, where a monument was erected to his memory by George IV.

The only real attraction in St. Germain at present is its beautiful *Terrace*, stretching along the brow of the hill for 2400 mètres =  $1\frac{1}{2}$  mile, and commanding a delightful prospect over the valley of the Seine and its windings, with the aqueduct of Marly, on the rt., Château of Maisons on the l., the railways and the Arc de Triomphe de l'Etoile, with the spires of St. Denis rising against the horizon, in front.

The *Forest of St. Germain*, one of the largest in France, having a circuit of 21 miles, occupies a promontory formed by a sweeping bend of the river Seine. It is intersected by roads offering agreeable rides and walks in all directions. In the midst of it is the Pavillon de la Meute (Dog-kennel), begun by Francis I. Deer and roes are found in the remote parts.

The name St. Germain-en-Laye comes from a chapel and monastery of St. Germanus, built in the reign of King Robert, in the midst of the forest then called *Silva Ledia*.

Many English reside here, on account of the cheapness of living and the pure air. The *Ch. service* is performed on Sundays in a private room.

There are 2 roads from St. Ger-

main to Mantes; the one called Chemin de Quarante Sous, keeping on the S. side of the Seine, is the shorter by about 5 miles, but more hilly; the other, the post road, and traversed by the diligences, cuts across the S. extremity of the forest to Poissy (p. 30).

The road descends the rt. bank of the river henceforth as far as Mantes, through

11 Triel (p. 30).

8 Meulan (p. 30).

The railroad is carried along the l. bank of the Seine, and passes in the rear of Mantes, where is a station.

15 Mantes (p. 31).

About half way between Mantes and Bonnières we pass Rosny (p. 31).

The railway is carried on a lofty terrace, side by side with the high road as far as Rolleboise, where it penetrates in a tunnel through a hill which the road surmounts by a steep ascent. (See p. 31.) An abrupt curve of the river, here sweeping round by the château La Roche Guyon (p. 49), is thus avoided. The farther extremity of the tunnel opens out close to

13 Bonnières (p. 32).

About  $1\frac{1}{2}$  m. beyond this the road to Caen and Cherbourg by Evreux (Route 25) separates on the l. from that to Rouen, which skirts the margin of the Seine under a shady avenue of walnut and ash trees. A small rivulet flowing into it from the S., crossed by our road, was the boundary of the ancient province of Normandy, as it now is of the department of the Eure; and 2 m. farther on we reach

11 Vernon (p. 32).

There is another post road from Vernon along the rt. bank of the Seine, by Andelys (22 kilom.), and Château Gaillard (Route 11), Pont St. Pierre (19 kilom.), Le Forge Férét (10 kilom.), to Rouen (11 kilom.), but it is longer by  $3\frac{3}{4}$  m. than the following:

14 Gaillon (p. 32).

The isthmus of the peninsula

formed by this curve is traversed by the railway in a tunnel (p. 31).

The post road quits the borders of the Seine before reaching Gaillon, and does not rejoin it until Pont de l'Arche is reached.

At the village Heudebouville the road to Andelys and Château Gaillard (6 m. distant) strikes off to the rt. Here also the road to Rouen divides into 2 branches; the rt.-hand one, by Vaudreuil, though shorter, is more hilly, and takes the same time to travel, so that by Louviers is preferable. Tall chimneys and numerous huge red-brick buildings with many windows proclaim the manufacturing town of

14 Louviers (*Inns*: H. de Rouën, dear; du Mouton—neither good), advantageously situated on the numerous branches of the Eure; it is one of the 3 principal clothing towns of France, the other two being Elbœuf and Sedan. It contains 30 cloth manufactories, and 19 spinning mills of woollen yarn, which employ from 7,000 to 8,000 persons in and around the town, though the number of inhabitants does not exceed 9,927. The cloth of Louviers is remarkable for its fine quality. The *Ch. of Notre Dame*, shrouded behind the number of its flying buttresses, presents a mass of incongruities and sad mutilations, yet is well worth examination. Its S. portal, projecting forwards on fringed arches, with a pendant hanging from the centre, is decked out with an exuberance of florid ornament. It was built in 1496. The W. end has 3 portals, the centre supported by a Corinthian pillar. In the inside the nave and choir date from 1218, and exhibit the transition from the round to the pointed style; low and thick columnar piers support pointed arches, on which rests a glazed triforium of round-headed trefoil arches, with lancet windows under trefoil arches in the clerestory; the aisles are more modern. The bas-reliefs, carved in wood, of sacred subjects from the life of our Saviour, and



the painted glass, merit notice, as well as the open gallery of flagree stone-work under the central tower, S. side.

The Gothic house with pointed windows, called *Maison des Tempeliers*, is probably as old as the 13th or beginning of the 14th century.

*Coaches*—to St. Pierre de Vauvray station of the Rouen and Paris Railway.

A road branches off hence to El-bœuf (R. 11); *coaches* thither daily.

At Vaudreuil, 3 or 4 m. to the rt. of the road to Rouen, is a modern château, surrounded by the waters of the Eure, and a fine *church* (12th cent.), with a beautiful W. window.

A considerable tract of forest is passed between Louviers and Pont de l'Arche (see p. 32).

To avoid a long bend of the river the road is carried over a high hill, whose top commands a charming view, but on the opposite descent regains the margin of the river before

17 Port St. Ouen, and thence runs beside it, skirting the foot of the chalk hills through a series of villages and hamlets to the extensive suburb of Eauplet, which extends up to the gate of Rouen. The entrance into the town on this side is by the Cours Dauphin, a raised causeway planted with an avenue of trees, having the Seine on the l. and the Champ de Mars on the rt. hand.

11 ROUEN (see Route 8).

ROUTE 10.

PARIS TO ROUEN (THE UPPER ROAD),  
BY GISORS OR BY MAGNY.

By Magny, 119 kilom. = 73 Eng. m. i.e.  $6\frac{3}{4}$  m. shorter than the Lower Rd. (R. 9), but much less interesting. By Gisors, 126 kilom. =  $77\frac{1}{4}$  Eng. m.

- |               |               |
|---------------|---------------|
| 9 Courbevoie, | } in Route 5. |
| 14 Herblay,   |               |
| 9 Pontoise,   |               |
| 18 Chars,     |               |
| 18 Gisors,    |               |

From Paris to Pontoise by St. Denis (R. 2) is 3 kilom. =  $1\frac{3}{4}$  Eng. m. longer, but there is a Railway.

At Herblay the road by St. Denis joins that by Courbevoie. It is a tiresome road from Pontoise to

14 Bord'haut, a hamlet dependent on the village of de Vigny, whose fine old *Castle*, flanked by round towers, topped with extinguisher roofs, and surrounded by a moat, stands on the l. of the road. It was built by the Cardinal d'Amboise, minister of Louis XII., and is a picturesque and interesting specimen of domestic architecture in the beginning of the 16th century.

13 Magny.—*Inn*: Grand Cerf. In the pretty *Church*, in the latest Gothic, passing into the Italian style, is a monument, consisting of three marble statues kneeling, to the memory of the family of Villerond (date 1617); another in bas-relief recording the virtues of M. Dubuisson, pastor of the parish, and a richly ornamented canopy, carved, and bearing statues, which covers the baptismal font.

We now enter the district anciently called *le Vexin*. The little river Epte divided the French from the Norman Vexin, and formed the boundary of Normandy. It is crossed at St. Clair-sur-Epte, whose ruined *Castle*, a mixture of late Norman and early pointed, is reputed the scene of the interview between Charles the Simple and the pirate Rollo; when the barbarian conqueror, called upon to do homage for the fertile province of Normandy, which he had in fact wrung from the weakness of the Frankish king, instead of kneeling to kiss the king's foot, seized the royal leg, and without bending carried it to his mouth, so as to upset the monarch from his seat, amidst the laughter of the rude warriors of the north.

The Epte is crossed on quitting St. Clair.

17 Thilliers-en-Vexin, in the midst of a monotonous plain of rich corn land. Near the middle of this stage the road passes, at some distance on

the rt., a village called Hacqueville, insignificant in itself, but deserving mention as the birthplace of *Mark Isambart Brunel*, the engineer of the Thames Tunnel, whom England is proud to own as her son by adoption, although France claims him by birth. He was educated in the college of Gisors, and when the vacations called him home his favourite resort was the shop of the village carpenter, whose tools and instruments had greater attractions for the youthful engineer than Latin and Greek, and his allotted holiday task (*devoirs*). The writer of this has frequently heard him describe the wonder and delight with which he for the first time beheld (1784), on the quay of Rouen, the component parts of a huge steam engine, just landed from England: "When I am a man," he said to himself, "I will repair to the country where such machinery is made."

15 Ecouis contains a remarkably fine Gothic Church, built in the unusual form of a Greek cross, founded by Enguerrand de Marigny, the unfortunate minister and high treasurer of Philippe le Bel, unjustly condemned to death without trial at the instigation of the succeeding king's uncle, Charles of Valois, and hung on the robbers' gibbet of Montfaucon. His monument, set up in this church at a time when his innocence and worth were acknowledged, was destroyed at the Revolution. That of his brother, Archbishop of Rouen, is still surmounted by his effigy in white marble. He went as ambassador to Edward III. in 1342, "and appeared at court in the guise of a warrior, not of a minister of peace." There are several other tombstones in the choir.

A rapid ascent and descent carries the road across the industrious and picturesque vale of the Andelle, in the midst of which is

9 Fleury-sur-Andelle. About 10 m. N.E. of this, and 2 from Lions la Forêt, are the ruins of the *Abbey of Mortemer*, begun 1154 by Henry II. of England. The church is pulled

down; but some of the conventual buildings in the style of transition from round to pointed—including a fine *chapter-house* (date 1174)—remain. It was at Bourg-boudouin that Roland, the ex-minister and Girondist, committed suicide, 1793. As soon as he heard of his wife's death by the guillotine, he resolved not to survive her; but unwilling to endanger the generous friends who had sheltered him in their house at Rouen, he took leave of them, and carrying a sword-stick in his hand, set out on the road to Paris. When he had got thus far, he sat down under a tree and stabbed himself, leaving about his person a note, written by his own hand, to this effect: "Whoever you may be who find me lying here, treat my remains with respect. They are those of one who devoted his whole life to be useful, and who died as he lived, virtuous and unsullied. May my fellow-citizens embrace more humane sentiments! When I heard of the death of my wife, I loathed a world stained with so many crimes." He perished an instance of the miserable fate which unerringly awaits those who, either from good or evil motives, are the first to plunge a country into revolution.

#### 12 La Forge Féret.

From the brow of the steep hill leading down through deep cuttings into Rouen, a fine view is obtained of that city and the Seine. The upper and lower roads from Paris unite in the suburb Eauplet.

#### 11 ROUEN (Route 8).

### ROUTE 11.

#### THE SEINE.—ST. GERMAIN TO ROUEN.

The figures mark distances from place to place in French lieues =  $2\frac{1}{2}$  Eng. m. From St. Germain to Rouen is 56 leagues, about 140 Eng. m.

*Steamers* used to go daily in summer, making the ascending voyage in 18 hours, the descending in 12, starting from Pecq (a suburb of St. Germain, p. 45). The steam navigation,



however, has been abandoned in consequence of the completion of the railway.

The scenery of the Seine (*Sequana*,—from the Celtic *seach*, devious, and *an*, water) is very pleasing, almost meriting the epithet “beautiful;” its banks are abundantly studded with towns, villages, and châteaux, and are alternately wooded, or rise in round bare hills, sometimes presenting escarpments to the river, which, from the white colour of the chalk, are not altogether picturesque. There are not many *old* castles—Château Gailard, however, is an imposing and interesting ruin, and perhaps, taken as a whole, the finest feature in the voyage. The number of islands in the river between Paris and Rouen is said to be 300. The circuitous windings of the river prolong the distance from Pecq to Rouen to 141 m., while by land it is only 71 m. The voyage *down* the stream, however, had the advantage of freedom from the fatigue of a land journey.

Between St. Germain (or Pecq) and Poissy the river makes a bend of 21 m., inclosing as it were in a loop the forest of St. Germain (p. 45); by land the distance is  $4\frac{1}{2}$  m.

L. the river skirts the forest of St. Germain, passing Mesnil at the extremity of the terrace of St. Germain, and the village. The Seine has been bridged to allow the railway to pass at

L. Maisons (1). Page 30.

Rt. Conflans ( $2\frac{1}{2}$ ), a village having a suspension-bridge over the Seine, by which the road from Pontoise to Versailles crosses the river, is situated a little below the *confluence* of the Oise with the Seine, whence comes its name.

Rt. Andresis is situated below the mouth of the Oise; it has a fine Gothic church.

L. Poissy ( $1\frac{3}{4}$ ); see p. 31. Poissy is not more than 5 m. by land from St. Germain, whereas by the windings of the river the voyage takes  $1\frac{1}{2}$  or 2 hours. The most interesting objects

*France.*

on the river as far as Rosny and Rolleboise are described p. 30, 31.

Rt. Triel ( $2\frac{1}{4}$ ). } The island Ile  
L. Verneuil. } Belle, opposite

Rt. Meulan (2). } Meulan, is reputed the prettiest in the whole course of the river; but it is feared its shrubberies, and thickets, and plantations, have been cut down.

L. Mantes ( $4\frac{3}{4}$ ), and Rt. }  
Limay, united by a }  
bridge. } see p. 31.

L. the château of Rosny  
( $\frac{1}{2}$ ), a red brick build-

ing, with terraces on which Sully may have walked, clipped avenues, &c.

L. Rolleboise ( $\frac{1}{2}$ ); between this place and Bonnières the curve made by the Seine measures 12 m., the direct distance is 3 m.

Rt. La Roche Guyon ( $3\frac{1}{2}$ ), one of the largest châteaux on the Seine, and one of the most striking objects, is a structure of different ages, part modern, part Gothic, situated at the base of a rock of chalk, which has been escarped artificially to make room for it. The kitchen, vaults, cellars, &c. are excavated in the rock, with merely fronts of brick. The oldest part is the tower on the eminence above, commanding the country far and near, and communicating with the château by steps cut in the hill side. On the summit of the hill is a large reservoir for water, excavated out of the rock. The château, long the property of the La Rochefoucaulds, now belongs to the family of Rohan. François de Bourbon, Comte d'Eng-hien, who gained the battle of Cérise-soles, was killed here by a box thrown out of the castle window upon his head. The chamber and bed occupied by Henri IV. on his frequent visits to the castle are kept in their original condition. The attraction which drew him hither was the charms of the lady of the castle, the Marquise de Guercheville, whose high-minded reply to his assiduities deserves recording: “Je ne suis pas d'assez bonne maison pour être votre

femme, mais je suis de trop bonne maison pour être votre maîtresse." The bourg adjoining the castle has a handsome Gothic church. "The houses of the poor people here, as on the Loire in Touraine, are burrowed into the chalk, and have a singular appearance; here are 2 streets of them, one above another."—A. Young. A Suspension Bridge of 656 ft. opening between the piers, has been thrown across the Seine here.

L. Bonnières ( $1\frac{1}{2}$ ).

Rt. Limetz, a village at a little distance from the river, nearly marks the situation of the embouchure of the Epte, a small stream, which once formed the boundary or *limit* of Normandy. Charles the Simple, in 911, was fain to offer to the Norman Rollo all the territory extending from this streamlet to the sea, and with it his fair daughter Gisela, to arrest the exterminating inroads of the warriors of the North. The offer was accepted; and Neustria, receiving the name of its conquerors, became *Normandy*.

L. Vernon ( $2\frac{1}{2}$ ), p. 32.

Rt. The hills which border the river, with nearly precipitous cliffs, have a singularly wavy outline, their curved tops being saddled, as it were, with green turf, while between them dry valleys or coombes open out. They rise in the form of an amphitheatre, encircling an extensive plain. Nearly at the centre of the curve which the Seine here describes, on the summit of a commanding chalk cliff, rises

Rt. *Château Gaillard* (6), the most picturesque ruin and interesting object, both from its situation and associations, in the lower course of the Seine. Immediately below its frowning antique towers, and crumbling crags, a light and convenient wire suspension bridge has been thrown over the river.

The castle was begun and finished in one year by King Richard Cœur de Lion, in defiance of his rival Philippe Augustus, and in the face of the treaty of Louviers, by which he had

bound himself not to fortify Andelys, the little town on the strand at the river side. He thus broke it in substance, while he kept to the letter. Exulting in his stronghold, as he first looked down from its commanding battlements on the defenceless town and exposed river below him, he named it, in the pride of his heart, his "Saucy Castle." Even now that it is reduced to a mouldering ruin, one cannot look up to its towering battlements, or gaze down from them upon the sunny landscape below—the glassy Seine, flowing close at the foot of the castle rocks, then girdling the peninsula in front, and reflecting vine and corn-clad slopes, trees, spires, and cottages in its surface—without sharing in this feeling of exultation of the fierce soldier king, in the possession of a stronghold which enabled him to defy his enemies, and overawe the country around, with the terror of his armed bands and unerring archers.

The eminence on which it stands projects forward, isolated from the neighbouring hills on all sides but one, where it is connected by a narrow tongue. This was cut through by a deep fosse skirting the outer line of wall. On all the other sides steep escarpments rendered the height inaccessible; towards the river, indeed, it presents a vertical precipice. Yet even along the edge of the cliff tall flanking towers were raised, some of which have long since toppled over, while others are tottering to their fall. But these were only the outworks; within them rose a citadel of singular form and strength,—a huge circular drum tower having a wavy surface alternately projecting and receding, like a frustum of a fluted column. The circle is broken by the insertion of a round tower shaped externally like a dice box on the side overhanging the Seine. This was the *Donjon*, and contained the royal apartments; its walls are 14 or 15 ft. thick. A second deep fosse surrounds this citadel, cut in the



chalk rock, here interspersed with flints which were used in the building, and thus it served at once as quarry and defence. Extensive caverns, supported by piers of the rock left standing, branch off from one side of this fosse; they probably were used as stables. The original gateway into the citadel is no longer accessible, but entrance may be gained by clambering through a small sally-port in the corner. It is to be feared that only a small part of the existing ruins belonged to the castle of King Richard. At his death Philippe Augustus, waging war as the champion of Prince Arthur with John, laid siege to this castle. It was bravely defended by Roger de Lacy for 6 months, when he was finally starved into surrender. He had previously expelled from its walls the useless mouths, the old men, women, and children, to the number of 400 or 500; but the French king, wishing to distress the garrison, drove them back and refused them passage, so that the poor wretches, denied admittance into the castle, perished of famine in the ditches between the two armies. Château Gaillard continued to be the chief bulwark of Normandy down to 1606, when Henri IV. demolished it along with other castles as dangerous to the royal authority. In 1314 two frail queens were immured within its walls, and one of them, Marguerite, wife of Louis X., was strangled here by order of her husband. David Bruce found an asylum here 1334, when an exile from Scotland, the castle having been ceded to him by Philippe of Valois. With a small garrison of 120 men it resisted for 16 months the forces of Henry V., and yielded at length because cut off from a supply of water by the wearing out of the ropes by which the buckets were let down into the well!

Against the face of the cliff above the Seine rises a curious pigeon-house tower, lined with cells for the pigeons, a common appendage to an-

cient fortresses, being a sort of natural larder. A chapel of recent date has been excavated in the rock near it.

The suspension bridge over the Seine beneath the castle opens a communication with Louviers (12 m.), rt. Below the castle rock crouches the town of Petit Andelys (no Inn); the large and conspicuous red building surmounted by a dome at the lower end of it, is an *Hospital* founded by the Duc de Penthièvre.

Grand Andelys (*Inn*, Cerf, dear; the house is a curious and picturesque specimen of domestic Gothic architecture within and without; it was the residence of the Archbishop of Rouen, Pierre Harley, temp. Henri IV.). This town of 5000 inhab. lies about 1 m. inland, away from the Seine. The *Gothic church*, somewhat in decay, curiously Italianized on its N. side, contains some painted glass, and a rude representation of the neighbouring Château Gaillard carved in stone. It has many rich details, including a fine oriel. Turnebus, the Greek commentator, was a native of Andelys. The hamlet Villers,  $3\frac{1}{2}$  m. from this, was the birth-place (1594) of *Nicolas Poussin*, the painter; but the humble cottage of his parents is pulled down, and no monument has been set up to his memory. In the *Mairie* is a picture by him—Coriolanus among the Volsci, receiving his mother and wife.

*La Fontaine de Ste. Clothilde* alone recalls to mind the monastery founded here by the first Christian queen of France. It is swept away, but the water of the well is believed by the peasantry still to retain the virtues imparted to it by the royal saint, and to cure their children of stomach-aches.

Andelys is above 4 m. distant from the railroad (R. 8). There is a direct post road to Rouen by Pont St. Pierre; it is traversed daily by a diligence.

The Seine, leaving behind the white crags and towering ruins of Château Gaillard, makes a wide sweep along the base of a series of semicircular

chalk cliffs. This curve of the river is 18 m. long, while the direct distance from (rt.) Thuit to the mouth of the Andelle is only 8 m. There is no place worth notice on the Seine between these two points. The railway (p. 32) emerges from a tunnel near (rt.) Venables, and skirts the river.

Rt. (5 $\frac{1}{4}$ ). The pretty and industrious valley of the Andelle opens out into the Seine at the foot of a green hill, "the last of a long promontory," bearing the name of *Côte des Deux Amans*. It is the scene of the old romantic *Lai* of Mary of France—of the young lover who was to marry the mistress of his heart, a king's daughter, provided he could carry her to the top of the hill without stopping to rest. He fell dead under his precious burthen, exhausted with the exertion, just as he reached the summit; at which the king's daughter died of a broken heart, and was buried in the same grave with him. The hardhearted father who had caused this catastrophe by imposing such cruel conditions, struck with remorse, founded on the spot where it occurred a convent whose existence is traced to an early period, but the building now standing on the top of the hill is not older than 1685.

At Romilly, 8 m. up the valley of the Andelle, are the most extensive copper works in France, consisting of a foundry with rolling mills. The banks of the Andelle are studded with fulling mills. A bridge has been thrown across for the railway a little above the influx of

L. The Eure, from which the Dept. is named, a considerable and useful river, on which stands Louviers, famed for its cloth manufacture (p. 46). The Eure falls into the Seine 2 $\frac{1}{2}$  m. above

L. 3 $\frac{1}{4}$  Pont de l'Arche (p. 32). This town is only 12 m. from Rouen; whilst, in consequence of several serpentine bends, the distance by water is 33. The Seine abounds in islands in this part of its course, which increase the intricacies of the navigation.

L. a little below the bridge stand the remains of the Abbey of *Bon Port*, consisting of the refectory, and another monastic edifice, the church being quite destroyed. It was founded 1119 by Richard Cœur de Lion, in gratitude for his escape from drowning in the waters of the Seine, into which he had plunged in the heat of the chase while pursuing a stag. On reaching the bank, after a severe struggle with the current, he called the spot "bon port," and vowed to build a church. The approach to the town of Elbœuf is marked by the number of tall chimneys, and the many floating arks moored in the midst of the river, used for washing wool.

L. *Elbœuf*, 3.

Elbœuf is exclusively a manufacturing town, and if Rouen has any claim to be compared to Manchester, it may be called a French Leeds, as one of the principal seats of the manufacture of cloth; more than half of its 15,000 inhab. and about 20,000 persons in the adjoining communes being weavers, or occupied in other departments of this branch of industry. Its situation on the l. bank of the Seine is advantageous to its prosperity. The wise enactments of the sage Colbert (1669) promoted greatly its already thriving commerce; but the revocation of the Edict of Nantes annulled their good effect, dispersing its industrious artisans, who settled in Leyden, Norwich, and Leicester. The manufactures of Elbœuf did not recover from this check until the events of 1815, relieving France from the competition of Belgium, gave them so decided an impulse that their produce is now threefold greater than it was then. The value of the cloth made here in one year is estimated at more than a million sterling.

The two Gothic churches of *St. Etienne* and *St. Jean* contain curious painted glass; in the latter is a window presented by the clothworkers' guild somewhere about 1466, in which various implements of the craft, such as shears and teasels, are introduced



The working classes are generally industrious and economical, and are consequently far better off than those of Rouen.

*Steamers* 3 times a-day to Rouen.

L. The *Rocks of Orival*, a range of chalk cliffs beginning at Elbœuf, consisting of detached pinnacles and projecting shelves, formed by the hard flint layers enclosed in the rock, present a singular outline of fantastic forms. On a platform half way up their face, a small chapel has found a niche; it is partly excavated in the rock, so are likewise many small dwellings around it. One of these needles of chalk, called Roche de Pignon, rises 200 ft. above the river. The Rouen Railway crosses the river and an island in the midst of it at an oblique angle near Oissel.

Rt. From Oissel ( $2\frac{1}{2}$ ), marked by its spire, to Rouen the river is thickly set with islands bearing long rows of tall poplars. Beyond (rt.) Authieux the rt. bank rises in tall chalk cliffs, at the base of which, between them and the Seine, runs the road to Paris (R. 9), passing a series of villages and manufactories.

L. St. Etienne de Rouvray,  $1\frac{1}{2}$  Wm. the Conqueror was hunting in the forest of Rouvray, which still exists behind this village, when the news was brought him of the death of Edward the Confessor, and of the usurpation of his throne by Harold, his brother-in-law.

Rt. The high hill of St. Catherine (p. 42) and the spire of the Cathedral are conspicuous long before reaching

2 Rt. ROUEN (Route 8).

## ROUTE 12.

THE SEINE, B.—ROUEN TO HAVRE AND HONFLEUR.

34 leagues= $85\frac{1}{2}$  Eng. m. The distance to Havre by land is 53 m.

*Steamers* daily, in summer, making the voyage in about 8 hours, i. e. a little longer time than the *diligence*.

The opening of the *Railway* to

*Havre* (Route 14) will probably put a stop to the steamers.

The scenery is so pleasing, that notwithstanding the windings of the river, the voyage in fine weather is very agreeable.

The *places* where the steamers stop for passengers are marked by Italics.

The hour of starting varies so as to enable the vessels to meet the flood tide off Quillebœuf, and by the aid of it to pass the shifting sands there. The boats start from the Quai du Havre close to the Hôtel de Rouen. Fare 10 fr., carriages 30 fr.

For some distance below Rouen the river is intersected by numerous islands, long narrow strips of earth planted with willows and poplars: a scene of rich verdure, but somewhat monotonous. The hills near Rouen are dotted with white country houses of its citizens and manufacturers.

Rt. The vale of Bapaume, beset with cotton factories, opens out.

L. Petit Quevilly (3 m. from Rouen). Here is an ancient little chapel of *St. Julien* in the Romanesque style, terminating in an apse having the windows and doors round-headed, built soon after 1162 by our Henry II., who had a hunting seat in the adjoining forest. Though now degraded into a barn, it is an edifice possessing an interest for the antiquary.

Rt. Canteleu, a château of the time of Louis XIV.; its terraces and gardens were laid out by Le Nôtre, but have been modernised.

Rt. Dieppedale, a long row of houses bordering the river.

L. Grand Quevilly once contained a Protestant church (temple) capable of holding 10,500 persons; but in 1685, through the machinations of the Jesuits, it was closed, and a few months after razed to the ground. This act of intolerance was committed shortly before the revocation of the Edict of Nantes entailed persecution and exile on the large and industrious Reformed community which then occupied this district.

L. *Moulineaux* (†), a prettily situ-

ated but poor village, on the high road to Honfleur (Route 23), has a ruinous but interesting church in the earliest pointed style; date the beginning of the 13th century. On the hill above it are some heaps of stone, the very scanty traces of the walls of a *castle* destroyed by King John, which, according to the tradition, once belonged to *Robert the Devil*, a fabulous personage, a sort of Norman Blue Beard, who murdered his friends and mistresses, and in the end sold himself to the evil one. Some suppose him to have been Duke Robert, the father of William the Conqueror.

L. Near *La Bouille* and Caumont are extensive quarries of building stone. Bare yellow cliffs line the river for some distance.

Rt. St. George de Boscherville. This famous abbey stands at some distance from the Seine, near the Havre road (Route 13), and is only just visible from the river.

The Seine makes a bend 18 m. long between Rouen and this point; in a direct line they are not more than 10 m. apart.

Rt. *Duclair* (5½), a pretty village traversed by the road to Havre (Route 13), squeezed in between the river and the rocks, one of which, an elevated crag, goes by the name of *la Chaire de Gargantua*. The rt. bank again sweeps round to the S., its elevated slopes covered with hanging woods.

Rt. It is recorded that at the little hamlet of Mesnil, Agnes Sorel, mistress of Charles VII., breathed her last, in the arms of the king. An old building is still pointed out as her abode; it retains its chimneys of the 15th century. It was called Mesnil la Belle; it is now a labourer's cottage. The l. bank below Mesnil has risen into round hills of considerable height, part bare, part wooded; houses few, and scenery solitary. To this succeeds on the rt. a plain, verdant and bosky, formed into a peninsula by the winding river, out of the midst of which rise the now spireless twin towers of Jumièges Abbey (p. 57).

L. The *Château de Mailleraye* (7½), situated at the water's edge, below the village of Guerbaville, where there is a large ship-builder's yard, belongs to the Duc de Mortemart. It is an edifice of the 17th century, in a park surrounded by green walls of straight clipped trees, and is a conspicuous object from the river, but not otherwise worth notice.

Below Mailleraye the river expands considerably, and its channel begins to be beset with the sand-banks which render its navigation so difficult, leaving only a narrow passage in the middle free.

Rt. *Caudebec* (2¼), the most considerable and prettily situated town on the banks of the Lower Seine; its long terrace of houses screened by an avenue of green trees, and surmounted by its elegant church spire, was a favourite subject of the landscape painter Vernet. It is described at p. 58.

Rt. A humble structure at the foot of the steep wooded heights below Caudebec, is the chapel of Notre Dame de Barre-y-va, much resorted to by sailors, who have covered its walls with ex-votos, paintings, models of ships, &c. The name probably comes from the circumstance of the much-dreaded Barre, or Bore, at the mouth of the Seine, ascending at times thus far.

Rt. *Villiquier*, prettily placed, and forming an agreeable intermixture of trees and houses surmounted by a Gothic spire, is a fishing village and station of the pilots, whose duty it is to carry vessels between this point and Mailleraye.

L. Vatteville la Rue.

The Seine, which has run nearly due S. from Caudebec, resumes its proper direction from E. to W. below Vieux Port, and preserves the same as far as its mouth. Its banks, retiring to a considerable distance from each other, allow it to expand into a wide but shallow estuary, frequently enlivened by large shipping, tug steamers (remorqueurs), &c.

L. *Quillebœuf*, an important town



and small seaport which Henri IV. wanted to convert into a fortress, but which his widow Marie de Medicis dismantled, is built on a projecting promontory, at the extremity of which stands its massive church tower and light-house. It is the station of the pilots to the number of 110, with 28 apprentices (aspirants), whose duty it is to carry vessels through the intricate navigation of the mouth of the Seine, from Havre and Honfleur up to Villiquier.

This is the most difficult and dangerous portion of the whole river for vessels, on account of the sunk rocks and shifting sands, only to be passed during high tide. Shipwrecks occurred here almost every year before the introduction of steam towage, which, by enabling vessels to pass up, even when the wind is unfavourable, has diminished the delay and risk. So variable are the sand-banks off Quillebœuf that they have been known to change their position more than a league in the course of twelve months: this indeed occurred in 1840. The cause of this must be looked for in the sudden contraction of the river at this point to about  $\frac{3}{4}$  m., while a little below it is 3 m. wide. The consequence is that the vast mass of water poured into the Seine by the rising tide forms capricious and powerful currents, and very commonly enters the river in the form of a lofty wave or wall of water 3 to 6 ft. high, here called the *Barre*, and similar to the *Bore* at the mouth of the Severn. It stretches across from one bank to the other, marked by a line of white foam, sweeping all before it with a roar like thunder, heard forty minutes before it arrives. It seems to acquire the greatest force abreast of Quillebœuf, where it dashes over the quays, hurling vessels against them, and sometimes injuring the buildings, but it is perceived as high as Caudebec.

The still water produced at the point where the rising tide encounters the descending current, allows the sand and mud, carried along by the

river when in rapid motion, to fall to the bottom, and accumulate into shifting deposits of sand. Among these sand-banks the "Télémaque," a vessel said to have been laden with property belonging to émigrés, and with jewels of the Bourbon princes, was lost at the time of the Revolution. A recent attempt to raise the hull failed.

Rt. Through the vista of the valley of the Bolbec, which opens out opposite Quillebœuf, a glimpse is obtained of the castle towers of *Lillebonne*, celebrated for its remains of a Roman theatre (p. 59).

Rt. The opening of another small valley is marked on one side by a conspicuous conical white rock called Pierre Gante (? Géante), overhanging the Seine at a height of 200 ft., and on the other by the *Castle of Tancarville*, the venerable stronghold of the chamberlains of the Dukes of Normandy, planted on a pedestal of high cliff forming part of the headland called Nez de Tancarville. To the water-side it presents an open terrace, on which stands a modern mansion, with sash windows and a tall watch-tower, round on one side, and angular like a bastion on the other. Behind stretch two long lines of varied and stately towers connected by curtains forming a large triangular enclosure, once the castle courts, now grass-grown and encumbered with ruins. The country behind it is one dense forest, over which these ancient battlements peer majestically. The best-preserved portions are the gatehouse with caged windows, and grooves for double portcullis, and the contiguous tower dating from the latter half of the 15th century. Here, within walls 9 ft. thick, may be seen the "cachots"—and the "chambre de question" which is frequently mentioned in the old archives. In the corner tower (L'Aigle), on the brow of the cliff overhanging the Seine, one or two old wall pieces, so constructed as to be loaded from the breech, are preserved. In this part only of the old

castle do roofs and floors remain. All the rest is mere shattered walls, gutted towers, enclosures dark and overgrown with nettles and hemlock, which now luxuriate on the hearths of the Tancarville, Montmorencys, Harcourts, and La Tour d'Auvergne, its ancient owners. The chapel and the Salle des Chevaliers, with 3 fire-places, are pointed out to strangers. The loftiness of some of the towers, and their singular form, deserve notice: the Tour de Lion is the segment of a circle; the Tour Coquisart, 60 ft. high, of 5 stories piled one over the other, and still surmounted by the stone-groined ribs of its roof, while all the rest is fallen, is in the shape of a triangle with curved sides. It communicates behind with the *Donjon*, which was detached from the body of the place and entered only by a drawbridge. It contains a well 300 ft. deep. The date of its construction is the early part of the 15th century, and scarcely any portion of the castle seems older. The English under Henry V. burned down the preceding one 1437. The modern mansion is tumbling to pieces as fast as possible. From the noble owners, whose names are mentioned above, Tancarville fell into the hands of Law of Lauriston, the South Sea schemer. It was plundered and demolished at the Revolution as the property of aristocrats and émigrés (the Montmorencys), but after having been for 20 years attached to a hospital at Havre, it has once more reverted to that family. The poor small hamlet of fishers' huts beneath the castle affords no tolerable accommodation for travellers. The distance from Lillebonne is 6 m. and from St. Romain on the road to Havre (R. 14) about 12 m.

Below this the banks of the Seine are too distant and destitute of objects of interest to need further notice, excepting the towns and ports of

Rt. HARFLEUR, in R. 14.

L. *Honfleur*, described in R. 23.

Passengers can be put ashore here,

where they can take the *diligence* to Caen. It is about 7 m. across to Rt. HAVRE, in R. 14.

### ROUTE 13.

ROUEN TO HAVRE—LOWER ROAD, BY ST. GEORGE BOSCHERVILLE, JUMIÈGES, —CAUDEBEC, AND LILLEBONNE.

86 kilom. = 53 $\frac{1}{4}$  Eng. m.

*Diligences* daily in 7 hours.

Although the *Railroad* from Rouen to Havre (Route 14) is the quickest way, yet the following route is one of the most agreeable in Normandy, both for the pleasing view of the Seine which it commands, and for the succession of ancient ecclesiastical remains in the vicinity of which it passes. It is, however, hilly. A little way beyond the industrious cotton-spinning village of Bapaume, it surmounts the long and steep hill of Canteleu, from whose top Rouen is seen to very great advantage, and the Seine winding away S. to double the ridge of which the hill of Canteleu forms a part. On the l. is the Château of Canteleu, belonging to M. Elie Lefebure, which commands the view in perfection, and about 2 m. beyond it a road turning off to the l. leads to the *Abbey of St. George de Boscherville*, whose *Church* is one of the most ancient and unaltered monuments in Normandy. It was founded by Raoul de Tancarville, chamberlain of the Conqueror, previous to the Conquest, and consecrated in the founder's presence. From the precision with which its age is fixed, it has been termed "a land-mark of Norman architecture;" as usual, it was destroyed at the Revolution, but the church was preserved for the use of the parish. It has the usual characteristics—vast proportions, simplicity, and austere grandeur. Its W. end has a round door ornamented with 5 mouldings and 2 side towers, in whose upper story the pointed arch of a very early date appears. This may have been the part of the church last finished. The vaulting of the nave and transepts is



also pointed, all the rest is Norman; the arches are carried round the ends of the transepts, forming 2 lofts or tribunes supported on a column, and there is an apse at the E. end of each, as in Winchester Cathedral, the older part of which is very like this church. The *Chapter-house* adjoining is of later date, 1157, and of mixed architecture, both round and pointed arches occurring in it. The capitals of its columns, sculptured with subjects in relief, such as the Passage of the Jordan and the Sacrifice of Isaac, merit notice.

Returning to the high road you descend to the borders of the Seine, on which is situated the village and post station.

20 Duclair (6 m. from St. George's), a row of houses between the river and the cliffs, one of which, from a supposed resemblance to a pulpit, is called *Chaire de Gargantua*.

The Seine once more takes a widely curving sweep, while the high road cuts across the neck of the peninsula. In the midst of this the twin towers of the *Abbey of Jumièges* are conspicuous. A cross road turns off to it near Yainville, whence it is about 2 m. distant. It was the most important monastic institution on the banks of the Lower Seine for its extent, the number of its inmates, and its share in promoting learning during the dark ages, and it now towers venerable and majestic above the humble timber-framed and chalk-walled cottages of the village. It has been compared with some of the Romanesque churches of the Rhine in its plain but stately W. façade, surmounted by octagonal towers which have only recently lost their spires, but between them the porch projects in an unusual manner. This and the entire nave as far as the cross, surmounted by a more massive central tower, one side of which only remains standing, is of unchanged early Norman (date 1067). The round arches are supported alternately on square piers and circular columns; their ca-

pitals, destitute of any sculpture, were ornamented with painted foliage, some traces of which still remain. The interior is in a state of ruin, entirely roofless save a small fragment of vaulting in the aisles, and open to the rains of heaven; greensward supplies the place of pavement; the E. end, which was in the pointed style of the 13th century, has been razed to its foundations. For the origin of this dilapidation the Revolution has to answer, but its consummation is of very recent date, this ancient and interesting fabric having been absolutely quarried, and carted away to build barns with its masonry. The stone employed is a hard chalk enclosing flints, which are frequently exposed in the courses of the piers. The present owner fortunately has respect for the ruins, and watches over their preservation, having fitted up the old gatehouse for his residence. A number of curiously and rudely sculptured fragments, keystones, bas-reliefs, &c. have been discovered by him, and merit notice. Beneath a plain black marble slab, fractured into several pieces and lying in a corner, was once deposited the heart of "Agnes Seurelle (Sorel), Dame de Breauté." She died near this at Mesnil (p. 54), and Charles VII., her royal lover, had apartments fitted up in the abbey in order to be near her. She was a benefactress to Jumièges, and the monks retained her heart, though her body was interred at Loches in Touraine. Breauté was the name of one of her domains; some have read the inscription erroneously "Dame de *Beauté*." Here also another mutilated monument has been brought to light. It consists of mutilated effigies of youths in royal garbs, with circlets on their heads, known by the name of "*les Enervés*" (i. e. the hamstrung), from a tradition that they represent the two sons of Clovis II., who, having rebelled and waged war against their father, suffered the cruel punishment of having the sinews of their

arms and legs cut. They were then bound and set adrift in an open boat on the Seine, whose current wafted them down as far as Jumièges, where they were kindly received by the monks and ended their days. On the S. side of the church are remains of the chapel of *St. Pierre*, a pointed work of the 14th century; and of a large vaulted apartment called "*Salle des Gardes de Charles VII.*," parallel with which runs a very extensive range of subterranean vaults, probably cellars, and the gatehouse.

---

The high road beyond Yainville and Le Trait is carried on a lofty terrace along the shoulders of the hills, commanding a most pleasing view of the windings of the Seine both upwards and down. Nearly in front the intervening slopes are covered with orchards and gardens, and on the opposite bank stands the *Château of Mailleraye*, a conspicuous and large edifice (see p. 54). At the little village Caudebecquet, about 3 m. before reaching Caudebec, a road turning to the rt. leads in  $1\frac{1}{2}$  m. to another monastic ruin, of inferior interest to the other two, but of great antiquity, *St. Wandrille*, founded by the saint of that name in the 7th century, and at first called Fontanelle. Here may be seen some elegant pointed arches, sole relics of a church sold and pulled down at the Revolution for building-materials. The conventual buildings, a palace in extent, are in the modern Italian architecture of the 16th or 17th century, and have been converted partly into a manufactory of *Jacquerie*, partly into a bark warehouse and mill. The *Cloisters* behind them contain several arches, rich *morceaux* of flamboyant Gothic, and a Lavatory, with a few relics of sculpture, becoming fewer every day through wanton mutilation. Part of the Refectory is Norman, and lined with a circular arcade.

The good judgment of the monks is very conspicuous in the choice of

the site for this convent, a nook shut out from the world in a side valley of the Seine, fertile, well watered, and wooded. *St. Wandrille* now stands a monument of the fall of ecclesiastic pomp and wealth. The hill side to the N. was terraced to form gardens and shady walks, now grown wild. On the top of the height above them is a little chapel of *St. Saturnin*, an early Norman structure, with 3 apses and windows like loop-holes and walls of herring-bone masonry, many centuries older than any part of the convent below. *St. Wandrille* is about 4 m. from

16 Caudebec.—*Inns*: Poste, — H. du Commerce, not very clean, but tolerable. This is one of the prettiest little towns on the Seine, with its quay and terrace along the water side, shaded by trimmed elms, forming a screen before the row of houses which face the river. In its outskirts, the hills are dotted with neat villas and country seats. Its only remarkable edifice is its *Church*, a beautiful Gothic building in the florid style of the 15th century, in the form of a parallelogram without transepts. It is surmounted by a tower having a short steeple of open stonework, the flamboyant tracery in it taking the form of fleurs-de-lis. Its flying buttresses and variously patterned parapets are very elegant. It was begun 1426, and stands at the side of the church. In the W. end, the gorgeous triple *portal*, with side porches bent back, all exuberantly ornamented with carved foliage, statues, and niches, and the rose window above, merit notice. Also the N. porch.

Within, there is much fine painted glass of the 16th century, and a wooden cover to the font, well carved in relief with subjects from the life of Christ. The spaces between the buttresses are occupied by small chapels; those at the E. end expand, and the central one, the Lady Chapel, behind the high altar, is distinguished by a finely groined roof, the ribs of which descend in the centre to form a *pen-*



dant of stone 14 ft. long, ending in a carved boss, or cul de lampe. In the next chapel of St. Sepulchre is a group of 8 figures as large as life, representing the holy personages at the tomb of our Lord, under a florid Gothic canopy. The master mason of the church, William Le Tellier, is buried in the Lady Chapel: he was employed on it 30 years, down to his death 1484, and in that time completed the upper part of the nave, the choir and chapels around it, including the Lady Chapel and its pendant.

The artist will find, in penetrating the dirty streets of the town, some picturesque bits among its timber-framed houses.

Caudebec was anciently a strong fortress; it was taken 1419 by the English under Talbot and Warwick, and during the wars of religion Alexander Farnese, Duke of Parma, commander of a Spanish force, sent in aid of the League, lost his arm in reconnoitring the ramparts, 1592. They have been long since swept away.

About  $1\frac{1}{2}$  m. up the valley, near the road which goes to Yvetot (R. 14), stands the *Church of St. Gertrude*, repaired 1841: it merits notice for its architecture, Gothic of the 16th centy., its stone tabernacle, and painted glass.

The Havre road beyond Caudebec quits the borders of the Seine, not to rejoin it until Harfleur is passed. It mounts a steep ascent and traverses a part of the table-land of the Pays de Caux. There is nothing of interest until you descend into the valley where lies the town of

16 Lillebonne (*Im.*: H. du Commerce), numbering 3500 inhab., prettily situated on the stream of the Bolbec, and interesting on account of its Roman theatre, a relic of the ancient *Julia Bona* of the itineraries of Antonine and Ptolemy, capital of the *Caletes* (inhabitants of the Pays de Caux), of which the present town occupies the site and retains (with a slight change) the name. The road,

on entering the town, passes under the *old Castle* on the rt., and nearly over the space which must have anciently been the stage of the *Theatre*. On the l. hand is seen the semicircular portion allotted to the spectators, for the most part cut out of the hill, which, forming a gradual slope for the rows of seats to rest on, saved the cost of vast substructions; an advantage of which the Romans and Greeks usually availed themselves in their theatres. The remains consist chiefly of foundations, and have been laid open since 1812. The fragments of walls in the centre belonged probably to the orchestra, those on the slope of the side to the dressing-rooms. On the hill, among fragments of masonry, are several semicircular terraces one above the other, with traces of the vomitories, or entrances, and round the whole runs a corridor or vaulted passage gradually rising from the side to the centre, by which entrance was obtained to the highest seats. The walls and part of the vaults here remain tolerably perfect; they are supported by many spurs or buttresses. The walls are faced with ashlar masonry, or with small stones about the size of bricks neatly jointed, the centre filled in with rubble of flint strongly cemented with grouting, the whole banded together at irregular intervals by horizontal courses of red tiles. The stone employed is a porous but coherent calcareous tufa, or travertine, which is to this day deposited by the water of a neighbouring brook.

This is the best preserved, and indeed almost the only example of an ancient theatre in the N. of France, or of Europe. It measured across the chord of the arc 300 ft., and the dimensions of the circular corridor were 625 ft. The ground in and about the town can scarcely be turned up without disclosing ancient remains of one sort or another. In 1823 a fine bronze male statue (now in the British Museum) was discovered; and

the Museum at Rouen has been greatly enriched from this mine of antiquities.

On the opposite side of the high road looking down upon the theatre is the *Castle*, a picturesque ruin, historically interesting as the residence of Wm. the Conqueror, who here called together his barons to unfold the momentous scheme of the invasion of England. The massive outer walls now serve to enclose a garden, and modern house, the residence of the present proprietor; close beside it is a tall round tower of beautifully even masonry, having walls 13 ft. thick, and some finely ribbed vaults; isolated by a deep fosse, crossed by a drawbridge. It is a construction of the 15th centy., built probably by the Harcourts, who owned the castle down to the Revolution. Not far off is a mutilated angular tower of the 13th or 14th centy. The Norman part consists of the great hall, now in utter ruin, its walls of rubble faced with free stone: its round-headed windows, towards the court, are supported by a pillar in the centre, with recessed pillars in the sides in the style of the 11th centy. In this hall, according to the tradition, William met his barons in council. The commanding elevation of these ruins gives them a magnificent view over the adjacent valley, with a peep, through a gap at its extremity, of the broad estuary of the Seine 3 m. below the town.

The *Parish Church* has a fine tower and spire, similar to that of Harfleur, but inferior, and a rich portal.

Owing to the abundant supply of water from the neighbouring hills, Lillebonne has become a manufacturing town, and cotton mills have multiplied considerably about it, especially up the valley towards Bolbec; calicos and indiennes are principally made here.

The *Castle* of Tancarville (Route 12) is 6 m. distant from Lillebonne, by cross roads, the latter part so narrow and steep as to be practicable only for a light carriage. A cabriolet

may be hired for 12 fr. to go thither, and on to St. Romain on the Havre road (p. 55), waiting to allow the traveller to see the castle. The direct road from Lillebonne to Havre passes within 3 m. of the castle: the diligences go round by Bolbec. (Route 14.) Both roads meet at

18 La Botte.

In descending from the Plain de Caux towards

*Harfleur*, a fine view is obtained of that town, its noble spire, and the Seine beyond. The road hence to

17 HAVRE is described in Route 14.

## ROUTE 14.

### ROUEN TO HAVRE—RAILROAD.

95 kilom. = 59 English m.

4 or 5 trains daily, in  $2\frac{1}{2}$  and 3 hrs.

This line was opened 1847. Its engineer is Mr. Jos. Locke, and its construction is almost entirely due to English skill, enterprise, and capital.

It is carried, for the most part of the way, over the high and fertile table-land of the Pays de Caux.

It quits the line from Paris to Rouen (Route 8) at Sotteville, and, a little above the town of Rouen, crosses the Seine by a timber bridge of eight arches, each 131 ft. span, its centre resting on an island.

In a hole cut in the chalk, shut in by escarpments which exclude all view of the town, lies the

ROUEN Station, in the Rue Verte (built by *Tite*, architect of the Royal Exchange). In order to reach it, the Railway is carried through 3 tunnels and by a viaduct over the streams of the Robec and Aubette, in the valley of Darnetal. The first *tunnel*, carried under part of St. Catherine's Hill (p. 42), is 1133 yds. long. It describes a radius of about half a mile; the works were very difficult, owing to the rush of waters from springs in the chalk. The line sweeps round the Boulevards of Rouen and passes a second tunnel of 1530 yards, near St. Hilaire, and after penetrating beneath the suburbs of



St. Hilaire, Beauvoisine, and Cauchoise, in a series of cuttings and tunnels, works of arduous execution and great engineering merit, made at great cost, emerges near the village of Déville.

6 Maromme Stat.

Even after Rouen is a long way left behind, the country traversed by the road exhibits the vivifying effects of the cotton industry, in mills or factories, country-houses, villages, &c. The chief of these is Déville, situated in a pretty valley which bears its name.

3 Malaunay Stat.

Here is a viaduct of 8 arches, and an embankment over the Dieppe road. Near this the branch railway to Dieppe (Route 6) diverges.

A 4th tunnel, nearly 1 m. and 3 fur. long, pierces the heights of Piccy-Poville, and the railroad crossing the high grounds is carried across the valley of

8 Barentin—Stat.

The curved viaduct of Barentin, of 27 arches, each 60 ft. span, the central arch 108 ft. high, 765 yds. long, was constructed by Messrs. Mackenzie and Brassey. It gave way in the early part of 1846, covering the valley with rubbish. It was reconstructed in the short space of 6 months, at great cost, with the utmost care and solidity, but this accident retarded the opening of the line.

Barentin is a town of 2500 inhab., in a small valley on the stream of the Austreberthe, which sets in movement many cotton-mills; the railway leaves it on the l. The railway has now emerged by gradual ascents out of the basin in which Rouen lies, to the table-land of the Pays de Caux, an elevation of about 400 ft.

2 Pavilly Stat.

11 Motteville Stat.

8 Yvetot (Stat.) is an industrious little town, of 9032 inhab., with houses of timber, containing some manufactures of cotton, but destitute of objects of interest. The title of "Roi d'Yvetot" has given a wide

celebrity to its name, and has greatly puzzled antiquaries and local historians, who have failed in proving the existence of any sovereign authority, or in discovering the origin of the title.

There is a tradition that one Gauthier, Lord of Yvetot, having offended King Clothair, son of Clovis, and having been banished his presence, ventured to throw himself at the feet of the king while he was kneeling in prayer before the high altar at Soissons on Good Friday, thinking that the holiness of the place, and of the day of pardon for the sins of mankind, might obtain forgiveness for him also. Clothair, however, no sooner saw him than he drew his sword and slew him, but repenting afterwards of his crime, and desiring to make atonement to Gauthier, created his heirs kings of Yvetot. But this story has no good foundation. Beranger describes the king of Yvetot:—

" Il était un roi d'Yvetot,  
Peu connu dans l'histoire,  
Se levant tard, se couchant tôt,  
Dormant fort bien sans gloire,  
Et couronné par Jeanneton  
D'un simple bonnet de coton."

Here, in the very heart of the Pays de Caux, the traveller will now in vain look for the Cauchoise head-dress, once commonly worn by the women. It was a huge structure of cambric and lace, something between a cap and a helmet, and appears to have been the fashion even in England during the 15th and 16th centuries. The modern modes of Paris have driven it out of the field, even in remote Norman villages, and it is now rarely seen.

The *Pays de Caux*, through the centre of which the railroad runs, retains the name, slightly altered, of its ancient inhabitants in Cæsar's time, the Caletes (? Celts). It is a high table-land, only here and there intersected by river-courses, exceedingly fertile, though somewhat arid. Trees are rare on the high ground, except the usual avenues of fruit trees on the

road side, and around villages and farm-houses, whose existence and position is invariably denoted by a sort of verdant rampart of stiff elms, planted in straight lines and double rows, on or near a high bank of earth; you may be sure that a farm or château is hid behind such an enclosure.

11 Alvimare Stat.

8 Nointot Stat. About 4 m. S. of this is Bolbec, a fresh-looking town of staring brick houses, which replace those of wood destroyed by a great fire in the last century: situated in one of the pleasant little valleys which intersect the Pays de Caux. It contains a vast number of cotton-mills, manufactories of calicos, printed stuffs and handkerchiefs; printworks, bleaching-grounds, &c.; in short, it is one of the most industrious places in the Dépt. of the Seine Inférieure, 9630 inhab. The abundant stream which runs through it, and is a main cause of this activity, turns no less than 113 usines before it joins the Seine below Lillebonne. That ancient town (see Rte. 13) is only 5 m. distant; its Roman Theatre merits notice.

Bolbec lying in a depression of the table-land, high embankments and a viaduct were required to carry the railway across it.

At Mirville is a brick viaduct of 48 brick arches, the highest 106 ft. above the ground. Hence there is a steep incline (requiring an extra engine to surmount in coming from Havre) by which the railway descends nearly to a level with the Seine at

6 Beuzeville Stat. (Fécamp).

8 St. Romain Stat.

HARFLEUR (Stat.) is situated on the Lézarde, a small stream now barely navigable for barges, and 2 m. distant from the Seine, yet Monstrelet calls it "le souverain port de la Normandie." The deposits brought down by the Lézarde have contracted its bed, and formed a fringe of land along the shore of the Seine, which has

greatly increased the distance between the town and the estuary. Before the rise of Havre, Harfleur was the chief port of the mouth of the Seine, at which the wool of Spain and Portugal was imported and sent up to Montevilliers to be wrought, while by reason of its fortifications it was the key to the entrance of the Seine. In 1415 it resisted for 40 days the besieging army of Henry V., who, as soon as it had yielded, uncovered his feet and legs and walked barefoot to church to say his prayers, after which he collected the inhabitants to the number of 8000, and turning them out of their houses with only the clothes on their backs, banished them and confiscated their property, substituting English colonists in their place. In 20 years, however, the town was surprised by a band of peasants, aided by a number of the former inhabitants, and the English were expelled. The tower and spire of its *Church*, built in the 15th cent., it is said, by Henry V., and its fringed S. portal, are deservedly praised as masterpieces of Gothic architecture.

The *Terrace* of the *Château of Orcher*, running along the heights above the town, commands a remarkably fine view of the river.

From Harfleur to Havre the railroad is carried along the side of a hill, sloping gently down to the Seine, whose embouchure is seen at intervals between the trees and houses. On the rt. a little above the road stands *Graville*. Its small church, prettily situated on a wooded bank, is Norman of the end of the 11th century. Its transepts are decorated externally with round intersecting arches, surmounted by figures of animals. The capitals of the pillars in the nave are sculptured with monsters. In the courtyard behind the Hôtel de Ville are caves in the rock, once the monks' cellars. The church was built in honour of St. Honoria. Her relics were removed for safety, at the Norman invasion, to Conflans, and



confided to the custody of the monks, who, when the danger was overpast, refused to restore them. Notwithstanding this loss, the place where they *had been* retained its sanctity, so that more pilgrims and worshippers repaired hither than to the church at Conflans which actually held them! Remains of the masonry of a quay, with rings to attach vessels, are said to have been found under Gravelle.(?)

Passing numerous gardens and country houses, intermixed with inns, taverns, and guinguettes, composing the towns of Gravelle and Ingouville, so numerous as to form an uninterrupted street, we reach

7 *Havre Terminus*, close to the Cours Napoléon, and not far from Bassin Vauban. It covers 36 acres.

HAVRE.—*Inns*: *Frascati*, an excellent modern hotel, outside the walls, on the seashore, with a good table d'hôte, reading-room, and neat and cheap warm-baths; much resorted to by sea-bathers in summer:—*Wheeler's*, an English house, on the Quai Notre Dame:—*Hôtel de l'Amirauté*, on the Grand Quai:—*Hôtel de l'Europe*, in the Rue de Paris.

Havre, originally Havre de Grace, from a small chapel of Notre Dame de Grace, which stood on its site, the port of the Seine and of Paris, one of the most thriving maritime towns of France, is situated on the N. side of the estuary of the Seine, and contains 28,000 inhab. It is quite a modern town, owing its foundation to Francis I. (1516), and its prosperity to the judicious enactments of Louis XVI., though it has received its great impulse since the war, and has been rapidly gaining upon its elder rivals, Bordeaux and Nantes. It has no fine buildings nor historical monuments; its streets are laid down chiefly in straight lines, and at right angles with one another, and they are grouped round the basins, or docks, which communicate from one to the other by lock-gates, and are placed so as to form a triangle entered from the outer (avant) port. The quays bordering

on the basins, lined with vessels, and choked up with cotton-bales, sugar-casks, &c., are the chief scenes of life. The strange cries and glittering plumage of parrots and macaws will remind the stranger of the connexion of the port with tropical countries. Its principal street (and it is a handsome one) is the Rue de Paris, extending through the Place du Spectacle from the Port d'Ingouville to the round tower of François Premier, at the entrance of the port, the only relic of the fortifications constructed by that monarch.

Great improvements are now in progress here. The old ramparts are to be removed, and Havre, Ingouville, and Gravelle, containing a population of near 70,000, are to be united into one, and to be surrounded by new and more extensive fortifications. The Citadel, built by Richelieu, in which Cardinal Mazarin shut up, in 1650, the leaders of the Fronde, the Princes of Condé, Conti, and Longueville, "the lion, the ape, and the fox, caught in one trap," to use the expression of Gaston of Orleans, has been dismantled. The release of these distinguished captives was at length effected (Feb. 1651) by one of those sudden popular risings so common in the history of the Fronde. Mazarin, prostrated from the height of power by this revolution, bethought himself how he might make friends of his former victims, and, disguised as a courier, posted off instantly from Paris, in order to be the first to tell the joyous news, and unlock the prison gates. Assuming an air of the most obsequious servility, he assured them he had no hand in their imprisonment, and stooped to kiss the boot of Condé as the hero mounted his carriage, amidst salvos of artillery, on his way to Paris.

It is only by aid of a reservoir of water (*Retenue de la Floride*), regulated by sluices, that the mouth of the harbour, formed in the flat alluvium of the Seine, can be kept clear from the deposits of the river still in progress. The port is accessible for

vessels during only four hours each tide; at low-water the port and avant-port are left dry. The three old docks are capable of containing 250 or 300 vessels or more with inconvenience; the fourth dock, the new Bassin de Vauban, the largest of all, situated outside the walls, and finished 1842, is a magnificent work, with a fine masting-machine and warehouses.

A 5th dock, destined for steamers, has been constructed at the extremity of the Retenue de la Floride.

The saying of Napoleon, that "Paris, Rouen, and Havre formed only one city, of which the Seine was the highway," explains the cause of the prosperity of Havre. It is the place of import of all the foreign articles needed for the supply of the French metropolis: like Liverpool with us, it is the chief *cotton port* of France, furnishing this commodity to the manufacturer of Rouen, Lille, St. Quentin, and from these cities it again receives the manufactured goods for exportation.

It is also the point of communication between the Continent of Europe and America; a great trade is carried on with the United States. The Declaration of Independence formed the groundwork of the present good fortunes of Havre. A line of Government steam-packets is established to run regularly 4 times a month to New York. Here also a great number of emigrants, many from Germany, annually embark for the New World.

The imports of Havre, though only one half in quantity and weight of those of Marseilles (the chief seaport in France), are said nearly to equal them in value. The number of vessels belonging to the port is 436. More than a million tons of shipping enter in and out yearly. Some of the principal mercantile houses here are English and American.

The ship-builders of Havre enjoy a high reputation for the skill and science which they display in the

construction of their vessels, which are capital sea-boats, yet their shipyards are nothing more than an open space on the sea-beach, outside the fortifications, fenced in with a wooden paling.

The annals of Havre are connected with the history of England at several points. Henry of Richmond embarked here, 1485, for Milford Haven and Bosworth Field, backed by 4000 men, furnished by Charles VIII. to aid his enterprise. The town was delivered over to the keeping of Queen Elizabeth by the Prince de Condé, leader of the Huguenots, 1562, and the command of it was intrusted to Ambrose Dudley, Earl of Warwick; but the English were ejected within a year, after a most obstinate siege, whose progress was pressed forward by Charles IX. and his mother, Catherine de Medicis, in person, sensible that the possession of Havre by the English would be a thorn in the side of France. Hatred of the English, indeed, had united all parties in France against them. The Protestant Condé served in the besieging army, which was commanded by the Constable Montmorency, previously the ally of the English. Warwick held out against vastly superior numbers, until his force was reduced by slaughter and the plague from nearly 6000 to 1500; he was himself shot in defending a breach, after which the place surrendered.

The fleet of William III., which had failed before Brest, made an ineffectual attempt in 1694 to bombard the town, as it had before done in the case of Dieppe with success. In 1796 Sir Sidney Smith, while cruising in the Channel, endeavoured to cut out a French ship of war from under the batteries, but became entangled in the currents and sandbanks of the Seine, and his vessel, having been perceived next morning lying high and dry, was captured by some gun-boats, and he was sent a prisoner to the Temple in Paris.

Bernardin de St. Pierre, author of



"Paul and Virginia," was born here in a house No. 47, Rue de la Corderie. Havre is also the birth-place of Mademoiselle Scudery, 1697, and of Casimir Delavigne.

There is an *English Chapel* in the Rue d'Orléans; service at 12 and 3½ on Sundays.

The *Cercle du Commerce* is a large commercial club-house, furnished with almost all the European newspapers and many American: strangers can be introduced to it by members.

The *Theatre* in the Place Louis XVI., or du Spectacle, at the extremity of the Bassin du Commerce, is one of the most striking buildings in the town.

Baths.—*Frascati*, on the sea-shore, not far from the pier, contains good hot and cold sea-water baths. In summer, bathing is carried on in the open sea. Cabinets are provided for dressing and undressing, and men and women bathe together, but covered up in bathing dresses. There are no bathing-machines; ladies are led out to a sufficient depth of water by the guide, who then seizes them by the shoulders, lays them on the surface of the water, and dips them by sousing their heads under water.

*N.B.* The draught of the tide is so strong as sometimes to overpower even skilful swimmers. The bathers may hold of ropes attached to posts, to prevent their being swept away in stormy weather.

British travellers to Havre need not procure *Passports* in England, as they are permitted to land at that port without them. They are to be obtained immediately on landing from Her Majesty's Consul, who has made arrangements for their delivery in time for the first train after the arrival of the steamers. These passports are countersigned gratis at the

*Bureau de Police*, Hôtel de Ville, at the corner of the Place François I., not far from the old round tower. The office is open at 8 o'clock a.m.

The *Custom-house*, corner of Quai Notre Dame and Grand Quai (en-

trance in Rue de la Gaffe), opens at 8—12, and 2 p.m.—5. After the baggage has been examined (see INTRODUCTION), the dues for the harbour on the landing, and for portage, are fixed by and paid to an Englishwoman, who manages this department of the establishment.

*Poste aux Lettres*, Place Louis Seize.

*Consuls* reside here from Great Britain and from other maritime states of Europe and America. (*Passports* may readily be obtained from Mr. Featherstonhaugh for 5 frs.)

*Railway to Paris* (p. 63, 60).

*Diligences* (offices, Rue de Paris, 49 and 101) to Rouen by the lower road (R. 13), the scenery of which is highly pleasing, but of course the travelling is more tedious than the Railway.—To Dieppe by Fécamp daily, in 9 hours (R. 18); to Caen (starting from Honfleur on the opposite side of the Seine) daily.—(Route 23.)

*Steamers* go to Rouen daily in 8 or 9 hours; to Caen daily in 4 hours (see R. 24); to Honfleur twice a day in ¾ of an hour (R. 23); to Cherbourg twice a-week; to Morlaix in Brittany in 18 hours, every Saturday; to Bordeaux once a fortnight, 1st place 80 fr., 2nd, 50 fr.; to Nantes; to London 4 times a-week, to Southampton daily (in summer); to Brighton twice; Dunkirk, Rotterdam, and Hamburg twice a-week; to Amsterdam; to St. Petersburg and Copenhagen twice a month. More than 40 steam-vessels, including tug-boats, belong to the Port du Havre.

The antiquarian and architect may visit the Norman Church of Graville, 2 m. on the Rouen road (p. 62).

Those who have an hour or two to spare at Havre cannot better employ it than in ascending the hill of *Ingouville*, a town of 12,000 inhab., separated from Havre only by the gate, consisting chiefly of neat country-houses with gardens. The view from the top, over the town of Havre, its forest of masts rising from amidst

its buildings, over the embouchure of the Seine, the distant hills of Calvados appearing on the horizon like an island, and over the heights of La Hève to the rt. (N.), crowned by its twin lighthouse — is very striking and pleasing.

The chalk cliffs under the lofty headland of Cap la Hève, on which the lighthouses are erected at a height of 300 ft., offer some fine rock scenery; but, except when the tide is low, the shingly beach is not favourable for walking. These rocks were the favourite haunt of the author of "Paul and Virginia."

### ROUTE 18.

HAVRE TO DIEPPE AND ABBEVILLE BY  
FÉCAMP AND EU.

171 kilom. = 106 Eng. m.

*Diligence* daily to Dieppe in 9 hours.

At Harfleur (p. 62) we turn out of the Rouen road, and ascend the pretty green valley of the Lézarde to Montivilliers, agreeably situated, with many trees about it, and containing some picturesque wooden houses. Its *Church* belonged to a once famous abbey of Benedictine nuns founded in the 7th cent. It is in the Romanesque style of the 11th cent., except the N. aisle, which is florid, and the Lady Chapel, early pointed. Notice should be taken of its elegant Norman tower surmounted by a light spire, with a florid portal on one side of it and a round doorway, ornamented with the embattled fret, on the other, and within, of the carved capitals of the columns, and a gallery of stone fretwork near the W. end.

16 Epouville. We now reach the high ground of the Pays de Caux (p. 61), but traverse a number of valleys or gullies intersecting it, running down to the sea, in every one of which a village or small town nestles; this renders the road a succession of ups and downs. When the harvest is cleared from the ground and sheep are feeding among the stubble, a long narrow cart, covered either with a

coved wooden roof or thatched with straw—a sort of horizontal sentry box on wheels, may be seen drawn up by the road side or in the fields; it is the moveable bed of the shepherd, in which he shelters himself at night or in bad weather.

14 Goderville.

13 Fécamp—(*Inns*: Poste, extortionate; H. du Commerce); a town of 10,000 inhab., nearly fills the bottom and sides of a narrow valley opening out towards the sea between 2 high falaises or cliffs, on one of which stands a lighthouse. It has the advantage of being at once a seaport and a manufacturing town, owing to the abundant stream which, as it descends the valley, turns numerous cotton and other mills, besides which there are 3 steam saw mills. The harbour is small and much sanded up, but is resorted to by colliers from Newcastle and Sunderland, and Baltic timber ships, besides fishing vessels.

In the centre of the town stands the *Ch. of the Abbey of Notre Dame*, a large and fine edifice in the early pointed style, with some Norman features, built in the beginning of the 13th cent., except the 2 round arched apsidal chapels, behind the E. end, which are older, and the S. side of the choir, which is more modern and florid. The Lady Chapel, with its carved woodwork of the 16th cent., and the monuments in the side chapels of abbots Richard (1223), William (1297), and Robert (1326), consisting of altar tombs enriched with crocketed niches, bearing their effigies reclining under florid canopies, merit notice. Also some curious carvings of Scriptural subjects in the N. transept.

Fécamp was the retreat of Cuvier during the storm of the Revolution. He commenced his studies in natural history here on the sea-beach. On the top of the cliff behind the town, near the new lighthouse, 328 ft. above the sea level, is the Gothic *Chapelle de la St. Vierge*, 14th cent., much re-



sorted to as a place of pilgrimage by sailors and fishers.

About 10 m. S.W. of Fécamp, on the coast, is the fishing village of *Etretat*, situated amidst rocks which have been excavated by the sea into arches, aiguilles, and other fantastic shapes. It is resorted to by French artists, and there is a tolerable and cheap little inn (*Au Rendezvous des Artistes*). The road thither is bad.

A hill, steeper than that which leads into Fécamp from the W., carries the road out of it on the side of Dieppe.

19 Cany, in its pretty green and wooded valley, is an agreeable contrast to the bare open land which precedes and follows. The *Château* belongs to the Duc de Luxembourg.

The road again approaches the sea at

12 St. Vallery en Caux, a fishing town, of 5328 inhab., with a port formed by locking the stream, which here descends to the sea.

14 Bourg Dun.

18 *Dieppe*, in Route 5 (p. 24).

A rudely jolting, one-horse patâche runs daily between Dieppe and Eu. A cabriolet costs 10 fr. to go and return. The road, as before, is carried over the high ground at some distance from the sea, and traverses in succession several valleys.

19 Tocqueville, a small hamlet. Beyond it a considerably larger village, Creil, with a massive church, is passed.

11 *Eu*.—*Inns*: Poste or Cygne; H. de l'Union, neither good nor cheap. Eu is a somewhat lifeless town of 3730 inhab., on the Bresle, a small stream which formed the boundary of Normandy, and which falls into the Channel 2 m. lower down, at Treport. In the centre of the town is an irregular market-place, no two sides of which are parallel, overlooked by the E. end of the *Parish Church*, a heavy building and injured by modern reparations, externally propped up by huge flying buttresses. It is in the early pointed style; the triforium

arches open into the aisles, the E. end is angular, but several of the side chapels are of late florid Gothic. Attention should be directed to the screen before that of St. Laurent, an Irish archbishop; to the Entombment in another chapel composed of statues as large as life; and to the fantastic, spirally banded column in the S. transept. The church has been restored by the King, who has also given several modern painted windows from the manufactory at Sèvres.

In the *crypt* (caveau) below the church are deposited a series of monumental effigies which were mutilated by the revolutionists 1793, and thrown into a vault filled with rubbish, but have been restored by the present King. The oldest is of St. Laurent, archbishop of Dublin, who died at Eu (1181), whither he had repaired on a mission of peace, to reconcile Henry II. and the king of Ireland. The rest are of the counts of Eu, of the family of Artois; viz. Charles d'Artois, 1471—the head and hands are of marble; of his father, Philip d'Artois, made prisoner at Nicopolis by the Turks, d. 1397 in Anatolia; Jean d'Artois, 1386, his surcoat studded with fleurs-de-lis of copper; he was taken prisoner at Cressy along with the French king; Isabella de Melun, his wife, in an elaborately carved dress, with dogs at her feet; Jeanne de Saveuse, wife of Charles d'Artois, a pleasing countenance and curious costume; Hélène de Melun, his 2nd wife; Isabelle d'Artois, who died unmarried, 1397.

Eu is chiefly remarkable, however, on account of its *Château*, belonging to King Louis-Philippe, who inherited it, with the Comté d'Eu, from his mother, daughter and heiress of the Duc de Penthièvre. His Majesty spends here in retirement a few weeks of every autumn, and here he received H. M. Queen Victoria in 1843. The château is a low building of red brick surmounted by high tent-shaped roofs of slate, like the pavilions of

the Tuileries, and is without architectural beauty. It was built 1578 by Henry of Lorraine, le Balafre Duc de Guise, on the site of a castle which had belonged in turn to the Lusignans, the Briennes, the Artois, the Clèves, and the Saint Pols, and which was burnt down by Louis XI. (1475), to punish the treachery of the Comte de St. Pol. It has been much augmented by the present King, and splendidly fitted up, the walls being clothed with a collection of historical and family portraits, including those of the royal family and the various lines of the counts of Eu to the number of 1100. Many of them are copies, others are mere furniture pictures; yet the collection is highly interesting, and the formation of it seems to have given rise to the grander gallery of Versailles, which this resembles on a miniature scale. There appears to be no other arrangement than that of making a certain number of pictures fit into certain spaces; names, dates, nations, and families are intermixed, and the walls are covered with them from the top to the bottom of the house.

As the pictures are chiefly valuable in an historical point of view, not as works of art, and as every one bears its name on the frame, it is useless to enter into long details, which would merely be to give a list of the most eminent names in French history. A few, however, are here noted down, as possessing some peculiar interest:—the Regent Duke of Orleans by *Mignard*—Napoleon and his father, Charles Bonaparte! There are several portraits of the frivolous and ambitious Anne Marie Louise de Montpensier, called sometimes la Grande Mademoiselle, who, after having aspired to the hands of her cousin Louis XIV., of the Grand Condé, of Charles II., and of the Emperor of Germany, was content at last to be married to Lauzun, a simple gentleman. She often resided in this château; and one of these likenesses, at the age of 43, in which she

is drawn holding her father's (Gaston, Duc d'Orléans) portrait, is mentioned by her in her "*Mémoires*." Her bedroom was that occupied by the present Queen. Some of the drawings in the Cabinet de la Coquille, on the first floor, are by her. She became possessor of Eu by purchase from Mademoiselle de Guise, the last descendant of that family in a direct line, 1661. She bequeathed Dombes and Eu to the Duc du Maine, natural son of Louis XIV., by Mde. de Montespan, and father of the Duc de Penthièvre, in the vain hope of ransoming Lauzun her husband from the prison of Pignerol. She first commenced the historic gallery of portraits at Eu, and her collection forms the groundwork of that still existing. At the back of one of the portraits of herself there is written by her own hand, "*Bergere alant a la faite du Village voisin*." *Portraits continued*—of Louis XVI., Marie Antoinette, his queen, the Dauphin their son, who died in the Temple, and all the other members of their family; those of Louis-Philippe and his family occupy the *Salon de Famille*:—the most pleasing and interesting is the Princess Marie of Wirtemberg, the sculptor of the admirable statue of Jeanne d'Arc. There are two portraits of Louis-Philippe Egalité (d. 1793), one as a young man in civic dress, the other in uniform, by *Sir J. Reynolds*.

One of the most superb and interesting apartments is the *Galerie des Guises*, filled with portraits of that remarkable family, who once owned this château; among them, Claude de Lorraine, with the armour and sword with which he fought at Marignan; François de Lorraine, Duc de Guise, who was wounded in the face before Boulogne by an English lance, and who endured the pain of having the lance head extracted from his cheek with a pair of pincers, while the surgeon rested his foot on the duke's head to obtain a purchase. He was the successful defender of Metz against



Charles V., and the capturer of Calais from the English; he was killed by the poisoned bullet of Poltrot, 1563. His son, Duc Henri le Balafré, so called also from a wound in his cheek received from an arquebuse at the battle of Dormans. He began to build the château d'Eu 1578; he was the chief of the Ligue, the hero of the Journée des Barricades, and the murderer of Coligny on St. Bartholomew's night. He was assassinated by Henri III. at Blois (Route 53), 1688, together with his brother, the Cardl. de Lorraine.

Marie de Lorraine, daughter of Duke Claude, Queen of James V. of Scotland, and mother of Mary Queen of Scots;—Queen Mary herself in her widow's weeds of white (royal mourning);—Catherine, Duchesse de Montpensier, sister of Le Balafré, who revenged his death by instigating Jacques Clement to assassinate Henri III.; the Duc de Mayenne, brother of Le Balafré, commander of the armies of the Ligue against Henri IV. Henri II. de Lorraine, Duc de Guise, conqueror and viceroy of Naples after Masaniello's rebellion.

"Le récit de cette salle a fait une longue digression sur les portraits qui y sont," are the words of Mademoiselle herself, in describing these very pictures in her own gallery; yet how momentous a tale does every countenance tell! Where shall we find such an accumulation of ambition, of crime, and of romance, as in that one family?

Of Louis XIV. there are several likenesses, also of his family, his mistresses, his generals, his court; and even more of Louis XV. In the billiard-room are Charles I. and II., Oliver Cromwell, Queen Elizabeth, Joan of Arc, and Agnes Sorel.

The superb *Salle des Rois* is so called because filled with portraits of kings and queens only: here are Marie de Medicis by *Van Dyk*, given by herself to Mademoiselle de Montpensier, and Henri IV. Here is a cast of the equestrian group of Jeanne

d'Arc striking down for the first time an enemy, by the Princess Marie.

In the *Cabinet du Roi*, among portraits of H.M.'s own family, including his father, are Madame de Genlis, his preceptress; Pamela, afterwards Lady Fitzgerald; and Madame de Lamballe, who was murdered 1793.

The *Hall of Victoria* is decorated with pictures representing the visit of the Queen of England to Eu, painted by French artists.

The small *Chapelle*, a mixture of Gothic and Italian in its decorations, has some modern painted glass windows from Sèvres; one is a portrait of St. Amélie, after the picture by *Paul Delaroche*.

The *Parc* or grounds are less attractive than the palace; being a wilderness of trees, mostly weedy elms, planted in rows with angular terraces; a gloomy canal, and muddy circular ponds beset with willows. No advantage has been taken of the slopes of the ground,—no taste shown in laying out the brotherhood of alleys and formal parterres. Only on the l. of the castle a few ancient beeches survive, beneath whose branches the Balafré Duc de Guise heard the suits of his vassals, and concerted plots against his sovereign. Here a small space has been railed in by the King, who has affixed this inscription:—"Ici les Guises tenaient conseil au XVIe siècle." At the extremity of the grounds is a terrace overlooking the gap through which the Bresle quitting the bare and dull valley enters the sea, and the little village Treport is perceived at its mouth. On this terrace is a brick *Pavillon*, fitted up by poor Mademoiselle, during the time she was banished to her estate at Eu by Louis XIV. for refusing to marry the paralytic and imbecile king of Portugal. Louis-Philippe has restored it, and ornamented it with pictures of the events of her life.

The effigies of the Duc Henri de Guise (Le Balafré), murdered at Blois, and of his wife Catherine de Clèves.

are in the *Église du Collège*, originally of the Jesuits, who were established at Eu by le Balafre. The church, built out of the ruins of the old castle, as well as the monuments, were raised at her expense; they are rich in marble, but of no value as works of art. He is represented in armour, she in ruff and farthingale; there are duplicate effigies of both, attended by figures of Prudence, Strength, Faith, and Charity; Gillot was the sculptor. From the pulpit of this church Bourdaloue preached his first sermon.

On the Bresle, close to the palace, is a *mill* for making sea biscuits, sawing timber, &c., established by an Englishman.

*Treport*, the port of Eu, 3 m. distant, is a fishing village of 2,265 inhabitants, having an old *Church* seated on a height, approached by a flight of steps remarkable for its elaborate W. *porch*, and for the roof of its nave distinguished by pendants of stone hanging from it, of the 14th century. Treport is supposed to be the *Uterior Portus* of Julius Cæsar.

16 Valines.

18 *Abbeville* (R. 2).

## ROUTE 21.

ROUEN TO ALENÇON BY BERNAY, BROGLIE, AND SÉEZ.

143 kilom.=89 Eng. m.

A malleposte runs this way from Rouen to Tours.

42 Brionne (R. 23).

15 Bernay—(*Inn*: La Poste, Lion d'Or), a manufacturing town of 7,244 inhab. It once possessed an important abbey, founded by Judith, wife of Richard II. duke of Normandy; the *Church* of which, now converted into warehouses, is one of the oldest Norman (Romanesque) buildings existing in Normandy, having been begun in the early part of the 11th century. It is large in its dimensions and perfectly simple in its style: plain square piers support equally plain circular arches. The columns attached to the piers are carved, and one is inscribed "*Isambardus me fecit.*"

The choir ends in an apse, and there is one in each transept. "The dome vaulting in circular courses over the aisles is exceedingly curious." In *St. Croix* are some painted windows, and the high altar was brought from Bec. *N. Dame de la Couture* is a Gothic church of the 15th century. The houses in the *Grande rue* retain curious porches and bits of Gothic.

10 Broglie, a town of 1,052 inhab.

The *Church* is an ancient and singular building: along its W. front runs a row of interlacing circular arches; one side of the nave rests on very massive piers; the other is modernised, the piers pared down, and pointed arches substituted for round ones. The large and plain *Château* on a height surrounded by wood near this is the family residence of the Duc de Broglie, ex-minister, and one of the most virtuous, enlightened, and eminent statesmen in France.

16 Monnai.

14 Gacé has a ruined *castle*.

12 Nonant.

12 Sécz (*Inn*: La Corne), a poor little city with a population of only 5,500, owing that title to the possession of a *Cathedral*, a fine edifice, the remarkable features of which are, the porch, 47 ft. deep, under the W. front, flanked by 2 spires; the nave, 80 ft. high, of pure early pointed Gothic of the 13th century; the windows are double lancet and very elegant. The choir and transepts are in the decorated style of the end of the 14th century.

A cathedral was built here in 1055, but no part of it exists in the present one, judging from the style. The town was burnt down in 1150 and 1353, and probably the cathedral also.

21 Alençon (R. 35).

## ROUTE 23.

ROUEN TO CAEN BY BRIONNE, OR BY HONFLEUR.

a. By Brionne 128 kilom.=79½ m.

The road after issuing out of Rouen crosses the Seine, and runs within a



short distance of the l. bank, here bordered by chalk cliffs (p. 53), skirting on the l. the forest of Rouvray, to

12 Grande Couronne; thence by Moulineaux (R. 12) and near the castle of Robert le Diable to Bouille (p. 54), where it quits the Seine, separating from the branch to Honfleur which turns to the rt. (see below).

13 Bourgheroude.

About 2 m. N. of the road and the same from Brionne are *the ruins of the Abbey of Bec Hellouin*, now of little importance or interest, but famous for having given two successive archbishops to the See of Canterbury, Lanfranc and Anselm. It has been demolished, except a tower of the 15th cent., and the vast conventual building erected in the 17th cent. is converted into a military stud-house.

17 Brionne.—*Inn*: La Poste, once the château of the seigneur of the place. Brionne is a small town on the Risle. The religious council which condemned the doctrines of Berengarius was held in the presence of Wm. the Conqueror in the church of *St. Denis*. There are some fragments of the walls of the keep of the castle, in the middle of the Risle.

11 Marché Neuf.

14 L'Hôtellerie.

13 *Lisieux*, in Route 25.

17 Estrées.

13 Moult.

17 CAEN (Route 25, p. 74).

Before reaching this the road falls into the great Route 25, from Paris to Cherbourg, and is fully described under that head.

b. By Honfleur 136 kilom.=84½ m.

To Caen by Pont Audemer and Honfleur, a *diligence* runs daily.

12 Grand Couronne.

13 Bourghard.

At 5 min. past 1 on Sat. 19th Sept. 1829, the tower of the parish church sank down in a heap, crushing the nave and covering part of the churchyard. Had the accident occurred the following day, it being the hour of mass, the whole congregation must

have been annihilated. There was a curious leaden font in this church. A dreary district extends from this place as far as the pleasant valley of the Risle, one of the loveliest streams in Normandy, in which lies

23 Pont Audemer.—*Inn*: Pot d'Etain: the samlets (saumoneaux of the Risle) are excellent. This is a prettily situated town of 5,400 inhab., famed for its tanneries, of which it contains 40; besides which some cotton is woven here, its industry being greatly promoted by the Risle, which passes through it in small streams. It once had a castle, in besieging which, in the early part of the 14th cent., cannon were first used in France: it was razed by Du Guesclin. The Churches of Notre Dame des Prés, now a tan-house, and of St. Germain, in the suburb, may furnish some points of interest to the antiquarian architect. The Churches of *St. Ouen* and of *St. Sepulchre* are said to be worth notice.

The Terrace of the château de Bonnebon presents a pleasant view. *English Ch. service* on Sundays, 45, Rue de Bernay.

A direct road from Pont Audemer to Pont l'Evêque, avoiding the détour by Honfleur, is completed—by Beuzeville 14 kil., to Pont l'Evêque 13 kil.

At Fiquefleur we obtain a fine view over the embouchure of the Seine.

23 Honfleur (*Inn*: H. d'Angleterre, close to the pier, and commanding a fine view; clean and good cuisine, with much attention.—Honfleur is famed for melons.) It is a sea-port town of 10,000 inhab. at the mouth of the Seine, here 7 m. broad, on its S. bank opposite to Havre, and communicating with that port daily by steam-boats. The town is dull and utterly without interest to the traveller, and moreover very dirty, but its situation, backed by wooded heights, is very pleasing. Its commerce, once considerable, has been absorbed by Havre. Its harbour, protected by a stone pier not yet finished, is accessible only at high water, and is principally resorted to by fishing vessels, though some timber

ships unload here. 7000 dozens of eggs are exported weekly to England, besides butter and fruit. The chapel of *Nôtre Dame de Grace* on the hill above the town to the W., much resorted to by sailors and filled with their ex-votos, is in a charming situation for the view over the Seine. It was formerly not uncommon for the crews of vessels which had escaped imminent danger at sea to make a pilgrimage hither in their shirts, bare-footed and bareheaded.

The English church service was performed twice every Sunday in 1844, in a building on the route de Rouen.

The *Steamer* from Havre to Rouen calls off the port in going and returning. (R. 12.)

*Steamers* twice a-day to Havre, 7 m. and back, start according to the tide: the passage takes up  $\frac{3}{4}$  of an hour.

*Diligences* daily to Caen and Rouen.

After the long and stately avenue of trees leading out of Honfleur, the way to Caen possesses no great interest: yet orchards and hedges give an English cast to the scenery. The head-dress of the women, a night-cap twisted like a Phrygian bonnet, is by no means elegant.

17 Pont l'Évêque, a town on the Touques. Trouville on the sea, at the mouth of the Touques, is a small bathing place, much frequented from July to Sept. for sea-bathing: the sea is not so rough as at Havre, and the water is more salt. *Steamers* several times a-day to Havre.

Here the road to Lisieux (Route 25) and Falaise branches S.  $\frac{1}{2}$  m. N. of our road, and  $2\frac{1}{2}$  m. from P. l'E.; in the midst of the Pays d'Auze is Beaumont, a small bourg with an abbey, in which Laplace, the mathematician and author of the "*Mécanique Céleste*," was born.

18 Dozullé. We here cross the Dives, from whose mouth the Conqueror set sail for England.

12 Troarn.

14 CAEN, in Route 25.

## ROUTE 24.

### HAVRE TO CAEN.

*Steam-boats* pass daily to and fro, starting as soon as the height of the tide allows them.

The voyage, which takes up about 4 hours,  $2\frac{1}{2}$  of them on the open sea, is pleasant in fine weather. The steamer skirts the coast of the dépt. Calvados, in sight of the bathing-place Trouville (see above), and of the mouth of the Dives, where William the Conqueror tarried for a month to collect his fleet of 3000 ships and his army of 50,000 men. The mouth of the Orne is entered with difficulty on account of the sands and rocks, and we then thread its sinuous channel between low banks, but the landscape is enlivened by several ancient churches. A canal is in progress, by which some of the windings of the Orne will be avoided, and the distance from the sea to Caen, 10 m., abridged. If the vessel, owing to tempestuous weather, should miss the tide to cross the bar, it must wait outside, and lie off the mouth for 10 or 12 hours for the next tide; but this rarely happens.

"At length the city of Caen extends itself, terminated at each extremity by the venerable abbeys of William the Conqueror, and Mathilda his queen; the latter, surmounted by 3 towers, is nearest at hand. There are no traces of workshops and manufactories, or of their pollution; but the churches, with their towers and spires, rise above the houses in bold architectural masses, and the city assumes a character of quiet monastic opulence, comforting the eye and the mind."—*Palgrave*.

Abreast of the town, the river is lined with sumptuous quays of solid masonry, alongside of which the vessel is moored.

CAEN. Route 25.



ROUTE 25.

PARIS TO CAEN AND CHERBOURG, BY  
EVREUX AND LISIEUX.

To Caen 223 kilom. = 138 Eng. m.  
Caen to Cherbourg 118 kilom. =  
74 Eng. m.

*Malleposte* in 15 hours to Caen,  
and 23½ hours from Paris to Cher-  
bourg. *Diligences* daily.

From Paris to  
70 Bonnières is described in Route  
9. A little beyond this we quit the  
route to Rouen, turning to the l. out  
of the valley of the Seine, up a  
wooded combe to an elevated and fer-  
tile but monotonous country.

15 Pacy-sur-Eure. 10 m. S. of  
this is Ivry, where Henri IV. gained  
a momentous victory over the Duc de  
Mayenne and the army of the League  
1590 (see p. 117).

At Cocherel, on the rt. bank of the  
Eure, 4 m. below (N. of) Pacy, Du  
Guesclin, in 1364, defeated the forces  
of the King of Navarre, Charles le  
Mauvais.

18 *Evreux*—(*Inns*: H. du Grand  
Cerf, tolerable—de France, opposite  
the Cathedral), chef-lieu of the Dépt.  
de l'Eure, has 10,287 inhab., and is  
prettily situated in a bowl-shaped  
valley shut in on N. and S. by hills,  
and watered by the Iton, an affluent  
of the Eure, divided into several  
branches. It has a considerable share  
in the cotton manufacture (ticking  
and stockings), here carried on by the  
hand-loom more than by the steam-  
engine. Its chief edifice is

*La Cathédrale*, presenting to the  
W. an incongruous front of Italian  
architecture, flanked by two towers,  
and surmounted in the centre of the  
cross by a loftier tower and florid  
spire, erected by the Cardinal de la  
Balue, favourite of Louis XI. The  
nave is in the Norman style, probably  
of our Henry I.'s time, since he  
burnt the town, with the permission  
of the bishop, on condition of rebuild-  
ing the churches. The upper part of  
the nave, and the rest of the ch., are  
*France.*

pointed, and for the most part more  
modern than the reign of Philippe-  
Auguste, who again burnt the town  
to revenge himself on the treachery  
of Jean Sans Terre, in making it over  
to him during King Richard's cap-  
tivity, but on Richard's unexpected  
return not only withholding it, but  
murdering the French garrison placed  
in the castle. The *choir*, supported  
on clustered columns with glazed  
triforium (1330-60), is very lofty  
and light. The Lady Chapel and  
the N. transept are still more re-  
cent (1465-75), and the *Portal* leading  
into it, in the flamboyant Gothic,  
elaborately ornamented, is deservedly  
admired, in spite of the injuries and  
loss of its statues inflicted by the  
Revolutionists. It dates from the  
beginning of the 17th centy. The  
beautiful rose window in the S. tran-  
sept, and the wooden screens to the  
side chapels round the choir, showing  
the flamboyant Gothic style modified  
by the reviving Italian, also merit  
notice. "The *Lady Chapel*, of ele-  
gant architecture (temp. Louis XI.),  
contains painted glass equally remark-  
able for its fine execution and perfect  
preservation."—*E. o. S.* The wood-  
work enclosing the chapels round the  
choir, of mixed Gothic and Renais-  
sance, merits notice.

The *Bishop's Palace*, built 1484,  
presents some curious details.

At the opposite end of the town is  
the *Church of St. Taurin*, attached to  
the séminaire; it is small, and re-  
sembles the cathedral in the various  
styles it displays, having shared like  
it the fortune of war and conflagra-  
tion. The outer wall of the S. tran-  
sept is ornamented with an arcade of  
semicircular arches, the panels of  
which are prettily diapered with a  
pattern formed of red tiles let into the  
masonry. This is supposed to be a  
relic of the church built 1026 by Ri-  
chard II. duke of Normandy.

The greatest curiosity of this  
church is the *Chasse* or *Shrine of St.*  
*Taurin*, which once contained his re-  
lics, preserved in the sacristy. It is

a wooden box, shaped like a Gothic chapel, covered with plates of copper, or silver gilt, enchased with a diapered pattern, and set round with bas-reliefs and small statuettes of bishops and saints; it is a work of the 13th cent. The architectural decorations are rich and in good taste: such shrines are now very rare. The precious stones which once ornamented it have been stolen or lost.

The streets of Evreux preserve many antique timber-framed houses, and on the Boulevards are traces of the walls which once defended it. It possesses a Beffroi called *Tour de l'Horloge*, built in the 15th century.

Excavations made at Vieil Evreux (Mediolanum Aulercarum) have led to the discovery of a theatre, baths, &c. and of various relics now deposited in the Musée d'Antiquités.

The title of the premier English Viscount, Devereux Visct. Hereford, is derived from this town: the family traces its descent from Normandy.

The Château de Navarre, about 1 m. from Evreux, exists no longer, having been pulled down 1837-8.

*Coaches* go hence to Chartres and Rouen (Route 50) daily.

The next post station to Evreux is called

18 La Commanderie, from a castle and church of the Knights Templars, of which the ruins and some tombs of members of the order remain. It lies very high.

17 La Rivière Thibouville. A little to the N. is Harcourt, cradle of one of the noble houses of England, who trace their descent from a baron of the name who fell beside William the Norman at Hastings. There are scanty remains of a castle.

10 Marché Neuf.

14 L'Hôtellerie. The upland district traversed by the road forms part of the Pays de *Lieuvin*, celebrated for its fertility and excellent cultivation.

13 *Lisieux*. (*Inns*: H. de France; —La Belle Fontaine.) A thriving manufacturing town (11,473 inhab.),

prettily situated at the confluence of the Touques with the Orbec. About 3,500 persons are employed in and around the town in weaving coarse woollens, flannels, horse cloths, &c. Its main street exhibits specimens of ancient domestic architecture, timber-framed houses and pointed gables, well suited to the artist's pencil.

The *Ch. of St. Pierre* (formerly cathedral) faces an open square, with its W. front surmounted by a spire; one of its towers is rebuilding. It is in the early pointed style of the 13th cent., with lancet windows, holding a place between the Norman and the lancet Gothic of England. A preceding edifice, built 1143-82 (when the pointed style had scarcely begun to appear in this part of France) was burnt down, 1226. Norman arches occur in the S. W. tower only; the outside of the S. transept is a fine example of the pointed style. The *Lady Chapel* was founded, in the 15th cent., by Pierre Cauchon, bishop of Beauvais, and president of the unjust tribunal which condemned Joan of Arc, in expiation of "his false judgment of an innocent woman," as he expressly states in the deed of endowment. (See p. 40.)

Henry II. was married to Eleanor of Guienne, the divorced wife of Louis le Jeune, 1152, in this cathedral.

There is a very singular old wooden house in the Rue aux Fées.

Lisieux was the capital of the *Lexovii*, a Gallic tribe mentioned by Cæsar, and ruins of the ancient town (*Noviomagus*, L.) have been discovered at a short distance from the present one. Thomas à Becket retired hither 1169, during his exile from England. *Le Val Richer*, a small country house near Lisieux, is the summer-retreat of M. Guizot.

17 Estrées. The road from Lisieux to Caen is almost destitute of interest.

13 Moulton.

17 CAEN. *Inns*: H. d'Angleterre; reasonable and very good;—H. de France, fallen off; table d'hôte, 3 fr.;



bed, 2 fr.; servants, 1 fr. 10 sous per diem;—H. du Palais Royal; not very clean, but moderate.

Caen, chief town of the Dépt. du Calvados (so named from a long reef of rocks on its coast, on which a Spanish vessel, the *Calvados*, was wrecked in the reign of Philippe II.), is situated on the Orne, 10 m. from its mouth, and has 43,079 inhab. A smaller stream, the Odon, passes through the town and around the line of its old ramparts, to which it served as a fosse, before it joins the Orne, turning on its way several mills. Notwithstanding the antiquity of Caen, its wider streets, its large central square, in which stands the statue of Louis XIV., and its houses of white stone, give it a more cheeful air than Rouen, though less enlivened by passing crowds. The tall white Norman head-dress of the women, ornamented with lappets behind and sometimes with lace, is striking and quaint to a stranger's eye.

To the traveller Caen recommends itself by its numerous specimens of ancient architecture, to the permanent resident by the salubrity of its site, and the cheapness of house rent and provisions, which have caused our countrymen to settle themselves down here in a colony 2000 strong.

Near the centre of the town, on one side of a small market-place full of bustle and quaint costumes in the early part of the day, rises the *Church of St. Pierre*, surmounted by one of the most graceful towers and spires, in the complete Gothic style, which Normandy can produce; the middle story, formed of tall lancet windows framed within reeded mouldings, is a model of strength and lightness; it is surmounted by a spire of stone, partly pierced au jour. It was built 1308, and is 242 ft. high. The nave was constructed probably about the same time, the choir, more richly ornamented, rather later, while its roof and the chapels round the choir were

added in 1521. The rich groining of the roof of the choir is surpassed in the chapels, where it assumes the form of pendent fringes, giving the roof a cellular character, while open rings are substituted for key-stones. The side walls of these chapels are pierced with arches and set with statues. Some of the capitals of the columns in the nave exhibit ludicrous carvings, such as Aristotle bridled and ridden by the mistress of Alexander, and Lancelot crossing the sea on his sword, from the old romances. The exterior of the E. end, well seen from the banks of the river, is as much Italian as Gothic, so entirely are forms and styles jumbled together.

Caen possesses two very remarkable monuments of the piety of William the Conqueror and his queen, in the churches of the *Abbayes, Aux Hommes* and *Aux Dames*: both founded 1066, and valuable in an architectural point of view, because their date is undoubted.

The *Church of St. Etienne*, or of the *Abbaye aux Hommes*, destined by the Conqueror as a resting-place for his own remains, was finished and dedicated by him in his lifetime, 1077, under Archbishop Lanfranc, who was the first abbot. The W. front is so perfectly and severely plain that it will probably disappoint expectations; it is surmounted by 2 stately towers and spires of later date (1200), which, with the choir, were rebuilt or added to the original edifice, long after the time of William. The interior of the nave, however, exhibits the rigid severity and massy strength, with the grandeur of proportion, of the Norman Romanesque style. The church is 371 ft. long and 98 ft. high. The lower row of arches supports a gallery, having arches of nearly equal span, and  $\frac{2}{3}$  of the height of those below, an arrangement resembling the arcades of the Roman Coliseum. These upper arches originally opened into the aisles, the vaulting below them being of posterior

date. The clerestory windows consist of a tall and short arch placed alternately on one side or the other to meet the curve of the vault. The choir ending in an apse, and surrounded by apsidal chapels, is in the pointed Gothic style, answering to the early English of the 12th century (some say 1316-44). A plain grey marble slab in the pavement before the high altar marks the *grave of William the Conqueror*, the founder of the church, but it has been long since empty: it was broken open, the costly monument erected over it by William Rufus destroyed, and the bones scattered by the Huguenots, 1562, and lost, without record, except one thigh bone, which was re-interred. The Revolutionists of 1793 again violated the grave, and this also disappeared.

The funeral of the Conqueror, undertaken by the charity of a simple knight, as already detailed (p. 39), was singularly interrupted, even within the precincts of the church, and before the service for the dead was concluded, by a cry from one of the bystanders, a man of low degree, who claimed the site of the grave, saying, that it occupied the place of his father's house, that he had been illegally ejected from it in order to build the church, and he demanded the restitution of his property. This claim, thus boldly made, in the presence of the dead monarch's son Henry, the chief mourner, being backed by the assent of the town's people, who stood by, was not to be denied or rejected, and the bishop was obliged to pay down on the spot 60 sous for a place of sepulchre for the royal corpse. Even then it is related, that as the coffin was being lowered into the grave, it struck against some obstacle, fell and was broken into pieces, so that the corpse, ejected from its tenement, diffused so horrid a stench through the church, that the rites were hurried to a close, and the assembled priests and laity dispersed.

The exterior of this church, sur-

mounted by its 2 W. towers, its central octagonal tower, and 2 turrets on the E., has a peculiarly striking effect from a distance, and reminds one of the arrangements of some of those on the Rhine.

The adjoining conventual buildings (date 1726) have been converted, since 1800, into a *College*, numbering not quite 300 students. On the W. side of the court adjoining is a handsome Gothic building (14th cent.), lately restored as a school, which occupies the site of the old Norman Palace, called *Grand Palais*.

At the opposite end of the town, on the heights of St. Gilles, is the *Abbaye aux Dames*, or church of *la Ste. Trinité*, founded 1066, and consecrated the same year, though probably unfinished, by Queen Mathilda, the Conqueror's wife, and destined by her for a nunnery of noble ladies. The conventual buildings attached to the church are quite modern (1726), and are converted into an *Hospital* (*Hôtel Dieu*), in which 40 sisters, of the order of St. Augustine, perform the duties of nurses of the sick: the choir of the church is railed off for their use. The church, in the lighter and more ornate character of its architecture, displays so broad a contrast to the masculine plainness of St. Etienne, that it would scarcely be supposed that they had been both in progress at the same time. With the exception of the upper part of the W. towers, however, this edifice is a perfect and unaltered specimen of pure Norman Romanesque; the choir ending in an apsis being of the same age and style as the nave. "The piers are lighter, the engaged pillars project more than in St. Etienne, the embattled fret here runs round the main arches, and instead of a lofty triforium the walls above them are threaded by a gallery supported by misproportioned pillars, exhibiting grotesque figures among the foliage of their capitals. The arches under the central tower are remarkably bold, and their archivolts are chased with



the Norman lozenge.”—*Sir F. P.* The one opening into the nave is obtusely pointed, but apparently of the same date. The choir, ending in a semicircle of double arches, one tier over the other, encloses in the centre the fragments of the black marble *gravestone* of the foundress, broken in pieces by the Calvinists who dispersed her remains, which, however, were collected some years after. Underneath is a *crypt* resting on 34 closely set pillars.

For the student of ancient architecture the following churches remain also to be visited. Not far from St. Etienne is *St. Nicholas*, another Norman church, coeval with the two abbeys, having been built, except the tower and the pointed vaulting of the nave, between 1066 and 83; it is now a stable belonging to the Remonte de Cavalerie. It is unaltered, very plain in style, and ends in an apse.

*St. Etienne le Vieux*, though desecrated and in ruins, is a fine specimen of pointed Gothic: on the wall of the choir is a mutilated equestrian statue, said to be William I.

*St. Jean* has two unequal and unfinished towers, in the style of that of St. Pierre, but inferior to it in late pointed style.

*St. Michel*, in the suburb of Vaucelles (Vauxhall?), displays some curious architectural features; in the Norman tower the very long but narrow and round-headed windows deserve notice. The fringed portal is surmounted by a gable filled with elegant flamboyant tracery, in the style of the 15th or 16th century.

There are many old houses, with curiously ornamented fronts of the 15th and 16th centuries, in the Rue St. Pierre (Nos. 52, 18, 20, 54, 24, &c.), but they are fast disappearing.

The Hôtel de Valois, Place St. Pierre, now the *Bourse*, is of Italian architecture.

The *Castle*, surmounting the height to the W. of St. Pierre, built by William the Conqueror and his son

Henry—held for a long period by the English, but finally taken from them by the brave Dunois, who compelled the Duke of Somerset with a garrison of 4,000 men to surrender, 1459—has now the aspect of a modern fortress bastioned and counter-scarped; but having been dismantled by a decree of the Convention, it is at present reduced to a barrack. The only Norman portion subsisting is the small *Chapel of St. George*; whose nave is probably of the 11th century, though the earliest mention of it is in 1181; while the chancel, separated from it by a bold arch, is of the 15th century; it is used as a storehouse. From the ramparts there is a good view of the town.

In the *Hôtel de Ville*, which occupies with its Grecian portico one side of the Place Royale, is a *Collection of Paintings*. The only ones worth notice are a genuine *Perugino*, Marriage of the Virgin, imitated by Raphael in the famous Sposalizio;—the Passage of the Rhine, by *Van der Meulen*;—Melchizedec offering bread and wine to Abraham, *Rubens*;—the Virgin with 3 Saints, by some old master, called *Albert Dürer*.

In the *Cabinet d'Histoire Naturelle* is a collection of the fossils of Normandy, including Ichthyosaurus, Plesiosaurus, and a very perfect crocodile from the neighbouring quarries of l'Allemagne. The collections made in the South Sea by Admiral Dumont d'Urville have been deposited here.

The *English church service* is performed on Sundays at 1, in the French Protestant *Temple*, Rue de la Geole.

The *Poste aux Lettres* is in the Rue de l'Hôtel de Ville.

Caen is well provided with *promenades*, formal avenues of trees;—the chief are called Grand Cours, and Cours Cafarelli, by the side of the Orne. The handsome *quais* bordering the Orne and the Odon near their junction form pleasant walks.

The women of the lower and middle classes in Caen, and throughout a large part of La Basse Normandie,

are finely formed, fully grown, and handsomer than in most other parts of France.

The principal street, in which are the best shops, is the Rue St. Jean.

Froissart narrates the story of the capture of Caen in 1346, a short while before the battle of Crecy, by Edward III. and the Black Prince, who, being irritated by the resistance of the citizens, gave it up to plunder. It was then "large, strong, and full of drapery and all other sorts of merchandise, rich citizens, noble dames, damsels, and fine churches." The English fleet returned home laden with its spoils.

Several of the leaders of the party of the Girondins, proscribed by the Jacobins of the revolutionary tribunal, and driven from Paris by the insurrection of May 31, 1793, retired to Caen to organise a revolt against the tyranny of the Mountain, but were entirely defeated and put down in a battle at Vernon. It was shortly after this event that Charlotte Corday (a native of St. Saturnin, near Séez), actuated by the spirit of resistance against the bloody tyranny of the Terrorists, which prevailed strongly at Caen, set out hence to Paris to assassinate Marat.

Among the illustrious natives of Caen, the learned Huet, Bishop of Avranches, born 1613, may be singled out; also Clement Marot, the poet.

Brummel, *the Beau par excellence* of the court of George IV. when regent, lived many years at Caen, and ended his days miserably in a mad-house here.

*Malleposte* daily to Paris and Cherbourg.

*Diligences*; to Paris morning and evening by Lisieux and Evreux (p. 74), and by the Stat. St. Pierre de Vauvray on the Chemin de Fer (Rte. 8) in 14 hours; daily to Cherbourg (Rte. 26); Dol and St. Malo (Rte. 27); to St. Lo, Coutances, and Granville (Rtes. 27 and 32); to Rennes and Nantes (Rte. 34); to Havre by Harfleur and Rouen (Rte. 23); to Tours by Falaise and Alençon.

The *making of lace* is said to occupy 20,000 women and children in and about Caen. The streets of the suburbs are lined with family parties seated round their cottage doors, merrily twirling their bobbins. They make tulles, brodées, and blondes.

With this exception Caen has no claim to be a manufacturing town; though it was so, in an eminent degree, until the revocation of the Edict of Nantes banished all its most industrious artisans.

*Environs.* A cabriolet or other one-horse carriage may be hired for 8 or 10 fr. the day.

The student of ancient architecture might spend many days profitably and agreeably in visiting the ecclesiastical and civil monuments which abound in the neighbourhood of Caen. The Dépt. du Calvados is particularly rich in monuments of architecture; the distinguished archæologist of Caen, M. de Caumont, enumerates nearly 70 specimens of the Norman architecture of the 11th and 12th centuries existing in it.

On the outskirts of Caen, to the E., at the extremity of the Rue Basse St. Gilles, is a singular castellated mansion called *Aux Gens d'Armes*, from 2 stone figures of armed men on the top. Though surrounded by battlemented walls and furnished with towers, it was not built as a place of defence, but as a *maison de plaisance*, for one Gerard de Nollent, in the beginning of the 16th century. Its walls are fantastically ornamented externally with medallion heads of emperors, &c.

There is a very beautiful and remarkable ruin near Caen, first described by *Prof. Whewell*, the *Abbaye d'Ardenne*, now a farm-yard. It has a fine gate tower with a round-headed gate and pointed wicket, large stables, "a buttressed barn which puts to utter shame the largest of our edifices of this kind," and a beautiful *Church*, closely resembling in style the early English of our abbeys of Bolton and Newstead, now a barn or hay-magazine. Its W. front is espe-



cially noticeable; it has a rose within a pointed window, and a rich porch supported "on detached shafts."

To the N. and N.E. of Caen, or between the town and the sea, lie the following objects of interest:—

*Thann*,  $7\frac{1}{2}$  m. N.W. of Caen. Here is a true Norman church, scarcely altered since the days of Henry I. when it was built, excepting the loss of its S. aisle. It is a good deal ornamented. The tower is capped with a hollow pyramid of stone, the oldest example of the nascent spire known.

$1\frac{1}{4}$  mile farther to the N. is the interesting *Château of Fontaine Henri*, a seat of the family d'Harcourt, built in the first 30 years of the 16th century, partly in the bastard Gothic, corresponding more with the late Elizabethan of England, partly in the Italian style, resembling the revived classic architecture of Audley End and Longleat. It is a mansion of no great size, but is distinguished by a preposterously lofty and steeply pitched roof, surmounting one wing, flanked by an equally lofty chimney. The most profuse decoration of sculpture is lavished on its singularly irregular façade. The ornaments of the windows, the panelling, balustrades, &c. are not inferior to those of the Palais de Justice at Rouen, which they much resemble. The *Church* of the village is Norman.

Farther on, 12 m. from Caen, on the sea, is Corseulles, a small bathing place and fishing port facing the terrible rocks of Calvados. It is famed for its oysters. Paris receives from the "parcs aux huîtres" here  $\frac{7}{10}$  of all that it consumes, amounting to  $5\frac{1}{2}$  million dozen annually. They are transported by light and fast carriages.

3 m. E. of Fontaine Henri is the pilgrimage chapel of *Nôtre Dame de la Délivrande*, to which the Norman sailors and peasants have resorted for the last 800 years. A very tolerable road, planted at intervals with stations and crosses, leads thither 9 m. from Caen. It has been thus admirably described by Sir Francis

Palgrave:—"The traveller will not fail to linger on the little hill just beyond the first crucifix. Here he enjoys a lovely prospect. The horizon is bounded by long lines of grey and purple hills; nearer are fields and pastures, whilst the river glitters and winds amidst their vivid tints; nearer still the city of Caen extends itself (see p. 72). About 4 m. farther we reach Cambres, one of the many seigneuries which belonged to the noble family of de Mathan. The *château* escaped spoliation at the Revolution. The *Church of Annisy*, on the l. of the road, is only remarkable for its herring-bone masonry, a complete imitation of Roman constructions, by Norman builders. It is composed of small flag-stones of the size and shape of tiles. The church of Douvre, the next village, is rather a picturesque building. The upper story of the tower has 2 pointed windows of the earliest date. The other stories of the tower and the W. end of the church are Norman: the E. end is in ruins."

The *Chapel* of la Délivrande is a small Norman edifice. The statue of the Virgin, which now commands the veneration of the faithful, was resuscitated in the reign of Henry I. from the ruins of a previous chapel destroyed by the Northmen, through the agency of a lamb constantly grubbing up the earth over the spot where it lay. Such is the tenor of the legend. The reputation of the image for performing miracles, especially in behalf of sailors, has been maintained from that time to the present, although it suffered much at the Revolution, when pilgrimages were forbidden. It was visited by Louis XI. in 1471.

From an eminence near this 6 or 8 church spires may be discovered; they have all a strong family likeness to that of St. Pierre in Caen.

Near this, on the coast, is *Luc* or *Lucques*, another small watering-place with an hotel (de la Belle Plage), said to be good.

Thann, Fontaine Henri, and La

Délivrande, may be all visited in the course of a summer-day, taking one road in going, the other in returning; the distance to and fro is rather more than 24 m. There is some sort of public conveyance to Corseulles in summer.

The church of Ifs, about 3 m. S. of Caen, has a curious early-pointed steeple; but a still more remarkable tower and spire exists at Norrey, on the way to Bayeux (Route 26).

The *quarries of Caen stone*, so abundantly used in England during the middle ages, and of which the White Tower, old London Bridge, Henry VIIIth's Chapel, Winchester and Canterbury cathedrals, besides many of our country churches, were built, are situated within the circuit of  $1\frac{1}{2}$  m. to the W. and S. of Caen, near Maladrerie, on the road to Bayeux, and at Haute Allemagne. The rock is an oolite, equivalent to our Stonesfield slate, but without its slaty structure; it is extracted from subterraneous quarries through vertical shafts, in blocks 8 or 9 ft. long and 2 ft. thick. It is still employed in England; the new tower at the W. end of Canterbury Cathedral is built of this stone.

A visit to *Falaise Castle*, the birth-place of the Conqueror, will occupy a day; a *diligence* runs thither and back daily (see Rte. 29).

Another antiquarian and architectural excursion may be made on the way to Bayeux, to Frèsne Camilly, Creully, and St. Gabriel (Rte. 26).

## ROUTE 26.

### CAEN TO CHERBOURG BY BAYEUX.

121 kilom. = 74 Eng. m.

*Malleposte* daily in  $8\frac{1}{2}$  hours.

*Diligences* daily, meeting the Granville diligence at Carentan (Rte. 32).

2 m. beyond Caen is la Maladrerie, so called from a lazaret-house founded by our Henry II., for lepers of the town of Caen, now replaced by a huge penitentiary (Maison Centrale

de Détention). Near this may be perceived the whims or wheels by which the Caen stone (see above) is raised out of the quarries. At St. Germain le Blancherbe, the direct but not post road to St. Lo (Rte. 32) branches off to the l.

The first relay on the way to Bayeux,

12 Bretteville, is called l'Orgueilleuse, though of what it has to be proud is not evident, except its handsome steeple. This, however, is entirely eclipsed by the very fine open belfry and spire of *Norrey*, seen on the l. about 1 m. off the road.

This beautiful *Church*, which has been termed a miniature cathedral, is in the pure and simple Gothic style of our early English, and of the most elegant proportions, with an enriched choir, circular apse, and N. porch. "All the mouldings are deep, free, and repeated so as to give the greatest strength of line to all its parts." The tower owes its character of unequalled beauty to the 4 narrow and tall lancet arches which occupy the N. face of its belfry-story; the two central ones open so as to let daylight through.

In going from Caen to Bayeux a détour may be made to visit Frèsne Camilly, a church in the transition style, round arches prevailing in the body of the building, with indications of pointed arches in a panelled arcade on the exterior of the N. wall. At *Creully*, the *Castle*, a construction of different ages, retains among more modern additions 2 round towers. It belonged to Robert of Gloucester, natural son of Henry I., and is now converted into a dwelling-house. The church is genuine Norman. A little farther is *St. Gabriel*, a ruined priory founded by Robert of Gloucester, 1128: the choir of the church alone remains, and is a very remarkable example of florid Norman. This is a détour which will repay those of antiquarian taste.

There is another road from Bretteville to Creully, passing by Sacque-



ville en Bessin, whose *church* is curious, partly pointed, partly round.

On the direct road from Caen to Bayeux, the country is not very interesting; orchards abound, or rather the corn-fields are planted with rows of apple-trees, under which the grain-crop ripens.

16 *Bayeux (Inn: H. du Luxembourg)*, a quiet and dull ecclesiastical city, with much the air of some cathedral towns in England, was anciently capital of the Bessin, and contains 10,303 inhab. It is washed by a small stream, the Aure, which enters the sea at 5 m. distance. It consists of two main streets, including some ancient specimens of domestic architecture, running up a hill to a large open *place*, lined with trees. Its only curiosities are its *Tapestry* and its

*Cathedral*, its chief ornament, though disfigured by a central cupola in a semi-Grecian style. The W. front is a fine elevation, in the pointed Gothic, surmounted by two steeples of the 12th century, in the towers of which pointed arches alternate with round. The 3 *porches*, which, as well as that on the S. side, deserve attention for their bas-reliefs and ornamental foliage, are later in date and florid in style. The interior is 315 ft. long and 81 high. The W. end of the *nave* consists of florid Norman arches and piers, whose natural heaviness is relieved by the beautifully-diapered patterns wrought upon the wall, probably built by Henry I., who destroyed the previously-existing church by fire, 1106. Above this runs a blank trefoiled arcade in the place of a triforium, surmounted by a clerestory of early-pointed windows very lofty and narrow.

The arches of the nave, nearest the cross and the *choir*, ending in a semicircle, exhibit a more advanced state of the pointed style, and are distinguished by the remarkable elegance of their graceful clustered pillars. They were built by Bishop

Henry de Beaumont, an Englishman, 1205. The circular ornaments in the spandrils of the arches are very pleasing and of fanciful variety.

The *stalls* are of oak, well carved; the modern screen is totally at variance with every part of the church, except the cupola.

The chapels in the side-aisles, and the exterior of the E. end, should not pass unnoticed. Under the choir is a *crypt*, probably the only part remaining of the original church, built, in 1077, by Odo, half-brother of the Conqueror, and 50 years bishop of Bayeux. It is supported on 12 pillars with rude capitals, and contains some episcopal tombs. In the *Trésor* is preserved the chasuble of St. Regnobert, in a casket of ivory, with enamelled ornaments, both apparently of Arab workmanship, said to be gifts of St. Louis.

The student of architecture may visit with profit the chapel of the former Séminaire, now *Hôtel-Dieu*, a simple oblong plain groined hall, lighted by double lancet windows, and not unlike the E. end of the Temple Church in London: its date is 1206. Behind the altar is a singular recess, beautifully groined. Also the little Norman *Church of St. Loup*, in the outskirts of the town, on the way to St. Lo.

The *Tapisserie de Bayeux* has been removed from the Hôtel de Ville, where it used to be unwound by the yard from a roller like a piece of haberdashery, and subjected to the fingers as well as eyes of the curious,—to a new room in the *Public Library*, where it is more carefully preserved, and quite as conveniently exhibited, under a glass case. Many persons will look upon it merely as a long strip of coarse linen cloth, 20 inches wide and 214 ft. long, rudely worked with figures worthy of a girl's sampler. It is, however, a curious historical record, of peculiar interest to an Englishman; and although it presents such anomalies as horses coloured alternately blue and red,

there is much spirit in the drawing. It is ascribed, with much probability, to the needle of Matilda, Queen of the Conqueror, and represents the Conquest of England, and the events which led to it. It was preserved in the cathedral until the Revolution, being hung round the nave on certain days. The earliest record of it is in an inventory of the effects of the church, taken 1476. Its series of rude worsted pictures represents such events as Edward the Confessor designating William as his heir; the treachery of Harold; the shipment and landing of the Norman army and battle of Hastings: in many of these scenes, Odo, Bishop of Bayeux, the Conqueror's half-brother, is a prominent figure. The design has evidently been to represent Harold as a usurper, and William as the rightful heir to the crown, having other claims besides that of conquest. The Normans are drawn with shaven heads and chins, in armour of scales, helmets protected by nose-pieces in front, and shields shaped like boys' kites, sometimes bearing devices of crests (supposed to be of later invention) suspended by a belt round the neck. All the buildings have round arches. At the bottom runs a curious border of animals, including camels and elephants, said to represent fables from *Æsop*. (?)

The tapestry has been excellently engraved for the London Society of Antiquaries by the late Charles Stothard. When Napoleon was meditating the invasion of England, he caused this tapestry to be transported from town to town and exhibited, on the stage of the playhouses, between the acts, to stimulate the spectators to a second conquest!

Wace, the author of the *Roman de Rou*, was a canon of the cathedral. According to it Harold actually did homage to William of Normandy, as heir of Edward the Confessor, for the throne of England. Many of the women about Bayeux still wear the Bourgoigne or Bavolette, a rich

and high head-dress, resembling that worn at the courts of the Dukes of Burgundy.

There are good *Baths* at the side of the river, and near them a pretty *Nursery Garden*.

*Diligences* daily to Caen (4), to Cherbourg and St. Lo, Granville and St. Malo.

In going from Bayeux to Cherbourg, the *diligences* make a *détour* of 9 leagues; by passing through St. Lo (Rte. 32), the *malleposte* takes the direct line, as follows, passing *La Tour en Bessin*, whose little *church* has a chancel in a style resembling the best English decorated; the nave is Norman, the tower and spire earlier than the chancel.

16 Formigny. Here the English were defeated (1450) in an engagement so decisive that it occasioned them the loss of Normandy, which has never since been separated from the French crown. A monument on the rt. of the road marks the battlefield, and commemorates the victory. It must be borne in mind that Sir Thomas Kyriel, who commanded the English, an old soldier of Agincourt, who took little account of superior numbers on the side of the French, attacked, with a vastly inferior force, the army of the Comte de Clermont, and while thus engaged was assaulted in the rear by a second army under the Constable de Richemont.

16 Isigny on the Aure is accessible for vessels of considerable size, with the tide. Much butter is exported hence to England and elsewhere.

The river Vire, forming the boundary between the departments of Calvados and La Manche, is crossed about one-third of the distance.

11 Carentan (*Imm*: H. de la Place, good), a town of 3193 inhab., in a low marshy situation surrounded by fortifications no longer kept up, possessing an old *Castle*, which belonged to the kings of France, and was besieged by Edward III., 1346, and a handsome *Church*, surmounted



by a spire; it is Norman, with pointed additions, the E. end in the style of the 14th century. There is some painted glass, but defective.

At Carentan we enter the peninsula of the *Cotentin*, so called from the "côtes," coasts, which border it on 3 sides. It is a fertile and pleasing district, celebrated for its pastures, on which large herds are fed, everywhere enclosed within hedges, and abounding in old ruined castles and ancient churches. It is particularly interesting to Englishmen, as the cradle of some of the oldest and most noble English families. At every step the traveller will encounter obscure villages and hamlets, whose names are familiar to him as household words, as patronymies of great houses distinguished in French and English annals, most of whose founders left their country in the train of William the Norman. Such are Beaumont, Greville, Carteret, Bruce, Neville, Bohon, Perci, Pierpont; but these are only a few examples among many.

13 Sainte Mère l'Eglise has a similar church to that of Carentan.

The ruins of the Abbey of Monteburg have been swept away to the foundation since 1817, having been sold in lots, and pulled down for the materials.

At Quinéville, 6 m. N. E. of this, on the coast, is an ancient monument of masonry 27 ft. high, and 30 in circumference at the base, which is square, and surmounted by a hollow cylinder garnished round with 2 rows of pillars. It is called *la Grande Cheminée*, and though some writers have made it a Roman monument, it may be more safely pronounced a structure of the end of the 12th century, and nothing more nor less than a chimney.

From the heights of Quinéville King James II. beheld the *sea fight* of *La Hougue*, which destroyed all his hopes of regaining his throne. It is said that in the heat of the battle, on seeing the French ships boarded and

carried in succession, his English feelings so far prevailed, that he exultingly exclaimed to the French officers about him, "Look at my brave English sailors." (See p. 84.)

Through a pleasing country, to which the hedges and woodlands give a perfectly English character, not unlike parts of Sussex, to

17 Valognes (*Inns*: H. du Louvre, kept by M. Guetté, one of the best cooks in France; "the andouillettes and homards à la broche renowned"—*R. F.*; Grand Turc, tolerable), a pleasant town of 6940 inhab., containing some large and handsome mansions, the residence of numerous genteel families. The castle of William the Conqueror is demolished; it was here that he was warned by his fool in the middle of the night, of the conspiracy of the Seigneurs of the Bessin and Cotentin to surprise and assassinate him. He instantly mounted his horse, and escaped with difficulty to Falaise.

M. de Gerville, a distinguished antiquary and geologist, resides here.

Although Valognes possesses nothing in itself to detain the traveller, in its vicinity are several objects of high interest. *St. Sauveur le Vicomte* (10 m. S.) has a picturesque ruined castle and abbey (Route 27). At *Bricquebec* (9 m. S. W.) is a convent of Trappists. The geology of the Cotentin is very interesting; its tertiary beds, in which more than 300 species of fossil shells, identical with those of the Paris Basin, have been found, and its Baculite limestone, may be well studied in the quarries near Valognes.

At Alleaume, the Roman *Alauna*, a village contiguous to Valognes, are very scanty remains of a bath: a Roman theatre described by Montfaucon has been totally demolished.

An excursion may be made hence to *La Hougue* and *Barfleur* by Tamarville (2 $\frac{1}{4}$  m.), where the Norman Church has an elegant octagonal tower (a rare form) composed of 3

stories of narrow round-headed arcades and windows.

St. Vaast la Hougue, 10 m. from Valognes, is a sea-port town of 3500 inhab., situated in a fine bay, with the fortified island and lazaret of Tatihou in front, provided with a pier 984 ft. long. Previous to the rise of Cherbourg, it was the chief port of the Cotentin. Vauban proposed to make it what Cherbourg is, the chief arsenal of France in the Channel, but the project was stopped owing to the difficulty of quitting its port with a N. wind. The English frequently effected hostile landings here, to lay desolate the fair fields of France. King Stephen in 1137 landed here, and the army which conquered at Crecy under Edward III. in 1346. Other armaments disembarked here in the reigns of Henry IV. and V., and in 1574 a force of 5000 French and English Protestants despatched by Queen Elizabeth under the Comte de Montgomery, to aid the cause of the Huguenots, made a descent upon Normandy at this point. La Hougue is chiefly known in English history, however, on account of the *sea fight* of *Cap la Hougue* in 1692, when the united English and Dutch fleets under Admirals Russel and Rooke annihilated the expedition prepared by Louis XIV. for a descent upon England, with the design of restoring James II. to the throne. The action commenced at some distance from the coast between Cape Barfleur and the Isle of Wight. The French admiral Tourville, a man of great bravery, having orders from his master to engage at all odds, ventured to measure his strength with a fleet of 80 vessels, the largest which had entered the Channel since the Armada, while his own force did not exceed 44. It is supposed that he was ignorant of the junction of the Dutch, and that he counted on the desertion of Admiral Russel, who, it is well known, was in secret correspondence with James.

However, nothing of this sort occurred, and after a running fight the French, in 3 divisions, retired to their own coast, pursued by the English. 3 of the largest ships, including the admiral's, le Soleil Royal, sought refuge in Cherbourg, where they were blown up by the English Admiral Delaval. Tourville, hoisting his flag on board another vessel, conducted 12 into the bay of La Hougue; where he had time, before the arrival of Russel the day after, to prepare means for a stout defence, running them aground on the shallows with their broadside to the enemy. The French army, united with a body of Irish and English refugees, was drawn up on the heights above; while the artillery was embarked on floating batteries, à fleur d'eau, to assist in repelling any attack on the ships. James II., attended by Marshals Berwick and Bellefonde, who commanded his forces, was a spectator of the action which ensued. The only really brilliant part of the battle was the attack and capture of this armament by the boats of the English squadron under Sir George Rooke; these, and a few light frigates, only being able to approach near enough to take a part in the action on account of the shallows. In the teeth of a tremendous fire of musketry and artillery from shore and ships, the English sailors pulled up to the stranded vessels, boarded them all one after the other with loud huzzas, and pointed their guns against the French on the shore. All the 12 ships of war were burnt, together with a number of transports, 300 of which had been collected in this and the neighbouring ports to convey the army across to England.

A magnificent view of the coast may be obtained from the churchyard of *la Pernelle*.

About 7 m. N. of St. Vaast is *Barfleur*, an ancient and now nearly deserted town, built of granite.



Down to the end of the 12th centy. it was the most frequented port by which the communication between Normandy and England was maintained, in spite of the dangerous rocks around. Upon them perished the "*Blanche Nef*,"—the ship which conveyed William, the only son of Henry I., with 140 young noblemen—through the fault of the intoxicated pilot and crew. The prince himself might have escaped had not an affectionate desire to save his natural sister, the Countess of Mortagne, caused him to turn back towards the foundering vessel. The boat which was bearing him to the shore was instantly filled by a crowd of despairing wretches, and all sank to the bottom together.

On the extreme point of the Cap de Gatteville, the W. horn of the great bay into which the Seine discharges itself, the E. headland being near Fécamp, about 1 m. N. of Barfleur, a magnificent *Lighthouse* was completed in 1835. It is 271 ft. high above the sea, and is constructed entirely of granite. The light is seen at a distance of 27 m. out at sea. There is a fine view from the top. Barfleur is 15 m. E. of Cherbourg: a good road leads thither. Near to it, about 2 m. E. of St. Pierre l'Eglise, lies the *Château de Tocqueville*, seat of the family "of that ilk," now belonging to the eminent writer on America, M. Alexis de T.; and on the other side of the village, the Château St. Pierre, a building of the 18th century, seat of the Countess de Blangy.

At the distance of about 7 m. from Valognes, the direct post road from Valognes to Cherbourg passes,  $2\frac{1}{2}$  m. on the l., the small town of *Brix*, a memorable name, since it is the same as Bruis or Bruce in its primitive spelling. The noble family of that name was allied to the Dukes of Normandy, and from it sprang Robert Bruce the king of Scotland. The castle of the Seigneur de Brix, built in the 12th centy., is now reduced to

a few ruined vaults and foundation walls. It was called *Château d'Adam*.

About 2 m. S.E. of Cherbourg, not far off the road, is the castle of *Tourlaville*, the magnificent seat of the family of Ravalez, now a farmhouse, belonging to the de Tocquevilles. Its position is beautiful and its architecture of high interest; part of it dates from the 15th centy., part was added in the reign of Henry II., and the *Tour des 4 Vents* (fine view from its top) has the character of Heidelberg Castle. "The bleeding heart, and motto of the Ravalez family, '*Un seul me suffit*,' are everywhere visible among the faded frescoes and gilding of its walls and ceilings."—*H. R.* There is nothing more to notice on the road, until from the top of the last hill a fine view of the sea is presented through the gap of the valley, with Cherbourg at its mouth. A winding descent through a picturesque gully, displaying here and there bare cliffs, terminates in a long avenue of trees, which forms the approach to Cherbourg. On the l. rises the eminence *La Fauconnière*, crowned by the telegraph; on the rt. the cliff of *Roule* exposes a precipitous escarpment, 350 ft. above the sea.

20 CHERBOURG. — *Inns*: H. de l'Europe, on the Quai Ouest du Bassin; H. de Londres, good restaurant—*R. F.*; H. de Commerce.

Cherbourg, one of the principal naval ports and dockyards of France, is situated at the N. extremity of the peninsula of the Cotentin, in the Dépt. de la Manche, in the centre of a bay, the extremities of which are formed by Cap Levy on the E., and Pointe Omanville on the W. Its docks have been gained out of the rock, and its harbour won from the winds; for no pains nor cost have been spared to secure for France on this point, so advantageously projecting into the Channel, a naval arsenal and port, whence she may be ready to watch or annoy her rival on the

opposite coast. The town lies in the hollow of the valley of the Divette, which opens out to the sea under the lofty falaise of the quartz hill of Roule, crowned by a fort. Apart from its consideration as a naval station Cherbourg is insignificant; with dirty streets, reminding one of Portsmouth Point. Its commercial relations are very limited; but its extensive naval works employ about 10,000 out of its 25,000 inhab., and upon them depends its prosperity. Among its few articles of export are eggs to the value of one million francs yearly, sent to England. Cherbourg has a *Bassin de Commerce*, a commercial harbour, formed at the mouth of the Divette, never very full of shipping, but often visited by vessels of the English *Yacht Club*, who come over to lay in provisions and champagne. It is lined with quays, and the entrance to it is protected by stone piers, with a lighthouse at its extremity. The commercial port is quite distinct from

The *Dockyard* (Grand Port), situated on the N. W. of the town. English travellers desirous of seeing the dockyard must provide themselves with a note of recommendation from the British Vice-Consul, from M. Le Magnen, or any resident householder, to the Major de la Marine at the Vieux Port, on the E. of the commercial harbour, in order to procure a *ticket of admission*. He will appoint a gendarme to accompany them, to whom a couple of francs may be given for his trouble. The Grand Port occupies a nearly triangular space of ground, one side resting on the sea, and is surrounded by fortifications, which have recently been replaced by more lofty ramparts, taking in a larger extent of ground, surrounded by fossés cut in the rock, faced with granite masonry, and adding greatly to the strength of the place.

The *Port Militaire*, and *Arsenal de la Marine*, designed as well as the Digue, by Marshal Vauban, whose plan, drawn by his own hand and

signed, is preserved in the H. de Ville, were only partly begun by Louis XVI. They have been more than 50 years in progress; and the new works, commenced since 1831, will take as many more, probably, to complete. They consist of an avant port, accessible for vessels of war at all tides, 30 ft. deep, capable of holding 12 or 15 ships of the line and frigates; of a floating basin (*bassin à flot*), closed by lock-gates; and of a third basin, begun 1836, now in progress of excavation, by the aid of gunpowder, out of the solid slate rock, which forms the foundation of the entire yard, and out of which the other basins were quarried in the same manner. From the stairs on the W. quai of the avant port, Charles X. and his family embarked in 1830. There are four slips (*Cales de Construction*), of very solid construction; the lofty roofs rest on arches supported by piers of granite and slate; the arches are partly closed by wooden blinds. Adjoining them is a dry dock (*Forme de Radoub*), and beyond them are the *Ateliers des Forges* (smithy), *des Machines* (workshops filled with machinery for planing, turning, scooping, and cutting rods, beams, screws, &c. of iron); the *Atelier de la Fonderie*, roofed with zinc, furnished with 2 large and 6 smaller furnaces, and with iron cranes, &c. On the W. of the docks the *Magasins Généraux*, the *Parc et Caserne d'Artillerie*, and the *Caserne de Marine*, magnificent buildings, are nearly completed.

The Timber Shed (*Hangar au bois*) is 958 ft. long, and supported on 130 stone pillars. The yard is supplied with water from the Divette by a long and expensive conduit.

Convicts (*forçats*) are not employed at Cherbourg.

*La Digue.* The roads of Cherbourg, though protected on three sides by the land, are naturally open and exposed to the N. wind. To remedy this defect, the project of throwing a Breakwater across the



bay's mouth, in the deep sea, has been favoured by every French government since that of Louis XVI. The old Bourbons, the Republic, the Empire, the Restoration, and Louis-Philippe, have all desired to advance a scheme which should contribute to secure for France a safe and strong harbour on this part of her coast, exactly opposite Portsmouth, which would be an eye to watch and an arm to strike the English on the opposite side of the Channel. Hitherto the French have possessed no port for ships of war from Dunkirk (and that is fit only for frigates) to Brest. Now that the works have been carried on nearly 50 years, and more than 28,000,000 of francs, together with about 4,000,000 cubic mètres of stone, sunk in the operation, the Digue seems at length approaching to completion, since  $\frac{4}{5}$ ths of it are now terminated, and its permanent duration seems probable, since for several years past no perceptible alteration has taken place in the structure or profile of the base. For a long time the undertaking could be regarded only as a series of experiments and failures. The plan first adopted under Louis XVI. (1784) was that of forming truncated cones of timber, or huge broad-bottomed tubs, floating them on empty casks to the proper place, sinking them, and filling them with stones, and heaping up others round about them. But a very brief exposure to a few storms overset some of the caissons, shattered the framework of others to pieces, and spread the stone and wood over the anchorage, so as to injure it. After a considerable interruption from the Revolution, another scheme was resorted to of forming a bank of small stones, and covering these with large solid blocks: this was continued down to the time of Napoleon, who, as was his custom, looked at the project in a military point of view, and at once directed the formation of a fort in the centre of the Digue. All exertions were thenceforth concentrated on this object; a mole was formed, a

battery raised on it mounting 20 guns, a garrison of 90 men was established on it, and lodged in barracks erected for the purpose. In 1808, however, a storm of extraordinary violence burst upon the roads; the waves, carried to an unusual height, soon submerged all the buildings raised upon the Digue, and by the impetuosity of their shocks, swept them all off, save the cabin of the commandant of the prison; and forming a wide breach in the masonry, poured over and through it with tremendous violence. There were at the time upon the dyke 263 soldiers and workmen, of whom 194 were drowned, 69 were saved by finding shelter in hollows among the stones, and 38 got off in a boat which they managed to reach during a short lull, with great difficulty, since the vessels in the roads within the Digue were all driven from their moorings. By this fatal disaster the operations of 16 years, in sinking large blocks, were nearly annihilated, and the whole mass of stone reduced to the condition of a rubble bed, rendering it doubtful whether the plan of even protecting the roads at all was practicable. Nevertheless, Napoleon did not abandon it, nor did his successors lose sight of it. A survey made by order of the government in 1828 showed, however, that the foundations had shifted in the course of 40 years from the position in which they had been first placed to a considerable distance. A fresh impulse has been given to the work since 1830; and under the vigorous superintendence of Louis-Philippe a new mode of proceeding was adopted in 1832. As the result of the schemes previously pursued had shown that the mere weight and volume of the stones thrown into the sea was insufficient to secure their fixity, a layer of beton, a species of concrete, composed of 1 part of small stones and pounded brick and 2 of lime, is now deposited on the loose stone heap, sloping on either side, and upon it a

vertical wall of well jointed and solid masonry, faced with granite, is raised. Even this, however, was destined to be the sport of the waves during a storm which occurred in 1836, the most terrible since that of 1808; the coat of concrete was broken and turned over in places; blocks of stone, weighing 3 tons, were raised 22 ft. high in the air, and carried over the wall to the inside of the Digue. At the end of 3 days 300 of them had found their way across, hurled with appalling violence, and a noise like thunder, against the granite masonry, and acting upon it like battering rams, so that serious breaches and wide gaps were formed in the body of the breakwater. This is more or less the effect of every serious tempest.

More than 500 workmen are constantly employed upon the Digue, being lodged in barracks on the breakwater, and protected during their operations by a movable shed. The colossal structure now raises its head several feet above the surface of the sea. At the present rate of progress it may be finished in 3 or 4 years.

The *Digue de Cherbourg* extends between the Ile Pelée and the Pointe de Querqueville for a length of 3,760 mètres, = 4,111 yards, or more than 2 m., leaving openings for the entrance and exit of vessels on the E. of 1,257 yards and at the W. of about  $1\frac{1}{2}$  mile. The width at the base is 310 ft. The depth of the sea about the Digue varies from 36 to 45 ft. at low water. There are to be at each end light-houses and forts, crossing their fire with those on shore, and guns will be mounted at intervals all along the Digue. The stone employed is partly from the quarries at the base of the Montagne de Roule, conveyed to the harbour along a tramway; the slate comes from the excavations made in forming the docks, and the granite from Fermanville and Flamanville.

Persons desirous of seeing the

Digue have only to hire a boat in the harbour and row off to it, the distance being about 2 m.

The following statement of comparative measurements in yards will show how much more serious an undertaking the Cherbourg Digue is than the Plymouth Breakwater:—

	Length.	Breadth.	Height.	
Digue,	4111	103-310	22	} yards.
Break- water, }	1760	{ 120 at base, 16 at top,	14	

It, however, remains to be seen whether the Digue will ever be completed successfully.

The Roadstead of Cherbourg is beginning to experience the benefit of the breakwater. Though only a third of its area is fit for large vessels, it is capable of containing between 30 and 40 men-of-war in its anchorage. It is protected by the batteries of Fort Royal, of 100 guns, on the Ile Pelée, and Fort du Homet on the W., to which must be now added the fort on the mole in the centre of the Digue.

These works would render Cherbourg, if not impregnable from the sea, at least very difficult to attack. On the land side it has hitherto been almost open, but the fortifications now in progress are intended to strengthen it there. The expenditure of money on the works here, including the Digue, considerably exceeds 400 millions of francs.

In 1758 the English, under General Bligh, effected a descent on the coast, to the number of 7000, in the face of 16,000 French troops, who offered no effective opposition. The English forces kept possession of Cherbourg for three days, in which time they destroyed all the naval and military works, docks, arsenals, &c., blowing them up with the powder which the French had left behind, burning the lock gates of the harbour, and all the vessels of war and commerce. They levied a contribution of 44,000 livres on the town, but no injuries nor pillage of the in-



habitants or their dwellings was permitted. To this the French themselves bear honourable testimony, acknowledging that the protection of the British officers prevented any outrage. All the cannon were carried off, but the bells of the church were conceded to the entreaties of the curé, and allowed to remain.

Cherbourg has no antiquities to show, except the *Vieille Tour*, which formed part of the ancient fortifications, washed by the sea, and the *Church*, not far from it; both built about 1450, and neither possessing any interest.

The *Chapelle de Notre Dame du Vœu*, outside the town near the dockyard, owes its existence and its name to a vow made by the Empress Maude when caught in a fierce tempest, which threatened to overwhelm the vessel in which she was attempting to gain the port of Cherbourg, on her flight from the usurper Stephen, by whom she had been driven out of England. While still at her prayers, and in the agony of anticipated death among the waves, "Chante, Reine," exclaimed a sailor; "behold the land; your prayers are heard:" and from this circumstance, it is said, the spot where the queen landed, and near to which she built the chapel, now enclosed within the dockyard, was called *Chantereine*,—a name which it still retains. The *present Chapel* of the Vow, however, is modern, and stands on a different spot. Mathilda is not the only refugee sovereign whom Cherbourg has seen within its walls at various periods; besides Charles X., who here took a last farewell of his country, after abdicating the throne at Rambouillet 1830, Don Pedro, ex-emperor of Brazil, arrived here, 1831, when driven from his states, and James II. repaired hither after the battle of La Hougue.

The *Hôtel de Ville* contains a *Collection of 164 Pictures*, formed and bequeathed to the town by a native, Thomas Henry, himself an artist.

"The best are (33) David, by *Herrera el Viejo*; (34), Christ bearing the Cross, by *Alonso Cano* (called *Murillo*);—the majority are of the French school."—*R. F.* In the court-yard is a very curious chimney-piece, of the age of Louis XI., rescued from a demolished convent.

*Consuls* reside here from Great Britain and the maritime states of Europe and America.

There is a *Bathing Establishment* on the sands, to the E. of the old Arsenal and Jetée, but it is not well appointed.

"M. le Magnen et Fils, agents to the Royal Yacht Club of England, are very obliging, and their wines, especially their clarets, are excellent."—*R. F.*

The *Poste aux Lettres* is on the Quai du Port.

*Malleposted* daily to Paris, in 22 hours.

*Diligences* daily to Paris by Caen; to St. Lo, Coutances, and St. Malo. Inferior coaches daily to Valognes; to Barfleur; to St. Vaast; to Bricquebec.

*Steamers* to Havre twice a week; to Weymouth once or twice in the summer.

*Excursions* may be made to the Phare de Gatteville; Barfleur, and La Hougue; to the interesting Châteaux of Martinvast (p. 90), belonging to the Comte Dumoncel; of Flamanville, a splendid mansion; of Tourlaville; of Blangy (p. 85).

Querqueville, 5 m. W. of Cherbourg, is a hamlet, whose name is variously derived from the oak, *quercus*, which once surrounded it, or, with more probability, from its small *Church* (kerk) of *St. Germain* standing by the side of the parish church. This is one of the oldest monuments of Christianity in Normandy. It is in the form of a cross; its chancel and transepts, lighted by loophole windows, all end in apses, and all this part is of herring-bone masonry: the nave and tower were added at a subsequent period. The ornaments of the towers, stripes of stone projecting

from the wall, surmounted by the round arch, resemble those of Barton on the Humber, Barnack, and others in England.

The fort of Querqueville is one of the defences of the roads of Cherbourg, and its lighthouse points out the entrance to them.

13 m. farther to the W., beyond Beaumont, the Cap la Hague (often confounded on the maps with La Hougue) stretches out towards Alderney (called by the French Aurigny), from which island it is only 9 m. distant. Both the cape and the island as well as the Cape Flaminville are of granite, the fundamental rock of the Cotentin, supporting the grauwacke and clay slates, which for the most part appear on the surface of that district. Opposite Cap la Hague, on a rock, called le Gros du Raz, about a mile out at sea, stands a lighthouse.

The Trappist Convent at Bricquebec, and the Castle and Abbey of St. Sauveur le Vicomte, are described in Route 27.

### ROUTE 27.

CHERBOURG TO ST. MALO, BY ST. SAUVEUR, COUTANCES, GRANVILLE, AVRANCHES, MONT ST. MICHEL, AND DOL.

205 kilom. = 127 Eng. m.

*Diligences* daily from Cherbourg by Carentan and Coutances to St. Malo.

Persons travelling in their own carriage may vary the road back to

20 Valognes, the first post station (p. 83), by going round by Octeville (1 m.), where is a Norman church with an octagonal tower and curious carvings (a Last Supper, &c. in bas-relief) older than the reign of Henry II.; and Martinvaast ( $2\frac{1}{2}$  m.), where is a still older church in the same style, and unaltered, with slender half pillars, supporting Ionic capitals outside its semi-circular E. end, and a cornice of grotesque heads under its eaves: its lofty stone vaulted roof is sup-

ported on horse-shoe arches. It stands in a sequestered spot, with a fine old yew beside it. There is a fine *Castle* still inhabited, hard by. Bricquebec (8 m. from Valognes), a village including an ancient *Castle*, whose lofty donjon keep, 100 ft. high, in shape a decagon seated on a high mound, remains tolerably perfect (date 14th century), as well as the walls of the outer enclosure. Other portions are as late as the 16th, and some as early as the 11th century. It belonged in turn to the families of Bertram, Paisnel (Paganel), and Estouteville. It was taken from the last by Henry V. after the battle of Agincourt, and bestowed on his favourite William de la Pole, Earl of Suffolk, who parted with it to ransom himself from the hands of the French.

In the adjoining forest, on the hill des *Grosses Roches*, are three Druidical monuments of the kind called "Galleries Couvertes." A little more than a mile N. E. of Bricquebec is the *Trappist Convent*, founded 1823 by M. Onfray, on a spot of ground just cleared from the forest. Its inmates, 32 in number, of whom 12 are priests, are bound by strict vows to silence, communicating by established signs on indispensable matters, living on coarse dry bread, a few vegetables, a salad with a spoonful of oil, a little milk, and a bit of cheese, and one plateful of a meagre potage, which on fast days is reduced to 6 oz. of bread in the morning, and 2 or 3 at night, with a fixed allowance of herbs and roots. They are prohibited from wearing linen even when ill, and sleep with their clothes on, upon a straw mattress, piquée, 2 inches thick. They are allowed one sort of meat when sick, but fish is forbidden. They rise daily at 2 A. M. and on fête days at 12 or 1, and spend their time in prayer, reading, and work.

There is a cross road from Bricquebec to St. Sauveur. On quitting Valognes our route separates from Route 26, and turning to the l. passes



by Columby (a church with pointed lancet windows) to

15 St. Sauveur le Vicomte, where there is a picturesque and imposing *Castle* of the Tessons and Harcourts, but given by Edward III. after the treaty of Bretigny to John Chandos, one of the most famous captains of the wars of Edward III. and the Black Prince. He built the square and lofty keep tower, one of the gateways, and other portions. In the 17th century it became a hospital, and continued such down to the Revolution. Although falling to ruin, at present it is the best preserved feudal fortress on the Continent.

Here are also ruins of an *Abbey*, which in 1831 were being pulled down for the sake of the materials. The church was beautiful, the ground-work Norman (1067—1160), with additions, in the pointed style, of the 13th century.

Between St. Sauveur and Bériers the post road passes near the *Abbey of Blanchelande*, founded by Richard de la Haye, a favourite of Henry II. (1115—85) who had been captured by corsairs, and passed many years in slavery. It is beautifully situated, and consists of the abbot's house, still perfect, and inhabited by a farmer, and part of the *Church*, in which late insertions have been added to an original Norman structure.

10 La Haye du Puits. The castle, dating from the 11th cent., the only thing of interest in this obscure little town, has been pulled down within the last 15 years to mend the roads! The last remains, a fine old machicolated tower, have probably by this time disappeared.

At Lessay is another abbey and church in the Norman style, begun in the 11th cent., but not consecrated till 1178. "It is of one character, plain, but grand throughout; and possesses a noble central tower. The W. portal is more ornamented than the other parts, and exhibits the dog-

tooth moulding, which does not appear in England till nearly the end of the 12th century."—*Knight*.

18 Périers.

16 *Coutances*. (*Inns*: H. de France, dear, 1846—*G.*; H. d'Angleterre; tolerable.) Coutances, at present a somewhat lifeless town of 8957 inhab., is built upon a nearly conical hill, the summit of which is occupied by the *Cathedral*, proudly predominating over other buildings, with its 3 towers. The high road, carried in a broad winding terrace along the flank of the hill, round the outskirts of the town, forms an agreeable walk, while on the opposite or E. side are more formal and gloomy promenades closely planted with avenues of trees.

The *Cathedral* is one of the finest churches of Normandy, in the early pointed style, free from exuberant ornament, but captivating the eye by the elegance of proportion and arrangement. "The whole is of a piece, complete in conception and execution. The lofty towers terminating in spires, both finished and alike, flank its W. front." "Its interior is very lofty, more than 100 ft. from the floor to the keystone of the vault. Cluster piers divide the nave from the aisles: coupled pillars surround the choir (which ends in an hexagon). Most of the windows are of later date than the body of the building."—*Knight*. The peculiarities of this cathedral are, the side porches close behind the towers; the open screens of mullioned tracery, corresponding with the windows, which divide the side chapels; and the excessive height of the choir, which has no triforium, only a balustrade just before the clerestory windows. The central tower is wonderfully fine in the exterior; it is apparently an expansion of the plain Norman lantern as at Caen. Some of the painted glass is in the oldest style; diapered patterns in a black outline, on a grey ground."—*Palgrave*.

A magnificent cathedral was built

at Coutances in the 11th century with contributions partly furnished by Tancred de Hauteville and his 6 sons, the conquerors of Sicily and Apulia, who were natives of the diocese of Coutances; "it was consecrated 1056 in the presence of William Duke of Normandy, 9 years before he conquered England."

Some of the antiquaries of Normandy have maintained that the existing edifice is the one completed at that time, and have claimed in consequence for their country the invention of the pointed style in the 11th centy.; but as no buildings either in W. France or in England were constructed in that style until 130 years after, and as, on the contrary, all the buildings erected during that period are in the round style; for instance, the church of Lessay, only 9 m. off, consecrated 1178; there is no reason to concede their claim. The evidence upon which they found it is, that the *Livre Noir* (a mere account of the advowsons of the diocese, compiled 1250) makes no mention of the rebuilding of the church after the 11th centy. There exists, however, proof, from inscriptions on the walls of the side chapels, that several of them were dedicated, and therefore probably built, in the latter half of the 13th centy. (1274), and it is also known that the church was nearly ruined in 1356 by the army of Geoffrey d'Harcourt, so that it must have needed serious repairs, though the record of them is lost, executed probably about the end of the 14th centy. (See *Knight's Normandy*.)

From the top of the fine lantern tower a view may be obtained of the sea, with the distant island of Jersey on the W., and of the rock of Granville.

The *Ch. of St. Pierre* is in the florid Gothic style of the 15th centy.

The steep and narrow valley which bounds the town on the W. and is traversed by the terraced road leading to Granville, before mentioned, is

crossed by the remains of an *ancient Aqueduct*, consisting of 5 perfect arches and 15 piers supported by buttresses, called *Les Piliers*, which is also the name given to the village, or suburb, in which it is situated,  $\frac{1}{4}$  m. out of Coutances. In most guide-books and descriptions of the town it is called a *Roman aqueduct*, but its pointed arches, its buttresses with offsets, and coarse irregular masonry, prove clearly that it is not so, but a work of the middle ages, probably monkish. According to Dawson Turner it was erected in the 13th centy. by one of the noble family De Paisnel (Paganel).

*Coaches* to St. Lo (Rte. 32) daily.

Those who love old Gothic ruins, either for their picturesqueness or architecture, will be repaid by an excursion hence to the *Abbey of Hambye*, about 13 m. to the S. E. It may be taken on the way to Granville, making a *détour* of 6 or 7 m. A good road leads through a pleasing but hilly country by Mesnil l'Aubert and St. Denis le Guest, leaving *Hambye l'Eglise*  $\frac{1}{4}$  m. to the rt., to Bourg d'Hambye, a scattered village, with a small but clean cabaret furnishing only homely fare,—coffee, milk, cheese, and cider. The old *Castle* of Hambye, whose keep, 100 ft. high, stood on an eminence over the Bourg, is swept away to mend the roads. Happily a better spirit is now abroad in France, and the government at present holds out an example to England, of zeal for the preservation of the many noble or curious edifices dispersed over the country.

It is a pleasant walk of  $1\frac{1}{2}$  m. from the Bourg to the *Abbey*, but the road thither, through narrow lanes, is practicable only for light cars.

The little *Abbey of Hambye* nestles in a retired valley, sheltered under picturesque cliffs by the side of a trout stream (the Sienne), the beau idéal of a monastic site. The roof and W. end are gone, the ivy begins to creep up the mouldering walls, and destruction is advancing apace, yet



there is much beauty in the narrow arches which enclosed the choir, resting on columnar piers, in the style of the 15th centy. Behind them are side chapels much older, having round and pointed arches in combination, which marks the period of transition. The tower in the centre of the cross rests on square piers which become octagonal below by chamfering. The convent buildings are now occupied by a farmer. The *Chapter House*, a double pointed vault elegantly groined, resting on angular pillars and entered by a fine doorway deep sunk in its early English mouldings, is now turned into a woodhouse: it should be seen. This abbey was founded by William de Pagnel 1145, but renovated, or probably rebuilt, in the 15th century, by Joanne de Pagnel, the last of her family, who was buried in the church with her husband Louis d'Estouteville, the defender of Mont St. Michel against the English (p. 96). Their tombs were destroyed at the Revolution.

About 5 m. from Hambye is *Perci*, cradle of the earls of Northumberland. The high road to Granville may be regained at Bréhal.

The direct road from Coutances to Granville has no interest.

19 Bréhal. Trees diminish in size and number on approaching the sea, glimpses of which and the island of Chaussey are seen at intervals. The entrance to Granville is by a steep descent, excavated partly through a deep hollow way; on the rt. a natural wall of rock separates the road from the sea-shore, and through a gap cut in it access is afforded to the baths and sea-beach. In front rises a high hill, its slope cut away evenly and levelled, until it is as steep and smooth as the roof of a house, in order to form a glacis for the fort on its top. A bend in the road presently discloses to view the lower town and harbour.

10 *Granville*.—*Inns*: H. du Nord and Trois Couronnes, neither first rate. This is a small but tolerably prosperous seaport (7,600 inhab.), chiefly resorted to by fishing vessels,

but driving some commerce along the coast and with Jersey (33 m. distant) and Guernsey.

Its situation is singular, built in steps or terraces under a rocky promontory projecting into the sea, surmounted by the fort, whose presence restricts many of the buildings from rising above one story in height. Under the shelter of this eminence lies the little port, screened by it from the N. winds. A new town is gradually spreading itself along the low margin of this harbour, and up the banks of a stream so small that it is generally swallowed up in soap-suds, and contributes, with the filthy abominations of the town itself, especially at low water, when the harbour is drained to the lees of mud, to produce a state of atmosphere barely tolerable. The sombre hue of the buildings, whose walls are dark granite and their roofs black slate, renders Granville on a near examination as unattractive to the sight as to the smell, and moreover it contains no objects of interest.

The stranger desirous to rescue himself from *ennui* must repair to the noble *Pier*, begun 1828 and still unfinished, enclosing an older one in its much wider circuit. It is very strongly built, so that guns can be mounted on it. The tide rises and falls here at times from 40 to 44 ft.

*Steamers* go hence to Jersey (in 3 hours) and to St. Malo once a week.

The *Church* at the W. end of the town is a low, gloomy building, chiefly in the late flamboyant style, though it has some round arches. It is of grey granite, even the capitals of its columns being worked in that hard stone.

In order to ascend the hill above the old town it is advisable not to thread the labyrinth of filthy alleys, steep slopes, and stone steps which compose it, but to issue out by the road to Coutances, and then scale the steep slope no farther than the walls of the fort, a point which commands a good sea view. Close under the cliffs lie the *baths* (*Salon des Bains*)

and *reading room*, which can be approached only through the breach in the rock before alluded to, leading also down to the sands, a fine smooth and broad expanse, quite shut out from the town. There are no machines; instead of them bathers are enclosed in cases of canvas carried in the fashion of sedan chairs, and they must walk into the water thickly clad: the ladies led by women: the men are banished to the distance of  $\frac{1}{2}$  a m. to the N.

Though Granville is not a particularly strong place, it resisted effectually the attack of the peasant army of *Vendeans*, 30,000 strong, on their ill-fated march, N. from the Loire, in 1793, led on by the gallant Larochejacquelin. The inducements of the royalists to make this attempt were the hope of opening a communication by the sea with England, whose government had promised to send them succour; and to secure a fortified place where they could deposit in safety the women and children, the sick and the priests, who embarrassed the operations of the army. The *Vendeans*, being destitute of artillery to breach the ramparts, were unable to resort to a regular siege. The attempt to storm the place, though conducted with the most dashing courage, was foiled. More than once these brave soldiers gained the ramparts, sometimes supplying the want of scaling ladders by sticking their bayonets into the chinks of the masonry, but as often they were swept off by grape and musketry from the walls and gunboats in the harbour, until at length they were forced to retire with a loss of 1,800 killed. Their army never advanced farther N.; this was the culminating point of their success, and from henceforth they were compelled to retreat. During this attack the suburbs of the town were set on fire by the republican commander of the fortress and burnt down.

It is a very pretty ride from Granville to Avranches; the view ob-

tained from the height, after crossing the wooded dell of Sartilly, of the peaked rock of Mont St. Michel, is especially striking.

About 4 m. N.E. of Sartilly is the ruined abbey of *Luzerne*. The church, in the transition style, is tolerably perfect: it was completed 1178, except the nave, which is later. The conventual buildings, turned into a cotton mill at the Revolution, are fast going to decay. The road from Sartilly is wretchedly bad.

26 Avranches. — *Inns*: H. de France; H. de Bretagne; both tolerable; H. d'Angleterre. Avranches (*Abrancæ*), a town of 7,269 inhab., is now chiefly remarkable for its very beautiful situation, on the sides and summit of a high hill, the last of a widely extending ridge, rendered accessible for the high road by broad terraces carried up its steep slope in zigzags. The view which you obtain in ascending, and especially that from the little mound on the l. of the road before you enter the town, in front of the Sous-Préfecture, is perhaps the most beautiful in the N. of France. The landscape abounds in wood with partial clearances of well-cultivated corn land, through the midst of which winds the river, flashing in glittering pools until expanding into a broad estuary it meets the sea, which borders the horizon. But the prominent feature of the view is the peaked rock of Mont St. Michel, and the twin islet of Tomblaine rising grandly from the hem of the waters.

Under this mound is a *Public Walk* planted with trees, formerly the garden of the archévêché, in the midst of which a statue of General Valhubert, a native of Avranches, who fell at Austerlitz, is set up.

The cathedral of Avranches, one of the noblest in Normandy, and the chief ornament of the town, was destroyed by the mob at the Revolution: its site remains an open platform, commanding an extensive view, and now named *Place Huet*, from the celebrated Bishop of Avranches.



All traces of the church are swept away, save the stone, now protected by a railing, which formed the step of the N. door upon which Henry II. kneeled, a humble penitent, before the Papal Legates, to make atonement for the murder of Becket, "which had affected him more than the death of his own father or mother." After swearing on the Gospels that he had neither ordered nor desired it, he here received the Papal absolution, 1172.

There are some portions remaining of the old *ramparts* of the town.

Another point of view, preferable perhaps, in some respects, even to that above described, is obtained from the *Jardin des Plantes*.

There is an extensive *Public Library* here, containing 10,000 volumes and some old MSS., among which was discovered a copy of Abelard's treatise called "Sic et Non," published 1836 by M. Cousin.

The beauty of the situation, the salubrity of the air, and the cheapness of living, have rendered Avranches a favourite residence of the English, who form a considerable colony here. The *English Ch. Service* is performed in a room once a barrack, in the Boulevard de l'Ouest, where it joins the Rue Sanguière.

The *Post-office* is in Rue St. Gervais.

There is a way practicable for a light carriage, with a guide, from Avranches to Mont St. Michel, across the sands when the tide is out; but as there are two watercourses to wade through or cross in a boat, it is preferable to go round by Pont Orson. As is the case on Lancaster sands, the rise of the tide here is so excessively rapid at times, that a fleet horse, it is said, could not outrun it.

In going to Pont Orson and Dol you quit Avranches by another series of zigzags overlooking the bay of Cancale with Mont St. Michel in the midst, rising above a beautiful foreground of trees, and at Pont au Baud, at the bottom of the hill, you cross the little river Selune.

At Louis a cross road, very bad, turns off on the rt. to the Mont St. Michel by Ardevan.

22 Pont Orson. *Inn: Croix Verte*; ~~cannot be recommended to stop at,~~ but it will furnish a horse and car for 5 fr. or 6 fr. to go to Mont St. Michel, and this is the best place to stop.

The *Castle*, now entirely swept away, was intrusted by Charles the Wise, 1361, to Du Guesclin, to hold as a frontier post against the English. During his absence on a foraging expedition, however, it was very nearly lost, through an understanding between an English prisoner, Felton, and the waiting-maids of Du Guesclin's lady. The attempt was discovered, as the enemy were scaling the walls, by his sister, a stout Amazon, who overthrew the ladders into the ditch, and the treacherous waiting-maids were sewed up in sacks and drowned in the river!

The granite *Church*, partly Norman, with a transition W. end and pointed choir, contains, in the N. aisle, a singular series of carvings in stone representing the Passion—but so mutilated as to lose much of their value; also a very old stone altar table, with sculpture mutilated in the N. aisle.

A good macadamised road, leading from Pont Orson to Mont St. Michel, 5 m., renders Pont Orson by far the best approach to the mount. It passes near Beauvoir and Ardevan, where are the remains of conventual farm buildings, anciently belonging to the monks of the mount. The road terminates on the margin of "la Grève," i.e. the sands, extending for many square leagues all around the mount, and left bare for 4 or 5 hours by the sea, which interrupts the passage to it between 1 and 2 hours near high water. "At neap tides (aux eaux mortes) the rock is not surrounded by water at all, at any part of the day. At spring tides (aux eaux vives) it is surrounded twice each day, and then the sea sometimes breaks into the soldiers' mess-room."—G. B. A.

The distance across the Grève to the mount is about a mile; the driest track is firm and perfectly safe for horses or carriages, but on either side are quicksands, which render it dangerous to diverge. There always remain behind a few pools which would reach above the ankles of a pedestrian. There is something mysterious and almost awful in the aspect of this solitary cone of granite, rising alone out of the wide, level expanse of sand. One might imagine it the peak of some colossal mountain just piercing through the crust of the earth, but deprived, at the moment of its appearance, of the geological force necessary to rear it aloft. Slight as is its elevation, its isolated position in the midst of the sea, and its heaven-pointed top, render it the prominent object of every view from the surrounding coast, and from a long distance give it the appearance of being much nearer at hand than it really is. On approaching it, it is found to be girt round at its base, by a circlet of feudal walls and towers, washed by the sea; above these rise the quaint irregular houses of the little town, plastered as it were against the rock, and piled one over another. Above them project the bare beds of rock, serving as a pedestal from which the lofty walls, high turrets, and prolonged buttresses of the conventual buildings are reared aloft, surmounted in their turn by the pinnacles and tower of the church (now bearing a telegraph) which crowns the whole, and forms the apex of the pyramid.

Not inferior in interest to its outward aspect are the historical associations connected with this shrine of the Archangel Michael—the successor of Bel and the Dragon—the saint of high places. Holy hermits succeeded to Pagan priests in the possession of this natural temple, which Norman dukes and kings further honoured by building a church, and converted into a fortress almost impregnable in ancient times.

Henry I. here effectually resisted his two elder brothers. Here Henry II., in 1166, kept his court and received the homage of the turbulent Bretons, whom he had subdued with a strong arm. This was the only fortress which held out for the French king when all Normandy was overrun by the armies of the conqueror of Azincour; successfully withstanding 2 sieges, in 1417 and 1423, under the brave Louis d'Estouteville. The shrine of St. Michel was for ages visited yearly by thousands of devotees from far and near, and the records of the convent preserve the names of more than a dozen royal pilgrims who have repaired hither to prostrate themselves as penitents before it, and to load it with their bounty. The Revolution dispersed the monks, interrupted the pilgrimage, and changed the destination of the building to a Prison, in which 300 aged priests were immured until death should release them. Its prisons and oubliettes, however, are of far greater antiquity. Who has not heard of the iron cage of St. Michel, which, though originally of metal bars, was afterwards changed to one of thick beams of wood placed 3 inches apart? Its last occupant was an unfortunate Dutch journalist, who was seized most unjustifiably, beyond the territory of France, for having abused the unscrupulous tyrant Louis XIV., who treated the Dutchman as he did the Italian prisoner of the iron mask. St. Michael's Mount in Cornwall, which bears so remarkable a resemblance to this, though on a smaller scale, was one of the foreign dependencies of the abbey.

The entrance to Mont St. Michel is by 3 gates, one within the other, the second flanked by two of the cannon with which the English forces of Henry V. ineffectually bombarded the mount in 1424, firing from them stone balls 1 ft. in diameter. Near this the arms of the knights of St. Michel, with a lion for supporter, are seen carved in the wall: the third



gate is provided with a portcullis, and within it is the little inn (not very inviting; crabs, shrimps, and other fish may be got here). The town (so to call it) consists of one narrow, steep, and very foul-smelling lane. The best way of ascending is by the ramparts, turning to the rt. after passing the gate, up a succession of grass-grown flights of stairs "hanging to the side of the rock," provided with machicoulis at the side to annoy an enemy below. The uppermost gateway, leading into the castle-convent, stands midway across a flight of steps, and is flanked by 2 bartizans or turrets; it "is very scenic and baronial," built probably 1257; but the chamber of knights and princes now re-echoes to the clank of chains and the rattle of the shuttle and beam. The present destination of the building is a prison for ordinary criminals and political offenders. For this reason only parts of it are accessible for the minute examination of strangers; and others are concealed by screen-partitions. The formality of delivering the passport, and requesting admission of the governor, having been gone through at this gate, the stranger is conducted by dark mysterious vaults and passages, up and down gloomy stairs, to the *Cloisters*, the most beautiful part of the building, and a gem of Gothic architecture, unique of its kind, built between 1220 and 1228, and "strangely moresque." Towards the court they are supported by a double row of pointed arches resting on thin granite pillars, leaving an exquisitely groined narrow vault between the rows. The pillar of one arch alternates with the point of the next, so as to allow a most graceful carved volute or sprig, issuing from the capital of every alternate pillar, to be seen. The spandrels of the arches are filled up with a vegetative creation of foliage, sprigs, flowers, garlands, such as is scarcely to be equalled any where for fanciful variety, and sharpness and excellence

*France.*

of execution; the whole is surmounted by a cornice of flowers, and is in good preservation. It highly merits to be drawn in detail. The arches and carvings are of soft limestone brought from a distance; all the rest of the buildings are of granite, and the rock of St. Michel itself is of that stone.

The *Church* of the convent consists of 2 parts, of different ages and styles. The Norman nave, in the massive style of the 11th century (1060), with slightly ornamented capitals, and a wooden roof, is now used as a chapel for the convicts. The pointed Gothic choir is of the 15th century (1452—1521):—the mouldings of the arches are carried down into the reeding of the piers without any interruption of capitals. The arches are closed up with walls, into which curious Scriptural bas-reliefs, such as Adam and Eve driven from Paradise, Noah's ark, &c., St. Michael killing the dragon, very grotesquely treated, are let in. The piers supporting the central towers having given way, owing to the injury they received from a fire, the last of the 8 or 10 conflagrations which, at different times, have consumed the abbey, the arches of the transept (also Norman) are staved up by a complicated framework of timber to prevent the roof falling.

The *Chambre des Chevaliers*, below the cloisters, is a noble hall or nave, of 4 finely-vaulted aisles, supported on 3 rows of pillars, and measures 98 ft. by 68. The date of its construction is supposed to be the 12th century. The chapters of the knights of the order of St. Michel, founded 1496 by the bigot Louis XI., who twice repaired hither as a pilgrim, were held in it. This is now filled with the looms, at which the prisoners are compelled to work, and is not shown to strangers. La Salle de Montgomery is also a fine Gothic apartment.

Beneath the choir of the church a circle of drum-like pillars, set very close together, with one in the centre, supports the superincumbent weight,

and forms a curious crypt. The view from the top of the church, elevated 400 ft. above the sands, from amidst its florid buttresses and pinnacles, now much mutilated, is curious. The Rochers du Cancale, on the coast of Brittany, the town of Avranches, and the neighbouring rock of Tombelleine, ~~Tomba-Beli, on which, as well as on St. Michael's rock, the god Bel was worshipped in Pagan times,~~ are the most conspicuous objects; all around is, as the tide ebbs or flows, either a waste of sand, interspersed with pools and channels of rivers, or a wild expanse of tossing waves.

~~Owing to the short stay the sea makes round the walls at every tide, and the hillocks and sandbanks which intersect the sands, the castle is hardly accessible by a boat, and from this circumstance, and its amphibious position, changing twice a-day from land to water, its strength as a fortress arises.~~

The river Couësson, crossed by a bridge on quitting Pont Orson for Dol, forms the boundary between Normandy and Brittany. A fertile and very picturesque country succeeds, well wooded; in fact, one entire orchard, the corn-fields being invariably planted with rows of fruit-trees. A last view is obtained of Mt. St. Michel from a lofty hill over which the road is carried.

The caps worn by the women hereabouts consist of a piece of white linen, bent like a roof, laid on the top of the head, the front, or gable, turned up in a sort of scroll, exactly corresponding with that seen on monumental effigies in English churches, of ladies of the 15th and 16th centuries (see p. 108).

19 Dol.—Inns: La Grande Maison, not very good; homely, but not dear;—Hôtel de Nôtre Dame.

Dol is a remarkable town, as bearing thoroughly the aspect of ancient days: the black hue of the granite of which its houses are built, contrasting sometimes with splashes of whitewash dashed over them, the heavy projecting gables, the arcades of

various heights and patterns, running under the houses, the quaintly carved granite pillars on which they rest, all give a peculiar character to the place, and offer some good bits for the artist's pencil, while he may fill a sketch-book with costumes in its marketplace. It has 3990 inhab. and a considerable corn market held in a desecrated church (des Carmes) distinguished by a fine flamboyant W. window and a Norman nave.

The chief building is the *Cathedral* (before the Revolution an episcopal see), built of sombre grey granite, uniformly in the early pointed style, except the porches; that on the S. leading into the nave being florid, and having carvings in white stone like those in the cloister of Mont St. Michel. The arches of the nave have deep mouldings, and rest on circular piers, composed of a group of 4 columns, the inner one towards the nave being detached half way up to the roof, where it becomes engaged like the rest. The choir, more ornamented than the nave, but in the same style, has a square E. end, like the English churches, but behind the high altar is an open arch of two divisions separated by a slender pillar admitting a view into a small Lady Chapel behind. The space above this arch is occupied by a large E. window filled with old and good painted glass. These are the most striking points in this fine edifice, which is worthy of attention for its similarity to the Gothic of England; indeed many of the churches of Brittany are said to be the work of English architects.

There is an antique building called *le Palais* or *Maison des Plaidis*, apparently Romanesque.

The old *walls* of Dol remain tolerably perfect, wanting the gates: many of their flanking towers and bastions are surmounted with deep machicoulis, and the whole is surrounded by a deep ditch. A high *Terrace* walk has been formed on the outside of this, and planted with trees. On the side of the town next the



(Mount St Michel)

The Sea has receded from this coast of late years that it does not reach the Mount except at Spring tide and then rises with such rapidity as to be extremely dangerous especially as it renders the sand quicks for some distance in advance of it.





cathedral a view is obtained from this walk of the solitary eminence of Mont Dol, a granite rock something like Mont St. Michel, only rising out of the dry land. (See below.)

These antiquated fortifications of the 15th and 16th centuries were defended by the Vendéans after their retreat from Granville against the Republican army, which was beat off after a bloody combat of 15 hours' duration, and compelled to retreat.

The tract of land between Dol and the sea, a distance of 3 m., is chiefly marsh gained from the waters by embankments; very fertile, but teeming with miasma, which, however, has diminished of late from improved drainage. A tremendous irruption of the sea, reclaiming its own in the beginning of the 17th century, overwhelmed this district.

About a mile outside of Dol and  $\frac{1}{2}$  m. to the l. of the Rennes road is one of those Druidical stones, so common in Brittany, called Menhirs (see p. 108). It is known as *la Pierre du Champ Dolent*, a name which probably marks it as a funereal monument, perhaps on some field of blood or battle. It is a rude, skittle-shaped obelisk of granite, a single block 30 ft. high above ground, and 8 or 10, it is said, below, rising in the midst of a corn-field, and surmounted by a wooden cross.

On the way to St. Malo you pass on the rt. the *Mont Dol*, a granite rock surmounted by a telegraph rising out of the flat land, and most probably once an island in the bay of Mont St. Michel, for the sea no doubt once extended thus far. Where the road reaches the present margin of the bay the shore is lined by a long scattered village, composed of nearly as many windmills as cottages. Not a boat can approach them, owing to the shallowness of the water, although the tide comes up to their doors twice a day. On the W. shore of the bay, however, is the small port of *Cancale*—4880 inhabitants—visible on the rt., backed by high cliffs, famed for the

oyster beds on the *Rochers de Cancale* below them, whence Paris and a large part of France are supplied.

In 1758 an army of 14,000 English, under the Duke of Marlborough, landed here, but after fruitlessly summoning St. Malo, which was found too strong to be taken by assault, they re-embarked, having burned a few small vessels, and, as Walpole said, "The French learned that they were not to be conquered by every Duke of Marlborough."

28 *St. Malo*.—*Inns*: H. de France, kept by M. Gogu  , once cook to Lord Melbourne, married to an English woman; very good, and not dear; rooms at 1, 2, and 3 frs. per bed. Table d'h  te at 5, 3 frs.; at 7, 2 frs.: d  jeuner    la fourchette, 2 frs. 50 c. The house is the one in which Ch  teaubriand was born. H. de la Paix, good. This fortified seaport town (pop. 10,100) may be styled a little French Cadiz from its position on a rocky island (l'  le d'Aron) communicating with the mainland by a long causeway called *Le Sillon*: the mouth of the river Rance, which forms the port, being separated from the open sea by the island and this causeway. The town fills the island completely, so that its picturesque walls and flanking towers, surmounted by a deep cornice of machicoulis, rise at once from the water's edge, washed by the waves, and the houses and buildings squeezed closely together, having no room for lateral extension, rise to the height of five or six stories above its narrow and filthy lanes.

The tides rise here higher than at any other point in the Channel, viz. to an elevation of 45 to 50 ft. above low water mark, and the harbour, which is protected by a stout pier, is drained perfectly dry at ebb, so that carriages and foot passengers cross it to go to the populous suburb St. Servan (9984 inhab.), in places covered an hour or two before with 4 fathoms of water. But a solid wall of granite has been thrown across from St. Servan, with lock gates in the centre

wide enough to admit steamers and frigates, so as to retain the tide, and form a floating dock (*bassin à flot*), of very large dimensions. This will open a second approach from the Rennes road to St. Malo, across the bridge to be thrown over the lock gates. A sort of *tête du pont* is constructed to defend it.

The harbour is lined with a broad *quay* running just under the town walls, and here the steamers moor when the tide permits them to enter. The *Town walls* afford an almost uninterrupted walk around the island, and the circuit may be made in  $\frac{3}{4}$  of an hour. The view out to sea is varied by the little archipelago of islands;—white, angular, bare rocks which raise their bristling heads around the roads: the larger ones crowned with forts and batteries. That called *La Conchée* is occupied by a strong citadel built by Vauban; and *Cisambre*, 6 m. off, is also strongly fortified. The smaller isles and the sunken rocks attached to them render the access to the port difficult.

The public buildings are of no interest: on the side of the town nearest the *Sillon*, and separated from it by a bridge, is the *old Castle*, which, together with a large part of the fortifications, may have been constructed in the 16th century by Anne of Brittany, who placed over one of the towers this inscription — “*Qui qu'en grogne, ainsi sera, c'est mon plaisir.*” The *Cathedral*, very capacious and much modernised, has a choir something like that of Dol, and a new gaudy Gothic altar from Paris, with several marble statues worth notice.

The sabbath is more strictly observed by the Malouins, and indeed in Brittany generally, than in most other parts of France.

*English service* is performed here on Sunday,—but there is no chapel.

The statue opposite the *Hôtel de Ville* is that of *Duguay Trouin*, a native of St. Malo (born 1673), and a naval hero of whom the French are

very proud “*parcequ'il a chassé les Anglais sur toutes les mers.*”

The illustrious Châteaubriand first drew breath in the *Rue des Juifs*, No. 15, in the house which is now the *H. de France*, in the room marked No. 5, from the window of which the sea and his tomb are visible. The Abbé de la Mennais, author of *Paroles d'un Croyant*, and Mahé de la Bourdonnais, governor of the French East Indies, who took Madras from the English, 1746, were also Malouins.

On the sea shore by the side of the *Sillon*, just beyond the castle, on the rt. of the road from Dol, are *Sea baths* and a *Subscription Reading-room*. There is a large expanse of sand extending at low water as far as a little rocky island in front, well adapted for bathing, but unprovided with machines.

St. Malo flourished during the war, when it was styled the “*Ville de Corsaires*,” fitting out privateers to prey on the commercial ships of England; many large fortunes were then made.

The best view to be obtained of St. Malo is from the half-ruined *Fort de la Cité*, situated on the promontory a little to the W. of St. Servan, reached by the first turning on the rt. after you enter that suburb from St. Malo. Hence from a considerable elevation you look down upon the town, upon the singular inlets of the sea branching out into the land which form the harbour, and on the archipelago of little islands grouped around its entrance. Among them the islet of Grand Bay, situated to S. W. of the town, chosen by Châteaubriand for his last resting place, and bestowed upon him by the municipality of his native town, is conspicuous. His fellow-citizens have erected a tomb on it to contain his remains. Immediately beneath the spectator on his l. rises the triangular tower of the *Solidor*, a feudal fort 60 ft. high, with flanking towers at its angles, approached by a drawbridge. It is now a prison. At *St. Servan*



the Union Boarding-house is recommended; charges 5 fr. a day, or 100 fr. a month, exclusive of wine. *English church service* is performed in a chapel, Rue Duperré—Sunday at 11.

*Diligences* daily to Rennes (Route 41), and Paris (Route 35), to Brest (Route 36), to Dinan (Route 41), to Dol and Caen (Routes 27 and 31).

*Steamers.* There cannot be a more delightful excursion than that by the river Rance from St. Malo to Dinant. A small steamer ascends and returns with the ebb, when the state of the tide permits; generally every other day. (Route 41.)

*Steamers* twice a week to and from Jersey, where they correspond with the boats to Southampton.

## ROUTE 29.

CAEN TO TOURS BY FALAISE, ALENÇON,  
AND LE MANS.

232 kilom. = 143½ Eng. m.

A daily communication is kept up by diligences, but with interruptions, and the traveller is compelled to wait 3 or 4 hours at a time for the coach which is to carry him on. A separate conveyance runs from Caen to Falaise, and back daily. A *Railway* is in progress. About 7 m. from Caen, and 2 or 3 to the right of the road, lies Fontenay le Marmion, cradle of the family of Marmion.

20 Langannerie. The country for the first 2 stages is bare, open, and monotonous, until the castle of Falaise is perceived on the rt. rising out of a picturesque valley.

6 m. short of Falaise, and nearly 2 to the l. of the road, lie the *rocks of St. Quentin*, sometimes called *Brèche du Diable*, a rocky gorge bounded by precipices, pinnacles, &c. It has been compared with Cheddar Cliffs, only on a much smaller scale.

15 *Falaise*.—*Imm*: H. de France, good. This ancient town of 9,580 inhab. occupies the summit of a lofty platform, bordering on a rocky precipice, or *Falaise*, whence its name.

One very populous suburb has extended into the narrow ravine below this precipice; and another, situated at the distance of 1 m. to the E., called Guibray, now rivals the town itself in size and population, and is distinguished for its Fairs established by William the Conqueror, held in August, celebrated for the horses then brought to market. Falaise is a dull lifeless town, at present, having only one object of interest to the passing traveller—the *Castle*, one of the few real Norman fortresses remaining in France, the ancient seat of the Dukes of Normandy, and the birthplace of William the Conqueror. It is a grand and picturesque ruin, occupying a commanding position at the extremity of the town, where the platform is cut into a narrow promontory by gullies which isolate it on 3 sides, rendering it a place of great strength, until the invention of gunpowder. To this it was indebted for the nine sieges which it had to endure. The approach to it is behind the modern Hôtel de Ville. A college or *grammar school* has been planted within the exterior court. A grassy terrace walk along the ramparts, shaded with trees, leads to the Norman *Donjon Keep*, an oblong square, whose walls, supported by high and massy buttresses, rise abruptly from the edge of the precipitous rocks de Norrou. It is now a mere shell partly filled with rubbish; its walls show traces of herring-bone masonry, and retain several round-headed windows, of 2 lights supported on short pillars, and having capitals carved with Runic knots. In one corner a cell is shown in which, according to the tradition, the Conqueror was born. From those windows and ruined walls you look down into the Val d'Ante, so called from the small stream which runs through it, crowded with mills and tanneries. It was while gazing upon this scene, according to the tradition, that Duke Robert, the father of the Conqueror (like David of old), first espied Arlotte, the tanner's fair

daughter, and became at once so smitten with her charms, that he made her his mistress, and continued faithful to her until death.

The keep is surpassed in elevation by *Tulbot's tower*, a cylinder of beautifully smooth and perfect masonry, rising beside it to a height of more than 100 ft., crowned with a rim of broken machicoulis. Its walls, 15 ft. thick, enclose a winding stair leading to the top, and a well opening into each of the 5 vaulted stories. The chapel is converted into a powder magazine. This tower is supposed to have been built by "Valiant Talbot," who was lord warden of the "Marche Normande," after the capture of Falaise by Henry V., between 1418 and 1450. Henry assaulted the castle from the top of the still loftier cliff Mont Mirat, on the opposite side of the ravine, where traces of his intrenchments still remain: the siege lasted more than 4 months. On the other side of the castle is a relic of another siege, viz. the breach in the wall by which Henri IV. carried the fortress by assault, after 7 days of cannonade, in 1589.

The churches are not remarkable. A considerable portion of the old town *walls* remain, running round the edge of the ravines, through which the stranger may ramble agreeably, either upwards into the suburb of Val d'Ante, the birthplace of the Conqueror's mother, below the castle keep, or issuing out of the picturesque "Porte des Cordeliers," the only gate remaining perfect, he may follow the direction of the Ante downwards through shady lanes, and re-enter the town by the dismantled Porte St. Laurent.

There are several cotton mills in the vicinity, and the weaving of nightcaps occupies a considerable number of hands.

22 Argentan.—*Inn*: Trois Maures (?). A town of 6147 inhab., on the Orne, surrounded by ramparts.

23 Séez (in Route 21).

21 Alençon (in Route 35).

14 La Hutte.

9 Beaumont-sur-Sarthe.

15 La Bazoge.

11 Mans (in Route 46).

21 Ecommoy.—*Inn*: Poste.

20 Château du Loir.—*Inn*: Poste. The *Castle*, after which this village is named, is gone; it was built 1080 by Robert *Eveille-chien*, Duc d'Anjou. The cliffs near this are hollowed into caves, serving partly for houses to more than 100 poor families, partly as cellars for the richer.

20 La Roue in Touraine.

20 TOURS (in Route 53).

### ROUTE 31.

CAEN TO RENNES BY VIRE, MORTAIN, AND FOUGÈRES.

171 kilom. = 106 Eng. m.

2 Diligences daily.

The road conducts through some of the most pleasing scenery in Normandy; at first it ascends the valley of the Odon, in which lies

13 Mondrainville. We now enter the *Bocage* of Normandy, a pleasing wooded district, situated about the source of the Orne, Odon, and Vire.

12 Villars Bocage; here is an hospice founded 1366, by Jeanne Bacon, of Mollay.

15 Ménil au Zouf.

19 Vire (*Inn*: Cheval Blanc, not good), a most picturesque antique town (pop. 8000), the capital of the Bocage, romantically situated on a lofty eminence, bordered by deep ravines. A Norman *Castle* occupies the extreme point of the promontory, naturally inaccessible on 3 sides, owing to the precipices which surround it; and on the fourth originally separated from the town by a deep ditch. It is now reduced to the fragment of the tall *keep*, a construction of the 11th cent., having been dismantled 1630, by order of Richelieu, but its ruins are carefully preserved, and surrounded by a charming pleasure-ground belonging to a private individual, planted with trees, extending



over the site of the castle courts, and forming one of the chief attractions at Vire. From its elevation it commands a view of the country around, and especially of the two valleys beneath it called par excellence *Les Vaux de Vire*, whence comes the word Vaudeville, originally applied to the merry and humorous drinking songs composed among these valleys by one Oliver Basselin. He was a native of Vire, and owner of a fulling mill, which still remains at no great distance from the town. He flourished in the 15th centy., and is reported to have been present at the battle of Formigny (p. 82). His chansons, chiefly in praise of good wine and his native province, soon became so popular over France, that their name was transferred to those truly national dramas peculiar to the French stage, in which the plot or story is carried through chiefly by songs.

In the narrow and steep streets of Vire may be found many specimens of ancient domestic architecture, well adapted for the artist's sketch book. The *Church of Notre Dame* is a fine building; but the chief boast of Vire are the *walks* in and about it. Besides the promenade above mentioned, particularly agreeable are the *walks*, adjoining the fish ponds, famed for their huge tame carp which come eagerly to be fed by the stranger's hand. The terraced paths are carried most agreeably up the hill side amidst thickets and plantations, commanding at intervals very pleasing views.

But almost all the valleys in the neighbourhood, generally shut in by craggy heights and copse-covered slopes, deserve to be explored. They abound in mills of paper and *cloth*, in which the clothing for the French army is made. This gives employment to half the inhabitants of Vire. On the 10th August the "Fête des drapiers" is celebrated here, and more than 10,000 persons assemble under the apple trees, which are illuminated at night for the occasion.

Vire has a gastronomic celebrity

for chitterlings (andouilles) and for pastry.

10 m. S. E. of Vire is Tinchebray, where Robert of Normandy succumbed in battle to his younger brother Henry, 1106. This victory secured a throne to the one prince, and a prison for life to the other.

13 Sourdeval.

10 Mortain. (*Inn* enlarged and improved: prices low; not bad to stop at. It is opposite the Church.) Mortain, a decayed and lifeless town, occupies a position nearly resembling that of Vire, and at least equally romantic. "The valleys are narrower, the steeps more rocky and better wooded; the river at the bottom is more considerable, and a wide extent of distant Campagna is seen through the jaws of the ravine. The whole scene put me in mind of Italy, and of Tivoli, and the cascades which we heard from above and visited afterwards helped to keep up the resemblance."—*G. Knight*.

"You *descend* to the side of the old *Castle*, but when you arrive there you find it a most suitable spot for an eagle's nest. A jutting cliff, only connected to the height by a narrow ledge of rock, afforded just space enough for a feudal fortress. The strength of this fortress made it once a place of importance. Here dwelt the brothers and the sons of kings of England." The whole of this venerable structure has been levelled with the dust, and in its place now rises the staring modern *Sous-Préfecture*.

The *Collegiate Ch.* has been groundlessly pronounced to be a work of the year 1082, when a church is known to have been founded here. But the only fragment remaining of that epoch is a circular doorway leading into the nave on the S. side, ornamented with zigzags and saw-tooth ornaments; the rest is of the pure and unmixed early pointed style of the 13th century, and the clumsy junction of the new wall around the old circular portal is very apparent. The arches of the nave

rest on thick short pillars; those of the choir are narrower.

About a mile out of the town, seated in a secluded valley, is the *Abbaye Blanche*, founded 1105. The *Church* is in the Transition style, round-headed windows alternating with pointed. An early pointed cloister also remains tolerably perfect, but the abbey is now a manufactory, and it is quite uncertain how long it will escape destruction.

The *Cascades* of Mortain are the finest, and indeed almost the only ones, in Normandy.

About 8 m. from Mortain are the ruins of the *Abbey of Savigny*, b. 1173, in the Transition style, but partaking more of the round than pointed character.

15 St. Hilaire du Harcouet is the entrepôt for the agricultural and manufacturing produce of a large part of Brittany:—its markets are greatly frequented. The frontier of Brittany is crossed about 4 m. to the N. of

11 Souvigné. Just before reaching Fougères M. de Lescure, the Vendéan chief, died of his wounds, and was buried at the road side—site unknown.

• 16 Fougères.—*Inns*: Poste, good; but bad attendance;—St. Jacques. This town (4635 inhab.), once a frontier fortress, the key of Brittany on the side of Normandy, “is full of picturesque interest. The old town, built on a steep acclivity, shows traces of the Middle Ages; the ancient arcades still obtrude in places upon the streets. It is still surrounded by antique ramparts. There is a *Church* of some architectural interest, and a charming *promenade*, on a high eminence commanding romantic prospects.”—*G.*

Attached to the town walls, at the lower end, is the huge and picturesque ruined *Castle*, of which the Donjon (Melusine) and Tour du Gobel in are probably of the 12th centy.; the rest of the 14th and 16th; and the outer towers and curtains are still later. Its approaches and defences are very curious.

20 St. Aubin du Cormier; near this La Trémouille gained a decisive victory, in 1488, over Francis II. Duke of Brittany, the Duke of Orleans, afterwards Louis XII., and others, who had leagued against the Crown.

10 Liffré.

18 RENNES (in Route 35).

## ROUTE 32.

### BAYEUX TO ST. LO AND AVRANCHES.

90 kilom. =  $55\frac{3}{4}$  Eng. m.

*Diligences* daily.

13 Vaubadon.

The road traverses a portion of the extensive forest of Cerisy. The *Abbey of Cerisy*, one of the most considerable in Normandy in olden time, lies on the rt. of the road. The church still exists, an early Norman building of the same plain character as St. Stephen's at Caen (p. 75). It was founded 1030, by Robert, Duke of Normandy, and completed by his son, William the Conqueror.

21 St. Lo.—*Inn*: Soleil Levant; far from good, and very dirty.

This town, named from St. Lo, or Laudus, who lived in the 6th centy., and came from this part of Normandy, is picturesquely situated, and its *Cathedral*, standing prominently on the brow of the hill, has an imposing appearance, with its double towers and spires, but as a building it is inferior to those of Bayeux or Coutances. The W. end is florid, of the 15th centy.; it has three fine porches, but the upper part is defective and irregular; and, as well as the choir, exhibits marks of slovenliness in its builder. The nave is earlier and better, in the pointed style of the 12th centy. Outside the Church, in the S. W. angle, is a fine stone pulpit, with a pyramidal canopy over it. Charlemagne founded here, in the 9th centy., the once celebrated Abbey of *St. Croix*; but this building was swept away at the invasion of the Northmen, and the present *Eglise de*



*St. Croix*, a very curious edifice in the early Norman style, does not appear older than the 11th centy. The nave arches rest on pillars, and the S. side is plain, and apparently older than the N. Over the round-headed doorway at the W. end is a bas-relief representing St. Lo restoring sight to a blind woman. The adjoining conventual buildings are of late dates; they are now converted into a *Stud* (haras), for improving the breed of horses.

St. Lo is chef-lieu of the Dépt. de la Manche, and numbers 8941 inhab.; it has a manufacture of fine cloth, but possesses no great attraction to the stranger. There is a small terraced platform to the W. of the cathedral, called *Petit Place*, which commands a view of the vale of the Vire.

*Diligences* twice a day to Coutances (Rte. 27), passing within a short distance of *Hauteville*, the humble village which sent forth the bold Baron Tancred and his six sons to conquer Sicily and Apulia. On the way from St. Lo to Vire (Rte. 31) lies the town of Torigni. The building now used

as an Hôtel de Ville is one wing of the *Château* of the family of Matignon, Counts of Torigni, one of whom, by marriage with Louisa Grimaldi, became Prince of Monaco. In 1793 the building was turned into a prison, and the park, terraces, and gardens sold piecemeal.

The *Church of St. Laurent* is early Norman, and that of *Nôtre Dame* retains traces of the same style.

The road from St. Lo to Avranches lies through

19 Villebaudon. The little humble village *Perci* was the cradle of the ancestors of the house of Northumberland.

15 Villedieu les Poêles derives the adjunct to its name from the number of coppersmiths, who drive a thriving trade in pots, pans, and other articles, which the French call *dinanderies* and *quincailleries*. These artificers were originally settled here by the Knights Templars, who employed them in making decorations for churches. Here are many furnaces for melting the copper, and mills for rolling it into sheets.

22 Avranches (Rte. 27).

## SECTION II.

## BRITTANY.

## INTRODUCTORY INFORMATION.

1. Character of the Country. 2. People. 3. Language. 4. Celtic Remains classified. 5. Superstition. 6. Churches, Carvings, Flamboyant Gothic, Bone-houses, Kersanton Stone. 7. Connection with England. 8. Chouannerie. 9. Books to consult. 10. Tour of Brittany. 11. Accommodation for Travellers.

ROUTE	PAGE	ROUTE	PAGE
35 Paris to <i>Rennes</i> , by <i>Versailles</i> , <i>Dreux</i> , <i>Verneuil</i> , <i>Alençon</i> , and <i>Laval</i> (RAILROADS to <i>Versailles</i> ) . . .	113	42 <i>Morlaix</i> to <i>Nantes</i> , by <i>Huelgoat</i> , <i>Carhaix</i> , <i>Pontivy</i> , and <i>Josselin</i> . . . . .	140
36 <i>Rennes</i> to <i>Brest</i> by <i>St. Brieuc</i> and <i>Morlaix</i> . . .	122	44 <i>Brest</i> to <i>Nantes</i> , by <i>Quimper</i> , <i>Lorient</i> , <i>Auray</i> , the <i>Druidical remains of Carnac</i> , <i>Vannes</i> and <i>Roche Bernard</i> . . . . .	143
38 <i>St. Brieuc</i> to <i>Brest</i> , by <i>Paimpol</i> , <i>Lannion</i> , <i>Morlaix</i> , <i>St. Pol de Léon</i> . . . . .	130	45 <i>Rennes</i> to <i>Vannes</i> , by <i>Ploermel</i> .—Excursion to <i>Carnac</i> . . . . .	153
41 <i>St. Malo</i> to <i>Nantes</i> by <i>Dinan</i> , <i>Rennes</i> , and <i>Château-briand</i> . . . . .	135	46 <i>Paris</i> to <i>Nantes</i> , by <i>Chartres</i> , <i>Le Mans</i> , and <i>Angers</i> . . . . .	153

1. There can scarcely be a more abrupt contrast to the smiling land of Normandy than that presented by the neighbouring province of sombre, poverty-stricken Brittany. Here we find an atmosphere of mist and moisture; and a soil based on hard granite, best fitted for heath, furze, and broom, the very broom (*genêt*) which supplied our first Plantagenet with his crest and name. In many points the country bears a strong resemblance to Scotland; the same wide, barren moors, the same deep and picturesque wooded dells, and storm-beaten coasts. Here, however, are no grand lofty mountain chains like the Grampians: the highest ridges of the Menez-Arrés hills, the back-bone of the peninsula of Brittany, rarely surpass 1,200 ft. above the sea level.

2. In civilisation it is behind almost every other part of France: its *inhabitants* are of Celtic origin, speaking a language of their own, allied to, and, indeed, essentially the same as the Welsh and Cornish, so that Breton sailors landing on our coasts can make themselves understood by the Welsh there. It is exclusively spoken to the W. of a line drawn from the point of Finisterre through Chatelaudran and Pontivy; the “Vrai Bretagne Bretonnante,” as Froissart calls it, to distinguish it from “La Bretagne Douce,” where French is spoken. One of the principal objects of interest and study for the stranger in Brittany is its inhabitants, who have been kept distinct from the rest of France by position as well as difference of language.

The peasantry are almost as wild as their country, excessively quaint in their costume, wearing broad-brimmed hats and flowing hair, and in some districts trunk hose (bragous bras = breeks) of the 16th century; in others wrapped up in goat-skins, like Robinson Crusoe, a costume which they retain



as it was handed down from their ancestors. They are usually mean and small in their persons; coarse-featured in face; squalidly filthy in their habitations; rude and unskilful in their agriculture. They are almost unchanged in their manners, customs, and habits: modern innovation has not entirely rubbed off the rust of long-continued habit; old legends and superstitions still retain their hold on the popular mind. They present a curious picture of a primitive state of society; and if a century behind their neighbours in what is called improvements, they are at least not corrupted by revolutions and commotions. In no part of France are the people, both of upper and lower orders, more observant of their religious duties, of festivals, fasts, &c.; nowhere are the churches so thronged.

“There is much picturesque beauty in Brittany, though of a character not so imposing at first sight as that of countries moulded on a grander scale. Scenery of great and winning loveliness is to be found on the banks of the Trieux, the Lannion, the Châteaulin, and the Rance, and in many other secluded and scarcely accessible valleys, where the ‘broomie knowe,’ the wooded dell, and the rocky cliff alternately border the brawling mountain torrent, as it flashes along its stony bed, or is pent up in the still pool of an old water-mill, which looks as if it had stood untouched (as it has perhaps) from the time of the ‘good Duchéss Anne.’ The quaint and antique aspect of the buildings adds much to the picturesque character of the country. Some, as in Dinan, Morlaix, Quimper, &c., are framed of timber, with projecting stories resting on grotesquely carved brackets: but generally the houses both in the towns and villages are of grey granite, with massive round or ogee arched imposts to the doors and windows, often enriched with Gothic mouldings; and presenting, from the peculiar colour and grain of the stone, an appearance of antiquity even in buildings recently erected. The churches again are features of great interest and beauty scattered profusely over the country, and many a ruined castle or tower, or dilapidated ‘manoir’ with its old avenue, huge granite portals, round turrets, and ‘extinguisher’ roofs, recalls the days of the Breton chivalry. Add to these characteristic features, that the country is usually very intricate and thickly wooded, the enclosures being small and surrounded by high earthen banks, upon which, from six to ten feet above the level of the road or field, grows a close phalanx of timber trees, oak, elm, or ash, gnarled and pollarded into grotesque forms, and intercepting all view, so as to give rise to constant excitement, as the scene changes almost at every step that the traveller advances.”—*G. P. S.*

“The Bretons are impetuous and violent in their temper, and give way to furious bursts of passion when angry. Their way of living is homely and frugal to a degree, even when in circumstances to afford better fare. Of drink they unquestionably are fond, but it is not a regular habit with them to indulge in strong potations—water is usually drunk at meals, and cider in small quantities on Sundays and feasts. Wine is hardly ever tasted in the province, but brandy is cheap and good, as in other parts of France. They live much upon buckwheat, made into cakes, and mix rye with their wheat into a coarse meal, which forms a dark-coloured bread; these, with savoury esculents, and at times salt-fish and meat, constitute the staple of their subsistence. With a climate unfavourable to production, or rather to the maturity of their produce (for the sun is even more coy in Brittany than in the British Isles), and a soil generally of a cold wet character, the Bretons labour under far greater difficulties than their Norman neighbours as to tillage. Yet if they would be guided by wise advice, much progress might be imparted to their well-doing. Even now some improvements have obtained, especially since 1834, and capital is finding its way to the land, although most

commonly in the shape of a loan to the occupant, who pledges his land for the amount. When a Breton saves a little money, he buys more land, if he can; he never seeks to apply more money to the land he has already under culture. The most perceptible feature of difference, perhaps, between Normandy and Brittany, is that, in the former, large and commodious farm-buildings are observed around the farmer's dwelling, whilst in Brittany it is rare to see a barn, or granary, or any roomy out-house—in short, the Bretons pursue the wasteful habit of threshing out their corn in August, and housing it in the grain; paying enormously for such labour (to an ambulant class called “*les batteurs*”), and losing the otherwise valuable season of warmth and daylight for cleaning and working the soil against seed-time. But having no barns, they must do this. Stacking is unknown, and besides, there is no sheltered floor for threshing on in winter; the threshing grounds, as in Italy (here termed “*aires*”), are in the open space adjoining the cultivator's dwelling, and are composed of bare earth, swept clean. It is a pretty incident in rural life when you behold all the family at this work, in fine weather, singing as the flail twirls to enliven their toil; but the inconceivable drawback which it forms to profitable farming obtrudes itself upon the mind of the traveller and impairs his pleasure at this primitive pastoral picture.”

“The indescribable forms of many of the caps worn by the Bretonnes are worth remarking. Both Norman and Breton caps are pleasing auxiliaries to the scenery, which they enliven by their snowy whiteness. Old point lace is not unfrequently discerned on peasant heads, and these curious and costly ‘*coiffures*’ sometimes adorn the brows of more than one generation in turn. When caught in the rain the women instantly cover their fine caps over with a coloured handkerchief. It is the Bretons who chiefly man the navy of France: their qualities are eminently suited to the seafaring life, and the perseverance and patient courage they display stand out in contrast with the natives of other provinces of France, and denote a totally different origin.”—*G.*

4. Of *Ancient Monuments* of different ages there is no lack in Brittany, and above all, of Celtic Remains; those extraordinary masses of rude unhewn stones whose objects, age, and uses have never been satisfactorily accounted for, but which are supposed to have been in some way connected with the religion of the Druids, and their number would prove this country to have been the chief seat of that mysterious worship. In Great Britain we possess a few, and above all, we have in Stonehenge a more stupendous monument than any elsewhere; but in Brittany the number is enormous; almost every wild heath possesses one or more. They are most numerous, however, on the storm-beaten promontories and islands of the W. coast; especially in the Morbihan, which includes the wondrous stony array of *Carnac* and the monstrous granitic obelisks of *Lokmariaker*, larger than any single blocks at Stonehenge, but now fractured.

These rude Remains are of several different kinds, distinguished by the following names:—

a. *Menhir* (literally long stone: *Ir-min-Sul*; long stone of the sun) is a monolith in the form of a rude obelisk set upright on one end, whose height much exceeds its breadth. There is a menhir near Dol which rises 30 ft. above the ground, but the largest specimen of this class known is at Plouarzel, near Brest; it exceeds 42 ft. in height. Those at Lokmariaker, now laid prostrate and broken by violence, were more than 60 ft. high, and were thick in proportion.

b. *Peulven* (pillar of stone), an upright stone of inferior height to the menhir; the single stones at Carnac are generally of this class.

c. *Dolmen* (from “*taal*,” table, and “*maen*,” or men, stoney, in England



commonly called Cromlech, is an arrangement of rude blocks, by which one or more upright stones are made to support a horizontal block or slab. Sometimes they nearly resemble a table; the upright stones serving merely as props or legs, and are called in French *pierres levées*, or *pierres couvertes*; at others the supporting stones are wide slabs, so arranged as to fit close to one another, and so lofty as to allow a man to walk upright beneath the horizontal roof-stone which they support. Kits Coity House in Kent is an instance of this kind, and there are others in Cornwall, but they are far inferior in size to those of Brittany, which are often 60 or 80 ft. long. The French sometimes call them "*allées couvertes*."

d. *Kistvaen* is similar to the Dolmen, inasmuch as it consists of two rows of upright stones supporting flat blocks; but the stones are smaller, and the whole structure lower and longer; it appears to correspond with the "*Hunnengräber*" of North Germany. The most remarkable example is on the island *Gavre Innis* near Lokmariaker.

e. *Galgal* is a tumulus, barrow, or cairn; the largest known is the *Butte de Tumiac* on the shore of the sea of Morbihan.

These Celtic remains are not confined to Brittany, though most numerous there; they occur almost invariably on some flat open plain at a distance from the hills, in situations corresponding with Salisbury Plain and Dartmoor in England. Brittany appears, like our Mona, to have been the sacred land of the Gauls, the centre of their worship, to which probably the various nations and tribes repaired on pilgrimage at stated times to pay their devotions.

Of the particular destination or object of these rude elevations in general, or of the individual uses of the different classes enumerated above, no satisfactory explanation has been offered. The accumulated ranges, the long avenues of stones of Carnac and Erdevan, amounting to thousands in number, may have stood in the place of temples where rites of initiation and purification, similar to the Grecian mysteries, may have been performed. The upright solitary menhir may have been a symbol of some individual deity, as the sun; the dolmen may have served as an altar or shrine, and the galgal and kistvaen were probably monumental. Equally unexplained are the mechanical means by which a rude people contrived to transport, and to elevate one above another, such huge masses.

5. Their mysterious influence is not yet, by any means, effaced from the mind of the lower orders in Brittany. The first teachers of Christianity in this region found this attachment to superstition so strong, that, after in vain attempting to eradicate it, by overthrowing and destroying these rude stones, they altered their plan to that of engrafting, to a certain extent, their own faith upon the old idolatrous worship of stones and fountains, converting the dolmen into a chapel, and making the menhir serve as a pedestal to a crucifix, which it commonly does even to the present day.

The influence of paganism lingered long in these remote wilds, attached as it was to visible objects: indeed, the inhabitants of Ouessant are said to have been idolaters until within 150 years.

Hence has arisen a strange jumble of Paganism and Romanism; thus pilgrimages are made to fountains by those who desire to be relieved from some malady, by pouring its holy water over the affected part: and visits are paid in the depth of night to some solitary menhir by the barren woman, who hopes to become fruitful by rubbing her bosom against the hard stone. Some of these inanimate objects also are supposed to possess virtue to cure the diseases of cattle. Heathen divinities were replaced by saints, of which the number in Brittany exceeds that of any other part of Romanist Europe;

most of them are peculiar to the country, their names being unknown elsewhere, and their canonisation conferred rather by the popular voice than with the authority of the Pope. Almost every church has its own strange legend, and on its saint's day a pilgrimage or *Pardon* is celebrated, when indulgence for past sins is obtained, and the penitent pilgrims are no sooner shrived than they begin to run up a fresh score at the riotous festivities which follow these assemblies. These pardons, or village festivals, which are nearly equivalent to the German Kirchweih, the Flemish kermes, and the English *wake*, deserve the attention of strangers, from the illustrations they afford of Breton life, manners, and costume.

6. In *Ecclesiastical Monuments* Brittany is not so well furnished as Normandy, but the architecture is of a different style, chiefly the florid or flamboyant Gothic, and of a much later period: indeed, even in architecture, Brittany seems to have been behind the rest of the world, and the fashions of building only reached it when superseded in other parts. The following excellent remarks apply generally to all parts of France, yet will not be out of place here. "The most obvious characteristics of the *Flamboyant style* are the flat 3-centred arches of doorways, the entire independence of different pilasters upon the same pier as regards the vertical height of their base mouldings, the scrupulous interpenetration of different mouldings, and the absence of capitals if the arch mouldings are continued on the pier, or their dying gradually into the pier by penetration, if they are not continued on it."—*G. B. A.* There are some peculiarities in "the Breton style," which render it well worthy the attention of architects. In elaborateness and profuseness of ornament, in the minuteness and delicacy of carving, especially of the foliage, (for the figures are inferior,) there are some churches in Brittany which yield to few in any part of Europe. As instances may be mentioned those of *Folgoat* near Brest, *St. Pol de Léon*, which is remarkable for its exquisite spire, *Théogonec* near Morlaix, *St. Herbot* near Poulahouan, and the cathedral of *Nantes*.

The Department of Finisterre is the quarter in which churches more especially abound, and it is quite as profusely supplied as Lincolnshire, and many of the village churches are of unusual size and richness. "In the churches near Brest, instead of building a tower with 4 walls, containing windows or panel work, the practice seems to have been to raise stages or floors, one upon another on open arches, so as to make a kind of square pagoda, not contracting in dimensions, through which in certain directions the light is seen and the arch piers look comparatively small. This peculiarity deserves attention from architects."—*G. B. A.*

Several of the churches, even in remote situations, as at *St. Herbot*, are decorated internally with *carvings in wood* and stone; roodlofts still exist at *Folgoat*, &c., though scarcely found elsewhere on the continent: painted glass is also by no means uncommon. These very gorgeous churches of Brittany were erected principally from the end of the 14th to the beginning of the 16th century.

Formerly the church-yards and even roadsides were adorned with *Crucifixes* of most elaborate execution, and comprising a multitude of figures; "most of them suffered by the Revolution, but many exquisite examples remain almost as perfect as those of *Plougastel* near Brest, *St. Théogonec*, &c., and hardly a single point of intersection of two roads can be passed which is not marked by a more or less mutilated cross, oftentimes restored by the piety of the present generation."—*G. P. S.*

The *Bone-house* or *Reliquaire* will be constantly found in the Breton churchyards, and illustrates a curious custom. To allow "the rude fore-



fathers of the hamlet" to repose quietly in the grave is opposed to the ideas of piety and affection in these rude people: after a certain number of years the survivors are required to show their remembrance and respect for their parents and relations by removing the skulls and bones from the coffin and placing them in the Ossuary,—where the former are arranged on shelves, open to the view of all, each with the name or initials in black paint written across the fleshless brow. There is a curious Reliquaire in St. Herbot.

One cause of the profuse decoration of these churches, and of their excellent preservation, may be referred to the materials employed—a green stone, peculiar to Brittany, called *Kersanton* (St. Anthony's house), remarkable for the facility with which it is worked, and its tenacity in withstanding the weather. Its composition is not exactly understood, but it is supposed by mineralogists to consist of mica and amphibole, in particles minutely disseminated. It is found only in two localities, on the W. of the harbour of Brest, near the escarped rocks of Quelern, between the river of Faou and that of Landerneau. It is regarded as volcanic, both from its composition and because the rocks adjacent to it show marks of dislocation, caused apparently by its intrusion. The weather has scarce any destructive effect on it, even after the lapse of ages; and its peculiarly bright green colour gives to a portal carved out of it the appearance of being cast in bronze.

Of churches in the Romanesque or Norman style the examples are few; among them are the church of Dinan and the *chapel of Lanleff*, which, after all the disputes of learned antiquaries respecting its origin and great age, is probably merely an equivalent to the round churches of England.

The cathedral of Dol nearly corresponds in style to the Early English; and the tradition of the country attributes it and some of the later churches to English architects. This is not surprising, considering the long and early connection between Great Britain and Little Britain, to the S. of the Channel: *Armorica*, as it was styled, which the careful researches of historians and philologists have proved to have been colonised by natives of Britain after the sixth century, partly during the Roman dominion, partly after the invasion of the Saxons. From Brittany, if we believe the native traditions, we derive our most popular romances, our nursery and fairy tales. Arthur here held his court with the Knights of the Round Table; and the cradle of Merlin was on the Ile de Sein, a low sand-bank in that stormy sea La Baie de Trepasés.

7. Many of the names of places closely resemble those of Wales and Cornwall. Brittany also has its *Cournouaille*, equally celebrated with our own for wrestling matches, still held annually, at which the true Cornish hug is said to be given; and for wreckers, whose infamous trade is promoted by the ever raging sea and iron-bound coast. The Droit de Bris, right of "jetsam and flotsam," is, however, nearly abolished in France as in England; and the time is past when a race or whirlpool was as productive to a landlord as a mine or fishery.

English armies have fought and bled on this soil of Brittany; and the chivalric heroes of our history, Edward III., Chandos, Sir Walter Manny, were opposed to no unworthy antagonists in the Du Guesclins and Clissons. In the castle of Elven, Henry of Richmond passed 15 years of his youth, though a prisoner, yet protected from the vengeance of the Yorkists.

A perusal of Froissart will be a good preparation for a visit to Brittany.

8. Brittany, old-fashioned in all things, is still the stronghold of that old-fashioned virtue, loyalty to its sovereign; and, besides sharing in the horrors and glory of the war in support of the legitimate monarch, which had its rise in La Vendée, was the seat of a hard-fought contest of its own, called

*La Chouannerie*, from the cry, “chou, chou,” in imitation of the night owl, the signal for onset among the Breton peasantry, originally employed as a sign by smugglers in their nocturnal expeditions. Memorials or recollections of these struggles will be encountered by the traveller at every step.

9. Those who desire full information respecting the antiquities, customs, legends, and poetry of the Bretons should read *Souvestre's* excellent work, “*Les Derniers Bretons*,” and *Fremenville's* “*Finisterre and Morbihan*.” For its churches and Druidic remains consult *Merimée*, “*Sur les Monumens de l'Ouest de la France* ;” for its history, *Daru* :—*Miss Costello's* “*Bocages and Vines*,” *Mr. Trollope's* “*Brittany*,” are interesting English works ; and *Mrs. Stothard's* “*Tour in Brittany*,” and *Villemarqué's* “*Chansons Populaires de la Bretagne*,” will repay the perusal.

### 10. *Skeleton Tour of Brittany.*

Brittany is accessible to travellers from England, by steamers either direct from Southampton to St. Malo, a very good starting point, or from Southampton to Havre, and thence by land through Normandy, or by steamer to Morlaix.

The traveller coming from Paris may commence his tour at Rennes, but the capital of la Bretagne does not possess any of the characteristic features of the province.

Dol.	{ Carhaix.
St. Malo.	{ Folgoat.
Dinan.	{ St. Herbot.
St. Brieuc.	{ Châteaulin.
{ Lanleff.	Quimper.
{ Paimpol.	Quimperlé.
{ Treguier.	Auray.
Morlaix.	Carnac and Lokmariaker.
St. Pol de Léon.	[Peninsula of Rhys.]
Folgoat.	Vannes.
Brest—dock-yard.	Roche Bernard.
Pointe St. Matthieu.	Nantes.
Châteaulin (by water).	

11. *Accommodation for travellers*, even in the large towns, is inferior to that of the rest of France ; while in spots at all remote from the high road the filth is most disgusting, the fare miserable.

The following excellent description of the chief inn of the chief town of the province is from the diary of a recent tourist :—

“The Hôtel de France, if it be not good, is at all events highly amusing as a curiosity. It is something akin to what the ‘Swan with Two Necks,’ in Lad Lane, or the ‘Four Swans’ in Bishopsgate Street, probably were 40 years since. You get a good dinner for 2 francs at the table d’hôte, exclusive of a fair table wine ; and, by dint of importunity at the kitchen, some coffee and bread and butter for breakfast. You also get your bed made in time to get into it again at night ; but you never see a servant except one who flits round at the table d’hôte. The yard is crowded with diligences and baggage, and strewn with straw and ordures, and the proprietors are incognoscible beings. Everything seems to move on by unseen agency ; yet you really want for nothing material if you will but give up



getting the *bell* answered. This inn is in fact a sample of the 'Tom Jones' Inn of the 18th century, and the landlady at Rennes (whom we succeeded in finding out before we left) was a French counterpart of the English one of that day: slaving daily at her stews and stoves, like any necessitous hireling, in a dress indicating the most rigorous economy. But the virtue of prudence and the desire of accumulation occupy the foreground in the mind of a French 'bourgeoise.' The landlord we learned had a delightful country house out of Rennes, whence he daily visited his gainful, but ill-appointed 'auberge.' No trade so profitable as an aubergiste, it would seem, in a frequented town of France."—G.

### ROUTE 35.

PARIS TO RENNES BY VERSAILLES,  
VERNEUIL, DREUX, ALENÇON, AND  
LAVAL.

355 kilom. = 220 Eng. miles.

The Brest malleposte goes daily (3 places) in 26 hours.

From Paris to Versailles there are 2 railroads, one on the l., the other on the rt. bank of the Seine.

A railroad to Chartres is in progress from Versailles.

a. *Chemin de Fer, Rive Gauche*,  $16\frac{3}{4}$  kilom. =  $11\frac{1}{4}$  Eng. m. Terminus outside the Barrière du Maine at Paris. Trains go every  $\frac{1}{2}$  hour. Those starting at the hour are stopping trains, those at the  $\frac{1}{2}$  hour quick or direct. Time employed 20 to 25 minutes, with stopping train 35 minutes.

Before issuing beyond the line of the new fortifications you see on the rt. Grenelle and Vaugirard, now forming a town of about 6000 inhab., most of the houses being Cabarets, the resort of the working classes on Sundays and fête days; and on the l. Montrouge, where are numerous quarries of building stone.

Beyond the Lines the railway passes between the detached forts of Vanvres and Issy, a village whose name is fancifully derived from a temple of Isis! In the *Séminaire*, which still exists as a sort of country-seat dependent on that of St. Sulpice, Fénelon was interrogated by a conclave of bishops, styled the Conference of Issy, on certain points of

doctrine, and here the Cardinal Fleury died, 1745.

Rt. Vanvres. The *Château*, formerly the property of the Condés, built here by Mansard for the Duc de Bourbon, now belongs to the Collège Louis le Grand.

5 Clamart (stat.). The village, half hid among the trees, on the l., was the retreat of La Fontaine, of the Abbé Delille, who wrote here his poem *L'Imagination*, and of Condorcet.

Emerging from a deep cutting we traverse on a lofty *viaduct* (Pont du Val) of 2 rows of arches, one above the other, 108 ft. high and 145 ft. long, the bosky dell of Val Fleury, commanding a pretty view of the château of Meudon on the l., while the Seine is perceived on the rt.

2 Meudon (stat.). A little on the l. lies the bourg of 3000 inhab. Rabelais was curé of Meudon, 1550.

The *Château*, now belonging to the Crown, approached by a fine avenue of 4 rows of lime-trees, was built by the Grand Dauphin, son of Louis XIV., who died in it, from designs of Mansard, 1699, by the side of an older château now destroyed, the work of Philibert Delorme, which the widow of the minister Louvois sold to Louis XIV. During the Revolution the Comité du Salut Public converted it into a factory for inventing and perfecting warlike engines, and surrounded it with a permanent camp to keep out spies. The existing château was fitted up for Marie Louise by Napoleon, 1812. The best things about it are its situation,

its gardens laid out by Le Nôtre, but lately re-arranged on a more modern plan, and its *terrace*. The view from the terrace is very fine. There is a breeding-stud for race-horses here belonging to the Duc de Nemours.

The Forêt de Meudon is a favourite holiday resort of the Parisians. Near this the fatal accident occurred on this railway, May 1842, when, by the fracture of the axle of a locomotive, several of the foremost carriages of a long train were crushed, thrown upon the engine-furnace, and set on fire, and more than 100 persons were burnt alive, together with the railway-carriages in which they were locked up, in the space of about  $\frac{1}{4}$  hour. An expiatory chapel, dedicated to Nôtre Dame des Flammes, has been erected on the spot where this catastrophe occurred. Another cutting succeeds, and the railway passes under the Meudon avenue.

1 Bellevue (stat.) was named from a villa built in a few months to please Madame de Pompadour, but pulled to pieces during the Revolution.

Rt. Sèvres (stat.), contiguous to Bellevue, is described farther on (p. 115). The high road, and the Chemin de fer, rive droite, now run parallel and within a musket-shot of our line.

A deep cutting through part of the crown forests leads to

4 Chaville (stat.), so called from a village on the l.

1 Viroflay (stat.).

4 *Versailles* (stat. in the Avenue de la Mairie). See Galignani's Paris Guide.

b. *Chemin de Fer, Rive Droite.* Terminus in Paris, Rue St. Lazare 120, the same as the St. Germain and Rouen railways, and the three railways use the same line of rails as far as Clichy. Trains every half-hour (stopping), and every hour direct, from  $7\frac{1}{2}$  A.M. to 10 P.M.,  $22\frac{3}{4}$  kilom. = 14 Eng. m.; time in going 30 to 35 minutes.

After crossing the Seine by the Pont d'Asnières (stat.) beyond Clichy, this railway turns to the l. out of the St. Germain line (see Rte. 8) to

Courbevoie (stat.), whose large barrack, built by Louis XV., is seen on the l., and beyond it the Arc de l'Etoile. The avenue leading from it, after passing the Seine by the Pont de Neuilly, branches out into two roads leading to Rouen, the upper and the lower, both of which are crossed by the railway before reaching

Puteaux (stat.) A fine view is obtained of Paris and the Seine from this part of the line, while skirting on the rt. the flanks of Mont Valérien (p. 43), now converted into one of the citadels of Paris.

Suresnes (stat.)

*St. Cloud* (stat.)

The Royal Château, built or altered by Mansard for the Duc d'Orléans, brother of Louis XIV., has been the scene of great events. Here the fatal Ordonnances of July 1830 were signed, which lost Charles X. the throne; here Napoleon, like Cromwell before him, laid the foundation of his power on the memorable 19 Brumaire (Nov. 11, 1799), by expelling with his armed grenadiers the Council of Five Hundred from the *Orangerie*, in which they held their sittings;—two of the most momentous of the Revolutions of France. It was a favourite residence of Marie Antoinette, and of Bonaparte, and is now occupied every summer by the present royal family.

The interior is handsomely furnished, and contains some paintings chiefly of the modern French school, Gobelin tapestry, Sèvres vases, &c. The finest apartment is the Salon de Mars; the most interesting for its associations, the *Orangerie* already mentioned. Even more remarkable than the Château is the *Parc de St. Cloud*, laid out by Le Nôtre, always open to the public, and well worthy of a visit on account of the beautiful view which it commands over the winding Seine and the country around Paris,



for its artificial cascades, and its water-works, which play the 1st and 3rd Sunday of every month. The *Grand Jet d'Eau* rises from the centre of a circular basin, at the extremity of a long avenue, to a height of 137 ft., and discharges 5,000 gallons per minute. The copy of the beautiful circular temple at Athens, called the *Lanterne de Démosthène*, should not be passed unobserved. In this part a fair is held on the 7th September, and lasts 3 weeks, one of the most celebrated and frequented of all the fêtes near Paris.

The name of St. Cloud is a contraction of St. Clodoald, grandson of Clovis, who escaped alive when his brothers were murdered by their uncle Clothaire, by hiding himself in a wood here, and living as a hermit. Here, in the *Maison de Gondi*, Henri III. was assassinated, by Jaques Clement, 1589, while his army, united with that of Henri of Navarre, were encamped on these heights preparing to attack Paris. The father of Louis-Philippe was born here.

The railway is carried under a part of the park of St. Cloud in a *Tunnel* more than 1650 ft. long.

Sèvres (stat.) Both railways have stations here, but at some distance from the village, as well as at

Viroflay (stat.)

Rt. The small village of Montreuil, famed for peaches, is the birth-place of General Hoche, who commenced life as an under groom in the royal stables, and rose to be commander of the army of the Moselle.

*Versailles.* Terminus, Rue Duplessis, Boulevard de la Reine.

c. *The High Road, Route Royale*, quits Paris by the Barrière de Passy. The village of Passy was the residence of Benjamin Franklin, 1788. He occupied the house No. 40, Rue Basse, previously Hôtel de Valentinois. The Abbé Raynal died here, 1796, and Bellini, the composer, 1834. Beranger has long lived in a very

modest house here. The road runs along the rt. bank of the Seine through *Auteuil*, 2 m. farther on, which was also the residence of many eminent men. The wise and good Chancellor d'Aguesseau lived and died here; an obelisk in the churchyard marks his grave. Boileau's house is still pointed out, Rue de Boileau 18, and Molière composed here a great part of his works. Condorcet and Madame Helvétius had also houses here. The park and château de St. Cloud are conspicuous on the hill to the rt. The river Seine is crossed by the Pont de Sèvres, a short way before entering le Bourg de

12 Sèvres (Pop. 4000), situated on the l. bank of the river, 6 m. distant from Paris, between 2 hills, the hill of Meudon on the l. and that of St. Cloud on the rt., along whose slopes the 2 railways to Versailles are carried. Sèvres, like Faenza and Delft, gives its name to the china made in it, and for which it is principally known. The *manufactory* is in the large building on the l. of the road, erected 1755, when the works were transferred from Vincennes, and purchased by Louis XV. It is still the property of the crown, and employs 150 persons. Admission to see it is given by the directeur, M. Brongniart, a distinguished mineralogist and geologist, to whose scientific researches the manufacture owes much of its present perfection. Besides the show-rooms filled with objects for sale, there is a very complete and curious *Porcelain Museum* here, consisting of clay, earthenware, and china of all countries and periods, from the oldest Greek and Etruscan vases down to the most recent productions of the nations of Europe and Asia, China, Japan, and the East Indies, and of many of the rude tribes of America. Here is a series of all the objects made in the establishment since its commencement, marking the change of fashion and forms: also the various materials, earths, calces, colouring matters used in the manufacture.

The Kaolin, or white clay, comes from St. Yreix near Limoges. The paintings are very remarkable from the talents of the artists employed, (among whom Madame Jacotot and M. Constantin rank highest,) and the skill displayed in the burning of the colours gives an equal pre-eminence to Sèvres ware. Several pictures by ancient and modern masters have been copied in the size of the originals; some were painted on the china tablet in Italy and sent over to Sèvres to be burnt, and again sent abroad to be retouched. The Sèvres manufacture is celebrated for its white unglazed ware, *biscuit de Sèvres*, the white glazed ware, the elegance of the shape, and the beauty of the painting.

The *manufacture of painted glass*, erroneously supposed to be lost, has been revived and brought to considerable perfection within a few years; also the imitation of precious stones.

The park of St. Cloud (p. 114) reaches as far as Sèvres; there are 2 entrances to it from the town.

The road continues between the 2 railways as far as Versailles, and enters that town by the Grande Avenue de Paris.

7 VERSAILLES.—*Inns*: H. du Réservoir and H. de France. (See Galignani's "Paris Guide.")

A *Railroad* is in progress from Versailles to Chartres. (Rte. 46.)

The road to Brest, in quitting Versailles, passes between the park wall and a large sheet of water, called *Pièce des Suisses*.

A little way on the rt. lies St. Cyr, converted by Napoleon into an *Ecole Militaire*, 1806, for 300 pupils—a destination which it still preserves, but it was originally founded by Louis XIV., at the suggestion of Madame de Maintenon, as a school for 250 young ladies of noble birth, and Mansard furnished the designs for it, 1686. Racine's tragedies of Esther and Athalie, written for the pupils of the establishment, were here first brought

out, in the presence of the King and Madame de Maintenon. She retired hither after Louis's death, and dying here, 1719, was buried in the church. At the village of Trappes the road leaves, on the l., the route to Nantes (Route 46), through a dull country to 19 Pontchartrain.

11 La Queue.

13 Houdan.—*Inns*: l'Ecu, le Cygne. There is a handsome Gothic *Church* and an old *Tower*, part of the ancient fortifications, in this town of 2000 inhabitants.

7 Maroles.

The river Eure is crossed at Cherisy.

12 Dreux.—(*Inn*: H. du Paradis) (Durocassis), a town of 6400 inhab., on the Blaise, a tributary of the Eure. It was on the plain between the two rivers that the battle, known as la Journée de Dreux, one of the bloodiest in the French religious wars, was fought between the Roman Catholics, under the Duc de Guise, who was victorious, and the Huguenots, under the Prince de Condé, who was made prisoner, 1563. The Duc de Guise shared his couch the night after with his mortal enemy, and slept soundly by his side.

The hill which rises above the town is crowned by the ruins of the *Castle* of the Comtes de Dreux, which was captured with the town from the Duc de Guise by Henri IV.: the remains of the keep tower of brick, of a handsome Norman gateway, and of a Gothic chapel, built 1142, still exist. The space enclosed by the walls is planted and converted into a garden, in the midst of which rises a modern *Chapel*, in the form of a Greek temple surmounted by a cupola, erected by the present King when Duc d'Orléans, as a burial place for his family:—beneath it are interred the Duchesse de Penthièvre, the remains of the Princesse de Lamballe, who was massacred at the Revolution, and the Princesse Marie of Würtemberg, the accomplished daughter of the King, and the lamented Duke of Orleans, heir to the



throne. The plan and style of the constructions have been altered since the death of the Duc d'Orléans. A large *Gothic* crypt, at the extremity of which is the *Chapel* of the Virgin, surmounted by a delicate Gothic spire, has been added to the Grecian chapel. *La Chapelle de la Vierge* is enriched with carving, with pendants from the roof, and with painted windows of modern glass, representing religious subjects. The sum laid out here exceeds 4,000,000 francs. Around the hill are carried agreeable walks. Its top is surmounted by a telegraph-tower, and the view from it is very extensive. The tall tower, which serves as a residence for the King when he visits the spot, has a subterranean communication with the chapel.

The *Gothic Parish Church*, its lower portions in the style of the 13th cent., the upper part and tower in that of the 16th, contains the graves of Rotrou, a dramatist of the 13th cent., and of Philidor the chess-player, both natives of Dreux.

The *Hôtel de Ville*, part Gothic, part the revival style of the 16th cent., now turned into a museum, contains a curious chimney piece, and a bell, cast in the reign of Charles IX., bearing a representation, in relief, of the procession of the Flambarbards.

There are numerous manufactures of coarse cloths, serges, &c. in the arrondissement of Dreux.

*Diligences* to Paris by Versailles:—to Chartres and Rouen daily.

11 m. N. E. of Dreux are the scanty remains of the Château d'Anet, built by the architect Philibert Delorme for Diana of Poitiers out of the funds furnished by the liberality of her royal lover Henri II., 1552, on the site of a castle which belonged to her husband Louis de Brézé, to which she retired to pass her widowhood. When she first became acquainted with the king she was 31, and he a youth of 13, yet she maintained her influence over him to the day of her death, in spite of the Queen, Cathé-

rine de Medicis, and he wore her colours—the widow's weeds, black and white—to the last, and her symbol, the crescent of Diana, is conspicuous in all his palaces. She was buried in the *Chapel*, which still remains surmounted by a cupola, but her monument was removed to Paris, 1793, when her body was torn from the grave and lost. The château was almost entirely pulled down at the Revolution; part of the façade was transported to Paris, where it has been re-erected at the Ecole des Beaux Arts. The ruins are pleasantly situated on the banks of the Eure. That stream traverses a little lower down the *Plain of Ivry*, the scene of one of the most decisive victories gained by Henri IV. over the armies of the Ligue, 1590, composed of French and Spaniards under Mayenne. Henri's words to his soldiers before the battle were, "Je veux vaincre ou mourir avec vous. Gardez bien vos rangs, ne perdez point de vue mon panache blanc, vous le trouverez toujours au chemin de l'honneur." The monumental obelisk erected on the spot to commemorate the battle was thrown down 1793, but restored by Napoleon. The *Ch. of St. Remè* near Dreux is a fine example of the flamboyant style.

14 Nonancourt.

The house in which Henri IV. slept the night before the battle of Ivry is pointed out.

11 Tillières-sur-Avre.

10 Verneuil.—*Inns*: Poste; Cheval Blanc. This interesting old town, of 4,000 inhab., contains several remarkable specimens of Gothic architecture,—the finest being the *Tour de la Madeleine*, a magnificent work in the most gorgeous late Gothic style, surmounted by a stunted spire. Verneuil was once a place of strength;—under its *walls*, which partly remain, a fine specimen of fortification of the 12th century, was fought a bloody battle in 1424, between the French and English, which, after two days of hard and uncertain contest, terminated in

favour of the Regent, Duke of Bedford, and was the last great victory obtained by him. The bravest leaders and most efficient troops who fought on the side of the French were the Scotch. Their commanders, the Earl of Douglas, who had been created Duke of Touraine, his son, the Earl of Buchan, and many other knights were slain. The English army was inferior in numbers to the enemy, yet it left 1,600 dead on the field, while on the side of the French there fell 4,000, including Scotch and Italian allies. As usual the English archers contributed mainly to the victory. Attached to the portion of the fortifications not yet removed, is a tall tower, 60 ft. high, on the margin of the Avre, called *la Tour Grise*.

The road by Argentan and Falaise branches off here (Route 29).

16 St. Maurice.

22 Mortagne.—*Inn*: H. de France.

An old town (5,158 inhab.) which claimed to be capital of la Perche. It is situated in a commanding position on a hill, surmounted by the high road in a series of zigzags, in order to reach the principal square. It was a place of strength, often besieged, and suffered much from the horrors of war. During the contests of the League, it was taken and pillaged by the two parties 22 times in 3½ years. Parts of its ramparts remain. Its only supply of water is obtained by means of a steam-engine pump, from springs at the bottom of the hill. The *Church* is remarkable for the pendants in the roof of its nave.

The *canvas used for pictures* is made at Mortagne, besides other coarse cloths, and some porcelain.

7 m. N. of Mortagne, at Soligny, is the convent of *La Trappe*, founded in the 12th centy.; but owing its celebrity to the severe rule of the order enforced, 1666, by the Abbé la Rancé, who, so far from leading a dissipated life in his youth, as is commonly reported, is proved, by documents and letters published by M.

Gonod, to have always lived "strictly and ascetically. The well-known story of his conversion is a pure fable."—*G.* The convent was suppressed 1790, by a decree of the Assemblée Nationale, and its church destroyed with the tomb of La Rancé, but the monks were restored in 1814 by the exertions of M. Lestrange. They are interdicted from all intellectual labour, and only allowed to work in the fields.

16 Mesle-sur-Sarthe. The Sarthe, a tributary of the Loire, is crossed here.

10 Ménil Broust.

13 Alençon (*Inns*: La Poste;—H. d'Angleterre), chief town of the Dépt. de l'Orne, has a population of 14,500, and is a thriving place, situated on the Sarthe, near the junction of the Briante, in an open plain. Its manufactures consist chiefly of cotton and woollen, hempen and linen cloths, called "*Toiles d'Alençon*."

The making of point lace, "Point d'Alençon," established here by Colbert, for which the town was long celebrated, has now nearly disappeared. Cyder and perry (poiré), the common drink of the country, are sold to a considerable extent, in casks called *pipes*.

The public buildings are not very remarkable. The *Cathedral* consists of a Gothic nave, built in the 16th century, having some painted glass, injured by a storm, 1821, and a pulpit approached by a staircase cut in the pier, attached to a plain modern choir. The crypt beneath the church contains the remains of the Ducs d'Alençon—lately opened.

Three battlemented towers of the old *Castle*, built by Wm. de Bellesme, 1026, are converted into a prison, and the *Préfecture* is a brick building, which once belonged to the Duchesse de Guise.

One of the most atrocious of the Revolutionary leaders, Hébert, the anarchist, editor of the infamous journal, *Père Duchèsne*, was a native of Alençon. He was led trembling



and weeping to the scaffold, to which he had condemned so many thousand innocent persons, in 1793, exhibiting in his last moments the most extreme cowardice.

The name *Diamants d'Alençon* is given to the crystals of smoky quartz (rock crystal), found in the neighbouring granite quarries; where the beryl also occurs.

*Diligences* to Tours and Caen. (Route 29.)

11 St. Denis. The river Mayenne rises near this, and is crossed about  $\frac{1}{2}$  way to

13 Prez en Pail, in the Dépt. de la Mayenne; the portion of it traversed by the road is a dreary country, unenclosed and covered with heath.

18 Le Ribay.

The high road to Brest merely skirts a suburb of Mayenne, leaving the town itself on the rt.

18 Mayenne.—*Inns*: Belle Etoile; —Tête Noire. A town of 10,000 inhab., situated  $\frac{2}{3}$  on the rt. bank and  $\frac{1}{3}$  on the l. of the Mayenne. Its manufactures of calicoes, linen cloth, and tickens, employ 8,000 persons in and around the town. The *Castle*, now in ruins, is a picturesque object, on the rt. bank of the river, near the bridge. It belonged to the seigneurs of Mayenne, and was taken after a 3 months' siege, by the English, under the Earl of Salisbury, 1424. Many of the streets are very narrow, and so steep that it requires 8 or 10 oxen to draw a cart up them.

Laval, chief town of the department, is situated 24 m. S. of this.

The road descends the valley of the Mayenne, having the river on the rt. but out of sight, to

13 Martigné.

17 *Laval* (*Inns*: Tête Noire; —Cour Royale), a curious ancient town, chef-lieu of the Dépt. de la Mayenne, on the river Mayenne, has 16,500 inhab. The oldest part consists of black timber houses, each story projecting beyond that below it, until the gable overhangs the street; but a new

quarter has risen on the W., where the streets are wide and regular. On the rt. bank of the river, close to the old bridge, the *Castle* of the seigneurs of La Trémouille rises from a basement of rock, on which its lofty wall is raised, flanked at one end by a machicolated round tower. It was built in the 12th centy., and its *Chapel* on round arches is perhaps of that date, but there are many later additions, and the jambs of some of the windows facing the inner court retain some rich ornaments in the style of the Renaissance (15th or 16th centy.). It is now a *prison*.

The *Cathedral* presents a singularity of ground plan, taking the form of a right angle, occasioned by the sloping ground on which it stands. It is a curious Gothic edifice. The nave and choir (except the aisles and side chapels, additions of the 15th and 16th centuries, in the flamboyant style) are not older than the 12th. The E. end is square; the porch is a wretched addition of recent times. Under the church are very extensive substructions and crypts, thrown up in consequence of the slope of the ground to form a platform or pedestal for the building.

*St. Vénérand*, a church of the 15th or 16th cent., has a little painted glass.

The *church* in the village of Avenières adjoining the town, built 1040, deserves the notice of the architect. Its choir, in the early pointed style, is surrounded by 5 apsidal chapels, and 2 others open into the transepts. Above the cross rises an elegant stone spire of decorated Gothic. The church contains a miracle-working image of the Virgin. The architect and antiquary ought not to leave unseen the little ruined *Church* of *Gre-noux*, 2 m. from Laval. It is destitute of all ornament. The structure of its masonry, small square stones with intervening bonds of tiles, marks the style of a period not later than the 9th century. Within it is a monument of a knight and his lady.

Laval is essentially a manufacturing town, occupied in the production of linens and cottons, (toiles, coutils, siamoises,) and of linen thread, large quantities of which are spun here. A market for the sale of these productions is held every week in the *Halle aux Toiles*.

Laval was the centre from which arose the Royalist insurrection of 1792, called *Chouannerie*, either from 4 brothers named Chouan, its first leaders of the village St. Ouen des Toits, or from the cry of the owl, imitated by the salt smugglers of this district as a signal to their confederates, and afterwards adopted during the struggle, by the peasant guerrillas, to announce the enemy's approach.

One of the most glorious victories of the Vendéans was gained in Oct. 1793, a little to the S. of the town. Defeated in several previous combats, and driven across the Loire, with a large Republican army in pursuit of them, their enemies believed the war extinguished. Barrère announced this intelligence to the Convention in Paris; "La Vendée is no more, the brigands are exterminated, a profound solitude reigns in the Bocage, covered with cinders and watered with tears:"—but at the very time that these words were being uttered, Laroche-jacquelain had carried Laval at the point of the bayonet; then turning round on his pursuers, he exhorted his brave bands to efface the memory of their former defeats, and to fight for the preservation of their wives and children who accompanied them, now far from their homes. Lescure insisted on being carried through the ranks on his death-litter, mortally wounded as he was, to encourage the Royalists by his presence, and to share their peril and toil. The Vendéans, obeying the appeal, on this occasion rushed upon the enemy in close column, routed them entirely, and pursued them beyond Château Gonthier, with a loss to the Republicans of 12,000 men, among whom

were the redoubted garrison of Mayenne, who were mostly cut to pieces, and of 19 cannon. The conflict began at les Croix de Bataille, 2 m. S. of Laval. So precipitate and complete was the rout, that the remains of the Republican army, reduced to 12,000 men, were not collected and reorganised until 12 days had elapsed, and not before they had left the town of Angers in their rear.

21 La Gravelle. "There are large coal works at St. Pierre la Cour, near this."—*L.*

16 Vitré (*Inn*: La Poste) is in appearance a town of the middle ages, Gothic and irregular, retaining the greater portion of its feudal fortifications, high and thick *walls* flanked by towers, surmounted by machicolations, and surrounded by a deep ditch. They appear not later in date than the 15th century. On one side of them, but detached from them by a ditch, stands a venerable and picturesque *Castle* of the Seigneurs de la Tremouille, now converted into a prison and falling to decay. In the court is an elegantly ornamented structure, half Gothic, half Italian, supposed to have been a pulpit. At the time of its construction the lords of the castle were adherents of the reformed faith, and the inscription, which may still be read around the console, "post tenebras spero lucem," probably alludes to the persecutions they suffered.

The *Church of Notre Dame* is in a style indicating the decline of Gothic art; attached to it, on the outside, is a stone pulpit, and within one of the chapels hangs a frame containing 32 small enamels, probably from Limoges.

The peasants of this part of Brittany wear a dress of goatskins with the hair turned outwards, which gives them a somewhat savage aspect, and reminds one of Robinson Crusoe.

About 3 m. S. of Vitré is the *Château des Rochers*, long time the residence of Madame de Sévigné; her bed-room and the cabinet where



she wrote many of her charming letters are pointed out, and there is a fine portrait of her by *Mignard*, but the furniture, &c. of the interior has been altered.

Near Essé, 7 lieues S. W. of Vitré, is a Druidical monument called "la Roche Aux Fées," consisting of 43 large rough blocks of stone—34 upright, supporting 8 others which form a roof.

The Vilaine river, after which the department is named, rises near Vitré; our road runs parallel with its course as far as Rennes, crossing it by a stone bridge at

15 Châteaubourg.

2 m. beyond this the road passes close to a large slate quarry excavated to a depth of more than 100 ft.

9 Noyal. The country possesses little interest.

12 RENNES.—*Inns*: No good inn;—moderate charges, but all dirty; H. de l'Europe;—H. de la Corne de Cerf;—H. de France, near the Mesageries. This town, formerly capital of Brittany, now chef-lieu of the Dépt. Ille et Vilaine, is situated at the confluence of these two streams, and contains 37,900 inhab. Here are few antiquities; the town has an entirely modern aspect, arising from a dreadful fire which in 1720 reduced nearly the whole to ashes. It lasted 7 days, and consumed 850 houses, besides nearly all the public buildings; the ancient and solidly built clock tower crumbled to pieces on the third day, calcined by the flames. The public buildings, of a date subsequent to this catastrophe, display for the most part the bad taste of the 18th century.

The streets are uniform; and, "notwithstanding the sober and gloomy hue of which the houses are chiefly built, Rennes is rather a handsome city," but dull. Considerable improvements have taken place, many narrow streets have been removed, and a new bridge has been thrown over the Vilaine.

The stately *Palais de Justice*, in France.

the handsome Place du Palais, was the parliament house of the States of Brittany, and is the most remarkable building here. It contains one fine large Salle des Pas Perdus, and several apartments rich in gilded ceilings and stucco ornaments, Cupids bearing festoons, &c. with roofs and panels painted by Jouvenet. Its date is 1670.

The interior of the *modern Cathedral* "is a very spacious, lofty, and imposing *Hall* of Grecian architecture; the principal aisle having a richly decorated vaulted roof, supported by massive and well-proportioned fluted Corinthian columns. On the whole the effect is striking, but not all ecclesiastical." *M. A. S.*—*St. Melaine* retains a Romanesque porch supported on engaged pillars with curiously carved capitals, probably of the 12th centy. The telegraph on the top of the cathedral is one of the chain communicating between Paris and Brest.

There is a very handsome modern *Theatre*, situated in another respectable square, with covered arcades around it, lined with shops.

In the modern *Hôtel de Ville* facing the theatre is a collection of pictures removed from the damp Musée in which they were before deposited: the greater part are of little worth. As a curiosity may be cited a Judgment of Solomon painted by *King René* of Anjou, but much injured, faded and dingy in hue. There is a *Lion Hunt*, said to be by *Rubens* (?)

Here is also the Public Library, containing 30,000 volumes, and many rare MSS., among them a charter of Don Henry of Trastamare, granting lands in Spain to Du Guesclin.

The chief attraction of Rennes, however, is its *Public Walks*, especially that called *le Mont Thabor*, planted with fine trees and commanding a pleasing view over the town, and valley of the Vilaine. A miserable statue of Du Guesclin has been set up in it. The other walks are *le Mail*, extending down to the junction of the

Ille and Vilaine, *le Mont de Madame*, and *le Champ de Mars*.

One of the old town gates, *la Porte Mordelaise*, is preserved opposite the new cathedral; the entrance is by a pointed arch, and the masonry includes a stone bearing a Roman inscription, dedicated by the town of Rennes (*Redonis*) to the Emperor Gordian; it is no longer legible. Through this gate the ancient dukes of Brittany made their solemn entry into Rennes on their accession, but before passing it they swore to preserve the Catholic faith and the church of Brittany, to govern wisely, and to execute justice; they were then conducted into the church, where, after 2 days spent in prayer, they were crowned with the golden circlet, and girt with the ducal sword.

The manufactures of Rennes are sail-cloth, which it supplies to the French navy; and some table linen. The butter (*beurre salé*) is excellent, especially that of *Prévalaye*, large quantities of which are sent to other parts of France.

Rennes has a communication by *Canal* with St. Malo and the Channel on the one hand, and with Nantes and Brest on the other.

*Diligences* daily to Paris and Brest (R. 36); to Dinan and St. Malo (R. 41); to Caen (R. 31); to Nantes (R. 41).

### ROUTE 36.

#### RENNES TO BREST.

240 kilom. = 149 Eng. m.

*Malleposte* daily in 18 hours.

*Diligences* daily.

10 Pacé.

13 Bedée.

14 La Barette.

16 Broons is remarkable only as the birth-place of Bertrand Du Guesclin, the great captain of France in the 15th century. He was 10th child of Robert Du Guesclin, and remarkably ill favoured to look upon. He first saw the light in the castle of La Motte Broons, of which no vestiges remain, but the place where it stood

is marked by an avenue of trees, and a *Monument*, erected at the cost of the department, by the side of the road to Brest, about 1 m. out of the town.

12 Langouedre.

15 Lamballe (4400 inhab.) was the chief place of the Comté of Pen-thièvre; the castle of the counts was reduced and dismantled by Cardinal Richelieu, 1626, to punish a rebellious seigneur. The *Ch. of Nôtre Dame* on the top of the hill, whose slope is occupied by the town, was originally the castle chapel, and is a fine Gothic building. Thick cylindrical piers, surmounted by capitals in bands, support the lancet arches of the nave, whilst the choir rests on clustered pillars, the arches being surmounted by a double triforium gallery. It has a wooden roof. In a side aisle is some good carved wood-work, with decorated and flamboyant tracery, perhaps the remains of a roodloft. Part of the church was built 1545.

The road to St. Malo (R. 41) diverges from this.

Glimpses of the sea are obtained on the rt. before reaching

20 *St. Brieuc*.—*Inn*: Croix Blanche, clean and good; one of the best on this road: dinner, bottle of wine, bed, and tea for breakfast, 4 fr. 50 c.

There is nothing worth notice in this town of 12,500 inhab.; it is situated on the Gouet, and has a port called Ligué, 2 m. lower down the stream, provided with a long quai, accessible for vessels of 400 or 500 tons to unload at. On the top of a hilly promontory, commanding the bouchure of the river, stands the ruined *Tour de Cesson*, built 1395, to defend its entrance, but blown up 1598, after the war of the League, by order of Henri IV. Such, however, was the thickness of the wall, and the coherence of the mortar, that one half of the cylinder remains standing, braving the tempests, while the other lies shattered into a few large masses at its base, as it fell. There is a pretty walk from St. Brieuc to Ligué,



through a narrow ravine, traversed by a small tributary of the Gouet.

St. Brieuc was taken by the Chouans in the Vendéan war, 1799.

An interesting antiquarian and architectural excursion to Lanleff, Paimpol, &c. may be made from this (Rte. 38).

17 Châtaudren, a small town on the Leff.

14 Guingamp (*Hôtel des Voyageurs*) is a very picturesque town, situated in the vale of the Trieux, which abounds in pleasing scenery (7200 inhab.). It formed part of the vast possessions of the Ducs de Penthièvre, and has descended from them to Louis-Philippe. The site of their castle, razed to the earth, is occupied by a grove of trees, and serves as a promenade; but fragments of the town walls remain. Its *Church*, surmounting the other buildings, part Gothic, part in the style of the revival, has some peculiarities; viz. grotesque heads, projecting from the shafts of its piers.

The *Fontaine de Plomb*, in the middle of the place, is rather an elegant work of Italian artists in the 15th century, it is supposed.

The *Chapel of Notre Dame de Grace*, 3 m. out of the town, is well deserving a visit, although its rich decorations in sculptured tracery and figures have been much mutilated. "Its elegant spire, finely proportioned pillars, and light arches, are still worthy of admiration; and much of the grotesque carving, which formed the cornices of the nave and aisles, may still be seen."—*Trollope*. It was erected in the 14th cent. by Charles of Blois.

19 Belle-Île-en-Terre.

The Dépt. of Finisterre, in La Basse Bretagne, the ancient Armorica, is entered before reaching

19 Ponthou.

15 *Morlaix* (*Inns*: H. de Provence, new, good, and moderate—*W. H.*;—H. de *Paris*) is a flourishing little port and town of 10,500 inhab., picturesquely seated in a valley, wide

enough only for the tidal river or creek which runs up it, lined with 2 quays and 2 rows of houses, "behind which the hills rise steep and woody on one side, on the other gardens and rocks and wood; the effect romantic and beautiful."—*A. Young*. The rock rises so close behind the houses as to give rise to a proverb, "From the garret to the garden, as they say at Morlaix." It is only  $6\frac{1}{2}$  m. from the sea, and is reached by vessels of considerable tonnage. To the stranger its chief attraction is the unaltered air of antiquity which it retains in its older quarters, such as the Rues des Nobles and du Pavé, and the thoroughly Breton character of its street architecture and houses, overhanging the foot-way, each story, fronted with an apron of slates, more nearly approaching its neighbour on the opposite side of the way, until the inmates of the garrets may shake hands. The grotesquely carved corner posts, ornamented with figures of kings, priests, saints, monsters, and bagpipers, the Gothic doorways, the sculptured cornices, would enrich an artist's sketch-book, and furnish employment for many days. The costume of the people, also, is thoroughly in keeping with the buildings; their pent-house brimmed hats, their loose trunk hose, their shaggy locks, hanging like manes down their backs, are all thoroughly characteristic of la Bretagne Bretonnante (§ 2).

Sad havoc, however, has been made in this antique town by modern improvements; and the outlet formed for the new Rue Royale, by which the road to Brest issues out on the W., has swept away a crowd of crazy, but picturesque constructions, whose loss would make Prout sigh.

Two small streams, descending from separate ravines, but uniting above the town, are arched over to furnish space for the market-place and modern *Hôtel de Ville*; below which, expanding naturally, and partly by their bed being artificially excavated, they form a port, lined with quays, and lofty

picturesque houses, resting on covered galleries or arcades, called *Lances*. One of the houses on this quai is particularly remarkable for its carved staircase. Beside these quays several merchant vessels may usually be seen lying together, with a variety of small craft.

The churches are not remarkable: *St. Mathieu* is Gothic; in *St. Melaine* is some good carved screen work.

Many of the houses in the Rue du Pavé and Rue des Nobles (especially the staircase of one high up on the right hand) deserve notice: they are richly ornamented in the flamboyant style.

The *Gothic fountain* of the Carmelites, and the *Chapel* of the Convent of St. François, may be visited by those who have time. The *Manufactory Royale de Tabac*, a large building on the W. quay, is said to produce the worst tobacco in Europe.

In 1522, the fleet of Henry VIII., who was at that time incensed with Francis I. for seizing the ships and goods of English merchants in French ports, on its return from escorting the Empr. Charles V. to Spain, under the command of Henry Earl of Surrey, entered the river, in number 50 vessels, and effecting a descent in the neighbouring bay of Dourdu, surprised Morlaix. The English set fire to it in four different places, pillaged it, massacred the inhabitants, and burnt to the ground great part of it, "together with some right fair castles, goodly houses, and proper piles."—*State Papers*. They retired to their vessels loaded with booty; but 600 of the hindmost were intercepted by the infuriated inhabitants, and cut off with great slaughter near a spring, still called *Fontaine des Anglais*, or, as the Bretons, like their Welsh kinsmen, style them, the Saxons.

Near the said fountain begins a very pleasant promenade, planted with trees, called *Cours Beaumont*, which extends nearly  $1\frac{1}{2}$  m. down the l. bank of the river. The views from it of

the river and the wooded valley are very pleasing.

The site of the old castle planted with trees also commands a fine view of the town.

Morlaix is the native place of General Moreau.

*Diligences* daily to Paris and Brest; to St. Malo; to Rennes; to Lorient.

A well-appointed *steamer* runs from Morlaix to Havre, 70 leagues, in 20 hours, once a week, fare 30 fr.

The churches of Kreisker, at St. Pol de Léon, and of Folgoat, may be visited by making a *détour*, on the way to Brest (Rte. 38). Another interesting excursion is to the mining district of Huelgoat and Poulahouen (Rte. 42).

Rather more than half way (9 m.) between Morlaix and the next relay, the village of Théogonec is passed, remarkable for its fine *Church* in the style of the Renaissance; a vast edifice, richly decorated with sculptures in the dark Kersanton stone. Its delicately carved pulpit, its reliquary and its Calvary, deserve notice.

21 Landivisiau has a church also with a very fine S. portal, filled with statues of the 12 Apostles, and at the W. end a most elegant tower and spire.

The *Church of Lanbader*, 5 m. N. of this, on the road to St. Pol, surmounted by an elegant tower and spire, was originally attached to a commandery of Templars, ruins of which exist near the tower. Within is a beautifully pierced and carved *roodloft* of wood, composed of exquisite flamboyant tracery, also a staircase in the same style. The chains of some knight, liberated from slavery among the followers of Mahoun, still hang in the choir.

3 m. short of Landerneau, on a hill above the village *La Roche Maurice*, stand the ruins of its castle, reduced to 3 shattered towers, but very picturesque in its outline and position.

In the churchyard is an *Ossuary*,



filled with skulls and dry bones, ornamented in front with a sculptured frieze, representing the *Dance of Death*, executed 1639. The *Church* is Gothic, and built 1559, and contains some good painted glass. The carved portal in Kersanton stone, and the sculptured roodloft of wood within, are worth notice.

16 Landerneau (*Inn*: Hôtel de l'Univers), a pretty town, seated in the hollow of a valley on the Elorn, whose mouth forms one branch of the roadstead of Brest. There are some picturesque Gothic bits among its old houses. 4,963 inhab.

The roads to Brest from Morlaix, from Carhaix (Rte. 42), and from Quimper (Rte. 44), all converge at this point.

A little beyond Landerneau, on the l. of the road, between it and the river Elorn, a ruined gateway, draped with ivy, is the sole subsisting relic of the *Castle of the Joyeuse Garde*, now known as Château le Forêt, the cradle of chivalry, the seat of Arthur, Lancelot du Lac, and the knights of the round table. Of course there is no pretension that the existing remains are of their time. No satisfactory explanation is given of the origin of the name Joyeuse Garde; but it is supposed to be a perversion of a Breton term.

20 BREST.—*Inns*: H. de Provence, best; H. du Grand Monarque.

Brest, the chief naval seaport of France, an arsenal of war and fortress of first class, is most advantageously situated near the W. extremity of the Dépt. Finistère (the Land's End of France), on that portion of her territory which projects most to the W. between the Channel and the Gulf of Gascony. It stands on the N. side of one of the finest harbours in the world, nearly landlocked, accessible only through a narrow and well-fortified throat, *Le Goulet*, and extending far inland in 2 branches, one running up to Landerneau, the other towards Châteaulin. The town is built on the sum-

mit and sides of a kind of projecting ridge, and some of its streets are too steep to be passable except on foot. A narrow but deep creek, which is in fact formed by the mouth of the small stream the Penfeld, running up from the harbour behind this ridge, serves as the basin to the dockyard, and divides the town on its l. bank from the suburb *La Recouvrance* on its rt. The communication between the town and suburb is kept up by numerous ferry boats. Close above the mouth of this creek, which is not more than a musket shot across, and is defended by several tiers of batteries on either hand, rise the feudal round towers and colossal curtains, not less than 100 ft. high, of the picturesque *old Castle*, which belonged to the Ducs de Bretagne. It was besieged in vain by Du Guesclin and Clisson, was long held by the English, having for governor, 1373, the brave warrior Robert Knolles. It was yielded up by Richard II. 1395, in consideration of 12,000 crowns, and was finally modernised by Vauban 1688, who formed casemates in the interior of its massive towers, and platforms with embrasures for cannon on their tops. From its walls there is a good view of the port and dockyard, but the Fort de l'Ecole, on the opposite side of the water, commands one still finer, including the roadstead also. There are numerous dungeons beneath the castle, and extensive vaults.

The inner port of Brest, or creek above mentioned, is so narrow that if the town had any commerce it would not be large enough to hold the merchant vessels, but there is no deficiency of depth (25 ft. at low water), and 30 or 40 ships of war might lie within it in single file. Above the castle the shores of both sides of this creek are enclosed by a high wall separating the dockyard within it from the town. The mouth of the creek is closed by a boom. The population of Brest is said to exceed 32,000, though, to avoid the additional contributions on large towns,

it is put down in the census at 29,860. There is accommodation in the numerous barracks for a garrison of nearly 10,000 men.

Although Brest is enclosed within ramparts, there are several fine open spaces within its walls; such are the square called *Champ de Bataille*, innocent of any other combat than a sham fight, and the *Cours d'Ajot* (so named from an officer of engineers who laid it out), a promenade agreeable on account of the fine trees which shade it, and the beautiful view of the roads, appearing like a vast lake, which its terrace commands; but infested all the morning by parties of recruits undergoing drill.

More rain, it is said, falls in Brest than in any other town of France, and the whole department of Finistère is peculiarly exposed to storms, winds, mists and fogs.

In 1548, Mary Queen of Scots, then a child 5 years old, landed at Brest, and a few days after was affianced to the dauphin Francis at St. Germain.

*The Dockyard, or Port Militaire.*—The authorities connected with the dockyard (major de la marine, &c.) are very niggard in giving admission to strangers, but an application to the Port-admiral or Préfet Maritime, made by the English consul, who is particularly obliging to persons recommended to him, will procure it. Entrance to the Bagnes and Hôpital de la Marine, the most interesting objects here, should be expressly included in the ticket of admission. The celebrated dockyard of Brest is situated on the 2 sides of a narrow but deep creek or arm of the sea, running up in a winding direction between high and steep rocks, which intrude so near upon the water that it is only by paring them down that space is formed for the buildings, and for the quays and yards required in front of them. The first view looking down from above into this narrow ravine, lined with long and massive ranges of buildings rising tier over

tier in the form of an amphitheatre, is exceedingly striking. On one side is the *Voilerie* (sail-house), *Magasin Général* (slop shop), and *Corderie* (ropery) of 3 stories, surmounted by the *Bagne*, and above it rises the *New Hospital*. On the opposite side are various ateliers, forgeries, *Atelier d'Artillerie de Marine* (burnt in 1833). The *Foundery* (for casting cannon), and the *Quartier des Marins*, or sailors' barracks, where they are lodged when in port in the same manner as soldiers—an admirable establishment, which might be advantageously copied by the English admiralty—fill up the opposite side. The level space at the water's edge is occupied by slips (cales de construction), only 2 of which are covered, about 8 being uncovered, dry docks (*formes*) at times converted to the purpose of building ships. It is surprising that the first dockyard of France should possess so few covered slips. There are besides timber yards, boat sheds, water cisterns supplied by a steam-engine where vessels fill their tanks, sheds for containing the new tanks, and government cellars, while a very large space near the sea entrance of the dockyard is covered with dismounted cannon. Here also is placed a trophy from Algiers, a brass gun 20 ft. long, which forms an excellent column, reared on its brecch. The precautions against fire and theft are very rigid; a vigilant guardian watches in every apartment, a door-keeper at every door; cisterns are placed at short distances, with tubs full of water every 8 or 10 yards.

The ground occupied by most of these buildings has been gained, as before observed, by excavations out of the hill side. Greatly as the space on either side of the water has been widened by artificial means, the cliffs even now approach too near the slips and timber sheds, preventing a free circulation of air, causing dampness, and consequently dry rot. Near the timber sheds is the *Musée Maritime*,



filled with models, ships' heads, &c., but containing nothing very remarkable.

On both sides of the port, roads are carried up the steep sides of the confining heights in zigzag terraces, so that they may easily be surmounted by heavy carriages.

The *Victualling Office* (Direction des Substances et Parc aux Vivres) is near the mouth of the port, on the rt. bank, and includes the bakehouse, containing 24 ovens, the slaughterhouse, kitchens, &c. In 1802-3, when the combined Spanish and French fleets lay in the roads, 50,000 rations were supplied hence daily.

The *Bagnes* (from bagnio, Ital. bath; the Christian slaves in Turkey and Barbary were employed in heating the baths of the sultans, pachas, deys, &c.) contain about 3,000 convicts (forçats), condemned to forced labour for a certain term of years or for life. Their dress is a jacket of dirty red serge, fitting no better than a sack, yellow trowsers, and a green, red, or yellow cap: the green cap denotes one condemned for life; the yellow sleeve one twice sentenced. The worst offenders are heavily loaded with shackles fastened to a ring riveted fast round the leg. The chain and shackle together weigh more than 7lbs., and usually cause a wound on the leg at first. It is not, however, the hideous dress nor the clanking chains which render the forçats repulsive; it is the countenance marked with bad passions and villainy, which indicate the degradation of human nature. The worst offenders are coupled two together to the same chain. They work in gangs, each gang accompanied by a plante or garde chourme, a fierce-looking moustache, with a tranchant sabre, accompanied by a soldier with a loaded musket. The *Prison of the Bagnes* has a long façade, with more of architectural ornament and style in its pediment than usually marks a prison destined for doubly and trebly dyed criminals. It contains 4 Salles, lofty,

wide, and airy, filled with large wooden platforms having sloping tops like desks; these are the bedsteads of the forçats, who recline on them upon a small mattress provided with a coarse quilt of sackcloth, the chain of each being passed over a bar of iron running along the foot of the bed, but allowing tether enough to move a distance of 5 or 6 ft. Only the better class of convicts are allowed a thin mattress.

As soon as their allotted task for the day is done out of doors, they are allowed to repair hither; some have writing desks, others employ themselves in handicrafts, many in making toys out of cocoa-nuts, horse-hair, &c., by which they may earn a little money. At gunfire the names are called over, and in an hour profound silence is required; the night, passed on a hard board, is a time of suffering, especially in winter, from the cold.

Their daily allowance of food includes a pint of wine, a measure of biscuit, or  $\frac{1}{2}$  a loaf of brown bread.

The 4 salles are closed by strong iron gates at night, but stand open during the day; there are, however, plenty of guards at hand, and immediately behind the Bagnes rises the *Caserne de la Marine Militaire*, which could pour in some hundred men in a few minutes, in case of revolt. The forçat, degraded as he is, is not allowed to be struck by his guards or keepers; his punishment, if he does wrong, is either solitary confinement in the black hole, a series of cells in the court behind the building, or deprivation of his wine, &c., coupling to another prisoner, or flogging with the rope's end. As a further preventive of tumult or rebellion, the walls of each salle are pierced with embrasures through which 2 cannon show their mouths; they are loaded with grape, and would enfilade the chamber, and sweep it from end to end.

Outside the dockyard, a little higher up the hill than the prison, rises the

*Hôpital de la Marine*, an edifice of great extent, though of unpretending architecture, of which Brest may well be proud. It was begun 1824. It contains 26 salles, each with 53 beds; and is attended by between 30 and 40 Religieuses, Sœurs Fidèles de la Sagesse as they call themselves, who are also lodged within the building. So far from being revolting, as is the case in many hospitals, it is a pleasing sight to enter one of the salles; its cleanliness puts to shame the confined frowsy wards of Greenwich Hospital. Here are wide, airy apartments, the roofs without speck, the floors, though of tile, sedulously polished and provided with pieces of carpeting, each window hung with white curtains, each bed of métal, also with white curtains and furniture. The *salle des officiers* is superior to the common rooms, even elegant. The kitchens, laboratories, linen closet, &c., are in the same style. Even the convicts when sick are received and nursed in this establishment.

A *British Consul* resides here.

At Hebert's library and reading-room, Rue d'Aiguillon, the papers may be seen, and many interesting works on Brittany, especially those of MM. Souvestre and Fremenville, obtained.

*Malleposte* daily to Paris in 40 hours; *diligences* daily to Paris by Rennes;—to St. Malo; to Lorient and Nantes. A *railroad* to Paris by Chartres is projected.

*Steamer* every other day traverses the roads and ascends the river of Châteaulin, on the way to Nantes (Rte. 44), as far as Port de Launay, a very pleasant voyage.

The *Roadstead of Brest* lies between the great promontory of Finistère on the N. and the smaller peninsula of Quélern on the S., which approach so near as to leave a passage only 1,749 yards broad between them, called the Goulet. The Mingan rocks, rising in the midst of this channel, contract the entrance still more, and

compel vessels to pass close under the guns of batteries which line it on either side and command it by a cross fire. The road consists of numerous bays into which several rivers empty themselves, the principal being the Elorn from Landerneau, and the Châteaulin, which is navigated by a steam-boat. In some places the harbour is 3 m. broad, and the area of its surface is estimated at 15 square leagues. All the fleets of France might lie snugly within it, and a hostile ship dare not venture within its entrance without the risk of being battered to pieces. Not only are the jaws of the harbour bristling with fortifications "*à fleur d'eau*," but the works are carried inwards so as to command the anchorage, and the batteries spread outside to the rt. and l. of the entrance, while every eminence is crowned with other forts commanding those below. The number of cannon and large mortars which could be brought to bear on an enemy from the batteries of the Goulet, and of the coast outside of it, is not less than 400, while 60 pieces sweep the anchorage from the forts within the Goulet. On the N. of the Goulet, in the midst of the bay of Bertheaume, are 2 island forts, united together by a rope bridge, and by one of wood with the shore. The extreme fort on this side is the batterie de St. Mathieu, under the ruined abbey (p. 129), and close to the new lighthouse. On the S. of the Goulet lies the bay de Camaret, one of whose numerous and formidable batteries goes by the name of *Mort Anglaise*, commemorating the miserable defeat of the expedition which landed here 1694 from a British fleet commanded by Admiral Berkley. On approaching the shore, the English found it bristling with armaments: batteries were thrown up on all sides, gunners at their posts, troops of horse and foot drawn up behind the guns, and as soon as the English began to disembark, 3 masked batteries opened on the ships a most destructive fire. 900 men under the



command of General Tollemache, who persisted in landing in the face even of such formidable preparations, reached the shore and were almost immediately cut to pieces: the ebbing of the tide having left their boats dry, and cut off their retreat. And thus the expedition failed miserably. What wonder! The news of the intended descent had been betrayed to Louis XIV. and James II. more than a month before by the Duke of Marlborough, the hero of Blenheim! These are the words in which he communicated the intelligence to his old master James:—"The capture of Brest would be a great advantage to England, but no advantage can prevent or ever shall prevent me from informing you of all that I believe to be for your service; therefore you may make your own use of this intelligence."—*Macpherson's State Papers*. In the interval between the receipt of this letter and the sailing of the armament, the skill and activity of Vauban had put the intended landing-place in such a state of defence, by throwing up batteries, disposing cannon, and collecting troops, as to render success hopeless, defeat inevitable.

The *Pointe des Espagnols* owes its name to a body of Spaniards, about 600 strong, who occupied it for several weeks, 1594, and threw up an earthen redoubt, which was captured by assault. The Peninsula of Quélern is defended by lines, drawn across the isthmus, which connects it with the mainland, nearly a mile long, consisting of bastions faced with masonry, constructed by Vauban, mounting 60 pieces of cannon. From a point near these lines, just above the Bay of Camaret, *the finest view* is obtained of the roads of Brest and their defences, with the point of St. Mathieu and the archipelago of Ouessant on the N., and on the S. the Bay of Douarnenez and the Pointe du Raz.

The defences above enumerated do not include those of Brest itself,

amounting altogether to 400 pieces of cannon, nor of the intrenched camp behind it, numbering 60 more cannon and mortars.

*Excursions.*—The country about Brest is far from picturesque, but it contains many objects of interest.

The *Menhir of Plouarzel* (§ 4), about 10 m. N. W. of Brest and 3 beyond the village of St. Renan, is the loftiest of those singular Celtic monuments now remaining in Finisterre. It measures 35 ft. in height, and stands on an eminence in the midst of a wild heath. Whatever its original destination, it is still looked on with awe by the peasantry, and singular superstitions are associated with it. Often in the dead of night the barren woman repairs hither, hoping to procure the boon of fruitfulness by rubbing her naked breast against the hard granite.

Near the mouth of the pretty river Aber Ildut, which flows past St. Renan, are the quarries of granite which furnished the pedestal for the obelisk of Luxor, erected in the Place Louis XV., at Paris.

3 m. N. of St. Renan, at Lanriouaré, is the graveyard of the 7777 saints, a walled enclosure, never trod by the peasants except with bare feet and head uncovered; it is paved with slabs, and marked by a cross.

The ruined *Abbey of St. Matthew*, situated on the extreme W. cape of Finisterre, N. of the Rade de Brest, is about 15 m. W. from Brest and 10 from St. Renan. The roads from both places converge at the little town of Le Conquet, where La Grâce de Dieu is a decent cabaret. Conquet suffered from an English fleet sent forth by Queen Mary, 1558, to ravage the French coast, and to surprise Brest, "because it was known not to be well garrisoned, and was thought the best mark to be shot at for the time." But the English commander contented himself with a far more inglorious enterprise. Landing at Conquet, "he put it to the sac-

cage, with a great abbey, and many pretty towns and villages, where our men found good booties and great store of pillage.”—*Holinshed*. Thence it is a walk of 3 m. along the tops of the cliffs, battered below by the waves, to the storm-fretted ruins of *St. Matthew's Abbey*, which stand on the bleak exposed promontory above the sea: the most W. spot of France, and with the exception of Cape Finisterre in Spain, of the European continent. It occupies a position similar to *St. Mary's Abbey, Whitby*, so as to be the first and the last object seen by the mariner quitting or entering the Bay of Brest. Whatever wind may blow, it is rare but it rages a hurricane around these mouldering arches and piers, which yet have braved for five centuries the pelting storm and whistling wind. The architecture is pointed in the greater part of the building, with some Romanesque portions and round arches. It is of solid granite, simple in style, and without ornament. Close beside the ruins, a *Light-house* has been erected. There is much savage grandeur in the scene around, viewed from this point, increased by the sullen roar of the mighty Atlantic chafing in the eaves and fissures of the rocks below. In clear weather the eye ranges over the dangerous strait called *Passage du Four*, beset with rocks, between the mainland and the granitic islands *Molène*, *Beniguet*, and *Ouessant*. The last is supposed by some to be the *Ultima Thule* of the ancients: its inhabitants remained idolaters down to the 17th century. The indecisive naval action of Ushant (as we call it) was fought off this island, 1778, between the French fleet under D'Orvilliers, and the English under Keppel and Palliser. On the S. the roads of Brest and the Peninsula of Quélern lie open, and on the horizon appears the *Pointe du Raz*.

On the E. side of the roads, and on the shore of the estuary of the *Landerneau* river, opposite to Brest,

lies *Plougastel*, remarkable for a *Calvary* attached to its cimetière, one of the most remarkable of the Gothic monuments of Finisterre. It is a crucifix of Kersanton stone (§ 6), adorned with a multitude of sculptures, rudely but forcibly executed, representing scenes of the Life and Passion of Christ. Some of the subjects, such as the Entry of our Saviour into Jerusalem to the music of the bigniou (bagpipe), the Temptation and Hell, are treated in a homely manner, approaching the grotesque, marking the hand of a rustic artist. “Notwithstanding its Gothic character, it appears by an inscription upon it to have been executed in 1602: but we must remember that the middle ages lasted longer in Brittany than elsewhere.”—*Souvestre*.

The costume of the women of *Plougastel* is remarkable for its elegance.

Ferry boats ply between Brest and the point of *Plougastel*.

The fine Gothic *Church of Folgoat* (Rte. 38) would form an agreeable day's excursion for any one who interests himself in architecture. He might take the patache, which runs daily from Brest to Lesneven and back.

## ROUTE 38.

ST. BRIEUC TO BREST.—COAST ROAD BY PAIMPOL, LANNION, MORLAIX, ST. POL DE LÉON, AND FOLGOAT.

The distances are marked in lieues communes of 3 Eng. m., measured from place to place.

This route properly consists of two excursions, from the high road from Rennes to Brest: it carries the traveller to a succession of interesting churches and ecclesiastical remains well worth visiting, though much of it lies over cross roads; no posting.

*St. Brieuc* (p. 122). A wretched patache runs between this place and *Paimpol*, passing near the little port of *Binic*, through *Plouha*.

Thus far there is nothing remark-



able, unless the traveller diverge about 1 m. to the l. of the road beyond Binic, to visit the beautiful Gothic chapel of *Lantec*, which has been compared with the Ste. Chapelle at Paris, but is far inferior to it.

From Plouha the antiquarian traveller should diverge to the l., to visit a ruined building, known as the

$7\frac{1}{2}$  *Temple de Lanleff*, about 8 m. from Plouha. A carriage cannot easily get within a mile of it, owing to the badness of the roads. It has been the subject of much controversy, some writers calling it a Pagan Temple: but in truth it is nothing more than an early Christian church, probably of the 10th or 11th cent., in the form of a rotunda, like the English churches of the Temple, St. Sepulchre, Cambridge, Little Maplestead, Essex, &c. But the building which it perhaps most nearly resembles, is the round church at Nymegen, in Holland, attributed to Charlemagne, but now in ruins. It consists of two concentric walls, the inner one a cylinder, 30 ft. high, resting on 12 circular arches, supported on square piers, with engaged columns on each side, of granite, having rudely carved capitals of monsters, human faces, rams' heads. Outside of this runs a lower concentric wall, destroyed for a considerable part of its circuit, but which once extended quite round the inner wall, and thus formed the aisles of the church. It is pierced with narrow loop-holed windows, which widen inwards, the early form common in churches built before glass came into use. The edges of the vaulted roof which covered this aisle may still be traced, and a small portion of the aisle is included in the modern church; but whether the vaulting of it be as old as the walls on which it rests cannot be distinctly affirmed. This ruin now forms a vestibule to a little village church. As a ruin, it is too rude in its architecture to be pleasing, but in the midst of it rises a noble *yew-tree*, tall and

straight, surmounting the old wall with its dark canopy of foliage.

The tradition of the country is, that it was built by the Templars, the "Moines Rouges," as they are called. It is just possible that Gothic architecture in Brittany was not more advanced in the 12th century than this building indicates.

Lanleff is about 24 m. from St. Brieuc and  $7\frac{1}{2}$  from

$2\frac{1}{2}$  Paimpol. — *Inn*: Pelican, ~~the only one, 1841, but not clean, and very extortionate.~~ 2112 inhab. *habable*  
*sur*  
*1850*

On the sea-shore, 2 m. to the E. of Paimpol, are the ruins of the *Abbey of Beauport* (in 1841 the keys were kept at Paimpol, and should be obtained before setting out). It is beautifully situated on the shore of a retired bay. The remains consist of a *Church*, now roofless, and deprived of the choir, in the pointed style, built 1202, with a W. front, showing an early English character, together with several conventual buildings at the E. end. An elegant small chapter-house, its vaulted roof supported on a row of circular pillars, is so perfect that it is now used as a school. On the N. side are an extensive vaulted cellar, and an apartment of a superior character also vaulted, which was the grand refectory. These serve the purpose of farm-buildings at present, being divided between 2 tenants.

From Paimpol to Treguier is about 9 m., passing through Lezardrieux, where the river Trieux, descending from Guingamp, is crossed by a fine wire suspension-bridge resting on lofty piers.

The castle of *La Roche Jagu*, near this, is an interesting specimen of domestic architecture, now in ruins, finely situated on the Trieux above Lezardrieux. It is a semi-castellated mansion, entered by a low doorway closed by an oaken door and a heavy iron gate of cross-bars. Although dismantled, it is inhabited by a peasant. There is a fine view from its roof.

Another still larger and loftier sus-

pension-bridge thrown over the Jaudy leads into

3 Treguier (*Inn*: Hôtel de France, tolerable), a town of 3178 inhab., occupying the summit and slope of a hill.

The *Church* in the market-place, formerly the cathedral, has a fine S. porch, the vaulted roof panelled, and the divisions filled with quatrefoils, and a doorway ornamented with statues in niches, of good workmanship. The piers of the nave are irregular in form, and its arches vary in width. The N. transept is Romanesque, with circular arches and well-wrought capitals to its pillars. Contiguous to it is a tower in the same style, and probably of the 11th century, though named Tour de Hastings, after the Danish pirate of a much earlier period. This tower is best seen from the cloisters, where some mutilated effigies of ecclesiastics and knights are deposited.

In a farm-house a little way out of the town, called Kermartin, is preserved the *bed of St. Yves*, a favourite Breton saint. It is a cupboard bedstead, the front of dark wood finely carved.

4 Lannion (*Inn*: Hôtel de ~~PEu-~~  
~~rope~~), on the Guier, possesses a market-place filled with odd old houses, several of a very peculiar style of architecture, and nothing else worthy of remark but narrow and dirty streets. A *diligence* runs daily to Morlaix. There is a post-road hence to Guingamp, 32 kilom., and another by Plesten, 18 kilom., to Morlaix, 19 kilom.

The district extending N. from Lannion to the sea, between the rivers Guier and Jaudy, is the very cradle of romance. King Arthur held his court at Kerdluel, graced by the presence of the Paladins, Lancelot, Tristan, and Caradoc; and a short distance off the coast is an islet called Agalon or Avalon, which the Bretons maintain to be King Arthur's burial-place, thus depriving Glastonbury of that honour.

About 6 m. S. of Lannion, on the E. bank of the Guier, between it and the road to Guingamp, is the *Castle Tonquedec*, one of the largest and best preserved in Brittany. It was built in the 13th century, and dismantled by order of Richelieu, after having served during the wars of the Ligue as a royal fortress. It consisted of 3 courts defended by moats, drawbridges, and portcullises. In the inner court is the *keep*, a tall round tower "accessible only by an opening in its 2nd story, approached by 2 drawbridges, supported midway upon an isolated square pier." The staircase was formed in the thickness of the wall. "In many respects these ruins are well worth coming some distance to visit. To the antiquary they are precious as a specimen of the finest military architecture of the 13th century. For the sketcher they combine the requisites to form a lovely landscape."—*Trollope*.

The direct road from Lannion to Morlaix (about 23 m.) passes St. Michel-sur-Grève, a spot where the sea encroaches on the shore, and a little farther we enter the department Finisterre. On the sands near this, according to the legend, King Arthur fought the dragon.

The *crypt* under the church of Lanmeur is of great antiquity, and encloses the holy fountain which caused its foundation, and is still held in repute by the common people. The piers which support the crypt have serpents carved on them.

About 5 m. N. of Lanmeur, close upon the coast, lies the village of *St. Jean du Doigt*, whose church, containing the precious finger of St. John, from which it is named, is a favourite place of pilgrimage with the peasantry, who repair hither to the number of 12,000 on the eve of St. John. The church has a wooden roof elegantly carved and painted, and surmounted by a spire of lead; it also possesses a ciborium bearing enamelled medallions of the 12 Apostles, a beautiful crucifix of the 16th



century, a chalice and a patina presented by Anne of Brittany, who was a patroness of St. John's finger. She built the hospice by the side of the church to receive pilgrims. *little*

Souvestre mentions a singular chapel called the Oratoire, between this and Plougasnon, in which the young girls who are about to marry in the course of the year, hang up their hair as an offering to the Virgin; this ancient Gaulish custom, however, is diminishing every year.

7½ *Morlaix* (Rte. 36, p. 123).

There is nothing very interesting beyond Morlaix until the towers and spires appear of

5 *St. Pol de Léon.*—*Inn*: Hôtel du Commerce, tolerable, and very cheap; bed, tea, and breakfast 2 fr.

This ancient and almost deserted ecclesiastical city reminds one of St. Andrew's in Scotland, and St. David's in Wales, in its remote position near the sea-shore, in its decayed state, and in its ancient edifices. It possesses 6700 inhab. and 2 very fine churches.

The *Cathedral*, dedicated to St. Pol, is flanked at the W. end with 2 fine towers, whose central stories, pierced with long and elegant lancet windows (like St. Pierre at Caen), are surmounted by spires, also pierced through to the sky. They open to the choir beneath, so as to form a sort of vestibule as at Peterborough. The nave is in the early pointed style, probably of the 13th century; the transepts display Romanesque features; in the S. transept is a fine circular window, its tracery cut in granite. The trough-shaped bénitier near the W. end was probably a tomb, and from its rude sculpture is certainly very old. The *choir*, longer, more ornamented, and of later date than the nave, is surrounded by double aisles, and ends in a Lady Chapel; it contains some good carved wood-work of the 16th century. The S. porch, a rich florid work with foliage delicately cut in Kersanton stone, merits examination.

The boast of St. Pol is the spire of the *Church of Creizker* (the word means centre of the town), 393 ft. high; a structure of open work of great lightness and grace, though constructed entirely of granite. The richly-ornamented square tower is surmounted by a very boldly-projecting cornice, above which rises the spire, its masonry cut to imitate overlapping tiles. The whole rests on 4 pillars, not particularly thick, but the arches of the aisles act as buttresses to support it. This spire was built at the latter end of the 14th century by John IV., Duke of Brittany; according to tradition the architect was English. The N. portal, florid and fringed, is very rich and in good taste, though much injured; the rest of the church is not remarkable. These are the curiosities of this dull town, and after exploring them one is happy to leave behind its grass-grown streets, and the melancholy which they inspire.

3 m. to the N. lies the little port of Roscoff. Half-way, near Chapel Pol, are some Celtic remains, several dolmens, and a menhir (§ 4).

Roscoff is filled with sailors and smugglers, and contains a vegetable prodigy, a *fig-tree*, in the garden of the Capucin convent, whose branches, supported by scaffolding, would shelter beneath them 200 persons. The church, though of the time of Louis XIV., has a Gothic character, while its details are Italian; below it are 7 very curious bas-reliefs in alabaster.

Opposite Roscoff lies the little island of Batz, separated from the mainland by a strait which may be crossed in 10 minutes. In the cemetery there is a monument of granite, to the memory of a lady who succoured the proscribed and fugitive priests during the Revolution. The young Pretender landed here after his hazardous escape from Scotland, subsequent to the battle of Culloden.

The road from St. Pol to Brest lies through

*rebuilt 1851 terrible.*

7 Lesneven. — *Inn*: Grande Maison; ~~does not look promising.~~ Some Roman remains, urns, &c. found a few miles S.-E. of this dull little town on the way to Landivisiau, have been supposed to mark the site of the long-lost Breton town *Occismor*.

Pursuing the road to Brest, 1 m. beyond Lesneven, on a drear, bleak, unsheltered spot, we reach the village of *Folgoat*, marked in the distance by its tall spire, little inferior to the Creizker, of unusual splendour for a village, attached to the *Church of Notre Dame*, one of the most remarkable Gothic buildings of Brittany. It owes its origin to the following circumstance:—This spot was once haunted by an idiot-boy, who was in the habit of begging alms of those who passed, using at the same time this one unvaried exclamation, "Oh! Lady Virgin Mary!" so that the place became known as "ar fol coat," the fool of the wood. The fool died, and in a short time there sprung up from his grave, even out of his mouth, according to the legend, a beautiful lily, whose leaves bore inscribed upon them the name of Mary. This miracle was noised abroad, and coming to the ears of John de Montfort, then warring with Charles de Blois for the dukedom of Brittany, he vowed to build a church on the spot if he triumphed over his rival. In consequence, after the victory of Auray, he laid the first stone on the spot where the lily had sprouted forth, but the church was not finished until 1423, by his son John V., who, in an inscription legible on the l. of the W. portal, claims to be its founder.

It is built of the very dark green stone called Kersanton (§ 6), which gives the edifice on the whole a gloomy appearance, but it is well adapted for delicate sculpture, and by the sharpness with which it has retained the delicate touches of the artist's chisel, shows how great judgment he exercised in selecting it. Almost every part of the church, in-

side and out, deserves minute inspection; the fertile invention, laborious pains, and dexterous skill of the sculptor are visible in almost every part, though the edifice has been sadly injured through neglect. This is more especially conspicuous externally in the W. portal, the canopy of which fell down 1824; but round the portal runs so delicate a wreath of thistles and vine leaves, perfect in their prickly flowers and stems, and even in the very fibres of the leaves, and the curves of the stalks and tendrils, as cannot be seen without wonder. Birds also (*chardonneret*) and serpents are interspersed among the leaves. Above the door is a bas-relief of the Nativity, the Adoration of the Magi on one side (St. Joseph with wooden shoes has all the character of a Breton peasant), and of the Shepherds on the other. Below, the centre pier is formed into an elegant niche enclosing the bénitier under a graceful canopy, and supporting it on a bracket. Among the foliage here and in other parts may be seen the ermine, the armorial device of the dukes of Brittany, bearing their motto, "*Melius mori quam fœdari*." The thistle (*chardon*) and the goldfinch (*chardonneret*) also recur repeatedly in the ornaments of various parts of the church.

A far more beautiful porch is attached to the S transept. Here 12 most exquisite niches line the vault leading to the door, in the mouldings around which similar leaves and wreaths are reproduced with far greater truth and delicacy. The stone from its peculiar colour has all the effect of bronze. This portal is believed to have been built by Anne of Brittany, as the arms of France united to those of Brittany are visible on it.

The sloping, open parapets which decorate the gables of the transept, the tracery of the E. windows, especially the central one surmounted by a rose, and the elegant arched niche at the E. end below it, on the out-



side of the church, constructed to receive the waters of the miraculous *fount*, which bursts forth from beneath the high altar itself, are not to be passed unnoticed. The water of this spring is held in great repute by pilgrims, who, regardless of bystanders, strip themselves to apply it to all parts of their persons.

Within the church on the rt. as you enter is the *Fool's chapel*, covered with frescoes nearly destroyed by the damp. Every capital, cornice, and border merits attention for the minute carving, but the chief object of interest is the *jube* or *Roodloft* between the choir and nave: it consists of 3 round arches most elegantly fringed, surmounted by canopies resting on panelled pillars, and supporting a gallery, of rich open work, pierced with quatrefoils. The foliage composing the crockets is an elaborate, yet natural imitation of the most complicated leaves, and the two angels who occupy the place of finials are well designed.

The E. window, seen from within, surmounted by its rose, is admirable for its tracery: the high altar below it is a single slab of stone, 14 ft. long, supported on a front of niche work filled with statuettes. The side screens and side altars are all more or less worthy of observation. There are numerous statues of saints curious for their costume. But the chief peculiarity of this church is the manner in which the sculptor who decorated it has rendered into stone the productions of the vegetable creation.

The roof of the church does not agree with the rest in splendour, and is evidently not completed conformably with the original plan.

The *Gothic College* on the N. side of the church was built by Anne of Brittany; she, as well as Francis I., were lodged in it when they came on a pilgrimage to Folgoat.

The country between St. Pol and Brest is very dreary; much heath, furze, and broom;—the cottages are

poor dingy peat-covered hovels, among which a few starveling black sheep seek a scanty mouthful: few trees appear higher than brushwood. There are many beggars, some of them rivalling in their rags the mendicants of Ireland.

We fall into the great high road from Paris about a mile before entering

6¼ *Brest*, in Rte. 36.

## ROUTE 41.

ST. MALO TO NANTES BY DINAN AND RENNES. — ASCENT OF THE RIVER RANCE TO DINAN.

To Rennes direct 71 kilom. = 44¼ Eng. m.; thence to Nantes 107 kilom. = 66¼ Eng. m.

The *détour* by Dinan is 13 kilom. or 8 Eng. m. longer than the direct road.

St. Malo is described in Rte. 27.

The pleasantest and shortest way to Dinan is to take the *Steamer*, which ascends the Rance 3 or 4 times a week, when the tide permits: at neap tides the steamer cannot navigate the Rance for 2 or 3 days. There is no beauty in the scenery nor comfort in the voyage except when the tide is up. It takes 3 hours.—*W. E. H.*

Owing to the variation of the tides on this coast, amounting to 40 ft., the current of the Rance is desperately rapid, and the river fills and empties with remarkable celerity.

The places passed in succession upon either bank are—

Rt. St. Servan and the Castle of Solidor, p. 100.

L. St. Suliac, the prettiest village on the Rance.

L. Port St. Hubert, a little watering place in a charming situation.

L. Plouer.

Rt. Pleadihen.

Chatelier.

L. Tadens.

The river is confined between lofty precipices nearly all the way to Dinan, and may vary in breadth from

$\frac{1}{4}$  to  $\frac{1}{2}$  a mile. Sometimes expanding into wide reaches, it resembles a Scotch lake. The sail up the Rance is very beautiful.

"On glided our boat; and, as the stream wound in and out amongst its high banks, we soon lost sight of St. Malo. Now darting through a narrow pass between immense bold rocks, which seemed scarcely to leave space for the passage of the boat, we could almost have touched the stony cliffs on either side; and now floating over the bosom of what seemed a wide, calm lake, we could perceive no outlet till we nearly reached the opposite shores. Thus alternately confined between tall crags, and pouring out into wide basins, the beautiful river flowed on; and, breasting its stream, we passed on in sunshine and shade, till at last, rushing out from one of the deep gorges through which it poured, we beheld an immense extent of undulating country, covered here and there with wood, and broken in various spots with crags, while, brightly relieved by the deep shadow of a cloud which covered all the foreground, the town of Dinan appeared on its high hill behind, with its old battlements catching the full light of the day, as they hung over the bold masses of rock on which the town is perched."—*G. P. R. James.*

The high road from St. Malo to Dinan runs on the E. side of the Rance, but only now and then in sight of it, and is devoid of interest until it comes in view of Dinan.

The postmaster charges 4 kilom. extra on quitting St. Malo at high water, on account of the circuit round the port which his horses are obliged to make, instead of crossing direct to St. Servan, as is done when the tide is out; but the new bridge will remedy this. See p. 99.

35 Châteauneuf, a strong fort covering the high road to Rennes; here are remains of an old castle.

We here quit the direct road to Rennes by St. Pierre de Plesguin

13 kilom.; Hédé 20 kilom. (in the chapel of Montmureau, near Hédé, Du Guesclin was armed a knight: here also he was married); Rennes 23 kilom. =  $34\frac{3}{4}$  Eng. m.

Some of the prettiest scenery of the Rance may be seen by those who, travelling *by land*, choose to quit the high road and their vehicle about 8 m. short of Dinan, walk over to the river at l'Ecluse, and ascend its rt. bank.

Pursuing the post road, the picturesque towers and spires of Dinan are close at hand as the crow flies, but it takes a good half hour to descend the steep hill at whose foot the Rance flows, and to ascend that equally steep, though now rendered accessible by zigzags, on the opposite side, before you can enter. A viaduct is in progress to carry the road on a level, but it will take some years to complete.

18 *Dinan.*—*Inns:* H. du Commerce, tolerable; Poste; both in the Place Du Guesclin;—H. de Bretagne, outside the gate, on the road to Brest, clean and cheap.

The country in which Dinan is placed is perhaps the most beautiful in Brittany. The situation of the town (8044 inhab.) is very singular, on the crown and slopes of a hill of granite, overlooking the deep and narrow valley of the Rance, flowing 250 ft. below it. The sides of the hill are excessively steep; but, notwithstanding, houses and streets have been built along the face of it to the water's edge. The Rue de Jersuel, which stretches down to the old bridge, is so precipitous as to be impracticable except on foot, and it is even difficult for a pedestrian to descend its slippery pavement; yet this originally formed the only approach to the town on the side of St. Malo, through a pointed and ribbed Gothic gateway.

The modern road from St. Malo, after making a wide sweep and many turns under the old walls, in order to master the hill, enters the town by the Porte St. Louis close to the old and picturesque *Castle*, built about



1300, and often inhabited by Anne of Brittany, but now a prison. It was besieged by the Duke of Lancaster, 1389, and successfully defended by Du Guesclin against the English. It stands on the edge of the ravine, on the outskirts of the town, and isolated from it by a deep fosse. The present entrance has been forced through a wall into the chapel, a finely vaulted chamber. A recess on one side, beside the altar, in which the lord or lady of the castle might hear mass without being seen, is called the *oratoire* of Anne of Brittany. The deep cornice of machicolations which crown the Donjon tower give it a very picturesque appearance, and there is a pleasing view from its top.

The *Place Du Guesclin* receives its name from that Breton hero, whose statue (in plaster!) is placed in the midst of it; and from the circumstance of its having been the lists in which he fought and vanquished an English knight, "Thomas of Cantorbrie," whom he challenged to single combat for seizing treacherously, in time of truce between the two nations, his brother Oliver, 1359.

The *Cathedral of St. Sauveur* is an interesting edifice to the antiquary, in the Romanesque style, such as is more commonly met with in the S. of Europe than in the N. The crumbling nature of the granite of which it is composed gives it the appearance of greater antiquity than it really possesses. The lower part of the W. front and the S. side are probably of the 12th or even 11th centy.: the rest is modernised. The central portal, a round arch deeply recessed within mouldings and pillars (the two outer ones detached), is flanked on each side by blank arches, containing statues of the four Evangelists standing on lions, &c., under curious Romanesque canopies. From the wall above, the winged lion and ox, attributes of St. Mark and St. Luke, project in high relief. The buttresses against the S. wall are in the form of round attached pillars,

or square pilasters surmounted by capitals. Nothing within the church merits notice except a black tasteless slab in the N. transept, bearing engraved on it and gilt a double-headed eagle, whose outspread wings are crossed by a bar, below which a quaint inscription, in gold letters, informs us that the heart of Bertrand Du Guesclin (spelt *g u e a q u i*) reposes beneath it, while his body lies among those of kings at St. Denis. Now, at least, neither statement is any longer true. The slab was found among the ruins of the church of the Jacobins, now razed to the ground; and all traces of the heart and of the tomb of the Lady Tiphaine, the wife of Du Guesclin, by whose side the heart was deposited, are gone: the body shared the fate of the royal ashes at the desecration of St. Denis in the Revolution. (See p. 22.) The old town wall and watch towers still remain; the streets in the older quarters abound in picturesque bits of architecture; and no spot in Brittany is better fitted to exercise the artist's pencil.

The admirer of ancient domestic architecture should explore the narrow streets with overhanging houses, the basements planted on pillars, each story projecting on corbels, which form the nucleus of the town. Arcades resting on carved granite pillars or wooden posts are very prevalent. Besides the steep Rue de Jersuel already mentioned, the Carrefour d'Horloge, so called from its lofty granite clock tower, the Rue de la Vieille Poissonnerie (where is a house bearing the date 1366), and the Rue de la Croix (where the house of Du Guesclin and his lady Tiphaine is shown near the Hôtel de Ville), are the most remarkable in this respect.

The English settled in Dinan are said to amount to 400 or 500: they have a *Chapel* here, in the Ancien Tribunal, Rue de la Lainerie, in which the English Church Service is performed on Sunday at 11½.

Mademoiselle Costa keeps a tolerable circulating *library*.

Mrs. Barr's Boarding-house, Rue de St. Malo, is recommended. It is kept by the widow of a captain of the 33rd.

The *Steamer* from St. Malo ascends the Rance as far as the bridge of Dinan. (See p. 135.)

*Diligences* daily to Rennes and Paris, to Brest, to St. Malo, and Dol.

On the outside of the town, under the old walls, now overgrown with ivy, while the ditches are converted into gardens, run most agreeable *Terraces*, commanding beautiful views over the vale of the Rance. The Mont Dol and Mont St. Michel are visible, it is said, from some points. There are manufactories of fine linen and of sail-cloth in and about the town.

*Excursions* almost without end, each varying from the other, may be made on horse and foot in this delightful neighbourhood.

At the distance of less than a mile from the Porte St. Louis, prettily situated in the bottom of a dell, through which a streamlet falls into the Rance, lies the village of *Lehon*, where are the ruins of a once celebrated abbey and a castle. The *abbey* is entered by a fine circular archway within deep mouldings: the church, now roofless, is in the early pointed style: it is called La Chapelle des Beaumanoir, from being the burial place of the family of that name, whose tombs were broken open at the Revolution, and the remains dispersed, while their monumental effigies, originally placed in the niches on either side of the church, have been removed to the Mairie. There are 4 figures of warriors armed, and an ecclesiastic, all in high relief; the drapery well executed, the hands folded in prayer. One of them is said to have been the leader of the Bretons in the famous "Combat des Trente." (See Route 42.)

The steep wooded height above the village is crowned by the *Castle*, now reduced to a square enclosure of walls

levelled down to the surface of the potato field which they enclose, having round towers in the angles and centre of each face. It was taken by Henry II. of England, 1168. From this castle-crowned height a beautiful view opens out of the village and abbey at its feet, of the course of the Rance and the romantic valley through which it flows. The navigation above this is continued by means of a canal which unites the Rance with the Vilaine.

The walk may be very pleasantly extended from this along the slopes of the hills, by paths across the fields behind the Hospice des Aliénés, towards the village of St. Esprit, where there is a curious Gothic crucifix, now much mutilated. The charm of this walk, however, is the fine view it presents of the antique towers and spires of Dinan, on the opposite side of the valley to the rt., and the insight it affords into the curious system of labyrinthine lanes, by which a great part of Brittany is traversed. The country is well wooded, abounding especially in oaks, and each field is surrounded by hedges. The lanes by which it is intersected in all directions, owing to the soft and crumbling nature of the soil, differ little from ditches worn down 8 or 10 ft. below the surface of the fields, and vary in character between a pool or slough of mud, or a mound of hard bare rock. A stranger is almost sure to lose his way among them, so intricate and numerous are their crossings. The country, seamed and grooved by these hollow ways, is like a rabbit warren, and this thoroughly explains how the Chouans and Vendéans were able, among such fastnesses, to put to defiance so long the armies of the Republican government.

On the opposite side of Dinan, about 1 m. distant, at the bottom of a really romantic little valley, is the spa or *Eaux Minérales*, a source of saline sulphureous water, good for liver complaints, much resorted to in summer. Alleys have been planted



and a sort of pump-room built, which contribute little to the beauty of the spot, though they cannot spoil it. A walk along the paths, cut through the trees along the steep sides of the dell, is highly to be recommended.

The *Château de la Garaye* is a ruined mansion of the time of Francis I., exhibiting in its falling walls and towers some picturesque bits of architecture, in the style of la Renaissance, intermixed with Gothic ornaments. The last owner, M. de la Garaye, quitting the gay world, converted this house into an hospital, while, with his wife, he devoted all his time and fortune to the care of the sick. To fit themselves for this duty they both studied medicine and surgery, and the lady became an excellent oculist. The hospital was destroyed at the Revolution, which the benevolent founders fortunately did not live to see, having died 1755-7; but the monument over the graves even of these benefactors of the district, in the churchyard of Faden, did not escape destruction from the ruthless hands of the Republican spoilers.

About 10 m. N. W. of Dinan is the *Château of La Hunaudais*, an interesting old castle surrounded by rampart and ditch, and tolerably perfect, in the form of a pentagon. It is supposed to have been built in the 13th century, by Olivier de Tournemine. It is to be reached only by a cross road, intricate to find without a guide, passing through Corseul, where Roman remains have been discovered.

About 10 m. beyond the castle, on the coast, is St. Cast, where an ill-contrived expedition of the English was ignominiously defeated in attempting an inroad on Brittany in 1758, with a loss of 822 men, including 42 officers killed and taken prisoners.

On the road from Dinan to Rennes the small town of Evrau is passed; it is situated on the *Canal* which joins the Rance to the Ille. The castle of the Beaumanoir here is now modern-

ised. The country beyond is very tame; fields and hedgerows, and few villages. Country houses, where they occur, lie at a distance from the road, without lodges or dressed grounds.

29 La Chapelle Chaussée.

24 Rennes, in Rte. 35.

There are 2 roads from Rennes to Nantes:

—a. By Derval 107 kilom. =  $66\frac{1}{4}$  Eng. miles.

16 Bout de Lande.

11 Roudun.

A high hill is crossed before reaching

17 La Breheraye.

9 Derval.

12 Nozay.

14 Bout de Bois.

14 Gesvres.

14 NANTES, in Rte. 46.

—b. By Châteaubriant 119 kilom. = 73 Eng. miles.

18 Corps Nuds.

17 Thourie.

18 Châteaubriant (*Inn*: H. des Voyageurs, small, but clean), a town of 3673 inhab., at the intersection of several roads. Its ancient walls remain nearly intact. The *Castle* was dismantled by Henri IV. and Louis XIII., but part of it, including a spiral stair leading to the chamber in which, according to tradition, Françoise de Foix was bled to death by her husband Jean de Laval (1525 or 37), are incorporated in the public offices. The *Ch. of St. Jean de Béré* is an interesting Romanesque structure.

18 La Meilleraye.

About 1 m. on the l. of the road lies a *Monastery of the Order of La Trappe*. It was sold as national property 1793, and was repurchased 1816 by a Romanist Society of Trappists, who had been settled at Lulworth in Dorsetshire, but their number has been greatly diminished (to 25) since 1830, in consequence of their having mixed themselves up with the Chouan insurrection of that period.

19 Nort is a small town on the l. bank of the Erdre, which becomes

navigable here for steamers. One plies daily between Nantes and Nort, to and fro. Below this the Erdre swells out into the form of a lake; on its rt. bank are Chapelle-sur-Erdre, and the castle of la Gâcherie, residence of the Princess Marguerite de Navarre, sister of Francis I., and authoress of the romances known by the title *Hep-tameron*.

A little farther is the castle of Blue Beard (Gilles de Retz), whose story is told in Route 58.

18 Carquefou.

11 NANTES, in Rte. 46.

### ROUTE 42.

MORLAIX TO NANTES, BY THE MINES OF HUELGOAT AND POULAHOUAN, CARHAIX, PONTIVY, JOSSELIN, AND PLOERMEL.

This is a cross country road, *not* a post road, but it is described because it includes several places of interest.

There is a good view of the picturesque town of Morlaix (p. 123) from the heights crossed on quitting it. The road gradually approaches and surmounts the chain of the Menez Arrés hills, through a desolate country chiefly moorland. The summit level is reached at Croix Court, which is also the boundary of the arrondissements of Morlaix and Châteaulin. About  $1\frac{1}{2}$  m. beyond Le Mendi, a hamlet 12 m. from Morlaix, a road turns off on the l. to Huelgoat (4 m. farther). Here is only a poor *Inn*, which, however, can furnish a clean bed and something to eat. Huelgoat is a town of 1,200 inhab., in a remote and thinly peopled district celebrated for its *Mines* of lead containing silver mixed with it. They are situated about  $1\frac{1}{4}$  m. from the town in the midst of a picturesque valley, through which runs a rushing stream, concealed from view at one particular spot by an *éboulement* of colossal fragments of rocks.

The path to the mines is carried through thick woods by the side of a narrow canal or aqueduct, conveying

water to move the machinery and the hydraulic pump by which the mine is kept dry. This machine is a masterpiece of mechanical skill, constructed by M. Juncker, an engineer of Alsace, and related to Cuvier. It well deserves the minute attention of all who take an interest in mining or machinery, and has been thought worthy of an eulogistic report, read to the Academy of Science by M. Arago. It has the force of 280 horses, and raises 3 cubic mètres 53 centièmes per minute, a height of 754 ft., effected by a column of water equal to 21 cubic inches, falling from a height of 196 ft. It has been at work for many years night and day; its movements are free from the least irregularity or the slightest noise. It is entirely under ground, at a considerable depth below the surface. The process of separating the silver from the ores by amalgamation with mercury is also very curious. M. Juncker, who for many years directed these works, introduced considerable ameliorations on the Saxon method, by means of which large masses of very poor ores have been worked, which were formerly rejected; by this means the prosperity of the Huelgoat mines has increased much of late years. Permission to enter the mines is readily given by the director. The best time for visiting them is at six o'clock, when the gangs of miners are shifted, and the nightworking set relieve those who have toiled through the day. The descent is made by a bucket and rope. The vein of lead has been traced for more than  $\frac{1}{2}$  mile in a clay slate of the upper Silurian formation. The lead ore (galena) is sent to Poulaouan to be smelted.

In the *Church* of Huelgoat is a curious reading desk (*lutrin*) resting on a pedestal resembling the classic tripod, but of wood, each of the 3 sides ornamented with a figure in bas-relief of a classic character. On one is a man with long hair and a mace over his shoulder, with no other



clothing than a short cloak; on another a young man in classic garb, bearing a torch in one hand, and a dart in the other; on the third a female bearing a cup and vase, in the guise of a Bacchante. It has been well described by M. Freminville; but nothing is known of its origin or the meaning of its carvings.

The *Ménage de la Vierge* is a species of cave formed by fallen masses of granite rock, through which a small stream of black water and of unknown origin flows, in places out of sight. It is possible with a sure foot and steady head to descend into the gulf. Near this is a *Rocking Stone*.

The *Cascades of St. Herbot* are worth the walk to them, less on account of the waterfalls themselves, than for the scenery of the little valley in which they lie, varied with dense woods and bare jutting rocks. The village *Church*, surmounted by a fine square tower on a height above, contains the tomb and effigy of the anchorite St. Herbot, some carved screen-work in the choir, and a *rood-loft* of elaborate and beautiful workmanship in the style of the Renaissance. There are 2 painted windows of rich colour with the date 1556. It has a fine W. portal in the decorated style, but bearing the date 1516, an ogee arch ornamented with frizzled foliage, and a still more beautiful S. porch, but the statues are poor. Herbot is a veterinary saint, who cures the diseases of animals, provided a lock of the beast's hair be laid on his altar.

At *Branilis* in the parish of Locqueffret, about 6 m. from Huelgoat, at a distance from any village, surrounded by 3 or 4 hovels, is a fine large *Church* in the best style of Gothic art, surmounted by a spire, and internally adorned with carving in stone and wood, and with painted glass, now all going to decay.

Poulahouan, on the direct road from Morlaix to Carhaix, contains other lead *mines*, but inferior in extent and productiveness to those of Huel-

goat. Here, however, are the *smelting houses* in which the ore from both mines is reduced. The galleries of the mine have been driven horizontally  $\frac{3}{4}$  of a mile and vertically more than 600 ft. in the *grauwacke*.

There is a direct road (15 m.) from Huelgoat to *Carhaix*, a primitive town (2,000 inhab.) among the hills, in the midst of that most unsophisticated district of ancient Brittany, Cornouailles. It abounds in old houses, with projecting cornices and carved timber work, and is inhabited by people as old fashioned as their dwellings.

Here is shown the house in which La Tour d'Auvergne (Théophile-Malo Corret) was born, in 1743; who, stern republican as well as brave warrior, steadily refused rank, but died the "premier grenadier de France," in the battle-field on the banks of the Danube. A statue of him by the Piedmontese artist *Marochetti* is erected in the Place. In the *Château de la Haye* are preserved his heart, an early portrait, his sword and his boots. The canal from Nantes to Brest will send a branch to Carhaix.

A little way out of the town on the road to Callac is an ancient structure, said to be a Roman aqueduct. There is also a Roman road which can be traced for more than a mile on the way to St. Gildas. Richard Cœur de Lion was defeated at Carhaix, 1197, by his rebellious vassals, the nobles of Brittany. Six high roads—to Brest, Morlaix, St. Brieuc, Vannes, Châteaulin, and Quimper—unite here.

A direct road leads from Carhaix to Lorient, by Le Faouet, and over the high range of the Montagne Noire. Not far from Le Faouet is a very handsome Gothic chapel.

The road to Pontivy and Vannes quits the dépt. of Finisterre soon after leaving Carhaix, passes Rostréven (dépt. Côtes du Nord), beyond which it crosses the Brest and Nantes Canal, and reaches

Pontivy (*Inn*: H. des Voyageurs),

an ancient town with old walls and gates, to which a new quarter was tacked on by Napoleon, who changed the name of the place to Napoleonville.

At the restoration of the Bourbons, however, his name and his public works were dropped; and many of the buildings remain half finished. The river Blavet, now rendered navigable to the sea at Lorient, and the canal from Brest to Nantes, afford openings for some commerce. The *Castle* of the Dukes of Brittany is of ancient foundation, but the actual edifice was rebuilt 1485. It is very picturesque, but rapidly falling to ruin. The fine church tower and spire of St. Nicodème is  $2\frac{1}{2}$  lieues from Pontivy.

About 6 m. N. of the road to Josselin is *Rohan*, cradle of the noble family of that name, now a poor and insignificant village, but prettily situated. Of the *Castle*, now neglected by the princes its owners, scarcely a morsel of wall remains above the surface; the last fragments having been pulled down to build cottages with the stones. —

Posting is established on the road between Pontivy and

34 Josselin.—*Inns*: Poste; Croix d'Or. The *Castle of Josselin*, an ancient feudal fortress, founded on a rock above the river Oest, was the residence of the famous Constable de Clisson, who added a donjon, now destroyed, to the building, and died here, 1407, in a chamber facing the river, still pointed out. The oldest parts are the round towers, on the outside, built of slate. The most remarkable portion of the building is the inner front, in the irregular but picturesque style of Gothic in its latest form, equivalent to our Elizabethan, and dating probably from the 16th centy. It is surmounted by pointed gables, and no two divisions correspond; the windows surmounted by Gothic canopies, are interspersed with parapets of interlacing tracery, in the midst of which the words “à plus,” the motto of the Rohans, to whom the castle still belongs, cut in letters

of stone, are constantly recurring. From the initials A. V. with a coronet, it is supposed to have been built by Alain VIII. Vicomte de Josselin.

The *Tomb of Olivier de Clisson*, in the *Ch. of Notre Dame*, was violated at the Revolution, and the effigies of himself, and his wife Marguerite de Rohan, through whom he inherited the castle, were broken to pieces. The mutilated fragments were to be seen lately in the sacristy. A modern mausoleum has been erected in execrable taste.

In the midst of a wild open heath, half way between Josselin and Ploermel, a modern obelisk marks the spot where the *Combat des Trente* took place. Here, if we may believe Breton poets and writers of modern date (for ancient authority is wanting for the event, and many have doubted whether it ever occurred), close to an oak, which has long since disappeared, called “chêne de mie voi,” a battle is said to have been fought 1351, between 30 Bretons on the side of Charles de Blois, and 30 partisans of Jean de Montfort, consisting of 20 English, 4 Flemings, and 6 Bretons, there not being enough English on the spot to form the full complement of combatants. The challenge was given by Du Beaumanoir, the Breton leader of the garrison of Josselin, to his opponents, who composed part of the garrison of Ploermel, in consequence of an alleged infraction of a treaty by the latter. The English were led on by a knight, whom the French call Brembro (? Pembroke), and after a very stout resistance were vanquished, chiefly owing to the death of their leader. The combat of the 30 is not mentioned in the oldest copies of Froissart, the contemporary chronicle of the wars of Brittany, and is doubted by Daru in his History; notwithstanding which the monumental obelisk erected since the Restoration, in the place of one destroyed at the Revolution, headed “Vive le Roi! Les Bourbons tou-



jours!" gives a list of the names of the 30 Bretons engaged in it.

12 Ploermel, in Rte. 45.

15 Malestroit.—There is no posting from this place to

Redon, a town of 4,500 inhab. on the Vilaine, a tidal river up to this point, and navigable for vessels of considerable size, while the navigation is continued by locks above this to Rennes.

The *Church*, originally belonging to the Abbey, is a fine Gothic building with a semicircular E. end. The conventual buildings are turned into a college.

The *Château de Beaumont*, in the vicinity of the town, retains 3 towers of considerable antiquity attached to its modern constructions. There are extensive slate quarries near this.

19 Rozay.

24 Bout de Bois. We here enter Rte. 41 a, p. 139.

14 Gesvres.

14 NANTES. (Route 46.)

#### ROUTE 44.

BREST TO NANTES, BY QUIMPER, AURAY, VANNES, AND LA ROCHE BERNARD.—EXCURSIONS TO LORIENT AND TO CARNAC AND LOK-MARIAKER.

307 kilom. = 191 Eng. m.

*Diligence* (mail) daily, in 36 hours, including 3 or 4 hours stoppages. It is a finely constructed road, though hilly from Brest to Le Faou.

Between Brest and Châteaulin the *steamer* (see below) is preferable to the diligence.

The high road from Brest to Châteaulin makes a great circuit, in order to avoid the creeks jutting out of the Bay of Brest: it follows the Paris road to

20 Landerneau (Rte. 36), then turns abruptly S. to

19 Faou, seated on a river which becomes all slime at low water. The costume of the people in these little towns, and indeed in this part of Brittany, is such as was worn in Eng-

land in the time of Charles I. and II.—slouched hats, trunk hose (bra-gou bras, *i. e.*, brogues or breeks), very wide, and with many folds, the hair hanging down the men's backs, reminding one of the pictures in Isaac Walton. The black charcoal burners thus attired have a very singular appearance. The women here wear a sort of cravat round their necks. The Pardon (§ 5), celebrated four times a year at Rumengol near Faou, is attended with very curious ceremonies.

From the high ground beyond Faou a pretty view is obtained on the rt.; the road, which is very hilly, next dips into a wooded and picturesque dell, at the bottom of which is a royal manufactory of gunpowder, called Pont de Puis. Another hill surmounted, and we reach the banks of the Châteaulin river at *Port de Launay*, the point of arrival and departure of the *steamer* from Brest.

The *steamer* runs only three times a week, making the voyage from Brest to Port Launay, 2 m. short of Châteaulin, in 4 hours. It traverses the Rade de Brest through its entire length, and thus enables the stranger fully to enjoy the beauties of that fine salt-water lake. For a general description of it, and of the vast range of batteries which defend it, see p. 128 (Rte. 36). On setting out, the opening of the Goulet is seen on the rt., and on the l. the wide creek or inlet which extends up to Landerneau. The steamer passes between

Rt. the Pointe des Espagnols, the extreme projection of the peninsula of Quélern, and l. the Pointe de l'Armorique, both strongly defended by forts. During the wars of the Ligue, a Spanish force sent over to aid the Duc de Mercœur in his resistance to Henri IV. took possession of the point, and intrenching themselves on it, completely commanded the entry of the roads. Their fort was at length captured by assault by Maréchal d'Aumont, assisted by 1800 English, commanded by Col.

Norris, sent over by Queen Elizabeth, after an obstinate defence, and all within it were put to the sword—the French say, chiefly through the savageness of the English. The English formed the forlorn hope, in scaling the breach; and here the veteran mariner Frobisher, the Tamer of the Spanish Armada, got his death wound.

The peninsula of Quélern, consumed on both sides by the ever restless waves, exhibits a fringe of notched and jagged rocks, which, as they become undermined by the ocean, are constantly giving way. Immense fissures are formed every year in the ground above, and are followed by numerous landslips. These bare and exposed promontories covered with heath, and cut up and corroded by the waves, were the chosen site of the worship of the Druids, and abound in those curious Celtic remains called Druidic stones. (§ 4.)

L. The Bay of Daoulas, or “Double murder,” is so called from the slaughter of two saints by a pagan chief, which gave rise to an *Abbey* whose ruins still remain. They are chiefly of the 15th cent., with earlier portions in the round style. Near this are the quarries of the Kersanton stone, so much used for the churches of Brittany. (§ 5.)

Rt. The steamer next enters the inlet of Châteaulin, bending round the projecting promontory Landevennec, on which are ruins of a church attached to a once celebrated Abbey, the Breton Chartreuse, which was destroyed at the Revolution, and its valuable charters and MSS. sent to Brest to be made into cartridges by the artillery.

The banks of the inlet, now contracting into a river, are picturesque, but the course of the stream is very winding.

At Port de Launay the voyage for steamers ends; the river Aulne being crossed by a weir and lock a short way above this, to render it navigable for barges as far as Châ-

teauneuf, where the canal to Nantes commences.

There are many slate quarries on the banks of the river near to

19 Châteaulin.—*Inn*: Poste, tolerable. A small, but not remarkable town in a pretty, park-like valley, having a bridge over the Aulne, and an old castle in ruins on a rock behind it. At *Pleyben*, 7 m. E. of this, is a fine Gothic *Church*, with a lofty tower and well-preserved sculptured portal, bearing inside of it statues of the twelve Apostles; the windows are adorned with painted glass. In the church-yard is a very curious *Calvaire* resting on 4 arches, on the sides and the top of which our Saviour's passion is represented in bas-reliefs and statues, more than 120 in number, not ill drawn, the drapery especially. The costume is that of the 16th cent., yet the date affixed to the monument is 1650.

Quimper may be reached from Châteaulin in about 2½ hours. The road here quits the valley of the Aulne by a steep ascent 3 m. long; from the very top of which, an open moorland tract, you still look down upon Châteaulin and its valley. This ridge is called the Black Mountain. It was near this part of the road that a party of intrusive clergy and bishops, appointed by the Revolutionist government, proceeding to a confirmation at Brest, were stopped, dragged out of the coach by a party of Chouans, and murdered on the highway.

24 Quimper (Corentin).—*Inn*: H. de l'Épée, the only good one.

Quimper is capital of the Dépt. Finistère, though it has only 9,860 inhab., while Brest has 30,000. It bears the stamp of antiquity as much as any town in Brittany, and is still partly surrounded by the walls and watch towers, erected for its defence by Pierre de Dreux, who, though a bishop, was also a great captain in his time. The *Cathedral* rears its stately W. front with a deep sculptured portal, rich in foliage, but much



fractured, between two massive towers, on one side of the market-place. It is a large and fine edifice, begun 1424, and has this peculiarity, that its nave is not on a line with the choir, which inclines considerably to the N.E., although the irregularity is not so perceptible as to be a defect. The interior is of a stately height; in the S. aisle is a curious grated niche. The pulpit is carved and gilt. The sculpture of the porch is like that of Folgoat in the beautiful treatment of the foliage. The towers though massive are not heavy, being set off by the slit windows 30 ft. high which pierce them, and by the light open parapet with which they terminate.

The ruined *Ch. of the Cordeliers*, begun 1224, with its elegant though mutilated cloister, and a large window looking over the Rue St. François, and the chapel of *Locmaria*, on the outskirts of the town to the S., apparently older than any in Quimper, and a work of the middle of the 12th century, will be appreciated by the antiquary.

The best and most modern houses line a quay on the rt. bank of the Odel, which flows through Quimper in the form of a canal. On its l. bank stands the Préfecture, fronting a sort of Champ de Mars, behind which a tall and steep hill rises, covered with a hanging wood, cut into terraces and zigzag paths, forming an agreeable public walk, leading to the top, whence there is a fine view of the river, which expands greatly below the town.

Quimper is said to be an agreeable residence; its situation is very pretty, and some trout fishing might be had in the neighbouring streams: the climate is bad, however.

For those who have time and inclination, there remains to be visited near Quimper the picturesque manoir of *Coat Bily*, a little to the rt. of the road to Châteaulin (date 1517); the elegant and well-preserved chapel of *La Mère de Dieu*, 16th cent.; the

*France.*

*Moustoir*, an ancient fortified mansion on the way to Concarneau.

A new high road has been made from this to the *Pointe* or *Bec du Raz*, a storm-beaten promontory surmounted by a lighthouse, which, though nearly 270 ft. above the sea, is constantly covered by the spray during tempests. The spot has little grandeur, but a savage wildness; the sea around is always tempest-tossed, and the shore of the Baie des Trépassés, so called from the number of dead bodies washed upon it, is perpetually covered with wrecks. The flat bare rocky peninsula of Penmarch abounds in Celtic remains. Near Soc'h is a Druidic parallelogram of upright stones, and the finest dolmen in Finisterre, consisting of 16 vertical slabs supporting two horizontal or tabular stones. (§ 4.)

The road out of Quimper to Quimperlé has been carried round the flanks of the hills, instead of over their tops.

21 Rosporden stands on the borders of a large pond.

25 Quimperlé (*Inn: Qy.* if any good one) is seated amidst hills, on a brawling river, the Elle, and is a pretty town. 5,300 inhab.

The large mass of building on one side of the Place, now serving as *Mairie*, &c., was originally a convent of Benedictines, attached to which, behind, is the *Ch. of Ste. Croix*, a building calculated to interest the antiquary and architect, from its age (10th or 11th cent.?), and its form, a rotunda surmounted by a dome with 4 projecting apses, one of which has been modernised. The arrangement of the central piers, concave inwardly, convex outwardly, the pilasters attached to them, the narrow, loopholed, roundheaded windows high up in the wall, all mark its antiquity. 3 flights of steps lead up to the altar, beneath which is a curious and still more ancient crypt, entered from the outside. It contains the grave of St. Gurlot: the

Bretons thrust their arms through a hole in his tombstone, in order to be cured of rheumatism. Above the main entrance to the church is a bas-relief of good execution, of the age of Francis I., representing the 4 Evangelists and the Theological Virtues.

There is another church (*St. Michel*) on the top of the hill, its ground-work Romanesque, with additions of the 12th and 15th centuries.

Travellers bound for *Lorient* (where the *H. de France* is a good *Inn*) take a route to the rt. of our line on quitting Quimperlé. There is nothing remarkable in that dull modern town of straight streets and 19,095 inhab., save its *Dockyard*, which is not readily shown to an Englishman, and which he need not care to see, as it is much inferior to those of his own country. The town is strongly fortified, and stands in the angle between two creeks, one of which, the estuary of the Scorff, forms the port militaire, the other the port marchand. They unite below the town, where they are met by the estuary of the Blavet from the E. and expand into the Roads; but as the dockyard occupies nearly the entire margin, and is surrounded on all sides by a high wall, all view of the water is excluded from the town, and contributes nothing to remove the monotonous dullness of its dirty streets, whose meagre houses look as though they were built merely to be knocked down. An excellent bird's-eye view of the dockyard may be obtained from the top of the tower of the parish church.

At the entrance of the *Dockyard* is the house of the *Préfet Maritime*. The adjacent buildings are part of those erected by the "Compagnie des Indes Orientales," whose establishment here, 1666, converted into a town a previously obscure village. The company was dissolved 1770. Law of Lauriston, the South Sea schemer, occupied the house which

is now the *Préfecture*. Near to it stands a narrow look-out tower 180 ft. high, overtopping all other buildings, affording a view of the whole roadstead and of the coast far and wide; near this is a small astronomical observatory. Lorient is exclusively a building dock; there are no bagnes nor convicts here. There are 15 or 16 building slips (cales) here, and on the opposite side of the creek, but only one has a permanent roof, fit for first-rates; the rest are mostly for frigates and steam-vessels. A new *Fonderie* near to the shed for masting vessels, 2 large mast-houses, and very extensive workshops, provided with a steam-engine, have been finished.

The roads open out at the lower extremity of the creek which forms the port: they are partly dry at low water. Some way down is the Ile St. Michel, covered with the yellow buildings of the Lazaret, and beyond it, on a projecting point, the fortress of *Port Louis*, commanding the entrance of the harbour, mounting 500 cannon. (?)

A *steamer* goes from Lorient to Nantes and *vice versâ* every week, touching at Belle Isle, a barren rock, which was captured by the English under General Hodson and Admiral Keppel in 1761.

The estuary of the Scorff is crossed by a wooden bridge in going to Auray from Lorient.

---

A *mail* runs between Quimperlé and Nantes daily in about 24 hours, through Lorient and Hennebon. The direct road to Hennebon passes out of the department Finisterre into the Morbihan about 6 m. from Quimperlé.

The river Blavet is crossed by an iron suspension bridge to reach

24 Hennebon, an antique town, 4477 inhab., situated on its l. bank, once the chief port of Morbihan. Its name must be familiar to all who



have read Froissart, through the noble defence which it made in the succession war of Brittany 1342, during two sieges sustained by Jeanne de Montfort against the armies of Philippe de Valois and Charles of Blois. The capture and imprisonment in Paris of Jean de Montfort would have ruined his cause in Brittany but for his heroic countess, who, possessing the courage of a man and the heart of a lion, threw herself into Hennebon, strengthened its works, filled it with provisions, and animated the courage of the garrison and inhabitants to resist to the last extremity. To marshal troops, to lead them to the onset, to fight hand to hand armed cap-à-pied with sword and casque, to manage a war-horse with the skill of the most adept cavalier, to preside in council, or dictate treaties; such were the accomplishments of this noble dame. Several times did she boldly sally forth at the head of her troops to assail the enemy, and on one occasion set fire to his camp; and when the besiegers turned round to defend it in such numbers as to cut off her retreat into the town, she forced her way through them and effected her escape to Auray, whence, after beating up the country around for 5 days, she returned in triumph to Hennebon with a force augmented from 300 to 600 men, and entered the gates in safety. At length the last extremity arrived; provisions were nearly exhausted, her counsellors advised surrender, and articles of capitulation were drawn up. She was forced unwillingly to consent to yield, provided at the end of 3 days succour did not arrive from England. On the eve of the 2nd day, as she was gazing from her watch-tower, she perceived the English fleet, which had been detained by contrary winds, entering the mouth of the Blavet full sail, bringing the brave knight Sir Walter de Manny, with a strong force of English knights and archers, and plenty of provisions. All

thoughts of surrender were now abandoned, and after one or two successful sorties the siege was raised. Two years after this, Edward III. in person landed here with an army of 12,000, which laid siege to Vannes. In 1375, however, the town was taken by Du Guesclin, and the English garrison all put to the sword, except the commanders Wisk and Prior, who were reserved for ransom. The only relics now remaining in the town from that period of bloodshed are a portion of the town wall on the side of the river, and an ancient *gate* which led to the castle; it is a pointed gateway between 2 very massive round towers, and is now a prison. The *Church* is said to have been built by the English; it is unfinished, and only remarkable for a lofty and elegant portal, recessed and fringed, not unlike that at Harfleur, surmounted by a crocketed steeple. There are some picturesque old houses here.

Near Baud (a poor town destitute of a tolerable inn), 15 m. N. of Hennebon, is the statue called *Venus of Quinipily*, from a castle of that name now razed to the ground, on whose site it is placed. It is of granite, coarsely worked and badly designed; the arms are crossed in front over a piece of drapery like a stole, descending half-way down the thighs; in other respects it is naked. Nothing is known concerning its origin, and the conjectures are very vague. One writer supposes, from its Egyptian character, that it was a Gallic Isis, and it is called Venus only in the inscriptions on the pedestal set up 1689. This much is certain, that down to the 17th century it was worshipped with foul rites, and is even now looked on with superstitious veneration by the peasantry.

A dreary and monotonous country of moor and heathland is crossed on quitting Hennebon to reach

13 Landevan.

15 Auray.—*Inn*: Pavillon d'en haut; tolerable. A town of 3734 in-

hab., on the Auray; in no wise remarkable, but from its position it is the best starting-point for a visit to the Celtic antiquities of *Carnac* and *Locmariaker*. Jolting gigs may be hired here for 10 fr. to go and return.

The Castle of Auray, no part of which is now standing, is said to have been founded by King Arthur. A battle fought under its walls, 1364, settled the succession to the dukedom of Brittany in favour of young de Montfort, son-in-law to King Edward III., who owed the victory to his English allies, led on by the brave John Chandos. In the opposite ranks fought Du Guesclin, who was made prisoner by Chandos, and Olivier de Clisson, who lost an eye in the battle. Charles de Blois was slain in the thickest of the fight, and there fell on his side not less than 5000 men, while the English lost a very small number.

*St. Anne d'Auray* is a celebrated pilgrimage church 6 m. from the town, frequented usually by 6000 devotees from all parts of Brittany in the month of July, but not otherwise remarkable. It is a modern and not handsome building.

In another direction, about a mile from Auray, is the nunnery of the *Chartreuse*, occupied by the Sœurs de la Sagesse, who instruct a school for the deaf and dumb. Attached to their church is the *Expiatory Monument* erected by the Bourbons to the memory of the 950 unfortunate Emigrés and Royalists who composed the ill-advised expedition to Quiberon, 1795, and who either fell there, or were shot by the Republicans on the banks of the Auray, at the spot marked by a Grecian temple not far distant from the Chartreuse. Another monument which has been placed in the church to record their unhappy fate is not a work of merit, either in general design or in the execution of the bas-relief intended to adorn it. It bears the names of those who fell.

The village of Brech was the birth-

place of George Cadoudal, a leader of the Chouans. Morbihan was the centre of their insurrection.

The *Excursion to Carnac and Locmariaker* may be made in one day by pursuing the following plan, and provided the traveller can walk 8 m., the only mode of passing between these two places being on foot. If the wind be favourable he may take a boat and descend the Auray to Locmariaker, a pleasant voyage of a little more than an hour; if he visit Gâvr Innis (*N.B.* In this case take candles and matches), 1 or 1½ hour more is required: from Locmariaker on foot to Carnac will take 2 hours. He must, however, beforehand, hire a gig at Auray, and send it on to Carnac to wait for him. He may return to Auray in the gig in 2½ hours.

In sailing down the estuary of the Auray he will pass

Rt. the Château de Plessis Kaer, a Gothic castle, with additions of the time of Francis I., and the ruins of another, called Rosnareu. Near this the boatmen assert that ruins of the piles of a bridge, which they attribute to Cæsar, may be discovered at low-water in the bed of the river.

Rt. A perfect Château, called Ker-entrec. The river now widens out, and a little farther on we enter

The *Morbihan* (Little Sea), an inland sea or archipelago from which the department is named, so thickly beset with islands that the common belief assigns them a number equal to the days of the year. The shores on all sides have a most jagged outline, fringed with capes, creeks, and inlets; they are of granite, barely covered with the scantiest vegetable soil, supporting a growth of barren heath; very often the surface is mere bare rock. 2 narrow peninsulas or arms, projecting from the E. and W., separate this gulf from the sea, allowing only a narrow passage between them. This archipelago is very difficult to navigate—a perfect labyrinth of islands, separated by intricate pas-



sages which only the experienced navigator can thread. The land rises but little above the sea; it is sterile in the extreme; the peasantry are miserably poor, and barely win a scanty crop from a soil whose proper productions seem heath and furze. Yet this melancholy and mysterious, but uninviting district, seems to have been the head-quarters of the religion of the Druids—the number of barrows, cairns, dolmens, and menhirs, &c. is extraordinary (§ 4).

The island of *Gâvr Inuis*, or Gaffr' né, nearly opposite Locmariaker, may be visited on the way thither, diverging a mile or 2 to the E. Here, underneath a cairn of stones (galgal), a subterraneous chamber has been discovered and cleared out. You enter by a triangular opening, crawling on hands and knees through a vestibule leading into a chamber, regularly formed, like a dolmen, of vertical stones covered by very large horizontal slabs. This chamber communicates with a much narrower gallery paved and roofed with stones, more than 40 ft. long: the entire length of the chamber being at least 50 ft.; its direction is from E. to W. Curious and unexplained figures of a rude kind, chiefly of a wedge form—intermixed with others evidently representing serpents—are engraved on the under surface of the stones; and one of them, forming a sort of partition, is pierced with a hole wide enough to pass the arm through, like the handle of a shield. Nothing has been discovered within this inexplicable structure; the stones composing it are granite. The only way to get to these islands is to take a boat from Locmariaker. The Auray boatmen either cannot or will not go over.

*Locmariaker* is a poor village, not possessing accommodation of the commonest kind for a traveller, nor even affording provisions. It stands on a heathy promontory projecting between the ocean and the Gulf of Morbihan, but is deserted by the tide at low water, so that one must land

at a sort of pier a little to the N. of the village, near the *Mout Hellu*, a mound of stones or galgal, about  $\frac{3}{4}$  m. N.W. of the village. There is another similar mound to the S.E. called *butte de Cæsar*. The most interesting of the Celtic monuments lie to the N. of the village, between it and the Mont Hellu. Contiguous to the last house is a menhir 20 ft. long, overthrown like every other in this district; a little to the l. on an eminence is a dolmen, the top stone of which is 12 to 15 ft. square, and in parts 3 ft. thick. Still farther to the N. lies prostrate and broken into 4 fragments the *largest Menhir* known; it measures nearly 60 ft. in length, and 5 or 6 ft. in height as it lies. It is difficult to imagine by what force so huge a mass can have been snapped short across, with such clean fractures. Some have attributed its fall to lightning. Near to it is another dolmen called *Dol ar Marchant*, the Merchant's Table, which seems larger than any other in the neighbourhood; it consists of 2 table-stones, one of them 16 ft. by 12, supported on 3 vertical ones; it is possible to creep under it, and remark the singular figures cut on its under surface. Between it and the Mont Hellu, a vast heap of cinders is said to have been found. (?)

There are many other similar monuments near Locmariaker, but these are the principal ones.

Locmariaker (i. e. place of the Virgin Mary) is supposed to occupy the site of the ancient *Dariorigum*, the capital of the Venetes: its position agrees with Cæsar's description of their "oppida in extremis linguis, promontoriisque posita," and some substructures of houses laid bare near the village are attributed to the Romans.

The *peninsula* of *Rhuys*, which, with that of Locmariaker, form, as it were, the natural piers separating the sea of Morbihan from the Atlantic, contains the following objects of curiosity. 1. Le *Grand Mont*, called also *la Butte de Tumiach*, situated

about 4 m. from Sarzeau, an obscure little town, but memorable as the birth-place of the author of Gil Blas. It is the largest tumulus existing in France, 100 ft. high and 300 in circumference, and is planted near the extremity of the promontory. 2. The ruined church of the *Abbey of St. Gildas de Rhuys*, remarkable because it was the retreat of Abelard in 1125, who narrowly escaped poisoning at the hands of the refractory and ill-conditioned monks, whose dissolute manners he wished to repress. The remains consist of a modern nave, and a very ancient choir in the Romanesque style, terminating at the E. end in 3 semicircular chapels. The walls of the transept are partly of herring-bone masonry. The date of the oldest part of the building is probably 1038. The tomb of the saint is pointed out; an ancient font deserves notice. St. Gildas is about 21 m. from Vannes. On the way to St. Gildas from Vannes, 3. the *Castle of Succinio* may be visited. It is a fine and perfect feudal fortress, built 1260 by John the Red, Duke of Brittany. It has nearly the form of a pentagon flanked by 6 round towers. It was the birth-place of the Constable de Richemont, who defeated the English at Formigny.

Between Carnac and Locmariaker, a deep frith of the sea penetrates far inland, and is crossed half way by a ferry; the way is very intricate, from the number of paths, so as scarcely to be found without a guide, and the road is very bad. The distance, 8 m., is practicable only on foot.

The Ferry of Cherispere over this inlet is prettily situated, and commands a view of the little port of La Trinité in the bay of Crach.


A little to the W. of the ferry, near some salt works, at the bottom of a shallow dell, is a rude monument to mark the grave of a royalist, shot on the spot, 1801.

The approach to Carnac is marked by the prominent Cairn, or *Tombelle de St. Michel*, so called from the chapel surmounting it. It is a cone

of loose stones artificially heaped together, standing at the E. extremity of the great army of rocks of Carnac, of which it commands a view, as well as of the sea and promontory of Quiberon.

*Carnac. Inn:* H. des Etrangers, a humble auberge.

The great *Celtic Monument of Carnac*, the most extensive in France, is situated about  $\frac{3}{4}$  m. from this remote village, and is traversed by the road from Auray. In the midst of a wide heath, as dreary and blasted in aspect as that "near Forres," extends this brotherhood of grey stones,—rude blocks set on end, angular, showing no marks of polish, and hirsute with the long moss which has covered the hard surface of the granite, and marks the length of time they must have stood in their present position. At first sight, it is difficult to distinguish any order, so many are overthrown, and the gaps left in the lines by depredations are so numerous and wide; indeed, every house and every wall in the vicinity seems to have been built out of this ready quarry. The great mass of the stones extends between 2 windmills. They are arranged in 11 lines, forming 10 avenues, with a curved row of 18 stones at one end, touching at its extremities the two outside rows.





The ranks are best preserved, and the stones are highest, near the farm called *Menec*. There are, it is said, not less than 12,000 stones, blocks of the granite which forms the basis of the country, and which is barely covered with soil, and in many places projects naked above it. None exceed 18 ft. in height, and a very large proportion are cubical masses, not more than 3 ft. high. They give one the idea of a regiment of soldiers, and the tradition of the country respecting their origin is, that St. Cornely (Cornelius), hard pressed by an army of Pagans, fled to the sea shore, but finding no boat to further his escape, uttered a prayer, which converted his pursuers into stones. Of the numerous theories invented by learned antiquaries to account for the origin and object of these stones, several are not less absurd nor more improbable than the legend just mentioned; none are satisfactory. The opinions perhaps least unworthy of consideration would suppose either that it was a burial place on the site of some great battle field, and that each stone marked a grave, or that it was a great temple dedicated to serpent worship. It was probably connected with some of those rites of initiation which formed part of the Druidical religion, and were derived from the same source as the Greek Mysteries.

At *Erdevan*, about 8 m. W. of Carnac, and again at *St. Barbe*, between Carnac and Erdevan, there are similar assemblages of stones, but not so numerous. Some have maintained that these three systems of rude pillars were once united, but there is no evidence of this. The piles of stones invariably follow the same direction from E. to W. One can scarcely see Carnac without comparing it with Stonehenge; and it must be admitted that in spite of the vast multitude of stones, the few and gigantic masses of Salisbury Plain are far more impressive than the long array of the petrified army on the heath of Mor-

bihan. At Carnac there are no cross-stones raised on the top of the upright slabs, as at Stonehenge.

The *Peninsula of Quiberon* stretches 10 m. S. into the sea, a little to the W. of the village of Carnac. Its name is associated with melancholy recollections of the ill-contrived and ill-executed expedition, consisting of 6000 French emigrants in the pay of England, who were landed there from a British fleet, 1795, and after a futile attempt to break through the Republican armies opposed to them, were for the most part driven into the sea by General Hoche. The surprise by Hoche, of Fort Penthièvre, which guards the neck of the peninsula, and of which the émigrés had made themselves masters on first landing, decided the fate of the expedition. Sombreuil, their brave leader, when expelled from it, drew up his little band on the farthest extremity of the sand, where they made the most determined resistance, so as to call down the admiration of their antagonists and fellow countrymen. Humbert, the republican general, advanced with a flag of truce, and promised that their lives should be spared if they laid down their arms. A storm prevented the British fleet rendering them any assistance; one corvette alone for a time checked the Republicans by its destructive fire, and a few of the fugitives were brought off in the boats of the squadron; but many, including women and children, perished in the waves. 950 unfortunate men, most of them persons of rank or station, who capitulated on promise of amnesty with their commander, Sombreuil, were, in spite of that, conveyed to Auray as prisoners of war, and shot there (see p. 148). The descent on Quiberon was an example of the danger of disgrace and failure which England runs by "waging a little war."

The road from Auray to Carnac is not good; the latter part is very bad.

There is nothing to note between Auray and

18 *Vannes*.—*Inn*: Hôtel du Commerce, tolerable. This town, capital of the Dépt. of Morbihan (population 12,000), is built at the extremity of a narrow inlet, branching out from the Gulf of Morbihan, and about 15 m. from the open sea. It possesses in an eminent degree the character of antiquity which distinguishes most Breton towns, in its narrow streets, overhanging houses, massive town walls and gates, but has no curiosities to detain the stranger. The portal of carved Kersanton stone, and the towers of the *Cathedral*, and a tower in the centre of the town, erroneously called *Tour du Connetable*, because Olivier de Clisson was said to have been confined in it, 1387, are the only buildings worth mentioning. 3 or 4 old convents, suppressed at the Revolution, now serve for barracks, and similar purposes.

The castle into which the Constable de Clisson was entrapped, under pretence of asking his opinion of the new fortifications, by John (IV.) de Montfort, who then locked the door upon him, and loaded him with chains, was the *Château de l'Hermine*, which was razed to the ground in the 16th century. Clisson owed his life to the forbearance of the governor, Bazvalan, who (like King John's Hubert) pretended compliance with de Montfort's order to murder his prisoner, but, when his master's anger cooled, informed him of his captive's safety. Clisson was not released, however, without paying a heavy ransom.

A sailing boat with a favourable wind will cross the sea of Morbihan to Locmariaker, on the way to Carnac (p. 148), in about 2½ hours; but as no conveyances are to be obtained at either of these places, most persons will prefer the land journey via Auray.

The excursion to the promontory of Rhuys is described (p. 149).

*Diligences* daily to Rennes (Route 45); to Brest; to Nantes.

Through a country abounding in heath and broom, we pass through

9 Theix, and

15 Muzillac, to

16 Roche Bernard, on the l. bank of the Vilaine, which is here crossed by a remarkably fine *Suspension Bridge* of iron wire, supported on 2 piers of granite masonry, each approached by 3 lofty arches of granite. The opening between the two points of suspension measures 626 ft., the elevation of the roadway above high-water mark 108 ft. In its general appearance it very much resembles the Menai bridge; it was constructed under the superintendence of M. Leblanc, the engineer des Ponts et Chaussées. It was completed 1839, and subjected to the trial of its strength, which the French law requires, by placing 2 rows of 115 carts and carriages heavily laden on the carriage way, and of 117 barrows filled with stones on the footpath, which it stood without the least symptom of weakness.

The road leading to and from the bridge is well engineered, and leaves the town of Roche Bernard on one side. *Inn*: Hôtel Silvestre, tolerable, on the new road,  $\frac{3}{4}$  m. S. of the bridge. Those who remember the tedious and dangerous ferry which this bridge replaces, and all the trouble and inconveniences of embarking and disembarking, will rejoice in the improvement.

There is nothing of interest beyond this; the country is very dreary, with few hills; the road in the Dépt. of the Loire Inférieure is only beginning to be macadamized.

19 Pont Château.

15 Le Moere. At Savenay, on the rt. of our road, in December, 1793, the last relics of that daring army of Vendéan peasants, which had crossed the Loire 6 weeks before 80,000 strong, now reduced to 8000 or 10,000, made a last stand against



the Republicans, but their obstinate bravery was of little avail against overpowering numbers. They fought long after their ammunition was exhausted, even women taking part in the combat, but were at length cut to pieces or made prisoners, 3000 only escaping back into La Vendée.

11 Le Temple. Glimpses of the estuary of the Loire, running parallel with our road, are seen on the rt. Near Santron, through which the road passes, is the Château de Buron, one of the residences of Madame de Sévigné. The approach to Nantes is marked by the number of neat country houses.

23 NANTES (in Route 46).

#### ROUTE 45.

RENNES TO VANNES BY PLOËRMEL,  
AND TO CARNAC.

92 kilom. = 57 Eng. m.

A *diligence* daily.

15 Mordelles.

20 Plélan.

24 Ploërmel (*Inn*: H. du Commerce), a town of 5207 inhab.

In the *Parish Ch.*, a low and heavy structure of the 12th centy., are the monumental effigies in armour of Dukes John II. (1305) and III. (1341) of Brittany. They were brought from the church of the Carmelites, founded by John II., who had fought in Syria against the Infidels, and had visited Mount Carmel; the sculpture is good, and they are tolerably perfect: the church was destroyed at the Revolution. These statues are interesting examples of the costume and armour of the time. There is some painted glass in the church.

About 7 m. W. of Ploërmel is the Castle of Josselin (R. 42).

10 Roc St. André.

16 Pont Guillemet.

Beyond this, about 1 m. to the rt. of the road, is the ruined *Castle of Elven*, one of the best preserved fortresses of the middle ages in Brittany, built on the model, it is said, of some castle in Syria. It stands on a flat, surmounted by a lofty octa-

gonal keep tower. Elven is interesting to an Englishman, because young Henry of Richmond (afterwards Henry VII.) was shut up in it for many years along with his uncle, the earl of Pembroke, by Francis II., Duke of Brittany. The two English fugitives, escaping from their own country after the battle of Tewkesbury, were driven by a storm on the coast of Brittany, and Henry remained a prisoner nearly 15 years, until 1484, when, escaping into France, he accepted the invitation of friends in England to supplant the tyrant Richard III.

18 Vannes. (R. 44; where the excursion to the *Druidical Monuments of Carnac* is also described.)

#### ROUTE 46.

PARIS TO NANTES, BY RAMBOUILLET,  
CHARTRES, LE MANS, AND ANGERS.

394 kilom. = 244½ Eng. m.

*Malleposte* daily in 28 to 30 hours.

*Diligences* daily.

*Railroad* from Versailles to Chartres.

The first part of the road by

12 Sèvres to

7 VERSAILLES, is described in R. 35. *N. B.* 8 kilom. "de faveur" above the real distance are reckoned in the first stage, and 4 in the second. The road to Rambouillet is uninteresting: it divides into 2 at Trapes; the rt. hand branch is the road to Brest (Rtes. 35, 36). Near Magny—Les Hameux are the scanty remains of the once celebrated abbey of *Port-Royal des Champs*, destroyed by royal decree, 1709, at the instigation of the Jesuits, as the head quarters of Jansenism, after the nuns, its tenants, had been subjected to the most cruel persecutions in order to compel them to subscribe to the bull of Alexander VII. against the doctrines of Jansen. In 1644, a number of learned men and profound divines, professing the same doctrines, settled in a farmhouse near the convent, called La Grange, repairing hither for study;

and here composed those works which, as "they were published anonymously, are known by the name of their place of residence. Arnauld, Nicole, are among the Messieurs de Port-Royal,—an appellation so glorious in the 17th century."—*Hallam*. Boileau and Pascal were their friends, and Racine, who wrote their history, their pupil.

"He whose journey lies from Versailles to Chevreuse will soon find himself at the brow of a steep cleft or hollow, intersecting the monotonous plain across which he has been passing. The brook which winds through the verdant meadows beneath him stagnates into a large pool, reflecting the solitary Gothic arch, the water mill, and the dove-cot, which rise from its banks, with the farmhouse, the decayed towers, the forest trees, and innumerable shrubs and creepers which clothe the slopes of the valley. France has many a lovelier prospect, though this is not without its beauty, and many a field of more heart-stirring interest, though this, too, has been ennobled by heroic daring; but through the length and breadth of that land of chivalry and of song, the traveller will in vain seek a spot so sacred to genius, to piety, and to virtue. That arch is all which remains of the once crowded monastery of Port-Royal. In those woods Racine first learned the language—the universal language—of poetry. Under the roof of that humble farm-house, Pascal, Arnauld, Nicole, De Sace, and Tillemont meditated those works which, as long as civilization and Christianity survive, will retain their hold on the gratitude and reverence of mankind. There were given innumerable proofs of the graceful good humour of Henri IV. To this seclusion retired the heroine of the Fronde, Ann Geneviève, Duchess of Longueville, to seek the peace the world could not give. Madame de Sévigné discovered here a place 'tout propre à inspirer le désir de faire son salut.' From

Versailles there came hither to worship God many a courtier and many a beauty, heart-broken or jaded with the very vanity of vanities—the idolatry of their fellow-mortals. Survey French society in the 17th century from what aspect you will, it matters not, at Port-Royal will be found the most illustrious examples of whatever imparted to that motley assemblage any real dignity or permanent regard. Even to the mere antiquarian it was not without a lively interest."—*Edit. Rev. St.*

The *Château de Dampierre*, in the vale of Chevreuse, has lately been restored by its owner, the Duc de Luynes, one of the richest nobles in France. It has been adorned with paintings by *Ingres*, and with sculptures by *Simart*. The park has an area of 2,000 acres. The valley is one of the prettiest and least visited spots in the vicinity of Paris. The *Château* is curious.

18 Coignières.

14 Rambouillet, a dull town of 3,000 inhab., remarkable only for its *Château*, long the residence of the kings of France, down to the time of Charles X., who, after the July revolution, here signed, in conjunction with the Duc d'Angoulême, his abdication of the French throne, Aug. 2, 1830; under pressure of the news that the mob of Paris, armed, was on its march hither, seeming to threaten results not unlike those which befel Louis XVI. at Versailles, Oct. 1789. It is a gloomy and ugly pile of red brick, with 5 flanking towers of stone, destitute of interest beyond what it may derive from its history. A chamber is shown in the great round tower where Francis I. died, 1547, aged 52. The dreary park and extensive forest adjoining, the favourite sporting ground of Charles X., are now hired to private clubs of sportsmen. The *château* is let to a private individual.

Beyond this the road becomes more hilly and varied.

13 Epernon, no tolerable *Inn*. The



name of this town of 1,600 inhabitants was changed from Autrist to Epernon by Henry III., who created it and the district around a duchy for his favourite Negaret. It retains portions of its old walls and towers, and is prettily situated on the banks of the Guesle, under a commanding rock of limestone.

The *Château* attached to the little town of

9 Maintenon was given by Louis XIV., with the estate and title of Marquise de Maintenon, to Françoise d'Aubigné, widow of Scarron, at the time when the king made her his wife. Their marriage is said to have been celebrated in the chapel of the castle by the Père la Chaise in the presence of Harlay and Louvois, 1685, she being 50 years old and Louis 47. The castle stands on the margin of the Eure, and now belongs to the Duc de Broglie; parts of it are said to belong to the original structure raised by Cocquereau, treasurer of finance to Louis XI. and Charles VIII. The bedroom of Mde. de Maintenon, and her portrait in robes trimmed with ermine and fleurs-de-lis, are shown.

The valley of the Eure is here crossed by the imposing ruins of the aqueduct, constructed 1684, at the mandate of Louis XIV., to convey the waters of the Eure from Pont Gouin to Versailles, but afterwards abandoned for the machine at Marly.

"As Louis had committed the blunder of building in a place without water, he proposed to remedy his mistake by conveying the river eight leagues, by a new channel, to adorn his park. To accomplish this it was necessary to join two mountains at Maintenon, and form an aqueduct: 40,000 troops were employed in this great work, and a camp formed expressly for the purpose. From the unhealthiness of the work or of the air, a great mortality ensued; the dead were carried away in the night time, that their companions might not be discouraged; but the loss of

many thousand lives to please the wanton caprice of a despot excited no sympathy and created no surprise. The war of 1688, however, interrupted the labour, and it was never afterwards resumed."—*Lord John Russell*. It was partly pulled down, after a lapse of 65 years, to build the villa of Crécy for Mde. de Pompadour. The remains consist of 47 arches, 42 ft. wide and 83 high. The total length of the canal, of which this was to form a part, would have exceeded 33 miles, if completed.

On leaving Maintenon behind, we enter the fertile plain called *La Beauce*, comprising some of the finest corn land in France. The twin steeples of Chartres are conspicuous a long way off.

19 CHARTRES. — *Inns*: Poste or Grand Monarque, best; Hôtel Duc de Chartres; Hôtel de France, tolerable.

Chartres, a city of 14,439 inhab., once capital of the fertile Beauce, and now of the Dépt. d'Eure et Loire, is situated on a slope, at the bottom of which runs the Eure, washing the only remaining portion of the old fortifications, and two of the city gates. The *Porte Guillaume*, one of these, is picturesque; the rest have been pulled down, the ramparts levelled into walks, and the town thrown open. Chartres is remarkable in a *commercial* point of view for one of the largest corn markets in France, held every Saturday, where the produce of the Beauce is disposed of; and in point of *architecture*, for its

*Cathedral*, one of the most magnificent in Europe, conspicuous far and near, with its two tall but unequal spires surmounting the hill on which the city stands. Its most striking and interesting features, after its vast dimensions and elegant proportions, are its two rich and singular lateral portals, its painted glass, scarcely equalled in France, and its three rose windows.

There is much perplexity in the dates assigned to different parts of the building, but, with the evidence of style, we may pronounce the *Crypt*, running under the whole extent of the choir aisles, to be the only part remaining which was built by Bishop Fulbert, 1029. He was aided in his pious foundation by gifts from the kings of England, France, and Denmark, and a great body of people came over from Rouen to work at it, encamping in tents around while it was in progress. The church, as it exists, was not dedicated until 1260, and the greater portion of it may safely be referred to the 13th centy.; but the W. front was completed in 1145, except the elegant crocketed N. spire raised in 1514, partly at the charge of Louis XII., by Jean Texier, an architect of the Beauce: it is 304 ft. high, and the upper part of beautifully light and delicately executed work. In the W. front, which is simple in its style, we have to remark the triple portal of pointed arches; that in the centre supported and flanked by statues of royal saints. These are attenuated figures with formal plaited drapery, characteristic of the Byzantine sculpture of the 12th centy. Above the door is the image of Christ in an oval, with the symbols of the 4 Evangelists, as designated in the vision of Ezekiel, around him. Below these are the 14 Prophets in a row, and in the arches above the 24 Elders of the Apocalypse, playing on musical instruments of the middle ages. The sculpture of the rt. hand portal relates to the life of the Virgin, and in that of the l. is seen Christ again surrounded by angels, with the signs of the zodiac, and the agricultural labours of the 12 months.

Far finer are the two entrances on the N. and S. sides, consisting of triple projecting Gothic porticos (something like the W. end of Peterborough), resting on piers, or bundles of pillars, with side openings between them. The stately statues which line

the sides and vaults are of a superior style of art, and of a later date (14th cent.) than those of the W. front.

The interior is of such consistent vastness in all its parts, that its dimensions do not perhaps strike the spectator, at first sight, to their fullest extent, but its length is 422 ft., and the height to the apex of its roof 112 ft. The style throughout nave and choir is the vigorous early Gothic. In the centre of the nave a maze or labyrinth, of intricate circles, is marked out on the pavement in coloured stone: to follow it through its windings (1320 ft. long), saying prayers at certain stations, was probably, at one time, a penitential exercise. The church possesses a perfect treasure of *Painted Glass*, more than 130 windows being completely filled, and few being quite destitute of this splendid ornament. They date, for the most part, from the 13th cent. Some of the glass is  $\frac{1}{2}$  an inch thick. The 3 rose windows at the end of the nave and transepts are remarkable for their size, 30 or 40 ft. diameter, and their complicated tracery, but it is somewhat clumsy. The windows, both in nave and choir, illustrate subjects from the Bible or Legends of saints; in the lower compartments are frequently seen representations of various trades—shoe-makers, basket-makers, &c., showing that their guilds or corporations were the donors.

Attached to the E. end is a chapel dedicated to St. Piat, in the form of an oblong; it was founded in 1349, and is flanked by two round towers externally.

The choir has double aisles and a semicircular E. end; in the inside 8 marble bas-reliefs, of Scriptural subjects, mediocre in design and execution, are inserted, and behind the high altar is a huge marble piece of sculpture, in the taste of the time of Louis XIII., not consistent with the character of the building. The outside of the screen, which separates the choir from its aisles, is ornamented with a series of very remark-



able Gothic sculptures, each representing an event in the life of Christ or the Virgin Mary, in 45 compartments surrounded with the most elaborate tracery and tabernacle work; they were begun 1514, and continued down to the middle of the 17th century, and are interesting as some of the final efforts of Gothic art. The execution has been compared to "point lace in stone, and some of the sculptured threads are not thicker than the blade of a penknife."

In the choir of Chartres cathedral Henri IV. was crowned, 1594;—Rheims, the ancient scene of the royal coronation, being at the time in the hands of the Leaguers. The ceremony was performed by the bishop of the diocese, and as the "Sainte Ampoule" was not to be got at, a vial of holy oil, said to have been given by an angel to St. Martin of Tours, to cure a bruise, was brought in procession from the Abbey of Marmoutiers, and with this the King was anointed. This cathedral narrowly escaped destruction by fire in 1836: fortunately the roof and interior of the towers were alone consumed.

After exploring this noble and surpassing edifice, the traveller will probably have little desire to look at inferior churches, yet *the only* other curiosities here are

The *Church of St. Pierre* (St. Père), contiguous to a huge caserne, once a convent, and not far from the river;—although very inferior to the cathedral, it presents a remarkable lantern-like E. end, filled with rich painted glass. The lantern character is increased by the triforium, running all round the choir, being open, and glazed. The choir, though pointed, must be very early in the style, the piers having a Romanesque character, the nave slightly different, and apparently later, yet retains the transition appearance in its columns. Its triforium is a row of trefoil headed arches, supported on pilasters.

*St. André*, also near the river, and

now a magasin de fourrage filled with straw and hay, is yet interesting to the student of architecture as an early, plain, and severe example of the pointed style. In the W. façade a circular headed doorway is surmounted by a triplet of lancet windows, and these by a bold rose window. The piers supporting the nave arches are cylindrical, marking the transition from Romanesque to Gothic. The choir, which was carried across the Eure, is destroyed. A curious crypt extends from the south aisle down to the river and below its level. St. André is supposed to have been founded 1108.

An *Obelisk* has been set up in the Marché aux Herbes to record the fact that *Marceau* was a native of Chartres—"Soldat à 16 ans, Général à 23; il mourut à 27." The original inscription mentioned his exploits in destroying the rebel Vendéans at Le Mans and Laval. The Revolutionary leader Pétion was born here.

The *Corn Market* is exceedingly well regulated; business is transacted for ready money, and is usually over in  $\frac{3}{4}$  hour. The measuring and selling of the grain, and receiving payment for it, are managed by a corporation of women, of long standing, remarkable for their integrity, and implicitly trusted by the owners.

There is a public *Library* of 30,000 volumes and a *Museum* in the town.

*Diligences* daily to Orléans and Rouen by Evreux (R. 50). To Tours by Vendôme (R. 54). To Nantes.

*Railway* to Paris by Versailles.

The little village *Bretigny*, 6 m. from Chartres, gives its name to the celebrated treaty of peace signed 1360, between France and England, by which Edward III. renounced his claim to the throne of France, and released the French king, John, taken prisoner at Poitiers, upon payment of a vast ransom, and delivery of numerous hostages. A violent storm which fell upon Edward and his army near Chartres, and "reminded

him of the day of judgment," caused him to make a vow (looking towards the towers of the cathedral) that he would give peace to France, and led to this important treaty.

The journey from Chartres is continued through the monotonous but fertile and well-cultivated corn plain of La Beauce to

19 Courville, 3 m. S. of which is the Château de *Villebon*, where the illustrious Sully died. It is a square building of brick, with towers at the angles, and not many years ago retained its ancient furniture, even to the bed on which the great minister expired. The Eure is crossed for the last time by the road near Courville; it rises about 15 m. to the N. of the road.

18 Montlondon. Here the fertile Beauce terminates, and the country becomes hilly.

19 Nogent-le-Rotrou, a town of 7070 inhab., contains a ruined *Castle*, the residence of Sully, and his *Monument* in the chapel of the *Hôtel Dieu* founded by him. It bears the marble statues of himself and his wife by Boudin, 1642, and a long inscription at the back: it escaped the fury of the Revolution, but the grave itself was violated, and the bones disinterred and scattered. The word Nogent is an abbreviation of the Latin Novigentium; Rotrou was the name of a count of Perche, in which district it is situated. The river produces crawfish in great abundance. (*Inn*: St. Jaques.) The road follows the direction of the Huisne river from Nogent nearly to Le Mans.

22 Ferté-Bernard is a prettily situated town in the Dépt. de la Sarthe, skirted by the road. Within it the *Parish Church* is an interesting Gothic building, having a richly sculptured external gallery with the words "Salve Regina" cut in stone, and 3 chapels, from the vaulted roofs of which hang stone pendants.

19 Connerré. Near this is a large Dolmen or Druidic monument of rude stone slabs, like Kits Coity house in Kent. (§ 4.)

10 St. Mars-la-Bruyère indicates by its name the desolate sandy heaths in the midst of which it is situated.

15 *Le Mans* (*Inn*: Le Dauphin), once capital of the province of Le Haut Maine, now chef-lieu of the Dépt. de la Sarthe, is situated on the l. bank of the river Sarthe, a little above the junction of the Huisne, and has 20,000 inhab.

The principal edifice is the *Cathedral* of St. Julien, which is well deserving of attention. It is in two styles; the *nave* Romanesque, though with pointed arches, dates probably from the 12th century, but its side aisles and walls and the plain W. front are not later than the 11th, perhaps much earlier. Indeed, the external masonry of the side walls, resembling Roman construction, is probably part of the original church, founded in the 8th or 9th century. Above the W. door are portions of reticulated masonry, and an ancient bust of a king or bishop; on each side are figures supposed to represent the 2 signs of the zodiac, Capricorn and Sagittarius.

On the S. side is a very richly carved Romanesque *doorway* — a round arch preceded by a pointed porch flanked by statues of kings and saints, resembling the W. door at Chartres, and with angels in the vault. It is much mutilated, unfortunately.

The *Choir* is a beautiful production of the 13th centy., the period of perfection in pointed Gothic architecture. It is surrounded by 11 chapels, and its windows are filled with beautiful painted glass, little inferior to that of Chartres, except in preservation. In the transept is a fine rose window, together with much stained glass, of the 14th or 15th century, a date rather more modern than that of the choir.

This church contains the monuments of Berengaria of Sicily, queen of Richard Cœur de Lion, brought from the abbey of Epau, and much defaced; of Charles of Anjou; and



of Langey du Bellay, distinguished as a soldier and as a writer in the reigns of Francis I. and Henri II. The last is attributed to Germain Pilon; its arabesques and bas-reliefs in marble are well worthy attention.

An undressed block of silicious sandstone, standing on one end, has been incorporated into the wall of the church on the outside; it is supposed to be a Druidic stone.

The Church of *Nôtre Dame du Pré* is probably of the 11th century.

*Nôtre Dame de la Coûture* (de culturâ Dei) has a very old choir, supposed to have been begun 990; both arches and vaulting are round and of rude construction: it has a very elegant portal, adorned with sculpture of considerable merit (Last Judgment). The conventual buildings to which it was originally attached are now the *Prefecture*, but contain besides, the *Library* and a *Museum*, partly devoted to natural history, partly to paintings of a very inferior order, but possessing one curiosity at least, viz. a portrait of Geoffroi Plantagenet enamelled on copper, a very early specimen of that class of art: it was anciently placed in the cathedral where he was buried. There are also many objects of Roman antiquity found in le Mans and the neighbourhood, at Alonnes pottery, &c.

*St. Pierre* is supposed to be the oldest church here, that is to say, the lower part of its walls.

The *Séminaire*, originally the *Abbaye de St. Vincent*, has a noble façade and a fine staircase. There is a handsome theatre.

Many specimens of ancient domestic architecture still remain here, especially in the *Grande Rue*. Nos. 7, 10, and 12 deserve attention; the last is known as the house of Queen Berengaria, but appears not to be older than the 15th century. It contains a chimney-piece adorned with bas-reliefs. The house of Scarron (husband of Madame de Maintenon) is pointed out near the cathedral.

The vestiges of the Roman rule at Le Mans are not considerable: the chief are the remains of 3 subterranean aqueducts, by which the city was supplied with water from a distance. A portion of them may be seen in a cellar of the *Rue Gourdaïne*. Fragments of the Roman town walls still exist; but all traces of an amphitheatre, discovered in the last century, have been swept away.

Le Mans was the birthplace of Henry (II.) Fitz-Empress, the first of the Plantagenet kings of England; a name derived from the plant or sprig of broom (*genêt*), the abundant production of his native province Anjou and Maine, which his father, Geoffroi, used to wear in his cap.

A great trade is carried on here in clover seed, which is sent over in large quantities to England. The chief article of manufacture is *wax candles*. Le Mans is also famed for poultry: its poulards and chapons supply the markets of Paris.

Le Mans witnessed the ruin and final dispersion of the Vendéan army in 1793. Worn out by the disastrous fatigues of a six months' campaign, they were here assaulted by the Republican forces under Marceau's command. Most obstinate was the resistance made by the Royalists in the streets and great square of the town before they were finally expelled, with their leader, La Rochejaquelin, who was wounded in the action. Then ensued the most fearful carnage, not only of the Vendéan soldiery, but of their miserable wives and children, who accompanied them. By the joint exercise of cannonades of grape, and platoons of musketry, discharged upon the defenceless crowd, under the order of the commissioners of the Convention, upwards of 10,000 persons were slaughtered on that occasion.

*Conveyances* daily to Caen by Alençon and to Tours (R. 29).

The road, on quitting Le Mans, crosses the Huisne just before it falls into the Sarthe, and then runs along the l. bank of that river as far as

16 Guécelard. On the outskirts of Le Mans, not far from the bridge over the Huisne, the buffoon Scarron threw himself into the river, to conceal himself from the pursuit and taunts of the mob, whose derision he had excited by parading the streets during the Carnival tarred and feathered, by way of masquerading. The result of this frolic, so little becoming his position as canon of the cathedral, was, that he caught a rheumatism in his limbs which rendered him a cripple for life.

Maize begins to grow to the S. of Le Mans, but nowhere to the N. of that place.

#### 7 Fouletourte.

The road descends into the pretty valley of the Loir (*N. B.* not to be confounded with the Loire), a little before it reaches

19 La Flèche (*Inn*: La Poste), a town of 6,500 inhab., prettily situated in a country where vineyards begin to be cultivated with advantage. The large edifice, now the Ecole Militaire, was built by Henri IV. as a Jesuits' College, 1603, but turned into its present destination by Napoleon. The heart of Henri is still preserved in the church. The *Church of St. Thomas* is a heavy Romanesque edifice.

20 m. N. W. of La Flèche is Sablé (*Inn*: Croix Verte, comfortable and moderate), "a beautiful little town on the Sarthe, with a Château built by M. de Torcy, foreign minister in the reign of Louis XIV. (1696-1715), and nephew of Colbert, still in the Torcy family. Near Sablé are immense marble quarries. Anthracite coal is worked at La Ragotène." —*L.* About 2 miles beyond Sablé,  $\frac{1}{2}$  an hour's walk by the river side, is the *Abbey of Solesmes*, recently purchased and re-occupied by a society of Benedictine monks, who devote themselves to study in this picturesque retreat. The church is remarkable for 4 groups of statues called *Les Saints de Solesmes*, enclosed in niches, each surrounded by a rich framework of architecture and sculpture, in a style of Gothic approach-

ing to the Renaissance. The groups of statuary represent, 1. The Entombment of our Saviour; the head of Christ, and the figure of the Magdalen, are particularly well executed. Above the recess rises an ogee arch decorated with the richest foliage of thistles and mallows. It bears the date 1496. 2. Christ disputing with the Doctors; the figures, in the dress of the 15th century, are somewhat coarse, reminding one of a Dutch painting. 3. On the l. of the choir, the Communion of the Virgin. 4. Death of the Virgin;—in the N. transept. These sculptures have been variously attributed to Italian artists, and to the Frenchman Germain Pilon, but without authority. An altar in the S. transept has been lately fitted up with fragments of other statuary found among the ruins of the abbey. The stalls in the choir, carved with the genealogy of Christ, are worth notice.

The road to Angers follows the valley of the Loir downwards, running at the foot of gentle hills covered with vineyards.

13 Duretal is a town of 1500 inhab., overlooked by two picturesque embattled towers, part of a *Castle* built by Foulques Nera, Comte d'Anjou.

#### 14 Suette.

The Loir now bends away from the road to the W., and 6 m. below this falls into the Sarthe.

On approaching Angers the road passes near some of the vast quarries of slate which form a principal production of the district.

19 ANGERS.—*Inns*: H. de Londres, on the quai opposite the landing-place of the steamers; Cheval Blanc.

Angers, chef-lieu of the Dépt. Maine et Loire, is situated on the Maine, called Mayenne in the upper part of its course, a little below the junction of the Sarthe with it, and about 5 m. above the influx of the Maine into the Loire. It has 33,000 inhab. Modern improvements, the formation of a broad quay along the l. bank of the river, the substitution of tall, regular, white stone houses,



like those of the Rue Rivoli, for the old gable-faced cottage-built structures, have greatly innovated upon the thoroughly antique character which Angers previously bore. A broad formal boulevard, planted with young trees, replaces the old fortifications,—

“The flinty ribs of this contemptuous town ;”  
 . . . . . “those sleeping stones,  
 That as a waist did girdle it about,  
 By this time from their fixed beds of lime  
 Have been dishabited.” *King John.*

The “strong barred gates” are all down, and only one tower remains near the upper bridge of those “saucy walls.” Black Angers, as it was called from the sombre hue of its buildings of slate, is now like an old coat with a modern trimming: but plunge into the midst of its labyrinth of buildings, scale its steep and narrow streets, many of them inaccessible to wheel carriages, and you will find traces enough of the Angers of olden time, the capital of Anjou, and residence of its dukes. In few towns of France will the antiquary, artist, or architect find a greater number of interesting antique churches and houses than here.

Most of the old houses are timber-framed, their fronts gable-faced, the roofs, and often fronts, covered with scales of slate, which abounds in the neighbourhood and forms the common building stone, and many of the door and corner posts, the joists and cornices, bear rich Gothic carvings. The most venerable relic of antiquity is the *old Castle*, at the water side, close to the new suspension bridge. Its walls were originally washed by the waters of the Maine, until its moat was partly filled to give place to the new quay. If its size and preservation be jointly considered, it is perhaps the finest feudal castle in France. Seventeen colossal towers surround it; they are 70 to 80 ft. high, close set along the walls, shaped like dice boxes, thick below, narrow waisted, and having bands of white stone let into the black rough slate of which they are built, so as to

give them the appearance of being hooped. A broad and deep ditch isolates the castle from the rest of the town; it is entered by a massive gateway under a perfect portcullis, and within its portal is the furnace where lead and pitch were melted for the benefit of invaders. This castle was begun by Philippe-Auguste, and completed by Louis IX. It serves at present for a prison, barrack, and dépôt of powder. The part which served as a palace of the dukes of Anjou, overlooking the river, is now in ruins, but shows the architecture of the Renaissance. It stood between the high tower called *Du Moulin*, because it once supported a windmill, and that called *Du Diable*, because close to it was the fearful Oubliette, down which criminals were cast alive. From this tower there is a capital view of the town, its spires and other buildings, of the river and its bridges; while a slight glimpse of the Loire also, deep set in its distant valley, may be gained. There is a neat chapel, now filled with fire-arms, showing, in the delicate tracery of its windows, a good example of Gothic. Beside it is a small building flanked with turrets, in which, it is said, King René of Provence and Anjou was born. The view from the terrace outside the castle-gate is less extensive, but nearly as good as that from within the walls, and on the whole the castle is more imposing from without than interesting within. On one side of the open space surrounding the castle stands a handsome modern building, originally *L'Académie d'Equitation*. Mr. Pitt (afterwards Lord Chatham) and the Duke of Wellington received part of their education at the military college here, now removed to Saumur, which occupied this edifice, still called *L'Académie*. It has been converted since the Revolution into a caserne de cavalerie and dépôt de remonte. No trace or tradition is preserved of either of these great men, of whose education it may be said “*fas est et ab hoste doceri.*”

*The Cathedral* of St. Maurice is everywhere conspicuous from its elevated position and its twin towers, placed so close together as to seem thrown into one. The very delicate spire on one side is injured by the contiguous ugly pavilion, an addition of the Renaissance (1540). The W. portal, a work of the 12th cent., is remarkable for the richness and good preservation of the sculptures surrounding its elegant early-pointed arch; they retain indeed even their colouring. On either side are 4 saints, male and female; above, the curved niches are filled with smaller statues, angels, &c., while the tympanum is occupied by the Saviour, surrounded by the attributes of the 12 Apostles. The workmanship is good, the faces expressive, the draperies elaborate, but the whole displays the stiff style of Byzantine art of the period. Higher up, in a row of niches, are 8 statues of dukes of Anjou, later in date (15th cent.) and inferior in execution. On the l. hand as you enter, passing from below the carved organ-loft, is an antique bénitier of oblong form, in verde antique, supported on lions, a Byzantine work of the Lower Empire; it was brought from the East, and presented to the church by King René. The church consists of a very long nave without aisles, each division of the side wall being a wide pointed arch resting on the ground without pillars, and an upper arch rising from engaged groups of pillars having Romanesque capitals, enclosing a pair of narrow circular-headed windows. The greater part of these windows, as well as those of the nave and choir, are filled with painted glass of the richest colour and very old (13th cent.), forming one of the chief ornaments of the church. This and other churches in the Angevine style are destitute of triforium or clerestory. The choir and transepts are short, the E. end is multangular. In the choir, on the l. as you look towards the apse, is a splendid Flamboyant doorway. Both

transepts (1225) terminate with fine wheel windows, the other windows are pointed, and below these along the wall runs a rich pointed arcade. The nave is about 80 ft. high, and nearly 54 ft. wide, stone vaulted. Local historians lay great stress on its roof being supported without flying buttresses, but their place is supplied by huge clumsy square piers at least 8 ft. by 10 square, and retaining the same thickness up to the roof, raised outside between each pair of windows and at the angles of the transepts, and thus the wonder is removed. Margaret of Anjou was buried in St. Maurice, but her tomb was destroyed at the Revolution.

Not far from the cathedral is the *Musée*, placed in a building erected by an intendant of the province, afterwards converted into the Séminaire, and added to in the time of Louis XIV. Its cloister and winding staircase are curious examples of the latest Gothic style.

It contains a large collection of mediocre paintings, mostly of the modern French school. Among them is placed a *Vase* of antique Egyptian porphyry, obtained by King René from the East, which for a long time passed for one of the water-pots used at the marriage feast at Cana. It bears 2 bearded masks carved on it, and is broken, which is not surprising considering its thinness. Here is a fine bust of Napoleon by *Canova*, in marble, condemned to be broken at the Restoration, but saved by being hid in a garret. One room is filled with casts from the works of the living French sculptor *David*, given by him to his native town. His statues of Guttemberg, inventor of printing, for Strasburg, of General Foy in a Roman dress, of Armand Carrel in loose pantaloons plaited round the waist, of the Greek girl at the tomb of Marco Botzaris; his busts of Göthe, Hahneman the homœopathist, and Jeremy Bentham, appear best worth notice. He has also executed a series of medallion heads



of celebrated persons of the 19th century.

The museum of *Natural History*, situated in the upper story of the building, is reached by a corkscrew stair remarkable for its lightness, and its singular groined roof. The collection is exceedingly well arranged and named. The geology of the department is illustrated in a series of specimens by themselves. Among a few antiquities is the crosier of Robert d'Arbrissal, founder of Fontevrault, found in that Abbey; it bears a semi-pagan representation of St. Michael and the dragon, of gold (?) partly enamelled. The shoes of Joanne de Laval, 2nd wife of King René, high-heeled and ornamented with open work; also an aerolite, which fell in one of the faubourgs of Angers 1822, deserve attention. The *Library* possesses some curious old MSS.

Not far from the musée is the ruined church of *Toussaints*, attached to a convent now converted into a *Dépôt des Subsistances Militaires*. It is an elegant pointed building, and almost identical in style with the early English. It is a cross church without aisles, with lancet windows, richly cut capitals, and corbels, from which springs the roof destroyed at the Revolution. The E. window is a wheel, apparently of later date.

The massive and stately tower of *St. Aubin* in the early pointed style, unfinished and surmounted with a conical roof of slate, is now converted into a shot tower.

A curious discovery was made some years ago at the *Préfecture*, viz. that along the corridor on the l. hand, then concealed by thick plaster, runs a colonnade of florid Norman architecture, of very early date, and of curious and elaborate workmanship. The small round arches rest alternately on piers faced with pilasters, and on detached pillars arranged in 2 rows, each 5 deep. All the pillars, cornices, and mouldings of the arches are most elaborate, sharply cut, very perfect, and no two alike.

The mouldings running round the arches consist of bearded heads, monsters, animals, fish, &c. In the midst is a circular portal, the lower part of which is sunk rather below the surface of the ground, supported on cut columns of varied patterns, and surmounted by a series of Runic bands, cords and foliage, each confined to one stone, and radiating from a common centre. Next to this is a double arch ornamented with fresco paintings instead of sculpture, the subjects being Herod on his Throne, the Massacre of the Innocents, the Temple of Jerusalem, and the Nativity and Adoration of the Magi, who are seen on horseback approaching Bethlehem. The style of drawing bears a near resemblance to the tapestry of Bayeux; the colours are very perfect. These arches formed part of an early church and convent of St. Aubin, of which the préfecture occupies the site.

The old *Eglise de St. Martin*, now converted into a magazine of fagots, and piled up to the roof with them, so as to be scarcely visible, will yet interest the antiquary from its age and style of structure. It is in the early Romanesque style, consists of an inordinately long nave, of a transept—having thick round pillars set in the 4 inner angles of the walls which supported the tower, and of an apsidal E. end. Its windows are round headed and long. It is the oldest church in Angers, and one of the few churches in France whose origin can with probability be referred to the period of the Carlovingian kings. The nave and transept, exclusive of certain repairs, appear to be part of the church founded in the 9th century by Hermengarde, Queen of Louis-le-Débonnaire, who died 819. The choir is later, probably of the 12th century.

At the extremity of the town to the N. is the *Church of St. Serge*, remarkable for a choir supported on 6 columns of peculiar lightness and height, from whose freely cut capitals rises an elegant pointed roof; behind

it is a square Lady Chapel. The style indicates the transition from Romanesque to early pointed. The windows are without tracery, for the most part round headed, enclosed within pointed arches. The transepts seem of a much older date than the choir; the nave is in the late Gothic of the 15th century.

Here is a finely carved spiral staircase of wood; every panel contains a different sculpture and composition.

In the same quarter of the town is the *Jardin des Plantes*, an agreeable walk in hot weather under shady trees, near to the *Séminaire*, a vast edifice.

Among the more interesting specimens of ancient domestic architecture, with which the streets of Angers abound, may be mentioned a corner house, in the Place behind the cathedral, adorned with curious carvings in wood; that called *Hôtel des Marchands* in the Rue Baudrière, and another in the Rue du Figuier known as the *Hôtel des Ducs d'Anjou*, for what reason is not evident, since René, the last Duke of Anjou, died 1480, and this building cannot be older than the 16th century, and is in the style of Francis I.'s time, with more of Italian than of Gothic in the composition of its architecture. The square turrets, or projecting oriels, at its angles are singular.

In the suburb of *Doutre* (beyond, or on the further (or rt.) bank of the Maine) are several buildings deserving notice for their antiquity. The *Eglise de la Trinité* is a Romanesque building probably of the 11th and 12th centuries. It consists of a long nave without aisles, having in the side walls a series of apsidal recesses under pointed arches. The choir, very shallow, and formed of a central and 2 side apses, is separated from the nave by a wall pierced with a pointed arch, which contracts the view of the high altar, but serves as a support to the *Tower*, which is square below, octagonal above, and very elegant.

Close to this church, indeed touching it, is a second equally ancient and in a nearly similar style, *l'Eglise de Ronceray*, once attached to an extensive nunnery; now converted into the *Ecole des Arts et Métiers*. The church serves as a chapel for the students; it is very plain and considerably modernized.

On the same side of the river, a little higher up, is the *Hospice St. Jean*, founded by Henry II. King of England, and duke of Anjou, 1153. The great hall, said to be of that date, is a fine apartment, lofty and airy, its groined and pointed roof supported on 2 rows of light pillars. Here the beds of the patients are ranged in rows, the males separated from the females by a low partition. The office of nurses is performed by nuns; the whole is kept very orderly, the linen-closet particularly neat. The cloisters between the great hall and the church are partly in the Romanesque style; double pillars support the arches; a round portal with deep mouldings leads into the *Chapel*.

A decayed Barn near the hospital is still older than it. It is Norman, with 3 aisles, like old Westminster Hall, and deserves to be drawn.—*F. P.*

At the opposite extremity of the Suburb *Doutre*, below the suspension bridge, near the Nantes road, is the vast Nunnery du Bon Pasteur, surrounded by high walls. The sisters keep a school for females.

Very extensive *Boulevards*, planted with trees and lined with some very handsome houses, the Mairie, &c., occupy the site of the old walls, and communicate with a wide open space for the exercise of troops, called *Champ de Mars*, traversed by the road to Saumur. Some of the houses about it bore until lately the marks of bullets fired in the attack of Angers by the Vendéan army, 90,000 strong, 1793.

The forces of King John laid waste Brittany in 1199, and to that period we must refer the scene in Shakespeare "Before the walls of Angiers,"



where the citizens are summoned by both the rival kings,—“Ye men of Angièrs, open wide your gates.”

Angers occupies a fortunate position near the mouth of 3 navigable rivers, in a country producing lime, coal, and slate.

Angers is famed for its *nursery* gardens; there are not less than 30.

The neighbourhood abounds in *Slate Quarries*, which employ between 2000 and 3000 men, and supply a large part of France. They furnish 80 millions of slates yearly, which are exported, to the value of 1½ million of francs per annum.

The most considerable, *Le Grand Carreau*, is about 4 m. off, a little to the l. of the road to Saumur. It is nearly 400 ft. (105 mètres) deep, and occupies an area of 4000 mètres. Besides the yawning open excavation, a considerable cavern, approached by a horizontal gallery on one side of the quarry, has been driven under ground. It is approached by vertical ladders, and frail extracting machinery overhangs the precipice. At times serious slips, or *éboulements*, produce very dangerous avalanches of rock.

There are 2 *steamers* daily to Nantes, and 1 to Tours, making the circuit of the tongue of land which separates the Mayenne from the Loire. (See R. 58.)

*Diligences* daily to Paris by Le Mans (R. 46); to Paris by Tours; to Nantes; to Chartres; to Saumur.

The direct distance from Angers to the Loire at Pont de Cé is about 5 m., and 5 m. beyond the river is the interesting *Château de Brissac*.

The road to Nantes quits Angers by the Suburb Doutre, and leaving the Mayenne on the l. hand, reaches the Loire at

17 St. George-sur-Loire.

8 Champtocé.

13 Varades.

13 Ancenis.

9 Oudon.

15 La Seilleraye.

} described in  
Route 58.

14 NANTES.—*Inns*: H. de France, in the Place Graslin, close to the theatre, ~~best, but~~ has only male attendants; H. des Colonies, ~~H. des Voyageurs~~, Rue Molière; H. du Commerce, *united, very good, full of comfort*.

Nantes, the ancient residence of the dukes of Brittany, when that province was independent—which disputed with Rennes the title of capital of the duchy, now chef-lieu of the Dépt. de la Loire Inférieure, is situated on the l. bank of the Loire, at the influx into it from the N. of the Erdre; the junction of the two rivers being in the middle of the town. The Sèvre (Nantaise) from the S. flows into the Loire a little below Nantes. There are at least 16 bridges in the town over these various streams. It is distant about 40 m. from the ocean, and is a flourishing seaport, the fourth in rank and population in France, numbering 77,992 inhab. Though less prosperous since the loss of St. Domingo to France, and of late outstripped by Havre as a port, it has remained nearly stationary in population and commercial prosperity for the last 50 years: it is still the seat of much respectable opulence and active industry. As a town it is one of the handsomest and most pleasing in France. Its fine *Quais*, extending about 2 m. along the Loire, and on both sides of the Erdre, and the wide open space left by these two rivers, enlivened with small craft, remind the traveller somewhat of the busy aquatic towns of Holland, Amsterdam and Rotterdam, and give a very cheerful character to Nantes, which is, besides, far less dirty than most French towns. In the new quarters it has streets lined with houses not unworthy of Paris. The Place Royale and Rue d'Orléans contain the chief shops, while the old quarters, belonging to the capital of the ancient duchy, abound in picturesque houses, gable-faced and overhanging the narrow streets. Those who admire and

would seek out picturesque bits of street architecture, now fast disappearing even from the old town under modern improvements, must penetrate the Rues de la Poissonnerie, where the house “aux Enfants Nantais,” so called from the carved figures of the martyrs St. Donatien and St. Rogatien, at the corner of the Place du Change, deserves particular notice: it dates from the 15th century. There are other old houses in the Rues du Calvaire and de la Juiverie. In the Rue de la Boucherie is a house said to have been inhabited by Anne of Brittany.

The most prominent and remarkable edifice is the *Cathedral of St. Pierre*, externally an unsightly pile, from the unfinished towers not rising much higher than the roof. The three lofty portals of its W. front, however, are striking for size and the great number of small bas-reliefs and other sculptures adorning them. It was begun 1434, and finished about the end of the century. The *nave*, of the same age, “a remarkably fine structure, of admirable proportions and great effect, in pure Flamboyant style,” is very imposing on account of the great elevation of its roof, 120 ft. above the pavement, and the elegance of its arches; but its windows are destitute of tracery. The *modern* wood carving in some of the side chapels, and the stone work of the organ-loft decorated with pendants, a delicate work of the 16th century, deserve notice. Attached to this noble nave is a plain Romanesque choir, inferior in height and plain in style, probably of the 11th cent.: it was already enclosed in new walls, corresponding with the nave, preparatory to pulling down the old structure, when the works were stopped for want of funds near the latter end of the 15th century. The solitary transept on the S. side, which had been alone completed, is now partitioned off, and serves to contain the splendid *Monument* (removed from the suppressed Carmelite convent) of

Francis II., last duc de Bretagne, and his wife, Marguerite de Foix, raised to their memory by his daughter, Anne of Brittany. It is a splendid work of art in the style of the Renaissance, executed by a Bas Breton artist, Michel Colomb, a native of St. Pol de Léon, who preceded Jean Goujon. It was fortunately secreted at the Revolution, and thus preserved from destruction. It is a large altar tomb of marble, black, white, and red, raised to a height of 5 ft. Upon it repose the recumbent figures of Francis and his wife; three angels support their heads, and their feet rest on a lion and greyhound. In the four corners stand statues as large as life in white marble: of Justice, with sword and scales, said to be a portrait of the Duchess Anne; of Power, strangling a dragon (heresy), which she draws out of a tower; she is attired with helmet and breastplate, and has a scarf wound round her arm: Wisdom bears a mirror and a compass; and Prudence, double-faced, holds a lantern in one hand and a bit in the other, as attributes. These statues are well designed, and executed with great delicacy, which is particularly conspicuous in the draperies. Along the sides of the tomb small statues of the 12 Apostles are ranged in niches, and below them are figures of mourners in coloured marble. The patron saints of the Duke and Duchess, St. Francis d'Assisi and St. Margaret, stand at their head, St. Louis and Charlemagne at their feet. The remains of the illustrious dead, for whom this splendid tomb was raised, having been torn up and scattered in 1793, the body of the Constable de Richemont, one of the generals who contributed to drive the English out of France in the reign of Charles VII., was deposited within it in 1815. The N. transept and the choir of this church are in progress of completion, to correspond with the nave, and it is proposed to pull down the old choir.



Beyond the cathedral, a broad and much frequented promenade, occupying the site of the old fortifications, and forming a sort of boulevard, extends from the Loire to the Erdre, under the names *Cours St. Pierre* and *Cours St. André*. The former is approached by a broad and stately flight of steps from the Loire, and is ornamented with statues of the Duchess Anne and the three Breton heroes, — the constables Du Guesclin, Clisson, and De Richemont. Between the two walks stands a *Column* raised to the memory of Louis XVI., and surmounted by his statue; but since 1830 made to commemorate a combat between some young men of the town with the troops of the line, in which 10 of the former were killed, during the July Revolution. The brass plate which records this, states that “*Des ouvriers Anglais ont fait graver cette inscription.*” ’Tis a pity English workmen cannot mind their own business, without meddling with the politics of a foreign country.

The *Castle* (*château*), a massive and venerable edifice of the 14th cent., partly modernized in the 16th by the Duc de Mercœur during the wars of the League, flanked with bastions, still bearing on them the cross of Lorraine, stands at the extremity of the *Cours St. Pierre*, on the margin of the Loire, surrounded on the land side by a deep fosse. Its massive round towers are built of slate and granite: a portcullis still defends its entrance, and the interior contains several constructions of the 16th century, in the latest Gothic: the windows surmounted with canopies. In one is a curious spiral staircase. Most of the kings of France, from Charles VIII. downwards, resided for a time within its walls. The powder magazine is said to have been the *Chapel* in which Anne of Brittany was married to Louis XII. (?), thus becoming for the second time queen of France. She certainly was born here, and made the castle her residence. In this castle Henri VI. signed the *Edit*

*de Nantes* for the protection of the Protestants in 1598, revoked, to the injury and stain of France, by Louis XIV.

In 1654 it was the prison of the Cardinal de Retz, who escaped by letting himself down by a rope from the bastion de Mercœur into a boat moored in the Loire, which at that time, and until the present quai was formed, washed the castle walls. The attention of the sentinel meanwhile was taken off by a bottle of wine given him to drink, and his eye was deceived by the cardinal’s red cloak and hat slipped off and hung over the battlements. De Retz reaching the shore by means of the boat, instantly mounted a horse provided for him by his friends, which, however, quickly threw him and dislocated his shoulder. In spite of this accident and the pain it caused, he rode to a place of safety, the *Château de Beaupreau*, whence he effected his escape through Spain to Rome. Madame de Sévigné describes her visit to the castle in 1648, shortly after, and the Duchess de Berri was shut up in it previous to her removal to Blaye. That adventurous Princess, after having long encouraged disaffection and fermentation in Brittany and La Vendée, was finally detected, after a concealment of 5 months within the city, which had eluded the vigilance of the police, Nov. 1832, in the *house No. 3, Rue Haute du Château*, facing the castle, which belonged to two ladies, named Du Guigny, zealous partisans of the Bourbon cause. Her presence in this house had been betrayed to the government by a Jew, named Deutz, previously a confidant of the duchess and her friends, and a party of soldiers and police were dispatched thither instantly. They searched the whole building from top to bottom, but found her not. Confiding, however, in their information, a party of gendarmes was left behind, to keep watch. Some of them, posted in a garret, remained a whole day beside a fire which they had lighted, when

on a sudden they were startled by voices and the sound of kicks, proceeding from an iron door which formed the back of the chimney, and, to the surprise of the soldiers, out scrambled four persons—the duchess, a lady, and MM. de Menars and Guibourg, who had passed 16 hours in a secret hole or hiding place, entered by a door 20 inches wide, and too low for a man to stand upright in. Not only this oppressive confinement, but even the heat of the fire were endured patiently, and without the slightest noise, until they were nearly suffocated, and the duchess's dress, entirely scorched by the iron door being heated red hot, was on the point of catching fire.

Nantes possesses a *Museum of Paintings*, rather above the average of provincial collections, though a large portion are copies; situated in the upper part of the Cloth Hall, Rue de l'Arche-Sèche. The greater part were collected by one M. Cacault, of this town. Among the curiosities may be specified a head of a Crusader painted by *Canova*;—an old church painting of a Holy Family, on two shutters; a head of Christ, brought from the cathedral; portrait of Queen Elizabeth (? artist unknown); portraits of the children of Henri II., by *Janet*; a Bull, by *Brascassat*, a modern artist, good. Here is a copy of Napoleon's bust by *Canova*.

Travellers who have leisure to devote any time to a *Library*, will find that of Nantes, above the Halle aux Grains, Quai Brancas, an especially rich collection of 30,000 volumes. A MS. copy of the *Cité de Dieu* of St. Augustin, of the year 1375, is remarkable for its beautiful miniatures.

The *Archives*, deposited in the Préfecture, contain a mass of curious documents relating to the history of Brittany; many ancient charters of Abbeys, &c., and the trial of that most infamous of criminals, Gilles de Retz, Maréchal de France, who was burnt on the Chaussée de la Made-

leine (R. 58). It is in Latin, and will not bear translation.

In the *Musée d'Histoire Naturelle*, Rue du Port Communeau, may be seen a collection illustrating the geology of the department, formed by the late M. Dubuisson; besides several fragments of antiquity found in the neighbourhood, and a mummy, presented by the Egyptian traveller Caillaud, who is a native of Nantes.

A handsome Arcade called *Passage Pommeraye* leads by a flight of iron steps from the Rue Crebillon to the Rue de la Fosse.

The *Quais*, lined on the one side by handsome houses, and on the other fringed with shipping, present a lively scene, and form an agreeable walk about 2 m. long\* (at least in the lower part, where they are gravelled). An Englishman, in traversing them, may remember with some interest that it was at this port that the young Pretender embarked on the expedition of 1745, in a fast-sailing brig, the *Doutelle*, provided by one Walsh, a French subject settled at Nantes, who accompanied him. He was disguised as a student of the Scotch college at Paris, and for better concealment had allowed his beard to grow. On the quais are situated the Halle aux Grains and the *Bourse*, which is not remarkable for excellence of architecture. The Quai de la Fosse is lined by a fine row of trees, reminding one a little of the Boompjes of Rotterdam. Near its lower end, where the ship builders' yards commence, in which the steamers for the Loire are constructed, is a building, insignificant in itself, but remarkable for its associations, and they are melancholy, called *Salorges*, built as an entrepôt for colonial merchandise, and still serving as a warehouse. Who has not heard of the *Noyades* and republican mariages; the invention of Carrier, the most detestable, perhaps, of the monsters of the revolution, when sated with single murders by the guillotine, and thirsting for more blood, and the excitement of executions on a large



scale? It was in front of the Salorges that they took place, and that building served as a temporary place of confinement for the miserable victims, who were dragged hence and put on board barges (gabarres) furnished with a sliding valve (soupape) or trap-door in their bottom. These boats, when towed into the middle of the river, and deserted by the crews, were sunk with their load of 20 or 30 human beings, by pulling from the shore a cord attached to the valve. To prevent the possibility of escape for the strong swimmer, or poor wretch who might be cast ashore alive by the current, armed men of the bloody band called *Compagnie de Marat*, composed of the most abandoned wretches whom the lowest dens in Nantes could pour forth, were stationed on the banks to fire on those who rose to the surface, while others, armed with swords, cut off the hands and fingers of such as struggled to reach the boats. As many as 600 human beings perished on one day; the total number of persons thus destroyed has never been correctly ascertained, but 25 of these Noyades or executions by water are known to have taken place, and the number who perished has been variously estimated at 6000 or 9000! At first the wholesale butchery was perpetrated at night, but, emboldened by impunity, and supported by a portion of the citizens, almost exclusively of the class of little tradesmen, the tyrants did not hesitate to immolate their victims in broad day. The most atrocious feature in these massacres is the number of women and of young children, who were thus consigned to eternity, without the possibility of having committed any offence, by the exulting savages who then ruled the people's destinies. When a remonstrance was made against the murder of the children, "*Ce sont des louvetaux, il faut les détruire,—Ce sont des vipères, il faut les étouffer,*" were Carrier's answers. The experiment of the Noyades was

*France.*

first tried on 24 priests condemned to transportation (*déportation*). "*Le decret de déportation a été exécuté verticalement,*" was Carrier's boast. The marriages *Républicains*, as another refinement of cruelty was called in mockery, consisted in binding together a man and woman, back to back, stripped naked, keeping them exposed for an hour, and then hurling them into the current of "*la baignoire nationale,*" as the bloodhounds termed the Loire. That river, as it were indignant at crimes scarcely paralleled in the history of the world, threw back upon its banks, at each returning tide, the corpses with which it was choked, until the air became pestilential, and its very water and fish poisonous. When Carrier was at length called to account for his crimes, which, however, had been connived at, if not approved, by the Convention a short while before, and asked for proofs of the accusations against him, he was answered, "*Vous me demandez des preuves? faites donc refluer la Loire.*" But these are only a part of the revolutionary atrocities committed at Nantes: to the victims of the Noyades must be added those who perished by the guillotine, by disease, famine, and terror in the prisons, and, above all, by the fusillades, which took place day after day on the *Plaine de Sainte Mauve*, where, at one time, 500 children, the eldest not more than 14, were mowed down by musketry, and where deep ditches, dug for the purpose, were filled with corpses heaped confusedly one over the other. The population of Nantes, which amounted in 1790 to 81,000, was reduced to 75,000 in 1800, and the number who were slaughtered in 1793 belonging to the town and surrounding country is estimated at 30,000. It is painful to describe these horrors, but they form an integral part of the history of Nantes, and that which is here detailed is only a sample; they might be greatly expanded.

The Vendéan war has also left

some sad souvenirs at Nantes. In the attack of the town by the Vendéan forces on the 29th June, 1793, their leader, the gentle Cathelineau (the carter), was mortally wounded in penetrating into the *Place Viarme*, now the cattle market, and his fall was the cause of their retreat. Not far from this spot another of their generals, Charette, was shot, at the corner of the *Rue de la Miséricorde*, April 1796.

Fouché, the police minister, Duc d'Otrante, and Marshal of France, regicide and minister of Louis XVIII. in 1814, was born at Nantes.

The *new Quarter* of the town, the West End of Nantes, was commenced 1784, by M. Graslin, ancien fermier-général, after whom the Place containing the theatre is called. He seems to have exhausted the *Biographie Universelle* for names to the adjoining streets; among them appear the *Rue Jean Jacques*, *Rue Racine*, *Rue Franklin*, *Rue Crébillon*, &c. The houses are built of white stone from the neighbourhood of Saumur.

The commerce of Nantes, though no longer what it was, is still of great value; in 1836 it was carried on by 458 vessels, but more than  $\frac{1}{2}$  of them were of less than 100 tons. Owing to the want of water in the Loire abreast of the town, vessels of more than 200 tons burthen are obliged to unload at Paimbœuf (p. 171), 24 m. lower down, near its mouth.

A *Canal* is in progress to connect Nantes with Brest by the Erdre; it will be about 230 m. long when finished.

The importations consist of sugar, coffee, cotton, and other colonial produce.

Nantes is gradually changing from a commercial to a manufacturing town. The most considerable manufacture is that of cotton yarn; in 1837 there were 16 mills in the vicinity of the town.

There is a singular manufacture here of preserved dinners ready cooked (*Conserves Alimentaires*),

prepared by the firm Colin et Comp<sup>ie</sup>, *Rue de Salorges*, No. 9, which sends forth, hermetically sealed, all kinds of provisions, so as to be capable of perfect preservation in all climates, and for any length of time. 150,000 boxes of young peas and 800,000 boxes of sardines (pilchards) are embalmed in one season, and 8 oxen can be cooked at once in a single boiler. Roasting is carried on by heated air, and boiling by steam, in a kitchen roofed with glass, after the manner of the *Passage d'Orléans* in the *Palais Royal*. The proprietor of the establishment employs in the autumn 800 persons in curing and packing sardines alone, and monopolizes all the green peas which come to market in early spring to supply his wants.

The suburb of Nantes on the S. side of the Loire is spread over a series of islands, formed by the branches of that river and the Sèvre, connected together by no less than 6 bridges in one line, over all of which the roads to Bordeaux and Clisson pass.

The *Protestant Church* is in the *Rue des Carmélites*, in the chapel of the former convent.

The *Poste aux Lettres* is in the *Rue Boileau*.

Prosper Sebire, bookseller, *Place du Pilon*, No. 5, has a number of views, plans, guides, &c. relating to Nantes, as well as maps.

*Fiacres* are found for hire in the principal squares.

*Omnibuses* (said to be a Nantais invention, transferred from this to Paris) run along the *Ligne des Ponts* from the *Place du Commerce* to the *Pont de Permil*, and along the quays from the *Bourse* to the *Chantiers de Construction*.

*Malleposte* daily to Paris in 25 hours. (R. 46.)

*Diligences* daily to Paris by Le Mans in 44 hours—3; by Angers and Tours, 54 hours (R. 58); to Brest, 2—Rennes, 3—Bordeaux, 4—Poitiers to Bourbon Vendée, 2.

*Railway*—to Tours in progress.



*Steamers.* — Inexplosibles daily ascend the Loire, reaching Angers on the 1st evening, Tours on the 2nd, starting from the Quai du Port Mailard.—The steamers of another company called Riverains, daily to Angers; down the Loire to Paimbœuf daily; and to St. Nazaire when the high tides permit; to Bordeaux, 3 times a month; to Lorient and Quimper once a week.

*Steamer* on the Erdre to Nort starts from the Quai Céneray, behind the Préfecture. (R. 41.)

*Environs of Nantes.*—The immediate vicinity of the town displays great marks of opulence and prosperity, in its numerous and neat white villas, many of them quite in the English style, and in the great number of factory chimneys, many of them new.

The excursion most commonly recommended to a stranger is that to *Clisson*, the Richmond of Nantes, 18 m. S. of the town, on the borders of La Vendée, described in Route 60. It is a pretty spot, though its beauties have been considerably exaggerated by local enthusiasts. You may go thither by the omnibus in the morning, visit the castle and all its curiosities, and return by the same conveyance at 7 p. m. But as this may leave the traveller a prey to ennui for several hours after exhausting the sights of Clisson, it is even possible to hire a cabriolet, and see Tiffauges, returning to Clisson in time for the omnibus.

*The Loire below Nantes*

Is navigated by steam vessels, but

with caution, on account of the numerous sand-banks.

L. a little below Nantes the Sèvre Nantaise enters the Loire.

On the island of *Indret*, 7 m. below Nantes, the French government have an establishment for the construction of steam-engines. More than 800 workmen are employed here. The steam-engines turned out here are very bad, far inferior to those made by private establishments. Indret is well situated at the mouth of the Loire, so as to have a speedy communication, safe from cruisers in time of war, with the great dockyards of Brest, Lorient, and Rochefort.

The estuary of the Loire is 3 m. broad abreast of

L. Paimbœuf (30 m. below Nantes). This place may be regarded as the out-port of Nantes, since large vessels above 200 tons burthen stop here and discharge their cargoes into lighters (gabarrs). The loss of St. Domingo, and the long-continued wars under Napoleon, reduced the population of this town from 9000 to 4000, which it does not exceed at present.

2 *Steamers* ply daily to Nantes in 4 hours. *Coaches* go hence to the watering place of *Pornic*, 12 m. S. of Paimbœuf, situated on the shore of the bay of Bourgneuf, opposite the island of Noirmoutiers, the last retreat of the Vendéan bands. Comfortable accommodation is to be had in the Etablissement des Bains. The town was burnt in the Vendéan war. An old castle overlooks its little fishing port.

## SECTION III.


ORLÉANOIS.—TOURAINÉ.—RIVER LOIRE.—LA VENDÉE.—  
POITOU.—SAINTONGE.

ROUTE	PAGE	ROUTE	PAGE
48 Paris to Orleans . . .	174	57 Tours to Saumur, by <i>Chinon</i> and Fontevrault . . .	201
49 Paris to <i>Orleans</i> (RAILWAY) .	175	58 THE LOIRE (c).—Tours to Nantes by <i>Saumur</i> and Angers (RAILWAY?) .	203
50 Rouen to Orleans by Char- tres . . . . .	182	60 Nantes to Poitiers, by <i>Clisson</i>	213
51 Paris to <i>Sceaux</i> —RAILWAY .	182	62 Nantes to Bordeaux, by <i>Bour- bon Vendée, Rochelle, Roche- fort, and Saintes</i> . . .	217
52 THE LOIRE (A).— <i>Gien</i> to Orleans . . . . .	183	64 Tours to Bordeaux, by <i>Poi- tiers and Angoulême</i> . . .	223
53 THE LOIRE (B).—Orleans to <i>Tours</i> , by <i>Blois</i> and <i>Amboise</i> . —RAILWAY. Châteaux of <i>Chambord</i> and <i>Chénonceaux</i>	184	65 Poitiers to Châteauroux, by <i>St. Savin. — Excursion to Montmorillon</i> . . . . .	232
54 Chartres to Tours, by <i>Ven- dôme</i> . . . . .	199	66 Poitiers to Rochefort by <i>Niort</i>	233
56 Tours to <i>Loches</i> and Châ- teauroux . . . . .	199		

## INTRODUCTORY SKETCH OF THE COUNTRY.

ARRIVED on the borders of the Loire, which divides France nearly in the centre, the traveller already finds himself amidst sunny landscapes, under the influence of the more genial climate of the south. The provinces bordering on that great river, Touraine, Orléanois, Anjou, Poitou, have been styled "the garden of France;" and the golden vineyards, the blooming orchards, the yellow corn-fields (especially those of La Beauce, the granary of France), and the acacia hedges, bear testimony to the facile bounty of Nature. But little pains have been taken to improve her gifts; an ornamental garden or pleasure ground is rarely seen: the earth seems to bring forth abundantly with less than the average amount of pains-taking: "c'est le pays de rire et de ne rien faire." The Loire, which forms its chief feature, is decidedly inferior in beauty to the Seine. In Touraine its banks are flat and monotonous, and it is only after passing Tours that it becomes really picturesque. Near Saumur it is a romantic stream; and from thence, with slight interruptions, nearly all the way to Nantes, the "considerable boldness of its banks, the richness of the culture, the wooded islands, and the animation derived from the swelling canvass of active commerce, conspire to render it eminently beautiful; but for the rest of its immense course it exhibits a stream of sand, and rolls shingles through the valley instead of water."—*A. Young*. "Quel torrent révolutionnaire que cette Loire!" was the expression of Barrère the democrat: and the unbridled impetuosity of its course, its sudden inundations and changes of bed, justify the epithet, and are as detrimental to the utility as to the beauty of this main artery of France. The inundation of the Loire in October (18th and 19th), 1846, was the most extensive and disastrous of that river on record. It burst through the Levée or dyke in several places above and below Orleans, spreading over the plain round





THE RIVER LOIRE

FROM ORLEANS TO THE SEA  
English Miles

French Leagues





Orleans to an extent of 39 kilomètres; while in the streets of Orleans the water rose 5 mètres. 100 barges, with bargemen, were sent from Paris to assist the inhabitants of the city and neighbourhood, isolated by the flood. In winter the Loire rages, and swells, and has too much water, just as in summer it has too little. Its broad shoals greatly disfigure the landscape; its shallows and sandbanks render the passage of steamers intricate. Navigation is limited to very small vessels, and is frequently arrested in the dry months. The cave dwellings excavated in the cliffs of soft chalk (*craie tufeau*) along the river banks, and the long *Levéé* or dyke raised to protect the right bank between Blois and Angers, a distance of 96 m., from inundations, will be remarked as peculiar features in the borders of the Loire. The descent of the Loire from Orleans to Nantes is productive of much interest, partly derived from its venerable cities, gloomy castles, and the great events in French history which have passed upon its banks.

These provinces of France, especially Touraine, were the chosen residence of her kings (Les Valois) down to Louis XIV., and they afford a hundred sites preferable to the sands and morasses of Versailles. The vast and castellated Chambord, bristling with turrets and pinnacles, studded with Diana's crescent, where the Emp. Charles V. was entertained by his good-natured enemy Francis I.; the gloomy Blois, haunt of bigotry and scene of the deep-plotted assassination of the Guises; Amboise, the favourite abode of the warrior Charles VIII., and also witness to conspiracy and wholesale massacre; Chénonceaux, the retreat of Diana of Poitiers; Plessis, the den of the timorous bigot Louis IX.; Chinon, where passed the careless revelry of the indolent Charles VII., and the opening scene of the wondrous career of "the shepherd girl of Domrémy;" Fontevault, the last resting-place of the lion-hearted Richard; Loches, with its dungeon of sighs and tears, a provincial Bastille, contrasting with more agreeable recollections of the beauteous and gentle Agnes Sorel; Dampierre, where Margaret of Anjou's life and sorrows ceased; and Nantes, which saw Henry IV. put his hand to the edict of toleration, and in later times witnessed the heroism and frailty of a daughter of Bourbon, his descendant:—all these are national monuments—integral portions, as it were, of French history. It is a region of interesting associations and recollections: here Joan of Arc first unfurled her victorious banner; here the chief events of the contests of religion in the sixteenth century occurred; this soil is watered with the blood of Guise and Condé; the fields of La Vendée are fattened with the unburied bones of the thousands who fell in the cause of loyalty, and in opposition to revolution and irreligion.

All the places above named or alluded to well deserve to be visited by the traveller. Orleans, though retaining few traces or relics of the Maid; Blois and Amboise; Tours, a fine city, though seated on a flat, amidst dust and glare; Saumur, once the stronghold of Protestantism; Loches, for its architectural remains and historical souvenirs, and pleasing situation in the charming valley of the Indre; black Angers, cradle of our early Plantagenet monarchs—all abound in specimens of ancient architecture, all possess more or less claims to attention. Chénonceaux is a charming specimen of the old French *château*, with turrets and extinguisher towers; without, all crinkum crankum, and within, lined with tapestry and armour; preserved unimpaired, and well kept up. Aizy-le-Rideau is nearly as perfect and beautiful, but with less interesting associations.

S. of Nantes, between the Loire, the sea, and the Sèvre Niortaise, lies La Vendée, celebrated in the history of the wars of the Revolution for its adhesion to royalty and opposition to innovation. The framework or founda-

tion of that country is composed of the elevated plateau of the Gatine, whose crest is in no wise distinguishable, and which presents a series of hills, furrowed by narrow glens or valleys, through which run a few muddy streams. "It is an inextricable complication of heaths, brooks, heights, hollows, and little plains having no connection with one another, and apparently no general water-shed. It is covered with trees, yet has no forests; every field, every dwelling is surrounded by quick hedges, abounding with close-set trees, and surrounded by ditches, forming complete natural redoubts. The lines of communication from place to place are hollow ways, cut so deep below the surface of the ground that a man's head in walking along them will not appear above it, and their vertical sides are surmounted by hedges. They are narrow, shady, and muddy or rutty according to the season, and intersect one another so as to form a multitude of crossways, looking all like one another. There are few high roads; no large towns; the villages are scattered and thinly inhabited; estates very much subdivided; houses concealed by trees and bushes, and a peasantry of primitive and rude manners: these are the combination of circumstances which have made this district a complete labyrinth, perfectly adapted as the theatre of the civil war which so long and so fearfully desolated it. It is divided into three parts: the *Marais*, comprising the sands, salt marshes, and ponds bordering the sea-shore, intersected by dykes and canals, abounding in pastures, destitute of drinking water; the *Bocage*, covered with thickets and heaths, rough and bristling, much cut up and well cultivated; and the *Plaine*, very rich and highly cultivated, abounding with corn and vines."

The traveller disposed to visit the theatre of the Vendéan war may do so from Nantes by way of Clisson; but the character of the country and its inhabitants is fast changing under the system pursued by Napoleon and Louis-Philippe; and intersected, as it has been by them, with a network of high roads, it has lost much of its primitive character.

The *Railway to Orleans and Tours* brings this interesting country in a manner to the gates of Paris, and opens the readiest line of communication between Paris, Lyons, Tours, Bordeaux, and the South of France.

## ROUTE 48.

### PARIS TO ORLEANS.

119 kilom. = 74 Eng. m.

The highroad is now superseded by the Railroad. Mallepostes and diligences are transferred to it. See R. 49.

The high road to Orleans quits Paris by the Barrière d'Enfer; it passes through Bourg-la-Reine, where Condorcet, proscribed by the Convention, put an end to himself by poison, 1794. It leaves about 1 m. to the rt. the town of *Sceaux*. (R. 51.)

12 Berny. Chatenay, about a mile to the rt. of Berny, was the birth-place of Voltaire, 1694. He was

born in a house which belonged to the Comtesse de Bóignes.

8 Longjumeau, a small town on the Yvette.

Beyond this the road skirts the hill of Montlhéry (p. 176).

12 Arpajon. The Marolles station of the railway is about 1 m. to the l. of this town (p. 176).

12 Etrécy, a walled town.

Morigny, on the l. of the road, beyond the river Juine, has a fine church.

8 *Etampes*, a station on the railway. (R. 40, p. 176.)

Beyond this the road enters the monotonous plain of La Beauce, famed for growing corn.



9 Montdésir.

At Méreville, on the l., about midway in this stage, is the Château of Comte de Laborde.

10 Angerville.

14 Toury.

14 Artenay. Here the road from Chartres falls in. (R. 50, p. 177.)

6 Chevilly.

We here enter the *Forest of Orleans*; Cercolles is a small hamlet in the heart of it, inhabited by woodcutters. The suburb Bannier, more than  $1\frac{1}{2}$  m. long, precedes the town of

14 ORLEANS (in Route 49).

### ROUTE 49.

RAILWAY.—PARIS TO ORLEANS, AND  
BRANCH TO CORBEIL.

121 kilom.=75 Eng. miles.

Trains go to Corbeil (30 kilom.=19 Eng. miles) in 1 hour, or 55 minutes, 8 times a day, on week days; every hour on Sundays and fête days.

The Trains to Corbeil stop at intermediate stations, which are distinguished by the letter C.

*Trains to Orleans* 7 times a day, in 3 and 4 hours. *Fares*: 12 fr. 60 c., 9 fr. 50 c., and 3rd class uncovered 6 fr. 35 c.; a place in the coupé 15 fr. Carriages 62 to 82 fr.

The railway was completed to Orleans in 1843.

*Terminus* in the Boulevard de l'Hôpital, close to the Jardin des Plantes. The line at first skirting the walls of the Hospital of the Salpêtrière, is carried through a pretty country, at the foot of the slopes which border the l. bank of the Seine. It approaches the river closely at each curve which the Seine makes, and commands pleasant views of it. There are many pretty villas and country-houses on the river banks, and villages are numerous.

It skirts the walls of Ivry, and of Vitry, famed for its nursery-gardens, on the rt.

10 Choisy stat. is close to a viaduct

of 8 arches, which also support the towing-path along the Seine; 4 of the arches are left open to allow a passage between the Seine and the town. Choisy is a very thriving manufacturing town, whose population has increased within a few years to more than 3,000. It was called Choisy-le-Roi, because Louis XV. made it one of his residences; the *Château* which he built for himself and Madame de Pompadour is demolished, except a fragment, now turned into a china manufactory. There are also manufactories of morocco leather (the largest in France), of glass and of beetroot sugar, and a chemical work. Close to the station the Seine is crossed by a bridge of 5 arches, built 1802. The château and village of Orly are seen on the height to the rt. The railway skirts the parc of

Villeneuve-le-Roi. A new bridge over the Seine gives access to it. We approach the vine-clad slopes bounding the valley of the Seine.

6 Ablon (C. stat.). Ablon is composed almost entirely of neat villas. One of the 3 Protestant churches which the reformers of Paris were allowed by the Edict of Nantes to possess, stood here.

2 Athis Mont (C. stat.).

9 Juvisy (stat.), situated at the foot of a hill on the rt., is remarkable for its antiquity. Its bridge over the Orge anciently formed the boundary between the kingdoms of Paris and of Orleans. Isabella of Bavaria was arrested here as she was carrying off the Dauphin.

[At Juvisy the *Branch Railway to Corbeil* separates from the main line to Orleans, turning off to the l., but continuing along the margin of the Seine, and running near the high road to Lyons (R. 105). It passes through Châtillon, a little port on the Seine. At Viry is the fine garden of the Duchesse de Raguse.

3 Ris (C. stat.), close to Laborde.

Here is a suspension bridge built

over the Seine by the late M. Aguado, the Spanish banker.

The railway cuts through a part of the park of Petit Bourg, broken up and parcelled out by its owner, the late M. Aguado. The *Château*, when it belonged to the Duc d'Antin, was often the residence of Madame de Montespan, who was visited here by Louis XIV.

4 Evry (C. stat.).

3 Corbeil (C. stat.) is a considerable manufacturing town of 3900 inhab., on the Seine, here crossed by a bridge, at the influx of the Essonne. Here are very extensive *Flour Mills* and a corn warehouse (*Magasin*), belonging to Government, for the supply of Paris. The *Ch. of St. Spire* (*Exupère*), rebuilt 1437, after a fire, contains the tomb of Jaques de Bourgoin, founder of the college of Corbeil, 1661, and the casket or reliquaire containing relics of St. Leu and St. Rembert. The little church of *St. Jean en l'Île* was built by the Templars, in the 13th century.

Omnibuses from Corbeil to Fontainebleau. (Rte. 105.) A continued street connects Corbeil with the village of Essonne.

At Juvisy (19 kilom. from Paris) the *Orleans Line*, curving a little to the S.W., enters the valley of a small stream, the Orge, the railway crossing previously the high road to Antibes. It traverses the gardens of

3 Savigny (stat.), a village possessing a handsome *castle*, fortified 1486 by Etienne de Vesi, chamberlain to Charles VIII., now the property of the Princess Dowager of Eckmühl. A great hemp market is held here. Viaducts of 3 and 5 arches lead to and from

2 (rt.) Epiny (stat.), which is 2½ m. distant from Longjumeau on the post road (p. 174). The quarries near this furnish paving stones for the streets of Paris. You next skirt on the l. the forêt de St. Geneviève; on the rt. beyond the Orge, you see the château of Vaucuse; Villiers,

and its villas of Paris citizens, and Longpont, whose church of the 14th cent. is the sole relic of its ancient abbey. A portion of the parc of the handsome château d'Ormay is traversed before reaching

4 St. Michel-sur-Orge (stat.). Montlhéry is about 1½ m. on the rt. Its ancient castle, of which a tower remains, built (1012) by Thibaut-File-Etoupe, forester of King Robert, was the terror of the kings of France in feudal times, and has been made famous by Boileau in the poem of the *Lutrin*.

“Ses murs dont le sommet se dérobe à la vue,  
Sur le cime d'un roc s'allongeant dans la nue,  
Et présentant de loin leur objet ennuyeux,  
Du passant qui les fuit semblent suivre les yeux.”

A bloody but indecisive battle was fought between Montlhéry and Longpont, 1465, between Louis XI. and the troops of the so-called “*Ligue du Bien Public*,” commanded by the Comte de Charolais, afterwards Charles the Bold, of Burgundy. The spot still goes by the name of *Cimetière des Bourguignons*.

The line passes through the midst of the collection of hamlets called

3 Brétigny (stat.), beyond which the railway attains a summit level, and descends into the valley of the Juine shortly before

5 Marolles (stat.) The village and château lie a little on the l.; Arpajon (2400 inhab.) is about 1 m. off on the rt. Beyond Cheptainville we pass through the park appertaining to the château of *Mesnil Voisin*, the property of the Duc Choiseul Praslin, a building of brick and stone on the borders of the Juine.

4 Lardy (stat.). Farther on to the l. is another château, Chamarande. The railway skirts the walls of

5 Etrécy (stat.) It here approaches the post road, which passes through Etrécy, a walled town, and the two run parallel for some distance.

7 Etampes (stat.), close to a ruined tower called *Guinette*, the only re-





Notre-Dame. is a very curious fortified church of the period of transition from the Romanesque to the early French style. with an elegant tower & Spire  
St. G.

St. Giles' ~~Ch.~~ is another fine transition church. The tower has 4 pables with ~~early~~ rude early crockets of the end of the 12 century

St Martin is also a fine edifice of the same Period with a tower at the West end but detached, and built in the Renaissance Period in imitation of ~~the~~ that of St Giles. The foundations have given way and it now leans considerably.



mains of the royal castle and palace, built in the 11th century, by King Robert, and dismantled by Henri IV. It is formed externally of 4 segments of circles.

This ancient town, of 8000 inhab., carries on a considerable trade in flour, the produce of its 40 water-mills, and in wool. ~~Notre Dame is a Gothic church of the 15th centy.; St. Martin, a very fine edifice, has a leaning tower.~~ The royal castle was given as an *apanage* to various remarkable personages, among others to the mistresses of the three French kings Francis I. (Anne de Pisseleu), Henri II. (Diana of Poitiers), and Henri IV. (Gabrielle d'Estrées). The town consists of one long street, and retains several picturesque old houses of the age of the Renaissance: one of them is attributed to Diana of Poitiers. The H. de Ville is an antique building with turrets.

Omnibus twice a day to Pithiviers.

4 Monnerville (stat.). The railway crosses the streams of the Louette and Chalouette on viaducts, and ascending the valley of l'Hémery reaches the upland plain of La Beauce and a second summit level. It crosses the post-road on a bridge shortly before reaching

5 Angerville (stat.). Coaches run hence once a day to Chartres. 14 m. from this is Pithiviers, famed for *pâtés d'alouettes*, for *almond cakes*, and for its trade in saffron. From this point the post and railroad run side by side, within a short distance of each other, so that the description of the one will serve for both.

13 Toury (stat.).

14 Artenay (stat.). Here the road from Chartres falls in (R. 50). A little to the W. of the road, near Rouvray, an English detachment of about 2000 men, under Sir John Fastolf, escorting a convoy of provisions to the army besieging Orleans, defeated a force 4000 strong, consisting of French and Scotch, commanded by Dunois and the Count of Clermont, who endeavoured to intercept them. The French left 500 dead on

the field, among them Sir John Stewart, constable of Scotland. This engagement, fought February 10, 1409, was called "The Battle of Herrings," from the salt fish for Lent, which formed the bulk of the provisions intended for the English.

A few months later, June 18, and nearly on the same ground, at Patay, the English forces under the same commander, retreating dispirited from Orleans, were put to flight at the first onset by the French, led on by Jeanne d'Arc. Fastolf ran away, and the brave Talbot, who never turned back on an enemy, being left to fight almost alone, was made prisoner together with Lord Scales.

6 Chevilly (stat.). Fossil remains of gigantic quadrupeds (*Deinotherium*) have been discovered near Chevilly.

14 ORLEANS TERMINUS a little to the E. of the Porte Bannier.

ORLEANS.—*Inns*: H. d'Orléans, close to the railway, H. du Loiret, excellent for families; very clean and comfortable—*L. F.*; ~~H. de France, Place du Martroy, H. de l'Europe~~ *gov*

Orleans (the Roman *Genabum*, named afterwards *Aurelianum*, from M. Aurelius, who rebuilt it in the 3rd century) occupies an extensive level area on the l. bank of the Loire; it contains 45,000 inhab., and is chef-lieu of the Dépt. of the Loiret. In a town so important for its situation, nearly in the centre of France, midway on the course of the sunny but shallow Loire, of consequence in a military point of view as commanding the passage over that river from the N. to the S. provinces of the kingdom, and conspicuous in history from a very early period—the traveller will probably expect more of interest than he will find. Orleans is not conspicuous for trade or manufactures, and is deficient in tangible historical memorials, chiefly owing to the cacoethes of pulling down for the sake of what is called improvement, which has prevailed to a most

*H. du boulevard, 13 very good*

destructive extent during the last 50 years in the town council. The town gates and walls have been destroyed, several of the latter since 1830, and above all, nearly every memorial of the heroine of Orleans, Joan of Arc, has been swept away.

A tolerably handsome street leads from the bridge over the Loire to the irregular *Place du Martroy*, which occupies nearly the centre of the town, and is prolonged from it under another name (*Rue de Banier*) to the *Barrière de Paris* and the railway.

A wide and handsome new street (*Rue Jeanne d'Arc*) has been driven through a dense mass of old houses from the *Rue Royale* to the W. front of the *Cathedral* (*St. Croix*), the chief building of the town, which this opening now for the first time allows to be seen to advantage. The remarkable circumstance connected with this church is, that it was built as it now stands, in the 17th centy., at a period when Gothic architecture was not only on the decline, but had fallen into disuse. Notwithstanding this it is a beautiful edifice, in a pure style, and reflects credit on its architects, and on Henri IV., who furnished the funds, to atone for the destruction by the Calvinists of the former church, to ingratiate himself (vain hope!) with the Jesuits, and to liberate himself from the pope's excommunication. He laid the first stone 1601, and the building, unfinished at his death, was continued under Louis XIII., XIV., and XV. The design of the W. front was made, 1764, by the architect Gabriel, and modified by his successor M. Paris. It consists of 3 somewhat plain pointed portals, surmounted by 3 rose windows flanked by two towers of equal height (280 ft.) and of great elegance: the circular top is capped by a circlet of cut stone; below this runs a light arcade with fringed arches; in each tower are 3 circular windows. Over

the W. portal are some incongruous coats of arms, supported by cherubs, including the shield of the old Bourbons, now lilyless. The S. porch is a Grecian abomination; indeed the exterior is in many respects faulty. The *nave* is flanked by double aisles. The magnificent effect of the interior depends in a great degree on the large size of the clerestory windows (double that of the side aisle windows).

A portion of the former cathedral, blown up 1567 by the Huguenots, who had previously turned it into a stable for their cavalry, in spite of the remonstrances of the Prince de Condé, still remains in the N. choir aisle: the choir ends in an apse. There is nothing else to notice in the interior. The other churches are either modern or so mutilated as scarcely to deserve notice. *St. Aignan* is the finest; its much injured portal and nave are in the florid style. Under it is a Romanesque crypt; its towers are surmounted by a pyramid. The houses Nos. 2 and 4 in the *Place* adjoining this church, formerly the Convent of *St. Aignan*, were built and inhabited by Louis XI. They are of plain red brick, with high pitched slate roofs, having dormer windows, and resemble closely the remaining fragment of the *château of Plessis les Tours* (R. 53). *St. Pierre-le-Puellier* (*Petrus Puellarum*) has a Norman N. porch and an ancient apse.

Next to the cathedral, the stranger will find the most to interest him in the *Musée*, in the ancient *Hôtel de Ville*, a picturesque old edifice of the time of Charles VIII. and Louis XII., situated *Rue des Hôtelleries*, not far from the *Rue Jeanne d'Arc*. Besides a considerable number of bad pictures it contains a curious collection of local antiquities, carvings in ivory, wood, and stone, which once ornamented the houses and churches of Orleans, chiefly of the 15th and 16th centuries. Amidst old furniture, cabinets, chimney-pieces, bas-reliefs and statues, is an elaborately



carved chest, bearing the history of Solomon and David in relief; another, which came from St. Aignan, is ornamented with a representation of the coronation of Louis XI. A Massacre of the Innocents in stone, an enamelled triptic, and some elaborate iron-work, locks, &c. with Gothic patterns, *chefs-d'œuvre* of the hammer and anvil, also deserve notice.

Not far from the Musée, in the Rue des Albanais, and Rue Neuve No. 22, is the *house of Diane de Poitiers*, so called because she is supposed to have been laid up in it with a broken leg; but it appears to have belonged to the Bishop of Orleans, and was built 1552. The inner front facing the court is a good specimen of Italian architecture, such as we see in the works of Inigo Jones.

Owing to the excessive filth and bad pavement of the older streets of Orleans, the stranger will do well not to trust himself to thread their labyrinths, but should rather keep to the great thoroughfares and the quays, and should only dive into the side streets to visit some particular object and return. The *Rue du Tabourg* contains some interesting specimens of domestic architecture, as the house of Jeanne d'Arc (No. 35), described page 180, and that of Agnes Sorel (No. 15), which is well worthy of examination, on account of its carved wood and stone work, its doors, the reliefs round the galleries facing the court, their roofs, and the staircases. The style of architecture and ornament, and the coats of arms, fleurs-de-lis, &c., render it probable that it was erected by Charles VII. for his mistress previous to 1470.

No. 28, Rue de la Recouvrance, called *Maison de François Premier*, is supposed to have been built for the Duchesse d'Etampes 1540, and in its general arrangement and sculptures (including the Salamander of Francis) is a good specimen of the *Renaissance*.

At one extremity of the Place du Martroy is a *bronze statue* of Jeanne d'Arc, erected 1804, affected in attitude, incorrect in costume, and entirely in bad taste: around the pedestal are bas-reliefs, representing her exploits and death. An ancient statue, erected on the bridge soon after her death, was broken to pieces by the Revolutionists of 1792, to melt into cannon! We have reserved to the last the enumeration of the few remaining memorials, souvenirs and relics of the heroic *Maid of Orleans*. A careful inquiry has only discovered the following:—

In the Salle du Conseil of the *Hôtel de la Mairie* is a portrait of her, painted 1581, from an older picture, it is said; it represents her in a theatrical attitude and in a female costume of the time of Francis I., and apparently deserves little confidence as a likeness. A view of the town, hung up here, shows its ancient configuration about the time of the siege. King Louis-Philippe has presented to the town a bronze cast of the statue by his gifted daughter, by far the worthiest representation of the inspired Maid.

In the *private cabinet* of antiquities, belonging to *M. Vergniaud Romagnesi*, a highly respectable furrier, who has devoted his attention to the archæology of his native town, there exists a likeness of Jeanne which has a claim to be considered as genuine: it is the banner which was carried at the annual procession to celebrate the raising of the siege, presented to the town by Francis I., and painted in the early part of the 16th centy., probably by Italian artists settled at Amboise. It is on canvas, painted on both sides. It represents the Virgin and Child in the centre; on the right hand Charles VII., supported by his patron St. Denis, kneeling to receive a ring from the infant; on the left the Pucelle, also kneeling with hands lifted in prayer, clad in full armour except the helmet, and girt with her sword.

Her long black hair parted across her forehead is bound by a fillet behind her back. The expression is remarkable, the eyes very deep set in the face. The background is a curious view of the town, including the old bridge and the tourelles in the midst of it. This banner still bears the cuts and slashes of the swords of the Huguenots, who regarded it as a relic of popery. It was removed from the Mairie at the Revolution, on account of the Fleurs-de-lis, which had nearly caused its destruction, and was concealed in the garret of one of the Echevins of the town, where it remained until a few years back. M. Vergniaud has among other curiosities some fine painted glass of the 16th centy. from Chénonceaux, and the halbert of La Trémouille, brought from his castle.

The Maid entered the city on Friday, April 29th, 1429, in the teeth of the English army, which was vastly superior to the French force. She had convoyed a supply of provisions from Blois to the famished townsmen, who, as she rode in triumph through their streets on her charger, in full armour, bearing her sacred banner, looked on her as their guardian angel sent from heaven. She was lodged in the house of Jacques Bouchier, treasurer of the Duc d'Orléans, which she had selected, with that sense of modesty which always actuated her, because she would there be under the protection of a matron of good repute, his wife. It stood close to the Porte Renard (long since removed), and only in part exists in the house No. 35, *Rue du Taboury*. The chamber which she occupied is removed, and a sort of pavilion of Italian architecture, erected in the latter part of the 16th century, occupies its place.

The scene of the chief exploits of the Maid was the *old bridge*, which stood considerably higher up the river than the present one (b. 1761), and rested in the centre on an island. It was defended at its extremity, on

the S. bank of the Loire, by a fort, or Tête du Pont, called *Les Tourelles*, which had fallen into the hands of the English before Jeanne's arrival, and, together with another tower in the centre of the bridge, formed a strong post, whence the English greatly annoyed the besieged by a battery of cannon planted on it. It was while reconnoitring the town from this battery, that the English commander, the Earl of Salisbury, was mortally wounded by a shot from the walls, which drove a splinter into his head.

The Maid in her enthusiasm decided that this post should be first attacked; and though her design was opposed by the most skilful of the French commanders, they were obliged to yield, because she carried the people and soldiery with her. As the bridge had been broken between the Tourelles and the town, when that fort fell into the hands of the besiegers, a chosen band of troops with the Maiden at their head was pushed across the Loire in boats, and began the attack upon the Tête du Pont on the l. bank, which formed part of the Bastille des Tourelles. It was defended by a picked body of 500 English soldiers, under Sir Wm. Gladsdale, who for many hours kept their assailants at bay by their unerring flights of arrows and fire of cannon. At length the Maid, seeing her countrymen falter, snatched up a ladder, and planting it against the walls began to mount to the escalade, but an arrow pierced her corslet, and she fell as one dead into the ditch. She was with difficulty rescued by her own people from being made prisoner, and was borne to the rear. Here, however, after a few woman's tears called forth by the anguish of the wound, she received, as she said, the consolation of "her voices," and encouraged by St. Michael, St. Catherine, and St. Margaret, &c. hurried back once more to the contest. Great was the dismay of the English when they



Page 180. -

The Authenticity of this Standard is very doubtful - It was picked up at a brokers' for 10 francs a few years since, but an engraving of it has been published by Mr. Gattman.





beheld her, whom a few minutes before they had supposed mortally wounded, again leading the assault, and waving on high her magic banner. To the feeling of supernatural agency being exerted against them, was now added the failure of arrows and ammunition, and the hopelessness of aid from their army on the opposite bank. The spirits of the French proportionately increased, and they now began to assault the Tourelles from the side of the town, throwing beams over the broken arch to render it accessible. 300 men had fallen on the side of the English, but the surrender of the fort was at length decided by the death of their leader, whom a cannon shot hurled into the river as he was crossing the drawbridge. That same evening the courageous Jeanne, whom but the day before the English had tauntingly desired to "go home and mind her cows," entered Orleans in triumph, by the bridge which had remained many months closed; as she had herself foretold before she began the attack. Next day the English broke up the siege, burning the remaining bastilles which they had erected around the town to hem it in, and retreating from before the walls. Thus in seven days from her arrival in the town, had the Maid accomplished its deliverance.

Opposite to the spot where the old bridge terminated, on the l. bank of the river, stands a small cross called *Croix de la Pucelle*; and the cellars, underneath the neighbouring cabaret called *Le Bœuf*, are part of the celebrated *Tête du Pont* included in the English bastille called *Les Tourelles*. They are now below the surface of the ground, but receive partial light from the old loopholes, which seem designed for the firing of cannon, and are furnished with rings above, from which it is probable that the guns were suspended by chains, as carriages were not then in use. The fort has two branches, and there

is a vaulted passage from it, which the people say led to the river. In its present state the fort is nothing more than a damp, dirty, low cellar, possessing this interest alone, that it is perhaps the sole remaining cotemporary relic of the siege.

The life of the Maid of Orleans has been admirably told in the *Quarterly Review*, No. 138, by one who has used the discrimination of the practised historian in sifting the true from the false, and has unravelled, for the first time, the mystery of her story, without depriving it of any of the charms of romance.

During the Wars of Religion, at another siege of Orleans, 1563, the Duc de Guise, the conqueror of Calais and defender of Metz, who commanded the Catholic army which invested the town, was assassinated before its walls by a fanatical young Huguenot, Poltrot de Méré. He was shot near the village Olivet (R. 70), and died a few days after in the Château de Caubrai. Orleans was then justly regarded as a stronghold of the Protestant party, and continued so until the revocation of the Edict of Nantes banished those who followed the Reformed faith. Previous to that event its population amounted to 54,000.

Francis II., husband of Mary Queen of Scots, ended his insignificant life at Orleans, whither he had repaired to assist at the meeting of the Estates, in the building now the Mairie. In his last illness, at the instigation of his mother, Cath. de Medicis, he sent a deputation of pilgrims to Nôtre Dame de Cléry, promising to purge the kingdom of heretics if he ever recovered. The vow was accomplished not by him, but by Charles IX., at the instigation of the same wicked mother, in the St. Bartholomew's night.

Cæsar mentions Orleans in the following passage: "Carnutes Genabum concurrunt, civesque Romanos, qui negotiandi causâ ibi consisterant, interficiunt."

*Promenades* are formed round the

town upon the line of the former ramparts.

The *Post-Office* is in the Rue d'Il-liers.

*Conveyances*.—*Mallepostes* to Bordeaux, and to Limoges, daily.

*Railways* to Paris, 7 trains daily. To Vierzon:—to Tours (R. 53).

*Diligences*:—to Bordeaux, Nantes, daily; to Lyons by Briare, Nevers, and Roanne; to Clermont by Bourges and Nérès; to Rouen, by Chartres; to Limoges and Toulouse.

A slow coach runs along the road on the l. bank of the Loire, through Cléry and St. Dié, which is only 3 m. from the Château de Chambord.

*Steam-boats* on the Loire, in summer, 3 times a week, to Gien, Nevers, and Moulins, up the river. (R. 52.)

*Environs*. The objects of interest in the vicinity of Orleans are—

Nôtre Dame de Cléry, the burial-place of Louis XI. (p. 184).

The *Château de la Source*, the residence of Bolingbroke (R. 70), is about 5 m. off; a cab costs 4 or 5 fr. The way thither leads across the bridge over the Loire to the village of Olivet, whither omnibuses run every hour from Orleans, where the road turns to the l. The château is named from the little river Loiret, which here rises at once out of the ground in full flood, from a natural basin, but injured by art, close under the walls of the château, in the midst of the parc. After a course of only 10 m. it falls into the Loire, giving, however, its name to the department. With this exception, the grounds, laid out in the formal French style, have little interest; nor has the château itself any other than what it derives from having been the residence of Bolingbroke, who rented it from the proprietor during the latter years of his life when exiled from England. He was visited here by Voltaire. He wrote here his *Reflections on Exile*. There is a second and more copious source, produced, at the beginning of the last century, by the

artificial means resorted to, to confine the waters of the old source, which, in consequence, broke a new passage for themselves.

## ROUTE 50.

### ROUEN TO ORLEANS BY CHARTRES.

201 kilom. = 124 Eng. m.

*Diligences* daily.

11 Port St. Ouen, } (Route 9).  
17 Louviers, }  
23 Evreux, (Route 25.)

13 Thomer. Our route traverses the fertile but monotonous district of *La Beauce* (Belsia), one of the granaries of France, on a table-land, extending nearly from the Seine to the Loire; of which Chartres is considered the capital.

15 Nonancourt.

14 Dreux. (Route 35.)

16 Péage.

16 Chartres (Route 46). It takes about 10 hours to travel hence to Orleans. At the village of Berchères are stone quarries from which Chartres cathedral was built. The road traverses the fertile corn-lands of La Beauce.

26 Allonne.

19 Allaines.

15 Artenay, on the Paris road (Rte. 48), and in the Dépt. du Loiret.

6 Chevilly.

14 Orleans (Route 49).

## ROUTE 51.

### PARIS TO SCEAUX—RAILWAY.

Terminus in Paris, Barrière d'Enfer.

The peculiarity of this line is, that, for the sake of economizing outlay, it is constructed upon steep slopes and curves of narrow radius, which are traversed in safety by railway trains called *trains articulés*, owing to the carriages being made to turn on their wheels like road carriages, the invention of M. Arnoux.

Arcueil Stat.

Cachan Stat.



Bourg-la-Reine Stat. (see p. 174) is situated in the valley, at the foot of the ascent on whose summit is situated the town of Sceaux. The intervening space is traversed by means of curves carried along the face of the slope in zigzags (lacets) of small radius.

The town of *Sceaux* was once famed for its splendid *Château*, built by the Minister Colbert (1760), afterwards enlarged by the Duc de Maine, whose duchess assembled around her here a literary circle the most eminent in France. It was destroyed, except some of the offices and the menagerie, at the Revolution, and its park, laid out by *Le Nôtre*, ploughed up. A part of it has been made a public garden, and part belongs to the Duc de Trevisé (Mortier). The Terrace is a favourite walk of the Parisians. Sceaux is now celebrated for its large cattle-market, and has a considerable glass-manufactory. Florian, the novelist, who resided in the château and died here, is buried in its Cimetière.

#### ROUTE 52.

##### THE LOIRE (A)—GIEN TO ORLEANS.

62 kilom. =  $38\frac{1}{2}$  Eng. m.

2 Diligences daily from Paris by Rail to Orleans, and by Gien to Lyons.

*Steamers* 3 times a week.

*N.B.* The common route at present from Paris to Lyons and Marseilles is to Orleans by railway. Thence by

12 Pont aux Moines	} along the north bank of the Loire.
13 Châteauneuf	
22 Ouzouer	
15 Gien	
15 Briare (in Route 105).	

The scenery of this part of the course of the Loire is not particularly interesting. When the height of water permits, the steamers ascend as high as Nevers, and sometimes even mount the Allier by Moulins to Digoin (Route 105). From Gien to Nevers the course of the Loire is described in Route 105.

Gien is a town of 5530 inhab., on the rt. bank of the Loire, here crossed by a bridge, on the road from Orleans to Lyons. Its old church, *St. Etienne*, has been injured by repairs. Near it is a portion of the ancient *Castle*, now turned into the préfecture. It was at Gien that the Maid of Orleans crossed the Loire on her way from her native village, to announce her divine mission to "Charles the Dauphin," at Chinon.

L., a mound of earth, called *Motte du Leon*, is supposed to be a Celtic tumulus.

About 12 m. below Gien lies

L., Sully, a town of 2145 inhab., possessing a wire suspension bridge, and an old *Castle*, resting its front upon the Loire, and separated from the town by a deep ditch. It is remarkable as the residence of the minister of Henri IV., Maximilian de Bethune, first Duc de Sully, who purchased it from its former possessors, the family de la Trémouille; and in the alterations which he made in the building every where effaced their arms to substitute his own, along with cannons, grenades, bullets, and similar ornaments. He passed here the latter years of his life, after his disgrace under Louis XIII., maintaining considerable state with his regiment of lancers, and occupying himself with the preparation of his work "*Sur les Economies Royales*," which he printed at a press established in one of the towers. It remained in the possession of his descendants down to 1807, when the last Duc de Sully died. One of them fitted up a little theatre in the château, and was visited by the literary men of his times, among them by Voltaire, who here commenced his *Henriade*. The building is now going to decay, and is no longer inhabited: in one corner a few bits of tapestry, old portraits, &c. have been brought together; also a statue of Sully.

Rt., the *Church of St. Benoît*, one of the oldest and finest in the Dept., was originally attached to a monas-

tery, destroyed 1792. Its tower was lowered in consequence of a revolt of the monks against the royal authority under Francis I. It has a curious N. portal, some carved stalls, and one or two curiosities in the sacristy.

Rt., Châteauneuf. Here are remains of a fine château.

The river is crossed by another suspension-bridge at

L., Jargeau, a town of 2358 inhab., 12 m. from Orleans. It still retains a portion of its old walls, within which a few hundred English soldiers, with their commander, the Earl of Suffolk, shut themselves up, after the raising of the siege of Orleans, to resist the attacks of the French led on by Dunois and the Maid. She was struck down into the ditch by a stone, while mounting a ladder to scale a breach made in the walls by the besiegers' cannon; but, recovering herself, instantly rose, and encouraged her followers by her voice and waving banner. The town was taken, and almost all the garrison put to the sword, in spite of the endeavours of the Maid to prevent the shedding of blood. Suffolk was made prisoner.

The *Church of St. Etienne and St. Vrain*, though injured by the Huguenots, 1562, is still a fine building.

Rt., a little below Checy, at Combleaux, is the opening of the canal d'Orléans, which unites the Loire with the Seine.

Rt., ORLEANS, Route 49.

### ROUTE 53.

THE LOIRE (B.).—ORLEANS TO TOURS

—RAILWAY BY BLOIS AND AMBOISE.

—EXCURSIONS TO CHAMBORD AND CHÉNONCEAUX.

*Rail-road* along the rt. bank of the Loire, 115 kilom., = 73 Eng. m. 4 or 5 trains run daily in  $3\frac{1}{4}$  hours.

*Steamers* have been superseded by the railway.

The course of the Loire from Orleans to Tours lies for the most part through a wide valley, slightly varied

by hills of very moderate height: its scenery, therefore, consisting chiefly of slopes covered over with vineyards, of low banks, and islands, fringed with willows and poplars, is somewhat monotonous, though of a sunny character, and relieved now and then by a frowning old town such as Blois or Amboise, or by a formal château. Lower down a yellow streak of cliffs hollowed out into caves and subterranean dwellings frequently forms the bank. The river itself winds very much: its shallow waters occupy a bed too large for them to fill in summer, and it is obstructed by shifting sandbanks.

The first thing worth noticing after quitting Orleans is,

L., the outlet into the Loire of the Loiret, a stream not 30 feet broad, which yet gives the name to a department. On the peninsula between the rivers once stood the abbey St. Mesmin, whose fertile territory was the gift of Clovis to the monks. A part of the church and traces of the gardens remain. The road to Cléry crosses the Loiret by a bridge at St. Mesmin.

7 La Chapelle Stat.

7 St. Ay Stat.

L., opposite to St. Ay,\* whose vineyards produce the best wine in the Orléanois, the spire of *Nôtre Dame de Cléry* may be perceived about 3 m. from the Loire, on its l. bank. This little town, 9 m. from Orleans, contains a very fine *Church*, remarkable for the veneration in which its image of the Virgin was held by the bigot and tyrant Louis XI., who was buried within its walls. Its name must be familiar to every reader of "*Quentin Durward*." Louis passing this way in his frequent journeys into Touraine always performed his devotions to our Lady of Cléry, whose leaden figure he carried in his cap. The existing church was almost entirely built by him, in the place of an older one ruined by the English under Salisbury, 1428. He selected it as his burial-place in pre-

\* *Post Road*.—13 St. Ay.



ference to St. Denis, because he believed he had recovered from a severe illness by the intercession of the Virgin. A grave was made for him in his lifetime, in which he used to lay himself at full length to ascertain whether it fitted him: but this, as well as the statue in bronze which adorned the tomb, was destroyed by the Huguenots, 1563. The existing monument is said to resemble the preceding one, except that the statue is in marble: it was executed by Michel Bourdin, an artist of Orleans, for Louis XIII. It went to Paris 1794, but returned 1818, and has a fresh and modern air from the restoration it has undergone. Louis is represented bare-headed, on his knees in an attitude of prayer, upon a black altar-tomb with four angels in the corners. The image of the Virgin is said to be the identical one before which Louis spent so many hours in prayer: it is black. Independently of its fine architectural proportions, the church possesses several objects of interest, as the sculpture of the Sacristy, much mutilated, the carved wood-work of its stalls, and the Chapel of the family of the Counts of Dunois, in which Tanne-guy du Châtel was buried, 1477. A wretched road leads from this to Meung on the Loire.

The Loire is crossed by a wire suspension-bridge at

6 Meung, or Mehun (stat.), a town whose name occurs in the annals of the English campaigns. It has a Romanesque church, and a red, ruined *Castle* close beside it, partly concealed by trees, and backed by a hill.

L. In the church-yard of Lailly, Condillac was buried without a line to mark the spot. An irregular bridge of some 30 arches, the oldest parts of which date from the 15th or 16th cent., is thrown over the Loire at

7 *Beaugency*\* (stat.), an antique town of 4849 inhab., prettily situated between two hills. Conspicuous above its old houses rises the square

\* *Post Road*.—13 k. Beaugency.

*Donjon tower*, of great antiquity (10th or 11th cent.) and solid construction, 115 feet high, adjoining the *Castle* built by le beau Dunois. The *H. de Ville*, designed by the architect Viart of Orleans 1526, has an elegant front ornamented with the arms of the Card. de Longueville and of the Comte de Dunois. The *clocher* de St. Firmin is the only remains of the church of that saint, and is now attached to the Hôtel Dieu. Beaugency gives its name to one of the best wines of the Orléanois.

The high road runs at the back of the town, skirting without entering it, and for the next 3 stages separates itself from the Loire, to avoid its windings, and passes the little town of

12 Mer (stat.) and Suèvres\*, and the village of

11 Menars le Château† (stat.), so called from the well-built but ill-kept château which belonged to Madame de Pompadour, and under Louis XVIII. to the Duc de Bellune. It is now the property of the Prince de Chimay, who has established a college here.

L. St. Dié, nearly opposite Suèvres, is about  $1\frac{3}{4}$  m. distant from the Palace of Chambord. (See p. 187.)

9 *Blois*‡ (stat.) — *Inns*: H. de l'Europe, tolerably good, near the river; bed 2 fr.;—Nouvelle Angleterre, close to the bridge;—Tête Noire, close to the bridge, very comfortable.—*R.C.* The crème de St. Gervais, a preparation resembling Devonshire cream, made at the village St. Gervais, near Blois, is said to be very good.

This ancient and picturesque town, chef-lieu of the Dépt. Loire et Cher, containing 14,000 inhab., is built upon a steep slope, crowned by its historic and gloomy castle at one end of the ridge, and by the cathedral at the other.

The quarter which reaches down to the river consists of modern houses, forming a handsome quay lined with rows of trees, and along it, between the town and the river, the high road

\* 13 Mer. † 10 Menars. ‡ 8 Blois.

passes. A bridge of 11 arches, surmounted by an obelisk in the centre, unites Blois with its suburb Vienne on the l. bank.

Numerous streets of stairs running up the hill, and winding narrow lanes lined with picturesque old houses, form the bulk of the town, and must be threaded to reach

*The Castle*, for ages the residence of kings and princes, and the scene of momentous events, crimes, and murders. It was degraded to a barrack until recently, when the government, with laudable zeal, began to restore it to its pristine splendour. The E. front, of red brick, facing the square, is of the time of Louis XII., who rebuilt this edifice, in which he was born.

The fine Gothic portal, surmounted by a niche or oriel, is not in the centre of the façade: it leads into a court, the E. side of which is lined with a cloister, resting on pillars carved with a net-like panelling. On the rt. hand (N. side) is the pile raised by Francis I. corresponding in style (Renaissance) with part of Chambord. That on the W. was commenced under Gaston Duc d'Orléans from the designs of Mansard, but never finished; that on the l. (S.) is the most ancient and least like a palace, the work of the early Dukes of Orleans. An elegant winding staircase of stone, from whose rich roof the Salamanders of Francis I. have been effaced, leads into the suite of rooms, now occupied with soldiers' beds, muskets, and accoutrements, in which the Tragedy of the Guises was consummated. Tradition, as it seems, gloating over this deed of blood and deception, has preserved the memory of the minutest particulars connected with it; and, though the interior was stripped of almost all its decorations at the Revolution, and the walls white-washed like those of a prison, points out the chamber and oratoire of Catherine de Medicis, the contriver of the plot,—the *cabinet of Henri III.*, where he distributed with his own hand the

daggers to his 45 gentlemen in waiting, who were to rid him of his rival, the hero of the barricades,—the *Vieux Cabinet*, at the entrance of which the victim, sent for by the king, was set upon by his assassins, as he was turning aside the tapestry hung over the door, and fell pierced with more than 40 wounds,—the outer chamber where the body lay for 2 hours with a cloak and a cross of straw thrown over it, until the royal murderer, issuing from his den to look at the corse of the once mighty Henri le Balafre, spurned it in the face with his foot, saying, “*Je ne le croyais pas aussi grand,*” and then ordered it to be burnt, and the ashes thrown into the river. During the progress of the murder, prayers were being offered up for its success in the adjoining chapel, distinguished by the pendants which still ornament its roof. This happened on the 23rd December, 1588:—on the following day the Cardinal de Lorraine, brother of the Balafre, was murdered in cold blood in another part of the castle. The ground floor at the N. E. angle of the building is occupied by the *Salle des Etats de Blois*, to attend the meeting of which the Guises had been enticed hither from Paris, their stronghold. It was while seated at the council board in this hall, eating prunes de Brignolles, that the duke was summoned by the royal page to attend the king. This hall is supposed to be as old as the 13th cent.: a row of pointed arches supports its double, barn-like roof of wood. The king's throne was placed against the wall on one side.

One other memorial of that age of crime and superstition remains to be noticed,—it is a sort of *pavillon* raised upon an old tower, detached from the S. side of the castle, projecting over the Church of St. Nicholas towards the river: this was the *Observatory of Catherine de Medicis*, to which she used to retire with her astrologer to consult the stars. It bears the inscription “*Urania Sacrum.*” A stone slab, like a tomb-stone, in front of



the pavillon, served as a support for the astrolabe.

A good general view of the gloomy château is gained by turning to the l., as you issue out of the great gate, through a vaulted passage into the Place du Collège, above which it rears aloft its blackening, ill-omened mass from a basement of grass-grown buttresses. Here we may remark the window from which Catherine de Medicis let herself down, to escape from the Calvinists engaged in the Conjuraton d'Amboise. (See p. 190.)

In the *Eglise St. Vincent*, now belonging to a sisterhood, facing this Place, is the tomb of Gaston d'Orléans, who passed here, in a sort of exile, the last 8 years of his insignificant life.

The *Ch. of St. Nicholas* is a fine Gothic edifice, chiefly belonging to the 12th century, except the lower part of the side chapel, said to be of the 11th, and the three first arches of the nave, which probably date from the 13th. The manner in which the capitals are executed, and the regularity of the arches, deserve notice. This church has been restored lately.

The terraced *Gardens* attached to the *préfecture* (formerly Evêché) form a most agreeable walk, commanding a fine view of the town and river, extending to the distant towers of Chambord and Chaumont. The *Cathedral*, or Ch. of the Jesuits, said to have been built by Mansard, has lately been repaired. Not far from it a *Maison des Fous*, a handsome edifice, has been built. A vaulted sewer, partly cut in the solid rock, by some attributed to the Romans and called an *aqueduct*, runs under a considerable part of the town. It is known to the common people as the Pont de César.

In the old streets of Blois may still be found some interesting specimens of domestic architecture of the 16th cent. The H. d'Alluye retains an elegant portico in its inner court, and some rooms on the ground floor, but little altered. Miss Cos-

tello mentions a curiously-carved house in the Rue Pierre de Blois, leading to the Evêché; and an elaborately-sculptured staircase of wood representing St. George and the Dragon, with a central balustrade corded to the top, and compartments filled with various compositions, is figured in Müller's views.

Among the illustrious *natives* of Blois may be named the learned divine and chronicler Peter of Blois, who died in England A. D. 1200; Louis XII.; and Denys Papin, for whom the French have claimed the invention of the steam-engine.

In 1814 the Empress Marie Louise, with the King of Rome, and the remnant of the Imperial court, government, and army, were despatched hither by Napoleon, who made his wife regent; and the last imperial decrees were dated from hence.

The interesting *excursion to the Château de Chambord* may be conveniently made from Blois, whence it is about 12 m. distant, a 2 hours' drive. *Omibus* daily to and fro; a carriage with 1 horse 8 fr., with 2 horses 15 fr. The road thither runs up the l. bank of the Loire in sight of the Château of Menars on the opposite bank, on an embankment or *Levéé*, nearly as far as St. Dié, a village with a small *Inn* (au Grand Chambord), 1½ mile distant from the château. A cross road, in very bad condition, leads thence to

*Chambord*, the Versailles of Touraine, until Louis XIV. deserted that beautiful province to fix the royal residence in a swamp close to the metropolis. It has no beauty of site to recommend it, being placed in the midst of a sandy flat, surrounded by a park 21 m. in circumference, where the roe and deer cross the traveller's path. By many the château itself will be pronounced ugly and fantastic: a vast group of turrets, minarets, and cones or inverted funnels, rise conspicuous at a distance from a solid basement, the chief features of which are 6 external round towers of pro-

digious size, 60 ft. in diameter, which seem the types of all those which characterise French châteaux. Its architecture marks the transition between the fortified castle and the Italian palace, and is a fine specimen of the age and taste of Francis I., who built it, after his return from captivity in Spain, on the site of a favourite hunting lodge of the Counts of Blois, engaging Primaticcio to furnish designs for it. He laid the foundation of it 1526, and employed 1,800 men constantly on its construction until his death. It was afterwards continued, though with less zeal, by Henri II. and Charles IX.; and even Louis XV. added the low screen at the back, which, though from Mansard's designs, is most ugly, and of course inappropriate to the style of the original. It is at present the property of the Duc de Bordeaux, having been purchased for him, and presented to him by public subscription. He has been confirmed in his possession, though the Bourbons have forfeited other estates in France, by the decision of the French law courts. Its 440 chambers are uninhabited, dismantled, and falling to ruin—the glass broken in the windows, the slates falling from the roof, the floors partly ripped up;—but the decay (dating of course from the Revolution) will, it is hoped, be arrested, since a small sum is now laid out yearly by its owner in repairs, and a few rooms are even fitted up with furniture and carpets.

Enclosed within the building a *central* tower rises above all the rest, called *Donjon*, or *Tour de la Fleur de Lis*, from the lily of France, in stone, 6 ft. high, which surmounted it. After having escaped the hammer which defaced all its minor brethren so profusely scattered over the building, at the first Revolution, this monster lily was destined to fall at the second.

This tower is filled with a very beautiful double spiral staircase, an architectural curiosity, so contrived that 2 parties may pass up or down

at the same time without meeting, scarcely even seeing each other. It opens on each floor upon 4 corridors, branching from it like the arms of a cross, vaulted. The compartments of their roof were once filled with the Salamander and F. of Francis I. One of these corridors was converted under Louis XIV. into a theatre, for the first performance of Molière's *Bourgeois Gentilhomme*, in which Molière and his troop performed before the king for the first time, 1670. The device of Henri II. and Diana of Poitiers, the H. and D. entwined with the crescent, are distributed over the parts which he built, but left unfinished.

It is worth while to mount to the terrace and top of the tower to examine the details of the building, its solid masonry inlaid with morsels of black slate cut into the shape of lozenges, crescents, &c. Its rich niches, its classic chimneys converted into ornaments instead of being eye-sores, its balustrades, and flying buttresses, are all curious specimens of the style of the Renaissance, resembling somewhat the Elizabethan architecture of Burleigh. The roof is like the hull of a ship, and must contain a forest of timber. From the top of the tower you look down upon the wide forest and wilderness of a park with its avenues.

There is little pleasure in traversing a labyrinth of empty rooms, mostly small, stripped of all ornament, open to the weather, and showing no traces of the frescoes with which they were decorated by Jean Cousin; unless the imagination can restore them, and repeople their halls and corridors with the brilliancy and beauty of the courts of Francis I. and Henri II., recalling the time when Charles V. was entertained here on his passage through France, 1539, by his generous rival, or that when poor Made-moiselle de Montpensier here lost her heart to the fickle Lauzun.

Among the occupants of Chambord since it was deserted by its royal own-



ers, was Marshal Saxe,—that veteran of a hundred fights, to whom it was given by Louis XV. He brought with him 6 cannon taken from the enemy, and a regiment of lancers whom he reviewed daily from the terrace, although with one foot already in the grave. He died here 1750. It afterwards became the asylum of Stanislas king of Poland, and his queen Maria Leczinska. It was plundered and dismantled by the mob of 1792, and sold as national property. Napoleon bestowed it in 1809 upon Marshal Berthier, from whose widow it was purchased by a body of Loyalists and presented to the Duc de Bordeaux, as already mentioned.

Another excursion may be made from Blois to Valençay by Selles, an old town on the Cher. The *Château of Valençay*, built by Philibert Delorme in the reign of Francis I., is interesting architecturally as a specimen of the style of the Renaissance, and historically as the prison-house allotted by Napoleon to Ferdinand VII. of Spain, from 1808 to 1814, and still more as the residence of M. de Talleyrand during the latter part of his life. The larger rooms contain portraits of monarchs (Napoleon and Louis-Philippe presented by themselves) and of statesmen, his contemporaries. His study and bedchamber remained in 1843 exactly as he left them: his shoes, one furnished with steel spring and bandages for a club foot, his walking sticks, his desk, writing materials, together with his robes, stars, and orders, in a glass case, may still be seen.

Talleyrand's last resting-place is in a vault beneath the chapel of a small nunnery, in a narrow street off the Place at Valençay. It is entered through an iron trap-door in the floor, and in one corner a dark stone sarcophagus contains all that remains of the wily minister of so many sovereigns. By the marriage of a niece of the Duchesse de Dino,

it now belongs to the family Montmorency.

Returning to Selles, the traveller may proceed down the valley of the Cher to Chénonceaux, and thence to Amboise or Loches, passing through St. Aignan, where there is a magnificent *Château* of various ages, formerly belonging to the Ducs de St. A. It is inhabited and kept up with beautiful gardens and terraces, fine trees, and profusion of flowers; the gardens open to the townspeople.—*L.*

Bidding adieu to Blois, its frowning castle, whose W. front looking down the Loire is imposing and more cheerful than the rest, with the astrological tower of Catherine de Medicis in front of it, and the pepper-box dome of the cathedral in the distance, we resume our voyage between vine hills and willow beds.

Rt. Hereabouts begins the colossal dyke called *La Levée*, commenced in very ancient times under the Carlovingian monarchs, and augmented and improved by different kings of France, to restrain the furious Loire within its bed, and check its destructive inundations. It runs along the rt. bank as far as the mouth of the Mayenne, below Angers, a distance of about 100 m. It is faced with masonry kept in constant repair, and the high road is carried along its top. It is a considerable work, though vastly inferior to the dykes of Holland, and was burst through by the inundation of 1846. There are other very extensive dykes on the l. bank in different portions of the river's course.

This high embankment conceals from the view of those who travel by water the wide and fertile plain beyond it; only now and then the tops of houses are seen rising above it.

9 Chousy (Stat.).\*

6 Ouzain St. The first object to be noticed below Blois is,

*L.*, the *Château de Chaumont*, a conspicuous building, on a height,

\* *Post Road.*—10 Chousy.

with machicolated towers, forming 3 sides of a square. It was the residence of Cath. de Medicis, who here spent her time in plotting and in reading the stars until the death of her husband, Henri II., when she obliged his mistress, Diana of Poitiers, to exchange her bijou château of Chénonceaux (p. 192) for this, which, however, Diana does not appear to have inhabited. It was the birth-place of the Cardinal George d'Amboise, 1460, the wise and popular minister of France under Louis XII. The arms, still visible, cut in the masonry, are a blazing hill,—chaud-mont.

Limeray Stat.

Rt.\* Veuves: a little beyond this the Loire enters the province of Touraine, and the Dépt. Indre et Loire.

The high road does not pass through Amboise, but through a suburb on the opposite bank of the river.

L. *Amboise* Stat.† — *Inns*: Lion d'Or. La Boule d'Or was shut up 1841. At the Cygne, on the rt. bank of the river, close to the Poste aux Chevaux, the landlord keeps a good horse and cab, and charges to Chénonceaux 8 fr., or thither and to Loches 15 fr.

Amboise, an old and languid town of 4,600 inhab., stands on the l. bank of the Loire, here divided by an island, upon which the 2 bridges which cross the river rest.

The principal and most conspicuous object is the *Castle*, long the residence of the kings of France, and now the property of Louis-Philippe. Its buildings, flanked by round towers roofed with cones, reduced to a very small portion of their original extent, occupy the platform of a lofty rock, escarped in front and rear. The present king, who inherits the castle as the descendant of the Duc de Penthièvre, has caused the old houses to be swept away from the base of the rock, so as to form an opening from the bridge to a *tunnel*, which he has bored through the rock and under the castle. It is

\* *Post Road*.—11 Veuves. † 12 Amboise.

vaulted with masonry. Two enormous towers, 90 ft. high and 42 in diameter, spring from the ground at the base of the rock, and rise to the level of the other towers. They contain 2 winding, inclined planes of so gradual a slope that horses and even carriages can ascend them to the summit of the rock. The one in front has been lately closed to form a saloon, but that behind, on the l. as you emerge from the tunnel, still gives access to the castle, and is remarkable for its elegant florid Gothic doorway and groined roof. This and most of the other existing buildings date from the time of Charles VIII., who was much attached to Amboise, having been born here, 1470; he also died here, 1498.

In the interior of the château there is nothing worth seeing; the improving hand of the present possessor having pierced holes as big as the embrasures of a battery in its old and massive walls, to admit broad day into vaults once perhaps cachots or oubliettes, but now, by the aid of whitewash, ventilation, and stoves, converted into comfortable kitchens, larders, pantries, and cellars; while the upper rooms, papered, polished, and filled with cast-off furniture from the Palais Royal, preserve no traces of antiquity. Yet in them perhaps was decided the bloody doom of those 1200 miserable and misled Huguenot prisoners concerned in the well-known "*Conjuration d'Amboise*," which had for its object to extricate the young and simple king Francis II. from the clutches and influence of the Guises, 1560. The secret of the plot was betrayed to the Duc de Guise by one of the conspirators, and its leader, La Renaudie, seized and hung on a gibbet in the centre of the bridge. The remainder of the conspirators were dispersed and everywhere seized; the castle walls were decorated with the hanging bodies of the criminals, and the courts and streets of the town streamed with blood, until the wea-



ried headsman, resigning his axe, consigned the remainder to other executioners, who drowned them in the Loire. Such was the extent of the carnage that the court was driven from Amboise by the stench of the dead bodies. This butchery formed the prelude to the still more horrible tragedy of St. Bartholomew. In 1470 the exiled Queen Margaret of Anjou and her son, through the intervention of the cunning Louis XI., were reconciled in this castle to her quondam foe, by whom her own husband had been dethroned, the Earl of Warwick, the king-maker. Hatred to Edward IV. became the bond of union, and they agreed in vowing vengeance on him.

The *gardens* are well kept up, and the view from their terraces is as good as that from the château itself, which is not worth entering, as it contains no paintings or architectural decorations, and is simply furnished as a country gentleman's house. Within the garden, however, stands the *little Chapel*, one of the most exquisite morsels of profusely florid Gothic in France, recently restored by the King in a manner most creditable to French taste. It is in the form of a cross, was built for Anne of Brittany, and is dedicated to St. Hubert, whose miraculous meeting with the stag having a cross growing between its horns is curiously carved over the rich doorway. This and the interior are panelled throughout, or decorated with foliage of the most delicate sculpture. The leaves, showing all their fibres, crisped and curled round the edges like kail, are cut behind in a style more common in ivory than stone. Interspersed among the foliage are singular and grotesque figures: along the wall runs a sort of frieze of stone work; the roof is elaborately groined, and the pendants hanging from it carved with grotesques, the whole reminding one of the richness of Henry VII.'s chapel, without its arrangement. Underneath is a crypt in which was ori-

ginally placed the *Holy Sepulchre*, now removed to the chapel of *St. Florentin* in the town below. It consists of a group of figures as large as life, well executed in baked clay and coloured, representing the Entombment of our Lord. The figures are said to be portraits of the family of an intendant of the palace named Babou, the three Marys being likenesses of his daughters, who were in turn mistresses of Francis I., as the story goes. Marie de Beauvilliers and Gabrielle d'Estrées, mistresses of Henri IV., were daughters of 2 of these ladies. The *Ch. of St. Denis* has lately been restored.

In the cliff a little above the castle, and entered from the garden behind a private house, are very singular caverns called *Les Greniers de César*. They consist of a lofty, narrow excavation running in a direct line into the rock, evidently once divided into three stories, as the broken edges of the chalk vaulting which formed the roofs and floors still remain; and by their removal the three are thrown into one. The walls are covered with cement. At the extremity is a round, vaulted chamber lined with masonry; at one side runs a staircase cut in the rock, descending towards the river and ascending to a level with the roof of the high excavation, where it leads to three other similar vaulted chambers, constructed, it is supposed, to hold corn. There is a tradition that Cæsar, after conquering the Gallic confederation, reached the Loire at this spot, and formed a camp, traces of which still exist on the cliff above, together with these caves below it, to serve as store-houses.

It seems likely that these caves had a much later origin, though their destination was probably for granaries or cellars.

Amboise is said to derive its name from its position between the two streams, "*ab ambabus aquis*," the Loire and the Amasse, which here falls into the Loire.

[A very pleasant excursion may be made from Amboise to *Chénonceaux*, 10 m. S. The road lies through the forest of Amboise, belonging to the King, passing on the rt. the pagoda of the park of *Chanteloup*, whose magnificent château, the retreat of the Duc de Choiseul, discarded minister of Louis XV., when banished from the court to his estate by way of punishment, has disappeared. After the Revolution, it belonged to le Comte Chaptal, the distinguished chemist, and minister of Buonaparte, who established here a refinery of sugar from beetroot, which he first brought to perfection. The château was pulled down and sold a few years ago by the "bande noir."

At Bléré (*Inn*: Boule d'Or) we reach the valley of the Cher; and a road turning to the l. up the rt. bank of the river, covered hereabouts with black vines (*gros noir*), leads to the village of Chénonceaux (possessing a tolerable little inn), which is connected by an avenue with the *Château de Chénonceaux*.

In front of the building extends a stately terrace lined with stone balustrades set with orange trees, approached by a flight of steps; and adjoining is a pleasure garden.

Château Chénonceaux has nearly as many *souvenirs* about it as Amboise, but not of so disagreeable a kind. It was built in the more joyous days of Francis the First. Its picturesque round towers, bartizans, and bridged moat, though still preserving the shape of a castle, were not meant for defence; and its front is covered over with graceful and delicate Italian ornaments, such as are seen at Longleat, at Audley End, and in works of Inigo Jones. It stands on the river Cher: literally *on*, for it is built partly upon a bridge, and the river passes under it. At a distance it is most picturesque, with its green court, its single advanced round tower, occupied by the *Concierge*, and pretty formal gardens around. Its interior is almost unaltered since the day it

was built, besides, what is so rare in France, being well and carefully kept up, retaining all its old furniture, old cabinets, old china, enamels, and glass. Its vaulted hall is hung with armour, its walls are covered with stamped cloth, its doors are screened by tapestry curtains which draw aside, and the rich ceilings are of blue ground studded with stars. You are shown the very glass out of which Francis I. drank; Mary Queen of Scots' mirror, &c. But its chief interest depends on the persons who have lived in it. It was given by Henri II. to his mistress, Diana de Poitiers, who enlarged it by extending the bridge, previously constructed over only part of the river, quite to the other side, and raising upon it a handsome, but less quaint and interesting building, of two stories. Hither her royal lover used to repair after hunting in the neighbouring forest of Loches. Her initial, D, is plentifully introduced combined with his H, thus, *HD*. She was, however, dispossessed of her fair mansion, on the death of Henry, by the wicked and unscrupulous Catherine de Medicis, whose bed-room, with the original furniture, is still shown. It was afterwards for some time occupied by Louise de Lorraine, widow of Henri III.: her chamber is still hung with black. Nor does the list of distinguished inmates cease here, for near the end of the last century all the wits of the time used to assemble here, drawn together by the owner of the mansion, Madame Dupin, a beautiful, amiable, and accomplished lady, who died so recently as 1799, at the age of 93. In her time, Voltaire, the exiled Bolingbroke, Rousseau, and many others, were her constant visitors; and in the little, dusty, faded theatre, which occupies the end of Diana's gallery, Rousseau's opera, "*Le Devin du Village*," was performed for the first time. The collection of historical portraits, including all the persons who have lived here, is very curious; among



them a whole-length portrait of Diana, said to be by Primaticcio, in the costume of her namesake, the goddess, with a dog in a leash, a bow at her back, and wearing a taffeta petticoat, embroidered with golden fleurs-de-lis. Here are also portraits of Henri IV., of Sully, of Rabelais, and a cast of the sweet face of Agnes Sorel from her monument at Loches. The most remarkable thing about Chénonceaux, perhaps, is that it escaped the ravages of the Revolution; owing solely to the respect which the character of Madame Dupin, its mistress, commanded. Strangers are obligingly admitted by the present proprietor, Lé Comte de Villeneuve, to see the interior.

*Loches* (Route 56) is about 18 m. S. of Chénonceaux; the road runs partly through the forest of Loches. It is a dreary ride.

Rt. The road to Tours, below Amboise, is carried along the Levée, at no great distance from the Loire.

Noisay Stat.

Vernau Stat.

13 Vouvray Stat. Here the railway is carried across the Loire to its l. bank on a bridge.

L. Mont Louis (Stat.), a village composed partly of caves cut in the rocks, was the place of meeting of an ecclesiastical assembly, convened to witness the reconciliation of Henry II. with Thomas à Becket only 3 months before his assassination.

Rt., Frillière.\* Near this, the banks of the river rise into considerable heights; and on the top of a projecting promontory stands, conspicuous from afar, rt., the feudal beacon-tower, called *Lanterne de la Roche Corbon*, not unlike a great factory-chimney of modern times. It anciently communicated by telegraphic signals with the Castle of Amboise. It is about 50 feet high, and stands on the very verge of the cliff, above the small village of Roche Corbon, remarkable because most of its habitations are cut out of the limestone

(craie tuffeau). They are sometimes faced with walls, at others with partitions of the living rock, and are prettily festooned with vines. One mass of rock which must have slipped from above, and now lies in a nook, is turned into 2 cottages of 2 stories. These habitations seem comfortable, and are mostly provided with little gardens in front. Some large excavations which belonged to the castle of Roche Corbon, with fragments of masonry, remain. It is worth while to climb up to the top of the rock, beside the Lanterne, to look down upon the Loire from thence—a pleasing prospect. It is possible to scramble through the vineyards along the top of the cliff nearly to St. Radegonde, and so to reach Tours (4½ m.), but there is no path.

Rt. A row of villas with formal gardens, interspersed with villages, line the bank nearly all the way to Tours, whose cathedral towers form a fine object in the distance.

Rt. The round tower, rising at the water-side, close to the road, together with a gate-house and a few crumbling foundations of pillars and walls, are the sole remains of the once magnificent *Abbey of Marmoutiers* (Majus Monasterium), one of the richest in France, founded by St. Martin, in which the sainte ampoule, or vessel of holy oil, given by an angel to St. Martin to rub a bruise which he had received, was preserved, an object of veneration with pilgrims. It was sent to Chartres to anoint Henri IV. at his coronation.

L. Just above the city of Tours is the mouth of the *canal* or cut which joins the Loire to the Cher, whose course is nearly parallel with the Loire, and only 13½ m. S. of it.

Rt. Opposite to it are remains of the Gothic bridge built by Eudes, Count of Touraine, in the 11th cent.

10 L. TOURS Terminus.

TOURS.\*—*Inns*: H. de l'Univers, a new, large, and handsome building, fitted up with every English con-

\* *Post Road*.—12 La Frillière.

\* *Post Road*.—12 Tours.

venience, close to the railway terminus—*R. C.*;—Faisan;—H. de Londres; comfortable, civil attendants;—La Boule d'Or; all 3 in the Rue Royale, close to the Messageries;—H. St. Julien, adjoining the church of that name.

Tours, chief town of the Dépt. Indre et Loire, and once capital of Touraine, is situated in the midst of the fertile but flat valley of the Loire, on its l. bank, and between it and the Cher, and has 28,000 inhabitants. The great road from Paris to Bordeaux and Bayonne here crosses the river by its *bridge* of 15 arches, 1423 ft. long, and traverses the whole extent of the town through its principal street, the *Rue Royale*, a fine avenue running in a direct line from the bridge, and containing the principal hotels, cafés, shops, and offices of the diligences. At its entrance from the bridge stands on the rt. the *Hôtel de Ville*, and on the l. the *Musée*, while in front run quays and planted platforms, serving as promenades. The town is no longer remarkable for the many objects of curiosity which it possessed before the sweeping convulsion of the Revolution; and the charms of its situation, in an unvaried plain, have been greatly overrated by the French. The Loire, though a fine river at certain seasons, contributes less to its beauty than might be expected, owing to a great part of its channel being left bare in summer, so that only three or four of the arches of the bridge bestride the shrunken stream, while the rest traverse wide, ugly beds of bare gravel. Owing to the flatness of the surface and the dust there are few interesting walks or rides in its immediate vicinity. However, our description of the town shall assume the form of a walk which may occupy a long morning or a short day.

Starting from any of the hotels in the Rue Royale, a turning on the l. (Rue de la Scellerie) leads you past the *Poste aux Lettres* to the Arch-*evêché*, approached by a handsome

Italian portal, at the side of which rises the stately *Cathedral* of *St. Gatien*. The W. front, consisting of 3 lofty portals enriched with florid ornaments, niches, and foliage, surmounted by a window having a 4-pointed head, astonishes by its vastness: it dates from about 1510. The 2 towers which flank it are 205 ft. high; their domed tops, carved as with scales, are somewhat later than the rest, and of a debased Italian style, not conformable with the lower part.

The interior, 256 ft. long and 85 ft. high, is in a mature and noble style of Gothic resembling early English, with varied capitals to the columns. The choir was begun 1170, and the nave carried on to completion in the reign of St. Louis; but the W. end is still later, of the 15th century. In the beautiful old painted glass surrounding the choir, and shedding a venerable gloom about the altar, may be seen the arms of St. Louis, of his mother, Blanche of Castile, and those of the town, a group of towers. The fine rose-window in the N. transept is injured in effect by a thick stone prop carried through the middle to support the roof. At the angle of the S. transept and aisle is the marble monument of the 2 only children of Charles VIII. and Anne de Bretagne, in consequence of whose early deaths the succession passed to the branch of Valois Orléans. Figures of the 2 princes, watched by angels, recline on a sarcophagus of white marble decorated with the arms of France, with dolphins, bas-reliefs, and ornaments in the style of the *Renaissance*: it is the work of 2 Tourangeaux artists named Juste, contemporaries of Jean Goujon.

It is worth while to ascend the towers on account of the view; which includes Amboise, Plessis les Tours, and the course of the Loire and Cher. The woodwork of the roof, a masterpiece of carpentry, covering the stone roof, and the elegant, light, spiral staircase (*Renaissance*), resting on a



crown of open groins or ribs in the N. tower, should be seen at the same time.

Passing from the cathedral towards the quay, two circular and machicolated towers are seen on the rt., enclosed within the Cavalry Barracks: these formed part of the *Castle* built by Henry II. of England in the 12th century. From this tower Charles de Lorraine, the son of the Due de Guise le Balafre, imprisoned by Henri III. after his father's murder at Blois, escaped by letting himself down by a rope. Turning to the l. and following the line of the quay, you reach the *Bridge* (b. 1762) already mentioned: several of its arches have given way at different times, owing to the river undermining its foundations.

The *Musée* contains a collection of nearly 200 bad pictures, chiefly copies, and some casts; it is open to the public only on Sundays, 12—4. A Last Judgment, brought from the chapel of the castle of Plessis, may be mentioned as curious.

A little way up the Rue Royale, on the l. in going from the bridge, is the *Ch. of St. Julien*, until these few years desecrated and turned into a remise and coach-house for diligences. It is a fine pointed edifice, date 1224, except the lower part of the W. tower, which is founded upon circular arches, with Romanesque capitals belonging to an older church. The building is undergoing repairs in order that it may be rendered fit for divine service. There are 3 or 4 desecrated churches here.

The first street on the rt. is the Rue de Commerce; and No. 35, said to have been the Chancellerie de Louis XI., is the handsomest old mansion in the town, and a perfectly preserved specimen of the style of the *Renaissance* (16th century) adapted to domestic architecture: its front is richly decorated with coats of arms, scroll-work, &c.; its dormer windows are terminated by crocketed gables; a turret projects in front, below which

is the entrance, and round the bottom runs a light trefoil balustrade.

Continuing our walk along the Rue de Commerce we come to the Rue des Trois Puellles, where the house No. 18 passes for that of *Tristan l'Hermitte*, the ill-omened executioner of Louis XI. (see "Quentin Durward"), though there is no authority for the designation. It is a brick mansion, evidently of the 16th century: its front terminates in a gable, and is flanked by a stair turret, 70 ft. high, overtopping the neighbouring houses and commanding a view of Plessis. Its door and windows are enriched with florid canopies, that over the door supported on twisted columns; but the remarkable feature, to which alone the house owes its name, is that the string courses dividing the 3 stories are formed by ropes in relief, ending in fantastic knots so as to resemble the noose of a halter; the same occurs also over the door. On the wall may be read the motto, "Assez aurons, et peu vivrons," and "priez pour —." The court-yard walls are similarly decorated, and on the ground floor is an elegant vaulted recess for a lavatory. In the same street, on the opposite side, is a house of evidently much greater antiquity (14th century), having a vaulted ground floor and an arcade of pointed arches running along its first floor.

In going hence to the Vieux Marché, a corner house, now a shop, is remarkable for the carvings on the front, representing the Holy Family.

In the centre of the market-place itself is a white *marble fountain*, La Fontaine de Baune, of considerable elegance, in the *Renaissance* style, executed by the brothers Juste. Among its ornaments are the porcupine, the crest of Louis XII., and the ermine of Anne of Brittany.

*Two Towers*, rising on either side of the Rue St. Martin, are conspicuous objects in all views of the town: one, containing the clock, having a domed top, is called the Tour de St. Martin, or d'Horloge; the other, La

Tour de Charlemagne, was so named, it is said, because his wife Luitgarde was buried below it. They deserve notice and mention as the only remaining relics of the vast *Cathedral of St. Martin of Tours*. The pædium of this celebrated building was the shrine of St. Martin, the first metropolitan of Tours (A.D. 340), which became to the barbarians of the dark ages what Delphi was to the Greeks—the oracle which kings and chiefs came to consult in the beginning of the 7th century. The concourse of pilgrims to this shrine occasioned the old Roman town *Cæsarodunum* of the *Turones* to swell to ten times its original extent. The great ecclesiastical establishment, of which this church was the centre, spread civilization and religion through the country, and its archbishop became the patriarch of France and one of the most influential persons in the state. At the head of the chapter even the kings of France were proud to enroll themselves.

Its treasures in precious metals, jewels, &c. amounted to 575 marcs of gold and 2200 marcs of silver, in 1562, when it was pillaged by the Huguenots, who broke the images, melted the lamps, and burnt the relics deposited here. After flourishing for twelve centuries, the church, an enormous edifice, was utterly destroyed at the Revolution, excepting two towers out of the five which adorned it. On viewing the space which now intervenes between them, some idea may be formed of its extent. One of these stood at the W. end, the other at the N.W.; both seem from their style to date from the 12th century. Attached to that of St. Martin may be seen Romanesque pillars and capitals of an earlier edifice. Louis XI., through gratitude for supposed benefits derived from the Saint's intercession, surrounded St. Martin's shrine with a railing of solid silver which weighed nearly 6776 marcs. His needy follower, Francis I., had it taken down and converted into good

crown pieces, which were called "testons au gros bonnet."

Bishop Gregory of Tours, a native of the city, was buried within the walls of this church.

A florid Gothic portal, forming the front of a house in the street running from the market to the Rue St. Martin, was one of the residences of the chapter.

The *Halle au Blé* is another secularised church, dedicated to St. Clement, gutted to a mere shell. It is a building of the 16th century; its florid N. porch, though mutilated, still retains portions of foliage cut with much delicacy. There is nothing to be seen within.

The new *Palais de Justice* is a splendid building.

*Plessis les Tours*, the castellated den of the tyrant and bigot Louis XI., with which all the world is acquainted through the admirable descriptions of Quentin Durward, is situated in the commune of La Riche, adjoining a humble hamlet of scattered cottages, on a perfectly flat plain, about a mile distant from the Halle au Blé, on the W. of Tours, passing the Barrière des Oiseaux, and beyond the Hospice Générale. Visitors to Plessis must not expect anything in the shape of a feudal castle, for it was built at a time when the fortress was giving place to the fortified mansion. When complete, it must have been somewhat like the older parts of Hampton Court and St. James's Palaces, which were built not many years after Plessis, with this difference, that the niggardliness of Louis, and his apprehension of danger, caused it to be built in so plain a style, and with so many defensive precautions, walls of enclosure, draw-bridges, battlements, and wet and dry ditches, that its external appearance must have corresponded with that of a gaol much more than of a palace. The small fragment now remaining, so far from having about it the least trace or character of a castle, looks like a mean ordinary dwelling: in-



deed it formed part of the inner constructions, but was surrounded by three ramparts and fosses. It is of plain red brick, with quoins of stone, and sash windows, surmounted by a high pitched roof, and almost all traces of the scanty ornaments have been destroyed. Beside it is a stair turret, recently raised 16 or 20 ft., with a wooden addition at the side, to convert it into a *shot tower*! Originally a cloister ran along the front. The interior is modern, except the stair, and contains nothing worth notice. All traces are gone of the pitfalls, fosses, &c. which originally surrounded the castle; but on the l., as you approach the house, are seen the foundations of walls of masonry; and a door, below ground, leads into a range of vaulted chambers barely lighted by small windows, which may once have served for prisons, as they now do for cellars. It is evident that the palace was well supplied with dungeons. At the end of the small terrace walk in the garden is another vault, called the *prison of Cardinal de la Balue*, who was shut up for betraying his master's secrets to Charles of Burgundy: it has been repaired, but the lower steps of a stair, the lower part of the fire-place, the grated bars and shutters are old. At the back of a cottage, nearly facing the garden gates, is a small vaulted chapel, now filled with casks, said to be the *Oratory* of Louis XI., where he passed hours in abject prayer to the Virgin and Saints for cure of his complicated maladies. The present doorway has been broken through the wall where the altar stood; the two small windows are nearly stopped up. Louis ended his miserable life here, 1483. Plessis was converted into a *Dépôt de Mendicité* about 1778; it was sold and pulled down at the Revolution. Plessis lies on the tongue of land between the Loire and Cher, about a mile from the Cher, and 9 m. above their junction.

Between Plessis and the Hospice

is an old house, called *La Rabaterie*, having a square turret at the back which passes for the residence of Olivier le Daim, the barber and minister of Louis.

There remains little else to describe at Tours. Under the mutilated and uninteresting church of *Nôtre Dame la Riche* (originally called *La Pauvre*) is a cave vaulted, and having pillars in the corners, where it is said St. Gatien, the predecessor of St. Martin, first preached Christianity to the Gauls, A.D. 251, but it is now shut up.

At the *Préfecture* is placed the *Public Library* of 40,000 volumes, including some curious MSS.; for example, a copy of the Gospels in gold letters on vellum, which belonged to the church of St. Martin, upon which the king of France took the oaths as premier chanoine of that church; Les Heures of Charles V. of France and of Anne de Bretagne, and numerous Missals, besides early printed books. The library is open Tuesday, Wednesday, Thursday, and Friday, 12—4.

The most respectable *Café* is that *De la Ville*, Rue Royale, opposite the Hôtel de Londres.

The *Poste aux Lettres* is in the Rue de la Scellerie, and the *Theatre* in the same.

The number of English established in and around Tours is very considerable; they have a subscription *club*.

The *English Church service* is performed every Sunday at 11½ and 6½ in the chapel, Rue de la Préfecture. There is a second chapel, 5, Levée St. Symphorien.

*Railways*:—To Nantes and to Poitiers in progress; to Paris, by Orléans; *Malleposte* to Bordeaux; and 3 great *diligences* daily, besides others to Poitiers, Angoulême, &c.; to Nantes, Saumur, Angers; to Loches, Bourges, and Chinon daily. Daily to Le Mans, Vendôme, and Chartres to Laval.

*Malleposte* to Rouen and Havre by Le Mans, daily.

*Stcamers*:—Les Inexplosibles daily

to Nantes (in 11 hours) and Angers start very early; 4 or 5 A.M.

Tours was long famed for its manufacture of silk, established 1480 by Louis XI., who brought over and settled here Italian weavers. This branch of industry, however, was ruined by the revocation of the Edict of Nantes, by which the population was reduced from 80,000 to less than one half. This tyrannical act transferred 3,000 families, with their wealth and industry, from France to Holland, and the manufacture dwindled away at Tours to take root at Lyons. Tours has now no manufacture of great importance, but receives some life from being a place of much passage, planted on one of the great high roads of France. The *pruneaux de Tours*, once so celebrated, are now far less esteemed in commerce than the dried plums of Gascony and Provence.

Tours is a city of some importance in history. The *Turones*, its ancient inhabitants, joined the league of the 64 Gallic towns under Vercingetorix against Julius Cæsar, and are mentioned by Lucan, "Instabiles Turones circumscita castra coerunt." The Lande de Miré, about 9 m. to the S. W. on the road to Azay-le-Rideau, is supposed to be the place where the Saracens under Abderahmen were defeated by Charles Martel, and Europe saved from the Mahomedan yoke, A.D. 732.

One of the chief mints of France was established in the middle ages at Tours, whence come the *livres Tournois*, silver pieces (libra or as of the Romans) the equivalent of francs at present, which were coined here.

The *Porte Hugon*, which stood at the end of a street running down to the Loire, is said to have given the name of Huguenots to the Protestant party in France, who being very numerous in the town, but checked and watched by their enemies, used to meet beyond the walls, issuing out stealthily through this gate at nightfall. A more probable deriva-

tion of Huguenot is from the Swiss Eidgenossen, *i. e.* Confederate. Another memorial of the days of persecution of the Protestants is retained in the name *Rue Renard*, persons suspected of heresy being pursued in the streets by the Romanists about 1562, hunted down with the cry "au Reynard," and often massacred.

Touraine was bestowed as an *apanage* on Mary Queen of Scots and her short-lived husband Francis, and she is said to have drawn revenue from it, as Duchess of Touraine, even while in captivity in England, but it was afterwards given in her lifetime to the Duc d'Alençon, brother of Henri III.

It is a pleasant walk of about 4 m. along the road to Orleans up the rt. bank of the Loire to the singular village *La Roche Corbon*, excavated out of the rock (p. 193). It would be better to ride thither, and thus avoid the long dusty road.

The *Colony of Mettray*, about 4½ m. from Tours, established by two philanthropic French gentlemen, the Vicomte Bretignères de Courteilles and le conseiller Demetz, deserves very high praise, and will be visited by all who take an interest in the improvement of their fellow-creatures. The objects which its founders and directors have in view are, the education, reward, and restoration to society of juvenile offenders who while in the public prisons have distinguished themselves by good conduct and by signs of penitence. This is sought to be effected by teaching them the mode of gaining an honest livelihood, chiefly by agricultural labour. The ground on which the establishment stands was given by the Vicomte; it is conducted by him and his friend in person, and is supported by voluntary donations and annual subscriptions.

More distant and highly interesting excursions may be made to Amboise (p. 190), Chénonceaux, 24 m.



off (p. 192; 4 hours' drive), Loches (p. 199), and to that curious and unexplained monument of antiquity La Pile de St. Mars (p. 204).

### ROUTE 54.

#### CHARTRES TO TOURS, BY VENDÔME.

139 kilom. = 88 Eng. m.

*Diligences* daily.

15 La Bourdinière.

16 Bonneval.

An ancient Benedictine convent here is converted into a cotton mill.

14 Châteaudun. A town of 6500 inhab., standing on the banks of the Loir. Its most conspicuous building is the ancient *Castle* of the Counts of Dunois, surmounted by a prodigious tower, 90 ft. high, built by Thibaut le Tricheur in the 10th century. The ancient name of the town, whence comes the modern, was Castellodunum.

During the next stage the road descends by the side of the Loir, passing the Gothic castle of Montigny on a height beyond the river.

12 Cloyes.

17 Pezou.

11 Vendôme.—*Inns*: Hôtel Gailarde, good; Lion d'Or, not bad. A town of 9470 inhab., on the Loir, at the foot of vine-clad slopes. Above it rise the picturesque ruins of the *Castle* of the Ducs de Vendôme, demolished at the Revolution, when the graves of Jeanne d'Albret, mother of Henri IV., and of several Bourbon princes, were rifled, and their tombs destroyed. "Near the Lion d'Or is a fine flamboyant *Ch.*, containing good painted glass, with elaborate and beautiful wood carvings in the stalls of the choir. It has an early Gothic tower and spire. Nearly opposite to it are very curious remains of a *Norman* Domestic edifice of unusually early date."—*E. o. S.* Several smaller churches will repay the notice of a lover of church architecture. There is a *College* here.

We now cross the Loir for the 4th

time, and quit its valley to traverse a monotonous plain to

14 Neuve St. Amand.

12 Château Regnault, a town of 2500 inhabitants.

15 Monnayé (Indre et Loire).

15 TOURS, in R. 53.

### ROUTE 56.

#### TOURS TO LOCHES AND CHÂTEAURoux.

108 kilom. = 67 Eng. m.

*Diligences*, daily, to Loches, in about 4½ hours.

You continue along the road to Bordeaux (Route 64) for about 2 m. after crossing the Cher; then turn to the l. There is little to notice until, after passing

19 Cormery, we reach the borders of the Indre, which flows through one of the richest and most fertile valleys of Touraine; in the midst of which stands

21 *Loches*. *Inns*: H. de la Tour; cheap, and obliging landlord:—H. Grand Monarque. This is one of the most picturesque towns of Touraine, far more striking than Chinon or Amboise; its buildings are huddled together round the base of a lofty rock, from whose commanding top the romantic ruins of its historic and ill-omened *Castle* still frown over the landscape, forming the grand and striking feature in every view. The town still retains several of its old *gates* grooved for the portcullis, and garnished with holes for stockade beams, and in its streets are some old houses. Pop. 4753.

On the opposite bank of the Indre lies the suburb of Beaulieu, connected with the town by a row of bridges. The river winding through the vale overspreads its bottom with a carpet of the richest verdure, fringed with willows and poplars, and turns the machinery of one or two mills.

The *Castle of Loches*, though long a royal palace, in which James V. of Scotland was married to Magdalen of France, and where Francis I. held his splendid court and received the Em-

peror Charles V. on his way from Spain to Ghent, is better known and has a more terrible reputation as a prison of state, especially during the reign of Louis XI., when "the sound of the name of Loches was yet more dreaded than Plessis itself, as a place destined to the workings of those secret acts of cruelty with which even Louis shamed to pollute the interior of his own residence at Plessis. There were in this place of terror dungeons under dungeons, some of them unknown even to the keepers themselves; living graves, to which men were consigned with little hope of farther employment during the rest of their life than to breathe impure air, and feed on bread and water. At this formidable castle were also those dreadful places of confinement, called cages, in which the wretched prisoner could neither stand upright nor stretch himself at length; an invention, it is said, of Cardinal Balue." —*Scott*. Louis appointed Olivier le Daim, the barber, who was also his prime minister, governor of the castle and gaoler. It is composed of a pile of buildings of various ages, partly in ruins. The most conspicuous of all is the tall white Donjon tower, rising at the extremity of the platform of rock to a height of 120 ft., and overhanging the verge of the precipice. Its walls of even and perfect masonry, supported by buttresses, in the form of circular pillars, pierced by scanty round-headed windows above, and by mere slits below, mark it as a work of the Norman style, probably of the 12th century, though some attribute its construction to Foulques Nerra, Comte d'Anjou, in the 11th. In its size, form, and the arrangement of the entrance stair, within a projecting lower tower, it is not unlike the White Tower of London, and the castles of Newcastle and Norwich. Its walls, 8 ft. thick, are now empty, gutted of the four stories into which they were divided. It stands within the inclosure of the town gaol, a

part of the castle having been converted into that ignoble purpose. Beside it rises a picturesque group of less ancient towers, in one of which, circular in form, are the terrible *Cuchots* of Louis XI., extending downwards in four stories below one another. Two of them contained the iron cages invented by Cardinal Balue, who himself expiated his treasonable betrayal of his master's secrets to the Duke of Burgundy by a confinement of 8 years in one of them. In another, Ludovico Sforza, *il Moro* Duke of Milan, the prisoner of Louis XII., was confined from 1500 until 1510, when death released him. Here Philip de Commines, the historian, was also shut up in 1486; the Duc d'Alençon, 1456; Charles de Melun, who was beheaded, 1468; and many more victims of tyranny. These dungeons are vaulted, and dimly lighted by small windows, whose deep recesses, in walls 10 or 12 ft. thick, are crossed by double iron gratings. The cages existed down to 1789.

At the other end of the castle platform, on the l. as you ascend from the town through the arched gateway, is a more modern pile of building, now serving as the *Sous-Préfecture*. At one end of the terrace behind it, within a small tower, is placed the monument of *Agnes Sorel*, mistress of Charles VII., who was born, 1400, in the neighbouring château of Fromenteau. Upon a base of black marble reclines the effigy of La Belle des Belles, well sculptured in white limestone, her hands uplifted in prayer, with two angels bending over her head, and shielding her with their wings, and two lambs reclining at her feet. She is gracefully attired in long robes, and a simple circlet surrounds her brow; her countenance exhibits a refined character of beauty, modesty, sweetness, and gentleness, not unworthy of the Madonna of Raphael, and befitting one whose influence over a king was never exercised but for



good. It has been proved, however, by an acute historian, that she could in no wise have contributed to stimulate Charles to the assumption of his dominions and the expulsion of the English, not having been seen by him until 1431, after the death of Jeanne d'Arc. When Charles died, the ungrateful monks of Loches, whom the bounty of Agnes had cherished and her bequests had enriched, were desirous of ejecting her remains and tomb from their church, on the score of some scruples as to the purity of her life; but even Louis XI., much as he hated Agnes, re-proved such ingratitude, and they remained in their place until the Revolution, when the grave was violated, and the monument was preserved from destruction only by the interference of the préfet.

Between the Sous-Préfecture and the Norman keep stands the *Church of St. Ours*, a very interesting monument of the ecclesiastical architecture of the 11th century, founded by Foulques Nerra, Comte d'Anjou, or his father; but said to have been in great part rebuilt at the end of the 12th century. It is surmounted by an octagonal cupola and by two spires, in the manner of the churches on the Rhine. A large W. doorway, enriched with very singular mouldings and carvings of monstrous heads, has been preserved in a very perfect state, owing to its being covered by a porch or vestibule. Another doorway on the N. has harpy-like figures on the capitals of its pillars. The choir and short transepts have apsidal terminations. The nave is singularly roofed in compartments, forming two cupolas which rise externally in the form of conical pyramids. The *crypt* chapel beneath the choir, recently discovered, was the place of devotion chosen by the bigot Louis XI.

The rest of the road lies up the pretty vale of the Indre to

21 Châtillon-sur-Indre, a town of

2,700 inhab., in the Dépt. l'Indre, and the ancient province of Berry.

23 Buzançais, a town of 3,800 inhab., on the rt. bank of the river, whose branches are here crossed by several bridges.

23 Châteauroux, in R. 65.

### ROUTE 57.

TOURS TO SAUMUR, BY CHINON AND FONTEVRAULT.

76 kilom. = 47 Eng. miles.

*Diligences* daily.

This route issues out of Tours lined by avenues of poplars, and crosses at the distance of  $1\frac{1}{2}$  m. the river Cher, a little to the E. of Plessis les Tours (p. 196). The Cher runs for about 15 m. below this nearly parallel with the Loire, before uniting itself to that river. Along its N. bank runs a considerable levée or dyke constructed by Madame de Vermandois, abbess of Beaumont les Tours, to protect the land between it and the Loire from inundations. After crossing the flat land, passing numerous white hamlets and villas, the road ascends and traverses an extensive table-land before entering the valley of the Indre, on whose banks stands

24 Azay-le-Rideau, a small town prettily situated, 15 m. from Tours. On the l. of the road, nearly concealed by trees, and surrounded by branches of the Indre, is the *Château*, one of the best preserved specimens in France of the semi-castellated manor-house, in the style of the Renaissance. It was built by Gilles Berthelot in the reign of Francis I., and over the chief portal, enriched with sculpture and combinations of three classic orders, may be discerned the emblem of that king, the Salamander, with the motto "Nutrio et extinguo," and the initials of Diana of Poitiers. The carving has been thought worthy of Jean Goujon; the entire façade and the staircase are very elegant, the wall partly panelled, and the compart-

ments filled with diversified patterns. The interior has been preserved nearly unaltered, and contains old furniture and a collection of portraits. A bed, supported in the 4 corners by carved figures, is of a most elaborate Gothic workmanship. A neatly kept garden surrounds the house. The present owner is M. de Biancourt.

A considerable tract of forest is traversed on the direct road from Azay, before it descends by the hollow way behind the castle of.

22 *Chinon*.—*Inns*: H. de France, best, tolerable, though small; — *Chêne Vert*, dirty. A deserted and dull town (6,700 inhab.), which yet deserves a visit, owing to its pleasing position on the rt. bank of the Vienne, and on account of the numerous and interesting historical associations attached to its utterly ruined *Castle*, the French Windsor of our Plantagenet kings, as it has been termed, where Henry II. breathed his last, uttering curses on his own sons, whose disobedience had hastened his death. It was the favourite residence, also, of the French monarchs from Philippe-Augustus to Henri IV., and the scene of Joan of Arc's first public appearance. The remains are of vast extent, but too much demolished, and too white in colour, to be very picturesque. They occupy the summit of a lofty platform of rock, rising nearly 300 ft. above the town and river. A natural escarpment surrounds it on 3 sides; where the cliff was not naturally vertical, it has been cut away, and huge walls of smooth masonry have been built up from below to a level with the top of the cliff, so as to render it hopeless, before the days of gunpowder, to scale or batter such a fortress. Between the river and the rock crouch the buildings of the town. Behind the castle, in a deep hollow, runs the road to Tours, originally commanded by the castle embrasures; and a deep gully or fosse is cut through the rock on the 4th side, to isolate the promontory from

the ridge of which it forms the termination.

Several of the tall flanking towers remain tolerably perfect; the rest is all crumbling wall. The 3 divisions into which the castle was separated, by deep dry ditches, may still be discovered. In the central division, above the entrance to which rises the tall Donjon, the only part now inhabited, are shown the royal apartments; and among them the very one in which Joan the Maid, the simple shepherdess of Domrémy\*, recognised Charles the Dauphin, though disguised in plain attire, and singling him out from among the crowd of courtiers, led him apart to the recess of the window, where she unfolded to him "secrets known only to himself and to God." The scene of that interview, and of the splendours of the court of the careless and luxurious Charles, whom even the loss of a kingdom could not recall from indolence and pleasure, is now a broken ruin open to the sky, with one or two transoms remaining in the windows, and a few traces of paint upon the walls. Close beside it is a very deep square tower, adjoining one of the ditches, and without openings, said to have been the Oubliettes down which prisoners were cast.

Crossing a bridge into the 3d court, we find around it the towers of *la Glacière*, in which Jacques de Molay, Grand Master of the Templars, is said to have been confined; the *Tour du Moulin*, so called because it was surmounted by a windmill, standing at the farthest extremity, and of very solid structure; and the *Tour d'Argentau*, from which, as the story goes, a secret passage led beyond the wall to the Maison Robardeau, the retreat of Agnes Sorel, Charles's mistress. Among all these fragments, the only trace of the original Norman castle is to be found in the round tower du Moulin; the rest seems not older than the 15th century.

\* See Quarterly Review, No. CXXXVIII.



The view from the walls is very pleasing, extending for a long distance up and down the fertile valley,—“a glowing and glorious prospect; a green expanse of groves and vineyards all blending into one,”—with the winding Vienne sparkling and flashing among the green meadows, or foliage of poplars, walnut-trees, and vines, nearly as far as its junction with the Loire, which, however, is not visible. Fontevrault, the last resting-place of Henry II. and his undutiful son, the Lion-hearted Richard, is concealed from view by intervening heights.

There is nothing worth notice in the town of Chinon (pop. 6,677) itself. No tradition is preserved of the hostelry in which the Pucelle was lodged, on her arrival from her native village, and where she was kept two days before she could obtain admission to the king, until his councillors had ascertained whether she was a sorceress. Nor can the church be pointed out in which she spent the greater part of each day in prayer, while she resided here. It was at Chinon that she first received from the king her suit of knight's armour, and an escort of a squire, a confessor, and 2 pages. Here she first girt on the mysterious sword found in the church of St. Catherine of Fierbois, and here unfurled her white banner sprinkled with fleurs-de-lis, made expressly for her under the direction of her mysterious “voices.”

The rocks behind the town, underneath the castle, have been quarried for ages to supply building materials, and these *subterraneous excavations* have attained a great extent. There is nothing worth seeing in them, nor is it a task of pleasure to explore them.

Chinon is the country of Rabelais, who was born 1483, in the farm-house called *la Devinière*, in the commune of Seuilly, a little way on the l. of the road to Saumur, on the opposite side of the Vienne. He commenced his education in the school of the neigh-

bouring abbey, whose monks he afterwards ridiculed in his writings.

At Champigny, about 9 m. S. of Chinon, is a chapel containing very remarkable painted glass, representing the life of St. Louis.

It is a very delightful drive from Chinon to Saumur, through a country teeming with fertility, amongst orchards, and walnut groves, and acacia hedges, while beneath the fruit trees springs up a crop of corn, without exhausting the soil. The valley of the Vienne terminates at Candes, remarkable for its fine church (p. 205), where that river falls into the Loire; and our road emerging upon its l. bank, is carried along it, through most pleasing scenery, to

30 Saumur, described, with the rest of the road, in p. 206.

At Montsoreau, close to Candes, our road passes within 3 m. of the *Abbey of Fontevrault*. The excursion thither is described in p. 205.

## ROUTE 58.

THE LOIRE (C): TOURS TO NANTES, BY  
SAUMUR AND ANGERS.

By land 200 kilom.=124 Eng. m.

A *steamer* descends daily to Nantes in about 11 hours, touching at Angers. Two steamers ascend daily between Nantes and Angers, in 10 hours.

*Railway* from Tours to Nantes (120 m.) is in progress as far as Angers, about 65 m.

The prettiest part of the course of the Loire lies below Tours, in the neighbourhood of Saumur, and thence to Nantes. For some distance below Tours, however, its banks continue low, and its bed, everywhere too large in summer for its stream, is left bare and unsightly. Owing to the want of water, and the constant shifting of sand-banks in hot summers, the navigation is very often interrupted for two or three months. In winter, the river sometimes rises 20 ft. above its ordinary level, and from these irregularities it is unfit for the per-

manent establishment of water-mills or manufactories on its banks. It is confined on both sides by levées as far down as Angers (p. 172).

The project of limiting its bed to a width of 120 mètres, by stone dykes raised in the midst of the stream parallel with its course, intended to force the bulk of water into a central channel, and allow the sand to be deposited behind them, has produced an exactly opposite effect; for the river, having in most instances broken through the walls, runs on the outside of them.

The *high road* continues, as before (p. 189), along the Levée, or river dyke, often on a level with the tops of the houses and cottages, which, together with the fertile fields, orchards, gardens, and vineyards, it protects from the inundations of the Loire, commanding, both on the river and land side, an extensive view.

Rt. St. Symphorien, nearly opposite Tours, forms a sort of suburb to that city; and not far from it is the pretty hamlet of St. Cyr, where a cottage, called La Grenadière, is at present the retreat of the veteran poet Beranger.

Rt. Luynes\* is a small town at the opening of a valley into the Loire, backed by a limestone cliff, pierced with numerous cave dwellings, on the top of which stands the old *Castle*, commanding the country around. It was the residence of the seigneurs of Luynes, and among them of the first duke, the favourite of Louis XIII. and Constable of France, who gave his own name to the castle and town, previously called de Maillé, 1619. Not far off are the ruins of an *aqueduct*, said to be Roman, of which nearly 50 square pillars and 8 arches remain. Luynes is the birth-place of Paul Louis Courier, the celebrated political writer; he was found shot dead near his own residence, Veretz, on the banks of the Cher, not far from this, 1825.

A little below Luynes is,

\* *Post Road*.—10 Luynes.

Rt., Cinq Mars, or more correctly St. Mars, since the name is supposed to be a contraction of St. Medard. Near this village, whose ruined castle gave a title to another favourite of Louis XIII., who fell by the executioner's axe, under the relentless rule of Cardinal Richelieu, is the curious ancient monument called *La Pile de Cinq Mars*, a square tower of brick, 92 ft. high and 13 ft. wide on each face, surmounted originally by 5 pinnacles 10 ft. high, one of which was thrown down by a storm, 1751. The origin, use, and age of the pile are equally unknown. Some attribute it to the Romans, others to the Celts. It is destitute of door, window, or other opening, and is perfectly solid. On the S. face the bricks are arranged so as to form 12 compartments. It was *probably* a funereal monument.

The traveller continues to pass entire villages cut in the yellow chalk rock, or *tuffeau*, whenever it rises into cliffs favourable for human habitations.

L. The Cher, after running parallel with the Loire for about 15 m., enters it a little above Cinq Mars, but sends off a branch which continues to run parallel with it until it joins the Indre, 9 m. lower down.

Rt. Langeais,\* another little town, has also a *Castle*, in tolerable preservation, which is remarkable because the marriage of Charles VIII. with Anne of Brittany was celebrated within its walls—an event which united that important province to France. The gate-house serves as a gaol. This castle was built, in the 13th century, by Pierre de la Brosse, minister of Philippe le Hardi, after having been barber to his predecessor St. Louis. He ended his career on the gibbet of Montfaucon, being hung for high treason in poisoning his master's son and accusing the queen of the crime.

Rt. Near St. Patrice is the Château of Rochecotte, where the famous Chouan leader of that name was born;

\* 14 Langeais.



it belongs to the Duchesse de Dino, now Princesse de Talleyrand, who was often visited here by her uncle, M. de Talleyrand.

Rt. Trois Volets.\*

L. Nearly opposite this, backed by a wooded hill, is the Château d'Ussé, belonging to one of the family of La Rochejacquelin, but partly built by Vauban, its original owner.

Rt. Chouzé,† on the confines of Touraine. Near this, if anywhere, the valley of the Loire exhibits its garden-like character, an exuberant vegetation, with trees of large growth, capable of furnishing some shade to the road,—among them the graceful feathery acacia, which also forms the hedges,—vines, Indian corn, and mulberry-trees, prevail. At Port Boulet the Loire is crossed by a wire suspension-bridge of 5 spans, leading to

L., Candes, opposite to which place we pass out of Touraine into Anjou.

L. The river Vienne here pours itself into the Loire; and immediately below it stands the pretty white town of Candes, where St. Martin of Tours breathed his last. It has an interesting church, of which the apsidal choir seems to be of the 12th century, and the nave of the 13th (1215). Its S. porch is remarkable, though much mutilated; 14 statues in trefoil-headed niches adorn the façade, with smaller niches below them filled with heads. The porch itself is a vestibule supported by a light central column, in the manner of the chapter-houses of English cathedrals. The W. end is flanked on either side by a machicolated buttress, and includes a circular window, now stopped up. The tomb of St. Martin is shown in this church. The possession of his remains was warmly contested between the Poitevins and Tourangeaux.

About 10 m. from Candes, up the valley of the Vienne, is Chinon. (Route 57.)

A small brook alone separates

\* Trois Volets      † 12 Chouzé.

Candes from Montsoreau, whose *castle*, now parcelled out among poor people, was the seat of that cruel Comte de Montsoreau who became the executioner of the Protestants of Anjou, by carrying out the infamous St. Bartholomew decrees of Charles IX.

3 m. up the little retired and wooded valley behind Montsoreau lies the *Abbey of Fontevrault*, one of the richest in France in ancient times, where 150 nuns and 70 monks submitted to the rule of an abbess, who was always a lady of high degree. This singular establishment, which thus combined members of both sexes, was founded by a Breton monk, Robert d'Arbrissel, 1099; who by his powerful preaching converted and led after him a multitude of followers of both sexes and all ages, amounting to 3000, whom he at length settled here, in a sequestered forest, on the borders of Touraine and Anjou. In spite of the scope for scandal, the convent maintained its existence for 9 centuries, down to the Revolution. It has an interest to Englishmen, from having been the burial-place of several of our Plantagenet kings. A tolerably good road leads to the poor village of Fontevrault, where the inn (Croix Blanche) does not look promising.

The *Abbey* is now converted into a prison (Maison Centrale de Déten-tion); one of the largest in France, covering 30 or 40 acres with its courts and ranges of building occupied by 500 women, 1200 men, and 300 boys; the entrance is in the little *place* close to the inn. The prison is not shown without an order from the préfet; but no objection is made to admit strangers into the church to see the tombs, which they can do without coming in contact with the prisoners. Above the abbey building rises a singular *octagonal tower*, ~~or oratory~~, called *Tour d'Evrault*; it dates from the 12th century.

The *church*, approached by a covered way, from which you look

*but was in fact the kitchen*  
*for an account see Tour. d'Arbrissel (1099)*

through loop-holes into the prison yards, is a very ancient building, supposed to have been begun by Foulques, 5th Comte d'Anjou, 1125. Its nave is now partitioned off, and, by the introduction of 2 floors, is converted into dormitories for the prisoners. The *Royal monuments* are transferred to the S. transept, enclosed by bolts and bars and grilles, in a dark corner; their mutilated visages and broken limbs bearing testimony to the violence of the Vandals of the Revolution, who tore them up in order to rifle the graves of their contents. The royal dust of 2 kings and 2 queens was scattered. The effigies, in spite of the injuries they received, are interesting from the evident marks they exhibit of being portraits; they retain still a little of the colouring with which they were ornamented. They are recumbent statues of Henry II. and Richard Cœur de Lion, represented in their royal robes without armour; the drapery of complicated execution. Richard is remarkable for his lofty stature (6½ ft.) and broad forehead; he wears moustache and a beard; his hair is cut short. The two female effigies are in better preservation; they represent Eleanor of Guienne, queen of Henry II., and Isabelle d'Angoulême, widow of King John; the last a statue of considerable beauty. It is much to be desired that these neglected effigies of our kings should be transferred from their dark prison-house to Westminster Abbey, where they would form an interesting link in the series of British historical sculpture. There can be no longer any harm in separating them from graves rifled and empty, and from an abbey now become a prison. The French government owes us some return for our ready compliance with its wishes to possess the bones of Napoleon.

The body of Henry II. was brought hither from the neighbouring royal residence of Chinon, and laid in the sanctuary previously to interment.

When Richard, his undutiful son, approached, the dead body is said to have shuddered convulsively, and to have sweated drops of blood while he remained in its presence; "the very corpse, as it were, abhorring and accusing him of his unnatural conduct."

L. Souzé, a little below Montsoureau, contains a castellated mansion, behind which are vast excavations in the rock, which is pierced through and through like a rabbit warren to furnish dwellings for people of the poorer sort.

L. Still lower down is Dampierre, where Margaret of Anjou ended a life of ambition and sorrow, in misery and poverty, in a house granted to her by Louis XI., who had ransomed her at the price of 50,000 crowns from the hands of Edward IV., after 5 years of imprisonment, dating from the battle of Tewkesbury.

L. The approach to Saumur is marked by the number of windmills on the heights, below which stands the domed church of Nôtre Dame des Ardilliers. Beneath its cupola runs an inscription celebrating the suppression of heresy throughout his dominions, and the expulsion of its followers, by Louis XIV.; a subject rather of shame than of boast, on a spot which suffered in turn the massacre of St. Bartholomew, the atrocities of the Dragonnades, and finally ruin from the revocation of the Edict of Nantes.

The convent attached to this church is now the *Hospice de la Providence*, attended by charitable sisters: a portion of the patients, including the insane, are lodged in cells and vast dormitories cut in the cliff behind.

Rt. La Croix Verte,\* a suburb of Saumur, at the extremity of the bridge opposite to the town, contains the post-house.

L. Saumur.—Inns: Belvédère, on the quay, well placed and good; fine

\* Post Road.—16 Croix Verte. 4 kilom. extra are paid by those who take the horses into or from Saumur, crossing the bridge.



Page. 206.

At a short distance from the Abbey is a  
curious cemetery chapel, or "Lanterne des Morts  
of the 13<sup>th</sup> century.





view from its top: Hôtel de Londres, Rue Porte Fouchard.

This cheerful white town is one of the most picturesque on the Loire. Seen from the river or the bridge, its quaint Hôtel de Ville, near the water-side, surmounted by a tent-like roof and pinnacled turrets, its church spires and towers, overhung by the castle behind, have a very pleasing effect. The town itself, however, is torpid, though its population amounts to 15,000 souls, and it does not possess many curiosities.

On the handsome quay which lines the river, stand a modern edifice which combines theatre and market-house, and the above-mentioned antique *Hôtel de Ville*, a square building of black and white stone, with a peaked roof as high as its walls, a cornice of trefoiled machicolations running under it, and turrets or bartizans in its corners. It was anciently included in the fortifications, and joined the town walls, and, therefore, has few openings in the lower part. The front towards the court-yard has not the same castellated character, but is enriched with florid Gothic ornaments, very elegant, and recently restored. The date of the building is probably the 15th cent., about the time of Louis XI. The upper story is converted into a *Museum*. The best part of its limited collection are the *antiquities* found in the department; such as Roman vases, statues, spear-heads, axes, &c. of bronze; a complete set of Roman carpenter's tools, Roman weights, glass, cinerary urns (30 of them dug up in one spot), pottery, &c. But its chief curiosity is a Roman trumpet of bronze, 5 ft. long. Among the Celtic remains are several stone axes, dug up under one of the Dolmens in the neighbourhood, and a Druid knife of flint, from that of Bois Berard.

*St. Pierre*, the principal church, in the centre of the town, is disfigured by a modern Italian façade, and its massy tower is surmounted by a recent spire. Its interior, originally

built without aisles, in the Angevine fashion, has had side chapels added. It is in the pointed style.

More curious for its age and architecture is the church *Nôtre Dame de Nantilly*, on the outskirts of the town. The oldest parts, the N. side, the nave, and E. apse, in the Romanesque style, have been supposed to date from the 5th or 6th, but cannot be older than the 11th cent. The S. aisle is an addition of the 15th cent., nearly as wide as the nave itself, and the pillars between are nothing more than the old buttresses. The roof of the nave is slightly pointed, with plate-bands running across from pier to pier. In the S. aisle is the oratory of Louis XI. Against one of the piers is a bas-relief of John the Baptist preaching in the wilderness, renewed 1830. The church is hung with curious antique tapestries, probably of the 16th cent., productions of the looms of Flanders, if we may judge by the style of art. In one, representing the siege of Jerusalem, one soldier appears to be discharging an instrument like a matchlock, (?) but all the others are armed with bows and arrows. In this church are buried Gilles, Archbishop of Tyre, keeper of the seals of St. Louis, whose crozier is preserved here, and the nurse of king René of Anjou.

The *Castle*, standing conspicuously on the top of the ridge which rises like a wall above the town (*Sous-le-mur* is a fanciful derivation of its name), is only worth entering for the view from its terraced bastions, over the Loire and the rich flat land on either side of it, not forgetting the pretty gardens at the base of the walls. The tall *Donjon*, circular below and octagonal above, and flanked by four turrets, is a magazine for powder and fire-arms, and is shut to strangers.

The wise Protestant leader, Duplessis Mornay, was appointed governor by Henri IV., and under his prudent and fostering care Saumur was a stronghold of the Protestants,

and a flourishing town of 25,000 inhabitants. The revocation of the Edict of Nantes annihilated its prosperity, by expelling the industrious Huguenots, and reduced its population to *one fourth*.

One of the greatest exploits of the Vendéan army was the capture of Saumur, June 10, 1793, by storming the heights, on which the Republican army, 15,000 strong, had formed an intrenched camp, defended by 100 pieces of artillery. Henri de La Rochejacquelin forced the intrenchments of the town from the side of the meadows of Varen, exciting his followers to the capture of a redoute by throwing his hat, conspicuous for its white plume, into the midst of the enemy, crying "Qui va me le chercher?"—an appeal not lost upon his followers, especially when enforced by his own example in taking the lead. Foremost of his band, with only 60 of his men to back him, he burst his way into the town, clearing the streets before him as far as the bridge. Here, seizing two cannon, he turned them against the enemy, drove them quite across the river and on the road towards Tours, thus separating them from the garrison of the castle, which surrendered the day following. The Vendéans obtained this victory with a loss of only 60 killed and 100 wounded, and with a gain of 60 pieces of cannon, 10,000 muskets, and 11,000 prisoners, who were released after having one side of their head shaved, and promising not to serve against La Vendée—humane conditions, contrasting strongly with the atrocious system of massacring their prisoners, already adopted by the Republicans at the command of the Convention.

Detached from the town, to the S.W., on the rt. hand, as you issue out of the main street, is the *Ecole de Cavalerie*, for the instruction, in all branches of information suited to their profession, of between 300 and 400 sous-officiers, who are drafted hence into different regiments to instruct their corps. There are large

*riding-schools*, covered and open, in which the various exercises of the manège are performed with much precision. This establishment was transferred from Angers hither at the latter end of the last century.

Some remains of the old fortifications may be seen in the Rue du Petit Mail; they consist of two feudal towers and a prison-house. In the quartier *des Ponts*, the suburb which fills the island on which the bridge rests, is a house built by King René of Anjou, and called *Maison de la Reine Cicile* (de Sicile). Its once highly ornamented front, in the latest Gothic, not unlike that of the H. de Ville in style, has been so deplorably defaced that it retains little interest, but it may still be worthy to employ the artist's pencil.

Within about 1 m. of Saumur, on the S., stands one of the largest, most perfect, and best preserved Druidical monuments in France, the *Dolmen of Pontigné* (§ 4). It may be termed a hall composed of huge blocks of unhewn stone, set upright to form the walls, with others laid across them for a roof, in the manner of a house of cards. This rude cot measures more than 80 ft. in length, yet consists of only 18 stones, 4 on each of the sides and on the roof, one at the W. end, which is closed, another at the E., now thrown down, serving as a threshold over which you step to the present doorway, formed by bricking up the mouth. The largest stone measures 24 ft. by 21 ft., and  $2\frac{3}{4}$  ft. thick. The stones are set so close, that originally a man could not force his body between them. The blocks composing it are of the sandstone found in this district, but not near at hand, nor near the surface. Among the adjoining vineyards stands an upright stone, also of Celtic origin. Near Riou,  $\frac{1}{4}$  m. distant, on the top of an eminence, is another *pierre-couverte*, formed of only 6 stones, in the manner of Kits Coity House in Kent.

The road to these Druidic stones,





P. 209

Our Summer is grown all ~~very~~ pleasant light effere  
vescent wine, and is supplied by Mr. Budan  
I can well recommend it (J.P.).



on issuing out of Saumur, crosses the small river Thoue by a handsome new bridge of 3 segmental arches, called Pont Fouchard, thence by cross roads proceeds to the village of Bagneux, beyond which they are situated.

Anne Lefèvre, who became Madame Dacier, the learned translator of Homer, was born at Saumur.

*Diligences* daily to Tours, Angers, and Nantes; to Le Mans; Chinon, Cholet; Poitiers and Bordeaux; to Niort and Saintes.

*Steam-boats.* The ascending boat from Angers and Nantes arrives here about 10 A.M.; the descending boat from Tours about 12. They bring to, for a few minutes, opposite the Belvedere.

L. The Ecole de Cavalerie is seen as you quit Saumur. The whiteness of the houses about Saumur is remarkable, and arises from the pure colour of the stone, which, being readily cut, is formed into smooth, nicely jointed masonry, and gives even to humble cottages the aspect of villas. They add much to the pleasing character of the country, peering from amidst the luxuriant foliage. Acacia hedges, vines, and walnut trees, with orchards and rich crops of corn, cover this really beautiful district, upon which all the bounties of nature seem to have been lavished.

L. The village of Tuffeau receives its name from its quarries of tufa, worked into vast subterranean catacombs, which have furnished building materials for the surrounding district.

L. Trèves is conspicuous owing to its pretty Gothic tower, 100 ft. high. It was built by Foulques d'Anjou, 1016, and given by Charles VII. to his Chancellor, Robert-le-Maçon, for saving his life at the capture of Paris by the Burgundians: it is carefully kept up by its present owner. Not far off is the *Church of Cunault*, attributed to King Dagobert, and though not of his time, at least of great antiquity: 11th to 13th century.

Rt. Les Rosiers. L. Nearly opposite, the very ancient *Church* of Geunes rises on the top of a hill: it is dedicated to St. Eusèbe, and is said to have been used by the early Christians. The ruined nave is built of small stones, alternating with bands of tiles in the fashion of Roman masonry. The N. door is arched with bricks intermingled with stones, and in the wall above is a row of small semicircular arches. Geunes lies in a remarkably pretty situation, on a streamlet called Avort.

L. The vast conventual buildings of *St. Maur*, with sixteen windows on a row in front, deserve to be looked upon with respect as the retreat of those learned and laborious Benedictines who, in the 17th century, under the patronage of Richelieu, 1621, compiled those ponderous folios—stores of learning and erudition,—“*L'Art de vérifier les Dates*,” “*Gallia Christiana*,”—the Collection of French Historians—the Monumental Antiquities, &c. “Works of general and permanent advantage to the world at large; showing that the revenues of the Benedictines were not always spent in self-indulgence, and that the members of that order did not uniformly slumber in sloth and indolence.”—*Sir W. Scott*. Among the most eminent names which distinguished this society of learned monks are those of Felibien, Montfaucon, Vaissette, Lobineau, and Mabillon.

A wire bridge of 5 spans has been constructed at

Rt. St. Mathurin,\* nearly opposite St. Maur. At Daguénière, a little lower, the Levées de la Loire (see p. 189) terminate, after running by the river side from Blois hither, a distance of nearly 100 miles; and here the road to Angers† and Nantes turns away from the Loire, to rejoin it about 20 m. lower down.

\* *Post Road* from Saumur.

15 Les Rosiers.

11 St. Mathurin.

† 21 Angers, on the Mayenne, is described in R. 46.

Below this the Loire is split into a number of channels by considerable islands, which are connected together by a series of 4 bridges of more than 100 antiquated arches of wood and stone, equally inconvenient for boats, which pass under, and for vehicles, which go over them, measuring altogether about 4,600 ft.

Rt. Ponts de Cè. A town of 3,520 inhab., on the rt. bank of the Loire, which is here nearly 2 m. distant from the l. bank. It is about 4 m. from Angers (R. 46). Some antiquaries have attributed its origin to *Ce-sar*, who, according to them, also bequeathed to it the first syllable of his name—a theory which is considerably thwarted by the fact that the name was anciently written Ponts de Scez. The bridges form an important passage over the Loire. A bloody engagement was fought here in the Vendéan war, 1793.

Coaches run several times a day between Ponts de Cè and Angers, p. 160.

L. About 7 m. S.E. of Ponts de Cè is the *Château de Brissac*, seat of the noble and ancient family of that name, consisting of a handsome Italian palazzo, between two older castellated round towers, of such solid construction that it was found impossible to remove them when the centre was built, and they were in consequence amalgamated with it. It is conspicuous for the red colour of the stone. The general effect of its façade, though of a mixed character, is stately and good, but the details of carving have been destroyed by mutilations. The château was ransacked, stripped, and dismantled during the Vendéan war, and returned to the Duc de Brissac at the Restoration a mere shell. It is still uninhabited, but contains only a few articles of antique furniture.

L. the Loire is joined by the Maine (called Mayenne above Angers) about 6 m. below Ponts de Cè. On the point of land between them stands the village of La Pointe,

where are numerous white villas and walled gardens of the citizens of Angers.

The steamers, both in ascending and descending the Loire, penetrate up the Maine to touch at Angers.

Below the junction of the Maine the Loire is sensibly augmented in expanse and depth, and its banks attain a more considerable elevation than above, rising into hills, often in abrupt precipices from the water's edge.

Rt. One of these heights, called Coulée de Serrant, is clothed with vines, the growth of which is much esteemed. The *Château de Serrant*, the stately mansion of Count Walsh, is one of the finest on the Loire, and is situated 3 m. from the river, between it and the high road to Nantes. Its gardens, park, and orangery are said to be fine and well kept up. In the chapel is a marble monument by Coysevoix to the Marquis de Vau-brun, killed at the passage of the Rhine. The family is of Irish origin, having emigrated with James II. A portrait of the Pretender, still in their possession, was a gift from him to their ancestor, who fitted out the vessel which conveyed Charles Edward from Nantes to Scotland in 1745.

The pretty wooded Ile de Béhuard contains a *chapel* of Our Lady, founded on a rock, whose uneven surface forms its floor, and projects upwards in a point 4 or 5 ft. high. It was for ages a place of pilgrimage, and was visited with superstitious veneration by Louis XI., whose faded portrait, a contemporary work in fresco, remains on the wall. Both he and his son lavished on it considerable gifts. By accident it was forgotten at the Revolution, and remains undespoiled, retaining many ex votos, some church plate, &c.

Its walls, still displaying the fleurs-de-lis and other coats of arms with which they were painted, are hung with the chains of Christian captives rescued from Algiers.



Rt. The *Church* of the small town of Savenières (Pop. 2500), opposite the Ile Béhuard, has parts of extreme antiquity. The front and part of the S. wall of the nave, of singularly constructed masonry, consisting of black slate alternating with bands or layers of red tiles, arranged in fern-leaf pattern, intermixed with white tufa stones, are probably as old as the 6th or 7th century. The doorway is more modern. The choir and E. apse, added in the 11th or 12th cent., display on their external walls and around the windows rich Byzantine ornaments and mouldings.

L. The triple rock of Rochefort was anciently crowned by a fortress, of which nothing now remains but a few fragments of wall. It was destroyed by Henri IV., 1598.

Between (l.) the picturesque town of Chalonnnes, surmounted by the square tower of its castle, and (rt.) St. George (at some distance from the Loire, on the high road), the river traverses a small coal field, which has been worked to a considerable extent of late, though it produces only an inferior quality of coal.

At Chalonnnes another suspension-bridge has been thrown over the Loire.

L. The eminence crowned with a modern-looking ruin, through whose numerous windows and roofless walls the sky appears, is Mont Jan; whose name, according to etymologists, has something to do with Janus—though they cannot exactly agree what the connection is. The ruins are those of a convent of Cordeliers: it had been converted into a sort of state prison, of which the monks were the gaolers, when it was burnt during the Vendéan war.

Rt. Champtocé,\* a little village opposite Mont Jan, and situated on the post road, which here again joins the Loire, is surmounted by the imposing

ruins of a feudal castle, celebrated from the crimes of its owner in the reign of Charles VII., the infamous Gilles de Retz, Sieur de Laval, a monster in human shape, the bugbear of the surrounding country, called Barbe Bleu, and the original of our well-known *Blue Beard*; who, although clothed by us in a turban, in reality comes from the banks of the Loire. His history affords a remarkable instance of the superstitions of the 15th cent., and of the impunity for his atrocities which a feudal seigneur enjoyed in that dark age. Having run through an enormous fortune by extravagance, and impaired by excesses his constitution in early youth, the Sieur de Retz sought to renovate both by magic. He kept in his pay an Italian alchemist and magician, who induced him to believe that a charm could be produced from the blood of infants, which would restore him to health and fortune by using it as a bath. For this end children and young persons were spirited away and murdered in the deep dungeons of his castles or in the solitude of his forests, to the number, it was said, of more than 100; he himself, in most cases, plunging the poignard in their breasts. At length the whole country rose up against the tyrant; and his suzerain, Duke Jean V. of Brittany, having heard the charges against him, caused him to be seized and tried: he was found guilty, condemned, and burnt at the stake in Nantes in 1440, after making full confession of his misdeeds. The peasant still regards with horror the ill-omened walls and vaults in which the monster raised the devil, and sold himself to Satan, according to the popular belief.

Rt. Ingrande, a long line of houses raised upon a terraced wall stretching along the strand, is placed exactly on the boundary of ancient Brittany and Anjou, and between the modern departments of Loire Inférieure and Maine-et-Loire. The name was ori-

\* *Post Road* from Angers.  
17 St. George-sur-Loire.  
8 Champtocé.

ginally "Ingressus Andium," the entrance of the country of the Andes, i.e. the Angevine.

Rt. At Montrelais are extensive coal mines, some of the pits extending under the river. The coal is not good enough for the steamers, which burn English coals.

L. The heights of St. Florent are marked by two piles of building; the vast but not picturesque ruins of the Abbey of Montglonne, whose foundation is traced to Charlemagne, burnt down and destroyed by the Republicans in the Vendéan war; and a little below it, the church of St. Florent, surmounted by a modern-looking tower, by the side of which rises a *Pillar* to the memory of the brave Vendéan general Bonchamps, but now surmounted, as if in insult and mockery, by the symbol of revolution, which he died in combatting, the drapeau tricolor. Wounded mortally in the fatal fray of Chollet, he was brought hither by the routed Vendéans to die. He closed his career with an act of mercy in rescuing the lives of 4000 Republican prisoners, who had been taken and shut up in the church, and against whom the irritated Vendéans were already pointing their cannon, worked up to madness by defeat, by the mortal wound of their general, and by terror for their wives and families. The commands and entreaties of the dying hero, and nearly the last words he uttered—"Grâce aux prisonniers"—had the effect of saving them from military execution, when nothing else could have rescued them. Bonchamps expired in a miserable hovel, in the village of Meilleraye, on the opposite side of the Loire, but is interred within the church of St. Florent, and a monument of marble by David is erected to his memory. St. Florent was the scene of the most memorable event in the war of La Vendée, which all who have read Madame La Rochejacquelin's touching *Memoirs* will remember—the passage of the Loire by the Vendéan army

after their rout at Chollet, 1793. They reached the narrow strip of level ground at the base of the semicircle of heights on the l. bank, in number nearly 100,000, half of them unarmed, old men, women and children; the enemy pressing on in the rear, the country behind smoking with the conflagration of their homes by the Republicans, who, to use their own words, "left behind nothing but ashes and piles of dead." The tumult of such a multitude crowding down to the twenty-five small barks which alone could be mustered to ferry them over, the cries of children seeking parents or relations, the groans of the wounded, the alarm caused by the enemy, formed a scene of pain, confusion, and despair, which Madame de La Rochejacquelin compares with the awful spectacle that the world must behold at the Day of Judgment. The whole multitude, however, were transported across in safety before the arrival of the enemy, whose advanced posts reached the river the day after.

The broad expanse of the river is divided by an island, between St. Florent and Rt. Varades,\* the spot where the fugitives, when landed, waited the junction of their companions. It is a town of 4000 inhabitants.

Passing many monotonous clumps and rows of willows, we reach the *suspension-bridge* of wire supported by wire shrouds or stays, erected 1839, of five arches, more than 1300 ft. long, which leads from La Vendée to the little town of

Rt. Ancenis† (*Inn*: H. de France; small, but clean and comfortable—*H. M.*), a town of nearly 4000 inhab., having remains of an old castle of the Ducs de Béthune at the water side, above the bridge, now reduced to a few strong walls and towers. The large barracks are formed out of a ci-devant convent of Ursuline nuns.

Here a broken remnant of the Vendéan host, which had crossed at Varades, endeavoured to recross a few

\* *Post Road*.—13 Varades. † 13 Ancenis.



weeks after, shattered by the recent defeat of Le Mans. La Rochejacquelin, on this occasion, volunteered to cross the river in the only boat which could be found on the l. bank, to bring over some hay barges attached to the opposite shore; but while so engaged he was attacked by the enemy and driven into the woods. A gun-boat of the enemy sunk the barges destined to transport his followers, and thus cut off all communication between them and their general.

L. On the top of a hill covered with brushwood stand the ruins of the castle of Champtoceaux, in which Jean de Montfort was kept a prisoner by Marguerite de Clisson; and at the foot of the hill a bridge or pier of two arches projects into the river, designed by the owner of the fort above to facilitate the levying of toll on the vessels which passed, in feudal times.

Rt. The tall black octagonal tower of Oudon,\* five stories high, surmounted by machicolations, overlooks the flat land and a series of islands which here intersect the river. It was built probably in the 13th cent.

Rt. After passing a group of pseudo-castellated modern constructions, worthy of a tea-garden, and called after their founder, a citizen of Nantes, Les Folies Siffait, we approach the (rt.) *Castle of Clermont*, on the top of an abrupt and lofty escarpment, yet not destitute of foliage, forming one of the most picturesque scenes on the Loire, but unendowed with any historical interest.

Rt. La Seilleraie†, at a little distance from the river, was several times visited by Madame de Sévigné, who dates some of her letters hence, and its gardens were laid out by Le Nôtre. The apartment and portrait of the Sévigné are preserved, and the mansion contains other portraits by Mignard, Le Brun, &c.

Rt. The precipitous heights gradually give place to gentle undu-

lations, which, below the rocks of Mauves, subside into a flat monotonous plain, out of the midst of which, in the distance, the towers of the cathedral of Nantes are seen to rise. Islands and sandbanks greatly multiply in this part of the river, interspersed with dykes of stone heaps to regulate the river, and a few insignificant villages occur at intervals.

NANTES.\* Route 46.

## ROUTE 60.

NANTES TO POITIERS, BY CLISSON.

178 kilom. = 110½ Eng. m.

*Diligence* daily in about 19 hours, and several from Nantes to Clisson.

Our road, before it gets clear of the suburb of Nantes (St. Jacques), is carried over the different branches of the Loire on a series of seven bridges, united by causeways, about 2 m. long, lined with houses. Beyond the last bridge the road to Bordeaux (R. 62) branches off to the rt. About 2 m. S. of Nantes we find the country, though nearly level in surface, covered with vineyards.

13 Tournebride.

The little village *Le Pallet* is celebrated as the birth-place of Abelard; the crumbling briar-grown foundations of a square tower behind the church on the l. of the road are called the remains of the house of his father Beranger.

The stream of the Sèvre Nantaise runs nearly parallel with our road, a little on the rt., as far as Clisson.

A small bridge carrying the road over a valley is stated in an inscription to have been built "l'An 2 du Règne de Napoléon le Grand."

15 *Clisson*.—*Inns*: H. de France, new; Poste, beyond the bridge.

This small town is celebrated for its very romantic situation in the deep narrow bosky valley of the Sèvre, on one side of which towers the stately old *castle*. The scene has a somewhat Italian character. As the town was destroyed in the Vendéan war,

\* 9 Oudon. † La Seilleraie.

\* 14 Nantes.

its houses are mostly modern, and contribute little to the beauty of it. A handsome new *Bridge* of 12 arches, 54 ft. high in the centre, rising on very lofty double piers, now spans the valley, carrying the road to Poitiers across, without descending the very steep slope which leads to and from the river. The perspective of the interior of the bridge from below, through its arched piers, forms a vista like that of a cathedral.

The *Castle of Clisson*, the cradle of that illustrious family from which sprung the famous Olivier de Clisson, the fierce and successful antagonist of the English in the wars of the 14th century, who was thought worthy to succeed Du Guesclin as constable of France, stands on the l. bank of the Sèvre. It is based on the rock, or, where that was wanting to furnish a foundation, huge sustaining walls have been raised from the bottom of the valley, on a line with the escarpment of the rock, to support its towers and bastions. Where not protected by an escarpment, it is surrounded by a fosse. On the l. of the grass-grown court-yard, after entering by the gateway of the Tour des Pèlerins, so called from the crusader Clisson, who built it after his return from Palestine, is a vast pile separated by ditches from the rest, entered by several gates in succession, containing the great hall, the tall donjon, of which one side only remains, and the kitchen, with its wide fire-place. From some of the windows a fine view is obtained over the two valleys of the Maine and Sèvre. All this part of the building is in a state of complete ruin, occasioned by the civil war of La Vendée. Before that broke out the castle belonged to the family of Rohan-Soubise, and had fallen into neglect, but its destruction was completed by the Republican army in 1793. When the town was set on fire, and destroyed by them, a number of its unfortunate inhabitants, chiefly old men, women, and children,

sought refuge within the castle walls, and remained in its gloomy vaults and dungeons, whither they had conveyed some of their cattle also, for a little time unnoticed. But no sooner was their retreat discovered by the army of Kleber, than they were dragged forth from their hiding-place, and hurled *alive* down a deep well in the second court of the castle, now stopped up, and marked by a cypress planted near it. For many hours the feeble and half-stifled cries of these unfortunate creatures were heard issuing from its depths, before they utterly perished. The number thus destroyed is variously stated at 100 and 405; the latter, it is to be feared, is nearest the truth. The story of the well of Clisson is one of the blackest spots on that page of atrocities.

The pretty grounds of *La Garenne*, once highly extolled, perhaps too highly, as "a show place," but now no longer kept up, are indebted for the considerable beauty which they possess to the full stream of the Sèvre, which flows past them, to the fantastic rocks piled one above another rising near its margin, and to the fine trees dipping their branches in its waters, alternating with rich flat meadow-land, which here gives variety to the valley, and to the glimpses of the old castle seen at certain points. Winding walks are carried through the park, decorated at intervals with monuments and statues, a temple of Vesta, a grotto called after Heloise, and a Roman milestone of the age of Antonine found on the road to Poitiers. The Garenne owes its artificial embellishment to the brothers Cacault, who deposited their collection of paintings here, and to M. Lemot, a sculptor; successively its owners, who built the house on the height now deserted.

The *Villa Valentin* is a would-be Italian cascina on a height above the Maine.

On leaving Clisson, you pass on the



top of the hill the little *Chapelle de toute Joie*, so called by a lord of Clisson who received on this spot the joyful news of the birth of a son, and built it in consequence.

The road from Clisson to Poitiers has been made about 15 years, and is part of a network of lines of communication formed to facilitate not only commercial intercourse, but the passage of large bodies of troops; they will contribute more than anything else to alter the primitive state of society in this part of France. Clisson is on the very verge of La Vendée (p.174), which begins on the l. bank of the Sèvre; but our road, running parallel with the river, does not enter it until within a short distance of

14 Torfou, a village almost exclusively composed of new houses, the old having been destroyed in the civil war. One of the greatest victories of the Vendéan peasantry was gained near this over a Republican army superior in numbers by 10,000 men, including the terrible garrison of Mayence,—veterans and reputed the best soldiers in France, and commanded by Kleber. A pillar set up on the post road, about a mile beyond Torfou, at the junction of four highways, marks the scene of the battle, which occurred Sept. 19, 1793. Its four sides bear the names of Charette, D'Elbée, Lescure, and Bonchamps, the four Vendéan leaders who took part in it. The day would have been lost for the cause of the Royalists, soon after the action began, had not Lescure rallied around him 1700 peasants of the village of Echanbrognes, who stood the brunt of the assault for two hours, until the division of Bonchamps came up.

About 3 m. from Torfou in a direct line, and more than 4 by the post road, passing the column (where turn to rt.), is the *Castle of Tiffauges*, an extensive ruin on a high table-land between the l. bank of the Sèvre and a small rivulet (La Crume) falling

into it. The donjon stood on the rocky height overlooking and commanding the gap through which the high road to Les Herbiers is carried. The inner courts, now separated merely by a few foundations of wall, are converted into productive corn fields; but behind two cottages, built in the midst of them, runs a pile of building skirting the brow of the cliff, originally occupied by the seigneur, and more perfect than any other part. The most picturesque bit is a round tower projecting over the rivulet, containing a fine vaulted apartment and a spiral stair, probably of the 16th cent. Round the top runs a covered gallery, resting on the corbels of the machicolations. These chambers now serve as store-rooms for hay, corn, and other farm produce, and the inner wall is prettily draped with vines. By a little postern you may descend into the valley of the Crume. This castle is said to have been one of the residences of the wicked Gilles de Retz, the Bluebeard of the Loire (p. 211); it was dismantled by the Card. Richelieu.

The part of the valley on which the village Tiffauges stands is rocky and somewhat bare of grass. A cotton-mill has been built under the castle. There is no good inn.

Those who take the direct line between Torfou and Tiffauges will have an opportunity of learning what sort of a country La Vendée was before Napoleon and Louis-Philippe intersected it in all directions by broad, open, macadamized high roads. At the distance of a few hundred yards from either village you find yourself in a labyrinth of lanes branching in all directions, worn down by cart wheels or winter torrents, considerably below the surface, lined on either side with trees or hedges which close above your head, and form a covered way like a subterranean passage. So numerous are these deep paths, and so intricate their crossings, that even the inhabitant is apt to be misled by them,

while the frequent stagnant pools, and sloughs of mud, alternating with deep ruts or projecting bosses of bare granite rock, render the passage through them harassing and fatiguing. At the same time, the country is so thickly wooded by thickets and hedgerow trees, which surround every small field, that it is difficult to see your way far before you. It can easily be understood what a complete strong-hold such a district would become when defended by a brave peasantry, fighting close to their own homes, and thoroughly acquainted with all its intricacies. 20 years ago, it must be remembered, only two high roads, properly so called, existed in La Vendée; that from Nantes to Bordeaux, and from Tours to Poitiers, and these were 70 m. apart. The peasantry were all accustomed to the use of the gun; many were old poachers, and capital marksmen. The tactics which they adopted was a species of skirmishing, never attacking the enemy but to advantage, themselves choosing time and place, when and where they found him entangled in the toils. At the word of command from their chief, these rude bands assembled at the place of rendezvous, scattered themselves on the enemy's approach, lining every hedge and copse, from which a murderous fire opened on all sides, the Vendéan marksmen picking out their men, while they themselves were invisible or unassailable.

15 Mortagne (Vendée) on the Sèvre was burnt down, like Torfou, in the Vendéan war, and has been since rebuilt. It was long the headquarters of the Royalist army. At *Chollet*, 8 m. N.E. of this, a manufacturing town of 8897 inhabitants, entirely rebuilt since its destruction in the civil war, two actions were fought in 1793; in the first of which the Vendéans lost one of their bravest leaders, M. Lescure, who was shot through the head, and in the second suffered a more fatal

defeat, which, in fact, decided the war, and drove them across the Loire (see p. 212). Before this battle began, on the 13th of October, 1793, the whole Vendéan army heard mass by torch-light, performed by the curé of this parish. On the first attack, the peasants, who here, for the first time, marched in close column, succeeded in driving back the enemy, and a party, headed by La Rochejacquelin and Stofflet, even captured a park of artillery; but a charge of the Republican cavalry, and an attack from the garrison of Mayence, the so-called "invincibles," turned the scale; the Vendéans were utterly routed, and their best general, the brave and generous Bonchamps, was carried off the field mortally wounded.

At a short distance from Nouaillé, on the road from Chollet to Saumur, a third leader of the Vendéans, Henri La Rochejacquelin, fell, March 4, 1793. For a long time after the wreck of the Royalist cause, he had carried on a successful partisan warfare, issuing out from the fastnesses of the Forest of Vezins at the head of a few determined followers, and spreading dismay among the Republican outposts. He was shot by a grenadier, while in the act of offering him quarter. At his death, the Convention could, for the first time, with safety and truth, proclaim that La Vendée had ceased to exist. An apple-tree is pointed out as marking the spot where he fell.

18 Châtillon-sur-Sèvre, destroyed also, except three houses, in the civil war, is now rebuilt. It was called Mauléon down to 1737.

22 Bressuire, a new town built on the ashes of one ruined by the same disastrous war.

31 Parthenay, a town of 4,024 inhab., though carried by storm by the Republican forces under Westermann, escaped annihilation, and retains some fragments of antiquity, in the ruins of its castle, the gate of St.

*H. des Trois Jillets.*



*Jacques*, and the church of *St. John*, said to be a structure of the 9th century. The town stands on the right bank of the *Thouet*, a tributary of the *Loire*, in a hilly district.

25 Ayron.

25 POITIERS. R. 64.

### ROUTE 62.

NANTES TO BORDEAUX, BY BOURBON VENDÉE, ROCHELLE, ROCHEFORT, AND SAINTES.

345 kilom. = 214 Eng. m.

A *malleposte* daily in 22 hours.

Diligences daily. It is an uninteresting drive.

*Steamers* ply regularly between Nantes and Bordeaux. *N.B.* Some trustworthy person should be consulted as to the efficiency and safety of the boats before embarking.

On quitting Nantes by the six bridges at the extremity of the *Faubourg St. Jacques*, our route turns to the rt. out of that to *Clisson* (p. 213), and crosses, on a handsome new bridge, the *Sèvre Nantaise*, just above its junction with the *Loire*.

21 Aigrefeuille.

A little beyond this the road enters the department of la Vendée, and thenceforth traverses the centre of the district which was the theatre of the terrible civil war of 1792-93.

13 Montaigu, prettily situated on a height above a small stream called the *Maine*, in the midst of the *Bocage* of la Vendée, has fallen from the condition of a town to a village since the war, when two-thirds of its houses were burned, and a large part of its inhabitants massacred. The terrace of the *château*, not now inhabited, commands a good view.

After crossing the *Maine*, a wild open heathy country succeeds, producing furze, broom, and a little barley or buckwheat, as far as

24 Belleville.

13 *Bourbon Vendée* (*Inns*: H. des Voyageurs; H. de l'Europe—both slovenly and comfortless), a new town of right-angled streets and ugly France.

fresh-looking houses, founded by Napoleon in the very centre of the rebellious province la Vendée, and destined by him to be called Napoléon-Vendée, is now the chef-lieu of the Dépt. La Roche-sur-Yonne, an ancient apanage of the Bourbons, occupied nearly the same site, and now, united with it, forms a suburb. It has not quite 5060 inhab. Destitute of commerce or manufactures, in a situation deficient in any advantages required to render a town flourishing, in the midst of a district of barren open heath, it stands about the dullest town in France, and a melancholy example of the folly of establishing a town by word of command. "It is exactly what one might expect it would be from the hasty and arbitrary manner of its creation. A huge oblong 'Place' forms the centre and principal part of it. From the sides and corners of this 8 or 10 streets branch off at right angles. The buildings which compose this square are almost all public edifices, each looking more mesquin and meagre than the other, and all having the appearance of being stretched out at the least possible expense to the greatest possible extent of front, for the purpose of making them go as far as possible towards the composition of the proposed town. A *theatre*, on the steps of whose portico the grass was growing, forms part of one side. A huge *Hôtel de Ville*, which seems deserted and shut up, stands opposite to a great barn of a church. A *préfecture*, a court-house, a *mairie*, and enormous barracks, surrounding a court in which a dozen regiments might manœuvre at once, occupy the most of the remaining space. The barracks have been constructed so much in haste and with so little solidity that they are already beginning to fall to ruins—new ruins, the most unsightly spectacle. They are deserted and apparently abandoned to their fate." —*Trollope, W. France.*

Conveyances go from this to Nantes, Bordeaux, Saumur, and Les Sables.

About 4 m. to the W. (2 of them not fit for carriages, but only for the pedestrian) are the ruins of the *Abbey of Fontanelles*; a Gothic chapel remains in excellent preservation.

Les Sables, 20 m. W. of Bourbon Vendée, on the sea, is a town of some interest, curiously placed on a narrow sand-ledge, at the margin of a bay forming a large and beautiful crescent. The sands are smooth and extensive. A fleet of 70 fishing vessels may be seen at times entering the roads in one hour, sweeping from the wide sea into a deep narrow channel between two piers, and so entering the large harbour at the back of the town. There are two peculiarities in the female costume here, a small bell-shaped laced cap, and an enormous blue hood of cloth-shreds or wool, giving to their upper figures the shape of a huge beehive.—*Inn*: H. de France, fair accommodation and civil people.—*F. T.*

The same dreary, unenclosed, and heath-clad land extends to

22 Mareuil, beyond which a fine corn country commences.

Between Les Sables and Luçon (25 m.) is the Castle of Talmont, a lofty picturesque feudal ruin.

10 Luçon, a dull and dirty small town, in a situation which is unhealthy, on account of its vicinity to the marshes, connected with the sea by a canal, and having a population of about 3000. Luçon was the episcopal see of the Cardinal de Richelieu, having been a sort of family living, into which he, though bred up for a soldier, was inducted at the age of 22. Its Gothic *cathedral*, surmounted by a tall spire of open-work, is the principal building.

10 Moreilles. Our route now lies across a district which may be called the Fens of France, a series of marshy flats, traversed by numerous rivers, the chief of which are the Vendée and Sèvre Niortaise: it is intersected also in all directions by canals, and, notwithstanding the drainage effected

by them, is unhealthy from malaria. A solitary conical mound rising out of the flat on the l. of the road is crowned by the village of Chaillé. The limits of la Vendée and the stream of the Sèvre Niortaise are crossed shortly before reaching

17 Marans, a town of 4000 inhab., 9 m. from the sea, exports corn from la Vendée and flour from Niort.

Before half the next stage is traversed the road crosses the canal from la Rochelle to Niort. Near this the marshes of la Vendée terminate, and the marly lands of the Aunis begin. At

15 Grolaud the canal is crossed.

A picturesque group of towers and spires, visible from a considerable distance, announces the approach to

9 *La Rochelle*.—*Inns*: Poste, very good; H. de France. This third-rate fortress, and commercial town of secondary importance, is situated on the sea, on the shore of a bay in front of which rise the Iles de Ré and d'Oléron. It was capital of the district of Aunis, and is now chef-lieu of the Dépt. de la Charente. Before its memorable siege of 1628 it had a population of 27,000; at present it contains no more than 14,857.

Its little *port* is entirely enclosed by the buildings of the town, and consists of an outer tidal basin, and an inner wet dock, protected by a pier, and flanked at its entrance on either side by the round towers of la Chaîne and St. Nicholas, built 1418 out of the remains of the castle. A quay, planted with trees, runs round the harbour, and forms an agreeable promenade.

Its chief commerce consists in the exportation of the brandy made in the adjoining province of l'Aunis, the finest in France, of wine, corn, and flour.

At low-water, the remains of the famous *dyke* thrown out into the sea by order of Richelieu during the siege of 1628-29, and which contributed mainly to the surrender of the town, by interrupting all supplies and suc-



cour from England, are distinctly visible. This long pile of stones, stretching for a distance of 1640 yds. from the point of Coreille to that of Fort Louis, was built by the engineer Metezeau.

In the *Hôtel de Ville*, a handsome building in the style of the Renaissance, of the time of Francis I., is shown the chamber in which the heroic Guiton accepted the office of mayor on the very eve of the siege, "on condition," said he, "that I be allowed to plunge into the heart of any one who speaks of surrender, the dagger which I hold in my hand, which I insist shall be placed on the table of the council-chamber where we meet, to be used against myself first, should I be weak enough to propose a capitulation." Influenced by so obstinate a spirit of resistance, the citizens held out for 14 long months against the vast force brought against them, commanded by Cardinal Richelieu in person, and supported by the presence of Louis XIII. At length, when famine, which followed the vigilant blockade established on the land side, by throwing up lines 3 miles long, and by the dyke before mentioned drawn across the harbour, had reduced the numbers of the besieged from 27,000 to 5000, la Rochelle, the bulwark of the Protestant cause in France, which had remained in the hands of the Huguenots since the first unsuccessful siege of 1573, was yielded up to the king, and its fortifications levelled, except the two towers at the mouth of the harbour. The ill success of the two expeditions fitted out by Charles I., whose favourite, Buckingham, contributed to the failure of the first by his incompetence, and who was assassinated by Felton while about to assume the command of the second, prepared the way for its fall. The town never regained its previous prosperity, though Protestants are still numerous here. By its capture, Richelieu destroyed the political influence of the Calvinists in France. The chair of Guiton,

and the council-table of marble, are still preserved in the H. de Ville. His house, at the Rue Guiton, is also pointed out—a building in the style of the Renaissance, flanked with tourelles. Six or eight of the old town gates remain, and the Tour de la Lanterne, a conspicuous structure, surmounted by a spire, dates from 1445.

The Gothic *Porte de l'Horloge*, whose architecture announces it to be a work of the 16th century, is another relic of the time of the *siege*, and there are some old houses still standing, which must also have existed at that memorable event, when streets and houses were rendered infected by the dead bodies too numerous for the living to bury. Such was the extreme misery to which the inhabitants were reduced, that one of them declared that for a whole week he had kept his child alive solely by blood drawn from his own body. One of the articles of capitulation was, that the invincible Guiton should continue in the office of mayor, retaining all his dignities: he is lost sight of, however, after the siege.

The town was again fortified by Vauban in the reign of Louis XIV. The tower of the church of *St. Sauveur*, the loftiest in the place, now used as a shot tower, commands from its top a view embracing the Iles de Ré, whose town, St. Martin, resisted all the efforts of the English under Buckingham to capture it, 1628; and of *Oléron*, a long low bank of land separated from Ré by a strait called Pertuis d'Antioche. Still nearer, not 2 m. off the shore, is the Ile d'Aix, opposite the mouth of the Charente: the fort and batteries upon it, defending the entrance of the roads, were captured by the English, 1757, but have been greatly strengthened since that time. An attempt was also made, 1809, by the English, to destroy the French fleet here by fire ships, and was partly successful, as, out of 14 vessels, 4 ran ashore and were burnt, and 2 were captured.

Some years ago, a singular plague of white ants (*Termites*), originally imported from India, infested the wooden buildings of La Rochelle.

There is an *Etablissement des Bains* here, situated on a fine Promenade or Mail, a grove of trees stretching along the shore; nice gardens are attached. Much salt is made near the town, by evaporating the sea water.

A steamer plies daily between La Rochelle and l'Ile de Ré.

Rochelle is the birth-place of Réaumur, inventor of the thermometric scale named after him, and of Billaud Varennes, member of the National Convention.

*Coaches* to Paris by Poitiers daily; —5 times a day to Roche fort.

An uninteresting tract of flat marshy land intervenes between Rochelle and Roche fort. Near the village of Passage stood an ancient town, Châtelailon, which preceded La Rochelle, and has long since disappeared, owing to encroachments of the sea.

14 Trois Canons.

17 Roche fort (*Inns*: H. des Etrangers; H. Grand Bacha), a fortress of 4th rank, but standing third in importance among the naval arsenals of France, is built on the rt. bank of the Charente, about 10 m. from its junction with the sea, and contains 15,911 inhab. The river is deep enough to float vessels of the largest size abreast of the town, having 20 ft. water at ebb, and 40 ft. at the highest tides, and five forts at its mouth protect the dockyard from hostile approach. Its position is well chosen, owing to its vicinity to the roadstead formed at the embouchure of the Charente, by the protection of the islands of Ré, Oléron, and Aix. In order further to defend the roadstead, a fort is being constructed at their mouth, on a sandbank called the Boyard, between the Ile d'Aix and Ile d'Oléron; and a million of francs was voted for the purpose, 1840. Roche fort is quite a modern town, founded in

1664 for the establishment of a dockyard by Louis XIV., or rather by his wise minister, Colbert, who saw the necessity for a second port and arsenal on the ocean besides Brest. Its streets are built at right angles, and the only buildings of consequence are those connected with the *Port Militaire*, or *Dockyard*. Admission is given by the Major de la Marine, on application of the British consul, and on exhibition of the passport. Among the vessels on the stocks are several large war steamers: the model room contains some curiosities. To describe the sailmakers' shops, the cable-twisting loft, the workshops whose machinery is set in motion by a steam-engine, would be nearly to repeat what has been said of Brest and Cherbourg (pp. 125 and 85). The only novelty to an Englishman, acquainted with the British dockyards, will be the *Bagne*, or convict prison, capable of containing 2200 forçats, but occupied by only half that number.

The largest and most remarkable edifice here is the *Hôpital de la Marine*, outside the town, consisting of nine separate masses of building, containing 1,200 beds. It is excellently arranged and well kept up, cleanly in the extreme. There is a tolerable anatomical museum attached to it.

The town was originally very unhealthy, owing to its low situation among the marshes; but these have been drained, and fevers are become rare. In the Grande Place is a *fountain* adorned with figures, representing Old Ocean shaking hands with the Charente!

In 1809 Lord Cochrane penetrated into the *Basque Roads*, between the Ile de Ré and the Ile d'Oléron, with a small squadron, and burnt 5 vessels of the French fleet destined for the W. Indies, he himself steering the leading fire-ship, charged with 1500 barrels of powder and 400 shells, through the concentrated fire of 1000 guns!



On the 3rd July, 1815, Napoleon arrived at Rochefort, seeking to escape to America, and lodged at the préfecture ; but finding that the *Bellerophon*, an English line-of-battle ship, was at anchor in the Rade des Basques, and that there were no possible means of evading it, he went on board on the 15th, and sailed for England, after in vain attempting to obtain a pledge from Captain Maitland for safe conduct.

A *Steamer* runs 4 or 5 times a-week from Royan, a small port on the N. bank of the Gironde, 29 m. from Rochefort, to Bordeaux: the voyage takes 7 hours. Coaches convey passengers between Rochefort and Royan, fare 4 fr. 25 c., and total to Bordeaux 8 fr. In going to Royan (a small watering place opposite the lighthouse of the Tour de Cordouan [R. 69]), the Charente is crossed by a ferry. The road traverses an uninteresting flat, only redeemed by drainage from the state of a pestilential marsh, called Les Marennes.

A *Steamer* ascends the Charente to Saintes (35 m.) every morning, returning in the afternoon: the passage takes 4 hours.

The voyage up the Charente is agreeable though somewhat monotonous, from the windings of the river and the unvaried nature of the green flat pasture lands on its banks. Near to Saintes it passes the ruined *Castle of Taillebourg*, on an isolated rock, near which St. Louis defeated the English in 1242.

Those who travel by land from Rochefort to Bordeaux cross the Charente by a magnificent new suspension bridge, in the place of the old ferry, close under the town of Tonnay-Charente, which Louis XIV. had fixed upon for the site of his dockyard, a design which was defeated by the enormous demands of its owners for the purchase of the ground. The Gothic *Castle*, having a park and gardens attached to it, is the ancient seat of the family of Mortemart. A great quantity of brandy is exported from

hence, almost all the vineyards on the banks of the Charente being cultivated for the manufacture of eau-de-vie (see p. 222): 6,000 casks, a large part of the produce of Cognac, is annually shipped here for England.

11 St. Hypolite.

13 St. Porchaire.

On the l. bank of the Charente stands

14 *Saintes* (*Inns*: H. du Bateau à Vapeur; best and very good), formerly capital of the province Saintonge, betrays in its name the antiquity of its origin, as chief city of the *Santonnes*, and has many traces to prove its importance under Roman rule.

The principal and best preserved ancient monument is, the *Roman arch of Triumph*, upon the bridge over the Charente, serving for a principal entrance into the town, constructed of a coarse limestone, originally very plain, and now, after the lapse of ages, much injured by the weather, which has rounded the angles of the stone, and converted the joints of the masonry into gaps. It is a heavy pile of masonry, pierced by two arches, and destitute of all architectural beauty, 38 ft. high. Five inscriptions upon it, now half-effaced, record that it was raised (in the reign of Nero) to the memory of Germanicus, of Tiberius his uncle, and of Drusus his father, by Caius Julius Rufus, priest of Roma and Augustus. It was saved from destruction in 1665 by Blondel the architect, who at that time rebuilt the bridge, and it was repaired in 1844, when the arch was pulled down, but the separate stones were marked for re-erection. It is said to have been built originally on dry land, and that the river has since altered its bed, and isolated the arch; but this seems doubtful.

There are also considerable remains of a *Roman Amphitheatre*, near the church of St. Eutrope, in the faubourg. Though nearly equal in size

to the grand circus of Nîmes, it is very inferior in an architectural point of view, being built of small stones squared, and destitute of ornament, and it is now reduced to a few fractured vaults and arches. The oval of the arena measures 70 ft. in its greatest length, and 57 ft. in width. The dens destined for the wild beasts still remain, and there are fragments of an aqueduct, contrived, it is supposed, to convert the arena into a naumachia for aquatic spectacles. (?) Many antique fragments, capitals, inscriptions, sarcophagi, &c. are preserved in the garden of the sous-préfecture. Such are the few traces of the former magnificence of the ancient *Mediolanum Santonum*, one of the most important cities of Aquitaine.

The *Ch. of St. Eutrope* is a structure of the 11th cent.: its huge crypt, the most curious part of it, ~~is probably still older~~; some of the capitals of columns have quaint carvings. The spire was built in the 15th cent.

The detached tower of the *Cathedral*, conspicuous from the pinnacles which surmount it, occupies the site of the church built by Charlemagne in fulfilment of the vow of his father Pepin, after defeating on this spot Gaiffre Duc of Aquitaine. The port-tall is ancient.

The public *Library* contains Fénelon's Bible, with notes in his own hand.

The population of Saintes amounts to 11,000. The Charente is here a tidal river, but navigable only for barges. Much eau-de-vie is sent down to the sea for exportation. About 18 m. to the E. higher up the river, on the road to Angoulême, is the town of *Cognac* (*Inn*: H. d'Orléans, poor outside, but very comfortable), which gives its name to the best brandy in France, produced from vineyards in its vicinity, and along the banks of the river near Jarnac and Angoulême (R. 64), in the department of La Charente. The quantity produced annually does not exceed

6,000 butts (tierçons), but the number sold under the name "les fines Champagnes," by which the best quality is distinguished, exceeds 15,000 butts. Cognac contains numerous distilleries, and is the staple place for the brandy produced in the surrounding districts. The vines cultivated for its manufacture are allowed to grow to greater luxuriance than those used for wine-making, and run along the ground, whence they acquire strength, while the earthy flavour which is inseparable from wine produced from creeping vines is dissipated in the process of distillation.

Francis I. was born at Cognac, while his mother Louise de Savoie, Duchesse d'Angoulême, was residing in the castle; but, according to tradition, he first saw the light under an elm-tree, where his mother was unexpectedly brought to bed. A stone now marks the spot.

A Diligence runs from Saintes to Mortagne on the Garonne, to meet the steamer to Bordeaux.

The road from Saintes to Bordeaux is carried through

12 La Jard.

9 Pons, a town of 4000 inhab., picturesquely seated on the l. bank of the Seugne. Its castle, distinguished by a keep-tower 100 ft. high, built in the 11th century, is now a prison. Théodore Agrippa d'Aubigné, grandfather of Madame de Maintenon, and a favourite of Henri IV., was a native of Pons.

11 St. Genis.

12 Mirambeau.

17 Etauliers, Dépt. de la Gironde.

The road reaches the banks of the Gironde at

13 Blaye, described in Route 69.

Steamers ply daily between Blaye and Bordeaux.

15 Graviers. There is a direct road from Etauliers to Graviers, avoiding the détour by Blaye round two sides of a triangle; but not long since this road was impracticable for carriages for want of repair.



14 Cubsac is on the high road from Paris to Bordeaux. (R. 64.)

10 Carbon Blanc. }  
11 BORDEAUX. } Route 64.

#### ROUTE 64.

TOURS TO BORDEAUX BY POITIERS AND ANGOULÊME.

328 kilom. = 203 Eng. m.

The *Malleposte* daily in 22 hours.

3 or 4 *Diligences* daily, besides coaches between intermediate towns.

The posting on this road is good—from Tours to Poitiers may be done in 8 hours. A Railway is begun.

A somewhat monotonous avenue,  $2\frac{1}{2}$  m. long, leads out of Tours across the Cher, and the rich green pastures bordering on it. At the end of the vista stands the *Château de Grammont*, once belonging to the Archbp. of Tours. Its gate and one window, through a gap in a tree, command the whole breadth of the valley. At this point the road bends to the rt., ascending a height which limits, on this side, the vale of the Loire and Cher, and commands an extensive view across it. A little beyond this the road to Loches (R. 56) turns off on the l.

13 Montbazon, a small town, with a *castle* on a rock. Here the Indre is crossed. A little beyond

7 Sorigny you pass on the l. the Chapel of St. Catherine de Fierbois, whither Joan of Arc sent from Chinon to fetch the sacred sword, "marked with 5 crosses, lying in a vault," which she afterwards bore in all her battles. She had previously passed through the village, however, on her journey from Lorraine to Chinon, and had doubtless then remarked the weapon; but the vulgar belief attributed its discovery to divine inspiration.

14 St. Maure: here a road to Chinon branches off. (See p. 203.)

The river Creuse is crossed at Port-de-Piles, about  $\frac{1}{2}$  m. above its junction with the Vienne. Higher up, on the rt. bank of the Creuse, and 3 m. to the l. of our road, is the

village of La Haye, the birthplace of the philosopher Descartes. The house in which he was born (1596) is preserved.

About 7 m. S. of La Haye, also on the Creuse, is the *Château de Guerche*, built by Charles VII. for Agnes Sorel, his mistress, where she resided when the king was at Loches, and where he used to visit her on his way to and from the chase in the neighbouring forest. It is a massy pile, rising 100 ft. above the water side, flanked by 4 towers at the angles. It retains in its interior some traces of fresco painting, and the punning initials of his mistress's name, an A over L (*A-Sur-Elle*). In the chapel is placed a statue of Agnes.

16 Les Ormes, on the Vienne.—The château belongs to the family d'Argenson.

The road runs parallel with the Vienne, though not in sight of it, through Dangé, and

12 Ingrande.

7 Châtellerault (*Inn*: H. de l'Espérance, good), a smoky town of mean houses, on the rt. bank of the Vienne, is one of the chief seats of the *Manufacture of Cutlery* in France, which gives employment to about 600 families, out of its 9437 inhab., who work for large houses. There is also a royal manufactory of swords and bayonets (*armes blanches*), established 1820. No sooner does the traveller's carriage stop here than he is assailed by a host of women plaguing him to purchase knives, scissors, &c., mounting upon chairs to force them in at the window.

The Duchy of Châtellerault was bestowed by Henri II. upon James Hamilton, 2nd Earl of Arran, Regent of Scotland, 1548, to induce him to consent to the projected match between his ward, the infant Queen Mary, and the Dauphin Francis. The duchy was forfeited to the crown, and has never been restored.

On quitting the town, the Vienne (which is navigable for a short distance higher up) is crossed; and a

portion of a gateway flanked by turrets, erected by the Duc de Sully, is passed at its extremity.

8 Barres de Nintré.

5 La Tricherie.

8 Clain. For the last 3 stages the road has continued to ascend the valley of the Clain. That stream traverses a rocky and wooded ravine, of much picturesque beauty, before arriving at

12 POITIERS.—*Inns*: H. de France;—best and comfortable; bed 2 fr., dinner 3 fr., tea 1 fr., coffee 15 sous;—Trois Piliers.

Poitiers, the capital of ancient Poitou, an early possession of the kings of England, who were its dukes down to the time of Charles V. (1371), stands on a rounded eminence of considerable height, the summit of which is occupied by the Préfecture and Palais de Justice. From this its streets sweep down in steep slopes, or curve, in winding mazes, to the small river Clain, which encompasses nearly  $\frac{3}{4}$  of its circuit, while the smaller river Boivre encircles another part, so that they formed, in ancient times, a sort of natural fosse round its ramparts, now almost entirely swept away by town-council improvements. The number of inhabitants is 23,128, but it has neither commerce nor manufacture of any great importance, as might indeed be surmised from its dull and empty streets, excepting the market-place, which is a scene of much bustle and densely crowded.

It has an *Ecole de Droit*, numbering between 200 and 300 students, but of greater celebrity in former times than at present. Lord Bacon in his youth studied here. The town still contains more than a dozen *nunneries*, chiefly serving as boarding schools for the education of young females.

The curiosities of Poitiers are chiefly of an antiquarian nature. It possesses a remarkably large number of churches, all more or less interesting to the lover of architecture and

antiquity,—and, as some of them date from a very early period, and others were commenced later, and continued down to comparatively modern times, they form a very instructive series by which to study the progress and change of style in building.

*Notre Dame de Poitiers*, in the market-place, nearly opposite the *Ecole de Droit*, presents a remarkable example of the florid Romanesque style in its W. façade, which is nearly covered with sculpture from top to bottom. It rests on a triple arcade; the central arch forming the entrance being circular, the two side arches pointed, but all decorated with mouldings and capitals of the same character of richness and singularity. The rest of the façade, on each side of a tall window, is occupied by arcades filled with statues and bas-reliefs; and the usual pointed oval frame (*vesica piscis*) within the gable contains 2 statues. The whole is flanked by 2 round turrets. The probable date of this façade is the middle of the 12th century.

The interior is of a more severe style: it has an apsidal E. end, with circular arches and hooped vaulting, except the side chapels, one of which, in the S. aisle, an addition in the florid style of the 15th cent., contains a rich recess to include a somewhat grotesque group of sculpture meant to represent the Entombment.

The *Salle des Pas Perdus*, attached to the *Palais de Justice*, which originally formed part of the palace of the Comtes de Poitou, is a vast hall, with an open wooden roof; its walls are decorated with arcades, circular on one side and pointed on the other, yet both perhaps nearly of the same date, the 12th cent. The front, recently thrown open, is said to have been built by Comte Jean de Berry.

The *Cathedral*, dedicated to St. Peter, is said to have been founded by Henry II. of England. The 2 towers, similar in style, but unequal in size,—the semicircular N. doorway,



in which the capitals of the pillars are human figures, stiff, but good in style,—and a large part of the body of the building, whose round and pointed arches are intermixed, as in the Salle de Justice,—may possibly be of Henry's time.

The plan of the building is a parallelogram, divided into 3 aisles, the central one being much the widest. It terminates a little way above the arches, without either triforium or clerestory; the latter being transferred, as it were, to the side walls, where it appears in the form of a range of windows; one large pointed window, or 2 narrow round-headed ones, filling each compartment. The E. end is square, and has 3 covered recesses, in the thickness of the wall, to contain altars. The piers, composed of 4 engaged shafts, surmounted by sharply-cut capitals, are very elegant. There are several painted windows, and a fine rose at the W. end, hid, internally, by the organ. Very solid buttresses support the walls and roof.

A little way behind the E. end of the cathedral stands the *Ch. of St. Radegonde*; the lower part of whose elegant Byzantine tower, though masked by a florid porch, is probably of the 11th cent., as well as the white marble *bénitier*, shaped like a horse trough, within it. Above it is a curious niche, containing the statue of a saint. The Romanesque choir is raised upon a very old *crypt*, perhaps older than any part of the upper structure, partly cut out of the rock. In this is deposited the black marble Coffin of St. Radegonde, resorted to, in the month of August, by thousands of pilgrims, chiefly of the lower orders, who throng the low vault to kiss the worn marble Sarcophagus (on which some curious ornaments of an early age may be discerned), and to bring their sick children to be cured. The saint's empty coffin, it appears, still retains the virtue of healing possessed by her body, before it was burnt by the

ruthless Huguenots in 1562. In the S. wall of the nave is a small chapel, fenced with iron bars, called "*Le Pas de Dieu*," because it contains the stone impressed by the footmark of our Saviour, who here appeared to St. Radegonde, according to the legend! It is covered over by an iron case to protect it. Part of the internal decorations of this church are, like the porch, of the 15th cent., and some of the sculpture is by no means appropriate to a church.

The building, called the *Temple de St. Jean*, now converted into a *Musée*, and previously a church, is, next to the Roman Circus, the oldest edifice in Poitiers, and one of the oldest Christian monuments in France; on which account, as well as from the style of its architecture, it deserves particular attention from those who take an interest in antiquities.

It is an oblong building, measuring about 40 ft. by 25, its greatest length being from E. to W., and its walls on these sides terminating in obtuse gables. The masonry is very neat; and on 3 of the walls, inside as well as out, a sort of arcade is introduced, consisting of a circular arch, flanked and surmounted by small triangles, resembling pediments. These triangular ornaments are similar to those in the old church of Lorsch, on the Rhine, and may remind the architect of the flat-sided arches occurring in the churches of Barton-on-the-Humber, and elsewhere in England. This debased style of building, arising from want of skill in the architects, and of funds in the founders, followed the Roman, at the fall of the Empire, and preceded the Romanesque, and it is probable, therefore, that the Temple de St. Jean dates from the 6th or 7th century. Its destination appears to have been that of a *Baptistery*, judging from the well in the centre of its floor, about 8 feet deep, having a pipe running obliquely into it.

This supposition,—taking into consideration the coincidence in style

with the church at Lorsch, a building supposed to be of the 8th centy., appears more probable than that which would make it a Roman tomb, merely because a Roman monumental inscription was found within it. The style of construction is decidedly post-Roman.

To convert it into a church, a semicircular apse was thrown out from the E. wall, and a sort of porch was raised before the W. The style of building in these alterations denotes a date probably not later than the 10th century; and the curious frescoes, still visible on the inner walls, are perhaps nearly as old. The bull's-eye windows by which it is lighted were originally round-headed windows, the lower part of which has been bricked up. This edifice was condemned, a few years ago, by the municipal authorities, to be pulled down, because it stood in the way of the road to Limoges. Luckily there were found in Poitiers some admirers of ancient art to save it from destruction.

The *antiquities* deposited within consist chiefly of broken fragments of Roman sculpture and architecture; a mile-stone of the age of Alexander Severus, and some inscriptions; also a curious Byzantine bas-relief representing St. Hilarius.

The following churches deserve the notice of the antiquary and architect, in addition to those already mentioned. *St. Hilaire*, finished 1049, has lost a portion of its nave. The apsidal choir rests on 7 lofty columnar piers. The Church of *Moutiersneuf* is also Romanesque, but has been much restored since the Revolution. *St. Porchaire* has a curious portal with bas-reliefs.

The Romans have left traces of their settlement here, on the site of Gaulic *Limonum*, a city of the *Pictavi*, in the remains of an *Amphitheatre*, which is best approached through the Inn called Hôtel d'Evreux. At the back of the stable-yard is a tolerably perfect wedge-shaped vault, now

filled with hay; and leading to it, a part of the vaulted corridor which ran round the building on the ground floor. The oval interior of the Circus is now converted into the inn garden, and some houses have been built upon the sloping constructions around it, which formerly supported the rows of benches. There is no doubt that other vaults and corridors remain under them. The hardness and regularity of the masonry, in the portions of the wall exposed to view, are such as characterise all Roman constructions.

The town of Poitiers is surrounded by narrow valleys or ravines, on all sides but the S.W., where a neck of land connects it with the high ridge whose extremity it occupies. In ancient times the town was defended on this side by strong walls and a deep ditch dug across the isthmus. The space immediately within these walls is now converted into a *Promenade*, called de Blossac, from an intendant of the province in the last century. It would be a very agreeable walk were it only kept clean, for the terraces, resting on the foundations of the old walls, command a pleasing view into the deep valley of the Clain below.

The *Bains du Belvédère*, not far from this walk, are comfortable, and the charge moderate.

From the heights on the rt. bank of the Clain there is a very good view of the picturesque town of Poitiers, but no path runs along them. The writer of this took an agreeable but scrambling walk, issuing out of Poitiers by the Paris gate, crossing the bridge over the Clain, then ascending through vineyards behind the Faubourg, and keeping along the edge of the cliff as far as the road to Limoges, where he recrossed the Clain by another bridge, at the back of St. Radegonde.

About 1½ m. out of the town, a little to the l. of the road to Limoges, on a height, is a *Dolmen*, or Druidic monument, called *Pierre Levée*. It



is a block of calcareous sandstone, about 13 ft. long and 3 thick, resting at one end upon upright stones, but at the other deprived of its support. Rabelais attributes its erection to Pantagruel, "pour le divertissement des escoliers de l'Université."

At about an equal distance from the town, in another direction, a little to the l. of the road to Angoulême, are remains of a *Roman Aqueduct*, which supplied water to the town and circus. 4 or 5 of its arches are still tolerably perfect, but they are neither imposing nor very ornamental.

Poitiers is historically very celebrated. The invading tide of the Saracenic hordes penetrated in the 8th century thus far into W. Europe, at a moment when the fate of Christianity seemed trembling in the scale. At that epoch, having already conquered Spain, they poured through the defiles of the Pyrenees, overspread Aquitaine, advanced up to the walls of Poitiers, under their famed chief Abdelrahmen, and burned the Church of St. Hilaire to the ground. They were even threatening to pass the Loire, when they were met, somewhere between Poitiers and Tours, by Charles Martel, in 732. This contest between the East and the West, between the Gospel and the Koran, ended in the defeat of the Saracens, 300,000 of whom, it is said, but on the doubtful authority of a single chronicler, were left dead on the field; and the remnant retired, never more to trouble Christendom in the West. The site of the battle-field has never been exactly ascertained, and no discovery of bones has been made, which would surely mark the scene of so enormous a slaughter. At an earlier period (507) the plains of Poitiers had been the scene of the defeat of Alaric, king of the Visigoths, by Clovis.

Poitiers is distinguished in English history by the signal victory gained under its walls, in 1356, by the army of the Black Prince, consisting of

English and Gascons, who early in that year had invaded the S. of France, and spread desolation through Languedoc, Limousin, and Auvergne, as far as the gates of Bourges in Berry. The prince's whole force did not exceed 12,000 or 14,000 men, and the expedition had no other design than that of a foray, to "harry" the fair fields of France. On his way back to Bordeaux, however, suddenly and unexpectedly, on the 9th September, he encountered the army of John, king of France, amounting to 60,000 men, of whose vicinity, and even of their march to meet him, he had been entirely ignorant.

"God help us," said the prince, "we must now consider how we can best fight them." The Pope's Legate, Cardinal Talleyrand, assuming the office of peacemaker, in vain endeavoured to prevent the impending strife and bloodshed; even Edward himself offered to acquiesce in any reasonable terms, consistent with his honour, to be permitted to go free. He offered to give up all the towns and castles he had taken, together with the prisoners, and not to bear arms against the French king for the space of 7 years. The French, however, confident in numbers, would listen to no conditions but the surrender of the Black Prince and 100 of his principal knights. The result is well known. The English owed the success of the day, under Providence, to their well-chosen position, to the deadly and skilfully aimed arrows of their yeomen, which availed more than the lances of their knights, and to the stout hearts of their leaders, the Black Prince and Lord Chandos, and of all the English under them.

On that fatal day France beheld the flower of her chivalry laid low, while her king, John, was led into captivity. The noble dead were buried by the towns-folk in the churches of the Cordeliers and Jacobins within the town. The field of battle, fixed by Froissart on a spot

which he calls Maupertuis, a name now lost in the country, is proved, by old records, in which it is frequently mentioned, to have been situated between the commandery of Beauvoir and the Abbey of Nouaillé, near the road to La Rochelle.

*Conveyances.*—Daily to Bordeaux and Tours, by Angoulême; to Limoges; to Rochefort (R. 62); to Nantes (R. 60).

The road from Poitiers to Angoulême possesses little interest. Shortly after quitting Poitiers, by the neck of land bounded by the Clain valley on the l., it passes on the l. the road leading to the Roman Aqueduct (p. 227), and at a short distance on the rt. that to Saintes and Rochefort (R. 62).

7 Croutelle.

12 Vivonne.

8 Minières.

8 Couhé.

11 Chaunai.

8 Maisons Blanches. *Civray*, 2 leagues E. of this, contains a Romanesque church, whose façade is curiously ornamented with sculptures, including signs of the zodiac, somewhat like Notre Dame at Poitiers, but dating probably from the early part of the 12th century. At Charroux, 8 m. farther off, are remains of an Abbey, now reduced to a tower about 80 ft. high, rising from 2 circular arcades, one above the other, supported by piers, formed of bundles of shafts. This was originally the central tower of a very curious church, consisting of a circular choir, preceded by a rectangular nave: but all the rest is destroyed. The abbey was founded by Charlemagne, but these ruins are not older than the 11th or 12th century.

12 Ruffec.—*Inns*: H. des Ambassadeurs, a capital dining house; the pâtés de perdrix aux truffes unrivalled.—*Ld. B.* Poste, good.

6 Les Nègres. At

11 Mansle the river Charente is crossed.

14 Churet.

The towers of the cathedral and

castle of Angoulême are espied 10 m. off. The cultivation of the vine now becomes general. The wines produced about Angoulême and along the borders of the Charente are of inferior quality, but fit for converting into brandy. The picturesque and broad valley of the Touvres is entered, and that stream is crossed at Pontoux.

A few miles up this stream is the Royal cannon foundry of Ruelle: charcoal is exclusively employed as the fuel for the smelting furnaces, and is abundantly supplied by the neighbouring forests.

Farther on, in the same direction, is La Rochefoucauld, whose castle was the ancient residence of the family of that name, its most noted scion being François, author of the celebrated "Maximes." It escaped destruction at the Revolution, and still belongs to the same family, though no longer inhabited by them. It is a huge pile, flanked by round, cone-roofed towers at the angles, forming 3 sides of a square, and, with the exception of the antique donjon, was erected, 1527, by Antoine Fontan, in the style of the Renaissance. A range of arcades serves as a passage along the inner façade, and a curious and richly ornamented spiral stone staircase leads to the upper stories. Below the castle are very extensive Caves, not now entered, which served as a refuge to the Huguenots, in the wars of Religion. There are similar natural caverns all along the valley of the Tardonère, the largest of which, Les Grottes de Rancogne, are about 3 miles above La Rochefoucauld. They are traversed by a streamlet, and contain some stalactites.

The approach to Angoulême lies through the long suburb de l'Houmeau (in which is the Poste aux Chevaux), and it is not necessary to enter the town at all, in proceeding to Bordeaux, unless you intend to stop here, but the inns are in the upper town. A very steep ascent leads from l'Houmeau into

11 *Angoulême.*—*Inns*: La Poste,



good; the landlord's pâtés of foies de canards, famous; the cuisine excellent:—H. des Etrangers, diligence-house. *A H. du Croix d'or*

Angoulême, the ancient capital of the Angoumois, now of the Dépt. de la Charente, occupies a situation, not unlike that of Poitiers, on the top of a high hill, terraced round with remains of the ancient ramparts above, while below it is nearly encircled by the course of the Charente, and by another small stream falling into it. The town is distinguished by far more life, industry, and trade than Poitiers, and possesses, with its suburbs, a population of 17,000 inhab. Though planted on the top of an isolated hill, more than 200 ft. above the Charente, it is most abundantly supplied with fountains of fresh water, pumped up by machinery recently established. Its houses, being of a very white stone, easily cut, have a cheerful appearance: it has many new streets and a few old buildings. Its most pleasing features, however, are the series of *Terrace-walks* running round it, in the place of the old ramparts, and commanding a charming view of the industrious valley, deep below, of the winding Charente fringed with verdure, of the suburbs, and the *paper-mills* on the river banks, which furnish the staple article of manufacture here. By far the finest portion of these terraces is the *Promenade Beaulieu*; and a series of walks and shrubberies extend down the slopes below it towards the bottom of the valley. In the midst of them stands a column dedicated, by precipitate loyalty, to the Duchess d'Angoulême in 1815, re-dedicated, since 1830, "à la Liberté."

In the irregular *Place*, serving for the market, in the centre of the town, stands the old *Castle*, distinguished by its 3 picturesque feudal towers, and tall donjon, now converted into a prison, and surmounted by the telegraph. It contains a number of vaulted apartments, but possesses nothing of interest, save the recollec-

tion that it was the residence of the ancient Counts of Angoulême; that Marguerite de Valois, Queen of Navarre, was born in it,—the most accomplished princess of her day, "La Marguerite des Marguerites," as her brother François I. called her; and that its walls gave shelter to Marie de Medicis. She retired hither, after her husband's assassination, under the protection of the Duc d'Epemon, governor of the Angoumois, who has been suspected of being the accomplice of Ravillac; while the queen-mother herself is not free from suspicion—"The death of Henry did not sufficiently surprise her."

The *Cathedral* is rather a curious than a beautiful edifice, in the Romanesque style, rebuilt from its foundations, in 1120. It suffered at the Revolution; and till very lately bore over its frontispiece the ill-effaced inscription, "Temple de la Raison," set over it at that period. It is surmounted by a fine tall tower, of 6 rows of semicircular arcades, rising on the N. side. The W. front is in the style of the churches of Italy; almost the whole space being divided by circular arcades, resting on elegant columns, enclosing statues much mutilated, surmounted, in the pediment, by a statue of the Saviour (once supposed to be Jupiter), surrounded by the attributes of the 4 Evangelists. The *nave* has no side aisles, and its roof is formed of 3 vaulted cupolas, a style of construction not known to the N. of the Loire. At the cross rises an octagonal tower. The choir ends in an apse. Numerous additions and repairs were made to the interior, after the barbarous devastations committed by the Huguenots in 1562 and 1568.

Among modern buildings, the *Palais de Justice* is by no means contemptible. In the attic has been placed the public *Library*, containing 14,000 vols., and a small collection of Natural History.

Outside the town, to the N., in the escarped rock below the ramparts, is

the *Grotte de St. Cybard*, a holy hermit, whose real name was Eparchus, who occupied it as his cell, and died here in the 6th century. By the sanctity of his life he caused the foundation of a church and monastery, which extended from the cave to the Charente, and was once much frequented by devout pilgrims, but both are now swept away. In the grotto, which Charlemagne himself approached on bended knees in order to perform his devotions, mass was said daily, down to the time of the Revolution. This oldest Christian monument in Angoulême is respected by its present owner, but no longer serves as a church.

Ausonius makes mention of this town under the name *Iculisma*, fancifully derived from "In collis summâ," and gradually softened down, as some conjecture, into the modern Angoulême.

Angoulême and the surrounding province were governed, from the 8th century down to 1303, when they were united to France, by a long line of independent counts, 19 in number; first of the race of Taillefer, and, after 1180, of the house of Lusignan. It also belonged to the English, and was some time the residence of the Black Prince after the battle of Poitiers, 1360. One of the town gates, not pulled down until 1808, was named *Porte de Chandos*, from the brave English knight who built it, while constable of Aquitaine, for Edward III. A house in the Rue de Genève is pointed out as that inhabited by Calvin, who sought refuge here 1533, and taught Greek to maintain himself. The *Place de Murier* receives its name from a mulberry-tree which stood in the midst of it while it was the convent garden of the Jacobins. During the outrages committed by the Calvinist soldiery, 1562, when they captured and sacked the town, the monk Michel Grillet was hung to its boughs, in the presence of the Admiral Coligny, whose death he is said to have foretold with his dying

words, saying, "You shall be thrown out of the window, like Jezebel, and shall be ignominiously dragged through the streets."

Among the remarkable persons natives of this place are Ravallac, the assassin of Henri IV.; Poltrot, who shot the Duc de Guise le Balafre before the walls of Orleans; and Montalembert, the inventor of a system of fortification.

The *Naval School*, established here at the suggestion of the Duc d'Angoulême 1816, was suppressed 1830, and very judiciously transferred to Brest, and the building in the Faubourg l'Houmeau still remains closed.

The manufactures of Angoulême consist of paper, made in numerous (36?) mills in the neighbouring valleys, and brandy.

Capital *pâtés de perdrix aux truffes* are made here.

The Charente is navigable up to the quay below the town. A *Steamer* runs to Saintes (R. 62) 3 times a week.

18 $\frac{3}{4}$  m. W. of Angoulême, on the way to Cognac (R. 62), is *Jarnac*, where a handful of Protestants, commanded by the Prince de Condé, engaged the royal army commanded by the Duc d'Anjou, doubling their force in number, and were defeated. Condé fell, after giving the signal for a third charge, which he led, with one arm in a sling, and his leg shattered. Young Henri, Prince of Béarn, his nephew, was a spectator of the bloody affray, but was not permitted to take part in it.

The road to Bordeaux descends from Angoulême into the valley by a series of zigzags, under the Promenade de Beaulieu. About the middle of the stage the ruins of the *Abbey of la Couronne* are seen on the l., in the midst of a green valley abounding in paper-mills. After escaping destruction at the Revolution, it has been demolished, for the sake of the material, since 1808, and is now reduced to a mere fragment, including the W. front with a fine door-



way, and part of a rose-window over it.

13 Roulet.

8 Petignac. The post house is like a little château: beyond it is a steep ascent.

13 Barbezieu.—*Inn*: Poste; Boule d'Or, the only good inn between Angoulême and Bordeaux: dinner in private, 4 fr., with wine. The high road traverses the boulevard, or promenade, on the outskirts of this little town, of about 2500 inhab.: it once belonged to the Seigneurs of La Rochefoucauld.

7 Reignac.

7 La Graulle, in a monotonous sandy district of heath and common.

At Chevanceau a road branches off to Libourne. (R. 71.)

14 La Garde-Montlieu.

6 Chierzac. More common and fir plantations. In this district, and elsewhere in the south, during very hot weather, the oxen wear coats, and the asses are breeched, to protect them from the flies.

13 Cavignac (Dépt. Gironde).

About  $1\frac{1}{2}$  m. beyond the village St. André the road reaches the post station

16 Cubsac, on the rt. bank of the Dordogne, here a broad estuary, formerly crossed in ferry-boats, in which passengers and carriages were embarked. The transit occupied from  $\frac{1}{4}$  to  $\frac{1}{2}$  an hour, and was sometimes attended with danger, and always formed a serious interruption to the communication between Bordeaux and the French metropolis. For this disagreeable ferry an iron-wire *Suspension Bridge* is now substituted, divided into 5 curves, supported on 6 pair of piers, consisting of hollow open columnar shafts or towers of cast iron. The road-way of the bridge is raised 93 ft. above the water, so as to allow vessels of large size to pass under it; and the approaches to it, from either bank, are by a series of lofty stilted arches, 29 in number, on either bank, which have a striking effect. The bridge

itself has much the appearance of the Brighton chain-pier, and is of slight construction, being warranted to stand no more than 40 years, it is understood. Besides the suspending wire cables, others are attached to the summits of the piers, in the manner of stays or braces, to steady them. The length of the central, or suspension bridge, is 1,640 ft., and the 29 arches, on either side, measure 656 ft., making a total length of 2,952 ft. or more than  $\frac{1}{2}$  a mile: it is 20 ft. wide. The wire bridge of Cubsac, the longest in France, and, indeed, in Europe, was begun 1835, and finished 1839, at a cost of 3,000,000 fr., by the engineer Fortuné de Vergèz.

The *tolls* for passing the bridge are heavy.

The Dordogne joins the Garonne 10 m. below this bridge, and their united waters form the estuary called the Gironde, after which the department is named.

The tongue of land which separates the Dordogne from the Garonne, across which our road lies, is a fertile district, chiefly laid out in vineyards and corn fields, and scattered over with country seats. It is called the "Entre Deux Mers."

The road from Libourne falls in on the l. (R. 71.)

10 Carbon Blanc.

The approach to Bordeaux is very striking; the road is carried down, from a considerable height, in gently terraced slopes, winding round the shoulder of the hill, overlooking the broad Garonne, and the city of Bordeaux lining its opposite concave bank. From the foot of the hill a straight avenue, 2 m. long, leads to the magnificent *Bridge*, one of the finest in Europe, consisting of 17 arches of stone, the walls and spandrels being brick, with stone quoins, 1,534 ft. long, traversing the Garonne, from the little suburb la Bastide to the city of Bordeaux.

Until 1821 the Garonne was passed, in the same manner as the Dordogne

was down to more recent times, by a ferry; and the want of a bridge has confined the city exclusively to the l. bank of the river.

A bridge of wood was begun in the time of Napoleon, but was abandoned soon after for one of stone, which was completed, 1821, by a company of shareholders, who are repaid, by the tolls during 99 years, for their outlay, which amounted to 260,000*l.*, (6½ millions of fr.) The architect was M. Deschamps.

A vaulted passage runs under the roadway, between it and the arches, for the whole length of the bridge: this gives a great height of wall between the crown of the arches and the parapet.

As the French are fond of comparing this bridge with that of Waterloo, the dimensions of both are here given in English ft.

	Length.	Width.	No. of Arches.	Width of Arch.
Bordeaux 1534	47	17	85*	
Waterloo 1326	40	9	118	

The view of Bordeaux from the bridge is very striking. Opposite the bridge stands the Porte de Bourgogne, erected to commemorate the birth of the Duc de B., grandson of Louis XIV.

11 BORDEAUX, in Route 73.

ROUTE 65.

POITIERS TO CHÂTEAUROUX BY ST. SAVIN; WITH EXCURSION TO MONTMORILLON.

119 kilom. = 73½ Eng. m.

This cross road, not much travelled, leads to some interesting antiquities.

23 Chauvigny, a town of 1,000 inhab., occupies a commanding height on the rt. bank of the Vienne. It was, in feudal times, a strong fortress, and still possesses the ruins of 3 distinct *Castles* built on the same plan, a square flanked by turrets. The *Donjon*, on the top of the hill, shows

\* Only the 7 central arches have this width, the rest are smaller.

on one side a breach in its wall, made by a battery of cannon in the 16th century, during the wars of Religion, and now filled up with bricks arranged herring-bone fashion. One of the castles, the most modern, probably, of the 13th or 14th century, with pointed windows, now serves as a prison. There are many old houses in the upper town dating from the 15th and 16th centuries.

The *Church*, also in the upper town, is a very interesting Romanesque building, decorated with all the ornaments of Byzantine art externally, and also within; the capitals of its columns being carved with mermaids, monsters, &c., as well as with Scriptural subjects.

19 St. Savin has a *Church* decorated in its porch, nave, and crypt, under the choir, with fresco paintings, representing Scriptural subjects from the Creation, the figures as large as life, and tolerably well preserved. Those in the crypt describe the Legend of St. Savin and St. Cyprien, and are of smaller proportions. They are probably the work of Greek or Italian artists in the 11th, or, at earliest, of the 10th century, and are certainly very valuable as monuments of early art. It has been remarked, as a proof of the antiquity or the Eastern origin of these frescoes, that the horsemen are represented riding without stirrups. The whole church was originally covered with paintings; those in the choir have been effaced by whitewash. The church itself is a very ancient specimen of Romanesque architecture; it is entered by steps leading down into it, and the W. end seems to have been separated from the rest, so as to form a Narthex, like the Galilee of some English churches. The choir and shallow transepts end in apses.

At *Montmorillon*, 12 m. S. of St. Savin, "in the court-yard of what was the baronial castle, and is now a college, there is an ancient and very curious chapel. Originally it must have been the domestic chapel of the



lords of the adjacent castle, doubtless erected by them, and for their private use. It consists of a subterraneous crypt, which, probably, was the family vault, and an octagonal chapel above it, with a conical roof. Part of this building is in the round style, and part in the pointed. That part which is in the round style may belong to the 11th cent. The pointed part cannot be older than the 13th. But the most remarkable feature in this building, and that to which it owes its celebrity, is a group of rudely sculptured figures which occupy a recess above the doorway. Various explanations of this singular group have been offered by the learned, but none of them are satisfactory, and the problem is more difficult to solve, as some of the figures are taken from ordinary life, and some are allegorical."—*H. G. K.* The most singular and inexplicable, perhaps, are two female figures, the one corpulent, having toads or scarabs hanging from her breasts; the other meagre, entwined by serpents, and suckling them. This *Church* has been repaired by the Government. Under an arch on the rt. is the tomb of Etienne de la Hire.

18 Le Blanc.

18 Scoury.

11 St. Gaulthier.

15 Lothiers.

15 Châteauroux. (R. 70.)

## ROUTE 66.

POITIERS TO ROCHEFORT BY NIORT.

132 kilom. = 80 Eng. m.

Poitiers (in Route 64) to

6 Croutelle, on the road to Bordeaux.

17 Lusignan on the Vonne (*Inns*: H. Ste. Catherine;—Lion d'Or) gave its name to the noble family which rescued Jerusalem from the Infidels and for some time occupied its throne. The castle was surprised and razed by the Catholics 1574, and a public walk occupies its site. The *Church*, a dilapidated building, has a curious portal, ornamented with the signs of the zodiac.

14 Villedieu du Perron.

15 St. Maixent (*Inn*: L'Ecu de France—extortionate), an old walled town, 5500 inhab., on a height above the Sèvre.

10 La Crèche.

13 Niort (*Inn*: H. de France—very good), a modern town, chef-lieu of the Dépt. of the Deux Sèvres, on the Sèvre Niortaise, 22,000 inhab.

The *old Castle*, surmounted by 2 keep-towers, each flanked by 8 turrets, remarkable as the birth-place, or at least the cradle, of Madame de Maintenon, whose profligate father, Constant d'Aubigné, was confined in it, is now the *Maison d'Arrêt*.

10 Frontenay.

13 Mauzé.

12 Surgères.

10 Muron.

16 Rochefort, in Route 62.

near Le Blanc is the Abbey

of Longuevaux, lately again taken possession of by the Trappists. The Church is a fine ruin of the 12th

and 13th centuries in process of restoration by the monks.

Four miles west of Montmorillon is Leprae les Châteaux, where there are several small Romanesque churches. The ruins of two castles are a bridge connecting them, the towers of which remain in the water, but the bridge appears to have been of wood, and is now gone.

## SECTION IV.


LIMOUSIN.—GASCONY.—GUIENNE.—THE PYRENEES.—  
 NAVARRE.—BÉARN.—LANGUEDOC.—ROUSSILLON.

## PRELIMINARY INFORMATION.

§ 1. Scenery of Limousin and of the Pyrenees. § 2. Objects of interest in the Pyrenees. § 3. Comparison with the Alps, Forests, Gaves, Lakes, Ports or Passes, Valleys, Cirques or Oules. § 5. A Dash into Spain. § 6. Inhabitants. § 7. Cagots, Sporting. § 9. History, the English in the Pyrenees, Froissart, the Black Prince, Wellington. § 10. Characteristics of the chief Watering-places, the Baths. § 11. Works on the Pyrenees. § 12. Directions for Travellers, Approaches and nearest Routes, Starting-points. § 13. Skeleton Tours. § 14. Passports, Accommodations, Inns, Conveyances, Guides, Horses, Chaises à Porteurs.

ROUTE	PAGE	ROUTE	PAGE
70 Orleans to <i>Toulouse</i> , by <i>Vierzon</i> , <i>Châteauroux</i> , <i>Limoges</i> , and <i>Montauban</i> (RAILWAY) . . . . .	246	84 The <i>Col de Torte</i> .— <i>Eaux-Bonnes</i> to <i>Cauterets</i> or <i>Luz</i> . . . . .	303
71 <i>Limoges</i> to <i>Bordeaux</i> , by <i>Perrigueux</i> and <i>Libourne</i> . . . . .	261	85 <i>Pau</i> to <i>Lourdes</i> , <i>Cauterets</i> , <i>Luz</i> , <i>St. Sauveur</i> , <i>Barèges</i> , and <i>Bagnères de Bigorre</i> .— <i>The Mountain Road</i> , with Excursions to the <i>Lac de Gaube</i> , <i>Gavarnie</i> , <i>Brèche de Roland</i> .— <i>Mont Perdu</i> , <i>Pic du Midi</i> , &c. . . . .	304
73 The GARONNE. — <i>Toulouse</i> to <i>Bordeaux</i> , by <i>Moissac</i> , <i>Agen</i> , <i>Marmande</i> . . . . .	263	86 <i>Bagnères de Bigorre</i> to <i>Bagnères de Luchon</i> .— <i>Mountain Road</i> , by the <i>Hourquette d'Aspin</i> , <i>Arreau</i> , <i>Col de Peyresordes</i> , and <i>Val de l'Arboust</i> . — Excursion to the <i>Lac de Seculeijo</i> . . . . .	321
74 The Gironde from <i>Bordeaux</i> to <i>La Tour de Cordouan</i> .— <i>Wine District of Médoc</i> .— <i>Château Margaux</i> , <i>Lafitte</i> , and <i>Latour</i> . . . . .	273	87 <i>Pau</i> to <i>Bagnères de Bigorre</i> , and <i>Bagnères de Luchon</i> , by <i>Tarbes</i> .— <i>Post Road</i> .—Excursions to the <i>Val de Lys</i> , <i>Port de Venasque</i> , and <i>Val d'Aran</i> . . . . .	324
76 <i>Bordeaux</i> to <i>Bayonne</i> , <i>St. Jean de Luz</i> , and the Spanish Frontier . . . . .	279	90 <i>Toulouse</i> to <i>Pau</i> , by <i>Auch</i> and <i>Tarbes</i> . . . . .	337
77 <i>Bordeaux</i> to <i>Bayonne</i> , across <i>Les Grandes Landes</i> . . . . .	287	91 <i>Toulouse</i> to <i>Bagnères de Luchon</i> and <i>Bagnères de Bigorre</i> , by <i>St. Gaudens</i> . . . . .	338
78 <i>Bayonne</i> to <i>Pau</i> , by <i>Orthez</i> . . . . .	288	93 <i>Toulouse</i> to <i>Narbonne</i> , and <i>Marseilles</i> by <i>Carcassonne</i> .— <i>Canal du Midi</i> . . . . .	339
79 <i>Bordeaux</i> to <i>Auch</i> , by <i>Castel Jaloux</i> and <i>Nerac</i> . . . . .	290		
80 <i>Bordeaux</i> to <i>Pau</i> . . . . .	291		
82 <i>Pau</i> to the Spanish Frontier, by <i>Oloron</i> and the <i>Val d'Aspe</i> . . . . .	295		
83 <i>Pau</i> to <i>Eaux-Bonnes</i> and <i>Eaux-Chaudes</i> . — <i>Pic du Midi d'Ossau</i> , and Spanish Baths of <i>Panticosa</i> . . . . .	296		





MAP OF THE  
PYRENEES  
To accompany the Handbook of France

- Post Roads
- Car D<sup>o</sup>
- - - Horse & Foot Paths
- Points of View
- Castles in Ruins
- Waterfalls

English Miles  
5 10 20 30 40  
French Leagues  
5 10 15





ROUTE	PAGE	ROUTE	PAGE
94 Narbonne to <i>Perpignan</i> , <i>Port Vendre</i> , and the Spa- nish Frontier . . . . .	343	<i>The Valley of the Ariège.—</i> <i>Vicdessos.—Andorre</i> . . . . .	346
59 St. Gaudens to Foix and Car- cassonne, by <i>St. Giron</i> s . . . . .	345	98 <i>The E. Pyrenees.—Perpig- nan to Mont Louis</i> and Puy- cerda, by the <i>Valleys</i> of the <i>Tet</i> and <i>Tech</i> .—Ascent of the <i>Canigou</i> . . . . .	349
97 <i>The E. Pyrenees.—Toulouse</i> to <i>Foix</i> and <i>Puycerda</i> .—			

§ 1. *The scenery of Limousin*, through which province the following Routes conduct the traveller to the Pyrenees, is thus described in the excellent work of Arthur Young:—

“In regard to the general beauty of a country, I prefer Limousin to every other province in France. It does not depend on any particular feature, but is the result of many. Hill, dale, wood, enclosures, streams, lakes, and scattered farms are mingled into a thousand delicious landscapes, which set off everywhere this province.”

The length of the portion of the chain of the Pyrenees running between the Mediterranean and the Bay of Biscay, and forming the boundary line between France and Spain, is estimated at about 270 m. The highest parts of the chain are near the centre, and it descends considerably towards the Mediterranean and the Gulf of Gascony. The highest summits do not occur on the central ridge or main chain, but on the buttresses running out from it to the S., and therefore belong to Spain. Only one summit within the French frontier, the Vignemale, attains an elevation of 11,000 ft., while 3 in the Spanish portion of the chain exceed that measure. The average length of the valleys running up from the plain to the crest of the mountains is about 36 m.

§ 2. Without doubt some of the finest scenery in France is to be found among the Pyrenees, which, though inferior in height, and on the whole in *grandeur* of scenery, number of snowy peaks, and area of crystal glaciers, to the Alps, yet possess beauties peculiar to themselves, of which the Alps cannot boast. The sunny atmosphere, which they owe to their more southern latitude, gives a warmth or glow to the landscape which will in vain be sought farther to the N.; and this genial climate, while it banishes perpetual snow to a height of about 9000 ft. (i. e. 1,300 ft. above the Alpine snow line), also spreads a richness of sylvan decorations over these mountains unparalleled in Swiss scēnery. Heights which in a more northern region would either be condemned to nakedness, or to a scanty growth of lichens, are here clothed in verdure to the very top; and precipitous rocks, elsewhere rejecting all vegetation, are tufted in every cranny and fissure with brushwood, especially with box, which thrives and spreads wonderfully.

But the pride and boast and chief charm of the Pyrenees are their vast forests, the seas of undulating foliage which clothe their sides and tops, not merely of dark monotonous fir, but oak and beech: examples of these are presented in the upper part of the Val d'Ossau, near Gabas, in parts of the Val d'Argelez and Val d'Aure.

The meadows which carpet the lower slopes and bottom of the valleys equal if they do not surpass those of Switzerland in intense verdure produced by irrigation and sunshine, and approximate to the even surface of an English lawn; and while the plains of Languedoc and Provence are parched into a yellow desert, here the hues of spring are prolonged into summer and autumn, and the traveller is constantly refreshed by vernal gales.

§ 3. The brawling rivers (*Gaves* is the local name, derived from the same

Celtic root as our *Avon*) are remarkable, beyond those of almost any other country, for their excessive purity, and for tints resembling beryl and chrysoprase. The waterfalls are second rate, quite inferior to those of Switzerland; those above Cauterets are pretty, and, perhaps, the finest. That of Gavarnie, the loftiest in Europe but one (in Norway), though 1300 ft. high, is a mere thread of water. Lakes are almost entirely wanting, and here the inferiority of the Pyrenean mountains to those of Switzerland is most decided. The Lacs de Gaube, of Seculeijo (or Lac d'Oo), and the Lac Bleu, though very interesting from the adjuncts of scenery, precipices, and streamlets dashing into them, are mere mountain tarns, yet they are the finest and almost the only sheets of water.

The chain of the Pyrenees has in a considerable degree the character of a vast wall drawn from sea to sea, inasmuch as it preserves an almost unvarying ridge, notched by frequent passes or cols, rarely more than 1000 ft. lower than the summit of the crest which surmounts them. The consequence is, that the passes leading across the chain are generally higher than among the Alps, far higher in proportion to the comparative elevation of the Pyrenees, and that they are much less accessible for high roads; indeed only two are practicable for carriages—the Pass of the Bidassoa, at the W. extremity, close to the Bay of Biscay, and that of the Col de Pertus, at the E., along the shore of the Mediterranean. There are however at least 50 passes known to and used by the shepherds and mountaineers, and most of them practicable on horseback. They are here called "*Ports*," a very expressive name, for in many instances they are literally doors cut in the crest of the mountains leading from France into Spain. The most striking of these, and well worth the traveller's attention, are the "*Brèche de Roland*," and the Port de Venasque, the passage of which reveals the grandest, and almost the only, view of the Maladetta, the monarch of the Pyrenees.

The valleys of the Pyrenees run nearly at rt. angles with the great dorsal ridge descending from the central spine into the plain, in a series of basins and gorges: the most considerable are the valleys of the Garonne and Ariège.

The most beautiful on the French side of the chain are the Val d'Argelez (which no one should omit seeing), Val d'Ossau, and valleys of the Garonne, Adour, and Lys, Val d'Aure, and Val d'Aran.

The most grand gorges are those leading from Pierrefitte to Cauterets and Luz, and that of Mahourat leading to Pont d'Espagne, and the approach to Eaux-Chaudes.

§ 4. Several Pyrenean valleys have a termination quite peculiar to themselves—in a *Cirque* or *Oule* (a local word, meaning pot, Latin *olla*), a vast circle or semicircle, excavated in the mass of the mountain, walled round by precipices of great height, surrounding two-thirds or three-fourths of the basin, and leaving no opening but that by which the waters escape. The finest of these cirques is that of Gavarnie, at the commencement of the Val de Lavedan: its walls are loftiest and most perfect; that of Troumouse at the head of the Val d'Héas is larger, but not so deep: another occurs at the bottom of the Val Estaubé. The nearest approach to this peculiar formation of the vale head in the Alps is at Leuk; but the precipices of the Gemmi, which wall it round, want the semicircular arrangement, as well as the waterfalls, the towers, and cylinders of rock which give the grand character to the scenery of Gavarnie.

The valleys of the Pyrenees are separated from one another by lateral ridges descending like ribs or buttresses from the great chain, over which the communication is maintained by numerous minor cols, called *Portillons*,



or in some parts *Hourquettes*. Such are the interesting passes of the Tourmalet and of the Hourquettes d'Arreau and d'Aspin.

Most visitors to the Pyrenees make a point of ascending one of the high peaks in the vicinity of the baths, either for the sake of the view, or to say they have been on such or such a peak: hence, "*Avez-vous fait quelques ascensions?*" is a common inquiry. The mountain which may be ascended with least trouble, and which repays well by its prospect, is the *Pic de Bergons*, above Luz. The *Pic du Midi de Bigorre*, conveniently reached from either Barèges or Bagnères de Bigorre, is loftier and more difficult. Less easy still are the *Pic du Midi d'Ossau*, the *Canigou* in the E. Pyrenees, and the *Brèche de Roland*; while the still more lofty *Vignemale* is no easy task to surmount, and the *Mont Perdu* is both difficult and dangerous—an exploit for a practised mountaineer; and the *Maladetta* wears snow on its crest never trodden by human foot until 1842.

§ 5. *A dash into Spain*, of three or four days' duration, will add much to the variety and interest of a journey among the Pyrenees. The points whence it may be made with most advantage, are either from Bayonne to St. Sebastian, from Eaux-Bonnes or Cauterets to the Baths of Panticosa, from Gavarnie to Busaruelo and Fanlo, or from Luchon to Venasque and the Val d'Aran. The scenery on the Spanish side of the Pyrenees is far grander and wilder than on the French. Those who attempt to explore it must be prepared to "rough it;" they will encounter a wild people, rude villages, accommodations of the very worst kind, yet very expensive, paths scarcely passable, and cookery nauseous to those unused to it, owing to oil and garlic. The sudden transition from France to Spain, the total difference of people, language, manners, habitations, food, combined with the grander features of the mountain scenery, yield the chief zest to such a journey. An invitation to one of the *Spanish Bullfights*, which are held every year in all the large towns of the N. of Spain, may tempt some to penetrate farther into the country. (See for details the HANDBOOK FOR TRAVELLERS IN SPAIN.)

§ 6. The inhabitants of the Pyrenees, composed of various races, interesting for their antiquity, customs, costumes, &c., are worthy of the attention of the traveller. At the W. extremity of the chain, S. of Bayonne, you have the *Basques*, the aborigines of W. Europe, who have seen Carthaginians, Celts, Romans, Goths, Saracens, pass before them, and still remain in possession of their mountain home, part in France, part in Spain, speaking a language which has nothing in common with any other of Europe. (See R. 76.)

The peasantry of Béarn, who occupy the beautiful Val d'Ossau and its tributaries, the land of Henri IV., in the midst of which he spent the years of childhood, are a fine race, retaining much of their primitive simplicity of manners, along with their ancient costumes, the men wearing the berret or cap, like the Lowland bonnet of the Scotch, and a red sash round the waist; the women covering their heads with the red hood or capulet. In the E. Pyrenees, the people of Foix and Roussillon have a considerable resemblance, in character, dress, and language, to the Catalans of Spain.

§ 7. The proscribed and outcast race, called *Cagots*, exist more in tradition than in reality at present among the Pyrenees. In these mountains there may be families who have intermarried with them, or are descended from them, but the ban of caste no longer hangs over them. They are said to have been weak in body and mind, low in stature, sallow in countenance, and to have lived only in the remotest valleys, shunning their fellow-men. There are various theories to account for their origin and name, none of them satisfactory—for example,

that they are the descendants of the Goths, dispossessed of Aquitaine by Clovis—"chiens de Goths," whence Cagots, by a somewhat forced derivation. 2nd. That they sprung from the Saracens, who stayed behind in France after their defeat by Charles Martel. 3rd. That they were lepers, banished from human haunts for fear of infection; or, what seems probable, fugitives tainted with heresy and driven apart from the community by the prejudices and aversion of the Romish priesthood. They are now nearly lost through intermixture with the mass of the population.\*

§ 8. *The Sportsman* may still find some occupation among the Pyrenees in the pursuit of the bear, the ibex or bouquetin, and the chamois or izard, though these animals are growing rare. The bouquetin, especially, is almost extinct; if anywhere, he may be found on the Maladetta. The izard is not uncommon, and the best localities for enjoying this chase are Eaux-Bonnes, where are some capital guides (see R. 83), the snow-fields of the Vignemale, the Mont Perdu, and the Maladetta, or in the Spanish Val de Broto.

The izard is hunted either by stalking, in the manner in which the red deer is stalked, though with much more difficulty and danger, amidst precipices, glaciers, and snow-fields, until, after a tedious pursuit, the huntsman may have the chance of a steady shot, or by driving the animals by guides and mountain shepherds towards the spot where the chasseur is posted. Success in this case entirely depends on the perfect knowledge possessed by the guides of the habits and haunts of the izard.

The rivers are so much netted as greatly to interfere with the sport of angling; a scientific fisherman, however, would doubtless find full scope for the exercise of his rod among its innumerable Gaves and mountain streams.

§ 9. *History and Antiquities.*—The passage of the Pyrenees by Hannibal, and afterwards by Cæsar, with large armies, are the earliest events of importance connected with these mountains. The pass by which they crossed was that of Pertus, at the E. end of the chain. Charlemagne's advance into Spain, in 778, was through that of *Roncesvaux*, where he received the memorable check so celebrated in history and romance, chiefly at the hands of the hardy mountaineers, the Basques, who fell upon his rear guard while entangled in the defiles, and killed many of his "paladins and peers," amongst them the renowned Roland, who has left his name upon the highest mountain ridge of the chain in the so-called Brèche, cleft through the rock, according to the tradition, by a swashing blow of his celebrated sword Durandal. The valleys and passes of the Pyrenees, like those of all other border countries, abound in *castles* and watch towers, relics of feudal times, when war and rapine was the business of a great portion of the inhabitants, especially of all who claimed to be noble or gentle. Those who would know something of the history of these ruined hill forts, and of the mode of life of those who occupied them in the 14th century, of the marauding expeditions which went out from them on border forays, to harry the cattle or fair fields of some neighbouring chief, of ambuscades to rob the burgess of the neighbouring towns of his merchandise, or capture some wealthy ecclesiastic or seigneur of eminence, and clap him into the deep dungeon until a ransom was paid, must refer to the delightful pages of *Sir John Froissart's Chronicles*, the oldest and best hand-book for the Pyrenees, which he traversed and threaded in various directions, picking up anecdotes for his history.

\* The Editor is desirous of obtaining information from personal research, not hearsay, respecting the present state and numbers of the Cagots; if, indeed, any of them do exist.



In his time many of these strongholds were held by English garrisons for the Black Prince, the province of Gascony, with Bigorre, having been ceded to the English as part of the ransom of the French king, John, captured at Azincour. The tradition of the country, indeed, attributes the building of some of the castles to the Black Prince. He led an English army into Navarre, to reinstate Pedro the Cruel on the throne of Spain, through the pass of Ronceval, the scene of the “dolorous rout” of Charlemagne.

Four centuries and a half later, the Pyrenees once more became connected with English history, and in a more glorious cause.

“Many of these romantic heights are endeared to an Englishman by the recollection of gallant deeds of British valour performed at the close of the Peninsular war.”—S. To visit the scenes of the masterly passage of the Bidassoa, and of the Adour below Bayonne, the spot where the fatal sortie took place under the walls of that fortress, the heights of Orthez, and those where the hard-contested but decisive and final battle of Toulouse was fought, cannot but add to the interest of the journey. It will augment the satisfaction of an Englishman, on visiting the theatre of the war, to know that the British commander, so far from displaying the insolence of a conqueror on entering the French territory, took measures to repress rigidly all acts of plunder on the part of his troops, by careful discipline. No inconsiderable difficulty was at first experienced in restraining the Spaniards, smarting under the oppression and wrongs inflicted on their own fatherland by the soldiery of the country which they then entered in triumph, and expecting to avenge upon its inhabitants the injuries they themselves had suffered. The firmness of the British commander, however, succeeded in alleviating, as far as possible, the horrors of war to the French; and the two following extracts, one from a general order of the Duke issued after the passage of the Bidassoa, the other from a letter written by him to a Spanish officer, will show how great care he took to effect this.

*General Order.*—“The Commander of the Forces is particularly desirous that the inhabitants should be well treated, and private property must be respected, as it has been hitherto.

“The officers and soldiers of the army must recollect that their nations are at war with France, solely because the ruler of the French nation will not allow them to be at peace, and is desirous of forcing them to submit to his yoke; and they must not forget, that the worst of the evils suffered by the enemy in his profligate invasion of Spain and Portugal have been occasioned by the irregularities of the soldiers, and their cruelties authorised and encouraged by their chiefs towards the unfortunate and peaceful inhabitants of the country.

“To revenge this conduct on the peaceable inhabitants of France would be unmanly and unworthy of the nations to whom the Commander of the Forces now addresses himself; and, at all events, would be the occasion of similar and worse evils to the army at large than those which the enemy’s army have suffered in the Peninsula; and would, eventually, prove highly injurious to the public interests.” \* \* \*

*To General —, a Spanish Officer.*—“I did not lose thousands of men to bring the army under my command into the French territory, in order that the soldiers might plunder and ill-treat the French peasantry, in positive disobedience to my orders; and I beg that you and your officers will understand, that I prefer to have a small army that will obey my orders, and preserve discipline, to a large one that is disobedient and undisciplined; and that, if the measures which I am obliged to adopt to enforce obedience and good order occasion the loss of men, and the reduction of my force, it is

totally indifferent to me ; and the fault rests with those who, by the neglect of their duty, suffer their soldiers to commit disorders which must be prejudicial to their country.”—*Dispatches*.

§ 10. *Hot Springs—Character of the Watering Places—Baths in the Pyrenees*.—The bounty with which Nature has poured forth, throughout the whole range of the Pyrenean mountains, mineral sources of healing quality, of various kinds, adapted to the various ills to which flesh is heir, is truly surprising, and an interesting natural phenomenon. It has been calculated that in the whole chain there are not less than 200 springs, many of them of a high temperature.

It has been observed, that they usually issue forth to light near the junction of the primitive rocks, as granite, gneiss, or slate, with some other formation, chiefly limestone.

The value of these natural medicines was not unknown to the Romans, traces of whose constructions have been discovered near more than one of the hot sources.

Here follows a list and a brief character of a few of the principal watering places, beginning from the W., with a notice of the nature of the mineral waters attached. The list might be greatly extended, for very many other springs gush forth unseen and unknown, “*carent quia vate sacro*,” *i. e.* because they have found no literary M. D. to celebrate them in an 8vo. volume.

*Eaux-Bonnes*.—A fashionable resort, consisting of a row of eighteen or twenty fine tall houses, chiefly modern, and Parisian in their style, and rather expensive, in a wild mountain nook. The water is sulphureous. It is recommended for those afflicted with complaints in the lungs.

*Eaux-Chaudes*.—Water sulphureous, nearly like *Eaux-Bonnes*, from which it is only 3 m. distant ; more homely accommodation, and visitors less stylish.

*Cauterets*.—Sulphureous water. A neat little mountain town, in an upland valley surrounded by colossal peaks. Plenty of accommodation, and good ; also a place of fashionable resort. In autumn frequented by many Spaniards. Climate bracing, if not cold, from the elevation of its site. Excursions numerous. Its waters and site are considered efficacious in bronchial complaints and rheumatism.

*St. Sauveur*.—Feebly sulphureous. A mere watering-place of 1½ dozen lodging-houses.

*Barèges*.—A complete hospital, thronged with miserable invalids ; inferior accommodation ; a poor village in a dreary gorge, which nothing but the hope of recovering health would render endurable beyond an hour or two ; yet the efficacy of its waters is astonishing, and in a medical sense it deserves its celebrity, more extended over Europe than that of any other Pyrenean bath. It is often quite full in the season, and lodgings dear. A sharp atmosphere, owing to its great elevation.

*Bagnères de Bigorre*.—Saline springs ; weak ; one ferruginous spring. A considerable town, something more than a mere watering-place, seated just within the roots of the Pyrenees on the verge of the plain, and not much raised above it ; warm climate. Various amusements ; pleasant excursions. The tepid baths are efficacious only for slight complaints : the waters are not powerful remedies.

*Bagnères de Luchon*.—Seated in the bottom of a basin surrounded by mountains ; resorted to for pleasure as well as cure. Its waters are sulphureous and hot—efficacious in rheumatic complaints or cutaneous affections. There are charming excursions in its vicinity.



At every French watering-place is a medical inspector appointed by the government, and invalids intending to take a course of the waters had better put themselves in communication with him. He will assist them respecting lodgings, and assign to them a fixed hour for bathing, which they will retain during the whole time of their stay; a measure often indispensable during the season, owing to the number of bathers, in order to obtain access to the bath at all.

The *Bath Houses* (*Etablissements Thermals*) of the Pyrenees are very far behind those of Germany in orderly and medical arrangement; the waters, in many cases, losing some of their properties in their passage from the source to the baths. But their chief inferiority is in want of cleanliness. The cabinets des bains are dark hot cells; the baths themselves, though of marble, mere troughs, calculated to inspire disgust in those who either do not need, or are not thoroughly convinced of their sanative power.

*Works relating to the Pyrenees.*—The best of all the descriptions of the Pyrenees are the works of Ramond (the Saussure of these mountains), “*Observations dans les Pyrénées*,” and “*Voyages au Mont Perdu*.” To these may be added, *Vayse de Villiers*, 2 vols. of *Itinéraire*; and Charpentier’s *Geological Essai*, &c., now superseded by the more recent geological papers by Elie de Beaumont and Dufresnoy, in the *Transactions of the French Geological Society*. In English, we have Mrs. Ellis’s very pleasant little volume, Lady Chatterton’s charming work, more recent and more comprehensive, and the Hon. Erskine Murray’s “*Summer in the Pyrenees*,” which relates especially to the little-visited valleys in the E. part of the chain.

The very amusing “*Letters from the Pyrenees, 1843*,” of Mr. Paris, a hardy and intrepid pedestrian, have shown the way into some of the most remote valleys rarely visited, and never yet described by any English writers.

## § 12. DIRECTIONS FOR TRAVELLERS IN THE PYRENEES.—APPROACHES AND MOST DIRECT ROUTES.

1. Southampton to Havre, steamboat; Havre to Rouen, up the Seine, or by railway; Rouen to Paris, railway; Paris to Orleans, railway; Orleans to Tours, railway; Tours to Bordeaux, land journey of 3 days. Bordeaux to Pau, a land journey of about 125 m., 2 or 3 days’ posting, 18 hours’ diligence; or up the Garonne to Langon, and thence by land to Pau.

The Railways from Rouen to Paris and from Paris to Orleans render this a speedy and agreeable route, perhaps the most eligible of all.

2. Southampton to Bordeaux, by steamer; passage 60 or 70 hours.\*

3. Southampton to St. Malo, steamer; St. Malo to Nantes, land journey of 3 days; Nantes to Bordeaux by steamer, or by land through Rochefort.

4. Paris, Orleans, Vierzon (railway), Limoges, Toulouse, Bagnères, a long and uninteresting land journey from Orleans.

5. Paris to Châlons-sur-Saône, by land; thence to Lyons, Avignon, and Beaucaire by steamer; to Nismes and Montpellier, by railway; by land or canal to Toulouse; a land journey thence of nearly 90 m. to Bagnères.

The best starting points for making the tour of the Pyrenees are Pau for those coming from the W., and Toulouse for travellers approaching from the E. Those who do not intend to make a permanent stay at any of the watering-places should dismiss their heavy baggage before they plunge into

\* This Steamer does not run regularly.

the mountains, sending it on by *roulage*, from the one extreme point of their intended tour to the other, from Pau to Toulouse, or *vice versâ*.

The Brunnen of the Pyrenees, ensconced each in its own beautiful valley, form good halting places for the passing traveller, who visits these mountains merely from curiosity to explore their beauties, and he may thus terminate almost every day's journey in a comfortable hotel, or at least in tolerable quarters. Almost every valley is accessible by a good *carriage road*, but it stops at a certain distance, without surmounting the mountain ridge, or penetrating into Spain, except the two extreme passes at the E. and W. ends of the chain. As there are few carriage roads over even the lateral ridges from one valley into another, those who travel only in carriages must retrace their steps down the valleys. Pedestrians and equestrians (and the only way to see the Pyrenees to advantage is on foot or horseback) may pass, in most instances, by foot or bridle-paths, out of one valley into another across the minor ridges which separate them, and thus enjoy some of the finest scenery without going twice over the same ground. The great chain can only be crossed in the same way, by bridle or foot-paths, over some of the many Ports or Cols, more than 50 of which are enumerated between the Bay of Biscay and the Mediterranean.

§ 13. SKELETON TOUR OF THREE OR FOUR WEEKS, TO INCLUDE THE MOST INTERESTING OBJECTS IN THE W. PYRENEES.

PAU. Starting-point to—	Barèges.
Eaux-Bonnes et Chaudes.	* Tourmalet.
* Pic du Midi d'Ossau.	* Pic du Midi de Eigorre.
* Col de Torte.	Bagnères de Bigorre.
* Val d'Azun.	* Lac Bleu.
Argelez.	Hourquette d'Aspin.
Cauterets.	* Arreau.
* Pont d'Espagne, Lac de Gaube	* Tramesaigues and the Vald'Aure.
[or from * Eaux-Chaudes to Panti-	* Port de Peyresourdes.
cosa in Spain, by Pont d'Espagne to	* Lac de Seculeijo.
Cauterets].	Bagnères de Luchon.
Gorge of Pierrefitte.	Val de Lys.
Luz, or St. Sauveur.	* Port de Venasque, Venasque,
Gavarnie.	Viella.
* Brèche de Roland, back to Luz	* St. Beat, in Val d'Aran.
[or to Busaruelo and Fanlo in Spain,	* Toulouse.
and back].	<i>N.B.</i> This mark * denotes places
* Val d'Héas.	which cannot be reached in carriages,
* Vignemale.	but only on horseback or foot.

CARRIAGE TOUR BY POST ROADS.

Pau. Eaux-Bonnes et Chaudes.	Cierp, St. Beat.
Louvie, Lestelle, Lourdes, Argelez,	St. Gaudens.
Cauterets.	Toulouse.
Pierrefitte, Luz, Barèges.	
Lourdes, Bagnères de Bigorre,	<i>N.B.</i> Ladies may be <i>carried</i> up to
Valley of Grip, Arreau (? no posting).	most of the points of interest in a
Lannemezan, Cierp, Bagnères de	chaise à porteur.
Luchon.	



COMPLETE ITINERARY OF THE FRENCH PYRENEES FROM BORDEAUX TO PERPIGNAN.\*

<i>Days.</i>	<i>Night Quarters.</i>	<i>Objects of Interest.</i>
1	Mont de Marsan.	
2 } 3 }	Bayonne.	{ Citadel (Sortie). Embankments to turn the course of the Adour.—St. Pierre d'Ar-ruby.— Biarritz.
4 } 5 }	St. Sebastian and back, by Diligence.	{ Interesting ride, through scene of the war in Spain.—Irun and Hernani, curious Spanish towns.—See Citadel of St. S. and walk to Passages.
6	St. Jean Pied de Port.	— <i>Inn</i> : Soleil.
7 } 8 }	Roncesvalles, 15 m. from St. Jean.	{ Arrange about passport and procure a guide and horse at St. Jean. It will take a day to go, and the same to return.—The Abbey is tenantless; but there is an Inn.
9	Oloron.	{ By Mauléon (Hôt. Vefour, good), a Basque town, and Tardetz.
10	Val d'Aspe.	{ Bedous, best sleeping place, but bad.—Take provisions—at least white bread.
11 }	Eaux-Chaudes: Val d'Ossau.	{ Cross from Escot by the Col de Marie Blanche, and Plan de Benou (the bed of a former lake), to Bielle in Val d'Ossau.
12 } 13 }	Eaux-Bonnes.	Ascent of Pic du Midi d'Ossau.
14	Pau.	{ By Diligence. Or, if you do not wish to visit Pau, cross Col de Torte and descend Val d'Azun to Argelez.
15	Cauterets.	{ By Lourdes (Argelez, ascend Val d'Azun, as far as Pouy le Hun).—St. Savin.
16	Cauterets.	Ascend Monné; 10 hours up and down.
17	Panticosa.	{ Visit, on the way, the Pont d'Espagne and Lac de Gaube.
18	Eaux-Bonnes.	By the Case de Broussettes.
19	Argelez.	{ By Col de Torte and the beautiful Val d'Azun, 12 hours' walk.
20	Luz.	Pic de Bergons.—St. Sauveur.
21	Luz.	{ Gavarnie and Brèche de Roland. If Val d'Heas also, must sleep at Gavarnie and scale the Brèche next day.
22 }	Grip or Bagnères de Bigorre.	{ By Barèges, which may be seen en passant. Turn off at foot of Tourmalet, and ride up by the Lac d'Oncet to the top of the Pic du Midi. Sleep at Grip, if unable to reach Bagnères. Must start early.
23 } 24 }	Bagnères de Bigorre.	{ See marble works.—Baths.—Walks.—Visit Lac Bleu.
25	Arreau.	{ Ascend Penne de l'Hyéris. Cross Hourquette d'Arreau.

\* Compiled from the notes of J. J., a most experienced traveller in the Pyrenees, obligingly communicated to the Editor.

<i>Days.</i>	<i>Night Quarters.</i>	<i>Objects of Interest.</i>
26 { 27 {	Aragnouet or Hospice de Coubise; miserable quarters.	Ascend Val d'Aure by Vielle, beyond which it splits into several branches. That called Val d'Aragnouet and Gorge de Couplan contains <i>magnificent</i> mountain scenery, forests, cascades.—Return to Arreau.
28	Bagnères de Luchon.	By Val de Louron, Port de Peyresordes, and Lac d'Oo. If time admits, ascend by Scala to upper Lake.
29	Bagnères de Luchon.	Val de Lys.—Go or return by Sopra Bagnères.
30	Luchon or Venasque.	Port de Venasque—Trou du Taureau—returning by Port de Picade, to Luchon. <i>N. B.</i> This excursion may be extended to Venasque, and round the Maladetta to Vitallez and Viella.
31	Val d'Aran: Lez.	By Port de Portillon to Œil de Garonne. — Castel Leon. — Bososte. — Sleep at Baths of Lez.
32	Cierp or Luchon.	Below Lez the finest part of Val d'Aran. —St. Beat.
33	St. Bertrand de Comminges; Inn in Haute Ville.	See the church and remains of Lugdunum Convenarum below the town.—Ride up Val de Barouse to Mauléon. The mountains are pierced with caverns.
34	St. Gaudens.	Visit la Basse Grotte de Gargas, 5 m. from St. Bertrand, near Tyberan.—Cross the Neste to St. Gaudens.
34	St. Giron; poor Inn.	By Diligence to St. Martory, where hire a horse to St. Giron, on the Sallat, a bad cross road, but practicable for vehicles.
35	Foix.	By Remont and La Bastide de Seron.
36	Tarascon.	Visit Iron Mines of Vic de Sos.
37 { 38 {	Ax or Mt. Louis.	Cross to Puycerda and Bourg Madame by Port de Morens. Arrange with the Douane to take a horse across the frontier. Sleep at Bourg Madame or at Cabannes under the walls of Mt. Louis.
39	Prades.	Ride by Olette down Vale of Tet.
40	Prades.	Ascend Canigou: must start early. Next day to Perpignan and Narbonne.

#### § 14. PASSPORTS—CONVEYANCES—ACCOMMODATION FOR TRAVELLERS.

*Passports.*—Those who mean to enter Spain should obtain a Spanish Consul's visé at Bordeaux or Bayonne,—to prevent their being mistaken for refugees or smugglers; they should also provide themselves with the SPANISH HANDBOOK.

*Mallepostes* from Toulouse to Bayonne and from Limoges to Pau. *Diligences* run regularly from Bordeaux and Bayonne to Pau and Tarbes, from Toulouse to Bagnères and Tarbes, which is the point of concentration for conveyances from all directions; and in summer a constant communication is kept up between all the watering-places. The diligences, however, are ill



appointed, and very slow, and the routes they follow exceedingly circuitous. They are of use to the pedestrian in conveying his luggage from place to place.

*Inns* are far inferior to those in the German watering-places: the best are at Pau, Eaux-Bonnes, Cauterets, Luz, and Bagnères de Bigorre (by far the best), but they have all the fault of filth. Those at Barèges are inferior.

The *charges* vary much, especially for rooms, according to the season, rising exorbitantly when the places are full. Provisions are cheap.—Bed, 1 f. 50 c. to 2 f.; dinner (table d'hôte), 3 f.; breakfast à la fourchette, 2 f.; tea or coffee, 1 f. 50 c. On ordinary occasions the traveller's expenses ought not to exceed 8 f. per diem; and if he stop a week or longer in an hotel, he may easily bargain for 6 f. The chance-traveller is often asked 3, 4, or 5 f. for the worst bed-room for a single night during the season.

		Fr.	cent.
<i>Expenses at Bagnères de Bigorre.</i>	Board and lodging at an hotel for a month or 6 weeks, per diem . . . .	5—6	0
	Calèche and 2 horses . . . .	16—18	0
	A horse, exclusive of feed . . . .	3—4	0
	"    "    for a month . . . .	60—80	0
	A room in the town . . . .	1 f. 50 c. to 2 f.	
	Bath at a fixed hour . . . .	1	0
	Warm linen . . . .	0	10
	Chairmen (porteurs) . . . .	0	40

Izard venison, game, ortolans, truffles, mountain-trout, green figs, and strawberries, are among the delicacies which await the traveller in the Pyrenees.

"The remote valleys—Val d'Aran, Val d'Aure, and all those on the Spanish side—are miserably off for inns; travellers should always take provisions thither, or at least white bread, as the rye-bread, which can alone be procured, is apt to disagree with strangers."—*J. J.*

*Riding horses*, or rather ponies, very unprepossessing to look at for the most part, yet hardy and capable of work, and well used to the mountains, are kept at all the watering-places. The charges for them are moderate, viz., 5 f. a day, including the feed, or 3 f. paying the forage, which it is not advisable to do. It is the custom of the French visitors at the baths to unite in large parties, and invade some quiet valley, or interesting point of view, in troops of cavalry 50 or 60 strong, and to establish there a pic-nic. Very little regard is paid by these riotous assemblages to the beauties of nature. Awakening the echoes with the loud cracks of the whip with which they urge on their jaded hacks, they scour along the rough roads, up hill and down dale, attired in the most fantastic costume—men and women wearing the red sashes of the peasantry, and broad-brimmed felt hats; while even the ladies assume neat white pantaloons, sometimes set off with boots and spurs.

*Guides*.—There are very excellent and trustworthy professional guides, well acquainted with the mountains, and many of them capital mountaineers and skilful sportsmen; though not, perhaps, so good as the guides of Switzerland or Savoy. The best are met with at Eaux-Bonnes, Cauterets, Luz, Bagnères de Bigorre, and Luchon. A guide receives 5 f. a day, feeding and lodging himself. A horse must be provided for him, unless the traveller is willing to be retarded by his following on foot.

For return-money, 4 f. a day each for horse and man, until the guide can reach his home from the place where he is dismissed, is the fair allowance; but 5 f. are generally asked.

*Chaises à Porteur.*—There is scarcely an excursion off the high-road, however distant, or a mountain-top, or other spot, however difficult of access, which ladies may not reach by the aid of a chair on poles. Each lady will require from 4 to 6 chairmen; the cost is 15 f. a day, and 3 or 4 f. pour boire. This conveyance has been pronounced by a lady traveller "at once the gentlest, safest, and most agreeable mode of conveyance imaginable. The chairmen will go anywhere and everywhere; and instead of being rocked and jolted in a dislocating machine, those who cannot walk, and fear to ride, are carried about like petted children, without the risk of fatigue or the probability of danger."—*Mrs. Boddington.*

### ROUTE 70.\*

ORLEANS TO TOULOUSE BY CHÂTEAUX, LIMOGES, AND MONTAUBAN.

570 kilom. = 353 Eng. m.

*Railway*—Orleans to Vierzon, 80 kilom.; opened 1847. A temporary bridge carries the line across the Loire. It nearly follows the line of the post road.

The tunnel of l'Allouet is 1236 mètres long, and is lighted by 18 openings.

*Malleposte* to Limoges in 20 hours; thence to Toulouse in 25 hours. Diligences daily. This is not an interesting road.

An avenue of trees leads from the bridge of Orleans to the suburb St. Marceau, abounding in country houses; and a little further on, the industrious village of Olivet (3250 inhab.) is reached. Here the river Loiret is crossed by a bridge, about 2 m. below its source, and 5 or 6 above its termination in the Loire. The *Château of La Source*, the residence of the banished Lord Bolingbroke, near this, is described in R. 48. Below the bridge, between it and the Château de Ponty, on the l. bank, it is pretended that the assassination of the Duc de Guise by Poltrot took place (see p. 181): he was conveyed to Caubray, where he breathed his last.

Our road, as far as Vierzon, traverses the district of *la triste Sologne*,

noted for its barrenness; a large part of it being waste land, heath, and common; a dead flat of hungry sandy gravel, the surface slightly varied, and the scenery monotonous. The name Sologne (*Segalonia*) has been derived from "segale," seigle, barley, the crop chiefly produced on its unprofitable soil (?)

21 La Ferté St. Aubin. At the entrance of this village, on the l., stands the Château of Lowendahl, named after a Danish general who served in the armies of France along with his friend Marshal Saxe, and was made Maréchal de France for his share in the capture of Bergen-op-Zoom. It now belongs to the Prince d'Essling, son of Marshal Masséna. It is a low building, surrounded by water. The name *Ferté*, an old form of fortifié, denotes the existence, in ancient times, of a castle, embattled and fortified by royal permission, granted to the seigneur.

12 Les Gyons, Dépt. Loire et Cher.

11 Nouan le Fuzelier.

12 Salbris.

9 La Loge.

14 Vierzon (*Inn*: H. des Messageries), a town of the Dépt. Cher, and of the ancient province of Berry, enlivened by the Canal de Berry, which passes through it, running side by side with the river Cher. By means of it the iron of Berry, manufactured in furnaces not far distant from the town, is exported; and coal is brought hither to smelt it. Population 4700. Here the road to Bourges strikes off to the l. (R. 103). Its

\* The Editor has not travelled this route beyond Vierzon, and will be glad of corrections or additional information from those who have.





P. 247.

La Pouteraie. (H. Bazile - dirty-) This town  
retains a great part of its' old fortification  
including a curious Gateway - tower - There  
is a good church chiefly 12<sup>th</sup>. century with  
an early crypt and a singular West Doorway

(J. H. P.)



*Cathedral* is one of the finest in France. At Vierzon the tiresome Sologne has terminated; the valley of the Cher is rather cheerful, and on its borders are some vineyards. The Evre and the Cher are crossed on quitting Vierzon.

10 Massay.

16 Vatan. 12 m. N.W. of this is the *Château de Valençay* (see page 189).

14 Maison Neuve.

At Bourg Dieu, or Déols, situated within  $1\frac{1}{2}$  m. of Châteauroux, are the ruins of an ancient monastery, and a church containing, in a crypt under the altar, a curiously carved marble sarcophagus.

16 *Châteauroux*. *Inns*: La Poste (Ste. Catherine), clean, and people attentive; H. de France. This town, chef-lieu of the Dépt. Indre, containing a population of 13,847, is of little interest to the traveller, but of considerable industrial importance, owing to its extensive cloth manufactures, the sale of which is estimated at 4 millions of francs yearly. The wools of Berry are almost exclusively used in their fabrication. Some trade is also carried on in iron, there being more than 40 iron furnaces in the department. The *Castle*, on an eminence above the Indre, close beside the modern Préfecture, is a gloomy building, flanked by turrets, probably of the 16th cent. It was the prison, for 23 years, of the unfortunate Clémence de Maillé, Princesse de Condé and niece of Richelieu, who here ended a life of suffering, 1694. The Grand Condé, her husband, repaid her devotion to him, and ill-requited affection, by procuring from Louis XIV. an order for her imprisonment; and his last dying request to the king was, that she should never be set free. Her grave in the church of St. Martin was violated 1793. The town owes its name to an older *château*, built in the 10th century by one Raoul de Déols. One of the old *town gates*, a venerable structure, still remains.

General Bertrand, who accompa-

nied Napoleon to St. Helena, was a native of Châteauroux.

*Diligences* go hence to Bourges, and to Tours by Loches. (R. 56.)

15 Lothiers, a dreary country of heath, to H. de la Promenade, very

14 Argenton, a town of 4,000 inhab., on the Crèuse: it had once a large castle flanked by 10 high towers, dismantled by Louis XIV., and farther reduced to ruin in recent times. *but still very interesting*

15 Le Fay.

25 La Souterraine. *Noto*

~~16 Morterolles.~~

~~17 Ville au Brun.~~

~~17 Morterol.~~

12 Chanteloube.

15 Maison Rouge.

14 LIMOGES (*Inns*: Boule d'Or, dirty; H. Richelieu, not much better; H. de Perigord), the capital of the ancient province of Limousin, at present chef-lieu of the Dépt. Haute Vienne, is a commercial and manufacturing town, situated on the rt. bank of the Vienne. Population 27,611. *but good in other respects*

It is very picturesque in its ancient street architecture, but has few curiosities to show to the passing stranger. The Revolution swept away the greater number of its churches, many of which were curious from their antiquity. Of those which remain the most interesting are

The *Cathedral* of St. Etienne, begun in the 13th cent., and slowly continued down to the 16th, when the work came to a stand; and the building has since remained a mere fragment, consisting of the *Choir*, the N. transept, and two compartments of the nave, now blocked up by a common partition wall, while at the spot to which it ought to have extended rises an isolated belfry, now in a very insecure condition, separated by a wide gap from the rest of the edifice. Under this tower is a Romanesque porch belonging to an older cathedral. The church is built of granite, and terminates in an apse. The interior is not remarkable in itself, but contains a *Jubé*, or rood-loft,

removed without reason, 1789, from its proper place between the choir and nave, to one side of the nave. It is a curious jumble of flamboyant Gothic ornaments and tracery, with sculpture in the style of the Renaissance: (date 1543.) It has been seriously mutilated, and its niches robbed of their statues, but contains curious bas-reliefs, among which are represented the Labours of Hercules. Its construction is attributed to Bishop Langeac, whose *Tomb* is remarkable for the richness and elegance of its decorations, far superior to those of the Jubé. It was prepared for him before his death, 1541, and includes some admirable bas-reliefs, well worth examination in spite of their mutilations; among them one, representing "Death on the White Horse," is much praised. Two other monuments, that of Bishop Regnault de la Porte, of the 14th century, and of Bernard Brun, his nephew, deserve notice.

*St. Michel-aux-Lions* is the most conspicuous object in the town, owing to its tall and graceful tower and spire, planted on the highest ground, surmounting the other buildings. This church, erected 1364, is named from the rudely sculptured figures of lions which ornament its porch; the lightness and height of the 8 lofty pillars supporting the roof are alone remarkable in the interior.

An old *Cross* of granite, in front of the church of *St. Aurelian*, deserves mention for the elaborate workmanship bestowed on it, which has recently been concealed under a coat of oil paint.

The *Episcopal Palace* is a handsome building of granite, with a fine *Garden* attached to it.

Although *Limoges* was an important place in Roman times, under the names *Lemovices* and *Augustoritum*, there are no remains of Roman buildings. The only trace of the amphitheatre, to which Molière alludes in *M. de Pourceaugnac*, Act I., Scene 6, is the name *Les Arènes* given to a

burial-ground. Its site is nearly covered by the *Place d'Orsay*, on one side of which runs a terrace whence there is a view over the valley of the *Vienne*. A Latin name, "*Aqua lenis*," is said to be retained in the *Fontaine Aigoulène*, and its water is supplied through a Roman conduit.

The ancient fortifications of *Limoges* have been thrown down, planted, and converted into boulevards and public walks; nothing therefore remains as a relic of that terrible siege (1370) and capture by assault of the place by the Black Prince, who, irritated at its revolting from him, through the treachery of its bishop, swore by the soul of his father that he would have it back again. Too ill to ride on horseback, he directed the operations from a litter, and having forced a breach by blowing up a tower, entered through it, and denying quarter to its wretched inhabitants, allowed 3,000, men, women, and children, to be massacred—a blot on the fair fame of his heroic career, the verge of which he had already reached, for the hand of death was upon him, and he breathed his last six years after.

*Limoges* is distinguished by having been the birth-place of the upright chancellor d'Aguesseau, born 1688. Vergniaud, the Republican orator, the leader of the Girondins, beheaded by Robespierre, 1793, Marshal Jourdan, the conqueror at Fleurus, and Dupuytren, the surgeon, were also natives. *Limoges* likewise produced in the 15th and 16th centuries a series of artists, among whom the names of Laudin, Noel, Leonard, Courtois, Rexmore, are conspicuous, eminent for the beautiful paintings in *enamel* which they produced, still so highly esteemed all over Europe. Nayllier, the last master in this *genre* of art, died 1765, and the art died with him. It appears to have originated as early as the 12th century, but was at its acmé in the time of Francis I. The private cabinets of



M. Germeau and M. Maurice Ardent, of Limoges, contain some very remarkable specimens of enamels.

The *Manufacture* at present most prevalent here is that of *porcelain*, due to the discovery in this neighbourhood (at St. Yrieix) of the *kaolin*, or pure white porcelain earth, consisting of the decomposed felspar, arising from gneiss, which alone furnishes a fit material for the manufacture. The substance appears to owe its origin not to a mere disintegration of the gneiss, but to an electro-chemical decomposition, and combination with neighbouring rocks, especially such as are ferruginous. Sèvres is supplied hence with the kaolin, and nearly 2000 persons are employed in and about Limoges in making china. There are also some cotton and woollen mills.

The Limousin horses are a celebrated breed, in much request for the French cavalry; they are reared in the prairies bordering on the Vienne.

A *malleposte* goes hence to Toulouse, another to Périgueux, Auch, and Pau.

*Diligences* to Toulouse, Bordeaux, Poitiers, Angoulême, Clermont, Moulins.

The road from Limoges to Bordeaux, by Périgueux, is described in Route 71.

At the town St. Junien, 18 m. from Limoges on the way to Angoulême, is a very curious *church* of the 11th century, containing at the back of the high altar a curious sarcophagus of white marble, adorned with reliefs in the Byzantine style of art. It contains the relics of the saint, much visited by devout pilgrims. In the lower part of the town near the bridge is a chapel of the 15th century of *Notre Dame*; and 1 m. out of the town, on the borders of the Vienne, are the ruins of *St. Amand*. M. Mérimée observed in its transept a basin hollowed out of the rock, supplied by a spring of running water, into which little pieces of

bread had been cast by the peasants, as offerings to St. Amand, who is believed still to work miracles, though his shrine has been destroyed for ages. This was in 1836-7.

At Boisseuil, 7 m. from Limoges, we leave about 1 m. to the rt. the ruined *Castle of Chalusset*, a curious example of the art of fortification in the middle ages, situated on an isolated rock at the junction of two streams. It must have been very strong both by its natural position and its outworks. It has been referred to the 12th century.

20 Pierre Buffière. Arthur Young praises much the beauty and variety of the country to Brives, hill and valley, a quick succession of landscapes.

21 Beausoleil.

18 Uzerche, a picturesque little town on a conical hill, converted into a peninsula by the bend which the Vezère makes round it. It has a curious *church* on the crest of the hill, surrounded at the E. end by 5 apsidal chapels. Under it is a *crypt*, containing the tomb of St. Coronat, in a niche, closed in front by a wooden railing. Insane persons are shut up within it for a night, in the belief that they will thereby recover their reason!

The road to Tulle here turns off to the l.

[*Tulle* (*Inn*: H. de Lyon), a town of 8000 inhab., singularly placed, in the fork of a deep narrow valley. A fresh bubbling stream runs through it, bordered for a considerable distance with houses. The *cathedral* had a slice cut from it, in Revolutionary times, to make way for a public walk.]

About 10 m. W. of Uzerche is the *Château de Pompadour*, anciently the residence of a noble family, several of whom were governors of the province of Limousin, whose name was never sullied, until, after the extinction of their line (1722), it was bestowed upon the mistress of Louis XV., the daughter of the bankrupt butcher Poisson.

25 Donzenac.

10 Brives (*Inn*: H. de Bordeaux, clean, comfortable, and a good cook, who makes capital pâtés) enjoys a fine situation in the valley of the Corrèze; but its favourable appearance at a distance is not realised in its interior, which contains nothing remarkable but an ancient *Gothic house* attributed to the English: it is said to have been the residence of the governor. Brives is the birth-place of the Cardinal Dubois, son of an apothecary, who became tutor and afterwards minister to the regent duke of Orleans; and of Marshal Bruñe, one of the generals of the Republic, assassinated at Avignon 1815.

The culture of the vine and of maize flourishes near this.

The road has now reached a hilly country: it passes within a short distance of the castle *de Noailles*, cradle of the noble family who derive their ducal title from it, now in ruins; a modern château has been built not far off. The old feudal *Castle of Turenne*, situated about 2 m. to the E. of the road, on the Tourmente, a tributary of the Dordogne, gave a name to another great family, illustrious by deeds as well as by descent: the Ducs de Bouillon obtained the domain and viscounty of Turenne by alliance. Within its walls, the wife of the Great Condé, a fugitive with her son from the pursuit of Mazarin, was received amidst a crowd of enthusiastic partisans of the Fronde, in 1650, and sumptuously entertained for 8 days; during which, taking counsel with the Ducs de Bouillon and de La Rochefoucauld, she planned the memorable rising in the South which was called the civil war of Guienne. She here summoned her vassals and retainers to mount the fawn-coloured scarf, and to rally round her for the rescue of her husband from prison. At the order of the Duc de Bouillon the tocsin was sounded in the 400 villages of his vicomté of Turenne, and the peasants at once

flew to arms and flocked round his standard.

20 Cressensac (Dépt. Lot).

Truffles flourish in the uncultivated ground around this village.

16 Souillac, a miserable little town in the deep valley of the Dordogne, on its rt. bank.

After crossing the river, a steep hill, nearly 3 m. long, requires to be surmounted, in effecting which the postmaster is authorised to attach a pair of oxen to all four-wheeled carriages. 2 m. on the l. is the village and château of La Mothe Fénélon, not the birth-place, as some have stated, of the author of *Télémaque*, but a property belonging to his family. A hilly country, arid, barren, and uninteresting, all the way to Cahors.

16 Peyrac.

18 Pont de Rodes.

17 Pelacoy. Near this is Murat, and a little beyond it La Bastide, the birth-place of Joachim Murat, general of cavalry, and king of Naples. Hé was the son of an aubergiste who was steward in the family of the Talleyrands.

A long but gradual descent of nearly 5 m. leads down into the valley of the Lot.

The very distant outline of the Pyrenees, 150 m. off, may be distinguished in clear weather near

16 Cahors. (*Inns*: H. des Ambassadeurs, not very clean, but excellent cook; Trois Rois; de l'Europe.) Cahors, the *chef-lieu* of the Dépt. le Lot (population 12,050), is situated on the top and round the base of an escarped rock, on a wide sweeping bend of the river Lot. It is a very ancient town of narrow streets, full of antique edifices, to which a new quarter has been added. The name comes from its ancient appellation, *Divona Cadurcorum*, and there still exist the scanty remains of a Roman amphitheatre, and of a conduit, which conveyed water to it from the village St. Martin de Vern, through La





Page 257. Montauban - Hotel de L'Europe  
Good clean, and ~~compos~~ full of comforts  
the best Hotel in this part of France.  
(at Montauban)  
The Ch. of St. Jacques has a curious octagonal  
brick tower of the 14<sup>th</sup> century.



Roque, where are vestiges of the arches of an aqueduct.

The *Cathedral*, a truly fine edifice, consists of a large nave, surmounted by two hemispherical cupolas, in the ~~Romanesque~~ style; a portal and the choir are Gothic. The Bishop's Palace is now the Préfecture. The bishop originally bore the title of count, and enjoyed the privilege of wearing a sword and gauntlets, which he deposited on the altar when he said mass. When he took possession of his diocese, he was received at the gate of the town by his vassal, le Vicomte de Sessac, bare-headed, without cloak, with one leg bare, and the foot in a slipper, and was conducted by the count in that guise to his palace, and waited on by him there at table. This curious tenure had fallen out of use before the Revolution.

The surprise and capture of Cahors in 1580 was one of the most brilliant exploits of Henri IV. (when king of Navarre). He reached the town by a forced march of 30 m. under a burning sun, and posting his men in ambuscade among the walnut-trees, awaited the night-fall, when silently approaching the gate, he blew it up with a petard, and entered himself the seventh, followed by 700 men, and leaving 700 outside to check the arrival of reinforcements to the garrison. The bursting of the gate had alarmed the town, which was strongly guarded, and a shower of stones and tiles from every house-top assailed the Navarrese troops and their general. The combat was carried on throughout the night, and yet when dawn appeared, the assailants had gained but a very small footing. Henri was strongly advised to retire, especially when intelligence was brought of the arrival of succour to the town; but the king, setting his back against a shop, persisted in fighting on, exclaiming, "Ma retraite hors de cette ville sera celle de mon âme hors de mon corps." The reinforcements were driven back, but Henri

still had to struggle step by step, to lay siege to every street and almost to every house. It was not until the fifth night that Cahors submitted. Henri's soldiers, irritated by the resistance made by the garrison, put a great many to the sword.

On the open promenade de Fossé, in front of the college, is placed a statue of Fénélon, who was a student here. One of the *bridges* over the Lot is curious, being surmounted by 3 gate-towers, to defend the approach to the town. Cahors is the native place of Pope Jean XXII., whose name was Jacques d'Euze; his *Castle* is pointed out near the entrance to the town, on the side of Paris; also of Clement Marot, the poet, author of sonnets, ballads, &c. (1495), and page to Marguerite, sister of Francis I.

The country around produces a good deal of *wine*, which is not much ~~known~~ and *truffles* in abundance, ~~but very few~~ <sup>known</sup> <sup>but very few</sup> <sup>9000</sup>

21 La Magdeleine.

17 Caussade stands on the fertile plain watered by the Loire; it is a town of 5000 inhabitants, famed for turkeys stuffed with truffles.

In the next stage the river Aveyron is crossed, and we enter the wide and fertile plain of Languedoc, which extends to the foot of the Pyrenees with little interruption.

23 Montauban (*Inns*: H.<sup>2</sup> de France; ~~best~~, de l'Europe), chef-lieu of the Dépt. Tarn et Garonne, is a good-looking little town, with clean and wide streets, on the rt. bank of the Tarn, here lined by a fine quay, and crossed by a <sup>brick</sup> bridge, at the end of which stands the *Préfecture*, a square building with 4 turrets at its angles. ~~There is nothing to be seen in the town.~~ The *cathedral* is a large modern building of Italian architecture, with a frontispiece at the W. end.

"The *Promenade* of Les Terrasses on the borders of the Trescon, and on the highest part of the ramparts, commands that noble plain, one of the richest in Europe, which extends on one side to the sea, and in front to the Pyrenees, whose towering masses,

heaped one upon another in a stupendous manner, and covered with snow, offer a variety of lights and shades from their indented forms, and the immensity of their projections. This prospect has a sort of oceanic vastness, in which the eye loses itself; an almost boundless scene of cultivation; an animated but confused mass of infinitely varied parts, melting gradually into the distant obscure, from which arises the amazing frame of the Pyrenees, rearing their silvered heads far above the clouds.”

—*A. Young.*

Montauban is a flourishing manufacturing town, producing various kinds of woollen cloths, hair stuffs (cadis, molletons), which are exported to the colonies. It has 24,660 inhab., nearly one-half of them being Protestants, and there is a *Protestant College* here for the instruction of pastors.

In the 16th and 17th centuries Montauban was a stronghold of Protestantism, its inhabitants having early embraced the Reformed doctrines, and being prepared to defend them. It endured in consequence a very memorable siege in 1621, from the royal army led on by the favourite Luynes, who brought hither his master Louis XIII.; but instead of witnessing its fall, after nearly three months of fruitless assault, Louis and his minister were forced to withdraw, such was the obstinate bravery of the inhabitants and the skill of their governors. Under the reign of Louis XIV., and the influence of Madame de Maintenon, the Protestants of Montauban were singled out to suffer the direst persecutions inflicted by the so-called *Dragonnades*, or quartering of regiments of soldiers on them, who exercised every species of licence, inquisitorial tyranny, and cruelty, with the design of forcing them to become Roman Catholics.

At the farther extremity of the bridge over the Tarn we pass under an arch of brick into the extensive suburb of Ville Bourdon, founded by

the Protestants expelled from Toulouse in 1562.

We enter the grand route, from Bordeaux to Toulouse (R. 73), a little short of

22 Grisolles. The Garonne runs parallel with our road, at a little distance on the rt., through a plain of unequalled fertility. The British army, under the Duke of Wellington, passed the river, before the battle of Toulouse, by 2 pontoon bridges above the small town of Grenade on the l. bank nearly opposite Castelnau, 15 m. below Toulouse. The road crosses the river Lers, a little farther on. The capture of the bridge over it at Croix Daurade, by a gallant charge of the 18th hussars, on the day before the battle, secured a communication between the columns of the allied army, part of which marched up the rt. and part up the l. bank of the Lers, to attack the strong position of Marshal Soult.

12 St. Jory.

The approach to Toulouse lies over a bridge, flanked by two columns, thrown across the *Canal du Midi*, which, half encircling the town on the N. and E., joins the Garonne about a mile to the rt. of this bridge in the Faubourg d'Arnaud Bernard.

The *Obelisk* on the height to the l. marks the centre of Marshal Soult's position at the battle of Toulouse, which, though strongly fortified by redoubts and cannon, was carried by the Allies (see p. 259).

17 TOULOUSE.—*Inns*: H. Bibent; very good;—H. de l'Europe, Place Lafayette, good situation; newly furnished; very comfortable; good cuisine;—H. du Midi. L. Y. H. Casset.

In the midst of the great plain of Gascony and Languedoc, beginning at the very foot of the Pyrenees, and stretching from them nearly 100 m. N., stands Toulouse, the ancient capital of Languedoc, and now of the Dépt. of Haute Garonne. It is built on both banks of the Garonne, just above the point where the Canal du



Midi, connecting the Atlantic with the Mediterranean, falls into it, after winding round the N. and E. sides of the town. The river is crossed by a brick bridge connecting the city with the suburb St. Cyprien on the l. bank of the river.

It is far from being a handsome city; its streets are irregular and dirty, its houses and even churches of brick: and neither public nor private buildings are distinguished by special architectural beauty: but it ranks as the seventh city in France, from the number of its inhabitants (77,400), and the extensive trade and commerce of a provincial capital, which it enjoys. It is interesting from its historical souvenirs, as the capital of the kingdom of the Visigoths from 413 to 507, when it was destroyed by Clovis on the battlefield of Vouillé near Poitiers; as the place where the art of the Troubadours was encouraged at the gay court of its counts; as the scene of the papal crusade against the Albigenses, headed by an English leader, and as the seat of the ancient Parliament of Toulouse. But the Revolution has, as usual, done its worst to extirpate all tangible relics of bygone days.

The *Place du Capitole* (once Place Royale), a handsome though unfinished square, consisting of three sides of regular modern buildings and one of old and irregular structures, is the centre of bustle and traffic; the chief market-place, and the point of departure of the main thoroughfares. It is named from *le Capitole* or Hôtel de Ville, so called either from the tradition that in the time of the Romans the Capitol of the Tolosates may have stood here, or from the meetings of the civic chapter (capitolium), whose members were also called capitouls, on this spot. The building presents externally a modern front, finished 1769, with eight columns of red Pyrenean marble in the centre, and includes, besides the municipal buildings and the archives, the

*Theatre* in the l. wing. The principal apartment, running along nearly the whole length of the first floor, is the *Salle des Illustres*, or hall of the worthies of Toulouse, so called from 38 terra-cotta busts of men of note, born in and near Toulouse, or connected with it, each with a pompous Latin inscription below it, filling as many gilt niches in the walls. In real truth a great many, as Riquet, engineer of the canal du Midi, Pope Benedict XII., &c., have no connection of birth with the town; and many more, though really citizens, have no claim to renown beyond its walls. Among those of most general celebrity may be mentioned Raymond St. Gilles, Count of Toulouse, one of the leaders of the first crusade; Cujas, the lawyer ("*cujus* merum nomen plus laudis amplectitur quam quælibet oratio potest"), who was rejected by the university here when a candidate for the professorship of law; and P. Fermat, the mathematician, inventor of the integral calculus, b. 1608.

In this hall are held every year the meetings of the *Société des Jeux Floraux*, deriving its origin from the ancient troubadours, but founded, it is said, by one Clémence Isaure, a Toulousan lady, who revived the science of the "gai Scavoir" in the 14th centy. (1333). Her very existence, however, is not a little doubtful, as there is no mention of her in the archives of the town, though her statue is preserved in the Capitole. In spite of these doubts, the society has adopted her as its patroness and founder, and every year at the beginning (3rd) of May, after making a pilgrimage to the church of the Daurade in which her tomb once was, it distributes, to various competitors, prizes consisting of golden and silver flowers, the violette, amaranthe, eglantine, souci, and lis, for the best original compositions in verse, and essays in prose, for which the directors give the subject. The society maintains about equal importance, and the prize compositions

have nearly the same literary value, as those of the bardic meetings held in Wales. Although the existence of Clémence is uncertain, there is no doubt of the antiquity of the society, and it claims for itself to be the oldest literary institution in Europe, dating from 1333. Indeed it appears that in that year a number of Troubadours, or Mainteneurs du Gai Seavoir, citizens of Toulouse, met in a field near the town to distribute prizes to the composers of the best verses.

In the same room with the statue of Clémence Isaure is preserved *the axe* with which Henri, Duc de Montmorency, the victim of the implacable Cardinal Richelieu, and one of the last of the great vassals of the crown of France, was decapitated. It is a sort of huge carving-knife, and was made in the town. The execution took place 1632, in the first court of the Capitole, at the feet of the statue of Henri IV., in whose reign that part of the building was erected. In the 2nd court on the rt., two barred windows mark the dungeon in which the Duke was confined, and belong to the oldest portion of the building. Here also is the old *Salle de Consistoire*, with ornamented roof and chimney (? if still existing). The council chamber of the senators of the town, or capitouls, equivalent to the échevins elsewhere, no longer exists.

The antiquity of the municipal privileges of Toulouse, and of the meetings of the magistrates, who were elected by the people themselves, and who were recognised by Raymond V. as far back as 1152, deserves notice. These rights, of five centuries' duration, were infringed, in spite of the remonstrances of the citizens, by Louis XIV., who caused the capitouls to be appointed at Paris by royal ordonnance.

The *Place du Capitole* is a good starting-place from which to visit the chief curiosities of the town.

*L'Eglise St. Sernin*, the largest,

oldest, and most perfect ecclesiastical edifice here, is a plain building of brick and stone in the Romanesque style, dating from the year 1090, when it was finished and consecrated by Pope Urban II. It is conspicuous for its lofty octagonal *Tower*, formed by five tiers of arches, each story less in size than that below it, the lower tiers surrounded by circular arches, the two upper by angular ones. The upper part is of the 14th century, the lower corresponds exactly in style with the church below. Of its two S. *porches* one is distinguished by a curious early bas-relief over the door in the Byzantine style, and by the capitals of its columns representing the murder of the Innocents, expulsion of Adam, &c.; the other, a double portal leading into the S. transept, bears carved capitals of the seven deadly sins. By the side of it, within a modernised chapel, open to the air, are several tombs of early counts of Toulouse. The interior is remarkable for its very long *Nave* (not unlike that of St. Albans, but flanked by double aisles). Its cradle-vaulted roof is supported by plain angular piers, having engaged columns, and above its circular arches runs a triforium having slight double pillars with delicately cut capitals, continued all round the transepts, and lighted by windows on the outside. The E. end is semicircular and its arches round; close set columns support the vault above the high altar, painted with the colossal figure of Christ and the symbols of the four evangelists. From the aisle behind it project five apsidal chapels, decorated with curious carvings of saints, and legends in wood. Here also is a model of the church as it stood before the Revolution, showing that it formed an isolated fortress, apart from the town, walled in by towers and battlements. Some curious Byzantine bas-reliefs in white marble, said to have belonged to the old church of St. Sernin, built by Charlemagne in the 8th century (?), are let into the wall of the aisle be-



hind the choir; they represent our Saviour, angels, and saints. The *Crypt* under the choir, modernised in the 15th century, was the place of deposit of relics in great number and esteemed of immense value. Before the Revolution this church indeed boasted of possessing the bodies of no less than seven of the apostles, one of them being a duplicate of St. James, another of his bodies being preserved at Compostella! This motto was blazoned over the entry—*“Non est in toto sanctior orbe locus.”*

The wooden stalls of the choir are well carved in the style of the 16th century.

The *Church of St. Taur*, situated in the street leading from the Capitole to St. Sernin, derives its name from the wild bull to whose horns the body of the martyr St. Saturnin was bound by his heathen persecutors. The struggles of the furious animal having detached it from the cords, on this spot, a church was in consequence erected. That at present existing has nothing remarkable but its flattened fronton belfry, surmounted by angular arches.

The *Church of the Cordeliers*, a brick building of great loftiness, erected in the 14th cent., is now turned into a magasin de fourrage, and filled with hay; that of the *Jacobins*, surmounted by a conspicuous brick tower, rising in arches having straight angled heads, is of vast size, and of brick like the other churches. It has become a barrack, and is divided by floors, the lower story serving as a stable for artillery horses.

Issuing out of the Place du Capitole by the Rue de la Pomme, we come to the *Cathedral*, or Eglise St. Etienne, remarkable for the irregularity and want of concord in all its parts. The large and beautiful rose window is out of the line of the centre of the main portal immediately below it; the centre of the nave is parallel with the side aisle of the choir, and its two walls do not correspond. The *nave* was built by

Raymond VI., Comte de Toulouse, in the 13th cent., at a time when he was favouring the heretical Albigeois, and was excommunicated in consequence by the Pope. Raymond was besieged within the walls of Toulouse by Simon de Montfort, Earl of Leicester, appointed by Innocent III. head of the crusade against the heretics. He met his death in one of the suburbs of the town, from a stone discharged by a mangonel, whilst he was endeavouring to repel a sally of the citizens in the 9th month of the fruitless siege, on St. John Baptist's day, 1218. Count Raymond's construction is the oldest part of the church, and was doubtless intended to be removed by those who raised the very elegant ~~Gothic~~ *Choir*. It was begun 1272, but not roofed until 1502, by the Cardinal d'Orléans, son of the brave bastard Dunois, who built also the clocher and the singular isolated column called *Pilier d'Orléans*, which fronts you as you enter the nave. There is some good painted glass in the choir. The tower is singular from its form, having two broad sides and two narrow.

In the Rue des Arts is the *Musée*, deposited in the desecrated church of the Augustins, and comprising a large collection of bad paintings, copies, &c., filling two rooms, one of them being the old church itself, which has been re-roofed and re-floored. The best pictures are a *Perugino*, St. John Evangelist and St. Austin; a *Vander Meulen*, Siege of Cambray; and a curious painting of the eight capitouls forming the town council of Toulouse in 1645. A good collection of *casts* from the antique is placed in the chapter-house, an elegantly vaulted and groined apartment of the 16th cent., supported on light pillars. The *Collection of Antiquities* in this museum is the most interesting sight in Toulouse; it is placed under the admirable direction of M. du Mège, who may be considered its founder. The locale which it partly occupies is the elegant Gothic *Cloister* of the

St. Ambroise.

14

old church, the traceried arches of which are supported on pillars of marble in pairs, producing an effect not unlike the Campo Santo at Pisa.

In addition to a small series of Egyptian sculptures, there are numerous inscriptions, Roman and Gallic, votive altars, &c., with fragments of statues and of marbles, from various places in Languedoc and the Pyrenees, showing that the quarries of the Pyrenees were worked by the Romans. The most remarkable part of the collection, however, is the three following series, forming an almost uninterrupted chain in the history of art, from the Gallo-Roman period to the Renaissance or cinquecento through the Gothic period.

1st. A very large collection of antiquities dug up near the small town of Martres, on the l. bank of the Garonne, a little below St. Gaudens, and proved by M. du Mège to be the ancient Calagorris. In consequence of the excavations undertaken at his suggestion, it has become a Gallic Pompeii. The discoveries consist of a series of about 40 busts and medallions of Roman emperors, and of members of their families, from Augustus and Claudius down to Gallienus, forming a tolerably complete portrait gallery;—of a number of small statues of gods and goddesses, of good execution, especially in the drapery, including Isis, Venus, Diana, Jupiter, Serapis, Esculapius, Harpocrates; a series of bas-reliefs, much mutilated, representing the labours of Hercules; a mosaic of the head of a river god; a number of Corinthian capitals, friezes, and other architectural ornaments. Among the bronzes are a pair of *wheels* and the *pole of a Roman chariot*, very rare and interesting objects, dug up at Fa, near the Bains de Rennes. Two bas-reliefs with inscriptions relating to the two Emperors Tetricus, have given rise to much discussion among antiquaries. They were found at Nérac.

2nd. A collection of works of art of the middle ages, consisting of bas-

reliefs, statues, monuments, portals, and a long series of curiously carved capitals of columns obtained from ecclesiastic edifices and Christian monuments destroyed or desecrated at or since the Revolution, beginning with early Christian tombs, sarcophagi, and coffins, covered with sculpture rude and debased in point of art, but showing Roman influence, bearing Christian symbols combined with heathen subjects, the cross, X, P, the vine-branch, &c. One of these brought from the outer wall of the church of La Daurade, where it went by the name of *Tombeau de la Reine Pedauque* (pes aucæ, queen goose-leg), bears six bas-reliefs of the multiplication of loaves and fishes, the raising of Lazarus, and other Scriptural events, which were adopted as types symbolical of the goodness of God, and of the resurrection, by the early Christians. Another sarcophagus from St. Orens, at Auch, displays, with similar symbolical allusion, the sacrifice of Isaac, and Lazarus deplored by Martha, with Adam and Eve. Others of these tombs come from the very ancient cemetery of St. Saturnin in Toulouse. Several bas-reliefs which ornamented a portal of that church are preserved here; one represents 2 females seated, their legs crossed; one holds a ram, the other a lion: the names of these two signs of the zodiac being written at the side, and below one of them, "*Hoc factum est in tempore Julii Cæsaris.*" They are supposed to have formed part of a Zodiac, or Julian Calendar, attached to that church. It is not improbable that they were executed in the time of Charlemagne. From St. Sernin also comes a carving of a hawk, with a human head, treading under foot a monster, inscribed "*Crocodilus:*" the allegory seems derived from Egypt. A *pedestal in white marble*, bearing 4 figures in relief, 2 of them saints with palms (St. Justus and Rusticus), the Virgin, and a crowned king, supposed to be Charlemagne,



holding a lotus-headed (?) sceptre, and wearing a cross on his breast, was brought from the Cathedral of Narbonne, of which he was the founder. The curious *Portal of the old Church of La Daurade*, pulled down in 1812 when the monastery attached to it was converted into a tobacco manufactory, has been re-erected here, as nearly as possible in its original condition. Its circular arch is supported by statues, instead of pillars: attached to it are 4 figures in bas-relief,—David playing on the Harp, and the Virgin and our Saviour, with a king and queen, founders or benefactors of the church.

In like manner, the *Portal of the Cathedral Chapter House*, at Toulouse, decorated with figures of the Apostles in bas-relief, has been removed hither.

Here are numerous statues, partly coloured and gilt, of Christ, the Virgin, Apostles, and Saints. A series of more than 60 capitals of columns, almost all differing in form and decoration, the greater part ornamented with subjects minutely carved from the Bible or Legends of Saints. The casts of sculptures from the church of St. Victor at Marseille, and from that of Moissac, merit attention, as well as many monumental effigies of noble knights and high-born dames, and holy ecclesiastics, mitred abbots, bishops, and several archbishops of Toulouse, here deposited.

The museum also boasts of possessing the *ivory horn* of the renowned *Roland*, richly carved—formerly preserved in the treasury of the church of S. Sernin.

A third division of the museum contains *Monuments of the Renaissance*, including casts from a portion of the carved wood screen-work in the Cathedral of Auch, and church of St. Bertrand de Comminges. A Pietà, in white marble, from the Eglise des Carmes at Carcassonne, several fragments of statues, bas-reliefs, &c. by *Bachelier*, a sculptor of Toulouse, and pupil of Michael Angelo, 1485—1567:

a relief, in white marble, of boys dancing, by *Pierre Paul Puget*, is very clever.

Toulouse possesses several other churches, scarcely worth visiting.

The plastered and stuccoed church of *La Daurade* derives its name from the *gilt* mosaics of a former church, of which no traces are now left: the monastery attached to it, on the quay, a little below the bridge, is now the Manufacture Royal de Tabac.

There are numerous specimens in the streets of the grand but exaggerated architecture of the Renaissance; one, perhaps the best, is attributed to Primaticcio's design, and is situated near the bridge over the Garonne.

If the stranger will continue past the bridge, up the street, on the rt. bank of the Garonne, called Rue du Couteliers, he may view the *Hôtel St. Jean*, of Italian architecture, that called *Hôtel Daquin*, or more commonly *Maison de Pierre*, a gaudy specimen of the style of the Renaissance, and nearly opposite an ornamental portal, in much better taste, designed by *Bachelier*, already mentioned.

Still farther on is the *cannon foundery*, occupying the ancient nunnery of Sainte Claire; and a little beyond it *Le Couvent de l'Inquisition*, an obscure edifice retaining its old ill-omened name, but now belonging to a religious brotherhood engaged in education. It is memorable for crimes which stain the annals of Toulouse. Here alone, in France, was that accursed tribunal allowed to take root. Here, as in Spain, it brought with it its usual train of tyrannous atrocities—torturing, imprisoning, roasting at the stake the living, tearing up the dead from their graves, or refusing Christian burial to persons deceased. It was first established here, in the time of Count Raymond VII. (1221), by the ecclesiastical council assembled to exterminate the heresy of the Albigenses, which, at the beginning of

the 13th century, had overspread the entire S. of France, under the connivance or encouragement of Raymond VI. of Toulouse, one of the wealthiest and most powerful princes of his time. St. Dominic himself, the founder of the Inquisition, visited Toulouse to water the thriving offshoot from his own terrible foundation; the cell which he occupied was shown until 1772.

The *Place de Salin* was the scene upon which the French Autos da Fé were enacted.

The house No. 50, Rue des Filatiers, was in 1762 occupied by a respectable Protestant family, named Calas. The father, Jean Calas, carried on the trade of draper, and prospered, in good repute with his neighbours, and in contentment at home. The only exception to his domestic happiness was the conversion, by a priest named Durand, of his third son, Jean Louis, to the Roman Catholic faith. The youth had, in consequence, been sent from home, receiving a small allowance from his father.

On the night of the 13th-14th October, 1761, cries were heard issuing from the house of Calas, and the chief of police, with an escort of soldiers, on entering it, found near the door the dead body of the eldest son of Calas, Marc Antoine by name.

A procès verbal was prepared, declaring that he died, hung by himself; which there can be no doubt is the truth, for he was of a melancholy temperament; but a malicious cry was raised in the crowd by a voice unknown, that he had been strangled by his father, to prevent his abjuring Calvinism as his brother had done, and the report spread and was partly believed by the fanatic Toulousans. The elder Calas was in consequence accused of the murder of his own son, before the Parliament of Toulouse; and that ancient and venerable assembly, without listening to one-tenth of the evidence which had been prepared, and without any proof of his

guilt, sullied its reputation for justice by condemning him, at the age of 63, to be tortured and broken on the wheel, and his remains burnt and scattered to the wind.

The act of condemnation, in virtue of which this atrocious judicial murder was committed, runs as follows:—  
“ La Cour le condamne à être livré aux mains de l'exécuteur de la haute justice, qui, tête, pieds nus, et en chemise, la hart au col, le montera sur le chariot à ce destiné, et le conduira devant la porte principale de l'Eglise de Toulouse; où, étant à genoux, tenant entre ses mains une torche de cire jaune allumée, du poids de deux livres, il fera amende honorable, et demandera pardon à Dieu, au Roi, et à la justice, de ses crimes et méfaits; ce fait, le remontera sur le chariot, et le conduira à la Place St. George de cette ville, où, sur un échafaud, qui y sera à cet effet dressé, il lui rompra et brisera les bras, jambes, cuisses, et reins; ensuite l'exposera sur une roue qui sera dressée tout auprès du dit échafaud, la face tournée vers le ciel, pour y vivre en peine et repentance de ses dits méfaits, servir d'exemple, et donner de la terreur aux méchants, tout autant qu'il plaise à Dieu de lui donner la vie; et son corps sera jeté dans un bucher préparé à cet effet sur la dite place, pour y être consumé par les flammes, et ensuite (ses cendres) jetées au vent. Préalablement le dit Calas sera appliqué à la question ordinaire et extraordinaire, sera le dit Calas Père étranglé, après avoir resté deux heures sur la roue. Jugé le 9 Mai, 1762.—Cassan, Clairac, rapporteurs.”

He bore the torture inflicted on him in the Hôtel de Ville with the greatest firmness, answering all questions with the utmost clearness, and giving no advantage to his interrogators, but persisting in maintaining his innocence. On the scaffold, after suffering with the most patient resignation the agonies of his punishment for 2 whole hours, during which he was subjected to the mental rackings of a Romish



priest, being still fully alive, the signal was given to the executioner to inflict the "*coup de grâce.*"

"De faux témoins ont égarés mes juges," exclaimed he, before breathing his last breath; "je meurs innocent: Jésus Christ, qui était l'innocence même, voulut mourir par une supplice plus cruel encore." The very Dominicans who attended Calas exclaimed as he expired, "Il est mort un juste!" With his murder an end was put to the martyrdoms and cruel persecutions of the Protestants which had disgraced the South of France for almost a century, and chiefly owing to the praiseworthy exertions of Voltaire in defending Jean Calas and exposing his persecutors. His sentence was reversed and his innocence proclaimed by the Conseil Royal at Paris.

The *Palais de Justice*, totally modernised externally, and for the most part a new building, was the seat of the Parliament of Toulouse, where its sittings were held. The fine ceilings ornamenting its interior have been retained in two apartments: one, carved with reliefs in compartments, representing the Labours of Hercules, is by no means contemptible; the other is richly gilt.

At a short distance below the bridge, the navigation of the Garonne is interrupted by a weir thrown across it, to supply water to the large corn mill of the town, called *le Basacle*, rebuilt 1814.

Between this mill and the church of La Daurade is the mouth of the *Canal de Brienne*, constructed by the archbishop whose name it bears, to remedy the interruption in the navigation caused by the mill weir. It runs nearly parallel with the Garonne for about  $\frac{3}{4}$  mile below the Basacle, and then falls into the *Canal du Midi*. A fine avenue of trees leads to this junction. Here the 2 canals are crossed by small bridges, between which, on a level with the water, is stuck a large piece of sculpture, in high relief, of white marble, repre-

senting some unmeaning allegory, without allusion to the founder of the great work, Riquet, and contemptible in execution.

A few hundred yards below this, the *Canal du Midi*, after sweeping round the E. and N. sides of the city of Toulouse, enters the Garonne through a basin provided with double locks, and guarded against ice by a sort of pier. The Garonne is at this point 144 mètres, or 473 ft., above the level of the Atlantic.

The navigation of the Garonne, though carried on by barges, is very difficult, owing to rocks and stems of trees in its bed, from Toulouse to the junction of the Tarn. A lateral canal has been projected from Toulouse to Castels in Dépt. de la Gironde. For a description of the *Canal du Midi*, see R. 93.

At the battle of Toulouse, the inner bank of the canal, towards the town, was lined with French troops, and every bridge over it strongly defended by *têtes de pont* and intrenchments. In an attack made by the British Light Division upon the bridge nearest the embouchure of the canal, designed by Wellington merely as a feint, but converted by Picton, in disobedience to orders, into a hopeless assault, the British were repulsed with a loss of 400 men.

A monument has been erected, in the grounds of the Château Gragnague, on the N. side of the canal, to a British officer of great merit, Colonel Forbes, of the 45th regiment. Several other English monumental tablets are also placed in the Protestant Church of Toulouse.

The best point of view for surveying the *field of the Battle of Toulouse* (April 10, 1814), as well as for viewing the town, is the *Obelisk* of brick, erected by the city, "*Aux Braves morts pour la Patrie*," occupying the site of one of Marshal Soult's redoubts, taken by the English, on the height of Calvinet. It is reached by traversing the fine oval *place*, and the broad *Avenue Lafayette* (origi-

nally d'Angoulême), crossing the canal at the flying bridge, or Pont Matabiau, and ascending at the back of the Ecole Vétérinaire. The view owes its chief interest to the distant chain of the Pyrenees, occupying the horizon, whose peaks may be discerned, in fine weather, from the Canigou on the E. to the Pic du Midi de Bigorre on the W., with the Maladetta, Crabioules, and Mt. Perdu in the centre. The city itself is not striking; the country around is very flat and monotonous, and the Garonne runs in too deep a bed to form a feature in the landscape.

The most important part of Marshal Soult's position, at the time of the battle, was along the heights called Mont Rave, composed of two platforms, Calvinet (on which stands the obelisk) and Sy pierre, both of which had been fortified, several weeks beforehand, with 5 redoubts, and intrenchments between them, mounted with a great many guns. The position was supported by the canal, and by the ramparts by which the town was then surrounded, in the rear of the canal; and in front the position was covered by the Ers. That stream was at the time unfordable, and all the bridges over it were blown up, or strongly guarded, except that of Croix Daurade, taken by the British Hussars the day before the battle. General Beresford's division, which achieved the victory, had to make a flank movement, marching for 2 m. up the rt. bank of the Ers, under the fire from the heights, over ground naturally very difficult, marshy, and intersected by watercourses, but rendered almost impassable by artificial inundations. After passing Calvinet, the British troops formed, and, charging up the height, took first the redoubt on Sy pierre, and afterwards those on Calvinet. Here, however, a terrible struggle took place: the British, "clinging to the brow of the hill," in spite of the masses opposed to

them, stood fast on the ground they had gained; and though the French made desperate efforts from the canal, they never retook Calvinet. A previous attack on Calvinet, made in the early part of the day by the Spaniards, had been very different in its result; so quickly, indeed, did they retire, that the Duke of Wellington said of them, "he never before saw 10,000 men running a race:" 1500 of them were slaughtered on the slope of this hill, chiefly in a hollow road upon its flank, raked by a battery from the Pont de Matabiau on the canal, which "sent its bullets from flank to flank, hissing through the quivering mass of flesh and bones," to use the words of Colonel Napier.

At 5 o'clock, p. m., Soult withdrew his whole army behind the canal. The next day he remained inactive, and on the night of the 11th was "forced to abandon" Toulouse, leaving behind 1600 wounded and 3 generals, to fall prisoners into the hands of the allies. They lost in this battle 4659 men and 4 generals; the French nearly 3000, and 5 generals killed or wounded; a useless waste of human life, since Napoleon had abdicated on the 4th April, some days previously, though that event was unknown to either of the commanders. There can be no doubt that the charge brought against Marshal Soult of fighting this battle though aware of what had happened at Paris is unfounded, and the Duke of Wellington himself has nobly vindicated him from it. The forces of the allies amounted to 52,000 men; but of these only 24,000, and 52 guns, were actually engaged in the battle; the French had 38,000 men, with from 80 to 90 guns. This is the estimate drawn out with the utmost fairness by Colonel Napier.

The country immediately about Toulouse is generally flat and uninteresting, and being besides arid, and burnt up in summer, the want of shade and verdure, and the excessive



dust, offer no inducements to explore. Its fertility, however, is very conspicuous.

Toulouse is joined by a *bridge* of brick, pierced with round holes between the spandrels of the arches, and terminating in an archway, with the suburb of St. Cyprien, which was invested by General Hill and one division of the British army at the time of the battle.

The principal *Cafés* are in the Place du Capitole. The market held here is very abundantly supplied: fruit, vegetables, poultry, and wine are very cheap; butter and milk dear; ortolans, truffles, figs, *pâtés de foies de canards*, are the delicacies which await the gourmand here.

*Mallespostes* daily to Paris by Montauban and Limoges; to Marseilles by Narbonne and Montpellier; to Bordeaux by Agen; to Bayonne by Auch and Pau.

*Diligences*—daily, to Paris; to Bordeaux: diligences also correspond with the steamers on the Garonne to Bordeaux; to Tarbes, Pau, and Bayonne; to Auch and Bagnères de Bigorre; to St. Gaudens and Bagnères de Luchon; to Foix, Ussat, and Ax: to Villefranche (Aveyron); to Nîmes and Marseilles by Narbonne and Montpellier; to Perpignan by Limoux; to Alby.

## ROUTE 71.

LIMOGES TO BORDEAUX, BY PERIGUEUX AND LIBOURNE.

215 kilom. = 133½ Eng. m.

*Mulleposte* as far as Perigueux.

*Diligences* daily.

Through a hilly country we reach the first relay at

12 Aixe, on the Vienne, a small town skirted by the road.

23 Chalus. The post-house and inn is situated at some distance from this little town, which is only remarkable for its *Castle of Chabrol*, rising above it in picturesque ruins. Beneath its walls, Richard Cœur de Lion received his death-wound from

the arrow of a youth named Bertrand de Guerdon. The tamer of the infidel, and hero of the Crusades, thus ended a chivalrous life of nearly constant warfare, before the petty fortress of a vassal, the Viscount of Limoges, which he had besieged in consequence of a quarrel about the division of a treasure found in the viscount's domain, of which Richard claimed the whole, or a larger share than had been conceded to him. The castle was soon taken, and the garrison of only 38 men were hung by the king's order, except the bold archer who had sped the shaft so fatal to him. The youth avowed, when brought before the dying monarch, that revenge for the death of his father and two brothers, slain by Richard, had prompted him to free the country of its oppressor. His life, though magnanimously spared by Richard, was taken after his death; and he is said to have been flayed alive by order of Richard's minister. The most conspicuous part of the castle yet remaining is a circular *donjon*, entered by a doorway high up in the wall, and no longer accessible without a ladder. The tower is entirely gutted. Around it are grouped some shattered fragments of buildings, including a portion of a chapel. A little conical stone, rising out of the meadows in the front of the castle, in the valley below it, is pointed out as the spot where Richard had placed himself to reconnoitre the fort, when the arrow struck him in the l. shoulder. The stone is called *Maumont*.

The bridge of Firbeix, 3 m. from Chalus, crosses the boundary line of the ancient provinces of Limousin and Perigord, famous for *truffles*, the groundwork of its celebrated *pâtés*.

13 La Coquille.

15 Thiviers.

13 Palissou.

19 *Perigueux* (*Inns*: H. de France; Du Chêne Vert), the chef-lieu of the Dépt. Dordogne, contains 12,157 inhab., and is situated on the rt. bank

of the river L'Isle, which was canalised in 1837. The town, composed of streets narrow, tortuous, and dirty within, is fringed by green alleys externally.

Its *Cathedral of St. Front* is supposed to be of an age ~~anterior to~~ the 10th century, except the lofty tower, 197 ft. high. The arrangement of the ground plan and the construction of this ch. display some remarkable peculiarities. It is in the form of a Greek cross, with 4 equal arms, formed by squares, set round a 5th square in the centre. Each square is surmounted by a stone-vaulted cupola, concealed from without by a wooden roof, but visible to those who choose to mount up to the roof. In a chapel within it, is a remarkable bas-relief in wood, representing the Assumption of the Virgin, of elaborate execution. The *Préfecture* is a handsome modern building.

The first ancient name of this city was Vesuna, retained in the tower *de Vésune*, a circular edifice of Roman construction, 100 ft. high, its walls 6 ft. thick, without doors or windows. It is supposed to have been a tomb, and is situated in a suburb called La Cité, which contains another ancient church. Traces of a *Roman amphitheatre* and *arch* in the town also still exist. At a later period, the name Vesuna was changed to *Petrocorii*, mentioned by Cæsar, whence Perigueux. The streets of Perigueux contain some curiously ornamented houses of the 16th century; one at the corner of Rue l'Aiguillerie bearing the date 1518: 2 others in Rue Taillefer, Nos. 31 and 37, and a 4th at the end of the Rue de la Sagesse, ornamented with arabesques and carvings, merit notice. There are some buildings and vaults which are as old as the 12th and 13th centuries.

The celebrated *pâtés de Perigueux*, well known to all gourmands, are made of partridges combined with truffles, and form an article of considerable export.

The road descends the valley of

the L'Isle nearly all the way to Libourne, crossing the stream opposite Castel Fadaise.

Passing under the castle of Montancey, we reach

18 Massoulie.

17 Mussidan.

17 Montpont.

18 St. Médard (Dépt. Gironde).

A few m. to the rt. lies Coutras, where Henri IV., while still only king of Navarre, gained a bloody victory over the forces of the League, under the Duc de Joyeuse, who lost his life on the field, along with many other great lords, 1587. Coutras is visible from a hill overlooking the valley of the L'Isle, surmounted before reaching

20 *Libourne* (*Inns*: H. de France; Des Princes), a town of nearly 10,000 inhab., situated on the rt. bank of the Dordogne, here a tidal river, capable of receiving vessels of 300 tons burthen, and crossed by a bridge of brick, like that of Bordeaux, at the confluence of the L'Isle, which is traversed by an iron bridge. It is a neat and regularly built town, ~~founded, it is said, by Edward I., on the site of the "Condatis portus" mentioned by Ausonius.~~

[An interesting excursion may be made from Libourne up the valley of the Dordogne to *St. Emilion*, a town of 3100 inhab. (3 m. distant), celebrated for its wines, and one of the most remarkable in France for the antiquity of its buildings. It is, as it were, a town of the middle ages, preserved to our times; with its crenelated ramparts, watch-towers, and 6 gates still perfect. It has a ruined *Castle, le Château du Roi*, built by Louis VIII., surmounted by a square keep tower, in a style resembling the Norman, most singular; in fact unique; a *monolithic Church* cut in the rock; a round Gothic church, called the *Rotonde*; the *Parish* or *Collegiate Church*, a fine building, reduced to the nave and W. portal, of the 12th century. On the S. side is a curious *Cloister*, and not far off



risers a graceful tower, octagonal above, square below, commanding from its top a very fine view; the ruins of several other churches; and a handsome building, the *Palais du Cardinal* de Cantarac. The Girondins Guadet, Pétion, and Barbaroux were captured and slain here, 1794.

About 12 m. S. E. of this is Castillon, under whose walls was fought, in 1453, the battle in which valiant Lord Talbot, Earl of Shrewsbury,

“The Frenchman’s only scourge,  
Their kingdom’s terror, and black Nemesis,”

hemmed in by a French force greatly superior to his own, was slain, at the age of nearly 80 years, gallantly fighting along with his son, the Lord Lisle, whom his father in vain counselled to depart out of the field, seeing that all was lost,—a real incident, which has furnished Shakespeare with a fine scene. The result of Talbot’s defeat and death was the capture of Bordeaux from the English, and their final expulsion from Guienne. Near Montraval on the rt. bank of the Dordogne, a tomb was formerly pointed out under the name of Talbot’s; but it is known that his body was transported by his friends to England. 3 m. from Castillon, on the l. of the road, but accessible only by rough cross roads, is the *Castle of St. Michel de Montaigne*, the birth-place of Montaigne, the philosopher of the 16th century, and Shakespeare’s favourite author. His room is preserved in the gate tower, over the entrance, and is decorated with Greek and Latin sentences; among them

“Homo sum: humani à me nihil alienum puto.”

There is a pleasing view from the terrace.]

The new road to Bordeaux, after crossing the bridge over the Dordogne, passes through

16 ~~Beynac~~ *Ygerac*, near the

A few miles S. of Carbon Blanc, the road falls into that from Angou-

lême to Bordeaux, described in R. 64, while

15 BORDEAUX itself will be found in R. 73.

### ROUTE 73.

TOULOUSE TO BORDEAUX BY MOISSAC, AGEN, MARMANDE:—DESCENT OF THE GARONNE.

256 kilom. = 158½ Eng. m.

*Malleposte* daily in 16 hours.

*Diligences* daily.

*Steamers* ply on the Garonne from Agen or Marmande to Bordeaux.

The first 2 stages from Toulouse by

17 St. Jory, and

12 Grisolles, are the same as R. 70; but we turn to the l. out of the road to Paris by Montauban, before reaching

16 La Vitarelle.

The Garonne runs nearly parallel with the road, but so far off (1½ to 2 m.) as scarcely to be seen.

After skirting the little town of St. Porquier, and crossing the road from Montauban to Auch, we reach

13 Castel Sarrazin, a town of 7000 inhab., carrying on some trade in the corn grown on the fertile plain around. Opinions differ as to the origin of the name; some deriving it from the Saracens, who may have built the *castle*, of which scanty remains exist, to secure themselves in this part of France; others, from Castel-sur-Azin, the name of the small stream running through it.

The river Tarn, flowing down from Montauban to join the Garonne, is crossed before entering

7 Moissac (*Inn*: Grand Soleil), a town of 10,165 inhab., on the rt. bank of the Tarn.

Its *Ch.* of *St. Pierre* and *St. Paul*, once attached to a celebrated abbey founded by Clovis, or more probably by St. Amand of Maestricht in the 7th centy., has a very remarkable *portal*, which was added, in the early part of the 12th centy., to the still older church. It is a deeply recessed

Hotel du Midi

from which still preserves its

porch, preceding a pointed arch, the mouldings and tympanum of which, over the door, are enriched with the most fantastic sculptures, designed with the utmost boldness and fancy. Figures of apostles, saints, angels, bas-reliefs, fanciful patterns and mouldings, have been dashed off with wonderful freedom. The central pier, supporting the doorway, and the side walls, under the porch, are similarly adorned. In the interior are some very early Mosaics.

The *cloisters*, a range of pointed arches, resting on twin pillars with singular capitals, ~~are supposed to have been constructed at the same time.~~

An ancient fountain in the town merits notice.

A hilly stage intervenes between Moissac and

10 Malause, a prettily situated town, whose ancient castle has been destroyed since the Revolution. The flat land ceases here, and the country around is very pleasing: the Garonne, which the road now approaches more closely, is a charming feature in the landscape.

The little town of Valence is passed, and a few miles further the road runs along a sort of terrace or quay by the side of the Garonne, through

12 La Magistère.

10 Croquelardit.

About half way between Toulouse and Bordeaux lies

10 Agen.—*Inns*: H. du Petit St. Jean, beds not clean, but good cuisine, famed for its Terrines de Nérac, its pâtés aux truffes;—H. de France.

Agen, chef-lieu of the Dépt. Lot et Garonne, is an uninteresting town of 12,500 inhab., agreeably situated on the l. bank of the Garonne, between it and the gently sloping height, covered with vineyards and country houses, called Côte de l'Ermitage. It is a very old town, chiefly of narrow streets. The Garonne is here crossed by a bridge of stone, and also by a suspension bridge, between which and the town runs a beautiful

avenue of trees, forming an agreeable promenade called *Les Gravières*. The old church of *St. Caprais* is a fine Romanesque building with numerous apses, and has been well restored. There are a few scanty remains of the cathedral of St. Etienne, destroyed at the Revolution, and its site is now become a beast-market.

The *préfecture* was originally the episcopal palace, and is a handsome edifice.

The *Canal* is carried over the Garonne here, on a stone aqueduct of 23 arches, of good architecture.

The town was known to the Romans under the name Aginum. The early Christians suffered severe persecution here from the Roman prætor; and St. Vincent, the 2nd bishop, and many followers, underwent martyrdom, being torn to pieces on the spot now occupied by the Fontaine St. Vincent. Agen suffered much from the fortunes of war, especially in the 14th century, when, by sieges and assaults, it passed repeatedly from the hands of the French to the English, and vice versâ. During the wars of the League, it was taken by the Maréchal de Matignon, with the aid of an engineer, who blew in one of the gates with a petard, 1591. Marguerite de Valois, who was in the town at the time, had great difficulty in securing a horse, with a pillion, for herself to escape, and post-horses for a portion of her maids of honour, many of whom were compelled to decamp "on foot without masks, others without riding-habits."

Those who have time should walk to the top of the rocky height of *L'Ermitage*, on the way to Ville-neuve, for the sake of the view over the beautiful valley of the Garonne and the distant Pyrenees. In a pretty gorge or recess in the slope of the hill is the curious house of the erudite Julius Scaliger, whither he retired, in the reign of Francis I., after migrating from his native city, Verona. He died here 1558, and here his no less learned son, Joseph Julius Sea-



~~perfect~~ page. 264 (In Cloister at Troissac.)

In one of the Pillars is a contemporary inscription  
saying "the cloister was built in one thousand one hundred.





liger, was born. Agen is also the birth-place of Bernard Palissy, inventor of a beautiful species of earthenware, the Wedgewood of the 16th centy., and not less scientific for his age; also of Lacépède, the naturalist. Here was born, and still dwells and sings, a rustic poet named Jasmin, a perruquier by trade, the last representative of the Troubadours. His songs are very popular throughout the S. of France, in the country of the Langue d'Oc.

A great number of plum orchards clothe the neighbouring slopes and fields, and produce the celebrated *prunes d'Agen*, which form an article of considerable export.

*Steamers* navigate the Garonne as far up as Agen, when the river is of proper height: the descent hence to Bordeaux requires 8 hours. The vessels are small and dirty; they do not take carriages, which must be sent by land by *voiturier*.

*Mallespostes* to Auch and Pau; to Limoges and Orleans; to Bordeaux and Toulouse. The traveller bound to the Pyrenees may turn off here to Pau, by Lectoure.

10 Pont St. Hilaire.

11 Port St. Marie. Here is a suspension bridge over the Garonne.

Near the village of St. Côme, on the rt. of the road, the remains of a tower, called *Tour de St. Côme*, constructed of small square stones, and supposed to be of Roman origin, are worthy of notice. It stands at a short distance from

10 Aiguillon, a town of nearly 2,000 inhab., on the l. bank of the Lot, about a mile above its influx into the Garonne. Its principal building is the large *château* on an eminence left unfinished by the Duc d'Aiguillon, minister of Louis XV., by favour of Mad. du Barry. But it is said to include portions of older construction. The duchy was created by Henri IV. 1599, to bestow it upon the Duc de Mayenne. The old castle, so stoutly defended by the English in 1346, when besieged for 5 months by Jean Duc de Normandie, *France.*

son of Philippe de Valois, with an army of 60,000 men, no longer exists. Although the prince directed against it twenty assaults in seven days, and though he had sworn not to move until it was taken, he was compelled to retire from before its walls, without having succeeded, being called off by intelligence of his father's defeat at Crecy.

The Lot is crossed here by a bridge of 8 arches, built by Napoleon.

11 Tonneins (*Inn*: H. d'Angleterre), a cheerful-looking town, chiefly of modern buildings, remarkable for the beauty of its situation, on the rt. bank of the Garonne, containing 6,500 inhab., half of whom are Protestants. There are extensive manufactures of rope here, and a royal manufactory of *tobacco*, large quantities of which are cultivated around Tonneins, and throughout the departments of Lot and Lot et Garonne, under the inspection of the excise.

There is a suspension bridge over the Garonne here.

17 Marmande.—*Inns*: H. de France; —H. de la Providence; —Tête Noire.

A town of venerable aspect, many of its houses being timber-framed, but possessing no objects of interest to the traveller. Population 9,900.

Below Marmande the navigation of the river is more sure, and steamers ply more regularly than above. One or two vessels run daily to Bordeaux, corresponding with the diligences to Toulouse.

The road avoids the windings made by the river below Marmande, being carried in nearly a straight line to

11 La Mothe Landeron, which lies within the Dépt. of the Gironde.

L. The lofty old ruined tower of Meilhau remains long in sight of those who travel by water, owing to its position at the extremity of an acute angle or elbow made by the river.

A fine suspension bridge of a single curve, 558 ft. wide in the opening, spans the river at

9 La Réole (*Cerf Volant*: a mere public-house, but clean beds and good

food)—a town of 4,000 inhab., retaining the ruins of an ancient castle, which Froissart says was built by the Saracens. The vast Benedictine convent, rebuilt in the 17th centy., and suppressed at the Revolution, has been converted into a nunnery. The Gothic church attached to it has been allowed to go to decay.

9 Candrot.

*Romanesque.* The ancient town of St. Macaire, retaining its feudal walls and possessing a fine Gothic church, is passed shortly before reaching the suspension bridge, 656 ft. long, which carries the road over the Garonne into

*de France*  
*only*  
*ul clear*  
*and*  
*cheap*  
*114*  
9 Langon (*Inn: H. d'Empereur*), a miserable town of 3,745 inhab., partly surrounded by old walls on the l. bank of the Garonne, which could be crossed only by a ferry boat, down to 1831, though Langon lies on the great line of traffic between Bordeaux and Toulouse.

The high roads from Bayonne and Pau to Bordeaux (R. 76 and 80) unite with that from Toulouse at Langon. The tide runs up as far as Langon.

The post road hence to Bordeaux is described in R. 76.

The banks of the river are now clothed with vineyards, whose produce, chiefly white wines, enjoys some reputation and fetches a considerable price, being known by the name of Vins de Grave. Sauterne and Barsac are both grown in the commune of

L. Preignac, not far from Langon. Bertrand de Gout, who became pope under the name of Clement V., was born in the very picturesque castle of Villandraut, about 8 m. S. of Preignac.

L. Barsac, whence comes the white wine named after it, is a town of 2,896 inhab.

Rt. Cardillac was the seat of the Duc d'Epemon, governor of the province of Guienne in the 17th century; the first duke, who was the favourite of Henri III., but died in the prison of Loches, built the *Château* (1598), which is now converted into

a female *Penitentiary*. His splendid monument, attributed to Girardon, erected by his son in the parish church, was destroyed at the Revolution, except one statue now in the Louvre. There is a great manufacture of wine-casks here.

12 (l.) Cérons, an old castle.

L. Podensac, 15 m. from Bordeaux.

Rt. At Langoiron, at the foot of the slope, are ruins of a castle built apparently in the 14th century: near this l'Ami des Enfants, Berquin, was born.

L. Portets is the place where the inhabitants of the Landes embark their rosin and timber, the produce of that sandy district, which stretches S. from the Garonne near this to the Adour.

11 (l.) Castres.

13 (l.) Bouscaut, at some distance from the river. Among the numerous villages which crowd the banks of the Garonne none appear to deserve particular mention. On approaching Bordeaux the wooded and vineclad (rt.) heights of Floirac form a pleasing feature in the view. The bridge is described in R. 64.

11 (l.) BORDEAUX.—*Inns*: H. de France, 29, Rue Esprit des Lois;—H. de la Paix (Sansot's), beds, 2 fr.; sitting room, 3 fr., very comfortable;—H. de Paris, frequented by English, good;—H. de Richelieu, good situation; no table-d'hôte.

Bordeaux, the second sea-port town of France, which may be styled its Liverpool, containing 110,000 inhab., is placed on the l. bank of the Garonne, on a spot where its voluminous stream, deep enough for vessels of 1,200 tons burthen, makes a very regular curve, which being lined with handsome buildings of varied architecture, chiefly Italian, forms a noble crescent, lined with quays not less than 3 m. long, surmounted by several Gothic towers and antique spires, in the background. No city in Europe, except perhaps St. Petersburg, can display a more splendid quay than this. The river abreast of the town,



2000 ft. wide, and 18 to 30 ft. deep, is filled with shipping up to the magnificent *Bridge*, the handsomest in France. (See Route 64.) This noble exterior, equally striking to the stranger whether he approaches by water or by land from the side of Paris, is borne out by the aspect of a large part of its interior, which has a courtly rather than a commercial air. The Rues du Chapeau Rouge and de l'Intendance, running E. and W. through the heart of the town, nearly separate the old town, of narrow and insignificant though very populous streets, from the N. or more modern quarter, consisting of wide openings: broad streets, extensive places, and avenues, and gardens running into one another, which render Bordeaux a sprawling city, difficult to get over on foot, but omnibuses and neat fiacres are fortunately very abundant.

The Place and Allées de Tournay are so named from an ancient intendant of the province, who in 1750 led the way in improving the city.

Some of the finest streets and rows of houses, and the open *Place Louis-Philippe* terminating at the river side with two lofty rostral columns, occupy the site of a citadel called Château Trompette, built by Vauban for Louis XIV. to overawe the Bordelais, dismantled under Louis XVI., and removed since the Restoration. The construction of this new quarter has united with the town of Bordeaux the vast Quartier des Chartrons (so called from a convent of Chartreux), stretching down by the river side, and once a distinct faubourg.

One of the most conspicuous, and at the same time handsomest buildings, is the *Theatre*, of good Grecian architecture, faced with a Corinthian portico of 12 arches and isolated on all sides; it is situated in a very central part of the town. It was erected 1780, under the direction of the Duc de Richelieu, by the architect Louis.

The *Cathedral* of St. André is distinguished by its 2 elegant spires, 150 ft. high, at the end of the N. transept, said to have been erected by the English, who held possession of Bordeaux for nearly 300 years, and flanking a pointed portal, enriched with statues and bas-reliefs, above which is a fine rose-window surmounted by a gable. The nave, partly in the round Romanesque style, partly, towards the W. end, repaired in a bungling manner in the 15th cent., after the destruction of a part of the church by an earthquake, is destitute of aisles, and remarkable only for its breadth—56 ft., which, being out of all proportion with its height, deprives it of the chief merit and characteristic of Gothic architecture—elevation. The choir is more elevated, and in a more truly Gothic style, with a triforium gallery and lofty clerestory windows; it is probably of the same age as the spires, and is also said to be by English architects. Our Richard II. was christened, and the marriage of Louis XIII. with the Infanta of Spain, Anne of Austria, was solemnized in this church, 1615.

Opposite the W. end of the cathedral are the Palais and Hôtel de Ville.

Near the E. end of the cathedral, but quite detached from it, is the *Tour de Peyberland*, a noble structure 200 ft. high, square below, and supported by buttresses, but gradually diminishing from its base until it terminates in a circular top. It was originally surmounted by a spire, which rose to a height of 300 ft. It is named from Pierre Berland, who rose from being the son of a poor labourer in Médoc to be bishop of Bordeaux; he caused it to be erected in 1430. During the Reign of Terror it was condemned to destruction; but the spire alone suffered, the rest resisting all attacks, owing to its solidity. Its handsome windows, however, were stopped, and it was converted into a shot tower, in which capacity it still continues to bear

the words, "Fabrique de plomb de chasse."

*L'Eglise Ste. Croix*, situated quite at the S. extremity of the town, near the quay, considerably above the bridge, is supposed to be the oldest church here, though a much earlier age has been assigned to it by some than it can claim, as its oldest parts cannot date farther back than the 10th or 11th cent. Its W. front, quite without uniformity, owing to its partial destruction and subsequent repairs, is a specimen of richly decorated Romanesque architecture, and from its age and quaint ornaments deserves some notice. Its semicircular portal and two lateral closed arcades are surrounded by mouldings elaborately carved, some with singular and unexplained naked groups of figures, intermixed with cable mouldings. In the tympanum above the door are three rows of bas-reliefs, in a style curiously resembling the Egyptian. The rest of the façade, and the wall of the tower rising on the one side, are occupied by arcades; groups of twisted or grooved pillars flank the portal, and 3 tiers of 4 small pillars, placed side by side one above the other, serve instead of buttresses to the tower.

The interior is of later date and inferior interest; its clustered roof rests on clumsy drum-like piers, partly plain, partly surrounded by shafts, some of them surmounted by curious stiffly-carved capitals. It contains a handsome canopied tomb of an abbot, in decorated Gothic. In a chapel on the l. as you enter, the panelled walls of which are decorated with tolerable paintings from the life of the Virgin by an old Italian artist, Vasetti, is an oblong baptismal font, bearing on 2 sides well-executed bas-reliefs of the Last Supper, with decorated ornaments.

In descending the quay from Ste. Croix, you pass, a little above the bridge, near the church of

*St. Michael*, situated nearly on a line with the bridge, and distin-

guished by its lofty detached tower, deprived of much of its effect by being hemmed in with mean houses. Its N. front is a superb Gothic elevation in the florid style (15th cent.). It has an elegant rose window framed within a richly decorated arch, whose mouldings are curved back below it. Under it is a florid *porch*. Over the door are placed a pair of bas-reliefs representing the Sacrifice of Isaac and the Paschal Lamb, dating from the 16th cent.; they are separated by a charming group of wonderful expression, representing Judas's kiss. Within the church, at the back of this portal, over the door, is another group, an "Ecce Homo" of the same period, and a century earlier than the bas-reliefs on each side of it, which represent St. Michael destroying the Dragon, and Adam and Eve. The nave and choir are nearly uniform, and of noble pointed Gothic; the choir (about the 13th cent.) has a triforium and clerestory running behind the high altar, so that the E. end is like any compartment at the side, except that the space below, behind the altar, is filled with a shallow apse.

There are a few good painted windows, and in the N. side of the nave a chapel furnished with an altar in the richest and most overlaid Renaissance style. Within its niches are three graceful statues—the Virgin and Child, St. Catherine, and St. Barbara.

Near the W. end stands the elegant detached *belfry*, 178 ft. high, which now bears the telegraph, but was originally surmounted by a steeple, and rose to a height of 300 ft. It is of octagonal form, supported by elegant buttresses, and was built between 1472 and 1480. In the vault beneath it are shown from 40 to 50 human bodies, interred in the vault below before the Revolution, and preserved by its dry and antiseptic qualities, until they are now like leather, or salt fish,—a disgusting sight.



*St. Seurin* (St. Severin), situated beyond the Place Dauphine, in the Allées d'Amour, is remarkable for a finely carved triple S. porch, consisting of a trefoil-headed door, enriched with statues of good workmanship, well-executed draperies, and dating from 1267. They represent the 12 Apostles and 2 more sacred personages.

The W. front is modern, but is a tolerable attempt to follow the Romanesque style. The W. porch consists of three detached low vaults, one within the other, supported on pillars with curiously carved capitals.

Within this church, on the rt. hand or S. wall, is a curious bas-relief within a pointed arch above a doorway, now walled up, representing a pope saying mass (supposed to be Clement V., archbishop of Bordeaux), assisted by a cardinal. On the opposite wall is another bas-relief of 7 figures in niches. The Gothic woodwork of the choir is curious, but sadly bedaubed with paint. Under the seats are numerous grotesque groups. The high altar is decorated with 14 curiously carved bas-reliefs of marble, framed, representing the legend of St. Severin, bishop of Bordeaux in the 5th century. On the one side of the chancel stands the *Bishop's Throne*, a curiously carved seat, under a canopy, all of marble, richly sculptured. This church was the cathedral before St. André. Under the choir is an early crypt with 3 aisles and semi-circular arches. At the W. end rises a tower surrounded by a double row of circular arcades.

In the *Chapelle of the College*, a bold Gothic structure, is the *monument of Montaigne*, the essayist, a native of Montaigne St. Michel in Périgord, who was mayor of Bordeaux in 1553. He is represented in full armour according to the custom of the period, laid on his back, with his hands joined in prayer. The statue is a well-executed work of the 16th

century. At No. 17, in the Rue des Minimes, stood his modest mansion, in which he lived and died, 1592, now pulled down.

These are the most remarkable ecclesiastical edifices of Bordeaux, but it retains still a monument of the Roman city *Burdigala*, in the fragment of an amphitheatre, now called *Palais Gallien*, not quite accurately, because, though possibly built in the reign of the Emp. Gallienus, it was not a palace, but a circus, capable of containing 1500 persons. It is supposed to have been built by Tetricus, one of the so-called 30 tyrants, who assumed the purple here. It was condemned to destruction 1792, and has been since gradually pulled down to build houses, so that it is now reduced to mere fragments, interesting to the antiquary alone, of an oval wall formed of small stones with layers of tiles between them, interrupted by the broken archways which lead into it. The interior is occupied by houses and workshops, and two streets cross in the centre of it: so that you may stand in the midst of its area and scarcely recognise these ancient remains.

Bordeaux has preserved two of its feudal town gates: one, now called *Tour de l'Horloge*, built 1246 by Henry III. of England, surmounted by 3 pointed turrets, formed part of the old Hôtel de Ville. The other, *Porte de Caillou*, at the end of the Rue du Palais, was built 1492 to commemorate the victory of Charles VIII. at Fornova. The old Bourse, in the Place d'Aquitaine, now an office of roulage, but built as a palace for Charles IX., and the old *Evêché* in a narrow street near it, are picturesque examples of the architecture of the 16th century.

Bordeaux, like almost every other chef-lieu de Département in France, has a *Gallery of Paintings*. They are placed in the numerous saloons of the Hôtel de Ville; but, except for their number, they are in no wise remarkable, and the less said of their

merits the more true the description. There are, however, some tolerable works of the French school.

The *Musée*, situated in Rue St. Dominique, a street leading out of the Chaussée de Tourny, contains a collection of antique fragments, inscriptions, altars, &c., chiefly Roman, found in the vicinity of Bordeaux; two sarcophagi, with bas-reliefs, of inferior merit and late date; also fragments of the marble bas-reliefs, representing the battle of Fontenoy, and the capture of Port Mahon from the English by the Duc de Richelieu, which ornamented the pedestal of the statue of Louis XV. in the Place Royale, destroyed at the Revolution. Here are some relics of Napoleon, including his tooth-brush! and the star of the Legion of Honour, which he wore. In the *Musée d'Histoire Naturelle* are tolerable collections of shells, of the fossils of the neighbourhood of Bordeaux, marked by blue tickets, and of the marbles of the Pyrenees. A specimen of a sea-eagle was shot at La Teste. These museums are open daily to strangers.

In the same locality, Rue St. Dominique, is the *library* of more than 100,000 volumes, partly the bequest of a member of the old Parliament of Bordeaux, partly the remains of conventual libraries forfeited at the Revolution. A copy of Montaigne's Essays with marginal notes in his own hand, and the first French translation of Livy illuminated, are among its curiosities.

The *Bourse*, the centre of the commerce and trade of the city, is situated on the quay at the extremity of the Rue Chapeau Rouge, between it and the Place Royale. The merchants meet here daily, under a glass dome which covers the inner court of the building, 98 ft. long by 65 broad.

The commercial importance of Bordeaux is due to its situation on a fine navigable river, where the rise and fall of tides amounts to 20 feet, in which vessels of more than 1000 tons

may ride at anchor, at a distance of about 70 m. from the sea. It is connected by the same river, through the Canal du Midi, with the Mediterranean. The commerce of Bordeaux is carried on chiefly with South America and Mexico, the United States, French colonies, and Great Britain. Its principal articles of trade and exports consist in wines, known in France as vins de Bordeaux, and in England as *claret*, a name of doubtful origin. From 50,000 to 60,000 tuns of wine are exported annually. Nearly half of the best quality and highest price is sent to Great Britain; very little is consumed in France. The Quartier des Chartrons is the focus of this trade; here the principal wine-merchants have their counting-houses and cellars.

The *Cellars of MM. Barton and Guestier*, leading bankers and wine-merchants, 35, Cours des Chartrons, are among "the lions" of Bordeaux. They are two stories in height, and commonly contain from 8000 to 9000 casks (barriques) of wine, never less than 4000 or 5000. The duty paid by this house in one year alone to the British government has amounted to 300,000*l*.

For an account of the wines of Bordeaux, see p. 274.

Among the *delicacies* furnished by the Bordeaux markets to the table are *royans*, a species of sardines (pilchards), caught in autumn; *Ceps*, a sort of mushroom cooked in oil; *Muriers*, small birds something like beccaficas; and *Ortolans*, caught in August, near Agen and the Pyrenees.

The Café de Paris is a tolerable Restaurant.

*Consuls* reside here from the chief powers of Europe and America; Great Britain is most respectably represented by Mr. Scott, No. 7, Place du Champ de Mars.

The *English Ch. service* is performed on Sundays at the English Protestant ch., 8, Cours des Chartrons, at 11 a.m. and 3 p.m.

The *Poste aux Lettres* is at No. 5,



Rue Porte Dijéaux: a letter reaches London in four days from this.

*Public baths* on a very extensive scale, in two fine buildings on each side of the Place Louis-Philippe.

Newspapers of all countries, English, French, German, Spanish, &c., may be found in great abundance at the *Cercle*, 7, Place de la Comédie, opposite the theatre.

The only *resident English physician* is Dr. Coppinger, Place Dauphine, 43.

Paul Chaumas Gayet, the bookseller, 34, Rue fossé du Chapeau Rouge, keeps a number of topographical works, maps, &c., besides the newest French publications.

Besides the *Grand Théâtre*, mentioned already (p. 267), open commonly three times a week, there is a smaller *Théâtre Français* or *des Variétés*, near the extremity of the Rue de l'Intendance, adjoining the Place Dauphine.

*Om nibuses* run along the quay from one end to the other, and in a direction across the town, from the river to its outskirts.

*Fiacres* stand for hire in the principal places: they are better but rather more expensive than those of Paris, charging 2 f. for the course, or, by time, 2 f. for the first hour, and 1 f. 80 c. for every hour after.

*Conveyances*.—*Mallepostes* daily to Paris by Tours in 34 hours; to Bayonne in 17 hours; to Nantes in 22 hours; to Toulouse in 16 hours.

*Diligences* daily to Paris (3 or 4) in 56 hours; to Toulouse several; to Bayonne in 17 hours; to Pau, Bagnères, Cauterets, and the Pyrenæan baths; to Libourne and Périgueux; to Nantes by Niort, Rochefort, and la Rochelle. You may post from Bordeaux to Paris in 48 hours, exclusive of stoppages.

*Steamers* to Nantes twice a week; to Havre 3 times a month in 60 hours—fare, 80 fr.

*Steamers on the Garonne*.—*Down the river* to Blaye and Pauillac daily, starting from the quay abreast of the

rostral columns; to Royan. Coaches thence to Rochefort 29 m. several times a week in 7 hours.

*Up the river*, daily to Langon and Marmande (R. 73), on the way to Pau or Toulouse; starting from the quay just above the bridge.

### *Environs of Bordeaux.*

A railroad has been formed from Bordeaux to La Teste, an inconsiderable place, 31 m. distant—a journey of about 2 hours, near the sea, on the borders of a great salt lake in the flat district of the *Landes*, whose sole productions are salt and pitch from the large fir forests.

This railroad has been most unaccountably made through a line of country where no previous traffic existed, to a spot possessing no commercial or manufacturing importance, in the vain hopes of generating these advantages in the midst of a desert. The speculators should have known that a railway is rather the consequence than the cause of traffic and commerce.

An excursion to La Teste (*Inn*: La Providence?) will give the traveller some notion of the nature of the sandy district called Les Landes, and will probably afford him an opportunity of seeing some of its inhabitants mounted on stilts. Here are several bathing establishments, and an Agricultural Association for redeeming the barren Landes.

*The banks of the Garonne* below Bordeaux, and the *wine district of Médoc*, which produces the claret, are described in R. 74.

The Garonne, above Bordeaux, in R. 73, p. 266.

The excursions to the Château de la Brède, the birth-place of Montesquieu, 2 hours' drive (R. 76), or to Blanquefort, the castle of the Black Prince, p. 276.

The wire suspension bridge of Cussac, on the way to Angoulême and Tours, is about 8 m. distant (see p. 231), and is worth a visit.

*Passages in the History of Bordeaux.*

The earliest mention of Bordeaux is in the geography of Strabo, who calls it *Bουρδιγαλα*, under which it was known to the Romans, and described in some pretty verses by Ausonius the poet, who was born here in the 4th century:—

“Impia jamdudum condemno silentia quod  
te,  
O patria, insignem Baccho, fluviiisque, vi-  
risque,  
Non inter primas memorem. \* \* \*  
Burdigala est natale solum, clementia cœli  
Mitis ubi, et riguæ larga indulgentia terræ;  
Ver longum, brumæque breves, juga fron-  
dea subsunt,  
Fervent æquoreos imitata fluentia meatus.”  
AUSON. *Claræ Urbes*.

Hadrian created it the capital of 2nd Aquitania.

Bordeaux belonged for nearly 300 years to the kings of England, who obtained it along with the duchy of Aquitaine by the marriage of Eleanor of Guienne, sole heiress of the last native duke, with Henry II., in 1152, and her inheritance became the fruitful cause of strife between England and France.

The Black Prince, having been invested by his father with the government of Guienne, resided many years at Bordeaux. Hence he set forth on that adventurous foray into the centre of France which led to the battle of Poitiers (p. 227). Here he held a brilliant court, to which Don Pedro the Cruel repaired, when driven out of Spain, with his two fair daughters, who were here married to the English Princes John of Gaunt and the Earl of Cambridge.

Here the Black Prince's son, Richard II., was born, and surnamed from his birthplace Richard of Bordeaux.

The Bordelais retained their affection for the English long after the downfall of our sway in the rest of France, in the reign of Henry VI.; revolting from the rule of Charles VII. to receive within their walls the valiant Talbot (1453), but his speedy

defeat and death forced them again to submit to the French monarch.

Bordeaux was the seat of one of the provincial Parliaments of France, or high court of justice, composed of laymen and ecclesiastics, who registered the royal decrees and transmitted them to the lower courts.

One of the most momentous events of the civil war of the Fronde was the siege of Bordeaux, undertaken by the royal army with Mazarin, young Louis XIV., and his mother at its head, while the city held for the Princess de Condé, the Dukes of la Rochefoucauld and Bouillon, at the head of their vassals, assisted by the townspeople and backed by the Parliament of Bordeaux. The heroic wife of the Great Condé having escaped the clutches of the Cardinal, who already held her husband in prison, and wished to transfer her and her son to like duration, traversed the country from Chantilly, and after a series of adventures and escapes threw herself into this city, where the interest of the Condés was strong. Her beauty, eloquence, and forlorn position enlisted in her favour the enthusiasm of the magistrates and townspeople, and upon her persuasion they agreed to admit her allies and resist the force of Mazarin. She captivated all hearts, and became, as it were, queen of Bordeaux, then the second city of the empire; and Condé, while shut up in Vincennes and employed in watering his pot of violets, learned with surprise that his feeble princess was acting the part of a general, conducting the defence of a town, and exposing her life on the walls. The defence was conducted with such obstinacy, that at the end of several weeks, Mazarin, having made little progress, was happy to offer fair terms to the Frondeurs. The citizens of Bordeaux were right glad to be released from the blockade just at the approach of the vintage, for their warlike enthusiasm had begun to cool at the prospect of being shut out from their vineyards.



A great impulse was given to the French Revolution by the inhabitants of Bordeaux. At the beginning of the reign of Louis XVI. the Parliament of Bordeaux, having refused to acknowledge the edict of the king, was banished to Libourne, and in consequence contributed largely to the clamour for the assembling together of the States-general. Many of the persons of greatest eloquence and talent sent as members to the Legislative Assembly, including Vergniaud, Gaudet, Gensonné, Ducos, &c., were returned by the department of the Gironde, whence the party which they composed was called the *Girondins*; but having themselves brought on all the evils of the Revolution, they were swallowed up by the monster they had created, and guillotined for the most part by the stronger party of the Montagne, which succeeded them in the Convention. Bordeaux had a Reign of Terror of its own; the guillotine was erected in the square near the centre of the town, called Place Dauphine (in honour of the Dauphin, afterwards Louis XIII.), but then named Place de Justice, and some of her best citizens were sacrificed. No less than 500 persons suffered death here, whom either envy of their merits, or cupidity for their wealth, caused to be condemned under the false charge of conspiracy against the sovereignty of the people.

The names of some of the streets afford a curious commentary on the history of the town, and a proof among many of the mutability of the French nation. The *Place Louis-Philippe* was Place Louis XVI. down to 1830, and a statue of that king had been prepared, and its pedestal actually erected, when the July Revolution broke out. The *Cours de Douze Mars* was the name given to the row of houses now called *Trente Juillet*, because on the former day, in 1814, the Duc d'Angoulême made his triumphant entry into Bordeaux, at the invitation of the mayor Lynch (whose name has also been erased

from a street which bore it), and amidst the acclamations of a part of the inhabitants.

On the 8th March in that year, 2 divisions of the British army, under Marshal Beresford, marched upon Bordeaux; where the presence of the dauntless Duchesse d'Angoulême, who had thrown herself into the town to revive the dormant spirit of loyalty towards her family, and the intrigues of the Duc d'Angoulême, contrary to the advice and wishes of the Duke of Wellington, caused the premature proclamation of the Bourbons by the royalist mayor. The Duke had expressly declared that "he could not interfere to produce any declaration in favour of the Bourbons, nor to support their measures by military force."

#### ROUTE 74.

THE GARONNE AND GIRONDE FROM BORDEAUX TO LA TOUR DE CORDOUAN; THE WINE DISTRICT OF MÉDOC.

100 kilom. = 62 Eng. m.

*Steamers* daily to Blaye and Pauillac—4 or 5 times a week to Royan; fare, 15 and 8 frs.

*Diligences* daily along the S.W. side of the river to Château Margaux and Lesparre, through the midst of Médoc, and along the rt. bank to Blaye. The road on the W. side of the Garonne passes Bouscat and Bruges, so named by Flemish settlers established here by Henri IV. to drain the marshes, and *Blanquefort*, whose *castle*, a favourite residence of the Black Prince, still preserves part of its outer circuit walls and fosse, and some of its apartments entire. The leopards of England are only half effaced from the walls. It is a picturesque object. Thence the road runs to Margaux.

#### *Bordeaux Wines.*

The long tongue of land stretching N. from Bordeaux, between the sea on the one hand, and the Garonne

and Gironde on the other, is called *Médoc* (quasi medio aquæ), because nearly surrounded by water. It is the N. termination of the extensive district of sand hills and sand plains, called Les Landes, extending from Bayonne north, which changes to a bank of gravel on approaching the l. bank of the Garonne, and forms a narrow strip of land nowhere more than 1 or 2 m. broad, raised from 50 to 80 ft. above the river, which is planted with vines, and contains some of the most precious vineyards in the world. The transition is abrupt from this gravel bank near the river to the mere Landes or sandy waste running to the W. and S. of it, producing nothing but firs, furze, and heath. The soil of Médoc is a light gravel, and indeed on the spots where some of the best wine is produced, it appears a mere heap of white quartz pebbles rolled, and about the size of an egg, mixed with sand. The best wine is not produced where the vine-bush is most luxuriant, but on the thinner soils, where it is actually stunted—in ground fit for nothing else, in fact, where even weeds disdain often to grow. Yet this stony soil is congenial to the vine, retaining the sun's heat about its roots after sunset, so that, in the language of the country, it works (*travaille*) in maturing its precious juices as much by night as by day. The accumulation of sand and pebbles, of which this soil is composed, is apparently the spoils of the Pyrenean rocks, brought down by the torrents tributary to the Garonne and other great rivers, and deposited in former ages on the borders of the sea. At the depth of 2 or 3 feet from the surface occurs a bed of indurated conglomerate, called *alios*, which requires to be broken up before the vine will grow, as it would stop the progress of the roots, being impenetrable to their fibres. The vine is trained exclusively in the fashion of espaliers, fastened to horizontal laths, attached to upright posts at a height not exceeding  $1\frac{1}{2}$  or 2 feet from the

ground, running in an uninterrupted line from one end of the vineyard to the other. Manure is scarcely used in the culture, only a little fresh mould is laid over the roots from time to time; but the plough is driven between the vines four times every season, alternately laying open and covering its roots: this is performed by oxen, who, with steady and unvarying pace, thread the ranks without treading on the plants. Manure destroys the fine quality of the wine, and moisture or standing water is most injurious to the plant. The vine begins to produce at 5 years of age, and continues productive sometimes when 200 years old, provided its roots have found a congenial soil to insinuate (*pivoter*) their fibres, which they sometimes do to a distance of 40 or 50 ft., when the soil is dry and deep enough to protect them from the sun. The wines are classed into growths (*crus*), according to their excellence, and only a very small part of the strip of land before mentioned is capable of producing the “*premiers crus*,” indeed so capricious is the vine, that within a few yards of the finest vineyards it degenerates at once. The following list will show the classification of Bordeaux wines, or clarets as we call them in England (though whence the name, or what its meaning, are unknown in Médoc), together with the average quantity of each produced in one season. The tun, or *tonneau*, contains 4 hogsheads, called *barriques*.

First Growths.	{	Château Margaux	-	140—160	} Tuns.
		Château Lafitte	-	120	
		Château Latour	-	120	
		Haut Brion	-	60—80	

The last is properly a vin de Grave, grown on the Garonne above Bordeaux, yet is classed with Médoc wines; it is less in repute now than formerly.

Second Growths.	{	Mouton (Lafitte)	-	120—146	} Tuns.
		Léoville, the best of the			
		wines of St. Julien	-	145—186	
		Rauzan (Margaux)	-	75—95	

La Rose Gruau, Pichon Longue-



ville, Durfort, Degorse, Lascombe, Cos-Destournelle, in all about 800 tuns.

It is needless to enumerate those of 3d, 4th, and 5th rate growths, many of which are produced in the vicinity of the first-rate vineyards, at the villages or in the communes of Margaux, Lafitte, Latour, without partaking in their excellences. The goodness of a season will sometimes give an excellence to second-class wines, while in bad years those of first class sink to mediocrity, and are not fit for exporting to England (such is the importance of maintaining the character of these wines there), but go to Holland, or are retained in France. This is so well understood, that some years ago the proprietor of the vineyard of La Rose used to hoist on a flagstaff above his house, the English flag in good years, the Dutch in middling, and the French in bad years. England consumes more than one-half of the premiers crus, and very little of inferior sorts; Russia takes a good deal, Paris little of the best; Holland is the great mart for wines of second quality, and the third-rate sorts or vins ordinaires are chiefly used in France. An erroneous notion prevails in England that clarets are prepared for the English market by a certain mixture of brandy. This is not the case; brandy would destroy the wine. A mixture does take place to adapt the wines to the English palate; but they are doctored with strong-bodied (corsés) Rhône wines, and chiefly with Hermitage, the principal consumption of which is for this purpose. The practice of mixing is very general. The characteristic of the good wines of Bordeaux is their aroma or bouquet; spirit they have none, and will distil away into nothing, yet the aroma will be retained and penetrate even through the Rhône wine, when it is judiciously added. The average price of a hogshead (barrique) of genuine wine of first growth, in the cellar of the first houses at Bordeaux,

is 50*l.*, which with carriage, duty, bottling, &c. amounts to 80*l.*, rather more than 70*s.* a dozen. A first growth wine of a fine vintage is scarcely to be had at a less price; indeed the whole produce of Château Margaux has been sold on the spot for 1000 francs the hogshead, in the case of a very first-rate vintage. Very great skill is shown, and much experience required, in the making of the wine, in the compounding of various growths and qualities, and in the preservation of it: a promising vintage often disappoints expectations, while a bad one sometimes turns out excellent; indeed all that can be said of the premiers crus is, that they are the wines which most often succeed. The total produce of Médoc, in average years, is from 150,000 to 170,000 hogsheads, of which about 6000 go to England.

Travellers desiring to visit the principal vineyards of Médoc may take the steamer to Pauillac (which may be reached in 4 hours, or 6 against tide), which is not far from Lafitte and Latour, or the coaches which run daily will convey them to Margaux. The high road thither, and thence to Pauillac, traverses the centre of the narrow strip of land forming the wine district. For some distance out of Bordeaux it passes a series of country houses.

The Garonne below Bordeaux is a fine broad tidal river, but very much charged with mud, having few features of interest, its banks being chiefly low, while an intervening fringe of marsh and meadow land, grown over with willows, separates the river from the vineyards, little of which can be seen from the deck of the steamer.

Nothing can be finer than the view of the long crescent quay of Bordeaux, and the broad river crowded with shipping, many of them 3-masted vessels, as the steamer casts off from the quay, opposite the rostral columns, and skirts the long Faubourg des Chartrons.

Rt. Lormont is a picturesque eminence, covered with wood and vineyards, interspersed with some neat country houses on its top, and below its steep side. In a recess under the hill stands the village, with a domed church, surmounted by a château.

Rt. below Montferrand, a small village hid by poplars, is a large *Château*, the residence of M. de Peyronnet, one of the ministers of Charles X., who signed the ordinances.

Rt. The tongue of land between the Garonne and Dordogne, called *Entre Deux Mers*, which produces a vast quantity of wines of inferior quality, draws to a termination at the low point called *Bec d'Ambés*. The union of the two rivers forms the broad estuary of the *Gironde*, whence the department is named. The monsters of the revolutionary Mountain, after overwhelming in 1793 their antagonists, the Girondins (so called because the leaders came from this part of the country), swamped even the name of the department, which for several months bore that of "Ambés." A long line of low hills, faced towards the water with cliffs, lines the l. bank of the *Gironde* and *Dordogne*. Looking up the *Dordogne*, you perceive on an eminence Bourg, a small town of 3855 inhab., where Louis XIV. when a child resided with his mother, Anne of Austria, for nearly a year (1649-50) during the continuance of the siege of Bordeaux (see p. 272). Mazarin, in order to superintend the operations and watch the leaders of the Fronde within the city, had repaired in person to the S., dragging with him the King, the Regent, and the Court. The ladies in waiting complained bitterly of the want of a theatre to enliven the ennui of their residence, and the cardinal got angry with the mayor because the whole place could not furnish a sedan-chair to carry him through the steep and dirty streets. The extensive vine-

yards around Bourg produced the wines (claret) esteemed the best in the district 200 years ago, before the cultivation of the vine in *Médoc* had commenced, which does not date farther back than 250 years.

Rt. The steamer stops to set down or take up passengers at the *Pain du Sucre*, a landing-place at the mouth of the *Dordogne*, close under the *Bec d'Ambés*, and about  $1\frac{1}{2}$  m. below Bourg. Two large islands are here formed in the middle of the *Gironde*.

L. Nearly abreast of the *Pain du Sucre*, a glimpse may be obtained of the mansion of *Château Margaux*, situated some distance inland: it is an Italian villa, the handsomest in *Médoc*, and belongs to the heirs of the Spanish banker, the Marquis d'Aguado, though rarely inhabited, owing to the malaria which prevails around it. It stands in the midst of the vineyards producing the celebrated wine of *Château Margaux*, the most esteemed growth of *Médoc*. The grape which yields it is small and poor to the taste, with a flavour slightly resembling that of black currants. The *Château* is about  $\frac{1}{2}$  m. from the village of *Margaux*, which abounds in neat whitewashed villas, seated in little gardens, amidst acacia hedges and trellised vines. It is about 20 m. distant from Bordeaux.

Rt. The yellow cliffs along the river side are pierced to form cellars, in which is deposited the wine grown above them: and for a considerable extent near *Gauriac*, they are excavated in quarries of building stone. At the base of the cliffs are several small villages.

Rt. *Blaye*. The dead walls and gloomy-looking modern bastions of the citadel of *Blaye* are seen projecting over the river at a height considerably above it. In the midst of them stands a fragment of the old feudal fortress, whose towers may be seen surmounting the turfed ramparts. This citadel was chosen as the prison of the *Duchesse de Berri*, who was confined here in a double



sense after her capture in La Vendée (see Nantes, p. 167), having been brought to bed of a daughter in 1833. After a detention of 7 months she was sent back to Naples. The body of Roland the Brave was, according to tradition, transported hither from Roncesvaux, by Charlemagne, and interred in the *Church of St. Romain*, with his sword *Durandal* at his head, and his famous horn of ivory (Oliphant), with which he had awakened the echoes of Fuentarabia, at his feet. The body was afterwards transported to St. Seurin, at Bordeaux.

Opposite Blaye several islands have been formed in the middle of the river by the deposits brought down by the Dordogne and Garonne, and are constantly increasing. On one of them is planted the little fort *du Pâté*, so called from its round shape. It crosses its fire with that of the fortress of Blaye on the rt. bank, and of Fort Médoc on the l., and thus commands the passage of the Gironde.

To the N. of Margaux the vines decline in quality; and it is not until after an interval of several miles of inferior vineyards that we reach others, producing wine of reputation, in the vicinity of

L. Beycheville, lying within the commune of *St. Julien*, a name of note on account of the wine grown in it. The *Château de Beycheville*, situated on the height in the midst of valuable vineyards, is the seat of M. Guestier, Pair de France, ancien Député, and one of the first wine-merchants of Bordeaux.

Here begin some of the most renowned vineyards of Médoc, which lie crowded together in almost uninterrupted succession, within a narrow space, stretching about 6 m. N. of Beycheville.

About 1½ m. off is *Château Léoville*, which produces one of the best second growths, nearly equalling the first growths. The estate is divided between Mr. Barton and M. de Las Cases. In the same commune is the vineyard of *La Rose*, a prime second growth; and in the adjoining one of

St. Lambert is the vineyard of *Château Latour*, yielding a well-known wine, premier cru. The estate, which does not exceed 330 acres, was sold a few years ago for 60,000*l.* The second growths, Pichon-Longueville and Mouton, come from the same quarter.

L. Pauillac, a small sea-port, behind which, at the distance of about 1½ m., is the vineyard of *Château Lafitte*, producing one of the three best wines of Bordeaux; it is the property of Sir Samuel Scott, and does not yield more than 400 hogsheads yearly. The region of good wines extends N. as far as Lesparre, but the wines are far inferior to those of the commune of Pauillac.

The aspect of the vine district of Médoc is that of an undulating country, slightly raised above the Garonne, affording here and there peeps of the river between the gentle hills and shallow gullies which intersect it. It abounds in marshes and stagnant pools, which render it unhealthy, so that the châteaux which occur in it are inhabited only for a small part of the year by their proprietors. Yet the district is populous, a group of cottages being attached to almost every vineyard, and inhabited by the peasants who cultivate it. The vineyards are open fields; even those of greatest value being for the most part unprovided with walls, or even hedges, in order to avoid the loss of any space of ground which must be left round the margin to allow the plough to turn. When the grapes begin to ripen, a temporary fence is formed round the vines, of twisted boughs interwoven with furze, to keep out the dogs, which are most destructive consumers of grapes. Further to deter both bipeds and quadrupeds from committing depredations, guards armed with guns are posted on the watch, day and night, while streaks of paint, and bits of white paper stuck upon poles, announce that the vineyard is strewn with poisoned sausages, and that the grapes themselves are smeared with

some deleterious mixture. The vines are planted in quincunx order on ridges (about 3 ft. apart): they are trained to espaliers, and not allowed to rise more than 2 feet above the ground. In the best vineyards they barely cover the soil, but allow the singular mass of pebbles, of which it almost exclusively consists, to appear between the rows. The growth of the vine is confined within a narrow line of demarcation, and the transition is most abrupt from the most precious land to an uncultivated sandy desert. The distance of a few feet makes all the difference. The vintage takes place in the month of September, and it is then that Médoc presents a scene of bustle, activity, and rejoicing. The proprietors then repair hither with their friends and families to superintend the proceedings and make merry: vigneron pour in from the l. bank of the Gironde, to assist in the gathering. Busy crowds of men, women, and children sweep the vineyard from end to end, clearing all before them like bands of locusts, while the air resounds with their songs and laughter. The utmost care is employed by the pickers to remove from the bunches all defective, dried, mouldy, or unripe grapes. Every road is thronged with carts filled with high-heaped tubs, which the labouring oxen are dragging slowly to the *Cuvier de pressoir* (pressing trough). This is placed usually in a lofty out-house, resembling a barn, whence issue sounds of still louder merriment, and a scene presents itself sufficiently singular to the stranger. Upon a square wooden trough (pressoir) stand three or four men with bare legs all stained with purple juice, dancing and treading down the grapes as fast as they are thrown in, to the tunes of a violin. The labour of constantly stamping down the fruit is desperately fatiguing, and without music would get on very slowly: a fiddler, therefore, forms part of every wine grower's establishment; and as long as the instrument pours forth its merry

strains, the treaders continue their dance in the gore of the grape, and the work proceeds diligently. The next process is to strip (*égrapper*) the broken grapes and skins from the stalks, with an instrument called *dérappoir*, and to pour the juice and skins into vats to ferment. The skin rises to the top, and the wine is drawn off into hogsheads as soon as fermentation is carried to the proper extent, in judging of which the utmost experience is required, as on it depends much of the quality of the vintage.

---

At Trompe-Loup is the Lazareth, where vessels from the Levant perform quarantine.

L. The cultivation of the vine ceases to the N. of Castillon, and the extreme point of Médoc, towards the mouth of the Gironde, consists of rich pasture land, famed for its breed of cattle, and some corn-fields. It lies on a level with the surface of the sea, and was redeemed from the condition of marsh by a colony of Flemings, invited over to France by Henri IV., who surrounded it with sea-dykes like their own country.

Rt. Mortagne. A diligence runs hence to Saintes in communication with the steamer.

Rt. Royan (*Inns*: H. de Bordeaux, best; d'Orléans) is a neat small seaport town in the Dépt. of the Charente, about 25 m. from Rochefort, whither a diligence runs. (R. 62.) It is a station of pilots, and is resorted to for sea-bathing.

On an isolated rock outside the mouth of the Gironde, which is beset with dangerous sandbanks, rises the lighthouse called *La Tour de Cordouan*, whose beacon guides mariners entering or quitting the river. It is a circular structure of three stories, the central one being domed like a church, from the midst of which rises a sort of pepper-box turret. It was designed in the reign of Henri II. by *Louis de Foix*, one of the architects



of the Escorial, 1611, who is said to have died here, and to have been buried within it. It replaced a light-house founded by the English 1362-71, while the Black Prince was governor of Guienne. (See Rymer.)

### ROUTE 76.

BORDEAUX TO BAYONNE, ST. JEAN DE LUZ, AND THE SPANISH FRONTIER.

227 kilom. = 184 Eng. m.

*Malleposte* daily in 17 hours, diligences daily in 24 hours, to *Bayonne*.

For a mile or two out of Bordeaux a succession of neat villas lines the road, and the ground is mostly laid out in vineyards. Here, however, the vines grow upright, and are not trained along the ground as in the more famous district of Médoc (p. 277). Their produce is a wine as black as ink, full of spirit, from which brandy is distilled. Before the end of the stage the country becomes open and heathy; it is, in fact, the border of that extensive region of flat sand called the *Landes*, to avoid which the high road to Spain makes a considerable circuit. (See Route 77.)

11 Bouscaut. Between 2 and 3 m. to the rt. of La Prade, a hamlet which is passed about the middle of this stage, lies the *Château de la Brède*, the birth-place and family seat of Montesquieu. It is a low many-sided castle, probably of the 15th cent., surmounted by a circular donjon entirely surrounded by the waters of the Guémort, which forms a broad fosse around it, and served anciently to defend it from foes, since it can only be entered by three bridges (once drawbridges). It is far from imposing, either without or within; but retains its primitive condition nearly unaltered, together with some old portraits of the family Secondat, and, above all, the *chamber* of Montesquieu, with his simple bed, arm-chair, &c., nearly as he left it. The wainscoting on one side of the fireplace is rubbed by the motion of his

foot resting against it, a habit attributed to him when seated in his easy chair lost in thought, meditating on his works. It was here that he composed his work "*Sur la Grandeur et la Décadence des Romains*," while it is reported that the dark feudal cachot beneath the castle, which is entered by a stair from his room, was his resort while he was preparing his reflections "*On the Liberty of the Subject*."

12 Castres. The road ascends the valley of the Garonne, but at the distance of 3 or 4 m. from the river, whose banks are described in R. 73.

11 Cerans. *Barsac*, passed in this stage, produces one of the best *white wines* grown on the Garonne; and 4 or 5 m. S. of Preignac lies the *château* of *Sauterne*, which gives its name to the best of all the white wines of this district. (See p. 266.)

12 Langon, on the l. bank of the Garonne, is described in R. 73. (*Inn: Cheval Blanc*.) Here the road to Toulouse (R. 73) branches off, and our road quits the Garonne and turns nearly due S., penetrating through a portion of the *Petites Landes*. Few houses and no villages occur before -

15 Bazas, an ancient town of 4300 inhab., which existed in the time of the Romans, and is mentioned under the name *Vesates* by Ausonius, whose father was born here. It has a Gothic church, once a cathedral, without transepts. The sculpture on the three portals of its façade is much defaced. Bazas retains on its outskirts fragments of the old town walls.

17 Captieux lies in the midst of sand wastes and pine forests; the country presents all the characters of the *Landes*, and the road enters the Dept. so called shortly before reaching

15 Les Traverses.

15 Roquefort, an insignificant town of 1600 inhab., named from the rocks of tufa which border the bank of the Douze, a tributary of the Adour. This place must not be confounded

le France

u. 700

with Roquefort, famed for cheese, in the Dépt. Aveyron, near Rodez.

About 20 m. W. of this, in the midst of the sandy Landes, is an obscure and wretched hamlet called *Labrit* or *Albret*. It was the cradle of the Sires d'Albret, one of the oldest families of France, from whom sprang the illustrious Henri IV., the son of Jeanne d'Albret.

Here the road from Bordeaux to Pau branches off to the l. (R. 80.)

12 Caloy. The chain of the Pyrenees, 30 leagues distant, may already be discovered in clear weather.

10 Mont de Marsan (*Inn*: H. des Ambassadeurs; a very tolerable sleeping place; Ortolans may be had in August) is chef-lieu of the Dépt. des Landes (3774 inhab.), and enjoys some commerce by virtue of its position at the junction of two streams, the Douze and Medou, which, becoming navigable here, take the name of Medouze. It is united with the Garonne by the Canal des Landes, nearly 60 m. long, designed to open a communication between Bayonne and Bordeaux when the sea is closed in time of war.

Roads branch off hence to Pau (R. 80), and to Orthez.

The road hence is somewhat less dull: it lies through extensive forests of spindly pines, whose sides are rasped or grooved to extract the *resin* which exudes from the wound, and is collected in a hollow at their foot.

13 Campagne. Beyond

14 Tartas, where the Medouze is crossed by a new bridge, are some fine oak woods.

11 Pontons. As before, the same alternation of pine woods and bare sand, not a pebble to be seen. Pyrenees well seen beyond Pontons.

Pouy, a village on the l. of the road shortly before reaching Dax, was the birth-place of the philanthropic founder of the order of Sœurs de la Charité, and of foundling hospitals, St. Vincent de Paul. When a boy he tended his father's flock in the sandy heaths near the Lazarist

convent of Buglose. The road passes through the village of

12 St. Paul de Dax, about a mile distant from the town of Dax (*Inns*: H. St. Etienne; de St. Esprit), which lies on the l. bank of the Adour, and is reached by a bridge of wood. Its name probably comes from its *hot springs* (de aquis), which are one of the curiosities of Guienne, and doubtless induced that bath-loving people, the Romans, to found here their settlement Aquæ Augustæ Tarbellicæ. They rise nearly in the centre of the town, and are received in a large square basin enclosed with porticoes, whence rise such clouds of steam as in a frosty morning to envelope all the town. The temperature at the source is 212° Fahrenheit, a scalding heat. The water is nearly tasteless, and though only partially used medicinally, is much employed by the washerwomen. There are several other sources in and about the town. Near the bridge are portions of the old fortifications; and Roman masonry may, it is said, be discovered in their substructions.

The tertiary strata near Dax abound in fossil shells.

The postmaster is entitled to charge 2 kilom. extra on carriages which cross the Adour into Dax from St. Paul.

The road beyond Dax traverses numerous forests of cork trees, which being stripped of their flaky bark to stop the claret bottles of the merchants of Bordeaux, have a singular effect, from the dark brown colour of their naked trunks. A new skin speedily repairs the loss of the old.

15 St. Geours.

The Pyrenean range now forms a grand feature in the landscape. They are not unlike some views of the Grampians, in which sharp peaks here and there surmount intervening roundbacked hills: the most conspicuous and picturesque peaks seen from this are the Arrhune in France, and the Quatre Couronnes in Spain. Near



13 Cantons, a large pond or étang is passed, and a peep is obtained over the Bay of Biscay on the rt.

The direct road from Bordeaux across the *Grandes Landes* (R. 77) falls into ours at St. Vincent, and the *Landes* cease altogether at Oudres.

The descent upon Bayonne presents that town under a striking aspect, seated on the Adour, surrounded by fortifications. A short way before you reach the Octroi, a lane on the rt. leads down to the *Cimetière Anglais*, a simple enclosure between 4 walls, planted with poplars; it contains the remains of many brave British soldiers, and several officers of the Coldstream Guards, who fell in the sortie from Bayonne, April 14, 1814. Bayonne is entered by the Faubourg of St. Esprit, in which is situated the *Citadel*, the strongest of the military works. The town itself is reached by a narrow bridge of boats over the Adour, about to be replaced by a stone bridge, and, after crossing the triangular strip of land between the rivers, by a permanent stone and iron bridge over the Nive.

19 BAYONNE.—*Inns*: H. St. Etienne; H. du Commerce; H. de l'Europe.

Bayonne, a strong fortress of the first class, commanding the Passes of the W. Pyrenees, and one of the two carriage roads leading from Spain into France, has an agreeable situation at the junction of the Nive with the Adour, and is divided into three parts, by these fine broad rivers, which are lined with quays, and always include a small quantity of shipping. The suburb St. Esprit, on the rt. bank of the Adour, lies within the *Dépt. des Landes*, and alone includes 5897 inhab. (more than the chief town of the *dépt.*), among whom are 2000 Jews, descendants of those expelled at different times from Spain. On an eminence rising above this suburb, just at the lower end of it and commanding with its formidable bat-

teries the town, both the rivers, and the plain to the N., rises the *Citadel*, the most formidable of the works, laid out by Vauban, and greatly strengthened, especially since 1814, when it formed the key to an intrenched camp of Marshal Soult, and was invested by a detachment of the army of the Duke of Wellington, but not taken, the peace having put a stop to the siege after some bloody encounters. The last of these, a dreadful and useless expenditure of human life, took place after peace was declared, and the British forces put off their guard in consequence. They were thus entirely taken by surprise by a sally of the garrison, made early on the morning of April 14th; which, though repulsed, was attended with the loss of 830 men to the British, and by the capture of their commander, Sir John Hope, whose horse was shot under him, and himself wounded. The French attack was supported by the fire of their gun-boats on the river, which opened indiscriminately on friend and foe. 910 of the French were killed. Admission to the citadel is obtained by a ticket from the commandant; but, except to a military man, it possesses nothing of interest. Steep approaches, resembling inclined planes, lead up to it, deep fossés surround it, nearly vertical walls 40 feet high and numerous bastions flank and enfilade every access to it: visitors are not allowed to mount the ramparts.

Bayonne Proper occupies the triangular space between the two rivers, and stretches for a considerable distance up the bank of the Nive, which is crossed by 3 bridges. Its total population, excluding St. Esprit, is 15,912 souls. Many of the streets have a half Spanish character from the piazzas running under the houses. The handsomest quarter of the town is that adjoining the theatre, newly built, consisting of fine tall houses.

The only building of consequence is the *Cathedral*, ugly externally, but within a fine lofty church in the

pointed Gothic of the 13th century, with choir, and transepts very short. The arms of England are still visible on its roof. The cloisters behind, in the florid style, nearly the largest in France, deserve notice. From the top of its tower there is a good *view* of the distant Pyrenees, of the town, rivers, and citadel, and of the spot a little below it, at the extremity of the long avenue of trees, where a part of the British army under Sir John Hope crossed by a bridge of boats furnished from the fleet of Admiral Penrose, and transported with much difficulty over the bar, Feb. 23-27, 1814, in order to invest the citadel.

As very malignant calumnies have been spread by some French writers respecting the conduct of the Duke of Wellington's army in France, it may not be amiss to refute them by the unexceptionable testimony of one of their own writers, and an eye-witness, the late M. Vayse de Villiers, author of the *Itinéraire de la France*, the best guide book for that country. He traversed the theatre of the war only a few months after the occupation by the Duke of Wellington, and states that so far from laying waste the country to a distance of a league around Bayonne, as a French writer had asserted, "Il avait établi une telle discipline qu'il était accueilli partout comme libérateur."—*Route de Paris en Espagne*, p. 91.

The Duke's own immortal Dispatches show with what severe discipline he prevented the troops, Spanish and English, under his command, imitating the cruel injuries which the French army had inflicted on Spain and other countries invaded by them.

The construction of the bridge over the Adour below Bayonne, and the passage of the Allies across it, display the genius of Wellington in conceiving, combining, and executing a measure deemed impossible by his opponents; and is styled by Colonel Napier "a stupendous undertaking,

which will always rank among the prodigies of war." The impediments consisted in the breadth of the river, the rapidity of its current, the height to which the tide rises (14 ft.), the difficulty of procuring and transporting the materials of the bridge: since, if sent by land, through bad and difficult roads, they must have alarmed the enemy: if by water, the bar, passable only at high water, and surf at the river's mouth, rendered the entrance of boats next to impossible. The latter measure, however, had been decided on by the Duke; and to effect this purpose, a little flotilla of chassemarées had been prepared in the Spanish harbour of Passages. But the long prevalence of storms and contrary winds had rendered its approach impracticable; and the gallant Sir John Hope, to whom the execution of this measure had been entrusted by the Duke of Wellington, at last on the 23rd of February, 1814, began to push his troops across upon a raft attached to a hawser; and thus in the teeth of a strong fortress and garrison of nearly 15,000 men, 600 men of the Guards gained the opposite bank; the French gun-boats which guarded the river being silenced by rockets, three of them burnt, and a sloop of war driven up the river under the guns of Bayonne, while the same effective weapons kept the garrison at bay. Next morning, in spite of the tempestuous weather, and the raging surf on the bar, which was so furious as to leave no strip of black water to point out the passage; without pilots, with no land-marks on the shore, the little fleet made for the mouth of the Adour. Each vessel had an engineer on board, and a supply of timber, cables, &c., and aided by men of war's boats from the fleet, they boldly dashed into the midst of the breakers, blindly seeking the entrance. Several of the foremost, mastered by the wind and the waves, ran aground or were dashed ashore, and their crews pe-



rished. This did not deter the others, however; one more fortunate boat discovered the only safe channel; and the rest following in its wake, gained smooth water within the bar—a glorious and gallant exploit. The twenty-six chassemarées thus introduced were moored head and stern by ropes stretched over the dykes which line the river, at a spot where it is 800 ft. broad, at a distance of about 3 miles below Bayonne. Platforms of loose planks were laid between the boats, and the ropes were left slack, so as to allow the bridge to rise and fall with the tide: yet this seemingly frail structure was strong enough to bear the heaviest artillery, and it was finished by the 26th. This deep-laid scheme entirely foiled Marshal Soult, whose attention had been drawn off by the British general to an attack among the Gaves, the tributaries of the Adour high up the country, at the very moment when the passage of that river was effected close to the sea.

Bayonne is a town of commerce as well as of war, though its port is of comparatively small use, on account of the shifting bar at the *mouth of the Adour*, which can only be passed at high-water, and not without danger at some seasons, though the employment of tug-steamers now diminishes the risk. In the 14th or 15th century the Adour changed its bed, owing to its mouth becoming obstructed by shifting sands or dunes blown up by the winds, and running N. parallel with the coast within this sand-wall, until it found an outlet either at Cape Breton, or at Vieux Boucaut. This lasted down to 1579, when the engineer, Louis de Foix, restored it to its old channel, called Boucaut Neuf. In 1684, however, it broke a fresh channel for itself to the l., in the direction of the *Chambre d'Amour*, but was brought back again shortly after to the bed by which it still finds a passage to the ocean through a waste of sand-hills.

The commerce of Bayonne consists

chiefly in Spanish wool, which is largely imported, and in an extensive smuggling trade carried on with that country.

Excellent *chocolate* and *eau de vie* are made here; but the *Bayonne hams*, so called because largely exported hence, are reared and cured among the Pyrenees, near Orthez and Pau. Some ships are built here.

From what has been said, it will be perceived that Bayonne has few sights to amuse the passing stranger. The well-supplied *markets* abounding in fruit and vegetables, sold at the cheapest rates, are worth a visit; and these, or the promenades, will afford an opportunity of seeing the Bayonnaise ladies, who are remarkably pretty, as well as the Basquaise peasants, who are also distinguished by pretty faces and good figures, and contrast with the inhabitants of the Landes to the N. of Bayonne.

Those who desire a pleasant shady walk and fresh air, should repair to the *Allées Marines*, an avenue of trees more than a mile long, on the l. bank of the Adour, below the town and opposite the citadel, reaching down almost to the bend of the river, near which the Duke threw his army across.

A little way outside the town is the dilapidated *Château de Marrac*, destroyed by fire in 1825 and gutted. It belonged to Napoleon, who here received the degraded sovereigns of Spain, Charles IV. and his queen; and her minion Godoy likewise. The Emperor also brought hither to meet them Ferdinand Prince of Asturias, whom, by false pretences, he had entrapped from Madrid in 1808: and in this château, under threat of death or imprisonment, they resigned to him their hereditary rights to the crown of Spain.

Bayonne was the capital of the ancient district, enclosed within the Adour and Bidassoa, called Pays de Labourd, from *Lapurdum*, by which it was known down to the 10th century. The name Bayonne is

merely the Basque *Baia una*, a port. Hence comes the word *Bayonnette*, said to have been invented in this neighbourhood (see p. 286), and first made here. The gloomy old *Castle* opposite the Sous-Préfecture, now a barrack, was probably the residence of Catherine de Medicis, when, dragging with her her weak son, Charles IX., she repaired hither to that secret conference with the cruel Alva, in 1563, at which, it is now known, the atrocious massacre of the St. Bartholomew's night was suggested and decided on. Yet Bayonne has the rare credit of refusing to execute the bloody orders of Charles IX., to slay all the Protestants in the town, owing to the firmness of the governor Dapremont, Vicomte d'Orthez, who told the king that the town of Bayonne included only good citizens and brave soldiers, but not a single executioner.

The chief place of resort for the inhabitants of Bayonne out of the town is the little watering-place of *Biaritz*, described farther on (p. 284).

*Cambo*, in the vale of Nive, is also a pretty watering-place, with mineral baths.

A short but interesting *excursion into Spain* may be made by taking the diligence to St. Sebastian, which starts every morning. You pass through a portion of the country which was the theatre of the late war, visit the citadel of St. Sebastian and the singular land-locked harbour of Passages, eat an olla, and smoke a cigarillo, and may return to Bayonne the following afternoon. See *HANDBOOK FOR SPAIN*.

The *British consul*, residing at Bayonne (Captain Graham), will sign his countrymen's passports for the journey.

In the coach-offices and inns at Bayonne will be found hung up advertisements of approaching *Bull Fights*, to be held at Vittoria, Tolosa, Saragossa, and other places in the N. of Spain, in the vicinity of the French frontier.

*Conveyances*:—*Mallepostes* daily to Bordeaux in 17 hours: to Toulouse in 21 hours.

*Diligences* daily to Bordeaux (2 or 3); to Toulouse; to Pau, by Orthez.

*Conveyances* into Spain: to Madrid—*Malleposte* travels by night, and is three nights on the journey.

*Diligences* belonging to 2 different companies to Madrid.

*Diligences* every other day to Tolosa and St. Sebastian in 10 hours.

---

The Southern Road quits Bayonne by the *Porte d'Espagne*, through which Napoleon poured so many gallant armies in succession into the Peninsula. The road is hilly the whole way to the frontier, and from time to time affords glimpses of the sea on the rt. After passing a number of country-houses, amongst which, at a little distance on the l., stands the *Château de Marrac* (p. 285), a finger-post at the end of 2 m. points the sandy way to *Biaritz* (*Inn*: H. de Monhau, rooms small, but clean and comfortable), a little secluded watering-place, 3 m. on the rt. and about 5 m. from Bayonne. It consists of a group of white-washed lodging-houses, cafés, inns, *traiteurs*, cottages, &c., and generally of a humble character, scattered over rolling eminences and hollows bare of trees, on the sea shore, here fenced with cliffs 40 or 50 feet high, excavated by the waves into numberless quiet coves and curious caverns. In these the sea at times roars and chafes, perforating the rock with holes, and undermining huge masses, which are detached from time to time; and some of them, left like islands at some distance from the shore, still project above the waves. From the tops of these cliffs, especially that which bears the ruins of an old fort or light-house, you look over the wide expanse of the Bay of Biscay, bounded on the rt. by the French coast, on which rises the new *Phare*, showing the way into the mouth of the Adour; and on the l., by the shore of Spain



beyond St. Sebastian, with peaks of distant Sierras rising behind it. The limpid purity of the sea and the smoothness of the sand render bathing in the sheltered bays most agreeable. French ladies and gentlemen “*en costume des bains*” consume hours in aquatic promenades. The ladies may be seen floating about like mermaids, being supported on bladders or corks, and overshadowed by broad-brimmed hats. The geologist will be interested to recognise in the rocks of Biaritz the fossils of the chalk or green sand, though the rock here assumes an external character very different from that we are accustomed to in England. Beyond its sea-bathing, its rocks, and its view, Biaritz must be the dullest place upon earth, except to those who have other resources of friends, &c. on the spot. Omnibuses and coucous are constantly plying between the baths and the Porte d’Espagne of Bayonne. The ancient mode of conveyance hither, which is peculiar to the spot, but is now becoming obsolete, was to ride “*en cacolet*.” In this mode of conveyance the rider, seated on one side of a hack, in a wooden frame fitting to a horse’s back, as a pair of spectacles does to a human nose, occupies the place of a pannier on one side of an ass’s back, while his conductor, usually a stout and buxom lass, fills the opposite division, and by her weight the balance is preserved. Some little skill is required in mounting, for unless both parties jump into their seats at the same moment, he who reaches it prematurely runs the risk of destroying the equipoise and of being capsized into the dust, and the same in dismounting. It is chiefly peasants and market women, now-a-days, who ride *en cacolet*; though under the ancien régime of the Bourbons, the frolicsome Duchesse de Berri, when on a visit to this part of France, was wont to resort to this primitive conveyance.

There are 3 lines of custom-houses

on the road from Bayonne to the Spanish frontier. The 3rd, or innermost, is not more than 5 m. from Bayonne. A large fresh-water pond within a funnel-shaped basin is passed shortly before reaching

11 Bidart. We now enter the *Pays Basques*, inhabited by that peculiar race who speak a language having no relation with any other in Europe. They occupy in France only a small part of the S. W. corner of the Dépt. des Basses Pyrénées, but are much more widely disseminated in Spain, where they form the mass of the population of 5 provinces. The French and Spanish Basques are distinguished by their speech, and also by their costume, consisting of the red beret, a cap resembling that of the lowland shepherd in Scotland, a red sash round the waist, and sandals made of hemp, called *Espartillas*, on the feet, and a stout stick in the hand. They are supposed to be the descendants of the “*Cantabrum indoctum ferre juga nostra*,” who sided with Hannibal in opposing the Romans, who contributed mainly to the defeat of Charlemagne and Roland in the pass of Roncesvaux, and whose boast is that they were never conquered. In France they are confined to portions of the arrondissements of Bayonne and Mauléon, which formed part of the ancient kingdom of Navarre.

9 St. Jean de Luz.—*Inns*: Poste; St. Etienne; good. A frontier town of France, at the mouth of the Nivelle, where it falls into a small creek or bay, over which a new bridge has been thrown. The inroads of the sea for some time past have washed away parts of the town, breaking through the dykes thrown up to protect it, and the shifting sands at the mouth of the Nivelle have almost entirely blocked up its port. The town is distinguished by its narrow street and white-washed houses, some of considerable antiquity. Here is the 2nd Douane. The suburb on the l. bank of the river is called Sibourre.

The marriage of Louis XIV. with Maria Theresa, Infanta of Spain, was celebrated here, 1660.

In Nov. 1813, the British army, under the Duke of Wellington, crossed the Nivelle close to this town, after attacking and carrying the very strong intrenched position occupied by the French army upon the heights on the l. bank of the river.

In the midst of barren, heathy, high ground stands

5 Urugne, last post station in France. The forms of the mountains are picturesque, especially of that called *Montagne d'Arrhune*, rising above Urugne, which is visible even on the other side of Bayonne. Before reaching this point, the traveller finds, contrary probably to what he could have expected from books, that the mountain chain of the Pyrenees by no means terminates in France, but stretches W., in lofty ridges and bare peaks tossed about in wild confusion, traversing Spain to its farther corner, and ending in Cape Ortegal in the Asturias.

Beyond Urugne, the antique Château of Urtubi is passed. Louis XI. came hither, 1462, to meet the King of Aragon, John II.

The French frontier *custom-house* is placed at Behobia, a small village (with a poor inn, Poste) on the rt. bank of the Bidassoa, which here separates France from Spain. The baggage of travellers entering France is strictly searched; and after it has undergone the process, they will do well to have it plombed, to save themselves from a repetition of the same twice between this and Bayonne. 10 sous is the charge for plombing each package.

The wild and lofty mountains around and behind Behobia, called *Montagne Verte* and *Mendele*, now so solitary, were strongly fortified by Marshal Soult in 1813, to defend the *Passage of the Bidassoa*, which the Duke of Wellington effected nevertheless, in the face and in spite of them. In the course of several

months preceding, intrenchment behind intrenchment had been thrown up by the French; every weak point had been strengthened, and the whole line of slopes and precipices, from the sea to the Arrhune mountain, bristled with ramparts and batteries, defending the fords of the river; the bridge of Behobia being then broken down.

From the middle of the existing wooden bridge, which unites France to Spain, the stranger looking up the stream will perceive the green knoll, or mamelon of St. Marcial; on this a strong battery was planted by the Allies, which covered the passage, by the ford higher up, of one division, consisting of Spaniards, under Gen. Freire, who won from the French the heights of Mendele. The most formidable part of the French position was the *Montagne d'Arrhune*, not only from its elevation, steepness, and tremendous precipices, but from the redoubts, intrenchments, abattis, &c. thrown up on it, wherever there appeared the least facility of approach, and from the strong body of troops, who held every commanding point, sweeping the slopes and ravines with their cannon and musketry. The Duke of Wellington employed nearly 20,000 men in the attack of this mountain, which was gained, as it were, inch by inch, the enemy being driven from one work after another up to the very summit, where they occupied a rocky height called the *Hermitage*. This was nearly impregnable, and they defended it for some time merely by rolling down stones upon their assailants. The bones of many a brave man are probably even now whitening among the dells and clefts of that rugged mountain: many who were wounded were left to perish where they fell, from the difficulty of discovering them among these vast solitudes.

A lower ridge, or projecting buttress of the *Montagne d'Arrhune*, is called *La Bayonnette*, from that fearful weapon of war, invented extem-



poraneously, it is said, on this spot, by a Basque regiment, who, having run short of ammunition, assaulted the Spaniards opposed to them by sticking the long knives which the Basques commonly carry, into the barrels of their muskets, and thus charging the enemy. This must have occurred some time in the 16th or early in the 17th century. The ridge of the Bayonnette was stormed and carried by the Allies 1813, before they gained the Arrhune.

Behind St. Marcial opens out the Valley of the Bastan, the cradle of the Bidassoa. Close below the bridge of Behobia is a little island, reduced by the washing of the current to a narrow strip of earth, tufted with grass and willows. This is the historically celebrated *Ile des Faisans* on which the conferences were held between the French Minister Mazarin and the Spanish Don Louis de Haro, which led to the famous treaty of the Pyrenees, 1659, and the marriage of Louis XIV. with the daughter of Philip IV. Each party advanced from its own territory, by a temporary bridge, to this little bit of neutral ground, which then reached nearly up to the bridge. The piles which supported the Cardinal's pavilion were visible not many years ago. The death of Velasquez, the painter, was caused by his exertions in superintending these constructions; duties more fitting to an upholsterer than an artist.

The Bidassoa forms the line of demarcation between the two kingdoms only for about 12 m.: it enters the sea about 5 m. below Behobia, between Andaye on the French side, and the ancient walled town of Fuentarabía (accent on the i) on the Spanish, after passing near the town of

9 Irun, first Spanish post station. (See HAND-BOOK FOR SPAIN.)

Between Irun and Fuentarabia are the 3 fords discovered by the Duke of Wellington, on the information of Spanish fishermen, by which he car-

ried one division of his army across, and, gaining the first permanent footing in the French territory, turned the rt. of the French position, and the strongly defended heights near Andaye (once famed for distilling brandy). These fords were practicable only at certain states of the tide, and for 3 or 4 hours, being covered by the sea, to a depth of 14 ft., at high water. Soult was therefore perfectly unprepared for an attempt to cross at this point, and his troops were deceived by the tents of the British camp being left standing as though still occupied. At the close of a fierce thunder-storm, early on the morning of Oct. 17, the allied army formed into 7 columns behind banks and ridges, issued forth at a given signal, and winding slowly, like snakes, across the broad sands, effected the passage.

## ROUTE 77.

### BORDEAUX TO BAYONNE, THROUGH LES GRANDES LANDES.

69 lieux de poste = about 173 Eng. m.

This was once the only road into Spain; but since the construction of the route through the Petites Landes (R. 76), and the removal of post horses from this line, it has been almost entirely abandoned, although it is 25 m. shorter than the other. In fact, it traverses a country scarcely practicable for carriages, owing to the want of proper materials for the roads; a small portion only, near Bordeaux and Muret, being paved. The accommodation for travellers is, of course, very scanty. Many of the old post-stations enumerated below, with the distances from one to another, are mere single houses or stables, established solely as relays, and perhaps now abandoned.

3 Gradignan. Beyond this village fields give place to heaths and pine-woods, interspersed with a few patches of barley and a little maize; for these crops will grow wherever manure

and industry can be employed upon the soil. The surface of the ground is of a dull grey or ash-coloured sand. A few flocks of lean, tattered, ill-conditioned sheep wander over this waste, tended by shepherds renowned for walking on stilts (*échasses*). By the aid of these they are not only enabled to stalk over the prickly bushes, and avoid the inconvenience of filling their shoes with sand, but they gain an elevation not afforded by the even surface of the ground, from which they can overlook their flock, and prevent their sheep straying. They carry a long pole, which, when stuck into the ground, forms a support, and against it they can rest, and knit stockings all the day through. A stranger, unprepared for the sight, would have some difficulty in explaining the nature of the extraordinary tripod thus formed; and the sheepskins worn by the peasant would not diminish the mystery. The peasants of the Landes are all accustomed to the use of stilts, and with a very slight exertion, and not a very quick movement, will clear the country at a pace which would keep a horse at a hard trot, by the aid of these wooden legs.

There is at least one thing which appears peculiarly at home among the Landes, which seems to rejoice in this dry sand, and to flourish in the most robust vigour—the *pine* (*Pinus maritima*). Nearly  $\frac{1}{4}$  of the *Dépt. des Landes* is covered with dark forests of this tree, and the distribution of it is greatly increasing, since, from the value of the timber and of the rosin which it produces, and the facility with which it is grown, large districts have been planted by order of the government. The Landes, it must be remembered, are not confined to the dept. so called, for we have hitherto been traversing that of the Gironde, and it is only between Bélin and the next station,

3 Muret, that the boundary line of the *Dépt. des Landes* is passed. Here the small river Leyre is crossed,

which falls into the sea at La Teste. Like all the streams of the district, its waters are brackish; and one of the chief evils to which the inhabitants are subject is the want of good water.

2 Bellevue.

2 Puch.

3 Barps.

2 Hospitalet.

2 Bélin, a small town.

3 Lipostey.

4 Bonhère. Here used to be the best inn on the line.

3 Belloc, a single cottage.

4 La Harie.

3 Esperon.

4 Castels.

The *Pignadas*, or pine-forests of the Landes, furnish a large quantity of rosin, which is obtained by grooving the trunk, or scarifying the bark 3 or 4 ft. above the root, and allowing the pitch to flow into a hollow below.

4 Majèse. An inn here formerly.

3 Les Monts.

2 St. Vincent. Here our road falls into the post-road from Bordeaux to

9 BAYONNE (R. 76, p. 281).

The wild district of the Landes stretches uninterruptedly from the Garonne at Bordeaux, to the Adour at Bayonne, and from the sea to Mont St. Marsan and Dax.

The inhabitants of the Landes occupy a low position, physically and morally, in the scale of civilisation.

*N.B.* Any more accurate and recent information than what is contained in the above route will be welcome to the Editor.

## ROUTE 78.

BAYONNE TO PAU BY ORTHEZ.

105 kilom. = 65 $\frac{1}{2}$  Eng. miles.

*Malleposte* to Pau and Toulouse daily. *Diligences* daily by Orthez and by Oloron.

The road turns to the rt., out of that to Bordeaux (R. 76), on the top of the hill above St. Esprit, the suburb of Bayonne. It runs in a direction nearly parallel with the Pyrenees, through a country abounding



in heath, having the Adour at some distance on the rt., until a few miles beyond

17 Biaudos, that river is crossed: the descent upon it is fine. The Gave de Pau falls into the Adour a little below the bridge; henceforth we ascend the rt. bank of that stream all the way to Pau. Hereabouts the Gave divides the district called Chalosse from the Pays Basque (see p. 285).

20 Peyrehorade (*Inn*: H. de Voyageurs; second rate), a prettily situated town, on the Gave de Pau, just below its junction with the Gave d'Oloron, under a height crowned by a ruined *Castle*, mentioned by Froissart. About a mile out of the town, a turning on the rt. carries the new road to Pau by Oloron (unfinished 1841) across the Gave de Pau, by a new wire suspension bridge. It passes through Sorde, a walled town, Sallies, so called from its strong brine spring, which furnishes the salt used in curing Bayonne hams, and Sauveterre.

The road from Peyrehorade to Orthez crosses, shortly before entering

16 Puyoo, a rivulet which anciently formed the boundary line between the kingdoms of France and Navarre.

The fertility of the plain, the abundant watercourses, the luxuriant festoons of the vines, and the magnificent views of the Pyrenean range, give great interest to this portion of the route. At Berenz, Sir Willoughby Cotton's division of cavalry, and Picton's 3rd brigade, crossed the Gave before the *Battle of Orthez*. That *victory* was achieved, Feb. 27, 1814, by driving the French from a very strong position on the heights above Orthez, extending from the town to the high road to Dax and the village of Boés. The retreat of the enemy ended in a flight, and they were pursued by the British, the same night, as far as Sault de Navailles. A wound received by the Duke of Wellington in the critical moment of pursuit contributed to save the French from

*France.*

greater loss. They attribute their defeat to a superiority of force on the side of the Allies, but the impartial estimate of Col. Napier sets down the numbers of Soult's army at 40,000 (including 4000 or 5000 raw conscripts), and that of the Duke at 37,000. The British cavalry outnumbered that of the enemy by 1000. The French lost nearly 4000 men killed, wounded, and prisoners; the Allies, 2300.

12 Orthez (*Inns*: H. Jennes;—H. Bergerot) is a somewhat dull town of 7857 inhab., though situated at the junction of 6 roads,—to Spain, by St. Jean Pied de Port, to Dax, to Bordeaux, to Oloron, to Pau, and to Bayonne. It has an old Gothic *bridge*, which resisted the attempts of the French to mine it and blow it up, consisting of 4 arches, surmounted in the centre by a tower from which, according to tradition, the Calvinist soldiers of the army of the Comte de Montgomery, after taking the town by assault, 1569, and putting to the sword most of its defenders, precipitated into the river the Roman Catholic priests who were found with arms in their hands, and who refused to abjure their religion. Jeanne d'Albret, Queen of Navarre, mother of Henri IV., established here a Protestant College.

Orthez was once a place of greater importance, as residence of the Princes of Béarn down to the end of the 15th century, when they removed to Pau. The *Castle de Moncada*, built by Gaston de Foix, IV., 1240, after the pattern of a Spanish castle of that name, is reduced to a few ruined walls, overtopped by one stately tower, left to attest its former splendour, on a height above the town. It is mentioned by Froissart, who paid a visit to Gaston Phœbus Comte de Foix, 1388, and was received into the household, in order to obtain, from the Count's own mouth, information for his history respecting the wars in Gascony and Spain. He describes the death of Gaston de

Foix, at the neighbouring village of Riou, on his return from hunting the bear, and the celebration of his funeral in the Church of the Cordeliers at Orthez, where he was buried in front of the grand altar. The Castle of Orthez was the scene of unparalleled crimes during the life of the brutal Gaston Phœbus, who filled its dungeons with the victims of his unbridled passion; among them his own kinsman, the Viscomte de Châteaubon, Pierre Arnaut, the faithful governor of Lourdes, who, because he refused to betray his trust, and surrender the fortress, was stabbed by Gaston's own hand, and thrust into a dungeon to perish; and, finally, his own son and only child, whom he killed with his knife, in the dark cell into which he had caused him to be thrust. The churches of *La Trinité* (1107) and of *St. Pierre* deserve notice.

The very picturesque peak called Pic du Midi d'Ossau is visible near this.

20 *Artix*. About 4 m. before entering Pau, the road passes, at a short distance on the l., the curious old and decayed town *Lescar*, supposed by some to be the ancient *Beneharnum*, whence the district of which it was originally the capital was called Béarn. The town was sacked and ruined during the wars of Religion, 1569, by the troops of the Comte de Montgomery. On a detached eminence, rising above the town, stand the Castle and the *Ch. of Notre Dame*, a decayed edifice, 10th centy., partly in the Romanesque style, containing carved oak stalls in the choir, and a curious mosaic pavement under the flooring. The early princes of Béarn, including Henri d'Albret, grandfather of Henri IV., and his wife, the Marguerite des Marguerites, were buried in it; but their tombs were destroyed either by the Huguenots or the Revolutionists. There is a fine view of the mountains from the cathedral terrace.

The *Jesuits' College*, founded here

by Henri IV. after his conversion, has been turned into a manufactory.

Still nearer to Pau, on the l. of the road, is Bilhère, where Henri was nursed by a peasant, whose humble dwelling is still preserved and pointed out with some pride to strangers. The eminence rising on the opposite bank of the Gave, its slopes covered with verdure and vineyards, is the *Côte de Jurançon*, which produces the best of all the Pyrenean wines.

The road, before entering Pau, skirts the woody ridge which forms its beautiful Parc; and which, intervening between the river and the road, conceals the view of the mountains.

20 PAU (R. 80).

#### ROUTE 79.

BORDEAUX TO AUCH, BY CASTEL JALOUX AND NÉRAC.

186 kilom. = 115 Eng. m.

The road is the same as R. 76 as far as

61 Bazas.

14 Grignols.

15 Castel Jaloux, a town of nearly 2000 inhab., owing its name and origin to a *Castle* built by the Seigneurs d'Albret, on the l. bank of the Avance, now in ruins.

At Barbaste corks are made. Henri IV. had a flour-mill here, whence he was sometimes called "le Meunier de Barbaste;" it still exists.

17 Pompiey. The road passes a little to the S. of the castle of Xaintrailles, the birth-place of Pothon de Xaintrailles, a knight celebrated in the wars against the English in the reign of Charles VII., who took the valiant Talbot prisoner at the battle of Patay.

13 Nérac (*Inn*: Tertres; famous for its *pâtés*, or *terrines* de perdrix), a town of 6327 inhab., pleasingly situated on the Baïse, once capital of the duchy d'Albret. It was an ancient possession of the family d'Albret, who built and resided in the venerable *Castle*, which remained nearly entire down to the Revolution,



but is now demolished, excepting one wing, and its fosses turned into gardens. Yet even this fragment is interesting, because within its walls Marguerite d'Angoulême, queen of Navarre, held her court, assembling around her the men most distinguished by learning and literary genius of the time; among others, Calvin, Beza, Clement Marot, here found an asylum from persecution down to 1534. At a later period, the "Bon Roi Henri," whose mother resided in the castle to within four months of his birth, passed here a portion of his youth. His chamber is pointed out at the W. end of the building. Here, in 1579, Catherine de Medicis held a conference. The tomb of Pothon de Xantrailles was destroyed along with the church of Cordeliers, at the instigation of the Calvinists.

The promenade called *La Garenne* was once the park of the kings of Navarre, planted by Marguerite de Valois. A bronze statue of Henri IV. has been erected to his memory by a private individual, inscribed "Alumno, mox Patri Nostro Ho. IV."

The *Fontaine de St. Jean* is overshadowed by 2 elms, planted by Henri IV. and Marguerite de Valois.

Corks are manufactured here for the wine-merchants of Bordeaux.

We enter the Dépt. de Gers before reaching

22 Condom (*Inns*: Cheval Blanc; Lion d'Or), a town of 7144 inhab., and of considerable trade. It has a handsome Gothic church.

19 Castéra Verduzan.

Near this village are mineral springs, one sulphureous, the other chalybeate, which are received into a *Bath-house*.

24 Auch, in R. 90.

## ROUTE 80.

BORDEAUX TO PAU.

195 kilom. = 120 Eng. m.

*Diligences* daily in summer.

Roquefort is a tolerable sleeping

place; so is Mont de Marsan (p. 280), but it is 12 m. out of the way.

The Bayonne road (R. 76) is followed as far as

108 Roquefort (*Inn*: ———), and by the diligence as far as Mont de Marsan (22 kilom.).

The mountains of the Pyrenean chain are visible even to the N. of this, rising ridge over ridge abruptly, from the low plain of Gascony, so as to give the greatest effect to their elevation, with a grandeur worthy of the barrier wall between two great kingdoms.

No villages of consequence, and few habitations, occur on the sandy tract between Roquefort and

16 Villeneuve de Marsan, on the Medou.

The district of sandy and heath-clad common, stretching from the sea coast through the Landes (Route 77) eastward, gives place to cultivated and enclosed ground near

22 Aire (Poste, a mere auberge), a poor, old town, of 4028 inhab., on the l. bank of the Adour, near which a detachment of the French army, retreating from Orthez, were defeated, a few days after that battle, by Lord Hill, who also gained possession of the French magazines here, and at St. Sever, lower down the Adour.

A steep ascent leads out of the valley of the Adour, and a table-land separates it from

17 Garlin.

12 Auriac,

From the top of each eminence, as you surmount it, a splendid view of the Pyrenees expands before the eye.

21 PAU.—(*Inns*: H. de France, at the corner of the Place Royale; good, and excellent cuisine; table-d'hôte, 3 fr.;—H. de l'Europe, Rue de la Préfecture, lately improved;—La Poste, Place de Henri IV.; beds, 3 fr. to 1 fr. 50 c.; café au lait and eggs, 2 fr.; table-d'hôte, 3 fr.—H. de Daurade, ditto.) Good lodgings may be had at the Bains de la Place

Royale. Try here the white wine of Jurançon, which, when good, deserves commendation.

Pau, ancient capital of the little kingdom of French Navarre and Béarn, now chef-lieu of the Dépt. des Basses Pyrénées, stands on a lofty ridge, forming the rt. bank of the river, or Gave de Pau, and has nearly 13,000 inhab. Its situation is perhaps scarcely surpassed by that of any town in France, if we consider the magnificent view over the chain of the W. Pyrenees, which expands in front of it. The English have shown their good taste in having chosen it for their residence, especially in winter. *The View*, reminding one somewhat of that from the platform at Berne, though far inferior to it, is well seen either from the Castle and its terrace, or from the extremity of the oblong, formal, gravelly promenade near the centre of the town, called the Place Royale, or from the *Parc*. This *Parc* is a fine natural terrace, running along the rt. bank of the Gave, thickly covered, on its top and sides, with noble trees, affording a grateful shade in the heat of the day, and provided with seats wherever, through gaps in the foliage, the different parts of the view appear to advantage. This spot formed part of the domain anciently attached to the old castle, and a communication between the castle and the *Parc*, through a formal square planted with rows of trees, called *Plante*, has been established by a handsome bridge of two arches, thrown over the high road.

The range of the Pyrenees, as seen from Pau, presents a strikingly beautiful and varied outline of peaks, cones, and ridges, often cut like a saw, rising against the S. horizon. Among the mass of summits, and precipices, and bold forms, are two pre-eminent from their elevation and shape—the Pic du Midi de Pau to the W., a peak with sides nearly vertical and cloven crest, rising at

the extremity of the beautiful Val d'Ossau; and to the E., the Pic du Midi de Bigorre. These members of the great central range are disclosed to view through the gaps of a subordinate chain of round-backed and wooded hills forming the middle distance; while in the foreground appear the venerable Castle of Pau, the torrent, or Gave, its banks beautifully fringed with trees, the picturesque bridge, and the ruins of another bridge destroyed by its inundations. Within the scope of this view appear Jurançon, a village famed for its wines, and Bilhère, where Henri IV. was nursed. It is a glorious prospect, to be dwelt upon and seen over and over again.

Pau owes its chief renown to its having been the birth-place of the “Bon Roi” Henri IV., who drew his first breath (Dec. 13, 1553) in its ancient, time-honoured, historic *Castle*, the most conspicuous and interesting building in the town. It stands statelily upon the ridge above mentioned, overlooking the river and bridge, at the point of a sort of promontory formed by a small rivulet which cuts its way through the town, and behind the castle walls at the bottom of a deep ravine, to throw itself into the Gave, just below it. The five towers of the Castle, and the outer wall which unites them, and serves to support the upper stories, are the oldest part, and supposed to date from the time of Gaston Phœbus, Comte de Foix, who founded the castle about 1363. The tallest tower, or *Donjon*, named after Gaston, rising at the E. end to a height of 115 ft., is of brick, furnished with loopholes. The windows have been stopped up in modern times. A copy of the contract for erecting it (dated 1375) still exists, and in it the Count himself engages to furnish the bricks from the Tuileries de Pau. In the gutted and half-ruined *Tour de la Monnoye*, rising on the side of the castle next



the river, from the bottom of the eminence on which it stands, to a level with the terrace, Margaret de Valois, it is said, gave an asylum to Calvin and other persecuted Reformers, and took great delight in listening to their discourse, although she never actually abandoned the Roman Catholic faith. This tradition, however, requires confirmation. The tower was used as a gaol until the Restoration (1814). The little oblong court-yard of the castle is destitute of architectural beauty; but the *Tour de Montauzet*, on one side of it, contained, according to popular belief, the oubliettes. It is about 80 ft. high, and its walls, to a height of 40 ft., were originally destitute of any opening, the gate at the bottom having been broken through in 1793, when the castle was sacked and despoiled by the Revolutionists. It stands within, and detached from, the outer wall of the castle, from which a small drawbridge, thrown over the gap, gave access to it through a little door. Within the thickness of its walls 7 or 8 confined dungeons exist, lighted by very small apertures, barred. The upper story only is provided with a window, looking into the court, and with a fireplace. Its wall, on the side of the court, is spotted with the marks of the shot fired by the Biscayans when they assaulted the castle during the troubles or civil wars in Béarn (1569), in the absence of Jeanne de Navarre.

Opposite the tower of Montauzet is the grand staircase, the vaulting of which, divided into squares, contains rich carvings, among which may be observed the letters H. M., the initials of Henri II. of Navarre and Margaret, the grand-parents of Henri IV., by whom it was built. The entire restoration of the interior, now in progress, has been undertaken by Louis-Philippe, and has been executed as yet with very good taste and splendour. The King has revived, as far as possible, the ancient decorations, injured by the Revolutionists,

who first stripped and ruined this ancient palace, and then degraded it to a barrack, and he has replaced those which they destroyed by others as far as possible in accordance with the age and style of the edifice. The walls of the chief apartments have been covered with tapestry, and the rooms filled with ancient furniture of the period, collected at vast expense.

In an apartment on the first floor is preserved a very interesting relic—the *cradle* in which Henri IV. was rocked, consisting of a large tortoise-shell, inverted and suspended by cords, like the scale of a balance. It is at present surmounted by a trophy of flags, embroidered by the Duchesse d'Angoulême, the staves of which serve to support it. When the castle was sacked in 1793 by the Republicans, bent on destroying all traces of royalty, they would certainly not have spared this; but, luckily, another tortoise-shell was substituted in its place, which was broken, and burnt with every insult. The parties who preserved the original shell were M. d'Espalunge d'Arros, commandant of the castle, who devised the pious fraud; M. Beauregard, the possessor of a collection of natural history, who exchanged a tortoise-shell of the same size for the cradle, which he afterwards concealed for many years in the roof of his house; and M. Lamaignère, concierge of the castle, who, at great risk, conveyed away the true cradle, and substituted the false in its place. A contemporary statue of Henri IV., preserved here, represents him leaning on his truncheon, after the battle of Ivry; it has little merit as a work of art. In front of the state apartments projects a balcony, commanding a view of the chain of the Pyrenees unsurpassed for its beauty. In the second story of the castle, in the room adjoining the *Tour de Mazères*, in the S.W. corner, Henri IV. was born. Here his venerable grandfather, Henri d'Albret, taking in his arms the newborn infant, after his lips had been

rubbed with garlic, according to the custom of Béarn, poured down his throat some drops of Jurançon wine, the best which the country affords, to give him a strong constitution! On the day of Henri's death, in 1610, there is a tradition that the castle was struck by lightning, which broke in pieces the royal escutcheon! Jeanne d'Albret was also born in the castle, 1528. It was alternately the prison of Reformers and Romanists during the religious wars and troubles of Béarn; and was the refuge of Theodore Beza and other Protestant teachers whom Jeanne de Navarre protected from persecution.

Among the costly and curious articles of old-fashioned furniture collected by the king to decorate the castle, and restore it to its ancient splendour, may be mentioned the bed in the chambre-à-coucher du Roi, said to be that of Henri IV.; it is curiously carved with medallion heads of the kings of France: in an adjoining room is the bed of Jeanne d'Albret, and a state chair, richly carved, bearing her arms, purchased in England by Marshal Solt, and presented to Louis-Philippe. The chapel has been newly fitted up, and has a painted window of Sèvres glass. The apartment leading to it contains some magnificent presents made by the late king of Sweden to the town of Pau, his birth-place. They consist of vases of porphyry of large size, superb tables of various kinds of porphyry, conglomerate, &c., and a chimney-piece of serpentine, all the produce of Sweden, and of great value and beauty.

Bernadotte, king of Sweden, son of a poor saddler in Pau, was born in a house Rue de Tran, No. 6. He quitted his native town, 1780, as a drummer boy in the Régiment Royal de la Marine. Some of his relations still remain in very humble situations in the neighbourhood.

It is a somewhat remarkable coincidence, that of the two most eminent men and sovereigns who first

drew breath at Pau, the one abandoned the Protestant faith, the other the Roman Catholic, in order to secure a throne.

The low ugly church of *St. Martin* is only remarkable because in it Jeanne d'Albret, the most sagacious and accomplished princess of her age, after our Elizabeth, first received the communion according to the form of the Reformed church on Easter day, 1560. Viret, the Reformer, preached from its pulpit.

A *Statue of Henri IV.* has been set up in the Place Royale; the bas-reliefs on the pedestal represent events of his life.

The *College*, at the E. end of the town, was originally a convent of Barnabites, founded by Henri IV., after he had abandoned the faith of his mother, in order to conciliate the Roman Catholics.

In the *Mairie* there is a collection of marbles of the Pyrenees, and a picture, by *Deveria*, of the birth of Henri IV.

The *Poste aux Lettres* adjoins the *Préfecture*, where is deposited a very curious collection of old records, deeds, &c., relating to the ancient state and history of Béarn, including the Fors (fueros, privileges) of Béarn; autographs of its most illustrious Béarnois sovereigns, and a list of the contributions collected in Béarn towards the ransom of Francis I. from captivity.

There are *Hot Baths* (for 75 c.) at the extremity of the Place Royale adjoining the Basse Plante.

There is a *Musée* devoted chiefly to the natural history of the Pyrenees, above the new *Halle*, where the markets are held.

The town of Pau in itself is not very handsome or remarkable. Its chief street is the Rue de la Préfecture, which on market days presents a bustling scene; here are the chief shops, such as they are.

Many English, as before observed, make Pau their residence, chiefly for the winter months, when its mild and



dry climate, and the stillness of atmosphere peculiar to it, are a great recommendation. — See Sir James Clark's excellent work on Climate.

Pau has been greatly resorted to of late by the wealthy Parisians also; good houses are consequently difficult to procure, and though provisions are cheap, house rent is enormously high; a moderately good suite of apartments costs more than a similar set at Paris. A number of new houses, however, have lately been built.

A *Protestant Church* has been built in the Rue des Cordeliers, mainly by the handsome contributions of the Duchess of Gordon. It is unfortunate that it should be so very ugly a building. The English church service is performed in it every Sunday by a resident clergyman, at 11 a.m.

A good *Circulating Library* of English and French books is kept by *Markham*, a respectable English bookseller, 18, Rue de la Mairie, where some very well executed views of the Pyrenees may be purchased.

*Conveyances*.—*Malleposte* to Toulouse and Bayonne. Diligences *daily*: to Bordeaux, in 22 hours; to Bayonne, 9 hours; to Barèges, Luz, and Cauterets, 12 hours; to Bagnères de Bigorre, 36 m.; to Toulouse, to Oloron in 3 hours; to Eaux-Bonnes in 6 hours.

*Commerce*.—From the swine, reared near this and at Orthez, are derived the so-called *Jambons de Bayonne*; they are said to owe their excellent flavour to the abundance of acorns in the woods where the swine are herded, and to the salt of Salies with which they are cured. There is a considerable manufacture of chequered handkerchiefs here.

Baggage may be transmitted from this to Toulouse, or *vice versâ*, by the house of Turettes et Comp., commissionnaires, or at a somewhat higher cost by the diligence.

Pau, situated at the termination of the plain, and at the roots of the *Pyrenees*, is excellent head-quarters for travellers intending to explore

those mountains and the valleys which penetrate into their recesses. Of these, no one surpasses in beauty of scenery the *Val d'Ossau*, which opens out to the S., immediately in front of Pau, and terminates in the magnificent Pic du Midi de Pau.

The excursions to Eaux-Chaudes and Eaux-Bonnes, about 26 m. distant, situated at the head of the valley of Ossau, near the base of the Pic, are described in Route 83; that to the Val d'Aspe in Route 82.

The *Ch. of Ste. Foi* at Morlaas, 6 m. N.E., in the Romanesque style of the 11th cent., is interesting, but much dilapidated. It has a splendid portal with much carving, and a rich chapel containing an altar-piece of the 16th cent. Morlaas was capital of Béarn down to the 13th cent.; it is now a village of hovels.

Lescar, the antiquated town, 4 m., and Bilhère, 1 m., where Henri IV. was nursed, are mentioned in Rte. 78.

Cauterets is about 45 m., and Bagnères de Bigorre 36 m., from Pau. (Route 85.)

## ROUTE 82.

PAU TO CAMPFRANC IN SPAIN, BY  
OLORON AND THE VAL D'ASPE.

113 kilom.=70 Eng. m.

A post road as far as Urdos.

*Diligences* daily to Oloron in 3 hours. The road has been greatly improved on the side of France, with the design of making it a highway to Madrid.

The road as far as Gan is the same as R. 83; beyond that place it crosses the hills to

17 Maison la Coste Belair.

16 Oloron. — (*Inns*: H. Condesse, good; dinner 3 fr.; — Poste; — H. des Voyageurs, chez Lustalot.) This is a large and prosperous manufacturing town of 6,500 inhab., on the Gave d'Oloron, a river formed by the junction at this spot of the Gaves d'Ossau and d'Aspe. The oldest part of the town occupies the summit of the hill, and includes the *Ch. of Ste. Croix*.

A lofty stone bridge thrown across the stream unites Oloron with the suburb St. Marie, containing 3400 inhab. Its *Ch. of St. Marie* shows the transition from Romanesque to Gothic: it has a fine Roman portal, and its sacristy contains some costly priests' vestments. At the side of the Gave is the new Séminaire.

The objects manufactured here are the chequered handkerchiefs so much in vogue as a head-dress among the peasantry of Aragon and Gascony, and also the berrets worn by the Béarnais. There is some trade in Spanish wool.

*Diligences* go in summer to Eaux-Chaudes and Bonnes (R. 83), and to Urdos.

The *Val d'Aspe*, at the mouth of which Oloron stands, contains scenery of great beauty, though it wants the boldness of many other valleys in the Pyrenees. A gradual ascent along a good road leads up it, following the course of the stream. At Asaspe the traveller has entered the Basque country, and is already in the heart of the mountains. The Gave is crossed at Escot, near which a Latin inscription, cut in the rock by the wayside, commemorates the first making of this road by the Romans, under one Valerius, and twice more before reaching

24 Bédous, last post town in France, 1,200 inhab.; it has a tolerable but dirty inn. Here the vale swells out into a basin shape. In the neighbouring village of Osse there is a Protestant community of 30 families, who have preserved their faith in the midst of Roman Catholics.

An *Obelisk* of marble has been reared near the village of Accous (Aspa Luca) to the memory of Desporins, the poet of the Pyrenees—their Burns, who was born here.

Grand defiles succeed to this basin; and in the midst the Pont d'Esquil, a bold antique arch, forms a fine object. Above Accous the new road has been blasted out of the rock. After passing the villages of Aigun and Et-

saut, we reach a grand rocky defile at the ruined fort Portalet, which once entirely barred the passage up and down the valley: it was destroyed by the Spaniards. Near this Buonaparte caused a road to be formed at vast expense, partly by excavating a shelf out of the face of the vertical precipice, partly by building up terraces of masonry for the conveyance of timber for ship-building from the neighbouring forests.

17 Urdos, a poor village of 300 inhab., at which the carriage-road ends.

11 Paillette (no post horses) is the last place in France. The journey into Spain as far as Jaca is a distance of 30 m., and must be performed on mules. On the way, 10 m. short of Jaca, lies

23 Campfranc, a village about equal in population to Urdos.

#### ROUTE 83.

PAU TO EAUX-BONNES AND EAUX-CHAUDS.—EXCURSION TO THE PIC DU MIDI D'OSSAU, AND THE SPANISH BATHS OF PANTICOSA.

42 kilom. = 26 Eng. m. to Les Eaux. Several *diligences* go daily from June to middle of Sept. in 6 hours, returning in about 4 hours; very slow.

A voiture may be hired at Pau for the journey at the rate of about 25 fr.

The road is very good, but up hill most of the way. For those who travel only in carriages it leads into a cul de sac; and to prosecute their journey to other parts of the Pyrenees they must retrace their steps nearly to Pau.

After crossing the bridge over the Gave du Pau, the village of Jurançon, distinguished by its groves of fine oaks, is passed on the rt.; it is famed for its wine, perhaps the best grown in the Pyrenees. The vineyards producing it extend along the slopes from this to Gan. One of the houses near the road was occupied for many years by the late Lord Elgin, when re-



leased from the dungeons of Lourdes by Napoleon; as prisoner on his parole. The well-wooded, verdant, shady valley, up which the road runs, is watered by the Nééz, or Neiss, a clear stream rushing over the limestone rocks, whose slaty foliations, crossing the direction of its current, resemble a flight of steps. In this country the vines are either trained over trellises upon cross bars of wood, or are allowed to climb up the trees; whence their long tendrils sweep down over the hedges: the box tree flourishes, and would attain great size were it not constantly cropped. At the village of Gan, on the l., also locally famous for its wines, is seen an old *castellated house*, in which Pierre Marca, the historian of Béarn and Archbishop of Paris, was born 1594. The front towards the court is said to possess some architectural interest. Here the road to Oloron (R. 82) turns to the rt. Above Rébénac rises its château on a hillock; and a little beyond, on the l., the copious source of the Neiss bursts out of the rock. A long and toilsome ascent leads up to the village of Sévignac, situated on the top of the ridge separating the Neiss and other streams flowing into the Gave de Pau from the tributaries of the Gave d'Oloron, flowing out of the Val d'Ossau, which we now enter. It here expands into the form of a basin, round which the Gave takes a wide turn, passing by the village of Arudy. In descending the wooded slope from Sévignac, several glimpses are afforded of the Pic du Midi d'Ossau, a grand object; but near the bottom of the hill, and as far as the Pont de Louvie, his cleft crest and precipitous cone appear in full majesty, filling up the vista at the extremity of the Val d'Ossau. This is a magnificent view on a clear day, and in advancing up the valley it is soon lost. Rocks and precipices of limestone now line the road, which is partly cut out of them. On their smooth surface, or in their narrow chinks, the box delights to fix itself.

They furnish the slabs of black and grey marble with which the door-posts and lintels of even the humblest cottage are here adorned. The Gave d'Ossau is crossed at the end of the village of

27 Louvie Juzon; and here also the road from Oloron (R. 82) to Les Eaux falls in, at the Hôtel des Pyrénées (indifferent accommodation), at the end of the bridge. The great transverse *Val d'Ossau*, which we are now about to ascend, and in which the Eaux are situated, is one of the most interesting among the Pyrenees, for its picturesque beauties, and for the people who inhabit it. They still retain much of their ancient customs and costumes. The women are distinguished by the scarlet *capulet*, a sort of monk's hood, serving at once for bonnet and shawl, descending as far as the shoulders. Whether sitting or walking, and even when carrying burthens on the head, the spindle and distaff are never out of their hands. They are inferior in stature and features to the men, which may perhaps be owing to the hard and unfeminine labours which devolve upon them; it is common to see them holding the plough, and carrying sacks of manure on their heads, or spreading it over the land. The men, however, are not idle; they are absent on the high mountain pastures tending their flocks and herds, or following the hardy trade of woodcutters and charcoal-burners a great part of the year.

The men are chiefly distinguished by the wide cloth cap or *berret*, properly and most commonly of brown colour, which, overhanging the brow and assuming very picturesque folds, sits very becomingly on a head of hair allowed to grow thick and of even length all round the neck, but cut short in front. They wear short jackets and knee-breeches, also brown, the colour of the undyed wool of the sheep, and round the waist a brilliant red sash of silk or woollen is tied. To defend them from rain or cold

they carry the white or brown *capa*, which resembles a sack, unseamed on one side, pulled over the head. An artist would find many good subjects among them, very picturesque countenances, such as are seen in pictures of Van Eyck and Albert Dürer.

The mountains around the valley abound in *Izards* (chamois), which are sometimes met with in troops of 40 or 50. The *chasse aux izards* is a common amusement of visitors at the baths, under the guidance of experienced huntsmen, of whom there is no lack. The haunts most frequented by the *izard*, in this district, are the *Pics d'Arcizet, de Gazie, and de Sesque*. *Bears*, though less common, are sometimes killed.

Flocks of sheep form the chief wealth of this valley; but as they are led up to the mountains in April, and do not return till the end of summer, they are seldom seen, except by those who traverse the high mountains. They are guarded by a remarkable breed of dogs of large size, very courageous, whose duty is less to drive the flock, as the shepherd's dog of England and Scotland, than to protect it from the wolf and bear.

The rustic fêtes, dances, &c. still kept up in some parts of the Val d'Ossau, especially at Laruns (Aug. 15), are well worth seeing, as they collect some of the finest specimens of the men of the valley, and of its primitive costumes. They have a peculiar musical instrument called *tambourin*, a lyre or zithern of 6 strings, struck with a stick by one hand, while the other holds the rustic mountain flageolet; it thus corresponds in simplicity and mode of playing to the old English tabour and pipe.

The part of the valley which we first enter is shut in by lofty mountains of bold forms and steep sides, separated by a plain of considerable breadth, through which winds the torrent, and it is scattered over with numerous villages. It is cultivated in patches to a considerable height, and covered below with large fields

of maize, or with meadows deriving their bright verdure from well-managed irrigation, and producing, by means of it, three crops of hay in a year.

Within a mile of Louvie you pass, on the opposite bank of the Gave, the ruins of *Castel Jaloux*, or *Geloz*, occupying the top of one of two little hillocks; the other, also anciently enclosed within its ramparts, is now crowned by a small chapel. This stronghold was the key of the Val d'Ossau, and residence of its viscounts in early times, while the valley formed a separate state, independent of Béarn.

In the *Ch.* of the village of Bielle, the finest in the valley in the pointed style, are 4 columns of marble, which, it is said, were so much admired by Henri IV., that he begged them of the inhabitants, but was met with this ingenious reply in the negative: "Nos cœurs et nos biens sont à vous, disposez en à votre volonté; quant aux colonnes, elles appartiennent à Dieu, entendez-vous en avec lui." The pillars themselves seem too poor to have excited the admiration of the king, but it was probably in the days of his boyhood, when wandering among his native mountains, that they struck his fancy.

A little before reaching the village of Laruns, one of the most considerable in the valley, a snow-white gash or scar, high up on the mountain side to the l., marks the situation of the *white marble quarry* of Louvie Soubiron, producing a stone well adapted for the sculptor's purpose. It has been employed at Paris for the statues in the Place de la Concorde, and for the bas-reliefs on the outside of the Madeleine. It is harder than that of Carrara, but is sometimes traversed by grey veins.

The situation of Laruns, encircled by high peaks and ridges, which impend on all sides above it, is very striking; among them the distant Pic de Gers raises his conspicuous head. The *Church* appears originally



to have had no windows much larger than loop-holes, though wide ones have been broken through in modern times: its font or bénitier, of the white marble mentioned above, is carved outside in the fashion of a basket, and within bears the inappropriate figures of mermaids.

On issuing out of Laruns you might suppose that you had arrived at the termination of the valley, so completely is it blocked up by the mass of the mountain *Hourat*; but after crossing the furious and injurious winter torrent, the Larienzé, and reaching the mountain foot, two roads are found to diverge; that on the l. to Eaux-Bonnes (p. 302), that on the rt. to Eaux-Chaudes, both places being equally distant (4 kilom. = 2½ Eng. m.) from this spot.

The old road to Les Eaux-Chaudes is carried up the mountain at an angle so steep as to render caution necessary in ascending and descending it with a carriage. At the top of this abrupt slope, the shoulder of the mountain, which, as it were, laps over, and conceals from the view of those below the upper part of the Val d'Ossau, has been cut down, and scooped out, by the aid of the auger and of gunpowder, into a notch, barely wide enough to allow 2 carriages to pass. After passing this gloomy recess, the portal of the valley, a sudden change of scene takes place. Before you opens out a lofty ravine or defile of mountains, almost precipitous, rising from 1,000 to 1,500 ft. above your head, and approaching so close to one another, at their base, as to leave no room for culture or meadow, only space for the torrent. Below the road, which now, resuming a gentle slope, continues for 8 m. as good and broad as an English post road, the torrent, here called Gave de Gabas, roars, chafes, and tumbles from rock to rock, boring the limestone, by its whirlpools, into cauldrons and pits. The deep fissure, at the bottom of which it takes its course, is well seen near the bridge, which transfers the

road from its l. to its rt. bank. From this point the river forces its way out into the lower Val d'Ossau, through a remarkable gorge walled in by precipices on either side, which long bade defiance to the passage of any road, and rendered necessary the steep ascent of the Hourat; it was quite inaccessible for man or beast.

The *new road*, completed 1847, and a very wonderful, singular, and laborious work, is carried to Eaux-Chaudes directly through this gorge into the valley, and thus avoids the steep and awkward ascent and descent of the Hourat. It has been blasted out of the rock at a great expense.

The approach to the Eaux-Chaudes is grand; the height and steepness of the mountains, now robed from top to bottom in box bushes, now starting out in lofty precipices of bare limestone, scarred by the course of torrents, which at times descend in long falls, like white ribbons from their brows, and the variety imparted to the road by the projecting shoulders, round which it winds, give much interest to this part of the journey. At length the last projection is doubled, and a view opens of the group of houses called

17 *Eaux-Chaudes.*—*Inns:* H. de France, on the l. of the road, new, best;—H. des Pyrénées is entered by the upper story; the rest of the building lies below the level of the road, and is traversed by long dark corridors; while in a vault below it are set up the booths of itinerant vendors of goods, as well as the *Baths*. Dinner at 5; table d'hôte 3 fr.; breakfast, or tea, 1 fr. 50 cents.; beds, 2 fr. There are 6 or 7 other lodging-houses, which form the bulk of the place. It lies wedged in, as it were, in the midst of the long trough of the valley, between lofty precipices, towering over head, and often draped with clouds. The houses are founded upon granite, which here first makes its appearance jutting up in a round boss behind the village. In its rise it has considerably elevated the lime-

stone above it, as may be perceived by the remarkable curve in the strata, visible on the face of the precipices on the l. bank, opposite the baths. The hot springs burst forth out of the granite, close to the junction of the limestone. This phenomenon of the outbreak of hot sources near the points of contact of granitic or trap-pean rocks is of frequent occurrence among the Alps and Pyrenees.

In spite of the name, Eaux-Chaudes, the temperature of the waters is not so high as at many other Pyrenean springs, the hottest not exceeding 95° Fahrenheit; and one of them is cold. The principal sources are Lou Rey (le Roi), named from Henri IV., a frequent visitor, 93°, and L'Esqurette, 95°, the most sought after, and most highly mineralised. The waters are sulphureous, and are supplied from 6 springs, 3 of which, used for bathing, are conveyed into the bath-houses; the others, used for drinking, partly burst out from the rock into rude little basins, whither invalids resort to fill their glasses, without the shelter of a pump-room, or the aid of a Hebe to fill it for them. A handsome *Etablissement des Bains*, however, including pump-room, promenade, and baths, chambers for the resident physician, and some sets of rooms for guests, has lately been constructed, at the expense of the Government, which gave 80,000 fr., and of the town of Laruns, which gave 30,000 fr., on the platform of rock below the hôtel. Into it the waters of 3 of the springs are conducted. This new building is furnished with 5 baths, besides douches, and contains *billiard-room*, *café*, and *reading-room*. The Eaux-Chaudes baths are resorted to, either by the real invalid in search of health, or the passing traveller attracted by the beauties of nature. The village, with its low houses, and its little narrow platforms intended for promenades, has a triste air.

There is, however, at least one very interesting excursion to be made

from this, viz. to Gabas and the *Pic du Midi d'Ossau*. Horses may be hired at 3 fr. to 4 fr. for the day; guides 4 fr. The valley of Ossau is a frequented passage between France and Spain, along which 15,000 mules pass annually. Its scenery, above Eaux-Chaudes, is far grander and more varied in its mountain outlines and vegetation than below; and the whole range of the Pyrenees presents few more interesting rides than that to Gabas (6 m.) The fine near view obtained, in proceeding thither, of the Pic du Midi, which is out of sight at Eaux-Chaudes, would alone well repay the trouble. About  $\frac{1}{2}$  m. beyond Eaux-Chaudes, the Gave is crossed by a bridge of wood, called Pont d'Enfer, above which, on the rt., a small cascade, named from the neighbouring but elevated hamlet of Goust, descends the mountain. In this portion of the valley the limestone has entirely given place to granite, which forms the substance of the mountains, and the vegetation which covers them is of a beauty and variety unrivalled. It is at this point that we pass into the zone of fir-trees, whose dark files, covering the mountain tops, descend half-way, mixing like mourners in the crowd of trees of lighter foliage; birch, beech, hazel, alder, and oaks, which rise from amidst an undergrowth of box, mixed with a wonderful profusion of wild flowers. At times the road mounts to a great height above the torrent; and there is a fearful pleasure in looking down, over the tree tops, upon its waters, writhing, struggling, and serpentine in the dark depths below. The firs in the forests around were formerly sent to Bayonne, to supply timber for the French navy, being hurled down the steep mountain sides, and floated down into the Gave d'Oloron.

Gabas is a poor hamlet, the last in France, having a small cabaret which will furnish a very tolerable dinner to a sharp appetite, and where Malaga wine may be had good. At



the extremity of the hamlet is the French *Douane*. Hence a fine view of the forked summit of the *Pic du Midi* is obtained. It is well worth while to take a walk (2 hours to and fro) beyond the *Douane*, crossing the bridge, and following the path to the rt. of the road and l. of the Gave. The pines here are magnificent. From *Gabas* also the *ascent of the Pic du Midi* is made, following the right-hand branch of the valley above *Gabas*. It takes 3 hours, passing the *Cabanes de Magne-Baigne*, to reach the *Crête de Pombie* at the base of the peak itself, which is of granite, very steep, and takes  $1\frac{3}{4}$  to 2 hours to surmount.

Should the traveller be disposed to take a peep at Spain, he may go from *Les Eaux-Chaudes* to *Panticosa*, an Arragonese watering place, a long day's journey of about 14 hours, including a rest of 2 hours. Start by 6 A.M. at the latest. The *charge* for a guide is 5 fr., and 5 fr. for each horse per diem (nourriture comprise): the guide finding himself in food and bed. Each lady ought to have a guide to attend to her horse on the Spanish side of the road.—*G. M. S.*

The route is quite easy, neither very steep in any part nor difficult to find, as there is a broadly-marked horse-track the whole way. The col is rather swampy in spring, after the melting of the snow.

The carriage-road up the valley terminates at

2 h. *Gabas*. A steep mule path turning to the rt. leads to the *Plateau of Bioux Artiques*, which commands so grand a view of the *Pic du Midi*, that Lady Chatterton says it is worth while to come all the way from England to enjoy it alone. It is only  $1\frac{1}{2}$  hour from *Gabas*. The mule-path turning to the l. from that place, on the E. side of the mountain, leads into Spain past the solitary house called

2 h. *Case de Broussette*, the last in France, which will furnish only very

homely fare, home-made cheese and the like, so that it is prudent to take provisions. It has been built by the Government as a sort of refuge or hospice halfway between *Gabas* and *Salients*.

1 h. The passage or col, called *Le Port d'Anéou*, is an hour's walk above this; a mule path of gradual descent leads from it, by the side of the stream of the *Gallego*.

2 h. *Salients*, the first Spanish village, is reached by a steep descent, a little beyond the Custom House. While the horses are resting here you may take a cup of excellent chocolate at the *Posada*, and visit the little church and its trésor. The village of *Panticosa* is  $2\frac{1}{2}$  hours' ride hence; and  $2\frac{1}{2}$  hours of difficult ascent by a winding path through a narrow and savage gorge, called *El Escular*, are required to reach the Baths. The baths consist of 4 or 5 large buildings, in a wild romantic situation, at a height of more than 8300 ft. above the sea level, in a confined hollow basin or valley, half of which is occupied by a lake surrounded by wild mountains of granite. The inn here is provided with a capital cuisine Française, and there is a daily table d'hôte during the season. Accommodation, i. e. a clean room, may be had at the house of Don José Juan Torla. The season lasts only for 3 months.

The Spanish *Valle de Broto* is one of the few remaining haunts of the ibex or *bouquetin*. The return to *Eaux-Chaudes* may be varied by going round the W. side of the *Pic du Midi d'Ossau*, traversing the *Plateau of Bioux Artiques* to *Gabas*.

From *Panticosa* village you may reach *Gavarnie*, or *Broto*, or *Torla*, in one long day, by climbing the Pass of *Bendeneta*. A guide is necessary, however. The scenery is very grand. See HANDBOOK FOR TRAVELLERS IN SPAIN.

From *Panticosa* to *Cauterets* is a journey of 8 hours on foot, and a little more with mules, over the Col

de Marcadaou, one of the most desolate passes in the range; traversed by a very rough mule track, but at times, when the snow is deep, it is impassable for mules. "For the greater part of the way there is no marked track. From Panticosa the ascent, for 2 hours of hard climbing, is up the face of a rock covered with débris. Another hour over swampy ground, bearing patches of melting snow, brings you to the foot of the col. The ascent from this to the frontier is as steep as a staircase, for about  $1\frac{1}{2}$  hour. The descent on the French side, passing some grand pines, equally steep,  $\frac{1}{2}$  hour. Another hour brings you to a hut at the foot of the col. Hence to the Pont d'Espagne another hour, and from the Pont to Cauterets  $\frac{1}{2}$  hour, though 2 hours are required to ascend."—*E. P.* (R. 85, p. 310.)

One of the first sights which travellers are invited to see at Eaux-Chaudes is the *Grotte*, situated in the rock on the l. side of the valley, 2 hours' walk above the baths.

The road to Eaux-Bonnes, branching off to the l. at the bifurcation beyond Laruns, crosses the Gave de Gabas by a bridge, whence there is a good view of the dark and narrow gorge through which that stream issues out of the upper valley (see p. 299). A steep ascent, carried up in a terrace along the mountain side, succeeds, and does not terminate till the road reaches Eaux-Bonnes. On the l., low down, lies the castle of Espalunge; and higher up, on the shoulder of a mountain, the village d'Aas looks down upon our road. The stream flowing at the bottom of the valley is a tributary of the Gave d'Ossau, called the Valentin. At the very entrance of Eaux-Bonnes a narrow, rocky gully, with a torrent at its bottom, is crossed by a wooden bridge. This stream is the contribution sent forth by the confined nook in which Eaux-Bonnes stands, partitioned off, as it were, from the vale of the Valentin by a ridge of rock of no great

height, and concealed from view until you are about to enter it. Beyond the bridge above alluded to is the fashionable and much-frequented watering-place

17 *Les Eaux-Bonnes*, consisting of a street of rather more than 20 hotels and lodging-houses, of large dimensions and many stories, which would not disgrace a German watering-place, and contrast with the homely low buildings of Eaux-Chaudes. One side, however, of the street is still incomplete, and is occupied by a miserable and filthy yard, planted with a few trees and hedges, nicknamed *Jardin Anglais*, a disgrace to the name and the place. The village is cradled in the lap of the mountains, niched in a complete cul de sac with precipices rising all around close to the houses, so that the rock has been blasted in order to make room for some of them.

Above these cliffs, to the S.E., towers the majestic *Pic de Gers*, the grand feature in all the views of this neighbourhood, while nearly due E. rises the serrated ridge of the Col de Torte.

*Inns:* H. de France et de l'Europe, chez Taverne Aîné (good, and civil landlord);—H. de Petit Paris, chez Cazères;—La Poste;—Quatre Nations;—H. des Etrangers. The *charges* are high, but vary according to the season and the throng of visitors. In the height of the season, in spite of the number of lodgings, rooms are frequently not to be had, unless ordered beforehand. The apartments are not well furnished. Meals are supplied even in the hotels by *traiteurs*, at the rate of 4 fr. per diem, including breakfast and dinner, at table d'hôte; or 5 fr. if sent into the visitor's private apartments; children 2 fr. 50 cents., and servants 3 fr. The season opens in June, and lasts till October, being at its height in July and August. Taverne Aîné keeps a *circulating Library*.

There are 4 or 5 *springs* here of warm sulphurous water, stronger than



those of Eaux-Chaudes, but of lower temperature, the hottest not exceeding 91° Fahrenheit. The principal ones rise at the foot of the craig called Butte du Trésor, and are conducted into the *Bath-house* at the extremity of the village. The water of one source is subjected to artificial heating to fit it for baths. The cold spring alone is used for drinking. Caution is necessary in using the waters: bad consequences have arisen from a stranger taking even a glassful to taste. It is usual to begin with a table spoonful and a half. Dr. Daüralde, the resident physician, has a high reputation for his treatment of consumption and spine complaints. The waters are considered good for complaints of the lungs and chest, and very efficacious in the early stages of consumption. Their reputation is of long standing, for the Béarnais soldiers of Henri d'Albret, wounded in the battle of Pavia, repaired hither for the cure of their injuries, and first gave the water the name of Eau d'Arquebusade.

The *walks* around Eaux-Bonnes cannot be too much praised: they have chiefly been made by M. Eynard of Geneva; except the *Promenade Horizontal* (so called to distinguish it from the others, chiefly steep ascents), this being admirably conducted on a level, and therefore suited for invalids. It commands noble views of the Valleys d'Aas and d'Ossau: it is already completed for 3 m., and it is to be carried on to les Eaux-Chaudes.

The well-wooded cliffs around have been rendered accessible for invalids by zigzag paths and terraces. The summer-house on the top of the Butte du Trésor commands a view of Laruns and the Val d'Ossau. Other paths lead down to the pretty but trifling waterfalls of the Valentin. The finest fall is that named *Du Gros Hêtre*, from a beech-tree now cut down, about 3 m. distant. Another very delightful walk of 1½ hour, at first under the shade of the beech-trees, leads to the Promenade Jacque-

minot, so called from a general who caused it to be cut.

Salanave is a *guide* to be recommended, and has good horses.

Persons residing at Eaux-Bonnes should not omit to explore the Val de Gabas above Eaux-Chaudes, with its luxuriant forests and its noble Pic du Midi, the grandest mountain in this district (see p. 300). It is a drive of an hour, or a walk of 2, to Eaux-Chaudes by the road.

The mountain-path over the *Col de Torte* from Eaux-Bonnes to Argelez forms Route 84.

#### ROUTE 84.

##### THE COL DE TORTE.—EAUX-BONNES TO CAUTERETS OR LUZ.

It takes 11 or 12 hours walking to Argelez. Send round the baggage.

“On leaving Eaux-Bonnes, by the road near the source, you traverse part of the mountain called Le Trésor. Keep the upper path, and, leaving the first bridge and cascade on your l., you come to a second bridge; pass it, keeping the torrent on your rt. The road is as yet well marked by horses, &c., and sufficiently steep to make a person unaccustomed to mountain-paths feel not particularly comfortable. In 2 hours thence, on horseback, you can make the Col de Torte; and, although the path is not always very distinct, you may know the Col by a remarkable rock which elevates itself on the l., and is like the root of an eye tooth. The descent on both sides is remarkably steep, and would induce most persons to descend from their horses. Leaving the valley of Assun and the river Assun on your l., keep under the Pic de Gabisos till you come to some châlets. The next Col is then right before you—a green and heathy mount, on which I passed within shot of 4 vultures. The descent from Col de Torte and ascent of this Col took me 1¾ hour on foot, with knapsack on back, as I sent back my horses from Col de Torte. In descending this

Col, the route, which, in the valley between the two Cols, is not well marked, is soon found; and the view from Arruns of the Hermitage and mountains which fill up the end of the valley, *i. e.* d'Arrui and La Rivelle, is one of the finest in the Pyrenees in my opinion. The descent from Col to Arruns occupies a good hour of walking. From thence the road either to Argelez or Pierrefitte is good: to the former about  $1\frac{1}{4}$  hour—to the latter at least  $\frac{3}{4}$  more. At Argelez I should recommend the H. de la Paix, where, I understand from a friend, that he was tolerably comfortable. H. du Commerce is quite the contrary, although I got a tolerable bed. (R. 85, p. 306.)

“It would be making a toil of a pleasure to attempt to reach Cauterets in 1 day from Eaux-Bonnes, at least on foot; especially as the road from Argelez to Cauterets is so magnificent, so pleasing, and so varied, that it alone deserves a day.”

#### ROUTE 85.

THE PYRENEES. — PAU TO LOURDES, CAUTERETS, LUZ, ST. SAUVEUR.—GAVARNIE, BARÈGES, AND BAGNÈRES DE BIGORRE, MOUNTAIN-ROAD.—EXCURSIONS TO THE LAC DE GAUBE.—BRÈCHE DE ROLAND AND MONT PERDU.—THE PIC DU MIDI, &c. &c.

A daily communication of diligences is kept up in summer between all the principal watering-places of the Pyrenees.

*Distances from Pau*—to Cauterets, 68 kilom. = 42 Eng. m.; to Luz and St. Sauveur, 71 kilom. =  $43\frac{3}{4}$  Eng. m.; to Barèges, 76 kilom. =  $46\frac{3}{4}$  Eng. m.; to B. de Bigorre.

This route includes some of the most interesting objects and places in the Pyrenees; and the drive from Lourdes to Luz and Cauterets in particular is a continued succession of the most beautiful scenery.

The road ascends the rt. bank of the Gave de Pau, through a plain of considerable width, nearly covered

with maize, and passes between festooned vines slinging their tendrils between the apple and cherry trees. One village rapidly succeeds another, but they contribute little to the cheerfulness of the drive, as the houses turn their backs on the traveller, whose gaze is met by dead walls. He has, however, something more interesting to occupy his attention in the varying forms of the mountains which he is gradually approaching. But there is one exception in the village of *Coarase*, where the Gave is crossed by a bridge; for its old tower, crowning a mound on the rt. bank, is part of the castle in which the Bon Henri IV. was confined from his early years to the care of Susanne de Bourbon, Baronne de Missans, and by the wisdom of his mother brought up in the rough fashion of the peasants of his native country, dressed like them, fed like them, sharing in their sports, and traversing the rugged rocks with bare feet; thus acquiring the vigour of body and strength of mind which enabled him to surmount in after-life so many hardships, dangers, and difficulties. Beside the ruin a modern château has been built.

The feet of the mountains are fairly gained at

24 Lestelle. — *Inn*: Poste. The Gave, running in a contracted rocky bed, is here spanned by a bold arch most picturesquely draped with ivy. Just outside of this village, at a spot where the road is hemmed in between a fine wooded hill, spotted with chapels or stations, and the river, stands the *Pilgrimage Church of Bétharram*, an ugly modern building, containing a statue of the Virgin reported to have miraculous powers, which attracts a multitude of devotees from a distance in the month of September. Here also is a *Séminaire* for the education of priests.

Traversing a narrow defile again on the rt. bank of the Gave, which is hemmed in between barren bracken-covered hills, we pass into the Dépt. des Hautes Pyrénées, and



from ancient Béarn into Bigorre, shortly before entering the little manufacturing town of St. Pé. It is chiefly inhabited by nailors, who obtain iron from the forges of Asson, and by comb makers who supply the Spanish ladies with combs of box-wood for their hair. It has a curious Romanesque church with apsidal terminations, and sculpture over the door. Much roofing slate is exported hence.

16 Lourdes (*Inns*: La Poste and H. Lafitte) consists of a picturesque but somewhat gloomy-looking hill fort, seated on a rock, around which the town of narrow dirty streets and shabby houses group themselves. This *Castle* was once the key of the valley of Lavedan, or of the Gave de Pau, commanding the 4 roads which unite here from Tarbes, Bagnères, Argelez, and Pau. It is reached by flights of stairs, and entered by a small drawbridge, and a door 4 feet high and only wide enough for one person to squeeze through; but, not being strong according to modern rules of art, is rather of use as a barrack than a fortress. It was long a state prison, and in 1804 Lord Elgin was incarcerated within it by Napoleon, who caused him to be seized in his passage through France from Constantinople. Far different was its importance in ancient times; it was held for the English monarchs, and the Black Prince, as part of the country of Bigorre, which was yielded up to the English by the French king John as part of his ransom, in conformity with the treaty of Brétigny. Froissart gives a very long account of its varied fortunes, which render this feudal fortress interesting for all who are acquainted with its history. He tells us that when the Black Prince came over to take possession of Aquitaine, which his father had given him to hold in fief, he and his princess, while on a visit to the Comte d'Armagnac at Tarbes, rode over to Lourdes, which he had a great desire to see. He was much pleased, "as

well with the strength of the place as with its situation on the frontiers of several countries, for those of Lourdes can overrun the country of Arragon to a great extent, and as far as Barcelona in Catalonia." The Prince intrusted the command of it to a knight of Béarn, one of his household, in whom he had great confidence, Sir Peter Arnaut, to guard it well. When the war broke out with France, he held it fast, and, assisted by many bold adventurers, made repeated incursions through Bigorre and all Languedoc, sometimes to a distance of 30 leagues. "In their march out they touched nothing, but on their return all things were seized, and sometimes they brought with them so many prisoners and such quantities of cattle that they knew not how to dispose of or lodge them. They laid under contributions the whole country except the territory of the Comte of Foix, where they dared touch nothing without paying for it. Tarbes was kept in great fear, and was obliged to enter into a composition with them." In 1369, not very long after the visit of the Black Prince, Lourdes was actually attacked by the French army, commanded by the Duc d'Anjou, and at the end of 16 days the town, defended only by a palisade, and much injured by the machines which the duke brought to bear against it, was won; but the enemy made no impression on the citadel above, which bade defiance for six weeks longer to all efforts to take it. The governor remained true to his oath sworn to the Prince of Wales to guard his stronghold, and resisted the offer of a large sum from the Duc d'Anjou to deliver it up. Another attempt was made to induce this faithful châtelain to betray his trust, by Gaston Phœbus, who invited him to his castle of Orthez. Before setting out, however, Pierre Arnaut confided his stronghold to his brother Jean, who took the same oaths of fidelity. Gaston, irritated at the steadfast honesty of Arnaut in re-

fusing his proposal to yield up the castle, in a brutal fit of rage stabbed him in 5 places with his poignard, and thrust him into a dungeon, where he perished. The atrocious crime availed him not; for Jean, the brother of his victim, proved as trusty a governor and skilful a captain as the murdered Pierre.

There is nothing to be seen here, but the artist-traveller may probably get a sketch of the castle and its picturesque donjon. The sides of the valley are very bare and uninviting near this.

The direct post road from Pau to Bagnères branches off from Lourdes, whence it is distant 21 kilom. (R. 87.)

When Lourdes is left behind we are in the heart of the mountains, but the valley continues for some time stern, rocky, bare; showing marks in its gashed sides and rock-strewn bottom of the fury of the torrents.

Here and there a feudal hill fort rises upon its rocky perch, a relic of the days when nearly every valley of the Pyrenees was the scene of almost constant border warfare.

This unpromising vestibule, however, leads into what has not unjustly been called the Paradise of Argelez, where the valley of Lavedan (for so this part of the watercourse of the Gave de Pau above Lourdes is called) expands into a wide basin renowned for its picturesque beauty, fertility, and cultivation, and ranking among the finest in the Pyrenees. This altered scene opens out to view after passing the widely conspicuous dismantled tower of Vidalos, which, rising in the midst of the valley upon a monticule, conceals the village and what lies behind it.

Rich maize crops or verdant pastures occupy the bottom, interspersed with orchards alternately powdered with blossom or laden with fruit, walnut, fig-trees, and vines; but the tilled land extends far up the slopes, and the grand mountains around are clothed with forests of noble growth,

the whole scattered over with houses and villages, which add to the whole the charm of much cheerfulness. In the midst of this lies the village or small town of *Argelez*. (*Inns*: H. de la Paix, and du Commerce, are the best, but dirty.) It is dirty and insignificant in itself, and destitute of a good inn, but, from its sheltered situation, enjoys a climate where winter tarries so short a while that its presence is scarcely perceived; where the snow flake melts as soon as it falls, and spring begins when the valley above and below is buried in snow. In summer, however, it is intensely hot. It is precisely in the midst of these beauties of nature that man appears most miserable: the maladies of goître and crétinism are very prevalent about Argelez.

The *Val d'Azun*, opening out on the W. opposite Argelez, and extending up into the central chain between the mountains called Pic du Midi d'Azun and Pic de Gabisos, includes some very fine scenery, and is well worth exploring. A path leads up by Anzizans, a beautiful spot, to Arrens, the highest village (8 m.); but beyond it stands the pilgrimage chapel of N. D. de Pouey la Hun, a picturesque building on a pedestal of rock overlooking the valley. From Arrens a mountain path runs to Eaux-Bonnes (R. 84), crossing two ridges, the second being the Col de Torte.

Beyond Argelez the scanty remains of the ancient abbey of St. Savin, long ago sequestered, are passed high up on the hill to our right. The view from the convent garden is beautiful, and the church, said to be as old as Charlemagne, is *very* curious. The valley of Argelez terminates at

19 Pierrefitte.—No good *Inn*. This village, whose population seems to live by begging, much to the traveller's annoyance, is the centre from which the roads to Cauterets and to Barèges separate: it is seated at the foot of a lofty and conspicuous mountain, which seems to block up



the passage, and which, in fact, gives rise to 2 minor valleys. The road to Luz, Barèges, and St. Sauveur (p. 311) runs up that on the l., and the way to Cauterets is on the rt. of this mountain. The highest point of the ridge dividing the valley of Cauterets from that of Luz is named the Pic du Midi de Viscos: it is 7030 ft. above the sea level. The whole way to Cauterets lies through a narrow gorge, where the cheerful beauty of the lower valley gives place to savage grandeur. A good carriage road, which took 4 years to complete, is carried through it, rising immediately behind Pierrefitte, before it penetrates into the defile, in well-contrived zigzags, either elevated on terraces of masonry or cut out of the hard rock: it is a fine work of engineering, not inferior, as far as it extends, to some of the celebrated roads through and over the Alps. The ascent by the old road was both difficult and dangerous; 4 horses and 3 pair of oxen being attached to a carriage to drag it up. A portion of the old way remains, and serves as a short cut for the pedestrian, whence he may survey to advantage the mouth of the narrow gorge, in the depths of which the torrent struggles along. It is a rent burst through vertical strata of slate, yet, except where its sides are absolutely perpendicular, they are either carpeted with bright patches of green meadow or covered with trees and brushwood, among which the hazel thrives. At a short distance from the mouth of the gorge, the view, looking back upon the vale of Argelez, is peculiarly beautiful, from the contrast of rugged, gloomy wildness in the foreground, with the sunny richness beyond of groves, pastures, and corn-fields. Near the middle of the pass, which *longo intervallo* may recall to the Swiss traveller some features of the Via Mala, the road surmounts in a series of graceful curves a bed of limestone or marble, called *Butte du limaçon*,

which stretches across the valley like a dam. Over this the Gave tumbles in a long rapid, which frets its waters into foam as white as snow, and leaves little to be seen of its natural hues of beryl and chrysoprase. To this succeeds a slight opening in the valley, and a tall pointed mountain appears at its extremity, clad in fir: at its foot lies Cauterets; though intervening hills conceal it from view until you are close upon it.

9 *Cauterets.*—*Inns:* Lion d'Or, comfortable; H. du Parc; H. de France.

There are tables d'hôte twice a day at the chief inns, and families may be supplied with meals in their rooms by a *traiteur*. Cauterets, though in a spot so remote and elevated (3096 ft. above the sea), with savage mountains encircling it in an amphitheatre, and overhanging its roofs with their peaks and pine forests, has a perfectly townish air, with an octroi at its entrance, paved streets of inns and lodging-houses, and in the centre an irregular market-place. It is one of the chief Brunnen of the Pyrenes, containing nearly 1000 permanent inhabitants,—abounding in agents, guides, horse-jobbers, and itinerant marchands, who beset the traveller the moment he sets foot within it. The number of houses is about 200; most of them have the door-posts, window-sills, and thresholds of grey marble, and over every other door is emblazoned "*Chevaux ou voitures à louer.*" Invalids repairing to Cauterets to take the waters, must address themselves to the inspector (Dr. Buron), who will inscribe their names in a book, and allot to them an hour for taking the bath, to remain fixed during the whole of their stay, with a chaise à porteur to convey them if required.

The chief building is the pump-room or *Etablissement des Bains*, recently built near the foot of the hill, to receive the waters of the source called *les Espagnols*, one of the most powerful and hottest in the Pyrenees.

It is so named from its having at an early period, according to tradition, cured the ailments of a king of Aragon, or from being much frequented by Spaniards, who cross the mountains in great numbers, to repair hither. The new building is supplied with water in pipes carried down the slope of the hill de Per-raute, from the source, situated at a considerable elevation, where the old bath-house stands. The bathing apparatus and accessories are constructed on the most approved plan dictated by the experience of modern science. The older bath-houses in the same direction are little better than wretched sheds, approached by paths so steep and stony as to require much exertion on the part of the robust to surmount; yet up them the invalid was formerly compelled either to toil on foot or be carried in a chaise à porteur.

The *Mineral Springs* here are sulphurous and hot, varying only in the quantity of the same ingredients, and in warmth from 102° to 122° Fahr. There are about 16 distinct sources, six of which rise, on the hill of Per-raute, above the town to the E., and the remainder are situated higher up the valley, on the banks of the Marcadaou, from 1 to 1½ mile distant. They are said to present in their strength, warmth, and qualities an epitome of almost all the sulphurous sources scattered over the Pyrenees; some of them being even more powerful than those of Barèges, others as mild as St. Sauveur. The chief of the springs on the banks of the Marcadaou, and the one most resorted to, is the *Raillère*, whose waters are received in a building of some pretensions, faced with a portico, on a raised terrace, at the foot of a granitic mountain, destitute of trees or verdure, but covered over with fallen blocks of stone, which descend its slopes in dreary ruin. From 6 to 8 in the morning all the world of Cauterets repairs to this desolate spot, and during the dense season

bathers assemble here at a much earlier hour, even at 4 in the morning. The road is thronged with sour-faced invalids; open sedan-chairs upon poles, covered with a canvas hood, of which 50 or 60 are kept in the town, hurry to and fro, occupied by muffled females; peasant women in red capulets, mingle with Paris dandies in white berrets, and red Béarnais sashes (*la mode des Bains*), black ecclesiastics in broad-brimmed hats, Capuchin monks in brown sackcloth and hoods, and Spaniards of swarthy olive-coloured visage and stately gait, their heads swathed in mottled handkerchiefs, their persons muffled up in the embozo of their cloaks, which are often no better than horsecloths, offering a singular combination of dignity and poverty,—such are the component parts of this motley and picturesque crowd which repairs daily to La Raillère. There are 23 Cabinets des Bains at La Raillère, with 2 douches and a fountain for drinking.

Above the Raillère is a group of other springs and a cluster of little bath-houses, built one above another against the hill-sides: the principal are the *Bain du Pré*, beneath a stream of fallen rocks, grown over with lichens, Petit St. Sauveur, Mahourat, B. des Œufs, and des Yeux. The *Source de Montmorency* is a sort of grotto, whose waters, too hot for the hand to bear, deposit a white, greasy slime; and the *Bain du Bois*, the highest in this direction, contains 4 cabinet baths, with a douche in each, and beds for the invalid who may desire to encourage the perspiration produced by the bath, and 2 piscines or large baths: the charge for one is 20 sous.

July and August are the *season* when Cauterets is most visited: lodgings are then very dear; poorly furnished apartments sometimes costing as much as 4 or 5 fr. each per diem.

There is a subscription reading-room or club here, called *Cercle*.



Several formal avenues and alleys on the outskirts of the town, by the side of the road to Pierrefitte, and the Parc on the margin of the Gave, satisfy the wants of French visitors as promenades, but must appear wearisome to English; indeed, except in the society of friends, or with the inducement of illness to make one tarry, the attractions at Cauterets are few.

*The Grange de la Reine*, a humble farm, so called from Queen Hortense having once been belated in crossing the mountains, and having passed the night there, is a good point of view for the basin of Cauterets, about 600 ft. above it. The mountain called *Peak of Monné* commands a far more extensive and very striking view, but is a serious mountain to climb; 10 hours up and down.

The sportsman may be thankful to know, that the rivers abound in trout, and that the chase of the izard and the bear may be pursued on the neighbouring mountains between the Vignemale and the Pic du Midi d'Ossau, with some prospect of success, at the latter end of spring. These wild animals are, however, becoming rare even in these their last retreats. Jean Destapins is a capital guide and chasseur.

*Chaises à porteur* cost 15 fr. a day, and 3 fr. pourboire to the porteurs, who are very agile and sure-footed; ladies are often carried by them as far as the Lac de Gaube. Good *ponies* may be hired here (p. 245).

Nobody thinks of quitting Cauterets without making the customary excursion (one of the most interesting in the Pyrenees) to the *Pont d'Espagne* and *Lac de Gaube*. There is a bridle road all the way, well marked but steep at its farther extremity, and the excursion may be performed by men without a guide. It requires about 2 hours' good walking to reach the Pont d'Espagne, and 45 minutes more thence to the Lac de Gaube: the return may be effected in less time.

The road ascends the desolate valley of the Gave de Marcadaou, passing

the source de la Raillère, between the mountains Perraute and Peyrénère, whose sides, strewn with rocks fallen from above, and in headlong ruin hurled, effectually prevent the growth of trees or shrubs. [The Gave is crossed by a wooden bridge beyond the Raillère, close to the junction of a tributary Gave descending from the Val de Lutour, up which runs a path leading to the pretty Lac d'Estom,  $3\frac{1}{4}$  hours;  $2\frac{1}{2}$  to return by the Col d'Arayé, a steep boulder-paved footway—a “mauvais pas”—to be taken by those only who have a mind for a rough scramble.]

It is not until after a steep and toilsome ascent has left behind the Bains du Bois, that a change comes over the features of the valley, and dark forests of fir relieve the bared and wrinkled face of the granite precipices. The torrent leaps down from the upper to the lower slopes of the valley in several fine *falls*, the best of which is the cascade *de Cerizet*. The precipices rising on either side of the gorge are surmounted by serrated peaks and pointed *aiguilles* of granite, which assume most picturesque forms, while their base is clothed with fir forests.

About 6 m. from Cauterets is the *Pont d'Espagne*, in itself a mere simple structure of pine trunks thrown across the torrent, here confined in a narrow chasm between rocks, just below the juncture of the Gave descending from the Lac de Gaube with that from the Marcadaou. The streams unite by leaping together into the chasm under the bridge, in picturesque *Falls*, but of no great magnitude. They are best seen about 20 or 30 yards on the path leading into Spain. These are but accessories to the sublime scene around, which, from the predominance of black fir forests, surrounded by granite cliffs shooting upwards in spires and pinnacles, our friend and fellow-traveller (*T.*) assures us, reminded him somewhat of Norway.

The valley above the Pont d'Es-

pagne, called Val de Jarret, continues of great grandeur, and is traversed by a path on the l. bank of the stream by the Marcadaou pass to the baths of Panticosa in Spain. (See p. 301, R. 83.) The road is good as far as "some saw mills,  $\frac{3}{4}$  hour above the Pont. The road then becomes stony and steep, ill fitted for horses, and you go faster on foot. From the saw mills to the summit is about 1 hour's walk. From the top (4 hours from Cauterets) you descend in  $\frac{1}{2}$  hour to some small lakes, by a rather difficult path. Thence to Panticosa, 3 hours, a fatiguing descent, but not dangerous, down a staircase, as it were, of granite. At several points the grandeur and loneliness of the scene equal that of the finest Swiss passes."—*H. A.* The journey occupies 8 hours good from Cauterets. It is well worth while to ascend the Marcadaou Pass, even if you do not cross into Spain, as far as the frontier, as the view towards Spain is magnificent; far finer than that from the Brèche de Roland. It comprises 4 chains of snow-clad mountains.

To reach the *Lac de Gaube* you must turn to the l. close to the Pont d'Espagne, immediately below it, where a very steep path strikes up the mountain side through the pine wood, and at first by the side of a torrent. After about  $\frac{3}{4}$  hour's walk (2 m.) over trunks and roots and shattered stones, you reach this lonely basin of green water. It is not more than  $2\frac{1}{2}$  m. in circumference, yet is the largest lake among the Pyrenees, and lies at an elevation of 1788 mètres = 5866 ft. above the sea level, and is 300 or 400 (?) ft. deep. The steep precipices on either side are bare, except where seamed with lines of straggling black firs, alternating with streams of fallen rocks; but the entire centre of the picture is filled with the noble mass of the *Vignemale*, one of the highest mountains in France, white with eternal snow, crowned by crags and by glaciers which feed the lake through a small fall. The only

habitation is the fisherman's hut, which now serves as a restaurant (furnishing lake trout for the hungry traveller's breakfast at a high rate), planted upon a ridge of granite, stretching across the valley, and damming up the waters of the lake. On a projecting rock a little *monument of white marble*, railed in, is the record of the melancholy fate of a young Englishman, named Pattison, and his wife, who, within one month of their marriage, were drowned in the lake. They had trusted themselves to the frail skiff of the fisherman to row across the lake; and it is supposed to have been accidentally overset, for no human eye beheld the accident. Their bodies were conveyed to Witham in Essex. A detestable, lying romance, grafted on their sad story, destitute of all truth, is sold on the spot—let no one buy it.

The *ascent of the Vignemale* is sometimes made from the lake, which is either crossed in the boat, or skirted by the path on the l. The clue to the ascent is the Gave, which forms the waterfall at the extremity. Following its bank, you ascend in succession, in the course of  $1\frac{1}{2}$  hour's walk, 5 different stages or steps of the mountain, each of which the torrent clears by a leap. The mass of the mountain is alpine limestone, which here overlies the granite prevailing from la Raillère to the Lac de Gaube. The Gave has its origin in the foot of a glacier stretching nearly up to the top of the mountain. Its crest is topped by 3 peaks detached from one another; the lowest of the 3, called Petit Pic, is alone accessible. The highest is 11,001 ft. above the sea level, surpassing every other in the French Pyrenees. The view is said to extend into Spain and over a large part of the French chain. This excursion cannot be performed without the aid of approved and experienced guides.

There is a difficult mountain path among broken rocks and the débris of glaciers, from the Lac de Gaube



over the shoulder of the *Vignemale*, keeping that mountain on the rt., through the *Col or Port de Ossouë* and down the *Val d'Ossouë* to *Gavarnie* (see p. 314). It requires 8 or 10 hours, and should not be undertaken without good guides, being one of the most difficult expeditions in the Pyrenees.

The course usually taken by persons proceeding to *Bagnères*, *Barèges*, and *Gavarnie*, from *Cauterets*, is to retrace their steps down the valley as far as *Pierrefitte* (see p. 307), and thence ascend the gorge leading up to *Luz*, which is so interesting in its scenery, that no one should omit to explore it.

It is a truly magnificent defile, differing from that to *Cauterets*, being rather less gloomy, but scarcely superior. It abounds in rich foliage throughout. Near the 3rd bridge over the Gave a new road has been made with much engineering skill, running 200 or 300 ft. lower down than the old, which mounts a very steep ascent, only to descend immediately after. It is alternately a shelf cut with vast labour out of the rock, or a terrace built up with masonry; with an abyss under foot, and towering masses over head. The chasm through which the Gave flows is very striking: it is a rent so narrow that its sides seem to overlap each other, and never to have been completely parted. The green torrent chafing along, and worming its way through the depths between the rocks, is a beautiful object. Where the new road, in one even gradual ascent, meets the old, the gorge opens into a basin-shaped vale, remarkable for its rich carpet of verdure, cultivated in patches, having little villages planted a considerable way up its sides, until fields give place to forests. The mountains by their separation leave space for a small plain nearly in the form of a triangle, entered by a narrow defile at each of its angles. On the S. W. opens that of *Gavarnie*, at the mouth of which lies *St. Sauveur*, on the S. E.

that of the *Bastan* leading to *Barèges*, guarded at its mouth by the Castle of *St. Marie*. From both of these issue Gaves which, meeting in the midst of the plain, escape by its third or N. angle through the defile leading to *Pierrefitte*, and traversed by the carriage road. At the upper end of the plain between the defiles of *Gavarnie* and *Barèges*, at the foot of a lofty mountain called *Pic de Bergons*, lies the little village of *Luz*. An avenue of formal poplars traverses the verdant flat meadows, gushing with rills of water, to which they owe their emerald tints and rich crops of grass, and leads into

*Luz*, where *Madame Cazaux's Inn* (*H. des Pyrénées* or *Poste*) deserves the praise of comfort, tolerable cleanliness, a good cuisine, and great civility. It is the best head-quarters for expedition to *Gavarnie* and *Barèges*. *Grandet's* lodging-house is also recommended.

*Luz* is a cleanly village, situated on a crystal Gave of rapid flow: to the refreshing stream of one of its tributary brooks, under the inn windows, horses and pigs repair to bathe all day long. The pigs in particular seem to have acquired unwonted habits of cleanliness in this country, and to enjoy excessively the ablutions of their sides administered by the swineherd, who bastes them with a wooden ladle.

The *Church of Luz*, enclosed within a castle furnished with battlements and loop-holed walls, is a great curiosity, bearing as it does the mixed character of the order of the *Templars*,—half monks, half soldiers,—by whom it was founded. They were planted here to guard the frontier in troublous times, forming an outpost of Christians against the *Saracens* at first, and *Spaniards* afterwards. The church, entered by a machicolated gate under a projecting turret, is a *Romanesque* building probably of the 11th century. The carved doorway, and the arcade of straight-sided arches, running round

the E. end on the outside, deserve notice; also a *small doorway* now walled up on the S. side, through which alone, according to a tradition, which wants confirmation, the proscribed race of *Caçots* were allowed to enter the church, where they occupied a chapel apart from the rest of the congregation (p. 237). Crêpe de Barèges is made at Luz.

The knoll behind Luz crowned with the ruins of a hermitage commands a very pleasing view, looking down into a valley on either hand, and is easily accessible. A path may be found to descend on the opposite side to St. Sauveur, crossing the road to Gavarnie, and the small wooden bridge over the Gave.

It is not more than  $\frac{1}{2}$  a m. by the level road from Luz to the *Baths of St. Sauveur*, a narrow street of white inns (H. de la Paix; de France) and lodging-houses planted on a narrow terrace or ledge, on the top of a rocky cliff, about 200 ft. above the Gave on its l. bank, and just within the jaws of the romantic and beautifully wooded defile leading to Gavarnie. Its most conspicuous edifice is a modern church in the form of a *Rotunda*, so badly built that its walls are cracked from top to bottom. Near it rises a *pillar*, which, by the erasure in 1830 of its inscription, has ceased to commemorate the event to which it owes its existence, viz. the presence of the Duchesse d'Angoulême at these baths. It stands in the so-called *Jardin Anglais*, a name given in France to a little spot where trees and weeds are allowed to grow promiscuously, without having any attention paid to it.

In the middle of the village are the *baths* (Etablissement Thermal), one of the handsomest in the Pyrenees, containing 14 or 16 baignoires, supplied from springs of sulphurous water, resembling those of Cauterets, but less warm, and less rich in gas. They are considered efficacious in female complaints, for nervous affections, &c. Thus the greater number

of invalids here are ladies, while at Barèges the male sex abounds. Being weaker than those of Barèges, a course of them is recommended as a good preparation for the stronger waters of Barèges.

The name St. Sauveur is said to be derived from an inscription set over the healing source by a bishop of Tarbes, at what period is unknown:—"Vos laurietis aquas de fontibus Salvatoris."

The carriage road up the valley stops at St. Sauveur: a wooden bridge opposite the baths leads over to the other side, where a bridle road is carried.

To a mere passing traveller Luz appears more cheerful and pleasant head-quarters as well as less expensive than St. Sauveur, while the one is as near to the various points of attraction in this neighbourhood as the other.

At Luz horses and guides may be had at the usual charges (p. 245). Jacques St. Laur, who may be heard of at Madame Cazaux's, is an excellent guide. Bernard is also recommended. Another guide, Pierre Sanio of Luz, made the ascent of the Maladetta in 1842.

The summit of the *Pic de Bergons*, the hill behind Luz and opposite St. Sauveur, 6,117 ft. above the sea, is one of the best points of view among the Pyrenees, and one of the most accessible, since even ladies may *ride* up without difficulty, or be carried in a chaise à porteur. About 2 hours are required to reach the summit, and  $1\frac{1}{2}$  to descend. From the top may be seen the Cirque of Gavarnie, the Brèche de Roland, and Tours de Marboré, and the more distant and loftier Mont Perdu to the S.; to the W. the Vignemale; to the E. the sterile valley of Barèges, and the Pic du Midi; to the N. the Vale of Lavedan and the plains beyond it.

There is a path, not easy to find without a guide, over the mountains from St. Sauveur to Cauterets: the journey takes 5 hours on foot; but the high road (already described) is



much grander in scenery, and as smooth as a bowling-green all the way, though it makes a wide détour.

*Cirque de Gavarnie—Brèche de Roland—Mont Perdu.*

The valley of the Gave de Gavarnie, at whose mouth stands St. Sauveur, contains some of the most striking scenery in the Pyrenees, and terminates in the most remarkable of those *Oules* or *Cirques* peculiar to the Pyrenees, and already described (p. 236). The distance from Luz or St. Sauveur to the Cirque de Gavarnie is about 15 m. A good but narrow horse road runs thither, and the time employed, riding as fast as stones, gutters, and steep and frequent ascents and descents will permit, is rather less than 3 hours; but ladies riding at a gentler pace will take 4 or 5. It takes 4 hours to walk; no guide is needed to Gavarnie, only thence up to the Brèche one is indispensable. On reaching the foot of the bridge leading to St. Sauveur, you turn short to the l., without crossing, and ascend by the road along the rt. bank of the Gave, passing the baths on the opposite side. The grand scenery of the defile begins at once:—umbrageous woods alternating with precipitous rocks—mountain peaks of picturesque form rear their heads aloft; below gapes a confined chasm. The road is a narrow shelf, cut in the face of a rocky precipice, down which the eye gazes 300 or 400 ft., sheer into the green and frothy river, agonised within the narrow, half-opened fissure below. One difficult pass around an angular shoulder of the mountain is called *Pas de l' Echelle*, because, before the present road was cut, it could only be traversed by a hazardous stair, descending on one side and ascending on the other. Here the peasants of Bigorre defeated a force of Miquelites (Spanish troops), who invaded the frontier for the last time in the wars of Louis XIV., 1708. There are ruins, down in the hollow, of an old *France*.

fort called *Escalette*, the vestiges of which are nearly-gone. Many small falls are passed and torrents crossed by high and narrow bridges, suspended over deep gulfs: many of the water-courses are bestridden by mills, not much larger than boxes; a row of such, close together, seen on the hill-side, near the romantic double *bridge of Sia*, looks like beads on a white string.

Twice the valley expands into the basins of Pragnères and Gèdre, and it is more often throttled (*étranglé*) by narrow defiles. On approaching the village of Gèdre from the hill above it, you have a fine view, for a short space, of the snowy mountains called *Tours de Marboré*, and of the *Brèche de Roland*, a gap in the wall of rock which crests the mountain, looking like a notch made in a jaw by the loss of a single tooth. It was cut through, according to the legend, by Roland, the brave Paladin, with his trusty blade *Durandal*, to open a passage in pursuit of the Moors. To the rt. of it the false *Brèche*, a similar gap, is seen. They both lie immediately above the Cirque of Gavarnie, and are soon lost to view behind intervening mountains, as the valley curves, and they are invisible from the Cirque itself. At Gèdre there is a small *Inn* (N.B. fleas), and a sight scarcely worth notice, but to which travellers are invited, called *Grotte de Gèdre*. It is an imperfect arch, formed by the torrent scooping out the rock, partly grown over with creeping shrubs. There is a pleasant excursion from Gèdre across the shoulder of the *Vignemale* to the *Lac de Gaube*, 4 hours' walk.

[The opening on the l., behind Gèdre, through which the torrent issues, is the mouth of the *Val d' Héas*, one of the largest and deepest valleys which penetrate the granitic region of the Pyrenees, containing fine wild scenery, and terminating in the Cirque de *Troumouse*, situated a little to the E. of that of Gavarnie. In coming from Luz the valley is

entered by a road turning to the l., on the height which precedes the village of Gèdre. It keeps up on the slope for some distance, then ascends along the rt. bank of the Gave, under the shade of fine trees, ashes and sycamores. The torrent descending on the l. from the Cambiel is next crossed on a bridge; a sombre gorge succeeds, leading to the village of Héas, remarkable for its *chaos* of granite blocks, about 4 m. from Gèdre, which have fallen from the mountain above, across the valley, and resemble that of Peyrada, described farther on. This enormous land-slip took place in 1650, blocked up the torrent, and formed a lake behind it, which lasted until 1788, when its waters, sweeping away the dam, broke out, inundating the valley below, and thus the lake was tapped and emptied.

Here is the celebrated *Chapelle de la Vierge d'Héas*, 4910 ft. above the sea level, resorted to yearly between the 15th of August and the 18th of September, by hosts of pilgrims from afar, who come to worship and kiss her miraculous image, which is dressed in gold-embroidered stuffs, and hooded with the red capulet of the country. Before the rude chapel was built by the shepherds of the valley, to shelter it, the image sought refuge upon an enormous block of granite, the largest and most elevated of the group of fallen fragments, called *Le Caillou de l'Arayé*, which is much revered in consequence. It is a wild and naked spot, with little cultivation. Beyond it the gorge d'Aguila opens out to the E. About 6 m. farther on the valley ends in the *Cirque de Troumouse*, a semicircular wall of precipitous mountains, enclosing a verdant plain. "It is larger than Gavarnie, but not so imposing, yet deserves to be seen. You may walk hence over the Coumélie mountain to Gavarnie. No provisions to be had at Héas."—*G. M. S.*]

The road to Gavarnie, from the prettily situated village of Gèdre, skirts the flanks of the mountain Coumélie, between hedges of box, and reaches in a little space the *Chaos* or *Peyrada*, an éboulement or slip of masses of gneiss fallen from above, so extensive that it looks as though a mountain had tumbled to pieces. It is a grand and savage scene. The path winds, in zigzags, through a perfect labyrinth of blocks, many of them as big as a house, and far larger than the Cumberland Bowdler stone, piled one above another in extreme confusion, forming mysterious cavities and sheds between them. These fragments sweep down to the Gave, and partly conceal it; their fall must have occurred long ago, from the lichens which cover their surface, and was probably produced by the action of the atmosphere, especially of frost, so powerful an agent in fracturing and disintegrating the slaty structure of the gneiss. Beyond the Chaos the road passes under the base of the Pimené, a picturesque mountain, rising on the l. to a height of 9384 ft.

In passing the Pont de Barregui the peaks and glaciers of the *Vigne-male* are disclosed to view for a short time, at the extremity of the Val d'Ossouë (p. 311), up which runs the mountain path to Cauterets by the Lac de Gaube.

Gavarnie is a poor small village, 4498 ft. above the sea level, with an inferior *Inn*, furnishing fresh trout and tough cutlets, which, unless a bargain is made, will be charged for exorbitantly.

The modernized and uninteresting *Church* contains the skulls of 12 Templars (?) beheaded in the reign of Philip le Bel; such is the tradition, and the Order certainly had a commandery in this desolate spot. One of the heads is said to be that of a female.

Behind Gavarnie rise the black walls of the *Cirque*, surmounted by eternal snow, shutting in the valley.



It appears close to the village, and the stranger will scarcely believe that he has 3 weary miles to trudge or ride, which will take nearly an hour, before he can reach its farther extremity. Three shallow, basin-shaped valleys, partly strewn with stones, partly carpeted with grass, seemingly at one time lake basins, are passed, before you surmount the small projecting wall of rock which masks the entry to the Cirque, and once, doubtless, dammed up the waters of the Gave. Here, shut out from the world, and, as it were, arrived at its end, you gaze up to the vast semicircle of rocks around, the tall rampire of a kingdom, at the base of which France terminates. The precipices forming its sides, varying in height from 1000 to 1400 ft., are divided into 3 or 4 steps or stages, upon each of which a glacier, covered with white snow, is heaped: not a scrap of vegetation relieves their bare sides. Down the vertical faces of the rocks stream 12 or 15 thin cascades, like white threads; but there is one on the l. hand, where the precipice is least interrupted, which falls in one white cord, only twice broken by ledges, nearly 1266 ft. high: it is reputed the highest fall in Europe, and is the head water of the Gave de Pau; but so small is it in volume that it dissipates into spray before reaching the bottom. These streamlets are the drainage of the glaciers above, and all, joining the Gave, escape from the Cirque by the only opening, that by which the traveller enters. The floor of the Cirque is an uninterrupted and irregular heap of rubbish and blocks of rock, the ruins of the neighbouring mountains which have fallen from above, very toilsome to walk over; and in the midst are one or two patches of dirty snow nearly consolidated into ice, under which the Gave flows in a hollow vault. It takes nearly  $\frac{1}{2}$  an hour from the entrance to reach the foot of the high waterfall, where the geologist may find specimens of the fossils contained

in the rocks of the Cirque, which have been ascertained by M. Dufresnoy to be identical with those of the chalk. An English traveller would certainly not recognise, otherwise, that formation, in the dark cliffs around, so unlike in colour and texture to the white chalk of England.

The mountains rising above the Cirque, but not visible from within its enclosure, are to the E. the *Cylindre*, 10,050 ft., so called from its shape, whose base is embedded in the great glacier whence springs the high fall; the Tours de Marboré, 9964 ft., forming part of the Mont Perdu; and on the W. the Brèche de Roland, and farther on the Fausse Brèche.

The ascent of the *Brèche de Roland* is made from the Cirque of Gavarnie: it is fatiguing and difficult, but not dangerous, provided the head be steady. Some provisions, and a wine or brandy flask, should be taken. It occupies 4 hours, and 2 to descend; slow walkers take  $3\frac{1}{2}$  to 4 h. to ascend, 3 to descend. The ascent commences from the corner of the Cirque on the rt. hand, opposite to the high fall. A stranger would scarcely find the spot; no path leads to it, and there is no apparent break or interruption in the perpendicular wall of the Cirque. The strata of the limestone are here vertical, and a buttress of it slightly projecting from the mass furnishes the means of scaling the precipice along the abrupt and shattered edges of the slaty rock here divided like the leaves of a book, set on end, but shivery on the surface. The broken angles and splinters serve as steps, in which one may insert the toes and fingers, but it is as abrupt as the ascent of a ladder; and wide spaces of smooth rock often intervene without any notch or projection offering a foothold. To those who cannot look down a sheer precipice many hundred feet deep without a tendency to giddiness, there is some danger in this escalade, as well as in passing over some smooth projecting shoulders of

rock, and round the edges of 1 or 2 cliffs, which alternate, higher up, with steep slopes, covered less with grass than with fallen stones. These steep grassy banks form a pasturage, called *Las Serrades*, for the flocks of some Spanish shepherds, who rent them from the commune of *Gavarnie*. There is no intermission to the steepness of the ascent, no flat interval between the slopes; it takes more than 1 hour of "treadmill work" to rise above the high cascade. It is a glorious sight to look down from this upon the precipices and waterfalls, and the great glacier which feeds them, at which, shortly before, you gazed up with aching neck. Hence the *Tours de Marboré* are well seen; and at this height, about noon, the roar of avalanches succeeds to the monotonous dash of waterfalls, which before alone interrupted the solitude. The *Cirque* is soon after lost sight of: above your head rises an expanse of snow and glacier covering a steep slope, inclined like the roof of a house, surmounted by the wall of rock, in the midst of which is *Roland's Breach*, and another similar embrasure on the rt. of it, called *Fausse Brèche*. As the glacier is too abrupt to ascend, you leave it on the l. hand, and begin to climb a less steeply inclined, snow-clad slope, which at some seasons is denuded down to the slaty rubbish below the snow. It is a work of some fatigue to surmount this, and crampons and a pole are generally furnished by the guide. When two-thirds of the acclivity are surmounted the guide turns to the l. across the glacier, whose surface is so highly inclined that it is not possible to scale it from below. Even to cross it when the snowy surface is hard or slippery requires great caution. The mountaineer sets his foot down firmly with a stamp, to secure a firm hold, and drives in his pole well at every step he takes: a false move would send you at once to the bottom. A few paces beyond the glacier brings

you to the *Brèche*. That insignificant notch in the mountain brow seen from *Gèdre* (p. 313) has now expanded into a colossal portal 300 ft. wide, 350 ft. high, and 50 ft. thick—9337 ft. above the sea level. The ridge or crest in which it is formed is literally, not metaphorically, a wall of rock varying in height from 300 to 600 ft., which here divides France from Spain, escarped on both sides, and not more than 50 or 80 ft. thick. Through this singular opening—as it were a window in the mountain, nearly square in its angles, and not much wider above than below—Spain is seen; a most uninviting prospect of rugged and bare mountains and valleys filled with stones and snow in the foreground, while the distance is formed by the hazy plain of *Arragon* rising high up against the horizon. On the French side there is more of interest in the striking forms of the *Vignemale*, the *Pic du Midi de Bigorre*, the *Bergons*, and a hundred other peaks.

The *Brèche* is said by *Raymond* to be visible from *Saragossa* and *Huesca*; and a practised eye, knowing where to search for these cities, might, with the aid of a telescope in a clear state of the atmosphere, be enabled to discern them from hence.

The threshold of the *Brèche* is angular, like the roof of a house, and the frontier line runs directly along it, so that one may sit astride of it with one leg in France and the other in Spain.

All along the front of the *Brèche*, on the French side, the glacier is scooped out into a deep fosse or cavity by the action of the sun's rays pouring from the south, through the opening, as *Raymond* has well explained, so that it cannot be approached directly, but only by skirting the edge of the cavity. The ascent was accomplished by the *Duchesse de Berri* in 1828, but it is not fit for ladies in general.



The Brèche de Roland is used by the inhabitants of several villages on the Spanish side as a pass into France, and especially by smugglers. Through it lies the way to ascend the *Mont Perdu*, whose top may be reached in 6 hours from the Brèche, descending at first some hundred feet, and skirting the crumbling slopes of the Marboré on the l. Travellers usually pass the night in a poor hut near its base on the high table-land called Millaris, scattered over with slaty débris, and traversed by rents and deep fissures. Mont Perdu is composed of 4 stages or terraces, faced by abrupt escarpments, each receding farther back than the one below. The 2 lower steps are easily ascended by means of a talus of marly débris fallen from above. The 3rd and 4th are very difficult to scale, especially the 4th, which can only be reached through a sort of chimney, serving as an outlet for the melting snow. The summit of the Mont Perdu is 11,168 ft. above the sea level, second in height to the Maladetta alone among the Pyrenees; and it was first surmounted in 1802 by Raymond after two dangerous and fruitless attempts. It is not to be tried without the aid of a skilful guide. One may ascend from the hut of the Millaris and return from the summit to Gèdre on the same day.

Very *interesting* excursions may be made from Gavarnie into Spain to Busaruelo (3½ hours), and one hour beyond towards Torla, through the grandest scenery, returning the same day; and, 2ndly, over the Brèche de Roland to Fanlo, Nerin, and the rivulet Bellos. See HANDBOOK FOR SPAIN.

*Barèges and Pass of the Tourmalet to Bagnères de Bigorre.*

It requires 1¼ hour to go in a carriage with two horses from Luz to Barèges, though the distance is only 4¼ m., but it is an ascent all the way, and the road is heavy and badly

made, because constantly washed away by the torrent. Notwithstanding this the accommodation at Barèges is so very inferior that the traveller bound for Bagnères by the Tourmalet had better lengthen his day's journey by starting from Luz than put up at Barèges.

On quitting Luz you pass on the l. the ruined castle of *Ste. Marie*, one of the last possessions retained by the English in the S. of France, since it held out for the Black Prince nearly as long as Lourdes (p. 305). It stands on a mount, at the point where the valley of Barèges, or of the Bastan, opens into the plain of Luz. This is one of the least attractive valleys of the Pyrenees; the mountains around it are not picturesque in their forms, and the fissile and easily disintegrated shale composing them, crumbling down and filling up the bottom and sides of the valley, has been cut through by the Bastan and other furious torrents which seam the mountains' sides. From time to time vast masses of débris are washed down, and éboulements ensue, which stop up the watercourses until a débâcle occurs, and spreads desolation below it. Such catastrophes are of frequent occurrence; and the main torrent, the Bastan, is a very scourge. The great elevation of the valley above the sea contributes to its cheerless and forbidding character; and it is in such a situation, at a height 4,180 ft. above the sea-level, confined by gloomy mountains which almost seem to overhang it, that

7 *Barèges* stands, a watering place better known by name, perhaps, in distant countries, than any other among the Pyrenees, and in deserved repute with those who are really ill and in earnest to get well, on account of the cures effected by its waters, but void of all other attractions, destitute even of a tolerable Inn (H. de France; best, but very uncomfortable: cuisine dirty and bad;—H. de la Paix; worse still). There is nothing to see here, so that our advice

to travellers for amusement is, pass through, and tarry not. Being the loftiest of the Pyrenean baths, its atmosphere is chilly and variable even in the height of summer. It contains about 70 houses, chiefly lodgings, with two miserable cafés, arranged in a long dull street, running by the side of the Gave. The buildings next the stream, which are *meant to last*, are based on huge buttresses of masonry, without which precaution they would long ago have been swept away by the inundations of the torrent. A wide gap, however, is left in the midst, upon which only a few temporary booths and huts of wood are raised, for the winter avalanches sweep down from the mountains Ayré on the S. and Midaü on the N., through the wide gaping gashes in their sides, which open out opposite the vacant space, and bury this part of the town under the snow for several months of the year. In consequence Barèges is inhabited only during summer and autumn, and is abandoned for the rest of the year, except by a few persons, who take care of the houses, to the wolves and bears, which often come down and prowl about the streets. Mr. Erskine Murray, who came hither in the midst of winter, found the entire population reduced to 30 men and women, collected around the great public bath for the sake of the heat of the water, all busily employed knitting. At the beginning of summer the owners return and dig out their houses from the snow, which covers them up to the first floor. The triste air of the place is greatly increased by the number of cripples, sick, and invalids you encounter at every step. This may be called the Hospital Brunnen of the Pyrenees, being visited yearly by 1,000 or 1,200 genuine invalids, to whom the prospect of regaining health is a sufficient attraction. The French government have established here a military *hospital*, capable of receiving 300 men and 100 officers (perhaps more) for 50 days. The

cures effected by the waters are wonderful: their efficacy is very great in gunshot and other wounds, in curing sores, in relieving rheumatism, stiffness of the joints, and scrofulous complaints. They cause old wounds, or ill-cured ulcers, to open afresh at first, then relieve them by discharges, drawing to the surface extraneous bodies long imbedded in the flesh, and promoting the exfoliation of carious portions of bone, and finally close the wound in a healthy manner.

The *mineral water* is very strong, its principal ingredient being sulphuret of sodium, with portions of carbonate, muriate and sulphate of soda, azote, sulphuretted hydrogen, and animal matter. It is derived from 6 or 7 different springs, the most potent being that called *Le Tambour*, but the supply is scarcely adequate to the demand. They are conducted into a miserably-arranged, dirty, and ill-smelling bath-house, where they fill 16 baths, for the use of which 1 fr. is charged, and into 3 piscines or public baths capable of holding from 12 to 20 persons each. One of these is appropriated to the soldiers, another to the civil service, the 3rd to the poor. Admission to them is settled by order of precedence, and they are in use all day and all night. Indeed so precious is the fluid, that the water from the bath-house is said to be turned into the piscines. The piscines are horrid vaulted dens below ground, their roof serving as a promenade, filled with vapour: and the water has a greenish-yellow tint. The waters have a strong smell of rotten eggs, and a nauseous oily taste; after standing they are covered on the surface with a film of glairy unctuous substance, which they also deposit on the sides and bottom of the bath, called *Barégine* by French chemists. These valuable medicinal springs rise (as usual in the Pyrenees) near a junction of the slate rock with the granite, and force their way to the surface through a mass of débris composed of the neighbouring



rocks. They were first brought into notice by a visit which Madame de Maintenon paid to them 1676, by advice of the royal physician Fagon, for the sake of the young Duc du Maine, natural son of Louis XIV., and her pupil. The “*gouvernante*” dates several of her letters from hence; and after a protracted residence she had the satisfaction of bringing back the little cripple so much better that he could enter the room to meet the king walking. She reached this place by crossing the Tourmalet, the road by Lourdes not being then made, and lodged in the *Maison Maraquette*. Barèges was once nearly swept away by the bursting of the Lac d’Oncet.

A scanty and stunted wood of firs and alders is planted on the hill above Barèges on the S. It serves as a partial protection from avalanches, and below is converted into a *promenade* by walks cut along the slopes.

The fine tissue called *crêpe de Barèges* is not made here, but at Bagnères de Bigorre and at Luz.

*Diligences* go daily in the season to Lourdes, where they correspond with those to Pau, Toulouse, and Bagnères. The direct road to Bagnères, and by far the most interesting, is over the *Tourmalet*, but it is not practicable for carriages. Horses and guides may be obtained at Barèges.

Besides the excursions described under the head of Luz, which may be made from Barèges nearly as well as from that place, is the ascent of the *Pic du Midi de Bigorre*, which lies but a short way off the road to Bagnères by the Tourmalet, and will now be described.

The distance from Barèges to Bagnères de Bigorre across the Tourmalet is about 18 m. Including a halt to rest the horses, it takes up from 7 to 8 hours. A good bridle road, which might be made passable for charrs, leads up the Bastan valley on the l. bank of the torrent. The valley looks very dreary from the barrenness of the mountain tops, and the deep

gashes cut in their crumbling sides by the avalanches which rush down them in spring. Yet the course of the falling snow is so regular, that on the very margin of these gashes cottages are built, each protected by a tuft of trees, and along their slopes a few cultivated patches of corn stretch upwards. Two torrents descend from the rt., out of the vales of Lienz and Escabous, at whose head lie nearly a dozen small tarns, or lakes. After passing these, the Bastan is crossed, and the main ascent begins.

[About 1¼ hour’s walk from Barèges, you pass on the l. a path striking N. up a small valley towards the *Pic du Midi de Bigorre*. That majestic mountain, which, though 9,553 ft. above the sea level, is free from snow in summer, rises on the l. of the Pass of the Tourmalet, and is accessible, even on horseback, in 4½ hours from Barèges. The path is steep, and in many places dangerous, there being scarcely room for a horse to step. It is possible to ride to within 100 yards of the summit. The way lies by the margin of the Lac d’Oncet, a picturesque tarn at the foot of the peak, nearly closed in by precipices, about 2,000 ft. below the summit. The view from the top is magnificent. It wants the numerous lakes of the Righi, but in other respects is superior. The Pic stands at the outer verge of the Pyrenean range: it descends with only one break to the plain, and affords a view towards Bordeaux and Toulouse, bounded only by the limit of vision. It comprises on the N. the plains watered by the Adour and Garonne; on the S. the great chain, including the step-like mass of the Mont Perdu, the Cylindre, Tours de Marboré, Brèche de Roland, and Vignemale, covered with glaciers; while among a multitude of peaks to the E. rises the Maladetta, the loftiest of the Pyrenees, forming a conspicuous point in this immense semicircle of mountains. There is another way down through the Hourquette de Cinq Ours and the ravine leading from the Lac d’Oncet

to Trames Aigues in the valley of Grip. See below.]

The *Tourmalet* is a low curved ridge, such as would be called a col in the Alps—an isthmus uniting the Pic du Midi with the main chain of the Pyrenees, over which lies the passage from the valley of the Gave de Pau into that of the Adour. The old and shorter road is carried up to the col in a series of sharp zigzags, over heaps of shivered shale: the pedestrian will save time by taking it. The new path is longer, and runs more on a level, round the shoulders of the hills. Those bound for the Pic du Midi take this path. On the rt. rise three bristling mountains of fine form, the Caubère, the Campana, and the Pic d'Espade. The summit of the Pass is 7,141 ft. above the sea-level: the view from it is not very striking; but as you look back the Monné and mountains above Cauterets are visible beyond it. The vale of Grip opens out far more pleasingly than that of Barèges, carpeted with beautiful pastures; it is the cradle of the infant Adour, which rises near the base of the Pic d'Espade. After a mile or two of gradual descent, the valley makes an abrupt dip, down which the path is carried, by a series of very steep zigzags called *Escalette*, to a hamlet occupied by shepherds, called Trames Aigues ( $3\frac{1}{2}$  hours from Barèges), at the mouth of a gorge through which the pyramidal mass of the Pic du Midi appears in full majesty. This is the finest object on the pass: its bare precipice, when lighted up by the sun, exhibits the most singularly contorted strata, imitating the lines on an agate. It remains in sight only for a short distance, but from no point does this mountain appear to greater advantage. The summit of the Pic is reached from Bagnères by ascending this valley.

Near Artigues, a hamlet on the rt. beyond the river, is a cascade formed by one of the tributaries of the Adour, and a little lower down is

another, the *Garret*, in the course of the Adour itself, beneath a black fir forest, which covers the shoulder of the mountain like a bear skin, above the village of *Grip*. Grip is a prettily situated group of scattered cottages, including a very tolerable country Inn, famed for its trout (H. des Voyageurs, chez Cazères): it is the one nearest Bagnères—4 hours' walk or ride from Barèges, and 3 from Bagnères de Bigorre. Grip is much frequented by visitors from both baths, on account of its waterfalls and its pleasing position, precisely in the part of the valley where trees flourish, corn begins to grow, and pastures become most verdant. The Pic du Midi may be reached in 5 h. from this, descending in 3 h. A mule path all the way; but up to the Lac d'Oncet, where it joins the path from Barèges, it is steep and rough.

From Grip to Bagnères de Bigorre there is a good carriage road, which, at Ste. Marie, falls into the *valley of Campan*, and the route to Luchon by Arreau (R. 86). The aspect of the Val de Campan from this point, and in descending to Bigorre, is less attractive than in ascending, owing to the arid, bare, and stained escarpments of the limestone cliffs (Jura limestone) on the rt. bank of the Adour; but there are some fine views on the l., looking up the tributary valleys towards the Pic du Midi.

Ste. Marie,  $7\frac{1}{2}$  m. from Bagnères, lies near the point of junction of two valleys, up one of which runs the road to Grip and the Tourmalet, and up the other, that to Luchon by Arreau. The village of Campan, lower down, which gives its name to the valley, is not remarkable, but every traveller is pestered as he passes to visit the grotto, which is not worth seeing.

16 The Pics du Midi and de Montaignu are well seen below this through the fine opening of the vale of Lesponne to the l.: near its entrance stands the mansion of St. Paul. (See p. 329.)



At Baudéan, a small village a little lower down, Baron Larrey, the army surgeon and favourite of Buonaparte, who accompanied him on his various campaigns, was born 1766, in a humble house marked by a marble tablet. The valley of Campan is fertile, well cultivated, and populous, with a considerable show of picturesque beauty (see p. 328). The precipitous mountain rising on the rt. is the *Penne de l'Hyéris*, often ascended on account of its view. The Pont de Gerde, over the Adour, leads to it.

2 m. short of Bagnères, close to the road, is Médous, a sequestered and abandoned Capuchin convent, reduced to uninteresting ruins. A copious source of clear water rising here serves to turn a marble mill. On the outskirts of Bagnères, the road passes close under the promenade called Allées Maintenon (p. 328).

BAGNÈRES DE BIGORRE (Route 86).

#### ROUTE 86.

THE PYRENEES — BAGNÈRES DE BIGORRE TO BAGNÈRES DE LUCHON — MOUNTAIN ROAD, BY THE HOURQUETTE D'ASPIN — ARREAU, COL DE PEYRESOURDE, AND VAL DE L'ARBOUST — EXCURSION TO THE LAC DE SECULÉJO, OR LAC D'OO.

This route may be divided into 2 days' journey by halting for the night at Arreau, situated about half way. The road to that place is practicable for light cars; beyond it there is only a bridle road. The total distance may be about 40 m., exclusive of the excursion to Seculéjo, which is about 12 m. more, to and fro, off the direct road. The route abounds in picturesque beauties; it ascends the Val Campan (described in R. 85) as far as the village of Ste. Marie,  $7\frac{1}{2}$  m., 4 hours' walk from Arreau. We here leave, on the rt., the road to Grip and the Tourmalet, and, crossing the Adour, ascend gradually along the bank of its E. tributary, up the Val de Séoube, and, passing through a scattered and picturesque

village, reach, in 2 hours, Paillole, a group of cottages, in the midst of green pastures, encircled by noble forests, which seem to have suffered little diminution from the woodman's axe. In the mountain on the E. side of the valley, composed of transition limestone, are the *quarries of Espiadet*, yielding the marble called of Campan, a great deal of which was employed in the decoration of the royal villa of Trianon. After being long abandoned, they are now again worked by M. Geruzet of Bagnères. At Campan itself, where the rocks are of the Jura limestone, no marble is obtained.

The ascent to the Col, or *Hourquette d'Aspin*, is carried up from the farm cottages of Paillole, at first in zigzags, entirely through forests of fir, composed of fine trees of ancient growth, covering the hill sides far and wide. Through gaps among the trees, the bare Pic d'Arbizon (?) is seen, from time to time, on the rt., at the head of the valley. The trees thin out before reaching the top of the pass, whose open curved slopes are covered with turf. The Hourquette d'Aspin ( $1\frac{1}{2}$  hour from Paillole) commands *one of the finest views in the Pyrenees*. Look back, and the Pic du Midi de Bigorre and the Pic d'Arbizon rise majestically above the pine forests; forward, and the billowy forms of many mountains, and the junction of many valleys, peaks, ridges, and hollows, one behind another, are presented to view, and the horizon is closed by the snowy top of the Maladetta, or at least of the Monts Maudits. The slope of the hills, on the side of Arreau, is so steep that the descent upon that town, which appears lying in a hole, as it were, no more than a rifle shot off, is only effected by most complicated tourniquets, or winding terraces, the vagaries of which are most extraordinary and tantalising: 4 or 5 times, when you think you are close to Arreau, the road turns away to penetrate nearly to the head of the valley,

on the rt. or l., and it takes a good hour from the top of the pass to reach the town, which is about 5½ hours' ride or walk from Bagnères. There is another pass from the Val de Campan into the Val d'Aure, and to Arreau, crossing the mountains more to the S. than the above, but the path is not so well marked, and is much steeper, though shorter. It is called Hourquette d'Arreau.

Arreau (*Inn*: H. de France, neither clean, good, nor moderate) is a small town, nowise remarkable except for its situation, nearly in the midst of the picturesque Val d'Aure, which runs up into the Pyrenees, between the Val de Campan and the Val de Luchon, at the junction of the Nestes (or torrents) de Louron and d'Aure, which turn several saw-mills: the number of inhabitants is about 1600.

Lower down the valley, near Sarincolin, are the marble quarries of Beyride and Camous.

[The upper part of the Val d'Aure unfolds scenery whose extreme beauty and magnificence will well recompense the pedestrian disposed to explore it, and prepared for the wretched accommodation which is to be found. Indeed it is advisable to take provisions of some kind, or at least white bread. A path along the l. bank of the Neste leads through the villages of Cadéac (½ hour), Ancisan, Guichen, all ancient settlements of the Templars, to Vielle (Aure), 5 m., a village with a wretched inn (H. d'Espagne). Over this part of the valley the Pies d'Arbizon and d'Azet rise in great grandeur. Continue along the l. bank from Vielle, 1½ hour, to Tramesaigues, a village having sulphureous springs, a very picturesque ruined castle on a height, and a curious *church* of the Templars, with a wooden clock tower, and a singularly ornamented door. It is one of the most romantic spots in the Pyrenees. "From the l. bank you have the best view of the Templar ch. and castle opposite. Cross here

by a bridge and return to Vielle by the rt. bank (1 hour). The only place where you have a chance of getting anything to eat at Tramesaigues is chez le Douanier. The upper part of the valley is well worth exploring by any one who can rough it."—*G. M. S.* Before reaching the village the valley divides, and 2 paths strike off into Spain, one due S. by the Port de Plan, the other inclining to S.W. by the Port de Bielsa, passing Aragnouet, whence a path mounts over the Port de Cambiel to Gèdre, at the mouth of the Val d'Héas. (R. 85, p. 313.) The *Port de Cambiel* is a depression between the mountains of Cambiel and the Pic Long, nearly 8000 ft. high, whence the Vig-nemale and M. Perdu are well seen.]

Two mule paths conduct from Arreau to B. de Luchon: one by the *Port de Pierrefitte* (7 hours' walk), which is the loftier and the finer in point of scenery, but a bad road; a guide is required at least up to the Col, as it is difficult to find; the other, more commonly taken, by the *Port de Peyresourde*. It runs up the Valley of the Neste de Louron, which, at first narrow, widens out, and becomes populous higher up, and is studded with a great number of old feudal castles, now in ruins, but which once defended the passage into Spain, perched on conical rocks. That of Bordères, on the l. bank, was the stronghold of the Counts of Armagnac, owners of the valley, the last of whom, John V., in the reign of Louis XI., 1475, on account of his infamous union with his sister, was excommunicated by the pope, and deprived of his princely domains by Louis. Below this, looking back, there is a good view of the windings of the road to the Col d'Aspin and of the town of Arreau, which looks well only at a distance. At Avejan, above Bordères, the road crosses to the rt. bank, and, gradually ascending by narrow lanes flanked by trees and hedges, through the villages Estravielle and several others, reaches



Loudervielle, distinguished by its square feudal watch-tower projecting over the valley, and confronted, on the opposite side, by a rival fort, based upon a rocky pedestal now quarried for slates. Above this, the vale of the Louron divides into 2 branches, terminating in the Ports de la Pez and de Clarbide, leading into Spain, but difficult, if not dangerous, and little used; and between them rises the grand Pic de Génos. Near the Port de la Pez are remains of a *tunnel* 200 ft. long, commenced by some speculators, who designed to bore through the mountain in order to reach the Spanish pine forests, and make use of their timber. The scheme was abandoned. The ruined gallery is situated high above all habitations, and to visit it would take up a day. We pursue our course up the valley no farther, but at Loudervielle (2½ hours' ride from Arreau) turn to the l. up a very steep stony ascent leading to the *Col de Peyresourde*, 4452 ft. above the sea, which separates the Val de Louron from that of L'Arboust, covered with coarse pasturage dotted over with a few fir trees. Cultivation is carried up very high in the opposite valley; but the woods (*arbusta*), from which, doubtless, it derives its name, are greatly diminished. Before descending, a narrow path, difficult, and not practicable for horses, strikes off on the rt. direct to the Lac d'Oo, or de Seculéjo. Horsemen must make a considerable *détour*, descending the valley as far as an ancient, half-ruined, solitary church, planted on a singular mound, by the side of which rises the brand or split fir tree set in readiness to be lighted on "The Eve of St. John" (1¾ hour from Loudervielle).

In order to reach the beautiful Lac d'Oo you turn to the rt. at this church, and by a very narrow and stony path, through the fields and along the slopes of a hill which drops down upon the village d'Oo and its picturesque castle, you enter the Val

d'Asto, as this branch of the Val de l'Arboust, at whose upper end lies the Lac de Seculéjo, is called. It is very narrow and deep, closed in by impending mountains, and at its head by glaciers. The horse-path up it crosses the clear stream of the Oo or Go, just outside of the village, and following the rt. bank of the stream, threads stony lanes between pastures of vivid green under the shade of ash-trees. Next, it emerges upon open meadows, beyond which it begins to mount in earnest, by a long series of zigzags, a high step stretching across the valley, which from below or above appears a precipice, yet is made accessible for horses, but is very toilsome to surmount. We now enter the fir-woods; the mountains, sternly grand, rise beetling over the path, which is at one spot a mere shelf cut in the face of the rock. At length the valley is traversed from side to side by a natural dam of slate rocks, whose strata are vertical. Behind this the little oval basin, called *Lac d'Oo*, or *de Seculéjo*, lies snugly cradled, shut in all round, save on the side of the dam, by precipices of great height, which, though vertical, are tinged green by partial vegetation. In front, a very fine cascade forms the centre of the picture, and is reflected in a white streak upon the dark mirror of the lake below. The waters of the lake escape in a fall over a gap in the slate-dam already mentioned, upon which also stands a hut where horses may be put up, and common refreshments obtained. The lake abounds with trout. Here a small toll is paid for keeping up the path.

The waterfall of the Lac d'Oo is fed from a still higher reservoir, the *Lac d'Espingo*, drawing its supplies from the contiguous glaciers. It may be reached either by a narrow path along the l. or E. margin of the Lac d'Oo, or by crossing it in a boat kept to convey people to the foot of the fall, and then by clambering up at the side of it through a rent in the slate rock, whose broken laminations serve as steps (*scala*); next, passing

above the cascade, it reaches the upper lake, *D'Espingo*,  $1\frac{1}{4}$  hour's walk from Lac d'Oo. The savage wildness and awful stillness of this scene render it very impressive. There is a third lake close beside it, called *Saounsat*, in which fish cannot live, though trout are found in its neighbour, lying at the foot of the Mount Espingo, amidst scenery far more savage than that of the Lake d'Oo. The path continues in a bad state above this, over beds of snow, past a fourth lake, which remains ice-bound almost the whole year, to the col called *Port d'Oo*, 9850 ft. above the sea-level, the loftiest col or pass in the Pyrenees, and exceeded by very few among the Alps, leading to the Spanish town of *Venasque* (R. 87). On the l. of this pass lies the vast glacier of the *Port d'Oo*, the second in extent, next to that of the *Maladetta*, among the Pyrenees.

It takes about  $1\frac{1}{2}$  hour to ascend from the village d'Oo to the Lac d'Oo, and 3 hours to descend from the lake to Luchon.

In going from Luchon to the Lac d'Oo you turn to the l. out of the *Val de l'Arboust* at the village of *Cazeau*: beggars and goîtres abound here. Lower down is *St. Aventin*, a large village named from a chapel of that saint.

Thus far the road is kept in very bad order; hence to Luchon, though steep, it is practicable for chars. After crossing the minor stream of the *L'Oueil*, the fine avenue called *Allée des Soupîrs* leads into

BAGNÈRES DE LUCHON (R. 87).

### ROUTE 87.

THE PYRENEES. — PAU TO BAGNÈRES DE BIGORRE, AND TO BAGNÈRES DE LUCHON, BY TARBES. — POST ROAD. — EXCURSIONS TO THE VAL DE LYS, PORT DE VENASQUE, AND VAL D'ARAN.

To B. de Bigorre, 60 kilom. = 37 Eng. m.; thence to Luchon, 78 kilom. = 48 Eng. m.

*Diligences* daily, but very slow.

The following is the direct post-road between the two Bagnères: it runs through the plain to the N. of the Pyrenees, affording only distant views of them. To explore their beauties, the traveller must pursue Routes 85 and 86—practicable partly only on horseback.

A high table-land, in part uncultivated, is traversed both before and after reaching

16 Bordes d'Expouy.

The village passed on the rt., shortly before entering Tarbes, distinguished by its lofty church, is Ibos.

23 Tarbes.—*Inns*: H. de la Paix, very good—*E. o. S.* (try coquille aux champignons);—H. de l'Europe;—H. de France. Sir John Froissart put up at the Star, and commended his hostel. Tarbes, chef-lieu of the *Dépt. des Hautes Pyrénées*, is pleasantly situated on the clear Adour, in the midst of a fertile plain, in full view of the Pyrenees. It has 12,630 inhab. and some manufactures, but contains few objects of interest. Several public walks contribute to the public health and recreation, the principal and most striking of which is the *Place Maubourquet*, where are the principal inns and cafés. There is also a pleasant walk by the side of the river. The buildings are not remarkable. On the *Place Marcadieu* the markets and extensive yearly fairs are held. The market-people, in their various costumes, are worth seeing. There is a fine bridge over the Adour, and a portion of its water is distributed in canals through the town. The chief building is a modern cathedral, said to occupy the site of the Castle of the Counts of Bigorre, of which Tarbes (the city of the *Tarbelli*) was the capital. The English monarchs retained possession of Bigorre, which, with Guienne, formed the dowry of Queen Eleanor, for 300 years, down to the reign of Charles VII. The Black Prince kept his court at Tarbes; Froissart de-



scribes his visit to the Comte d'Armagnac.

The distant *view* of the Pyrenees is scarcely equal to that from Pau, but the Pic du Midi de Bigorre here forms the prominent object, and the mountains about Luchon are also visible. An English baronet keeps a pack of fox-hounds here, and turns out several times a week in the season. Tarbes was the birth-place (1755) of the infamous Bertrand Barrère de Vieusac, member of the National Convention, the meanest and most dastardly as well as the most cruel of the monsters of the Revolution. (See *Edin. Rev.* 1844.)

A smart action was fought at Tarbes, in the interval between the battle of Orthez and that of Toulouse, in which the British army drove the French from their position, and compelled them to retreat. One French brigade was attacked by the 3 rifle battalions:—"The fight was short, yet wonderfully fierce and violent; for the French, probably thinking their opponents to be Portuguese, on account of their green dress, charged with great hardiness, and being encountered by men not accustomed to yield, they fought muzzle to muzzle, and it was difficult to judge at first who would win. At last the French gave way." But out of the 120 men who fell on the side of the British, there were 12 officers and 80 men of the Rifles.—*Napier.*

The road from Tarbes to Cauterets and Barèges, by Lourdes (19 kilom.), is described in Route 85. Tarbes is the key to the communication with all parts of the Pyrenees.

*Mallepostes* go daily to Pau and Bayonne; to Auch and Toulouse; to Auch, Agen, and Limoges.

*Diligences* go to Lourdes and Barèges; also to Bagnères; to Toulouse and Bordeaux; to Bayonne, Auch, Agen; to Bagnères de Luchon, by Lannemezan, a long stage of 20 Eng. m.

From Tarbes our road ascends the

l. bank of the Adour; gradually advancing within the embrace of the mountains, which rise in height in proportion as we advance. The country is richly cultivated, copiously irrigated, and thickly peopled; no less than 8 villages being passed on this stage. A little off the road lies the Château d'Odos, where Marguerite, Queen of Navarre, sister of Francis I., died, 1549. Near Montgaillard, the road from Lourdes, Barèges, and Cauterets, to Bagnères, falls in on the rt. At Trebons, the Val d'Ossouet opens out on the rt., and runs up towards the Pic de Montaigu.

A little below Pouzac occurs a church, walled round like that of the Templars at Luz. About 2 m. below Bagnères, on the rt. bank of the Adour, near the farther extremity of a wooden bridge over that river, the geologist will discover a knob of hornblende or trap rock (ophite), which appears to have affected the rocks about it, since, a little lower down, the granite is found decomposed, intermixed with a limestone which has assumed a large granular structure.

The knoll passed on the rt., a little behind the village of Pouzac, before reaching the town, is the *Camp de César*, so called from an intrenchment upon it.

21 BAGNÈRES DE BIGORRE.—(*Inns*: H. de France, good; comfortable apartments, and excellent table-d'hôte; Galignani is regularly taken in; persons making some stay may board and lodge for 6 fr. per diem;—Frascati, a large establishment, including mineral baths and springs, a concert room, billiard and coffee rooms;—H. de Paris, good;—H. du Grand Soleil; du Bon Pasteur, good; de la Paix.)

Bagnères is the most town-like of the Pyrenean watering-places in extent, amusements, shops, &c., having a permanent population of 8000, often augmented by 6000 or 8000 strangers intent upon pleasure as

well as health, during the season, which lasts from the end of June to the end of September. It is a cheerful town of white-washed houses, set off with blue marble window-sills and door-jambs, delightfully situated, just where the plain of Tarbes begins to contract into the vale of Campan, and the slopes which bound it to change from hills into mountains, whose noble peaks and masses rising to the S. form the background of all the beautiful views in and about the town, while undulating slopes, trees, fields of maize, vines, and villas fill up the foreground. It stands at a height of only 1852 ft. above the sea level; and its fault is the fervid heat, dust, and glare during part of the summer, unfanned by the mountain breezes. The Adour, on whose l. bank it is built, is here greatly reduced in breadth and volume by the numerous artificial cuts and canals, which borrow its waters for the purpose of irrigation, and to turn marble, paper, and other mills. A large part of these streams also is made to circulate through the streets; and thus they contribute to clean them, while they freshen the air. Every street and lane has its own clear gutter, at which the housewives wash their linen and domestic vessels before their own doors; while to the deeper canals, horses, asses, and pigs repair twice a day, and after wading knee deep, are ladled over with water thrown from their backs by a wooden scoop.

Montaigne preferred Bagnères above all the Eaux-Thermales which he had visited, "comme celles où il y avait plus d'aménité de lieu, commodité de logis, de vivre, et de bonne compagnie;" and on almost all these heads it still continues to deserve praise. The climate is warmer and less variable than that of the mountain baths; the cost of living and price of provisions are moderate, lodgings being very numerous, since almost every householder in the town

lets either part or the whole of his domicile.

To the passing traveller its chief attractions are the picturesque beauties of the valleys and mountains around, which afford endless resources: in the town itself are scarcely any curiosities or sights.

The tall, octagonal, Gothic tower, rising near the H. de France, belonged to a church of Jacobins, suppressed at the Revolution. The church of St. John, which belonged to the Templars, but is now converted into a playhouse, retains a fine pointed doorway, enriched with mouldings. One or two old feudal towers remain of the ancient *fortifications*, relics of the days when Froissart describes Bagnères as "une bonne, grosse ville, fermée," whose peaceful citizens suffered sorely from a neighbouring den of thieves, or castle, or, to borrow Froissart's words, "Ceux d'icelle ville avoyent trop fort temps, car ils estoient guerroyés et harriés de ceux de Malvoisin qui sied sur une montagne." (See p. 329.) Bagnères was given up to the English by the Treaty of Bretigny; and, as a border fortress on a line of passage into Spain, it was taken by Henry of Trastamare by storm, after the death of his brother, Don Pedro the Cruel. One of the towers, called de Malfourat, still stands opposite the Thermes.

Bagnères de Bigorre owes its reputation as a watering-place to its warm *saline springs*, varying in temperature from 87° to 123° Fahrenheit. They are good for disorders of the digestive organs, and resemble those of Baden-Baden, but contain a smaller quantity of saline substances. They were known to the Romans, as inscriptions found in and near the town prove; indeed the name Bagnères is not improbably traced to the Latin "*Balnearia*." The sources rise, to the number of about 40, within the space of 3 or 4 hectares, out of a shaley, calcareous rock, sup-



posed to be the equivalent of the Jura limestone.

The *Public Bathing Establishment*, or *Thermes*, situated at the extremity of the town, under Mount Olivet, is the largest building in it, and the handsomest and most cleanly in the Pyrenees, though the arrangements for conducting the mineral waters to it are said to be defective, and to deprive them of a part of their medicinal properties. The six springs, La Reine (named from Jeanne de Navarre, mother of Henri IV., who used it 1567), Le Dauphin, Roi de Lannes, St. Roch, Foulon, and Des Yeux, are conducted into the building and distributed among its 29 baths and 4 douches. The water is previously received and cooled down in open tanks; and it is in this situation that the substance called by French chemists Barégine, but whose nature, whether animal or vegetable, conferva or oscillatoria, has not yet been ascertained, collects on the surface.

There are about 20 other private establishments in and around the town; indeed it is only necessary to bore into the ground to a certain depth to obtain with certainty a warm saline spring. The most fashionable and frequented bath, and the water apparently most efficacious, is that of *Le Salut*, rather less than a mile out of the town, in a great recess in the flank of the Monné hill. The bath-house is a solitary building, approached by a long avenue of poplars, winding through the pretty green valley, crowded at all hours, but chiefly in the morning, by bathers on horseback or foot, or in sedan chairs. It contains only 10 baths, so that, during the season, they are in request at all hours. The water of the Salut is saline, with a sulphureous smell; and it has the property of blackening silver. It has scarcely any perceptible taste, only a sort of milky feel in the mouth.

Bagnères also possesses a chalybeate spring, *Fontaine Ferrugineuse*

(or d'Angoulême), almost the only one in the Pyrenees, situated on the E. flank of the Mount Olivet, in the direction of the village of Pouzac (p. 325). Granite is stated to have been found by digging, within a few feet of the spring, which doubtless originates in that rock.

The vale of Campan above Bagnères abounds in the beautiful marbles for which the Pyrenees are famed: they are much used in Paris, and the working of them gives employment to many persons here. The *Marbrerie* of M. Gêruzet is on a very extensive scale, and the modes of cutting, turning in the lathe, and polishing large blocks, by machinery moved by the river, are well worth seeing. Tables, chimney-pieces, buffets, pillars, slabs, as well as vases and other articles, are made here; and no less than 20 varieties of marble are employed. The prices are not extravagant: a list of the cost of the different varieties is printed. The most beautiful are the green and flesh-coloured marbles of Campan, the blood-red or Griotte, filled with fossilised shells of the nautilus, whose spirals are disclosed in cutting. The quarries whence they are derived occur in the transition limestone formation. M. Gêruzet is also banker and agent of Coutts.

The knitting of the *fine wool* of the Pyrenees, derived from Spain, gives employment to the greater part of the females, young and old, in and about the town, who may be seen sitting at their cottage-doors, in the roads and streets, hard at work. The articles made here are counterpanes, mittens, aprons, caps, work-bags, besides shawls and scarfs of woollen gauze, rivalling in thinness fine lace. The so-called *crêpe de Barèges* is not made at that place, but in Bagnères and Luz. The principal dépôt for this kind of articles seems to be chez Mademoiselle Laffourque.

The *English service* is performed on Sunday at 11½, in a room in the

Mairie (1846): ? if a permanent service.

There is a *Theatre* here in a de-secrated church.

Concerts and balls, during the season, are given at Frascati's, a superb establishment, which was formerly a gambling-house.

*Diligences*—4 or 5 daily to Tarbes; thence to Pau, Auch, Bordeaux, Limoges; daily to Toulouse, to Bagnères de Luchon, to Cauterets, Luz, Barèges (nearly 40 m. distant by the post and coach road, 20 by the Tourmalet). (See R. 85.)

*Guides* and *ponies* for excursions in the mountains are very numerous. The landlords of the H. de France or other inns will recommend the most trustworthy.

*Chaises à porteurs*, or sedan-chairs, are much used by invalids to go to the bath. To be carried to the Bain de Salut and back costs 1 fr.

The *Promenades* most frequented in and near the town (besides the *Avenues de Salut* already mentioned) are the *Coustous* (? Côteau), a long platform in the midst of the town, lined with houses and cafés; shaded with trees, under which a sort of fair is kept up throughout the season, in temporary booths occupied by itinerant marchands. It is crowded in the cool of the evening.

The *Allées de Maintenon*, a row of trees planted along a bank above the road leading to Campan, are named from the lady who became the wife of Louis XIV., but who visited these baths in the capacity of gouvernante to his deformed child, the Duc du Maine, for the benefit of the waters, in 1675, 1677, and 1681.

The *pleasantest walk* in the morning is along the slopes of the *Mont Olivet*, the wooded hill rising behind the Thermes. Numerous shady paths are cut through the trees, whence you may survey the vale of the Adour. One path skirting the flanks of the hill leads to the chalybeate spring.

In the rear of Mont Olivet and of

the Bains de Salut rises the loftier cone-topped mountain *Bélat*, which takes more than half an hour to ascend, but is accessible on horse-back.

By crossing the two bridges over the two main arms of the Adour, by which the road to Toulouse quits the town, and turning to the rt., after passing the second, up a steep road in zigzags, the *Palombière* is reached; a row of trees on the top of the hill, between which the fowlers stretch their nets in September and October, to catch the migratory flocks of wild pigeons, aided by boys hoisted aloft in a sort of cradle at the top of a pair of poles 130 to 150 ft. high above the ground—a position which seems terrific, owing to the bending of the poles beneath their weight. On the approach of the birds the boy throws down a piece of wood somewhat in the shape of a pigeon, which making a whizzing noise causes the birds to stoop in their flight, so as to come within the reach of the net, which the fowler allows to fall on them by loosening the cords. There is scarcely a better point than this to look up the valley of Campan and survey the magnificent mountains at its head, bounding it on the S.W.; the Pic du Midi and the Pic de Montaigu, with the Penne (*Pen* or *Ben*, Celtic, head) de l'Hyéris rising on the l. In the midst, the white buildings of Bagnères are spread out, backed by the dark masses of the Mont Olivet, the Bédat, &c. The Adour makes little figure in the view, so much are its streams frittered away; but below the town to the N. its wide, cultivated plain expands to view for miles and miles, until it unites with that of the Garonne.

*More distant excursions*, of great beauty and interest, are to the Valley of Grip and its cascades; to Trames Aigues, on account of the fine view thence of the Pic du Midi, described at p. 320; the ascent of that Pic also, p. 319.



The most beautiful scenery of the Vale of Campan is to be found within the branch of it called *Val Lesponne*, opening out near the Château de St. Paul, between Baudéan and Campan, and running up between the Pic du Midi on the S. and the Pic de Montaigu on the N. Its lower-portion has chiefly the pastoral character of rich verdure, alternating with cultivated fields. Beyond the village Lesponne it contracts in width, its aspect alters, and becomes wilder; bare rocks and rugged crags succeed to dark forests of beech and pine: the forms of the mountains are very striking. About 2 m. above Lesponne a gorge, opening on the rt., displays the entire mass of the Montaigu, a noble spectacle; and the streamlet traversing it descends the steep rocks in a pretty fall. Half an hour's walk farther, and the valley divides: the branch on the rt. leads, in 3 hours, over the pass called Hourquette de Baran by Villelongue, to Pierrefitte in the Val d'Argelez; that on the l., disclosing the noble form of the Pic du Midi, leads up to the *Lac Bleu*, in which the stream of the Val Lesponne takes its rise. The ascent to it is very steep and fatiguing, though achieved by ladies; it is cut through the mica slate rock, covered at first by a wood, beyond which are extensive pasturages. The lake itself "is an oval basin, or tarn, about 2 m. long, at the top of a mountain, surrounded by bare craggy peaks of the most curious formation, within whose declivities the snow always remains. It is a solitary spot, with no house, or tree, or living thing to be seen in its vicinity, a stillness almost death-like reigning around. It might be dreary, but for the rich warm colouring of the rocks, the depth and stillness of the water, and its intense blue, whence it takes its name."—*Ellis*. It takes 6 or 7 hours, on foot, to reach Lac Bleu from B. de Bigorre. Higher up is another smaller tarn, difficult to approach, distinguished

as the *Lac Vert*, another of the head waters of the Adour.

The shortest and most romantic way to Bagnères de Luchon from B. de Bigorre is the bridle road by Arreau over the Hourquette d'Aspin, at the head of the Val de Campan, and through the Val de Louron, described in Route 86. Those who cannot endure the fatigue of riding must pursue the circuitous post road, which doubles the mountains, and skirts their roots between the valley of the Adour and that of the Garonne, as follows. It quits Bagnères by crossing the Adour, and for the two first stages is identical with that to Toulouse. A steep hill precedes.

12 Escaladieu, where the post house occupies part of the buildings of the ancient *Abbey*, now in ruins, charmingly placed on the borders of the Arros. It now belongs to a gentleman of Bordeaux, who has fitted up a portion of the building as a dwelling. The chapel remains, with some fragments of Gothic sculpture. A little beyond it the ruins of the *Castle Mauvezin* (i. e. Mauvais Voisin, a name given by the inhabitants of the neighbouring towns, who suffered from the depredations of the bands of marauders sheltered in this stronghold) crown a detached hill. It witnessed many exploits during the occupation of this country by the English. It was besieged 1374 by the Duc d'Anjou, with an army of 8,000 men; and the strength of the castle was so great that it would have held out for a very long time, but the well which supplied it being without the walls, the besiegers cut off the communication, and as the weather was hot and the cisterns dry, not a drop of rain having fallen for six weeks, the garrison were obliged to come to terms. The Duc d'Anjou allowed them to depart, saying, "Get about your business, each of you to your own countries, without entering any fort that holds out against us; for if you do so, and I get hold of you,

I will deliver you up to Jocelin (his headsman), who will shave you without a razor." He also allowed them to carry off as much of their booty as they could convey in trunks on sumpter horses.—*See Froissart.*

Capbern, a little farther on the road, is a small village, on one side of which,  $\frac{1}{2}$  m. off, in a retired nook, are the Sulphureous Springs of *Capbern*, having a bathing establishment, 3 hotels, and several lodging-houses attached to it. It is a place of increasing resort, owing to the virtue of its waters.

14 Lannemezan (*Inn* not good): on quitting this small bourg, a road branches off, S., into the Val d'Aure, to Arreau (R. 86). There is a short cut for the pedestrian, or equestrian, to St. Bertrand, by La Barthe, where is a good little country inn, opposite the ancient square tower, at the E. end of the village.

16 Montrejeau (*Inn* tolerable), a town of 3,034 inhab., in front of the opening of the Vale of the Garonne, whose vista is terminated by the grand peaks and ridges attached to the Monts Maudits, ranking among the highest of the Pyrenees; at whose foot, on the S., rises the Ebro, and on the N., the Garonne. It is a truly magnificent view. The stream of the Neste d'Aure falls into the Garonne a little above this. Here the road to Toulouse (R. 91) turns off to the l.; and that to Luchon, crossing the Garonne, begins to ascend its valley. On its rt. bank lies the ancient and curious walled town of

St. Bertrand de Comminges (Lugdunum Convenarum), situated at the opening of the Val de Barousse, upon and around a solitary rock, rising picturesquely out of the plain. Its summit is crowned by a Gothic church, the finest among the Pyrenees, in the Pointed style, whose choir and organ are ornamented with wood carvings, of very remarkable excellence, executed apparently in the 16th or 17th centuries. The painted glass, and a monument of a

bishop (date 1351) in white marble, deserve notice. Upon the walls are a series of rude and ancient (? fresco) paintings of the Miracles of St. Bertrand; and some relics of the Saint are preserved in the sacristy. Here is hung up the skin of a crocodile, which is said to have infested the neighbourhood, and to have been destroyed by the saint! In a fragment of the cloisters, which have only recently been pulled down, are some curious old tombs. This church was once a *cathedral*, and the town itself, now deserted (847 inhab.), was the capital of a comté, and a bishop's see. Many of the houses belonged to the canons and chapter. The inn is in the upper town.

The *Grotto* of Gargas, 5 m. S. of Montrejeau, in the wooded hill extending between the Garonne and Neste, is the finest in the Pyrenees, for extent, and the beauty of its stalactites: the entrance is a hole so small that it is necessary to crawl through on one's hands and knees.

The high road, leaving St. Bertrand on one side, again crosses the Garonne, by the Pont de Labroquère, and pursues its l. bank, through scenery of great interest, in which well-cultivated fields, enclosed by festoons of vines, hanging from tree to tree, form the foreground, and grand mountains the distance, by

16 Estenos—to Cierp, where we quit the Garonne, and enter the Vale of the Pique, which becomes its affluent at Cierp, a picturesque village both on account of its antique cottages, and from its position, under cliffs which nearly overhang it, at a point where the vistas of 2 valleys meeting, disclose noble views. There are quarries of a beautiful marble near this.

A road runs from Cierp up the Valley of the Garonne (Vallée d'Aran), one of the most beautiful in the Pyrenees, to St. Béal, the last town of France, situated in a narrow gorge between high mountains. (See p. 337.)



St. Béat is not more than 5 m. from the Spanish frontier.

The Valley of the Pique, which is very picturesquely varied with wood, rock, human habitations, and cultivated fields, presents a succession of savage contractions, and smiling basin-shaped expansions, covered with verdure, the river alternately winding over the plain, and dashing through the gorge; its upper end terminated by the grand, snowy peaks contiguous to the Port de Venasque. The road, which now makes several awkward ascents and steep descents, is about to be carried on a regular terrace. When the iron furnaces of Guron are passed, we traverse, near Pont de Casaux, the defile, before the geological rupture of which, the basin of Luchon must, doubtless, have been a vast lake.

21 *Bagnères de Luchon.*—*Inns:* H. de Londres, one of the best inns in the Pyrenees—*H. N.*; a café and reading room attached; H. du Commerce; H. de France. The accommodation and cuisine at the inns are inferior to that afforded at Bagnères de Bigorre. Strangers about to stop some days here had better hire lodgings, of which there are enough to accommodate from 1,500 to 2,000 persons.

The situation of Bagnères de Luchon is somewhat like that of Bigorre, except that the mountains are loftier, and entirely surround the flat, fertile plain on the edge of which it stands, forming a sort of oval basin in the very heart of the Pyrenees. On the W., close to the town, the Val de l'Arboust (R. 86) opens out; on the S., high among the clouds, rise bare, serrated ridges, destitute of vegetation, but contrasting grandly with the luxuriantly cropped plain near at hand.

Luchon is a town of 2000 inhab., of narrow streets and mean houses, less neat and civilised than B. de Bigorre, with one exception,—the *Allée des Bains*, a triple avenue of limes, lined with buildings, including the

chief inns and best lodging-houses. Another avenue stretches up the hill to the entrance of the Val de l'Arboust; and a third, of poplars, crosses the valley, from the church, towards the river Pique. These Allées enable the pedestrian to move to a considerable distance under shade, protected from the sun, and enjoying the view of the mountains which close the upper end of the valley. This range of peaks and precipices, among which the Pic de la Pique is conspicuous, screens from view the Maladetta, the Monarch of the Pyrenees. In the middle distance rises the tower of Castel Vieilh, which stops the mouth of the gorge to the S.

At the end of the Great Allée are the *Baths*,—a group of buildings, neither handsome outside, nor convenient within. The chief of them was burned 1841, and it is to be hoped may be replaced by a better. They stand at the foot of a precipitous wooded hill of slate, called Super Bagnères: the waters issue forth at the junction of the slate with the granite; they are sulphureous (except two, one saline, the other ferruginous?), and vary in temperature from 77° to 152° Fahrenheit. The accommodation for bathing is more extensive, there being about 80 baths, but not more comfortable than at other French watering places, for the cabinets are small, dark, and do not look cleanly. The waters are good for rheumatic complaints, paralysis, and cutaneous disorders, but are injurious in nervous diseases, and to persons of sanguine temperament. They are taken internally as well as in baths.

By driving horizontal galleries into the rock of the mountain behind, near the old sources, an experiment which was 2 years in progress, hotter water, and a more copious supply, has recently been obtained, but some of the old springs are dried up in consequence.

The Romans were well acquainted with the hot springs of Luchon; many altars and inscriptions, now in the

museum of Toulouse, have been dug up here, some of them dedicated *Deo Lixoni*, from whom the place would appear to be named.

Protestant service is performed in the *Mairie*.

Zigzag paths run up the hill behind the baths, through the wood, and along the face of the hill; but they are too steep for invalids, and too filthy for anybody English.

The chief *season* of these baths is from July to the middle of September, but many come before and others linger after that period.

About 200 *horses* and ponies are kept here for hire, at the usual charges, and are in constant request in fine weather. *Guides* are proportionably numerous; among them Laffont, called Prince, is hardy, experienced, and trustworthy, and has very good horses; he knows every step of the country around, and every mountain peak.

*Diligences*—daily, 3 to Toulouse; 1 to Auch; 1 or 2 to Bagnères de Bigorre.

The inhabitants of the valley of Luchon and its tributaries appear an inferior race to those of the valleys in the W.; not so well off, nor so well clothed. In their dress, the berret gives place to an ugly night-cap, and the capulet, if retained, is black, instead of red. Beggars are very numerous, and goîtres not uncommon; yet the lower parts of the valleys are fertile, producing two crops of corn in the year; the first, of wheat or maize, the second, late in September, when the fields are literally white, for the harvest of buck-wheat. Many goats are kept, which find sufficient food in the luxuriant herbage of the rocks; and the tinkling bells of the scampering flock, as they enter the town at sunset, produce a merry sound.

The *Cascade of Montauban*, on the E. side of the valley, is a very romantic spot, and, though the fall is inconsiderable, forms an agreeable walk. It is approached through a

garden made by the curé of the village, who devotes to his parish the douceurs left by visitors.

The *Excursions* to be made from B. de Luchon are superior to those from B. de Bigorre, and are indeed the finest in the Pyrenees. That to the beautiful Lac de Seculéjo or Lac d'Oo will be found in R. 86, p. 324; 4 hours are required to go thither, and 3 to return. No one should quit Luchon without seeing the

*Val d'Aran* (p. 337). An excursion of 1 day, on horseback, may be made thus: over the Port de Portillon to Bosost  $2\frac{1}{2}$  to 3 h., bad road—to St. Béat 3 h.—rest the horses.—St. Béat to Luchon  $2\frac{1}{2}$  to 3 h. It may be lengthened to 2 days by ascending the valley from Bosost to the Hermitage of Artigues Tellina  $2\frac{1}{2}$  h.: while the horses are baiting go and see the Œil de Garonne. From the Hermitage to Viella 3 h. by a path in the wood, difficult to find without a guide. You cross the stream by a bridge about 1 m. below the Hermitage, and enter the wood, from which you do not emerge until in sight of Viella: sleep there (see p. 337). This excursion may be combined with that to the Port de Venasque. (See below.)

A ride of 2 hours or a walk of 3, the distance being 7 or 8 miles, is to the *Val de Lys*, so called, not from its lilies, but from an old or provincial form of the word *eau*, water, from the number of streams and waterfalls. The road to it ascends the valley from the baths, having the Pique at some distance on the l. It passes, also on the l., the picturesque border tower of *Castel Vieilh*, perched on a projecting crag, before the mouth of the Gorge de St. Mamet, watered by the Bourbe, leading, by the pass of the Portillon, into the Spanish Val d'Aran (p. 337). This tower was designed to defend the entrance into the Val de Luchon by the ports of Portillon and of Venasque. Soon after passing it, the road crosses the Pique to its rt. bank,



and  $\frac{1}{2}$  a mile farther, leaving on the l. the road to Venasque (p. 333), it recrosses the Pique, to enter the fine wooded gorge out of which the Lys issues to unite with it. After a mile and a half's pleasant ride through the wood, under the shade of beech and hazels, the gorge expands into a green basin-shaped valley, of a truly pastoral character; the pastures covered with herds occupying its bottom being overlooked by very lofty mountains, girt with fir woods, especially at its upper end. It is there shut in by the snowy peaks and glaciers of the Crabioules, rising above the fir-clad precipices, which look like a festooned curtain of black drapery drawn across the valley head. The centre of this curtain of foliage is streaked by the white lines of the foaming cascades which form the lions of this valley. The principal one leaps down into the valley, about 200 yards above the little *cabin*, half *châlet*, half *pot-house*, where visitors put up their horses, and may obtain some common refreshments. The slate rock is cleft by a very narrow fissure or groove, called *Trou d'Enfer*, down which the fall, really a picturesque one, dashes. The other fall, on the l., called *Cascade de Cœur*, is less striking in character and less accessible; it is fed by the glaciers of the Tuque de Maupas. The glacier of Crabioules, which feeds the other, is very difficult of access, owing to its steep inclination and its crevices. It joins, on the W., the glacier of the Portillon d'Oo and the Port d'Oo. The pedestrian should go to the Val de Lys or return from it by the hill of Super Bagnères, the height behind Luchon, whence he will enjoy a magnificent view.

None of the excursions from Luchon, nor indeed in the whole range of the Pyrénées, surpass that to the *Port de Venasque*. It is somewhat difficult, yet is achieved by ladies in *chaises à porteur*. The expense for taking up one lady is 60 francs. It is practicable on horseback, and no one should

omit it who has strength and love of fine scenery. It may be accomplished in 9 hrs., allowing  $1\frac{1}{2}$  hr. halt at the Port. A guide is necessary. The road is the same as that just described as far as the 2nd bridge over the Pique above Castel Vieilh. Leaving the opening of the Val de Lys on the rt., without crossing this bridge, you continue up the valley of the Pique, through park-like scenery, under the grateful shade of beech forests interspersed with firs and yews, between whose branches appear the rugged crags of the Pic de la Pique on the opposite side of the torrent. The ascent is gradual up to the Hospice de Bagnères ( $1\frac{1}{2}$  hr. ride), the last habitation in France, where the horses are commonly allowed half-an-hour's rest to prepare them for the fatigue in store for them. It is a large, massive, dirty stone house, like a Refuge on a Swiss mountain pass, belonging to the Commune of Luchon, intrusted to an innkeeper who resides here till the 20th December, and on his departure leaves behind a store of bread and wine, wood and straw, for the entertainment of wayfarers, who cross the pass even in the depth of winter. No one avails himself of this provision without leaving behind money in payment for it. The house is on a par with a common cabaret, affording only the commonest necessities, and appears a miserable hovel to those who need neither food nor shelter. It stands in a grassy hollow at the foot of high hills, some way below the head of the valley where the Pique takes its rise at the foot of the mountain called La Picade, over whose shoulder lies the pass of the Port de Picade. The path to it scales the hill behind the house, and it is a good 2 hrs. ascent, chiefly over grass, to reach the Port.

Opposite the house, at rt. angles to the vale of the Pique, a colossal semicircular recess, or natural cirque cut out of the mountains, which surround it with bare precipices, opens out; it is a scene of dreary solitude,

disturbed only by the hoarse raven or the howling blast. It is approached by a little wooden bridge crossing the Pique in front of the hospice, under the singular Pic de Picade, rising on the l. hand.

Within 100 ft. from the top of this obelisk of rock a very remarkable gallery was discovered 1843, bored into the mountain for about 300 ft., supposed to have been made by the Romans in search of lead, which still abounds. The spot is accessible only with great difficulty: a profitable lead mine has been opened near the base of the peak.

“We were all puzzled, as our horses’ heads were turned towards the glen, and we commenced the ascent, to tell by what magic men on foot, much more laden beasts, were to pass up and over this wall in any part of its circumference. Up, however, we went, toiling for 2 hrs. incessantly along a slightly traced path, always winding in zigzags, over large stones or rough beds of débris fallen from the mountains, alternating with smooth solid rock. Our little jaded horses did the work wonderfully well, taking to the steep staircase road most willingly, and clambering among the cliffs like kids, never making a false step. As we mounted higher, however, ‘the rushing mighty wind,’ which sweeps down the gully with a hideous howl and a force perfectly tremendous, rendered it very difficult to keep one’s seat. There is a proverb, that in ascending the Port de Venasque, ‘a father will not look back at his son, nor a son wait for his father.’ About 3-4ths of the way up is a small ledge or recess in the face of the mountain, in which lie 4 small, deep-sunken tarns or ponds, frozen over a great part of the year. The steepness of the mountain and the shortness of the zigzags constantly increase till, near the top, the angle of the slope is so highly inclined that the path turns abruptly at every 6 or 8 ft.; and as the ground is covered with loose splintery shale, the horses have

no secure footing. The rocks in front hide all view until the moment when you enter the *Port*, a wedge-shaped fissure cut into the crest of the mountain;—a mere gate, not more than 6 ft. wide. On passing this doorway, you step from France at once into Spain. To tarry in the singular portal or port-hole was impossible on account of the wind, which threatened to blow us back again more quickly than we had entered; so we descended a few steps, driving our horses before us, and seated ourselves on the smooth slate rock, which here dips downward as abruptly as the roof of a house. But what a scene opened before us—not a glimpse of which had been perceived before! We beheld an enormous mountain, the highest of the Pyrenees, called the *Maladetta*, or *Accursed*—I suppose from the utterly barren and dreary air of it and every thing about it. Its huge round top and ridges are covered with everlasting snow, except where one or two bristling black peaks break through it; its lower part is shrouded with scanty fir-trees: a great gulf or deep ravine separates it from the bare slope on which we stood; not a sign of human habitation or cultivation; all around a desert, as though a corner of the world forgotten and left unfinished.”  
—*MS. Journal*.\*

\* In Blackwood’s Magazine, No. CLXV., will be found a most vivid and true description of the Port de Venasque. The final ascent is thus related by its observant author:—

“Our position became at every step more interesting and extraordinary; for to all powers of observation this cul-de-sac was so perfect, and all means of exit so inscrutable, that not one of the party, after the most mature inspection, could form a conjecture as to the continuation even of the very pathway, much less of the pass itself, which appeared to elude our grasp as we drew near, and yet must, if it really existed, be now close at hand. At length, on . . . a sharp corner, the pass started in view, about 50 ft. above our head. . . . The poor animals, as if conscious that the severest portion of their task was drawing to a close, exerted themselves with redoubled efforts to accomplish the remaining—I may say—steps in the ladder. . . .



This road has lately been improved, so that not only ladies, but even the fat and infirm may easily surmount it in a chaise à porteurs, or even on horseback.

The pass called *Port de Venasque* (reached in 2 hrs. from the Hospice of Bagnères) is cut through the mountain wall called Penna Blanca, at an elevation of 7,917 ft. above the sea level, but at a considerable depth below the crest of that mountain. The frontier line, near its top, is marked by an iron cross. In the depths of the hollow below the Port, within the Spanish territory, the Essera takes its rise, and a low ridge stretching across at its head unites the Maladetta with the main chain and the mountains of the Port de Venasque. To the E. of this ridge, on the l., lies the mysterious *Trou du Taureau*, an oval basin or gulf without visible outlet, excavated in the limestone rock to a depth of 80 ft., which, swallowing up the waters descending from the N. E. slope of the Maladetta, is believed to convey them *under* the intervening mountains into the French Valley of Artigues Tellina, where, rising again to light, they form the

*Source of the Garonne.* This phenomenon merits the personal investigation of travellers.

The *Maladetta*, erroneously included in some maps in the central chain, and even placed within the French frontier, is an outlier or buttress, lying to the S. of the dorsal spine of the Pyrenees, and entirely shut out by it from France, as it were by a screen of peaks and ridges. Though the highest of the Pyrenees, 11,426 ft. above the sea level, it loses much of the effect of elevation when seen from the Port

de Venasque, on account of the great height of the Val d'Essera, out of which it rises. The highest of its summits, the Pic de Nethou, had never been reached until 1842, when it was surmounted by a Russian officer named Tchitchacheff, with one French companion and 3 guides. The glacier upon its N. flank is the largest in the Pyrenees, and is dangerous to cross on account of the crevasses. In 1824 a guide, named Barran, perished miserably in one of them, owing to the covering of snow giving way beneath him, before the eyes of two French gentlemen, pupils of the École des Mines, who heard his agonising cries as he gradually sunk down, without being able to render any assistance. The crags and snows of the Maladetta are the favourite haunt of the izard; and many a bold chasseur dares all the perils of the mountain in pursuit of them.

The *Spanish town of Venasque* is about as far from the Port to the S. W. as Luchon is to the N., i. e., a walk of 4 hours; but the way is very rough and difficult, following at first the windings of the Essera, wading the torrents which fall into it, and threading the mass of rocks and rubbish fallen from the gigantic wall of Penna Blanca on the rt.: no danger, however. The scenery far more magnificent than on the French side. Some way down is the Spanish Hospice, "a vile posada," serving as a guard and custom-house, occupied by carabineers, and supplying the place of a hospice swept away by an avalanche in 1838, which resembled that on the French side of the pass. From this to Venasque, about 10 m., the path runs by the side of the Essera, and is very difficult. The scenery of the gorge is grand but savage, its striking feature being the number of its waterfalls, and rapidity of the torrents descending into it. A bath has been built on the opposite slope of the valley.

The path from the Port d'Oo

"Another man brought me to the breach, when I drew and in motionless and speechless I sat with my eyes riveted on the stupendous scene so singularly, so suddenly revealed. . . The Maladetta was immediately in front, without a single intervening object, standing in all its dreary nakedness, like the ghost of some mountain belonging to a departed world."—S.

(see p. 324) descends [the Val d'As-tos. The sides of the mountains are stripped of wood near

*Venasque*, which is suddenly disclosed to view by a bend in the valley. Its most conspicuous feature is the picturesque *Castle* by which it is surmounted, originally a stronghold of the middle ages, converted by modern works into a fortress, which was besieged and taken by the French in 1809, and possesses no great strength. It is surrounded on three sides by deep ravines.

In the principal street, *Calle Mayor*, are several picturesque old houses ornamented with sculptured figures, coats of arms, &c., and some of these retain the towers which originally served for defence. The *Church*, at the end of the town farthest from the castle, is a curious Romanesque building, fitted up in the Spanish style, with carving, gilding, &c. Another church was destroyed by the French, who did much mischief here. "The *Inns* are ventas of the most miserable class, unfit to shelter an English dog. Strangers are received, as a great favour and at a high price, in 2 houses belonging to rich, proud Arragoneses. It is necessary to make a bargain before you discharge an article of baggage, and  $\frac{1}{2}$  an hour is spent in haggling. They demand 10 frs. for a miserable supper, bed, and small cup of chocolate in the morning. You may get off with 7 frs."—*G. M. S.*

You may return from *Venasque* to the Spanish Hospice and over the *Pommereau* into the gorge of *Artigues Tellina*, visiting on the way the *Œil de Garonne*; sleep at *Viella*, and reach *Luchon* by *St. Béat* the 3rd night.

The excursion may be prolonged round the base of the *Maladetta*, from *Venasque*, through wild and magnificent scenery, by the *Port de Castanéze*, 3 hours; village of *C.*, 4 hours; *Vitalles*,  $2\frac{1}{2}$  hours; *Hospice de Viella*, 4 hours, situated amidst stupendous scenery, superior to any

on the French side of the Pyrenees; *Port de Viella*,  $11\frac{1}{2}$  hours, 8322 ft. above the sea, and very grand; town of *Viella*,  $2\frac{1}{2}$  hours, in the *Val d'Aran*.

*Venasque to Luchon*—

a. by the *Port de Picade*.

b. by the *Port de Pommereau*.

The ridge of the *Penna Blanca*, through which the *Port de Venasque* opens, is traversed about  $1\frac{1}{2}$  m. to the E. of it by another pass, called *Port de Picade*, reached by turning to the l., traversing the meadows at the base of the mountains, whence the *Port de Venasque* looks as though it had been formed by chipping a bit out of the *Sierra*, and then scaling a steep ascent encumbered with rubbish, and not marked by any path. On the top you pass out of *Arragon* into a corner of *Catalonia*, and look down upon a chaos of wild peaks and ridges. Here you have the choice of two passes, the shortest the *Picade*; on the l. is a very narrow path carried along the shattered edges of the slaty stone, barely traced among shivers and splinters of rock upon the very ridge or crest of the *Sierra*, along the brink of the precipice. It is a grand wild spot, and is named *Picade* from the gigantic obelisk of rock which rears itself aloft. It leads back to the *Hospice de Bagnères* by a path marked with tolerable distinctness on the grassy slopes, and, though steep, much easier than that up to the *Port de Venasque*. Thus the traveller has passed from France into Spain through one door or gap in the great separation-wall between them, and returned through another.

b. The pass on the rt. hand, after reaching the crest of the *Port de Picade*, is called *Port de Pommereau*, and leads into the vale of the *Garonne*, the upper part of which is called the *Val d'Aran*, and though lying on the French side of the Pyrenees, belongs to Spain. The descent runs through the grand gorge of *Artigues Tellina*, covered, as you proceed down it, with dense



intact forests of primæval growth, in the midst of which, in a deep hollow at the foot of precipices, 10 minutes distant from the path, one of the chief *sources of the Garonne* issues forth from a series of cavities encumbered with broken rocks called *Œil de Djoueou*, and by the Spaniards *Ojos de Garonna*, “the Garonne’s eye.” It is said that the copious stream which here bursts forth to day is the torrent whose cradle is the snows of the *Maladetta*, and which, after being lost in the *Trou de Taureau* (p. 335), pursues its way under ground, through the caverns of the limestone mountains, as far as this spot, where it rises a ready-made river. This is one of the most important sources of the Garonne. A little farther down lies the Hospice of *Artigues Tellina*. The part of the valley below this is covered with pastures. Much timber is cut in the forests, and floated down the Garonne to Bordeaux. Near the junction of the valley of *Artigues Tellina* with that of the main stream of the Garonne of *Viella*, the river is crossed by a bridge near the ruined *Castel Leon*, destroyed by the French in the war of the Succession. The *Val d'Aran* contains 32 towns and villages, 69 churches, and 20,000 inhab.; it runs up towards the great chain, 14 m. above *Castel Leon*; 5 m. up it lies *Viella*, the chief place of the valley, containing 900 inhab., 8 m. below the *Port de Viella*. Below *Castel Leon*, at *Las Bordas*, the path to *Luchon* by the *Portillon* and the *Val Burbe* (p. 332) stretches off to the W. Good sleeping quarters may be found in a farm-house at *Viella*, 2½ hours. Lower down is *Bosost*, the second place in the valley, a miserable village, but in a charming situation. On the outskirts of the village of *Les* are *Baths* supplied by sulphureous springs, and a boarding-house or *Inn*, belonging to the proprietor, affords the best accommodation in the valley. Below this a *France*.

fine view is obtained of the *Maladetta*. Here the *Val d'Aran* puts on its greatest beauty and grandeur, which cause it to rank high among the Pyrenean valleys. The river is jammed in between the rocks near a bridge over a tributary stream, called *Pont du Roi*, which marks the frontier of France; it is the custom-house post, &c. The *Val d'Aran* belonged to France down to 1192, when it was transferred as the dowry of *Beatrix de Comminges* to her husband, a prince of Aragon. It was ravaged by the Carlists in the late war. *Fos* is the first place within the French territory. The valley contracts lower down to a grand defile, in the midst of which lies *St. Béat* (3 hours below *Bosost*), a very picturesque and interesting old town, consisting of a narrow street overhung by beetling cliffs; a ruined castle stands on a rock in the midst of the defile. The scenery around is most lovely. The *Inn* (*Fortan's*) is not good, but it is one of the best in the valley. There is an excellent carriage road from this to *Cierp* and *Luchon*.

There are quarries of marble here.

At *Cierp*, 6 m. below *St. Béat*, the Garonne is joined by the *Pique* coming from *Luchon*, and our road falls into the high road from *Bigorre* and *Toulouse* (p. 330), leading thither.

\*.\* More detailed and accurate information respecting the *Val d'Aran*, the scenery S. of the *Maladetta*, and *Venasque*, would be acceptable to the Editor.

## ROUTE 90.

TOULOUSE TO PAU, BY AUCH AND  
TARBES.

188 kilom. = 116 Eng. m.

*Malleposte*, daily in 15 hours.

*Diligence*, daily.

*Toulouse* is in R. 70.

At the radiation of roads outside the *Faubourg St. Cyprien*, called *Patte d'Oie*, the branch on the rt. is

that which leads to Auch; it crosses, at the distance of 2 m., the stream of the Touch.

18 Leguevin.

15 L'île Jourdain (H. de France), a town of 2000 inhab., on the rt. bank of the Save.

18 Gimont.

9 Aubiet. The road runs through a highly cultivated and very productive country, in a direction nearly due W., not inclining in the least to S., all the way from Toulouse to

17 *Auch* (Inns: H. de France; best, and very good—*E. o. S.*), the chef-lieu of the Dépt. du Gers, a town of 10,461 inhab., and see of an archbishop, is situated on the top and slopes of an eminence washed by the Gers at its base, and crowned by the *Cathedral*, begun in the reign of Charles VIII., and completed, by the tasteless addition of its inappropriate Grecian portico, in that of Louis XIV. The church is 347 ft. long, and 74 ft. high. The *painted glass* is of rare richness of colour, but is coarse in design; it was executed (1513) by Arnaud de Moles. The *carved woodwork* of the choir is equally remarkable, and is scarcely surpassed in France. At the back of the stalls are well-executed figures of Virtues, &c. in bas-relief, enclosed in niches and canopies of elaborate workmanship (date 1525-7). The choir is separated from the nave by a gallery (jubé), or rood-loft.

Long flights of stairs lead from the lower town to the upper; many old houses are preserved here. The *Place Royale*, in the higher and better quarter of the town, is a handsome square; adjoining it is the *Cours d'Etigny*, so named from a magistrate by whom it was laid out, commanding a glorious *view* of the chain of the Pyrenees.

Auch was anciently capital of the *Ausci* (whence Auch), afterwards of the Comté d'Armagnac, and seat of the primate of Aquitaine.

A *malleposte* runs hence daily by Agen to Limoges (R. 73, 70).

15 Vicnau, Dépt. Gers.

9 Mirande. Inns: H. Dupuy; very comfortable; there is a large establishment of baths attached to it; *L. Y.*—Soleil; good.

13 Miélan. Soon after crossing the Arros we descend a slope, commanding the view of the Pyrenees, among which the Pic du Midi de Bigorre, rising directly in front, is grandly conspicuous, into the plain of the Adour, which stretches hence to the foot of those mountains, and enter

16 Rabastens, an old town mentioned by Froissart. A perfectly straight road connects this place with

19 *Tarbes*, in R. 87.

23 Bordes d'Expouy.

16 PAU (R. 80, p. 291). There is a second and more direct road from Toulouse to Tarbes, which, though unprovided with post horses, is taken by the *diligence* daily, in 22 hours, passing through Lombez, Boulogne, and Trie.

## ROUTE 91.

TOULOUSE TO BAGNÈRES DE LUCHON  
AND BAGNÈRES DE BIGORRE, BY ST.  
GAUDENS.

To B. de Bigorre, 144 kilom. = 80 Eng. m.; to B. de Luchon, 135 kilom. = 84 Eng. m.

*Diligences* daily.

The first part of the road, across the great plain of Languedoc, and along the l. bank of the Garonne, though seldom in sight of the river, is very monotonous. The Pyrenees are yet too distant to form an important feature, but the richness of the soil and abundance of the crops are very remarkable. The Duke of Wellington attempted the passage of the Garonne at Portet, a village on the l. of the high road, 6 m. above Toulouse, but the width of the river proved too great for the pontoons provided, and the army consequently crossed lower down, below Toulouse. The confluence of the Arriège with the Garonne takes place opposite Portet.



20 Muret.

The army of the Comte de Toulouse, aided by Pedro II., king of Arragon, amounting to 40,000 men, was defeated under the walls of Muret by Simon de Montfort, who made a sortie with 14,000 men, and cut the besiegers to pieces, leaving Pedro dead on the field.

13 Noè, on the l. bank of the Garonne. At Carbonne, above this, some way to the l. of the road, Lord Hill crossed the Garonne with 18,000 men; but finding the roads impassable, speedily returned to march along the l. bank, against St. Cyprien, the faubourg of Toulouse.

27 Martres. In a field near this, interesting Roman antiquities have been discovered, consisting of an immense number of busts, statues, reliefs, inscriptions, &c., now deposited in the museum of Toulouse, marking this as the site of the ancient town *Calagorris Convenarum*.

There is a bridge over the Garonne at St. Martory. A new road has been made to skirt the town, and avoid the narrow streets of

28 St. Gaudens (*Inn*: H. de France; good), an old and gloomy town of 6020 inhab., at a little distance from the Garonne, has a church of considerable antiquity, in the Romanesque style, with 3 apses at the E. end, and small round-headed windows. The road to Bagnères de Bigorre diverges on the rt at St. Gaudens, up the l. bank of the Garonne to Montrejeau, where it falls into R. 87.

From St. Gaudens, by St. Girons, to Foix and Carcassonne is R. 95.

The Garonne is crossed by the road to Luchon, a short way out of the town; and from the slope leading down to it there is a fine view of its windings and of the distant Pyrenees.

At the distance of 6 or 8 m. farther the road passes abruptly from the plain into the midst of the mountains, by ascending an eminence, the extreme root or spur of the Pyrenees, to avoid a wide curve of the Garonne,

but descends upon the river at the foot of the opposite slope. An uncommon view is here presented of the interesting town of St. Bertrand (R. 87), which our road leaves on the rt. "You break at once upon a vale, sunk deep enough beneath the point of view to command every hedge and tree, with St. Bertrand clustered round its large cathedral on a rising ground. If it had been built purposely to add a feature to a singular prospect, it could not have been better placed. The mountains rise proudly around, and give their rough frame to this exquisite little picture." —*A. Young*. The Garonne is crossed at the Pont Labrèquere to

27 Estenos, described, with the rest of the road, to

21 Bagnères de Luchon, in R. 87.

#### ROUTE 93.

TOULOUSE TO MARSEILLES, BY CARCASSONNE AND NARBONNE.—CANAL DU MIDI.

420 kilom. = 260 Eng. m.

*Malleposte* daily, in 27 hours.

*Diligences* daily. With post horses in 9 hours to Carcassonne.

*Bateaux de Poste* daily, along the Canal du Midi from Toulouse to Agde: a very tedious conveyance (35 hours), to which, for the most part, the lower classes only resort: the boats very uncomfortable, no restaurant, the delays from locks excessive: boats are changed at Beziers.

The road, on quitting Toulouse, passes on the l. the hill of Pech David—a good point of view to see the Pyrenees from; and skirting, at a short distance on the l., the *Canal du Midi*, continues to run nearly parallel with it for several stages. This great and useful public work, sometimes called Canal des Deux Mers, because it unites the Mediterranean with the Atlantic, was executed under Louis XIV., by the enterprising Paul Riquet, though the design is clearly sketched out in the

Mémoires de Sully. It was commenced 1666 (100 years save 6 before Brindley, in England, began the Bridgewater Canal), and finished 1681, the year after Riquet's death. It measures, from the basin where it joins the Garonne at Toulouse, to the Etang du Thau, near Agde, where it falls into the Mediterranean, 244 kilom. = 151 Eng. m.; it is 20 mètr. (65 ft. 7 in.) wide at the surface, and 10 mètr. (32 ft.) at the bottom. It cost more than 16 million livres = 33 million fr.

It has 64 locks, and many other considerable works, reservoirs, &c., which will be enumerated as we approach them. These, though wonderful for the time when they were constructed, have been surpassed by many in England, and even in France. The articles transported along the canal consist chiefly of corn, oil, soap, wine, brandy, &c.; it is navigated by barges of 100 tons, but the traffic is not very extensive, judging from the number of voyages yearly to and fro, which is only 960. It is closed for a month or 6 weeks once in 3 years for the "chômage" (still stand), in order to be cleaned.

Our road lies across a rich corn country, but monotonously flat, which before the end of summer becomes parched, dusty, and arid.

12 Castanet. The canal and the river Lers, running parallel with it, are crossed at

12 Baziège.

11 Villefranche, a town of 2,400 inhab., consisting of a long street traversed by the road.

Beyond Avignonet we pass from the Dépt. Haute Garonne into that of l'Aude, and a little farther skirt on the rt. the *Bassin de Naurouze*, an artificial reservoir formed for the supply of the canal, which here attains its summit level (point de partage). The water is derived from a still higher and larger reservoir, *le Bassin de St. Féréol*, measuring 5,249 ft. by 2,558 ft., situated on the flanks of the Montagne Noire, whence it is

conducted hither in an artificial channel to be discharged into the two seas. The descent of 208½ ft. between this and Toulouse is effected by 18 locks, and that of 719 ft., down to the level of the Mediterranean at Agde, by 46 locks. Riquet intended to have founded a town upon the basin of Naurouze—a design not yet accomplished; but an *obelisk*, by way of *monument*, was erected to him by his descendants, on this spot, 1825. A little island has been formed in the basin opposite the mouth of the Canal by the deposits brought down by it. After crossing this main feeder of the canal, there is nothing to notice until reaching

22 Castelnaudary (*Inns: La Flèche; Notre Dame*), a town of nearly 10,000 inhab., on an eminence, skirted at its base by the Canal du Midi, which here expands into a *bassin*, much larger than that at Naurouze, the only thing remarkable here. There are stone-quarries and lime-kilns near.

The name has been traced to "Castrum Novum Arianorum," the name given by the Visigoths to the town, which they refounded. It suffered severely in the crusade against the Albigenses, having been taken both by Simon de Montfort and the Comte de Toulouse: and in 1237 the inquisitors enacted an auto-da-fé here; in which, in their desire to root out heresy, they not only burnt many persons alive, but many dead bodies, dragged ignominiously from the grave for this purpose. The most memorable event in the annals of Castelnaudary is the *battle* fought here on the banks of the Fresquel, 1632, between the forces of Louis XIII. and of Gaston Duc d'Orléans, at which the unfortunate Duc de Montmorency was wounded and made prisoner, and soon after conveyed hence to Toulouse to be beheaded.

12 Villepinte. The rounded outline of the Black Mountain bounds the view on the N.

8 Alzonne, a town of 2,000 inhab.



16 *Carcassonne*.—*Inns*: H. Bonnet or Bonet, good;—St. Jean Baptiste, good and reasonable; on the airy Boulevard. This chef-lieu of the Dépt. de l'Aude, a city of 17,394 inhab., is traversed by the river Aude, and by the Canal du Midi, which, at first carried at a distance from its walls at the request of the inhabitants, has, in recent times, received at vast expense another direction, in order to bring it up to the town, where it now forms a large *bassin*.

Carcassonne itself is composed of two parts, the modern town on the plain and the old town on an eminence above it, forming a picturesque background with its venerable towers and commanding battlements. The lower and newer town, cheerful, flourishing, and industrious, consists chiefly of modern-built houses in streets, ranging at right angles with one another, surrounded by boulevards, occupying the site of its ramparts, including squares planted with trees and furnished with marble fountains, and running with freshening rivulets. It contains several large woollen factories, and not less than 7,000 persons of the town and its vicinity are employed in the *manufacture of cloth*, chiefly exported to the Levant, Barbary, and S. America, where it is esteemed for its brilliant dyes. From this and other sources of commercial prosperity it has increased, in the course of 4 or 5 centuries, from a suburb to be the town itself, while the original city on the height has dwindled down into an insignificant faubourg. Beyond this, however, it has no claim to detain the passing traveller. Its modern cathedral, and church of St. Vincent, whose tall tower stands on the line of the meridian of Paris, are not remarkable. The *avenue of trees* planted along the margin of the canal, and embellished with a column of the red marble of the country to the memory of Riquet, its founder, leads to the aqueduct bridge by which the canal has been carried over

the stream of the Fresnel in recent times.

The *old town*, on the height beyond the Aude, deserves the notice of all who take an interest in antiquities, as retaining unchanged, to a greater extent perhaps than any other in France, the aspect of a fortress of the middle ages. A traveller with such tastes must not be deterred from entering by odious smells, steep, narrow, dirty, and desolate streets, with the grass growing in many of them, and the houses falling to ruin, for it has been abandoned entirely to persons of the poorer class and to artisans, composing a population of paupers pent up within its narrow enclosure. It is enclosed by double *ramparts and towers*: a portion of the inner line is attributed to the Visigoths with much probability; and the rest, including the castle, with its curious postern, seems to be of the 11th or 12th century, while the outer circuit has been referred to the latter end of the 13th century. The former are therefore the same defences which withstood for a time the assault of the army of Crusaders under the fierce Simon de Montfort and the Abbot of Citeaux, who, reeking with the blood spilt at Beziers, laid siege to Carcassonne, where a vast number of fugitives, together with the Viscomte de Beziers, had taken refuge. At the intercession of the King of Aragon, his uncle, the papal legate promised to spare his life and those of 12 others with him; but the brave young warrior rejected these terms, declaring that he would sooner be flayed alive than betray one of those who had endangered themselves for his sake. Finding, however, that, owing to the number of men, women, and children who had poured in from the surrounding country, it was impossible to hold out, he managed to let them escape by a secret passage, and surrendered under a promise of safe conduct for himself. He was nevertheless seized treacherously, and soon after died in prison, while of

those who remained in the town 50 were hung and 400 burnt alive. In 1356 this fortress effectually resisted the Black Prince, who burnt the suburb below, and ravaged with fire and sword the whole of Languedoc. A curious sally-port, or *barbacane*, projects from the walls on the side nearest the modern town; and one of the towers has been split into two, but the one half, though fallen down, has not broken to pieces—such is the thickness and solidity of the masonry. The legend respecting it is, that Charlemagne, after in vain besieging for several years the town, which held out, though defended only by one Saracen woman named *Carcas*, was about to raise the siege in despair, when this tower gave way of its own accord, and opened a breach by which his army entered. The figure of this Saracen Amazon is still to be seen rudely carved over the *Porte Narbennaise*, on the E. side of the town.

The *Ch. of St. Nazaire*, formerly cathedral, in the middle of the old town, consists of a Romanesque *nave*, part of the church dedicated by Pope Urban II. in 1096, supported by massive piers round and square, and of a Gothic *choir* and transepts added at the beginning of the 13th century. In this part of the church are two fine circular windows, and some painted glass of great brilliancy of colour, though inferior in drawing. On one side of the high-altar a slab of red marble is said to mark the grave of Simon de Montfort, Earl of Leicester, that cruel and ambitious warrior, who, steelled in the holy wars, in the school of the Templars and Assassins, turned at the bidding of the Pope the sword whetted against the infidels upon the heretical Christians, the unfortunate Albigenses. In one of the side-chapels of the nave is a curious *bas-relief*, representing an assault of a besieged town, probably of the 13th century. This church has been restored.

Near the centre of the town is a

very wide and deep well, into which, according to tradition, the Visigoth kings threw their treasures.

Carcassonne was the birth-place of the Revolutionist *Fabre*, who called himself *d'Eglantine* because he had gained the prize of the golden sweet-briar in the floral games at Toulouse (see p. 253): he began his career as an actor, and ended it on the guillotine in 1793.

*Diligences* daily to Narbonne, Montpellier, Nismes, and Marseilles; to Perpignan by Limoux; to Toulouse.

At Caunes, 12 m. N.E. of Carcassonne, are the quarries of marble commonly used in churches and other public buildings in the S. of France. They are associated with slates of the transition series, and furnish 4 sorts: 1, flesh-coloured, much employed by Louis XIV. and XV.; 2, *marbre cervelas*; 3, grey marble containing *Enerinites*; 4, *Griotte*, including *nautili*. One variety is called "*œil de perdrix*."

On quitting Carcassonne, the road crosses and runs for some distance by the side of the Aude. The canal makes a bend to the N., its new channel being cut through deep excavations. The cultivation of the olive begins near this, though the tree can scarcely be said to flourish hereabouts.

14 Barbeira.

Near this, a little to the N. of the canal, is the drained lake of *Marseillette*, converted from a useless pool or morass into 2900 hectares of excellent arable land by the enterprise and capital of Madame Lawless, an Irish lady domiciled in France. The drainage was completed 1808, and the ground is now portioned out into 24 farms. The country between this and Narbonne is very dreary: large part of it white naked rock. Trees very scarce.

13 Moux.

15 Villedaigne.

13 Narbonne, in R. 126.



ROUTE 94.

NARBONNE TO PERPIGNAN, PORT VENDRES, AND THE SPANISH FRONTIER.

To Perpignan is 62 kilom. = 40 Eng. m. *Diligences* twice a day.

The road is very uninteresting, skirting on the rt. the low chains of the Corbières, consisting of bare rocks without trees or herbage; only a few bristly plants, and tufts of the heath which produces the Narbonne honey; and on the l., the salt lagoons, or shallow lakes, called Étangs de Bages, de Sigean, de la Palme, and de Leucate, which here line the shore of the Mediterranean, bordered with mud and sand. The district is unhealthy, owing to the miasma from this marshy tract. At intervals, when the road surmounts a slight eminence, a glimpse may be obtained of the open sea beyond the étangs.

21 Sigean, situated on the margin of the lagoon of the same name, was the scene of a victory gained by Charles Martel over the Saracens, 737.

The few trees near the road are all bent in one direction, to the S.E., by the violent winds from the N.W., which prevail here for 8 months out of the 12.

16 Fitou stands on the edge of the large étang, called de Leucate, from a half-deserted town on the tongue of land between it and the sea: a place of strength and importance during the period when Roussillon belonged to Spain, and Leucate stood on the frontier of France. The extremity of the chain of the Pyrenees, stretching into the sea, may be discerned near this.

10 Salces. The fort on the rt., before entering this village, was built by the emperor Charles V.; it is now a powder magazine.

The little town of Rivesaltes, famed for its wine, lies about  $1\frac{1}{2}$  m. on the rt., upon a small stream often dried up, the Agly, which is crossed by the road half way between Salces and Perpignan.

The two branches of the torrent-river Tet are crossed in order to reach Perpignan; between them stands the suburb Notre Dame; and on the rt. bank the lofty and singular castle of *Castellet*, a double tower of brick, surmounted by machicolations erected by Charles V., now a military prison.

15 PERPIGNAN. — *Inns*: H. des Ambassadeurs;—du Commerce;—de l'Europe;—Petit Paris, good;—du Midi.

Perpignan, chef-lieu of the Dépt. des Pyrénées Orientales, also a first-class fortress of great strength, defending the passage by the E. Pyrenees from Spain into France, is placed on the rt. bank of the Tet, about 6 m. above its termination in the sea, in the midst of the level plain of Roussillon, and contains 18,500 inhab., exclusive of its garrison. As Roussillon, of which province it was the capital, was not permanently united to France until the Treaty of the Pyrenees, in 1659, it is not surprising that both the town, in its narrow dirty streets covered with awnings, its semi-Moresque buildings, its houses furnished with wooden balconies and courts (patios), and its inhabitants, especially the lower orders, should resemble those of Catalonia, on the S. side of the Pyrenees, in their physiognomy, language, dress, dances. Those to whom Spain is unknown will be struck with this novel character; but beyond this there is not much to interest the stranger here. Almost all the public buildings date from the Spanish period, and are of brick or rolled pebbles. The *Cathedral*, begun 1324, and continued by Louis XI., during the time he held Roussillon in pawn from the king of Arragon, consists of a very broad and lofty nave. The altar screen, of beautiful carved work, partly wood, partly stone, in the style of the Renaissance, deserves notice; and the massy frame-work, gilding, tapestries, &c., which decorate this part of the church, are thoroughly Spanish

in style. The font, of marble, in the form of a tub, is very old; some attribute it to the time of the Visigoth kings. Adjoining this church are remains of a still older church, now in ruins, called *St. Jean le Vieux*. Of the church and *convent* of the Dominicans, now a military store, a portion, in the Romanesque style, belongs to the edifice which St. Dominic, the Inquisitor, inhabited when he entered Roussillon. The building called *La Loge*, from the Spanish Lonja, exchange or bazaar, is a curious example of the mixed Moresque and Gothic styles of the end of the 15th century. Its façade, exhibiting flamboyant ornaments, foliage and tracery, though much mutilated and injured by alterations, and the covered galleries round the court behind, merit notice. The ancient University contains the public library of 20,000 vols., and the commencement of a museum.

The *Citadel*, separated from the town by a wide glacis, and surrounded by a double line of works, is considered very strong, and commands the town. The inner ramparts were raised by Charles V., the outer by Vauban; and in the midst rises a tall square castle, or *Donjon*, built by the kings of Majorca, and the remains of a *church*, whose façade is remarkable, and is said to resemble that on Mount Sinai. The portal is a pointed arch, faced with slabs of marble, red and white alternately, resting on columns whose capitals represent fighting dragons. On one of the ramparts, an arm carved in stone (*dextrochère*), projecting from the parapet, was formerly pointed out as marking the spot where the emperor Charles V., going the rounds at night, found a sentinel fast asleep at his post, and, pushing him into the fosse, himself took the musket, and did duty until relieved by the guard. This has been recently destroyed. From the citadel a view may be obtained over the plain of Roussillon, extending 15 m. on all sides, save

that towards the sea not more than 6 m., and surrounded by a semicircle of mountains, the most elevated being the Pyrenees on the S., though they are still distant. The only mountain which makes a conspicuous figure is the *Canigou*, the highest of this portion of the chain.

Perpignan is more remarkable as a fortress than a place of commerce, but some trade is carried on in *wines* of Roussillon, also in cork, from the mountains.

For information regarding passports on entering France from Spain, see INTRODUCTION, *d*.

*Diligences* twice a day to Narbonne; daily to Toulouse, by Limoux; and to Barcelona in 2 days.

M. Arago, the mathematician and astronomer, is a native of Estagel, a poor village near Perpignan.

About 17½ m. S.E. of Perpignan is the sea-port of Port Vendres; the road to it passes

12 *St. Elne*, the ancient *Illiberis*, mentioned by Pliny as “*ingentis quondam urbis tenue vestigium*,” and by Livy as the place where Hannibal first encamped, after crossing the Pyrenees on his march to Rome, “*Pyrenæum transgreditur, et ad oppidum Illiberis castra locat*.” It was rebuilt by Constantine, who gave it the name of his mother Elena. It has a very ancient *Church of St. Eulalie*, once the cathedral, and episcopal see of Roussillon before Perpignan. It dates from 1019, and is in the Romanesque style, but with a pointed roof; it is quite plain internally, but the *cloister* adjoining is very richly ornamented with carvings, bas-reliefs, &c., and is worth notice. It is entered from the church by a pointed doorway resembling that in the citadel of Perpignan. Many inscriptions and bas-reliefs are let into the outer walls of the church; one of them is called the Tomb of Constans, who was assassinated at Elne by order of Maxentius. Elne is now reduced to a poor village. On quitting it the river Tech is crossed, and Argelez is passed.



Beyond this the E. extremity of the Pyrenean chain, dropping down into the sea, forms, by its projecting buttresses and roots, a number of headlands, and retreating coves or bays. On the shore of one of these lies

14 Collioure (Cauroliberis), defended by numerous forts, the whole commanded by the citadel of St. Elne, between this and Port Vendres. At the entrance of the harbour rises a little rocky island bearing a Church of Pilgrimage, dedicated to the Virgin. The town contains about 2000 inhab., and is surrounded by vineyards: the rocks, bare as they are, suffice to maintain the vine, and even the aloe, and produce some of the best wines in the department.

About 2 m. beyond Collioure is

3 *Port Vendres* (*Inn*: H. du Commerce), a town of 1305 inhab., and a harbour of some consequence, as it is the only port of refuge between Marseilles and the Spanish frontier, and is accessible for frigates. It is defended by 4 forts and 4 batteries, but is entirely commanded by the heights behind. It has gained of late in prosperity, from its increased communication with Africa, most of the troops destined for Algiers being embarked here. 3 or 4 *steamers*, plying between Marseilles, Barcelona, Gibraltar, and Cadiz, touch here every week. The marble *obelisk*, 100 ft. high, in the square, was raised to Louis XVI., who caused the harbour to be cleared, excavated, and made useful, 1780. The ancient name of this place was *Portus Veneris*, from a temple of Venus, built here by the Romans. There is a mule path hence into Spain, by the village and Col of Banyuls to Lanza, the first place in Catalonia.

The interesting road up the valley of the Tech, from Boulou, is described in R. 98.

The high road into Spain from Perpignan continues to cross the monotonous plain of Roussillon, but, as it gradually approaches the Py-

renees, commands a fine view of the Canigou on the rt.

22 Boulou lies at the foot of the mountains on the Tech, whose valley is described in R. 98. The stream is crossed as you quit Boulou, and about a mile farther the ascent begins, the road making considerable curves, up to the pass or *Col de Perthus*, which may be reached in 1½ hour. Half way, upon the l. of the road, is the ruined castle of L'Ecluse. At the summit on the rt. of the col, on a height above the little village of Perthus, stands the fort of Bellegarde, constructed by Louis XIV., in 1679, to command the passage into Spain. It is a regular pentagon with 5 bastions, in one of which, facing Spain, General Dugommier, killed in the battle of the Montagne Noire, on the road to Figueiras, 1794, is buried.

This pass was crossed by the conquering army of Pompey, who erected upon it a trophy of his successes, inscribed with the names of 876 places which he had subdued. Cæsar followed not long after, and raised an altar by the side of the monument of Pompey, over whose lieutenants he had, in turn, been victorious. No traces of either now remain.

Junquiera, the first Spanish town, 15 m. from Boulou, and the road to Barcelona, are described in the HANDBOOK FOR SPAIN.

## ROUTE 95.

ST. GAUDENS TO FOIX AND CARCASSONNE BY ST. GIRON.

“About 117 Eng. m.; road good, and very pretty, but hilly. St. Gaudens is in Rte. 91.

At St. Martory the road quits that to Toulouse, and crosses the Garonne by a picturesque stone bridge. The fine old *Evêché* of St. Elize, perched on a steep rock, now a lunatic asylum, is passed about 1 m. before reaching

47 St. Giron (*Inns*: H. de Biron;—H. de France, not good), a town situated close to the junction of

the Salut with the Gau. Good road, but against the collar, to La Bastide. A new, well-made road, avoiding hills, to

Foix, in Route 97. Road hilly, but good, to

26 Lavelanet (H. chez Elanet).

Good road, chiefly descent, to

23 Chalabre (*Inn*: H. d'Espagne), not good. Very mountainous, but good road to

26 Limoux (*Inn*: H. du Parc, capital).

25 Carcassonne (H. du Bonet, good). (Rte. 93.)"—A. S.

### ROUTE 97.\*

THE EASTERN PYRENEES. — TOULOUSE TO FOIX AND PUYCERDA.—THE VALLEY OF THE ARIÈGE.—VIDEASSOS.—ANDORRE

81 kilom. = 59 Eng. m. to Foix, 18 lieux thence to Puycerda = 50 Eng. m.

A post road as far as Foix. *Diligences* run daily to Foix, Ussat, and Ax.

At Portet (p. 338) the road turns to the l., away from that to Bagnères de Luchon (R. 91), and crosses the Garonne by a brick bridge, nearly opposite the influx of the Ariège, and afterwards runs along the l. bank of that river.

26 Viviers.

A little above Beccarest is Cinte-gabelle, where Lord Hill passed the Ariège in 1814.

22 Saverdun, a town of 3000 inhab., was the birth-place of Pope Benedict XII.; he was the son of a baker or miller. At Mazères, a little to the E. of our road, Gaston de Foix, Duc de Nemours, the hero of the battle of Ravenna, was born 1489. Crossing the Ariège, by a bridge at Saverdun, the road ascends its rt. bank to

\* Routes 97 and 98 not being described from personal knowledge, may perhaps be somewhat inaccurate, and the Editor would feel much obliged to any traveller who has travelled on these lines for notes to correct them.

15 Pamiers, a cheerful and pretty town, has a population of 6000 souls, a *Cathedral*, surmounted by an octagonal Gothic tower of brick, spared by Mansard when he rebuilt the nave in the style of the 17th cent., and several *promenades*; one, near the church, looks out upon the distant Pyrenees. About 12 m. W. of this the philosopher Bayle, author of the Dictionary, was born, 1647, in the obscure village of Carla le Comte.

The road still runs along the rt. bank of the river; the valley contracts in width, and increases in beauty.

19 Foix (*Inns*: Rocher de Foix;—H. la Coste, good), the ancient capital of the Comté de Foix, is now the chef-lieu of the Dépt. l'Ariège, which is nearly coequal with the Comté de Foix. It is one of the smallest chef-lieux in France, as its population does not exceed 4857. It has a very picturesque site, at the junction of a stream called the Larget with the Ariège. "It fills up the mouth of the valley, here narrow and bounded by precipitous hills, and lines either bank of the rapid river, whilst an isolated rock, rising from amidst the houses, sustains the ancient *castle* of the Counts of Foix, who resisted with such invincible courage the attacks of the kings of France and Arragon, and whose line terminated with the chivalrous Gaston. It is known by the name of *Les Tours*, an appropriate one, as its lofty towers, built of a coarse whitish marble, and preserved unstained by the dryness of the climate, stand prominent. Part, also, of the ancient ramparts have resisted time's decay; and the antique character of many of the houses, together with 'the magic of a name,' have thrown a colouring over it that makes it, although now unimportant and remote, a spot interesting to the tourist."—J.

The *Castle*, now converted into a gaol, and much injured by modern erections, is approached by a very narrow, steep path, bending, with



very abrupt turns, along the edge of the precipice. Of its 3 fine towers, all of different ages and all anterior to the 15th cent., the tallest, or donjon, 136 ft. high, is also the oldest, having been built 1362, by Gaston Phœbus Count of Foix: it commands a fine view from its top. Simon de Montfort in vain besieged this stronghold, in 1210, during the wars of the Albigenes; and at a later period, 1272, Philippe le Hardi, unable to take it by other means, began to undermine the rocky pedestal, with the intention of toppling it over, together with the fortress on the top of it! Such, at least, is the popular tale; and though there seems little possibility that such a threat could have been accomplished in days when gunpowder was unknown, it had the effect of inducing the garrison to surrender.

An elegant building of the 15th cent., at the foot of the rock, serves as *Palais de Justice*.

The *Préfecture* was originally part of the abbey of St. Volusien, suppressed at the Revolution. The church of St. Volusien, rebuilt by Roger II., Comte de Foix, is a heavy Gothic building.

A considerable trade in iron, the staple of the Dépt. l'Ariège, derived from the mines of La Rancié, in the Vicedessos, is carried on here. The metal is embarked on the Ariège at Autrerive, below St. Foix, for exportation.

*Diligence* hence to Toulouse.

The valley above this is bare of trees, but productive in corn and wine; the vine itself being frequently planted on the heaps of boulder stones cleared away from the fields, where they are otherwise so numerous as to hinder cultivation. Tarascon, a smaller town than Foix (1555 inhab.), having also its ancient castle on a rock above it, stands at the point of convergence of several valleys,—that of Vicedessos, in which the iron mines of La Rancié are situated, traversed by a carriage road as far as Sens,

that of Saurat (near the entrance of which is the fine cave of Bédeillac), up which runs a carriage-road to St. Girons, by the Col de Portet and town of Massat (1000 inhab.), and that of the Ariège.

[The valley of Vicedessos is rendered one of the most industrious in the Pyrenees by its iron mines and works. It is further embellished by the neat houses and gardens of the iron-masters and miners, and by several picturesque old castles, among which that of Méglos is very conspicuous. The *mines of Rancié*, situated 460 ft. above the village of Sem, reached by a difficult path in zigzags which takes an hour to surmount, have been worked for many ages, but without a proper system; and it is supposed that the supply of ore will be exhausted in 20 years. The ore is chiefly the hydrate and carbonate of iron, and is very rich, often yielding 60 per cent.; but as it requires to be brought down from the mine on mule-back, and to be transported often 40 or 50 miles to the furnace, and as the fuel (charcoal) must be sought for in many situations from a like distance, the metal produced is very dear, in spite of the cheapness of labour. Yet nearly 60 furnaces are supplied from hence in the Dépt. of Ariège alone. The iron ore is found deposited in caverns, veins, and hollows within the strata of a limestone rock, belonging apparently to the lower Jura limestone (lias) formation, and within a short distance of the fundamental granite. The ore has been worked horizontally to a depth of 300 mètres, and vertically to a height of 600 mètres. Owing to the unskilfulness, want of concert, and heedlessness of the miners, the ore has been extracted without any regard to economy or safety of life; the roofs and walls of the galleries and chambers excavated, having no proper support, are constantly giving way in consequence, and serious loss of life has frequently attended these éboulements. Many

of the galleries leading into the mines have been blocked up by the ruins. At the village of Viedessos, which is surrounded by furnaces (forges), there is a clean inn. There is a path up the Val de Sallix, over the mountain-pass called Port d'Aulus, into the Val d'Ercè, and by Aulus and Oust to St. Giron.

A little more than a mile above Tarascon lie the *Bains d'Ussat*, a group of lodging and bath-houses, &c., including 2 large and comfortable *Hôtels* (Des Voyageurs, close to the road, and L'Etablissement, on the opposite side of the river), which the traveller may conveniently make his head-quarters when exploring the neighbouring valleys. They stand, shaded by trees, within a few yards of the river, at a point where the valley is closed by mountain-walls of limestone, barely allowing a few box-bushes to take root in their crevices, but traversed by numerous caverns, in some of which fossil bones have been found. The cave on the l. bank of the river, above the Hôtel des Voyageurs, is of considerable extent, requiring an hour to reach its extremity. The *waters* are warm, acidulous, and, when administered in baths, are said to have a calming effect over the nervous system, and are much used by females. The baths are hollows excavated in the ground, lined with slate, filled naturally by the water rising from beneath.

The high road runs up the l. bank of the Ariège, but there is a path along the rt. from Ussat to Tarascon. Above Tarascon the vale of the Ariège makes an abrupt bend to the E., round the N. base of the Mont St. Barthélemy, one of the loftiest of this portion of the chain of the Pyrenees, whose top, surmounted by snows and glaciers, appears, from time to time, domineering over the upper valley on the l. The Pont de Gudane carries the road over the stream of the Aston, descending from the lofty and snowy range separating France from Andorre. Numerous

old ruined castles, built originally to command the valley or defend the frequented passage through it into Catalonia, occur at intervals, rising on peaked eminences above the valley; but the largest and most lordly and picturesque of all is that of *Lordat*, near Cabannes; its origin is attributed to the Moors or Goths. Iron-works in equal number alternate with these feudal remains; thus the romantic associations of former times combine with the active industry of the present to add an interest to a valley which derives so many attractions besides from the beauties of nature. Its ancient inhabitants were called *Tectosages*, from the *sagum*, or cloak, which they wore, which has descended to the present generation, who, by a curious coincidence, still designate it by the same name, in their patois, "*un sayo*."

Ax, 13 m. above Ussat.—*Inns*: H. d'Espagne; H. de France; both extremely dirty. Ax is a town of 2000 inhab., prettily situated amidst granitic mountains, at the junction of 3 valleys, out of which issue 3 mountain torrents, whose streams combine, in or near the town, to form the river Ariège.

In the name Ax it is easy to discover the Latin *Aquæ*, derived from the hot *sulphureous springs* which burst out on all sides; indeed there appears to be a natural kettle of boiling water under the town. More than 30 hot sources issue forth in different parts of it, varying in temperature from 113° to 168° of Fahrenheit; and in order to obtain cold one must resort to the river; and even it, in some parts, is rendered tepid by hot springs rising in its very bed: the snow rests but a few instants on a soil so thoroughly heated from below. Besides the application of the waters to baths, of which there are 2 or 3 establishments, and for drinking, it is turned to various domestic and economic purposes by the inhabitants, who wash not only their linen, but a vast quantity of wool in its tepid streams. The



town itself is a miserable collection of dirty lanes, the only considerable buildings being the hotels and hospitals, one of which has been constructed by government for military patients. Near the hospital is an ancient bath, established in 1200, and still called *Bassin des Ladres*, or Lepers' Basin.

The carriage-road up the valley ceases shortly before reaching Merens—a poor village; beyond it the mountains close in and form a long, gloomy defile; it afterwards expands into an open, stony, and uninteresting tract. A very rough and steep path leads to Hospitalet (12 m. from Ax), a journey of 3½ hours on horseback. This is a poor hamlet, but has a small inn. 1½ hour's ride above this is the pass or col over the mountain, called *Port de Puymaurins*, upon which a custom-house is planted. [Close to this pass, on the W., begins the territory of *Andorre*, a small neutral state between France and Spain, which has been allowed by its powerful neighbours, partly through its insignificance and poverty, to maintain an independent existence, under a republican form of government, for six centuries since the days of Charlemagne, resembling in this respect the republic of San Marino in Italy. It is shut in by high mountains on all sides but the S., where the river Embalire issues out towards the Spanish town of Urgel. Its population amounts to about 15,000, and its capital, Andorre, numbers about 2000. It is governed by a council of 24, a syndic, and 2 viguiers, or magistrates, appointed, one by the king of France, who, as protector of Andorre, receives 960 fr. of tribute yearly, the other by the bishop of Urgel. It consists of 3 valleys, hemmed in by grand mountains of great elevation: its productions are limited nearly to wood and iron; and from the sale of these (and from smuggling) the inhabitants are enabled to purchase corn and other necessities, which their barren and lofty country refuses to yield. For

the traveller there is no accommodation; and he that ventures thither, if he be not prepared to sleep in the open air, with some risk of starving, should carry letters with him from persons of authority at Ax to some of the wealthy proprietors. The only English traveller who has given an account of Andorre, derived from a personal acquaintance with the country, is the Hon. Erskine Murray.]

After passing the crest of the great chain by the Port de Puymaurins the path descends the S. slope, through a very wild valley, strewn with rocks, passing the hamlets of Porté and Porta, near which a path strikes off to the rt. up a minor valley, into Andorre. Between Porta and Courbassil is the old ruined castle, after which the vale is named, called *Tour du Carol*, built, according to popular tradition, by the Moors; but upon the conquest of this country and their expulsion from it by Charlemagne, the towers were christened Carol, after him. They occupy a very picturesque position, on the top of an immense isolated mass of granite, rising in the midst of this narrow and rugged valley. Beyond Courbassil is the village called Tour de Carol, situated within a mile of the Spanish frontier, which is marked neither by stream nor mountain, but is a mere imaginary line at this point. About 2 m. within it lies the Spanish town of

Puycerda, 13 m. from Hospitalet. See HAND-BOOK FOR SPAIN.

The road hence to Perpignan, by Mont Louis and the Valley of the Tech, is described in R. 98.

### ROUTE 98.\*

EASTERN PYRENEES.—PERPIGNAN TO MONT LOUIS AND PUYCERDA, BY THE VALLEYS OF THE TET AND TECH.—ASCENT OF THE CANIGOU.

About 47 Eng. m.

A post road as far as Olette, but not always provided with horses.

\* See note to Route 97.

The vale of the Tet, up whose rt. bank our road ascends, is flattened down and absorbed in the great plain of Roussillon, near Perpignan, and it is not until after leaving behind, at some distance,

24 Ille, a walled town of 3,000 inhab., that the road enters fairly among the mountains. From Vinça, another town, the ascent is gradual to

18 Prades. This town of 3,013 inhab. possesses a tolerable *Inn*, but is in no wise remarkable, except for its pretty situation on the rt. bank of the Tet, in a valley abounding in corn, wine, and fruits, vineyards terraced up the hill-sides, maize, and hemp fields. "The banks on the rt. and l. are spotted with villages, and clustered with old châteaux." Prades lies at the N. base of the Canigou, whose summit may be reached by 8 or 9 hours' walk up the vale of Llentilla.

There is, however, another and more interesting way of approaching the Canigou, pursuing the high road into Spain (R. 94) as far as Boulou (22 kilom.), where it turns to the S. W. up the *Valley of the Tech*. At Ceret, 6 m. up, the river is spanned by an ancient bridge of a single bold arch, 144 ft. in the opening, whose construction is attributed to the Visigoth kings, but which in reality is not older than 1352. It is very narrow, and the arch thins out towards the keystone. Ceret, a town of 3,000 inhab., is about a mile farther; and 7 m. above it is the small fort of Arles-les-Bains, constructed by Louis XIV., on the top of an eminence, from whose base issue hot sulphureous springs of a temperature of 157° Fahr. They were known to the Romans, and the vaulted chamber in which one of them is still received is of their building, but is remarkable only for its solidity. Between this and the town of Arles are some iron forges, where the ore derived from mines situated high up on the N. flank of the Canigou, and brought hither on mules' backs, is smelted.

The Tech is again crossed before entering the town; it has 2,000 inhab. The *Church* is ancient; the front and portal enriched with curious carving, in white marble, dated from 1045. On the left of the façade, under a sort of shed, is a very ancient sarcophagus resting on 4 feet, filled with miracle-working water, which is never exhausted, and is sold at 20 sous the vial-full. It owes its virtues to the coffin having enclosed the relics of two saints, which were brought from Rome to free the neighbourhood of Arles from dragons, lions, &c., which then infested it! Adjoining the church is a cloister, a range of pointed arches on slender pillars, of the 13th century, without a roof.

About 10 m. distant among the mountains, and approached by steep paths, from which fine views are obtained of the Canigou, is the Romanesque church of Coustouges, which may interest the antiquary, as it is supposed to date from the 9th centy.

8 m. above Arles, in the Valley of the Tech, lies Pratz de Mollo, a frontier town of 4,000 inhab., surrounded by old-fashioned fortifications, but commanded on the height above by the efficient Fort Legarde, constructed from the plans of Vauban. A mule path runs hence over the mountains to the Spanish town Compredon.

The *ascent of the Canigou*, which projects forward from the great chain of the Pyrenees, and rises, almost isolated, above the plain of Roussillon, to a height of 9141 ft., was made by Mr. E. Murray from Arles. He followed the mule paths leading to the iron mines, as far as the old tower of Batères, standing on a ridge whence you look down upon both valleys of the Tech and Tet; and after 3 or 4 hours' scrambling from this ridge, "up steps, along precipices, and over snow wreaths," attained the summit; whence the eye surveys the plain of Roussillon, and the coast of the Mediterranean, with Perpignan on its margin; the valleys bordering on the Tet; the mountain range of Cata-



lonia on the S.; and on the W., the chain separating Roussillon from the Vale of Ariège. "The ascent or descent to Valmania is so difficult and dangerous as to deter many an aspirant from attempting to surmount it; but no one, with a tolerable pair of legs, good lungs, and not unaccustomed to mountain climbing, ought to be discouraged: should he succeed, he will find himself amply repaid for his toil and fatigue." Valmania is a hamlet, composed of a few miners' houses, and a very humble cabaret, which will afford night shelter, and fresh eggs, with vin du pays, in a wild situation under an old ruined castle. The iron mines occur near the junction of a limestone (of the age of the chalk) with the granite. It is a five hours' walk hence to Prades, descending the vale of the Lentilla, through picturesque scenery, and joining the high road near Vinca.

Above Prades the plain of the Tet contracts into a valley; and, after passing the old *castle* of Ria, the cradle of a noble line, whence came the Counts of Arragon and Barcelona, narrows to a gorge at Villefranche, a town fortified by Vauban, but not strong, because commanded by the neighbouring heights, which squeeze it in as it were, and leave barely space for its two narrow streets, and the river below.

8½ m. from Prades, in the vale of Corneilla, which penetrates S. from this into the flanks of the Canigou, lies *Vernet*, a watering-place, supplied by hot sulphurous springs bursting out of a slaty quartzose rock, which here composes the Pyrenæan chain. They are useful in cases of rheumatism, paralysis, wounds, and ulcers. The place was visited by Ibrahim Pasha in 1846. Above Vernet rises the ruined abbey St. Martin de Canigou.

The high road crosses the Tet, by a bridge, on quitting Villefranche, and

terminates soon after, giving place to a mere mule path.

16 Olette. 2 m. farther the cultivation of the vine ceases; the valley becomes sterile and wild; the road, ascending more rapidly, traverses a narrow defile, guarded and closed, in ancient times, by walls, towers, and gateways, whose ruins still remain. To this succeeds an open expanse, a table-land of green meadow, a pastoral scene, surrounded by fir-clad heights; and in the midst, at a distance of 10 m. above Olette, stands

Mont Louis (a tolerable *Inn*), a frontier fortress (442 inhab.), built 1684 by Vauban to guard the passage from Spain.

The town consists of 8 short streets, in straight lines, crossing one another at right angles, surmounted by the *Citadel*, whose casemates afford shelter for 800 men. A road runs N. from this to Carcassonne (R. 93), and a path over the mountains by Langles into the vale of the Ariège.

About 2 m. from Mont Louis, and at a height of 350 mètres above it, 1,559 mètres above the sea-level, is the pass over the mountains, called *Col de la Perche*. The path from it descends into the basin-shaped valley of the Cerdagne Française, traversed by numerous streams, the chief of which is the Seyre, or Segre, a tributary of the Ebro. The territory of France has here been pushed, for some distance, down the S. slope of the backbone of the Pyrenees, in the same manner that the Spaniards occupy the head of the vale of the Garonne, on the N. of the chain (R. 87). 5 m. below the col is Saillagousa, a town of 400 inhab.; 2 m. farther is Llivia; and 3 m. more carry the traveller across the frontier to the first Spanish town, Puycerda (10 m. from Mont Louis). See *HAND-BOOK FOR TRAVELLERS IN SPAIN*.

The road from Puycerda to Toulouse is described in Route 97.

## SECTION V.

CENTRAL FRANCE. — BERRI. — AUVERGNE. — VIVARAIS. — ARDÈCHE. — CANTAL. — BOURBONNAIS. — LYONNAIS. — THE CEVENNES.

ROUTE	PAGE	ROUTE	PAGE
103 Orleans to <i>Bourges</i> and Clermont . . . . .	356	112 Clermont to Lyons, by <i>Thiers</i> . . . . .	410
104 Orleans to Moulins and Lyons by Bourges . . . . .	361	114 Clermont to Toulouse, by the <i>Cantal</i> and <i>Aurillac</i> . . . . .	412
105 Paris to <i>Lyons</i> .— <i>Route par le Bourbonnais</i> , by <i>Fontainebleau</i> , <i>Montargis</i> , <i>Nevers</i> , <i>Moulins</i> .— <i>The Baths of Vichy</i> . . . . .	362	116 Clermont to Toulouse, by <i>St. Flour</i> , the <i>Baths of Chaudes Aigues</i> , <i>Rodez</i> , and <i>Alby</i> . . . . .	415
106 Paris to Lyons.— <i>Route par la Bourgogne</i> , by <i>Sens</i> , <i>Auxerre</i> , <i>Arnay-le-Duc</i> , <i>Châlons-sur-Saône</i> , and <i>Mâcon</i> .— <i>Descent of the Saône</i> , from Châlons to Lyons . . . . .	383	118 Lyons to Le Puy, Aubenas, <i>Mende</i> , and <i>Nismes</i> .— <i>Railway to St. Etienne</i> .— <i>The Cevennes</i> . . . . .	420
107 Paris to Châlons-sur-Saône, by Auxerre and <i>Autun</i> . . . . .	391	119 Roanne to Valence on the Rhône by <i>St. Etienne</i> and <i>Annonay</i> .— <i>Railway</i> from Roanne to <i>St. Etienne</i> . . . . .	425
109 Moulins to Clermont and <i>Le Puy</i> .— <i>Volcanoes of Auvergne</i> . . . . .	393	121 Valence to Nismes, by <i>Priavas</i> , <i>Aubenas</i> , the <i>Volcanoes of the Ardèche</i> , and <i>Alais</i> .— <i>Railway</i> from <i>Alais</i> to <i>Nismes</i> .— <i>The Cevennes</i> . . . . .	429
110 Clermont to <i>Mont Dore les Bains</i> . . . . .	407		

## CENTRAL FRANCE.

## GENERAL VIEW OF THE COUNTRY.

AMONG the crowds of English travellers who annually roll along the high road from Paris to Lyons on their way to Italy, complaining of the dull monotony of France, how few have taken the trouble to ascertain what beauties and curiosities were presented by the districts which they almost skirted with their carriage wheels—Auvergne, the Vivarais, the Ardèche, and Dauphiné! Auvergne, little known even to the French themselves, except among men of science, in whose works it is minutely described, is best approached by quitting the high road to Lyons at Moulins, and ascending the valley of the Allier to Clermont. The road thither, and for some distance beyond, traverses a country contrasting remarkably with that left behind at Moulins in varied surface, fertility, and abundance of foliage. It is thickly inhabited, and sprinkled over with towns and villages, not hidden, but planted on the road side or on the top of conspicuous eminences, where they alternate with ruined castles. The chief source of interest, however, in Auvergne consists in its *extinct volcanoes*, which of themselves deserve to attract visitors from all quarters of the globe. Even the distant outline of these commanding mountain groups marks them as something uncommon,



while on a nearer approach their structure and composition furnish undeniable proof of their extraordinary origin. Many of them swell into domes, showing that

“The earth hath bubbles as the water has ;”

others are formed into craters as regular and perfect as those of Etna and Vesuvius, assuming the shape of a funnel or inverted cone. In many instances the lava streams may be traced from the very lips of the crater out of which they originally flowed for miles over the country, capping the hill tops and filling up the valleys.

*Castles* of the feudal ages, dismantled by the levelling politician Richelieu, or by the unbridled fury of the Revolutionists, abound in Central France and contribute to adorn the landscape. In the volcanic country they are usually perched on a platform of basalt crowning some conical peak, which is the relic of a great bed of the same rock which once overspread the country. These ready-made pedestals, from their isolated position and precipitous sides, afforded security for property in troublous times, and impunity for violence and rapine.

The best head-quarters for exploring Auvergne is Clermont, at the foot of the Puy (or Pic) de Dôme, whence numerous excursions may be made over the Phlegrean fields of France, including a visit to Mont Dore les Bains, situated within another volcanic chain, the Monts Dore. Farther S. lie the volcanic groups of the *Cantal*, between Murat and Aurillac, whose scenery is striking and very peculiar ; of *Velay*, in the midst of which stands the town of Le Puy, one of the most singular and picturesque in France ; and of the *Ardèche* or *Vivarois*. Both the Cantal and Le Puy are accessible by good roads from Clermont, but there is a want of communication between them, and a carriage can only proceed from one to the other by a long détour, while the Ardèche is accessible by good roads only from the Rhône. The pedestrian and geologist will find his way readily across the country.

Aubenas, in the Ardèche, has a good inn ; Vals, too, which is even more central, affords very fair accommodation, where travellers may put up while exploring its basaltic causeways, its domes of ashes, and craters of scoriæ, on which the chesnut luxuriates. The pedestrian and equestrian can pass from Le Puy, by Langogne, direct to Thueyts and Montpezat. (R. 121.)

Bordering upon the Ardèche to the S. extends the wild mountain chain of the *Cevennes*, which may be termed a *moral* extinct volcano, the last stronghold of persecuted Protestantism in France, “Le Désert,” as its own inhabitants called it, while further, in allusion to the children of Israel, they styled themselves “Les Enfants de Dieu.” The Cevennes fill a large part of the departments of La Lozère and Gard ; and, by tracing up to their sources on the map the rivers Tarn, Gardon, Vidourle, and Herault, the reader will ascertain the theatre of that dire struggle, in the course of which 30,000 Cevenols perished in battle or on the scaffold, and a much larger number of royal troops fell, between November 1702 and December 1704. The boundaries of the Hautes Cevennes are precisely marked by the lozenge-shaped outline formed by the head waters, or forks, of the Tarn, and the two Gardons, that of Andouze and that of Alais. The Basses Cevennes lie S. of this, between the Gardon d’Andouze and the Vidourle. These mountains are a natural citadel, an inextricable labyrinth of gorges and defiles well fitted for desultory warfare, where a handful of bold defenders could hold out against a host ; with mountain peaks and ridges for camps ; passes and gorges for ambuscades ; forests to rally in, in the event of defeat ; and for escape and refuge, mountain paths, trodden only by the wild goat, and caves haunted by the fox ; but which the Cevenols converted into arsenals and storehouses. The

best disciplined troops availed nothing in storming these bulwarks of nature ; and army after army, sent forth by the bigot Louis XIV., at the instigation of the Jesuits, was annihilated by rude peasants, and their leaders were recalled with disgrace. But the miseries of war, the assassinations, burnings, pillagings, slaughter of females and infants, were not confined to these mountains : they spread far and wide down into the plain, to the ocean on the S., to the Rhône on the E., and N. beyond the Ardèche : the incursions of the peasants in their forays, pouring down from the hills, repeatedly spread consternation up to the very walls of Nismes, Uzès, Alais, and Montpellier ; and their leaders in disguise boldly penetrated into the interior of these towns when in search of provisions or intelligence. And who were these chiefs ? Simple peasants, shepherds, labourers, carders of wool, and weavers, who exercised the double office of military leaders and prophets ; a singular compound of psalm-singing and throat-cutting, combining the strongest religious fanaticism with much worldly vanity, love of fine dresses, and of plunder ; and above all, the most dauntless courage. One or two had served as soldiers in the ranks, during the war of the Alps ; but this could not have given them that skill in generalship which enabled them repeatedly to bring their wild hordes to face troops four, six, or eight times more numerous, not only in the mountains, in advantageous positions, but also in the plain, with so much skill as to call forth the admiration even of Marshal Villars. The story of the poor peasants of the Cevennes differs but little from that of the Covenanters in Scotland, except that the oppression which the Cevenols endured was more cruel. It affords a remarkable proof how fruitless are the efforts of bigoted persecution and tyrannic cruelty, even when backed by unlimited power, in procuring passive submission. When, in an evil hour for France, Louis XIV., listening to the advice of Louvois and Bossuet, backed by the Jesuits, revoked the Edict of Nantes, made it a crime to pray except according to his own religion, banished the Reformed pastors to distant lands, pulled down the churches, and let loose the Dragonnades to torture the people into conformity, a strange fermentation was produced in the public mind, heated by the perusal and misapplication of particular parts of the Bible. Prophets and prophetesses began to spring up among the Protestant community. That wild enthusiasm, bordering on insanity, which roused up the Maid of Orleans to resist the oppression of the English, here seems to have developed itself among a whole community. The disease of prophesying seems first to have broken out in Dauphiné, but soon spread, like an epidemic, across the Rhône, and a large proportion of the cases were mere boys and girls, and all untaught peasants. The ignorant peasantry, believing the ecstasies of these preachers to be inspired by the Holy Ghost, flocked from far and near to listen, and, deprived of the sober guidance of their own exiled pastors, imbibed the fervour of fanaticism. The spirit of resistance began to show itself, drawn forth by the recital of their wrongs, the denunciation of their tyrants, and the assurance of support from heaven : conventicles were held, in spite of the terrors of prison, torture, and the soldiery, in the open air among rocks and caverns. The desire of vengeance on the instrument of their suffering, a bigoted priest who had acted the part which Archbishop Sharp is supposed to have done in Scotland, and who was assassinated by a fanatic French Balfour of Burley, was the signal for denial of mercy on the part of the ministers of Louis, and of open rebellion on the side of the Cevenols. Hereupon commenced the insurrection of the *Camisards*, as the persecuted outcasts of the Cevennes were called by their enemies, it is supposed from the white shirt (in Languedocian, *Camisa*) which they wore over their clothes to distinguish themselves. The whole of the Protestant communities were organ-



ized chiefly by the leaders Roland and Cavalier; troops were levied from the different parishes, and each furnished its quota to the ranks and the commissariat or a contribution of money; and losses in the ranks were filled up by fresh levies. The Cevenol force never exceeded 3000 in arms at one time, and was divided into three brigades under different chiefs, each of whom had his own post and district (generally near his own home) among the hills. Such troops and commanders, intoxicated by the wild harangues of prophets and prophetesses who accompanied the expeditions on horseback, and made their hearers believe that their bodies should be as stone against sword and musket, and who led them into action with some inspiring psalm, produced acts of most dauntless daring and prowess, and a total disregard of the numbers brought against them. The seizures, tortures, executions, by breaking on the wheel and burning alive (the common modes of punishing a Camisard), led to reprisals on their part—to murders of priests, sacking and burning of popish churches. Yet, horrible as were the acts of vengeance and violence committed by the Cevenols, they were equalled, if not surpassed, by the crimes, plunder, and murder of women and children, perpetrated by the ruffian soldiery in the pay of Louis, especially by the guerrilla bands called Florentins. The royal troops carried fire and sword into every village; and the unscrupulous generals and governors of Louis acting in Languedoc resorted to the atrocious measure of devastating the whole of the Upper Cevennes; destroying by fire and axe 400 hamlets and villages, and driving away the inhabitants. The Camisards did not attempt to defend their homesteads, but retorted by carrying fire and sword over the fertile plain, and spreading terror into the cities of Nismes and Montpellier. The rebellion was at length arrested, less by any successes gained against the Protestants in the field, by the number of troops employed against them, and the skill and generalship of the four marshals of France dispatched in turn to take the command, than by the cautious policy of one of them, Marshal Villars, in cajoling and bribing the Cevenol leaders.

Though the struggle of the Cevenols ended in failure—though the tolerance of their faith, according to the Edict of Nantes, the chief object for which they contended, was denied them—though the insurrection was followed, not by alleviation of their wrongs, but by persecution continued for half a century,—yet these misguided sufferers, who bled upon their native mountains, who were broken alive on the wheel, burnt alive on the pile, tormented in dungeons, or pined away their lives in gaol, gave a terrible lesson to tyranny and religious bigotry, and shook the “Grand Monarque” on his throne. Even at the present time their country has not recovered from the desolation inflicted by the destruction of its houses and temples. Many parishes, destitute of places of worship, meet for prayer in the open air, and the traveller in passing through them may be arrested by the distant sounds of psalmody, or in passing an abrupt turn in his road may come upon a congregation of peasants attentively listening to the pastor, who holds forth from the top of the rock, or from beneath the shade of a venerable tree. Many families trace their descent from the chiefs of the insurrection. The people are poor, and the greater part of their country, especially the Upper Cevennes, is not easily accessible for want of roads. There is but little traffic along the two highways from Mende to Nismes (R. 118), and from Aubenas to Alais (R. 121), which skirt or traverse it. Manufactures, however, are gradually creeping up its remote valleys from the S.; and the railway completed between Nismes and Alais, and the neighbouring coal-field cannot fail to give an impulse to traffic and commerce. The traveller

find little picturesque beauty, owing to the bare aridity of the hills, the want of foliage and of verdure.

Its history and ancient associations form its chief interest. An Englishman may be willing to be reminded, as he traverses this district of former strife, that many of the Irish officers and soldiers who fought at the battle of the Boyne on the side of James II., and afterwards accompanied him to France, were employed here against the Protestants; that the Cevenol leaders were encouraged by the ministers of William III. and Queen Anne, and received promises of assistance, but promises only; that on two occasions British fleets, under Sir Cloudesley Shovel, approached the coast of Langue/doc to support the insurrection with troops and arms, but failed in effecting that purpose; that the band of Cevenol insurgents expelled from France by the intrigues and negotiations of Villars was formed into a regiment under their chief Cavalier, and fought in the English army commanded by Peterborough in Spain, at Almanza, where they were almost cut to pieces by their own countrymen; and that Cavalier, their leader, died a pensioner in Chelsea Hospital.

A full account of the war of the Cevennes, and the events which led to it, will be found in Peyrat, *Histoire des Pasteurs du Désert*, Paris, 1842.

For the geology of Auvergne, Velay, and the Vivarais, there is no work so good as Scrope's *Central France*, with illustrations from the author's sketches. Consult also Lyell's *Geology*, and the French works of M. Elie de Beaumont; those of MM. Lecocq and Bouillé, and of M. Bertrand de Doux. Miss Costello's *Summer in Auvergne* may also be referred to. Merimée's *Notes d'un Voyage en Auvergne* contains the most complete account of the monuments of that district. There is an admirable *Map* of Auvergne by *Desmarest*.

### ROUTE 103.

#### ORLEANS TO BOURGES AND CLERMONT.

111 kilom. = 69 Eng. m. to Bourges. 71 kilom. thence to Clermont.

#### *Railroad to Vierzon.*

This road is the same as R. 70 as far as

79 Vierzon. About a mile out of the town, on the banks of the Canal, is the village Les Forges, consisting of very extensive furnaces, where the iron of Berry is wrought in large quantity.

*Diligences* daily to Bourges, &c. The post road passes through

18 Beauregard, having on the rt., near to the river Yèvre, the town of Mehun, where a fragment, consisting of 2 machicolated towers, alone remains of the *castle* in which Charles VII. spent much of the early part of

his reign in indolence, and at last ended his days; allowing himself to die of starvation, through the fear of being poisoned by his son, afterwards Louis XI., 1461. The demolition of the building has been chiefly effected since 1812, down to which time the chamber of the king, and that of his mistress, Agnes Sorel, were still pointed out.

14 BOURGES.—*Inns*: H. de France;—La Boule d'Or, near the Diligences: both second rate;—Le Bœuf Couronné.

Bourges, anciently capital of Berry, and now of the Dépt. of the Cher, is situated nearly in the centre of France, upon a considerable eminence, rising abruptly out of an uninteresting and flat country, *watered* by the river Auron, and has 20,440 inhab. It possesses little trade and no extensive manufacture; though



some cloth is woven and some iron ore is smelted in it. Its streets may be divided into 2 classes: those of very ancient houses with gables facing outwards, many of them having frame fronts of timber, generally occupied by shops; and streets of dead walls and *portes cochères*, denoting the habitations of families of independent fortune, and in easy circumstances, in which class Bourges abounds. The number of silversmiths is remarkable in a provincial town. The highest platform of the hill on which the town is built is occupied by the *Cathedral of St. Etienne*, a colossal and magnificent edifice, one of the finest in France, conspicuous, with its 2 solid towers, far and near. Its W. façade presents a row of no less than 5 deeply recessed portals, all ornamented, in a style of peculiar richness and originality, with sculpture; that in the centre, higher than the rest, is decorated, above the carved wood doors, with a bas-relief of admirable execution, representing the Last Judgment. In the centre, Christ seated amidst Archangels, and the Virgin and St. John on either side, on their knees: below, on his rt., the Good led to the Gate of Paradise by St. Peter; on the l. the Wicked seized by Demons and hurled into a fiery Cauldron, which divers Imps are exciting with the Bellows: 6 rows of niches, filled with figures of the Angelic Choir, Saints, Patriarchs, &c., line this deep porch on either side. The varied expression of the countenances, the elevated character of many, the easy flow of the drapery, and the good execution of the whole, bespeak the work of an eminent sculptor, but his name, as well as that of the architect of the building, is unknown. The portals have been lately restored, with great care and skill, in a species of clay. The injuries are attributed to the Protestants; but if they be the result of a popular commotion, and not of the mere progress of time, they are wonderfully slight. The other portals have

smaller reliefs, from Scriptural and legendary stories, and fewer niches, but equally deserve examination. Those on the rt. of the spectator represent the stoning of St. Stephen, and the Acts of St. Ursin; on the l. the Death of the Virgin, and St. Ursin and St. Just preaching the Gospel in Berry. The foliage between the mouldings can scarcely be surpassed for delicacy.

The oldest part of the church is the lateral doorways on the N. and S. sides; they are circular arches, adorned with florid Norman ornaments and statues, in a stiff style, dating, probably, from the 12th century. The N. door is covered by a projecting porch of later date. The N. and most perfect *tower* was founded 1508, and finished 1538. Its builder was Guil. Pellevoisin: it is 199 ft. high; it is called the butter tower, because built with the money raised from indulgences to eat butter in Lent. The S. tower is inferior in elegance.

The interior consists of one long and vast parallelogram, without transept, but, to make amends, provided with double aisles on each side, those next the centre being 65 ft. high, and furnished, like it, with triforium and clerestory, worthy of a cathedral nave, extending all round the choir. Beyond the outer aisle are 18 chapels. The vaulted stone roof of the central aisle, 117 ft. high, is supported by 60 piers, with capitals in the early English style, presenting the most varied and striking perspective.

One of the chapels is said to have been built by the celebrated jeweller Jacques Cœur, and his son John, 88th *Archbishop* of Bourges, 1446. The sculpture of the portal of the sacristy is very delicate. One of the chief boasts of this cathedral is the quantity, excellence, and good preservation of the *painted glass* of the windows of the choir and chapels. They include specimens of the art from the 13th down to 17th century. The oldest, confined chiefly to a

beautiful arrangement of patterns, may be called a transparent Mosaic, unsurpassed in the beauty of the colour: these were succeeded, in the 15th and 16th centuries, by glass pictures, groups, and single figures, well drawn, and also of good colouring. The chapels containing the finest examples of the latter state of the art are those of Jacques Cœur, St. Loup, St. Denis: those in the chapels of Tullier and Coppin are the work of Lécuyer, an artist of Bourges (d. 1556). One of the most modern specimens is a beautiful Ascension of the Virgin, given, 1619, by the Maréchal de Montigny, whose portrait, with that of his wife, is seen in the corner below.

In the *crypt*, an early Pointed structure, running below the choir, in a semicircle, is deposited the monument of Jean le Magnifique, Duc de Berri, son, brother, and uncle of kings, and nephew of Charles V. of France, erected by his own nephew, Charles VII. His effigy, in marble, of good execution, was brought hither from the Sainte Chapelle, which he built, now destroyed. Here are also the effigies in marble of the Maréchal Montigny and his lady, and the statue of the Virgin, of good design. Louis XI., son of Charles VII., b. at Bourges 1423, was baptized in the cathedral by Huri d'Avanjour, 89th archbishop.

Adjoining the cathedral, on the S., is the *archevêché*, a handsome edifice, in the Italian style, with gardens attached, traversed by fine avenues of limes; and a little way from it the *Caserne d'Artillerie*, an immense building, formerly the Grande Séminaire, surrounded by numerous detached buildings, stables to accommodate the men and horses, of whom 800, with all their train and equipments, are commonly stationed here.

The city of Bourges is still surrounded by *Remparts*, converted, for the greater part of their extent, into a public promenade, and planted with trees. It was formerly defended by

60 watch-towers, all of which have been demolished except 6 or 8. Two of these, behind the *archevêché* and cavalry barrack, opposite the promenade called the *Cours Seraucourt*, deserve notice, as being undoubtedly Roman. One is formed of huge blocks of stone, now much worn at the edges, a style of durable masonry (*opus incertum*) employed by the Romans in their great works; the other is of smaller stones, with layers of large tiles in bands; the substructure of the wall, as far as the garden of the *préfecture*, is of the same kind. These Roman relics are of some interest. Joseph Scaliger and D'Anville are satisfied that Bourges is the ancient *Avaricum* (named from the river Avara, now E'vre), chief town of the Bituriges (Berry), mentioned by Cæsar in his Commentaries (viii. 13), "*Oppidum quod erat maximum munitissimumque, in finibus Biturigum, et totius Galliæ urbs prope pulcherrima.*" On account of its importance and beauty it was the only city of the Celtic Gauls which they spared to burn to the ground, when, like the Russians in Moscow, they resorted to that expedient as a last resource to check the conquering armies of Julius Cæsar.

At the entrance of the Garden of the *Préfecture*, close to the Promenade de Seraucourt, is a Romanesque portal of the 11th century, removed from the *Church of St. Ursin*, now destroyed. It is a circular arch, enclosing curious sculptures in relief, representing the 12 Months of the Year, a Boar Hunt, &c., Scenes from Æsop's Fables, as the Stork and the Fox, a Fox drawn by Geese, of very good execution.

Next to the cathedral, the most interesting building is the *Hôtel de Ville*, originally the private mansion of Jacques Cœur, a citizen of the town, a great capitalist and successful merchant and jeweller, and finance minister to Charles VII., who, after lending his master 200,000 gold crowns, was torn from his palace, cast



into prison, and condemned to death and confiscation of his property—a sentence commuted by the king into perpetual banishment. The cause of his accusation and condemnation remains a mystery. The building, begun 1443, is in the late or florid Gothic style, of great magnificence, yet not overladen: the walls alone cost 130,000 livres. There is no uniformity of parts; no one wall or window corresponds with another—all is varied, yet all is harmonious. The entrance is flanked by a most elegant tourelle, and is surmounted by a projecting balcony, or open oriel of elegant tracery. Two figures, sculptured in stone, on each side, are said to be the servants of Jacques Cœur, on the look-out to warn him of danger from the officers of justice, but are more probably a mere freak of the architect. This elegant palace is distinguished, like many other French domestic edifices of the 15th century, by its circular cone-roofed towers, containing spiral staircases. Its windows, surmounted by flat arches, are ornamented below with open tablets of quatrefoils, among which is introduced the punning device of Jacques Cœur, the heart, and the scallop-shell of the pilgrim to St. James's Shrine. On a little Gothic balustrade between the outer gateway and its flanking turret the motto of Jacques Cœur, "A vaillants Cœurs rien impossible," is most elaborately carved in tall Gothic characters of stone. Over the doorways in the court are singular bas-reliefs: observe that on the l. of the great entrance, and that over the kitchen. The *chapel* above the gateway deserves to be seen, but especially the upper part divided from the lower by a modern floor, its groined roof being elegantly painted in fresco, probably by Italian artists, with angels in flowing robes of white upon a blue ground, representing the multitude of the angelic host, bearing scrolls, inscribed, "Gloria in excelsis Deo, et in terrâ pax," &c.: the figures are well foreshortened, and in

good preservation. In the lower part of the chapel are 2 elegant niches, nearly blocked up. The rest of the interior has been sadly mutilated and altered, to fit it for conversion into law-courts, stripped of panelling, cornices, and chimney-pieces, so that the chapel alone is now worth entering. This palace was appropriated as a residence to the youthful Condé, destined to become *Le Grand Condé*, while pursuing his studies at the Jesuits' College here.

The *Caserne de Gendarmerie*, in a street behind the Hôtel de Ville, not far off from it, was the house of Cujas, professor in the *University*, which existed here from 1465 to the Revolution. It is of brick, of very solid construction, in a style resembling the Tudor of England, built towards the end of the 16th century, and displays about its door, windows, and turrets, some fragments of elegant decoration.

The Convent of the *Sœurs Bleues*, in the Rue des Vieilles Prisons, originally the mansion of the family Lallemant, and built probably about 1512, has an irregular front, flanked by tourelles, gracefully decorated with arabesque patterns, bas-reliefs, &c., in the style of the Renaissance, which will please an architect. It contains a little family oratory, about 10 ft. by 15, surmounted by a roof of 3 stone slabs, divided into 30 compartments, each filled with some device, as a Globe on Fire, a Hand gathering a Chesnut, or other pattern, rebus, relief, or ornament, alternating with the letters R E, often repeated, most elaborately carved, but of which the meaning is difficult to explain.

Bourges was the residence and refuge of Charles VII., at a time when three-fourths of his kingdom of France belonged to the English, when he was little more, in fact, than "king of Bourges."

Bourges has a *museum*, a receptacle of antiquities, of various ages, and other curiosities, without order or arrangement. A series of 6 weep-

ing figures (pleureuses), in alabaster, from some monument; a model of the Sainte Chapelle, mentioned above, now destroyed; an ebony cabinet, ornamented in the style of the Renaissance, from Agnes Sorel's castle, Bon-sire-aimé, and some portraits, including those of Louis XVI. and Marie Antoinette, merit notice.

Bourges is the birth-place of Louis XI., and of *Bourdaluë*, one of the first pulpit orators of the French church.

*Diligences daily* to Vierzon to the railway, thence to Orleans and Paris; to Tours by Châteauroux and Loches; to Toulouse by Limoges; to Nevers; to Clermont, and the Baths of Nérès.

There is little to interest in the flat but fertile country across which we proceed to Montluçon by

18 Levet.

13 Jariolè.

A little on one side of the road is the ruined *Abbey of Noirlac*, so named from a dark pool near it. It is now converted into a China manufactory, including *The Church*, a large and still perfect structure, and a good example of the transition Gothic of the latter part of the 13th century, 1189. The kitchen and refectory, supported on pillars, still remain, as well as the cloister.

16 St. Amand Montrond, a neat town of 6636 inhab., on the Marmande, about a mile from the rt. bank of the Cher. Only a few shapeless ruins remain of its *Castle*, once an important stronghold, belonging to the princes de Condé, in which the sickly infant who grew to be le Grand Condé was nursed and reared. His heroic wife, the Princess Clémence de Maillé, after her escape from Chantilly, 1650, threw herself and her son into this castle, whence, after gathering around her the dependants and retainers of the house of Condé, she set forth to cross some of the wildest provinces of France in order to join the Dukes of Bouillon and La Rochefoucauld, and put herself at the head of the army of the Fronde, which

kept possession of Bordeaux against Mazarin. Montrond was the birth-place of Gaston de Foix; it was fortified by the Duc de Sully, who wrote here his "*Adieux à la Cour*:" after enduring a siege of a whole year's duration, 1652, from the royal forces, it was compelled to surrender to the Comte de Palluau, who levelled the fortifications. The last tower which remained standing has been pulled down, in order that the proprietor may make gardens and terraces on the site.

About 21 m. S.W. of St. Amand is the *Château de Meillant*, built 1511, for Charles, Seigneur de Chaumont, somewhat in the style of the house of Jacques Cœur at Bourges, with similar external ornaments, balustrades, and projecting towers to contain the snail-shell stairs, but vastly inferior to it. The blazing hill, sculptured in various parts, is intended as a sculptured pun on the owner's name, *Chauds Monts*. The decorations of the interior are not supposed to be later than the 18th century. On the towers are sculptured figures of sentinels threatening all who approach, like those on the battlements of Alnwick.

The road from St. Amand is very agreeable, running by the side of the Cher. At Drevant, on its rt. bank, traversed by the road, extensive substructions of a theatre, and other Roman buildings, have been laid bare.

A branch of the Canal du Cher runs parallel with the Cher and the high road from St. Amand to Montluçon, and the coal mines of Commeny, where it terminates.

18 Meaulne.

16 Reugny (Dépt. Allier).

15 Montluçon (*Inns*: H. de France, and de l'Ecu), a very ancient town of the province of the Bourbonnais, having 5400 inhab., picturesquely situated on the slope of a hill, whose base is washed by the Cher, and its summit crowned by a *Castle*. During the middle ages it was a strong fortress; and, from its position near the



frontier of the French king's domains, had often to sustain the attacks of the English. A part of its old walls, and their flanking watch towers, still remains, constructed with great solidity. The donjon, and a few towers on the summit of the hill, are all that remains of the *castle* of the Ducs de Bourbon, which commanded the town, as its ruins still command an extensive view.

A hilly and uninteresting road to 8 *Néris* (*Inns*: Grand Hôtel;—H. Leopold), a watering-place of considerable resort within a few years, but well known to the Romans, who must have had a magnificent establishment here, judging from the architectural fragments—columns, friezes, foundations of walls—discovered from time to time. Yet it is only since 1821 that the French have begun a *bath-house*, which is not yet finished, and which, with several boarding-houses attached to a poor village of 800 inhab., compose the place. The *mineral waters* are warm, alkaline, but nearly tasteless, so that the inhabitants employ them for culinary purposes and for drinking; they are furnished from 4 sources, one of which, La Source Nouvelle, burst forth, 1757, at the time of the earthquake at Lisbon. They are exclusively used for baths, being introduced into the houses. They resemble the spring of Schlangenbad, have the same unctuous feel to the touch, the same smoothing effect on the skin, and sedative influence on the nerves. It is usual to go to bed after taking the bath, in order to promote perspiration. There are also douche and mud-baths, and 3 piscines or public baths.

The very pretty promenade, or *Jardin des Bains*, occupies the site of an *amphitheatre*, built by the Romans for the recreation of visitors to these remote baths of *Aquæ Neri*, as *Néris* was anciently called. Concentric terraces mark the stages on which the seats were placed; and traces remain of one of the passages which divided them into cunei or

*France*.

wedges. There are considerable fragments of walls.

The *Church* is a very ancient Romanesque edifice, in the form of a basilica, ending in 3 apses. The arches in the nave are pointed, those in the choir round. From the rude sculpture of the capitals, its date has been referred to the 11th century.

The country around is pleasing, and the situation very healthy.

The road to Clermont is carried through a wild hilly district, passing out of the coal formation into a country of primitive rocks shortly before reaching

18 Montaigu, a little town appropriately named from its site on a pointed hill, crowned by a castle, situated in the Dépt. Puy de Dôme.

At Menat are quarries, whence tripoli or polishing slate is obtained: it is produced by the spontaneous combustion of iron pyrites among beds of bituminous clay. It contains impressions of vegetables, fish, and insects. Near this the road ascends a long and steep hill, commanding a very extensive view over the volcanic ranges of Auvergne, and near at hand looks down upon the Castle of Blot, seated amidst rugged rocks. The river Sioule is crossed before reaching

27 St. Pardoux. The very peculiar forms of the volcanic mountains of the Puy de Dôme cannot fail to arrest attention (p. 352).

We now enter the fertile plain of the Limagne d'Auvergne.

23 Riom } described in Route  
15 Clermont } 109.

## ROUTE 104.

ORLEANS TO MOULINS AND LYONS, BY BOURGES.

The Paris and Orleans railroad offers facilities to travellers bound for the S. of France, who may shorten the duration and lessen the fatigues of the journey by proceeding from Orleans to

191 Bourges (as in R. 103), and thence by a good road.

14 St. Just (Cher).

21 Blet.

16 Sancoins.

17 St. Pierre le Moutier (in R. 105, p. 368, where the rest of the road to Lyons is described).

The quickest way from Paris to Lyons is to take the railroad to Orleans (R. 49), and to post thence by Gien (R. 52) to Briare.

### ROUTE 105.

PARIS TO LYONS.—ROUTE DU BOURBONNAIS, BY FONTAINEBLEAU, MONTARGIS, NEVERS, AND MOULINS.—THE BATHS OF VICHY.

473 kilom. = 293 Eng. m.

The Marseilles *Malleposte* follows this route daily, but only as far as Roanne, to which place it takes 31 hours.

*Diligences* go to Lyons in 48 hours. By the Route de Bourgogne (R. 106) 52 hours are required; but the traveller may enjoy a night's rest at Châlons, and go thence by water to Lyons. *Two Diligences* daily go from Paris by rail to Orleans (R. 49), thence by Gien to Briare (R. 52).

The road, soon after quitting Paris by the Faubourg St. Marceau and the Barrière d'Italie, passes at a short distance on the rt. of *Bicêtre*, an hospital for old men, a lunatic asylum, and a penitentiary. Its name is said to be a corruption of Winchester, because it is thought to occupy the site of a country house built, 1290, by John, Bp. of Winchester; another derivation is from its owner in the 15th centy. (1410), John, duc de Berry, in Latin, "Dux Bituricensis." The oldest of the existing buildings are chiefly those constructed by Cardinal Richelieu, as an asylum for wounded soldiers, which was afterwards transferred to the Invalides.

Nearly 4500 criminals are confined here, including convicts awaiting their transmission to the hulks.

The road, which is paved, runs

through an avenue of trees along the table-land which sinks down into the valley of the Seine.

8 Villejuif. At the entrance of this town, on the l., stands an obelisk, marking the N. base of a triangle, established for the construction of Cassini's Map of France: a similar obelisk, at Fromenteau, marks the other extremity of the base.

11 Fromenteau.

Napoleon, hastening to the relief of Paris, March 30th, 1814, here met the head of the column of dejected troops who informed him of the surrender of the capital to the allies; in consequence he was forced to return to Fontainebleau, where he soon after signed his abdication. Near Juvisy our road crosses the railroad to Orleans (R. 49), and runs for some distance parallel with the branch to Corbeil.

12 Essonne, a small town, in a hollow, on the Essonne, which falls into the Seine,  $1\frac{1}{2}$  m. below, at Corbeil (R. 49), where the branch-railway terminates.

There are several châteaux near this part of the road, Villeroy on the rt., Coudray on the l.; but they contribute in no respect to adorn the road, as the parks, and lodges, and seats of England. On the l. the Seine, winding through its fertile valley, is a pleasing feature.

11 Ponthierry.

8 Chailly. The postmaster here furnishes only grey horses, of which he has 40 or 50.

About 5 m. short of Fontainebleau we enter its noble *Forest*, which extends over an area of about 23,700 hectares, the attractive hunting-ground which induced the monarchs of France, ardent lovers of the chase, to build a palace within it, and make it their favourite resort. At the Revolution of 1830, however, all the deer were exterminated. Only a small portion of the forest is occupied with full-grown trees; but here and there it has preserved noble groves of oaks and beech, of majestic size and luxuriant foliage, which may



have sheltered the jovial François I., the Bon Roi Henri IV., Louis XIV., and Napoleon. A large space is covered with broom, heath, and underwood, and with extensive plantations of black fir, from the midst of which picturesque masses of bare sandstone rock (grés de Fontainebleau) break through, and give great variety and picturesqueness to the forest scenery. The points best worth visiting are—to the rt. of the road from Paris, the *Gorges d'Apremont* and *de Franchard*, above which are remains of a hermitage, as old as the days of Philippe-Auguste, destroyed by Louis XIV.; and to the l. of the road *La Vallée de la Solle*.

“La Croix du Grand Veneur,” an obelisk on the grand route, at a place where 4 roads meet, receives its name from a spectral Black Huntsman, who was supposed to haunt the forest, and who appeared here to Henri IV., according to the story, shortly before his assassination. The forest is so intersected with roads radiating in all directions, that it is difficult to find one's way without a map or a guide.

10 *Fontainebleau*.—*Inns*: H. de France, facing the *Palace*; good; bed-rooms 3 frs., or if a family, 2 frs.; dinner 5 frs. a head, or for a family 4 frs. *M.*—La Poste (Ville de Lyon), very clean, comfortable, and moderate. *W. W. L.* and *W. M.*

This town, planted in the midst of the Forest of Fontainebleau, has swelled, under the influence of the presence and smiles of royalty, to a populous town, from a poor hamlet in the time of Louis VII., who first built a castle here (1162). It owes its consequence entirely to its

*Château Royal*, a palace of much historical interest, but not very imposing as an edifice, externally, in spite of its extent; the masses of building composing it, though they enclose 6 courts, being limited to low ranges of 2 or 3 stories, chiefly of brick. The oldest and the greatest part of the existing edifice dates from

the reign of Francis I., excepting the chapel.

Time, neglect, and violence had greatly dimmed the splendour of this venerable seat of kings, when Louis-Philippe undertook to revive it; and his judicious and splendid restorations, following closely the style and character of the different periods at which it was originally constructed, have added greatly to the magnificence and interest of the palace.

The entrance is by the “Cour du Cheval Blanc,” so called from a plaster cast of the equestrian statue of Marcus Aurelius at Rome, which Catherine of Medici set up in it, but it no longer exists. In the midst of this court, near the foot of the horse-shoe stair, Napoleon took leave of the remnant of the Old Guard, who had followed him to the last, midst his reverses, previously to his departure for Elba, 1814, an event commemorated by the well-known picture of “*Les Adieux de Fontainebleau*.”

The apartments first entered are those recently fitted up for the late lamented Duc d'Orléans, on the occasion of his marriage; they had been originally occupied by Catherine de Medici, and Anne of Austria, whence they got the name *Appartements des Reines Mères*. Here Pope Pius VII. was lodged, rejecting all the magnificence and comforts prepared for him by his imperial jailer, who desired that his forced residence of 3 years should have the appearance of a visit rather than an imprisonment. Napoleon attempted in a private interview to wring from the old man his consent to the Concordat, by which he renounced temporal power. The ceiling of the *salon*, recently restored, is very gorgeous.

In the *Chapelle de la Trinité*, whose paintings are inferior and faded, the marriages of Louis XV. with Maria Leckzinska (1725) and of the late Duc d'Orléans (1837) were celebrated. The *Galerie de François I.* is one of the most striking in the palace; perfectly characteristic of the

style of art of the period of the Renaissance; and it supplies specimens of some of the productions of the Italians attracted, at the king's bidding, to France, where they founded a school of art. Its roof is of walnut wood, its walls are richly panelled and covered with stucco, scroll-work, carvings, trophies, devices, among which the Salamander of Francis is often repeated alternating with terms, or Caryatid figures, medallions, bas-reliefs. These serve partly as frames to 14 pictures, in fresco, the work of *Rossi* (Maître Roux), a Florentine, and his scholars. One of Danaë, however, is attributed to *Primaticcio*, who is supposed also to have designed the ornaments. The paintings, now too much faded or injured to be appreciated, are chiefly mythological subjects, chosen for their allegorical reference to the life of Francis. In the first he is represented opening the Temple of Art and Taste to a crowd of blind persons; next comes a Triumph, in honour of the victory of Marignan, led by a caparisoned elephant; then the Rape of Europa; the Burning of Troy; Æneas carrying off Anchises, &c. In the centre is a bust of Francis. The paintings of the age of Francis I. were of so licentious a character, that Anne of Austria thought right to cause a great part of them to be effaced in 1653, when she became Regent, and this will account for the slight remains now existing. The *Cabinet de Travail* contains the little round mahogany table at which Napoleon, in 1814, signed his abdication, a facsimile of which, blotted and scrawled, is suspended on the walls. His bedroom remains nearly as he left it. The *Salle du Trône* is of the age of Louis XIII. and XIV., but the throne was set up by Buonaparte. The *Boudoir de la Reine* was fitted up for the unfortunate Marie-Antoinette by Louis XVI., and the metal window bolts (espagnolettes) are said to have been wrought by his own hand, and are masterly specimens of his skill in

smith's work. The *Galerie de Diane* is a long Corridor, built 1600, but decorated with paintings relating to that goddess, by modern artists. Below it runs the *Galerie des Cerfs*, which was in 1657 the scene of the atrocious murder of an Italian, the Marquis Monaldeschi, by 3 assassins hired for the purpose by Christina of Sweden, at that time residing in the château as the guest of Louis XIII. The reason assigned by her for the crime was some alleged betrayal of her secrets by Monaldeschi, who was her high chamberlain, and had enjoyed her full confidence. She subjected him to a sort of mock trial, in which she acted as judge and jury. She sent for a priest to confess him before she gave orders for his murder, which was executed in the confessor's presence. Monaldeschi seems not to have been free from suspicions of his mistress, for he wore under his dress a coat of mail, which turned the first thrusts of the sword of the assassin. The French court was content to give a hint of displeasure at this atrocity, but the queen remained here until 1659. This gallery is now subdivided into small apartments, and is not shown.

The suite of rooms called *Salons de Réception* comprises one called *de François I.*, containing Gobelins tapestries, of recent date, as brilliant as oil paintings, and a chimney-piece ornamented with Sèvres china. A second is named after *Louis XIII.*, because he was born in it; and the *Salle de St. Louis* is ornamented with a high relief of Henri IV. on horseback, over the fire-place. The *Salle des Gardes* is admirably and most richly restored: the paintings on the walls are in the style of those of the Loggie of Raphael. The chimney-piece rests on 2 figures of Strength and Peace, and in the centre is a bust of Henri IV.

The *Salle du Bal*, or *Galerie de Henri II.*, is the most splendid of the recent restorations, and one of the finest things in the palace. The



paintings have been renovated with as much care as possible, yet, it is to be feared, retain little of the master pencils of *Primaticcio*, and his pupil, *Niccolo del Abbate*, by whom they were executed. The ceiling is most gorgeous and elaborate with ornaments; the walls are of consistent richness. Everywhere appears the crescent of Diana of Poitiers, and her initial D. linked with that of her royal lover, H. The chimney-piece, glittering with fleurs-de-lis, and resplendent with marbles, was the work of the sculptor *Rondelet*.

The *Chapelle de St. Saturnin*, on the ground floor, is said to be of the time of Louis VII., and the oldest part of the palace; but the repairs of Francis I., who found it in ruins, have disguised and altered it so that little of its primitive structure can be traced. It was originally dedicated by Thomas à Becket. In its windows is some good modern painted glass, from the designs of the late talented Princess Marie d'Orléans.

The *Porte Dorée*, a splendid portal, decorated with revived frescoes, originally by Rossi, leads from the Cour Ovale to the *Allée de Maintenon*, "named by the proudest and vainest king in Europe after his plebeian wife." The Oval Court is also called Cour du Donjon, from an elevated pavillon on an archway in the style of the Renaissance, and includes the oldest part of the Palais. The other entrance to it is called *Porte Dauphine*, because built at the birth of Louis XIII., 1601.

The *gardens* at the back of the palace are not, on the whole, very remarkable to one accustomed to those of England. That called *Jardin Anglais* is bordered by a triangular pond, in the midst of which rises a pavillon surrounded by water. The "Fontaine de Belle Eau," which gave the name to the palace, rose, it is said, within the garden; but the source has been lost in forming the artificial ponds.

Philippe le Bel was born and

died at Fontainebleau; the emperor Charles V. was lodged in the Salle des Poëles, and entertained here by Francis I., 1539. Henrietta Maria sought refuge here when the cause of Charles I. became hopeless, 1644; here the Maréchal de Biron, betrayed by his agent Mafin, was arrested for conspiracy against Henri IV., 1602, and conveyed to the Bastille; the Grand Condé died here 1686, and Louis XIV. here signed (1685) the Revocation of the Edict of Nantes.

In the old *church* of the village of *Avon*, a little to the E. of Fontainebleau, the miserable Monaldeschi is buried, at a spot marked by a small square stone near the bénitier.

Farther to the E., on the borders of the Seine, at Thomery, are grown the fine *Chasselas grapes*, called *Fontainebleau grapes*. 5000 or 6000 baskets of them, packed in heather, are sent down the Seine every week in autumn, to supply the markets of Paris. The vines are trained along the houses and walls of the village, sheltered by narrow roofs from the rain. Even the streets are vineyards, and every foot of wall is covered with vines.

The *Sandstone quarries* around Fontainebleau furnish paving stones, not only for the road we are traversing, but for many others, and are transported in vast quantities down the Seine to Paris. The rock sometimes presents very pretty groups of crystals, covered over with fine sand, well known to every mineralogist.

A *steamer* goes from Valoin, a village about  $2\frac{1}{2}$  m. from Fontainebleau, down the Seine to Paris, a pleasant voyage; but the railroad from Corbeil to Paris is much more expeditious. (R. 49.)

Travellers may gain the road to Châlons (R. 106) from Fontainebleau through Moret, a very pleasant drive, and Fossard (21 kilom.). Moret has an old church, castle, and walls, and is interesting from its antiquity.

On quitting Fontainebleau our road passes an *obelisk* or Pyramid, planted in the midst of a star (*étoile*) formed by the divergence of 11 roads; among them those to Orleans, to Montereau, and to Nemours, the last of which we follow.

For 4 or 5 m. the road continues through the forest; then issues out into a plain of sand, amidst which the traveller's carriage flounders; in summer enveloped in tormenting dust, in winter sinking up to the axles in mud. The pavement ceases near

16 Nemours, a town of 3830 inhab., deriving its name from the woods (*memora*) which once surrounded it. The *old castle*, the residence of the Ducs de Nemours, of the line of Savoy, still exists, flanked by 4 towers, and includes several institutions.

The *Parish Church*, originally attached to the Priory of St. John, is a fine building. St Pierre is the oldest in the town.

Mirabeau was born at Bignon, near Nemours, in 1749.

We continue by the side of the small river Loing all the way to Montargis, through

13 La Croisière.

7 Fontenay.

14 Montargis (*Inn*: Poste;—H. de Lyon; not good to sleep at, dirty), a town of 7757 inhab., on the borders of an extensive forest, at the junction of the *Canal de Briare* with that of Orleans, by the side of which there are public walks. The castle, which for a long time formed part of the domain of the crown, and, serving as a royal nursery, was called "*le Berceau des Enfants de France*," is entirely destroyed. It was of vast extent; but was sold in 1809, to a *démolisseur*, for 60,000 fr. Over one of the fire-places in its great hall (for it had no less than 6) was a fresco painting, representing the combat between "*the Dog of Montargis*" and the murderer of its master, Macaire, which is said

to have taken place, in the presence of Charles VI., in the lists of the Ile Nôtre Dame at Paris. The sagacity of the dog not only indicated the spot where his master was buried in the forest of Bondy, but also singled out the murderer; and the king, according to the spirit of the laws of the time, directed that the cause should be tried by a duel between the dog, as accuser, and the accused. After several attacks, the dog seized his adversary, who was armed with a club, by the throat, and compelled him to confess his crime. In 1652, the Grand Condé, then a rebel against the royal authority, arriving before Montargis with a small force, summoned it to surrender. The magistrates hesitated, but Condé, taking out his watch, declared he would sack the town and slay the inhabitants if it were not given up in an hour. This produced the desired effect, and gave rise to the saying, "*que M. le Prince avait pris Montargis avec sa montre.*"

The country in which Montargis lies belongs to the district anciently called Gâtinois; it has little interest. The road is carried, in a straight line, through a dull district, to

17 Nogent-sur-Vernisson.

A road strikes off from this to Gien on the Loire (R. 52), whence a *steamer* descends to Orleans.

About 5 m. to the E. lies Châtillon-sur-Loing, in whose ancient castle the Admiral Coligny was born, 1516. After his murder on the Bartholomew's night his body was cut down from the gallows of Montfaucon, upon which it had been shamefully hung by his Romanist assassins, and conveyed by his cousin Montmorency to his wife, who concealed it for many months before she could venture to commit it to the tomb at Chantilly. Châtillon belonged to the family of Condé.

12 La Bussière has a handsome château of the 15th century. From the summit of a hill, on approaching Briare, the valley of the Loire bursts



into view: the pleasing effect of the broad winding river, and its vine-clad banks, is much enhanced by the previous barrenness and monotonous road.

12 Briare (*Inn: Poste*), a town of 2730 inhab., on the rt. bank of the Loire, has given its name to the *Canal*, begun by Sully, and completed 1642, remarkable as the first attempt to open a communication between 2 river basins by means of supplies of water stored up on the summit level (*point de partage*). It runs from the Loing at Montargis to the Seine at St. Mamet, thus opening a communication between Paris and the S. and centre of France. From Briare there is a post road along the rt. bank of the Loire by Gien (R. 52) to Orleans, where the traveller may take the railroad to Paris.

17 Neuvy. *Inns: Poste*, small, but the bed-rooms comfortable.—*W. M.* H. de Nièvre, clean. Here is the quiet, unpretending country seat of the late Marshal Macdonald, in an English-looking park. Across an undulating country, commanding, from time to time, peeps of the Loire, the road proceeds through

14 Cosne (*Inn: Grand Cerf—H. N.*), where there are iron forges; and a little way above which the town of Sancerre is seen on the opposite bank of the river.

15 Pouilly.

13 La Charité (*Inn: Poste*, pretty good—*C. B.*), an ancient town of 5,000 inhab., still partly surrounded by ramparts, flanked by watch towers, of the 14th century. It is said to have derived its name from the benevolence shown to travellers by the Monks of St. Benedict; and its arms are 3 open purses, on a field azure. Its *Church (Notre Dame)* must originally have been a very fine Romanesque building; but the nave is, in part, destroyed, and the aisles and other portions modernised. The *choir*, however, surrounded by pointed arches, on light piers with elegant capitals, and the front, are probably

as old as the latter part of the 12th century. The church, which had 5 doors (4 Romanesque and with bas-reliefs still remaining), 5 aisles, and 5 apses round the choir, was in great part destroyed by fire, 1204, and was restored by Philippe-Auguste. A ruined tower is the only remaining relic of the monastery, whose priors were so wealthy and powerful, that in the 16th centy. the Pope found it necessary to interfere and regulate the number of knights who should form their escort when they went abroad.

The road to Bourges here crosses the Loire on a stone bridge (R. 103): there is also a suspension bridge. A *diligence* goes daily to Bourges.

At La Marche are ruins of a Romanesque church, which, from the rudeness of its architecture and carved capitals, is probably as old as the 10th century. Under its E. end is a crypt.

13 Pougues.

There are mineral springs about a mile from this.

From the top of a hill surmounted in the course of this stage, a fine view is presented of the valley of the Loire and of that of the Allier, which joins it a little below Nevers; the latter river, however, is not visible.

At Fourchambault there are extensive iron furnaces and forges, perhaps the largest in France, where the iron conservatories in the Jardin des Plantes, the arches of the Pont du Carrousel, the frame-work for the roof of Chartres cathedral, and the piers for the bridge of Cussac, were cast. They employ between 2,000 and 3,000 workmen.

12 Nevers (*Inn: H. de France*), an unprepossessing, dirty, but ancient city of 17,085 inhab., chef-lieu of the Dépt. de la Nièvre, formerly capital of the Nivernois, is situated on the rt. bank of the Loire, at the confluence of the Nièvre. It is mentioned by Cæsar in his Commentaries, “Noviodunum oppidum Æduorum, ad ripas Ligeris opportuno loco posi-

tum." He deposited here his money-chest.

The oldest ecclesiastical edifice here is the *Ch. of St. Etienne*, in the Romanesque style, and very plain, both within and without, probably of the 11th centy. It is entered by descending several steps. The transepts are separated from the body of the church, opening below in a wide arch surmounted by smaller arcades. The date of the foundation of this church is proved by the charter to be 1063. *St. Sauveur*, near the Loire, another Romanesque church, is turned into a warehouse; *St. Genest*, an example of the Transition into the Pointed style, is also desecrated into a brewery.

*The Cathedral* of St. Cyr, on the hill top, somewhat heavy externally, consists of a nave and choir, built in the 13th, 14th, and 15th centuries, with an apse at both ends; that at the W. is Romanesque, and probably of the 10th century; beneath it is a large crypt. The nave and choir have not the same axes, the choir inclining perceptibly to the S. (rt.) The tower is flanked at the angles by colossal figures, in bad taste. The decoration of the interior is praiseworthy; the capitals of the columns sculptured with rich foliage, of admirable workmanship. All the statues were mutilated at the Revolution. There is some painted glass and old tapestries in the choir; and in the S. transept a rich flamboyant *doorway*, leading to a fanciful spiral staircase, is a remarkable example of what Mr. Willis calls "interpenetration," or the running of several series of mouldings into one another: these complicated interlacings pervade not only the canopy of the arch, but even the pinnacles.

The *Hôtel de Ville*, also on the height, facing an irregular place, formerly palace of the Dukes of Nevers, built by the princes of the line of Clèves, is an edifice in the flamboyant style, retaining several of its picturesque turrets and gables.

The old *walls* and *towers* of the 15th centy. still remain. One of the *town gates*, a relic of the fortifications erected by Pierre de Courtenay, Seigneur de Nevers, at the end of the 12th centy., rebuilt 1393, still exists in the *Porte du Croux*, black with age and dirt. Another entry into the town is by a *triumphal arch*, erected to commemorate the battle of Fontenay, 1746.

Behind the H. de Ville is a public garden, formerly the park of the palace.

Nevers is a thriving, busy manufacturing town; its potteries are 8 centuries old, and employ 700 persons: in its iron works, chains and cables for suspension bridges are made; the iron used is that of Berry. There is a *royal cannon foundry*, for the navy, where 125 pieces are cast annually. Not far from Nevers, the lateral canal of the Loire is carried over the Allier in an aqueduct, called *Pont Canal de Guétin*, said to be a work of magnitude, recently completed.

*Steamers* ply on the Loire to Gien and Orleans, except when stopped by ice, fog, or drought, which is not seldom, and up the Allier to Moulins in 13 hours. In some years they ascend the Loire to Decise and Digoin (H. du Commerce), whence passengers may proceed overland to Macon 40 m. by diligence and drop down the Saône, 4 days from Orleans, stopping each night. The *descent* to Orleans is made in 2 days.

The road crosses the Loire by a heavy bridge of 20 arches on quitting Nevers, and, leaving that river on the l., proceeds to ascend the valley of the Allier, its tributary. The scenery between Nevers and Moulins is on the whole very pleasing, the country much enclosed with hedge-rows, and generally fertile. The river Allier is seldom seen, concealed as it is by trees, in the flat valley through which it passes.

12 Magny.

11 St. Pierre le Moutier. Near this is a large pond. Hence a road



strikes off to Bourges and Orleans (R. 104).

8 St. Imbert.

10 Villeneuve-sur-Allier (Dépt. Allier).

12 *Moulins* (*Inns*: H. de Paris, best, and very good;—H. d'Allier, dirty;—Lion d'Or, pretty good), a cheerful town, without the activity of much trade or commerce, pleasantly situated on the rt. bank of the Allier. It is chef-lieu of the Dépt. d'Allier, and contains a population of 15,231.

It is a comparatively modern town, and has no fine buildings. The *castle* is reduced to a square tower, of the 15th centy., called *La Mal Coiffée*, and some buildings erected by Cath. de Medicis.

The *Cathedral of Nôtre Dame* consists merely of a lofty choir in the Florid style of the 15th centy.: its vaulted roof is elaborately groined. It contains an old painting of the Virgin and Child, the two shutters of which, now detached from it, and hung against piers, bear portraits of Pierre II., Duc de Bourbon, and his wife, Anne of France, attended by their patron saints, attributed to *Ghirlandajo*.

In the *Chapel of the College* is the monument of Henri Duc de Montmorency, who suffered, under the heavy hand of Richelieu, for having conspired against him and his master, Louis XIII., and was executed at Toulouse, 1632. His widow, Marie Orsini, conveyed his remains to this chapel, then attached to the Convent of the Visitation, of which she became superior, spending in it the rest of her days. The monument, attributed to an Italian sculptor, *Agheri*, consists of the reclining statue of the duke, in Roman armour, resting on his helmet, with his duchess beside him in an attitude of grief and resignation; the expression of profound sorrow in her countenance is perfect, and the draperies are very beautifully executed. On either side is an allegorical figure—*Valour*, a sort of

*Hercules*, and *Liberality*, a coarse female. The fact of this monument being in honour of a man beheaded for conspiring against a king preserved it from demolition at the Revolution.

Marshal Villars, the opponent of Marlborough, and Marshal Berwick, natural son of James II. by Arabella Churchill (Marlborough's sister), who won the battle of Almanza from the English in Spain, were both born here.

The watering-place of *Bourbon l'Archambault*, a town of 3017 inhab., frequented on account of its mineral waters, is about 19 m. W. of Moulins. The waters are saline, and are supplied by a hot spring, and a cold spring called *Source de Jonas*. There is a bath-house in the middle of the town. There are very considerable and picturesque remains of the ancient *castle* of the early Sires de Bourbon, and a fragment of the apse of the *Ste. Chapelle*. Diligences run daily from Moulins to the Baths in summer, and the road thither passes through *Souigny*, a poor village 5 m. from Moulins, containing an *Abbey Church*, which is one of the most remarkable Gothic monuments in the province for size. The central nave, the apses at the E. end, and the crypt below the choir, date from the 11th cent.; the more recent portions from 1446, when the church was rebuilt. The *nave* is flanked by double aisles, the outer ones nearly as broad as the centre. In the N. aisle is a curious bas-relief in the Byzantine style. The *Chapelle Vieille*, on the S. side, is separated from the choir and transept by a stone screen, beautifully carved with flamboyant tracery. It encloses the monument of Louis, Duc de Bourbon, and Anne his wife, bearing their recumbent figures, of white marble, sadly mutilated by the Revolutionists. A recess, or niche, in the wall opposite, displays, amidst most rich decorations of flamboyant tracery, the word "Espérance," the motto of the Order

of the Thistle, founded by the Duke. This chapel, the greater part of the choir, the vaults, and windows of the nave, 4 divisions of the outer S. aisle of the nave, and the remains of the cloisters on the S. side of the chapel, are supposed by M. Merimée to have been built 1441. On the N. side of the choir is *La Chapelle Neuve*, similarly decorated, and even more injured by the Vandals of 93, containing the tombs of Duc Charles, and his wife, Agnes de Bourgogne. The date of this chapel is somewhere about the end of the 15th or beginning of the 16th century.

All persons who take an interest in Gothic architecture should visit Souvigny from Moulins: in spite of its mutilations, it is a very interesting church. The Auberge de la Poste was the ancient Priors' palace. At *St. Menoux*, not far from Souvigny, is another ancient church, once attached to a Benedictine abbey, but much decayed. The choir is the most interesting portion, and a good example of the florid Romanesque.

Some cutlery, of an inferior kind, is made at Moulins; the manufacture has much fallen off.

At Moulins the very interesting road through the Limagne, Clermont, and the Volcanic district of Auvergne, strikes off up the valley of the Allier (R. 109). *Diligences* run daily, and a *Malleposte* to Clermont and Montpelier. It is possible to go this way to Lyon by Montbrison, and to Marseille by Le Puy and St. Etienne, though, in both cases, it is a *détour*.

*Diligences* go hence also to Vichy (see below). No one will quit Moulins without thinking of Sterne and his Maria, the scene of her melancholy story being laid here.

15 Bessay.

15 Varennes.—Poste; a comfortable little Inn.—*C. B.*

11 St. Gerard-le-Puy. From this a road turns off to the fashionable watering-place of *Vichy*, on the Allier, 61 kilom. from Moulins = 39¼ Eng. m., through a rich but unpicturesque

country, the only objects of interest being the Puy de Dôme and Mont Dore; visible the whole way.

*Vichy* (*Inns*: every one lives in boarding-houses; of these there are 6 or 8.—H. Guilliermen, good.—*L.*; H. de Corneil; civil people;—H. de Paris is most frequented by Parisians. In none is the accommodation first-rate. The guests live together, taking their meals in public, consisting of a breakfast à la fourchette at 10, and dinner at 5. Nobody is allowed to be served in his own room, unless illness prevent his appearance in public.)

Vichy consists of an old town, seated on the rt. bank of the Allier, in nowise remarkable, and of a new external quarter, or suburb, of handsome lodging and boarding houses, connected with old Vichy by a fine *promenade*, shaded by avenues of plane-trees. This is the watering-place, now one of the most frequented in France; and here rise the *mineral springs*, of acidulous alkaline water, which has been compared with hot soda-water, their principal ingredients being carbonate of soda and carbonic acid gas, and their peculiarity the small quantity of iron, in proportion to these ingredients, which accompanies them. They operate with advantage on the digestive and urinary organs, and are efficacious in long-standing stomach disorders, obstruction and enlargement of the spleen.

There are 7 springs, varying in temperature from 86° to 111° Fahr., but differing only slightly in the proportion of the same ingredients; 3 of them are received in the *bath-house* (*Batiment Thermal*), a very handsome building, faced on the ground floor by a long colonnade, containing, in the upper story, a cabinet de lecture and ball-room; and in the lateral ranges 72 baths, tolerably well appointed, and 4 douches. The principal source, or the one most used for drinking and exportation in bottles, is that called *Grande Grille*. The water, received into stone basins,



has the appearance of boiling, from the quantity of gas which bubbles up through it. The season begins here in the early part of May, and ends by the middle of September.

The routine of a day is as follows:—As early as 6 the crowd assembles to drink the waters, which takes up an hour or two: 10 is the hour of breakfast: to this succeeds, after an interval, the bath, for those who are recommended to bathe, each individual having his hour and turn marked upon a card. The table-d'hôte dinner takes place at 5; and in the evening the company assemble in the drawing-room (salon) of the hotel, where cards or music afford resources for passing the evening. Precedence is determined by the order of arrival, those who have been longest resident occupying the upper seats at table, &c. There are occasional balls at the rooms, but, as the physicians are masters of the ceremonies, they begin at 8½, and usually end before 11: raking is not allowed. Frequent collections (quêtes) are made at the instigation of the curé, for the good of some charity, or parish school, and the poor-box is commonly carried round by a lady and gentleman.

The situation of Vichy is agreeable, but not striking, in an open and highly cultivated country, the celebrated Limagne d'Auvergne (R. 109); in fact, Vichy's main attractions are its waters.

Some pleasant *excursions*, however, may be made in the neighbourhood, and many troops of *donkeys* are kept for the use of the guests.

The valley of the *Sichon* affords pleasant walks or rides.

More distant expeditions may be made to the *Château of Effiat*, a building of the 17th cent., now dilapidated, but still inhabited, and retaining its formal garden flanked by fosses. It was erected by Marshal Effiat, who was ambassador to England to negotiate the marriage of Henrietta Maria with Charles I., and

father of Cinq Mars, beheaded by Richelieu at Lyon.

The *castle of Randan*, in which Bayard tarried so long, paying court to its noble *Châtellaine*, now belongs to Madame Adelaide, sister of the King of the French, who has become the Lady Bountiful of the neighbourhood.

*Diligences* go daily to Moulins, on the way to Paris; to Roanne, on the way to Lyons; to Clermont (R. 109), &c.

The road to Lyons has now quitted the valley of the Allier, and enters on a hilly country. The mountains of Auvergne appearing to the S.W., and those of Forez more to the E., form features in the landscape.

10 La Palisse.—*Inn*: Poste—*C. B.* Between this and la Pacaudière the road traverses a hilly tract.

The road crosses a deep ravine by a very lofty bridge, called Pont de la Vallée, shortly before entering

8 Droiturier.

7 St. Martin d'Estréaux is seated on a height, in the midst of a barren and hilly country.

7 La Pacaudière. Here we are once more in the valley of the Loire, though that river is not reached until, after passing

12 St. Germain l'Espinasse, we arrive at

12 Roanne, (*Inns*: H. du Midi, new and good—*H. N.*; Poste, bad and dirty—*L. F. M.*; H. de Flandres), a town of 12,000 inhab., deriving importance from its situation on the l. bank of the Loire, at the point up to which it is navigable against the stream as well as downwards. It has a great transit trade: the manufactures of Lyons, the iron and coal of St. Etienne, the productions of the S. provinces of France, and the imports from the Levant, conveyed hither from the Rhône by railway or canal, are transported hence, down the Loire, to Nantes, or through it, and the Canal de Briare, to the Seine and

Paris. There are also considerable manufactures of cotton in the town and its neighbourhood. There is an old *Ch.*, *St. Etienne*, rebuilt 1549, near the château, and a *bridge* over the Loire which cost 3 million francs.

The *railroad* from Roanne to St. Etienne and Lyons is described in R. 119; it is very inferior, as a line of conveyance, to those in the vicinity of Paris. The *malleposte* to Marseilles here turns out of our road, and proceeds, by Montbrison, to St. Etienne and Valence (R. 119). The Loire is crossed by a fine stone bridge on leaving Roanne, and the road proceeds across the plain for some distance parallel with the railroad. About half way to

17 St. Symphorien-en-Lay, the ascent of the Montagne de Tarare begins. The ascent has been made comparatively easy by a truly Alpine road, carried up in a series of zigzag terraces, sweeping round the shoulders of the hills, and crossing the gorges on handsome bridges of masonry, protected, at the sides, by stone studs like milestones.

15 Pain Bouchain. Near this is the summit of the Pass, about 3,000 ft. above the sea. You reach the foot of the descent at

12 Tarare (*Inn*: H. de l'Europe, beds clean; fare middling—*W. M.*; le Soleil), a wonderfully thriving manufacturing town, of 7,762 inhab., seated in a narrow valley. The weaving of *muslins*, remarkable for their fineness, is the staple branch of manufacture, and it is calculated that between 3 and 4 millions of pieces are produced annually. It is said that as many as 52,000 persons are employed in the town and surrounding country on this branch of industry. The weavers ply their trade in damp cellars, which are neither floored nor warmed by fire, in order to keep up the moisture necessary for weaving fine webs, and to prevent the breaking of the thread.

The road continues along the narrow valley of the Tardine from Tarare to

11 Arnas, where the country opens out.

19 Salvagny.

A few m. to the l. of the road is the copper mine of Chessy, which produced the beautiful blue ore of copper so well known to the mineralogist, but it is now abandoned.

“As you approach Lyons, the road becomes extremely fine, and immediately above the city you look down upon it, extending along the banks of the two great flowing rivers, surrounded by an amphitheatre of hills. Handsome country seats, gardens, and vineyards are dotted over the landscape, bespeaking the wealth and prosperity (in a mercantile sense) of the district. As the town is entered by the quay of the Saône, it assumes a most picturesque character, the grey rough rocks forcing themselves, as it were, into the city, protruding between the lofty houses,—a singular mixture of nature and art. One of these rocks is the celebrated Pierre Scise.” See p. 378.—*F. P.*

14 LYONS (French, Lyon).—*Inns*: H. de l'Europe; H. d'Univers, rue de Bourbon, new and very comfortable; kept by an Englishman; a first-rate hotel; H. de Rome, in the Place St. Jean, Cathedral Square, quiet, comfortable, and clean; no table-d'hôte; dinner à la carte, at 4 or 5 fr. Near the Saône and Place Bellecour, H. du Nord, a really well kept house; cuisine good; H. du Parc.

There are few more stately cities, in external aspect, in striking situation, seated as it is on two great rivers, the Rhone and Saône, or in the lively air of bustle and commerce diffused through its interior, than Lyons, the second city of France, the chief seat of manufactures, the focus where the commerce of the North and South converges. It is a fortress of 1st class, and chef-lieu du



Dépt. du Rhône. Its population amounts to 200,000, including its suburbs.

The appearance of grandeur, however, is limited to its quais, bridges, and noble rivers, to the steep and commanding heights of Fourvières on the rt. of the Saône, and to the two Places Bellecour and des Terreaux; it is deficient in fine streets and long open thoroughfares. The interior is one stack of lofty houses, penetrated by lanes so excessively narrow and nasty as not to be traversed without disgust.

It is worth the stranger's while to remember, as a clue to find his way through this labyrinth, that the streets whose names are written on black plates run parallel with the course of the two rivers, those on yellow plates at rt. angles to them.

Lyons stands on both banks of the Saône and Rhône, but the largest part occupies the tongue of land between these two rivers, extending from the heights covered by the populous suburb of La Croix Rousse, the residence of the silk-weavers and the hot-bed of insurrection, down nearly to the confluence of the rivers, towards which the quarter of Perrache has pushed forward buildings. On the l. bank of the Rhône are the suburbs of Les Brotteaux, the scene of revolutionary executions, and of Guillotière, where a new town is rapidly rising; on the rt. bank of the Saône, the suburbs of Vaise, through which you enter Lyons from Paris, of Fourvières, mounting up the face of a slope so abrupt as scarcely to be accessible for wheel carriages, of St. Irénée behind it, and of St. George, lower down, near the water-side. These dry topographical details will be best understood when the traveller has scaled the Height of *Fourvières*, which *he should do the first thing after his arrival*, on account of the view it commands. To reach it you pass between the Palais de Justice and the cathedral, ascending the steep and narrow streets above

the cathedral, which are very foul and stinking.

You pass behind the huge straggling hospital of *Antiquailles*, occupying the site of the Roman palace in which Claudius and Caligula were born, now assigned to the reception of 600 patients, the most miserable wretches of this populous city, afflicted with madness and all sorts of incurable and disgusting diseases, to the care of whom 27 Frères Hospitaliers and 67 Sœurs devote their lives. Up narrow lanes, as steep as stairs, partly in zigzag, and in front of a row of shops, in which rosaries, medals, pictures, candles, and wax models of different parts of the body for suspension in the church, are displayed before the eyes of devout pilgrims, you reach

The *Ch. of Nôtre Dame de Fourvières*, only remarkable for the quantity of ex-votos, paintings, &c., to the number of 4,000, with which its walls are covered, offered to the altar of the miracle-working figure of our Lady of Fourvières, whose intercession is stated, by an inscription over the entrance, to have preserved Lyons from the cholera. Close beside the church a speculator has built a *tower*, by way of observatory, 630 ft. above the Saône, and from it, even better than from the terrace beside it, a most magnificent view may be obtained. The city of Lyons appears unrolled as a map beneath your feet, including the two noble rivers visible (nearly) to their junction, the Saône crossed by 8 or 10 bridges, the Rhône by 7. Beyond it stretch fields, plains, and hills dotted over with country houses, and the distance is closed (in clear weather) by the snowy peak of *Mt. Blanc*, nearly 100 m. off, this being one of the farthest points from which it is seen. More to the S. the Alps of Dauphiné, the mountains of the Grande Chartreuse, and the Mont Pilas appear. The ch. of Nôtre Dame is seated on the very summit of the hill, and is said to occupy the site, and retain the name, of the Roman *Forum*

*Vetus*, built by Trajan. Numerous but inconsiderable Roman remains have been brought to light on the hill, the principal being an amphitheatre within the *Jardin des Plantes*, and a fragment of an aqueduct.

In the faubourg St. Irénée, behind Fourvières, is the *church of St. Irénée*, an uninteresting modern building, but erected on the grave of that saint and martyr, and upon subterranean vaults, in which St. Polycarp preached, at the age of 86, and where, it is said, the early Christians met for prayer, and were afterwards massacred, by order of Septimius Severus, A.D. 202. In the midst of this crypt, an ancient Romanesque building, resting on plain columns, is a sort of well, down which the bodies of the Christians were thrown, until it overflowed with the blood of the 9,000 martyrs, for such is the number reported to have fallen, according to the legend; and a recess is filled with their bones.

The upper church was destroyed, and the crypt much injured, by the Calvinists, 1562.

The *Cathedral of St. Jean Baptiste*, on the rt. bank of the Saône, has 4 towers, two of which flank the W. front, and two more massive but shorter, form the transepts. The W. front is the most recent part, not having been completed until the reign of Louis XI.: its bas-reliefs and statues are curious, but they have suffered from the Calvinistic iconoclasts of the 16th century; these injuries have usually, but unjustly, been attributed to the infamous Baron des Adrets, since he was not in Lyons at the time when they were perpetrated. "The greater portion of the cathedral is of the age of St. Louis; but, though Gothic, the attentive observer will remark some curious imitations of Roman ornaments, particularly in an incrustated band or frieze of red and white marble, composed of masques and foliage, copied from the antique, with considerable exactness, running round the principal apse. The painted

glass windows are remarkably fine. The centre tower, which opens into the cross, contains a rose window, which produces a peculiarly good effect. In a side aisle, on the floor, stands the once celebrated clock, made or built by Nicholas Lippeus of Basle in 1508. It is very much like that at Strasburg, exhibiting various processions of little figures, the courses of the sun and moon, and the like; but it is quite out of repair; and to be called in action it requires the administration of half a franc to the sacristan."—*F. P.* "The clerestory presents an interesting series of windows, giving, in order, the gradations from plain lancets and circles, without foliation, or even a containing arch, to the perfect mullioned window with flowing tracery" (*Petit*), a good lesson for the student. *The Bourbon chapel*, built by the Cardinal Bourbon and his brother Pierre de Bourbon, the son-in-law of Louis XI., is remarkable for its ornaments, principally flowers and foliage of the most delicate sculpture. Amongst them the thistle or *chardon* is repeatedly introduced; a pun or rebus, allusive to the *cher-don* which the king had made to Pierre in the gift of his daughter."

"The see of Lyons, the religious metropolis of the Gauls, ascends to the era of the primitive church, its founders having been St. Pothinus, an Asiatic Greek, in the 2nd century, and St. Irenæus, disciples of the apostles, both of whom suffered martyrdom here. Before the Revolution, the cathedral enjoyed many high privileges. The canons had the title of Counts of Lyons: and in the service many ancient usages are retained; amongst others, yellow or native wax alone was used for the tapers, and no instrumental music was allowed. Adjoining the cathedral is a building, part of the ancient archiepiscopal palace, which seems to be of the 9th century. According to popular opinion, Becket lodged here; but as it is not known that he visited Lyons, though Anselm did, the two archbishops may



have been easily confounded; several anthems and hymns yet sung in the cathedral are said to have been composed and set to music by Becket.”—*F. P.*

On the quai, a little above the cathedral, opposite the Pont Seguin, destroyed by the flood of 1840, is the new *Palais de Justice*, a handsome building, faced with a colonnade of 24 pillars. Baltard is the architect.

On the opposite side of the Saône, about  $\frac{1}{2}$  mile lower down, at the end of a street running up from the Pont d'Ainay, is the *Church of the Abbey of Ainay*, a very remarkable monument, both of Pagan and Christian antiquity. “The centre of the cross is supported by 4 ancient granite columns, supposed to have belonged to the altar erected at the confluence of the Rhône and Saône (which originally met close to the church), in honour of Augustus, who resided for 3 years at Lyons, by the 60 nations of Gaul. In the representation of that altar existing on medals, there are only 2 pillars, one on either side of the altar, each supporting a statue of Victory; but these lofty columns, each of a single shaft, having been cut in two, now form the 4 supporters, of somewhat low proportions, to the central lantern.” The measurements of the diameter of the sections in each pair show how they were joined. Their capitals, an imitation of the Corinthian, are mediæval. The original capitals were Ionic. The church, as a building, was in existence before 937 (its foundation as a monastery was much earlier), and these are possibly of that æra. The outer tower is probably Carolingian; but the building has recently been restored, in some parts awkwardly, so as to prepare much perplexity for the antiquarians who are yet unborn. Beneath the sacristy are the *dungeons* in which Pothinus and Blandina were immured previously to their martyrdom.

“The sufferings of these witnesses for the truth rest upon a document

of great authenticity, the Epistle of the Churches of Vienne and Lyons to the Brethren in Asia and Phrygia. Pothinus, chosen bishop of Lyons, and then 90 years of age, was sent back into this dungeon, where he expired after two days' confinement. For Blandina, who was a converted slave, greater tortures were reserved. After being scourged and exposed to the fire in an iron chair, she was delivered over to the beasts in the amphitheatre. These events took place during the persecution under Marcus Antoninus, the implacable enemy of Christianity, A.D. 177.

“These dungeons are most gloomy cells, without light or air, below the bed of the adjoining river. The apertures by which they are entered are so low that you must creep into them upon hands and knees. They adjoin a crypt which, until the Revolution, was used as a chapel: traces of Roman work are here distinctly seen.

“The middle-age name of Ainay is *Athenacum*, and most of the historians of Lyons are unanimous in supposing that it is built upon the site of the *Athenæum* founded by Caligula, and the buildings of which joined to or included the Augustan altar. It was a school of debate and composition, in which pleaders competed for the prize. Great honours were bestowed upon the successful competitors; but those who failed were liable, according to the statutes of the imperial founder, to the most severe and humiliating punishments—to be chastised with a ferula or thrown into the river, and to obliterate their own compositions by licking them out with the tongue: hence even the most gifted would approach the altar with trepidation and fear” (*F. P.*); and hence the line of Juvenal—

“Palleat, ut nudis pressit qui calcibus anguem,  
Aut Lugdunensem rhetor dicturus ad aram.”

Some other remarkable churches,

&c. have been spared;—*St. Nizier*, a splendid example of the flamboyant Gothic. The bosses of the arched roof are curiously pointed. The portal, in the style of the Renaissance, is a work of the architect Philibert Delorme, in the 16th century. Several hundred of the insurgents in the insurrection of 1834 were pursued within the walls of this church by the soldiery, and killed there.

*Ste. Pierre* has a curious Carlovingian portal, in perfect preservation, though barbarously coated with oil-paint.

The *Church of the Cordeliers* is strikingly monastic.

The square called *Place des Terreaux*, one side of which is occupied by the Hôtel de Ville, and another by the Museum, or Palais des Beaux Arts, was the scene of the execution of Cinq Mars and De Thou: "they perished on the scaffold, the one like a Roman, the other like a saint;" thus atoning for their share in a conspiracy against the unrelenting Cardinal Richelieu. Here also, in 1794, the guillotine was erected, and actively kept at work until the square became so flooded with human blood, that the Terrorist chiefs, fearing to rouse the sensibility of the people, resolved on a wholesale massacre, by musketry and grape, in the Brotteaux, on the other side of the Rhône.

The *Hôtel de Ville* (1447-55), with its lofty roofs and bold projections, is not unworthy of the ancient consulate, who, before the Revolution, were a most influential and useful magistracy, though much reduced in authority by Henri IV. In this building sat the Revolutionary Tribunal which, under Challier, before the siege of Lyons, and after it under Couthon, Collot d'Herbois, and Fouché, despatched so many thousand victims to perish by the guillotine and the fusillade. Collot d'Herbois, the chief of these tyrants, had been an actor, and in that capacity had been hissed off the stage

of Lyons. He vowed vengeance against the town in consequence of this affront; and amply did the savage glut his desire for it.

The *Palais des Beaux Arts*, or *Museum*, in the ancient convent of St. Pierre, contains some very remarkable specimens of Roman antiquity. A *Taurobole*, or square altar, 5 ft. high. "The *Bronze Tables* containing the speech made by Claudius, when Censor, in the Roman senate (A.D. 48), on moving that the communities of *Gallia Comata* should be admitted to the privileges of the citizenship of Rome—an act of the highest national importance. They are beautifully cut, and the letters are as sharp and as legible as if they had just issued from the engraver's hands. In these engravings we have probably the very words or composition of Claudius himself. They were discovered in the year 1528, on the heights of St. Sebastian. Claudius was born at Lyons on the very day when the altar of Augustus was consecrated.

"In contemplating a relic of this description in the city to which it belongs, we become sensible how much of its interest would be diminished by depositing it in any situation out of its proper locality. A very fine mosaic pavement, representing the *games of the Circus*, in which the Spina, and the gates whence the chariots started for the race, are fully given, was found at Ainay, 1800. Several other pavements were found in or near the city, including one of Orpheus and the Beasts, brilliant in colour, with many sepulchral and other inscriptions."—*F. P.*

The legs of a bronze horse, extracted from the bed of the Saône, are remarkable.

In the *Picture Gallery* are several paintings of celebrated masters.—*Pietro Perugino*: The Ascension, the heavenly choir in the sky, the Apostles and Virgin below; one of the best works of the master; given to



the city by Pope Pius VII. *Rubens*: St. Francis, St. Dominic, and the Virgin interceding for the world, against which the Saviour is about to launch his thunder; finely coloured, but coarse, profane, and offensive in the composition. The Adoration of the Magi. *Spagnoletto*: St. Francis after Death, as placed in the tomb by Gregory IV.; the ghastly glare of the eye and rigidity of the frame are truly, but somewhat painfully, represented. *Caracci*: The Baptism in the Jordan. A Portrait of a Canon of Bologna. *Guercino*: The Circumcision. *Teniers*: St. Peter delivered from the Prison, or rather soldiers gaming in the guard-house; for what is called the subject is rendered merely an accessory. *Perugino*: St. Gregory and St. James. *A. Dürer* (?): The Emperor Maximilian and the Empress. A Portrait of Jacquart, inventor of the silk-loom named after him, by *Bonnefonds*. Portrait of *Mignard*, by himself. Portrait of William III. of England. *Van Heem*: A View of the Rock and State Prison of Pierre Scise, now destroyed, is curious.

A School of Design established here has been attended with remarkable success in improving the manufactures of Lyons. A portrait of Jacquart, in imitation of an engraving, but produced by the loom invented by him, is both a monument to his memory and a proof of the skill attained by his townsmen. Copies of the Madonna of the Seggiola, and of a Crucifixion, have also been executed in the same style. Here is also an academy of the fine arts. The productions, judging at least from two exhibitions, are not above mediocrity.

In one of the apartments are placed the busts of some of the illustrious natives of Lyons, as Philibert Delorme, architect; Bernard Jussieu, the botanist; Jacquart, inventor of the silk-loom; Suchet, marshal of France; Poivre, governor of L'Ile de France, who introduced pepper.

The *Museum of Natural History* is very creditable to the town, by its extent; and most useful and instructive to the student, by its *excellent systematic arrangement*, according to orders, families, genera. It is tolerably well filled in all the departments of natural history; but where specimens of a genus are wanting, the place is supplied by a drawing.

Among the *minerals* are a very complete and valuable series of *marbles*, antique and modern, of Italy, France, &c.; a suit of the blue and green copper ores from the mine of Chessy, on the Saône, now abandoned. The mineralogical and geological topography of France is illustrated in a collection of rocks and fossils from the different departments.

"The *Bibliothèque Publique* is the best provincial collection in France. The consulate of the city took great pride in this institution, which was originally annexed to the college. It contains many manuscripts, and about 80,000 printed volumes. Amongst them are many valuable and all but unique articles of the early printers—the delight and despair of the bibliomaniac. During the siege of Lyons in 1793, the library suffered greatly from the bombardments and the cannonade to which the city was exposed. The roof of the library was beat down, large heaps of the books were covered by the rubbish, and it might have been wished that they could have continued so during the reign of the Convention. Some were carried to Paris; others stolen. The foregoing were at least preserved for literature. But the library was turned into a barrack; the National Guard lighted their fires and boiled their coffee with the volumes, which they employed in preference to any other combustible; and a Juge de Paix in a different canton caused a cart-load to be brought to him every decade for the same purpose; for, said he, they are all books of devotion, and we do not exactly seek truth in the age of reason."—*F. P.*

In the suburb of Vaise, on the rt. bank of the Saône, on the line of the old fortifications, and just above the road leading to Paris and Châlons, rise the scanty remains of the escarped rock of *Pierre Scise*, or Encise, so called from its having been cut through by Agrippa, in order to open a military road. It is now used as a quarry, and the proprietors are carting off the picturesque and beautiful by wholesale. Upon this rock stood a castle, formerly the dwelling of the Archbishops, and of which the central tower was remarkable for its symmetry. It was demolished during the Revolution, perhaps in consequence of the odium which it acquired by having been anciently employed as a state prison, and also because it was offensive to the inhabitants from its domineering over the town. In this castle Ludovico Sforza, called Il Moro, was confined by Louis XII. ; he was afterwards removed to the castle of Loches, where, being occasionally confined in an iron cage, he sank under the misery that he sustained. So closely was he incarcerated, that the exact time of his death is unknown : some writers place it in 1508, others in 1510. (See R. 56.)

Here also Card. Richelieu shut up M. de Cinq Mars, for conspiring against his authority, and corresponding with Spain ; and De Thou, the son of the historian, for not betraying the conspiracy.

Farther on, upon the opposite (l.) bank of the Saône, is an antique castle, surmounted by a lofty tower, called *Tour de la Belle Allemande*, from a tradition of a German damsel being immured in it while her beloved was shut up in Pierre Scise. He, as the story goes, having escaped, by leaping into the Saône, was swimming across the river to join her, when he was perceived by the castle guard, and shot at the foot of the tower.

“The charitable institutions of Lyons are numerous. The principal one is the *Hôtel Dieu*, on the quay facing the Rhône, between the Pont

de l’Hôtel Dieu and Pont Guillotière : it is the most ancient, perhaps, now subsisting in France, having been founded by Childebert and Ultrogotha, his queen. The present edifice, built by Soufflot, has a splendid new front. The plan of the building is that of a cross, and it is arranged upon the Panopticon principle. An octagon altar is placed under the central dome. From this the wards radiate, and the crucifix and the officiating priest can be seen from every bed in the hospital. The chambers are very lofty and spacious. Amongst other attendants are 150 sisters of charity.”—*F. P.*

This building was destroyed during the fatal siege of 1793, when filled with wounded, by shells and red-hot shot : a black flag, hoisted upon the building to avert the deadly shower, seemed only to attract towards it a larger share of the fire ; and after the flames had been in vain extinguished 42 times, it was finally consumed. From an inscription discovered not long since in a courtyard of the Hôtel Dieu (once a Protestant burial-ground), it would seem that Mrs. Temple, daughter of Young, author of the “Night Thoughts,” who died at Montpellier, 1736, was actually buried here. By the archives in the H. de Ville, it appears that 729 livres were paid for permission to inter her.

On the quay of the Rhône, below the Pont Guillotière, is the still larger *Hospice de la Charité*.

The *Place Bellecour*, one of the largest squares in Europe, perhaps too large, covering nearly 15 acres, ornamented in the centre by a statue of Louis XIV., has been rebuilt since 1793-94. On the capture of Lyons by the republicans, the total annihilation of the town, and of all its chief buildings, public and private, which had escaped the 11,000 red-hot shot and the 27,000 shells hurled against it, during a bombardment of several weeks, were decreed by the National Convention, in order to humble the



pride of the Lyonnais. The demolition of the houses of the Place Bellecour was directed by Couthon, who, borne on a litter, on account of illness, gave the signal by striking with a little hammer on the door of each condemned house, repeating the words "Je te condamne à être démolie au nom de la loi." A mob of discharged workmen and others of the lowest classes then hastened to carry into effect these commands. Lyons, the chief manufacturing town of France, was reduced to a heap of ruins, and the expense of merely pulling down amounted to 700,000*l.*—a sum larger than that which built the Hôtel des Invalides at Paris. Thus was fulfilled the decree of the Montagne, that "Lyons should no longer exist," that "even its name should be effaced," and that of "Commune Affranchie" substituted. This decree enacted also that a column should be erected on its ruins to bear these words:—

"Lyon fit la guerre à la Liberté ;  
Lyon n'est plus."

*The Siege of Lyons*, which preceded this wanton razing of the town, was undertaken by the National Convention, to punish and bring back to their side the people of Lyons, who, irritated by the vexations, and horror-stricken by the tyranny, of the club of Terrorists, and the municipality, had risen up in arms against them, and made prisoner, tried, and executed their president, the infamous Challier, a Savoyard, and once an abbé. In consequence 60,000 troops were collected from all quarters against this devoted town. Its defence was intrusted to about 30,000 of her citizens, who cheerfully manned the walls, resolving that their oppressors should not capture the place without marching over piles of ruins and heaps of dead. After an heroic resistance of 63 days, during which acts of the utmost bravery and scenes of the direst misery were exhibited, after all the surrounding heights had been gained by the ene-

my, and 30,000 persons had perished within the walls, famine began to arrest the power of all further resistance, and the town was yielded, Oct. 9, 1793.

The *Suburb of Perrache*, between the Saône and Rhône, receives its name from the architect who conceived and executed the plan of removing the confluence of these rivers, which, before 1770, were united a little below the church of Ainay, to its actual situation. He effected this by strong embankments; and the greater portion of the land thus gained is either built over, or is prepared for building. Here is situated the terminus of the railroad to St. Etienne. (R. 118.)

Until the commencement of the present century, the Rhône merely skirted the city, and Lyons may be said to have been confined to its rt. bank; or, as Gray in his letters humorously describes the confluence, "the Saône goes through the middle of the city in state, while he (the Rhône) passes *incog.* outside the walls, but waits for her a little below."

Since that time the l. bank of the Rhône has been covered over with houses, forming the suburbs of Brotteaux and Guillotière. Several streets of fine and lofty houses are now building here, and a new bridge in construction over the Rhône will connect them directly with the business quarter of the city. At the back of these new constructions an embankment has been formed, and a military canal dug, protected by forts, so as to serve the double purpose of securing the neighbourhood from the inundations of the Rhône and the attack of an enemy. In the *Brotteaux*, at the extremity of the street called *Avenue des Martyrs*, a *monumental Chapel*, in the form of a pyramid, perpetuates the memory of the miserable victims of one of the worst atrocities of the Revolution. After the siege and capture of Lyons, as narrated above, the guillotine proved too slow an instrument of slaughter

of the accused or suspected victims condemned, with or without cause, to suffer by the mandate of the revolutionary tribunal. The bloodthirsty and infamous tyrant Collot d'Herbois therefore conducted the prisoners, by 60 at a time, under the escort of soldiers, to a field beside the granary of La Part Dieu. Here, with their hands bound behind their backs, they were fastened by ropes to a cable attached to a row of willows; and at the end of the line two cannons, loaded with grape-shot, were so placed as to enfilade the whole. At the first discharge few fell dead; a second and third, directed against the poor wretches, mutilated, wounded, and deprived of their limbs a great number, but left the greater part still alive, rending the air with their agonising shrieks, so that the soldiers were obliged to finish the work with their swords or the butt end of their muskets. So laborious was the task, and so imperfectly performed, that some were found breathing 12 hours after, when their bodies were covered with quicklime, and thrown into a hole for burial. These heart-sickening massacres were repeated, by the aid of grape-shot or musketry fired by platoons of soldiers, until the number of victims amounted to 2,100. Collot d'Herbois and Fouché looked on while these deeds were done; and the former, when informed, on one occasion, that a band of prisoners about to be led forth to death exceeded by two the number condemned for execution, replied, "Qu'importe? s'ils passent aujourd'hui, ils ne passeront pas demain."

The miscreant Collot d'Herbois, exulting in his atrocities, forwarded from time to time to Paris reports of his proceedings to the Convention, from which these are extracts. He says of himself and colleague, "The sword of the law is falling on the conspirators at the rate of 30 at a time; that they have already despatched 200, and they were occupied, in the most unceasing manner,

in the discharge of their functions." 3 days after he writes, "I send you a second list; the number now amounts to 300. A more grand act of justice is preparing; 400 or 500, with whom the prisons are filled, are one of these days to expiate their crimes; the stroke of powder shall purge them from the earth by a single discharge." In a vault beneath the chapel are shown about 200 skulls and skeletons, the relics of the miserable sufferers by this tyranny.

At the extremity of the suburb of La Guillotière is an ancient castle called *Château de la Motte*, in which Henri IV. was married to Marie de Medicis.

The *Bridges*. There are 7 over the Rhône:—the *Pont Morand*, of wood, opposite the Place des Terreaux, leading to Les Brotteaux, named after its architect, who perished by the hand of the revolutionary assassins; *Pont Lafayette* (formerly de Charles X.), of wood, on stone piers; *Pont de l'Hôtel Dieu*, a suspension bridge; *Pont de la Guillotière*, between the Hôtel Dieu and la Charité, leading to the Place Bellecour, is of stone, 539 yards long: it is the oldest of all the bridges, its foundation being referred to Pope Innocent IV., 1190, though no part of the present structure is of that age. The high road to Savoy passes over it. A very curious silver buckler, bearing a representation of the Contenance of Scipio, in relief, was found at the base of one of its piers.

The bridges over the Saône, between L'île Barbe and La Mulatière, are 10 in number. The principal are *Pont de Tilsit*, a beautiful stone bridge, leading from the Place Bellecour to the Archevêché; the *Pont Sequin*, a suspension bridge (destroyed 1840), named after its engineer, opposite the Palais de Justice; and higher up, the *Pont du Change*, an old stone bridge.

The *Inundations* of October and November, 1840, were the most fatal in the records of the city. The Saône,



usually regarded as a placid stream, submerged the suburb of Vaise, destroyed nearly half its houses, and 4 bridges, and overspread nearly the entire city between it and the Rhône, from the Place des Terreaux, which escaped, downwards: the Places Bellecour and Des Célestins became lakes, and most of the streets canals. In three places the waters of the Saône forced a passage, through the midst of the city, into the Rhône, cutting a deep bed, owing to the rupture of the dyke of the Tête d'Or. The entire suburbs of Guillotière and Les Brotteaux were covered by the swollen waters of the Rhône, which spread over the country to a distance of  $1\frac{1}{2}$  m. from its banks, destroying 450 houses. The grand increase of the Rhône began on the 27th October, but abated on the 31st; that of the Saône continued until Nov. 5. It was calculated that the quantity of rain which fell during 7 days preceding this catastrophe equalled that usually distributed over 7 months.

The Quartiers des Capucins, between the Place des Terreaux and Croix-Rousse, and of St. Clair, are chiefly inhabited by rich capitalists and manufacturers. The former stretches up the foot of the hill of Croix-Rousse, separated from the faubourg of that name by a line of antiquated ramparts and bastions.

The *fortifications of Lyons* consist of 18 detached forts arranged in a circle of  $12\frac{1}{2}$  m. around the town, crowning the heights of St. Croix and Fourvières, on the rt. bank of the Saône, and of Croix-Rousse, above the suburb of that name; and the circuit is completed round the faubourgs Brotteaux and Guillotière. They owe their origin to the fearful insurrections of the workmen and others, which took place as a consequence of the July Revolution in 1831 and 1834; and they are at least as much designed to repress intestine revolt as to withstand invasion from without. A garrison of 6000 men

would suffice to defend them. The chief work, the *Fort Montessay*, is so constructed that its guns entirely command, and could level with the dust, the *faubourg of La Croix-Rousse*, the St. Antoine of Lyons, a moral volcano teeming with turbulence and sedition; while a fortified barrack on the Place des Bernardines separates it, at will, from the rest of the city. From this faubourg issued, in 1831 and 1834, the armed insurgents who for several days held possession of the town, having expelled the military, until an army could be assembled large enough to put them down, which was only effected with a loss of more than 1000 lives. Indeed, in these recent revolts (for they were far too serious to fall under the name of riots), this ill-starred and ill-conditioned city experienced a renewal of many of the horrors, the bloodshed, and misery of the first Revolution. Many workmen were obliged to quit the town for their share in these disturbances, and settled in Switzerland.

The Croix-Rousse is principally inhabited by silk weavers, who live in densely crowded narrow streets, where 12 to 20 families are piled, one above another, in the lofty houses.

*Silk* is the staple manufacture of Lyons; in the extent of it she surpasses every other town of Europe. The manufacture of silk was first established in Lyons in the year 1450. In variety of design, in taste, in elegance of pattern, and in certain colours, the manufactures have a superiority over the English. "They can work 25 per cent. cheaper; but the hand-loom weavers of Lyons are nearly as ill off as those of Spitalfields."—*Laing*. There are no huge factories here; the master, instead of having a certain number of workmen constantly employed in his own premises, merely buys the raw material, and gives it out to be manufactured by the weavers, dyers, &c., at their own houses, by themselves and their families. The patterns are produced

by draughtsmen (generally a partner of the master manufacturer), and the laying or preparing of the pattern (*mise en carte*) is the province of another artiste. There are about 31,000 silk looms in and about Lyons. The silk weavers are, bodily and physically, an inferior race; half the young men of an age for military service are exempted, owing to weakness or deformity. Of late manufactories of cotton, hardware, &c., have been established in Lyons: it is also the centre of money transactions with Switzerland and Italy.

The *Conseil des Prudhommes* is a commercial tribunal, composed half of masters, half of workmen, designed to settle disputes, respecting wages and such matters, between the two classes, and between masters and apprentices, in a spirit of conciliation. It is of immense service, and exists in other manufacturing towns, and might, perhaps, be imitated with advantage in England. Every workman is provided with a "livret de bonne conduite," in which particulars of his ability, industry, and conduct are entered from time to time, so that it serves as a passport for him when in want of work, provided it shows a good and steady character.

The *Condition des Soies* is an establishment in which the quality and goodness of raw silks brought hither for sale is tried, by exposing them to heat, at a temperature of  $72\frac{1}{2}^{\circ}$  to  $77^{\circ}$  Fahrenheit. The weight of the silk is then ascertained, and marked by a sworn estimator, and fraud is thus prevented.

There are several *Theatres*; the chief one behind the H. de Ville, another in the Place des Célestins, which abounds with *cafés*.

The *Post Office* is in the Place Bellecour. The *English Ch. service* is performed in the Chapelle Evangélique, No. 36, Rue de l'Arbre Sec, Sunday, at 3 p. m.

*Omnibuses* traverse the town from end to end; and *cabriolets* and *fiacres*

stand in the Places des Terreaux and Bellecour, and on the Quai de Retz.

*Malleposte* daily to Paris in 36 hours; to Strasbourg in 36 hours.

*Diligences* daily; 4 to Paris (2 morning, 2 evening), in 60 hours in summer, 72 in winter; to Turin, by Chambéry, in 38 hours; to Aix les Bains; 4 to Marseilles in 2 days; to Strasbourg, by Lons-le-Saulnier, Besançon, Belfort, Colmar; to Clermont, by Montbrison, to Grenoble.

*Railroad to St. Etienne.* Office, Place Bellecour, whence omnibuses go to the terminus in the Quartier Perrache. Trains 3 times a day. (See Route 118.) *A Railway* to Paris is in progress.

*Steamers on the Rhône* start for Vienne, Valence, Avignon, and Arles, every morning at 4 or 5 A. M., from the Quai on the Rhône. (See Route 125.)

*Steamers on the Saône*, for Châlons, starting from the Quai (Route 106) every morning, from 4 to 6 A. M.

The *Environs of Lyons* are correctly described by Gray: "The hills around are bedropped and bespeckled with country houses, gardens, and plantations of rich merchants and bourgeois." These villas are much more numerous than in the vicinity of Paris.

"*L'Ile Barbe*, an island in the Saône, above Lyons, nearly surrounded by escarped rocks, and connected with the banks of the river by a wire bridge, is celebrated as having been the frequent residence of Charlemagne; and at the upper extremity is a species of watch-tower, on which, according to tradition, the emperor sat and contemplated his Paladins, heading his army, as it marched along the banks of the river. This castle seems not older than the 15th centy.; and a chapel on the island dates, probably, from the 12th. Many curious antique fragments are dispersed in the island."—*F. P.*

*A few Historical Notices of Lyons.*—The ancient city of Lyons, the



Roman *Lugdunum*, founded, according to Dion Cassius, by Munatius Plancus (B. C. 40), occupied the heights of Fourvières. Here Augustus and Severus resided. Here still exist traces of the vast *Aqueduct*, constructed, it is said, by the soldiers of Marc Antony, when his legions were quartered here, to supply the town with water from the distant mountains of La Forez. It may be still traced for miles, crossing the valleys on arches, of which the most considerable remains are at Bionnat (6 arches), Chapponost, Chardonniers, and Oullins.

Remains of Agrippa's 4 great roads, which met at Lyons, radiating thence to the Pyrenees, through the Cevennes, to the Rhine, to the Ocean through Picardy, and to Marseilles, may also be traced.

The settlement of the early Christians, and the persecutions they endured in the 2nd and 3rd centuries, have been alluded to in pp. 374, 5.

Lyons was possessed and governed by its archbishops, who held it by a grant from the Emperor of Germany, during the 12th and part of the 13th century, and was not restored to the French crown until the reign of Philippe le Bel.

The silk manufacture was established here in the middle of the 15th century by Italian refugees, and was nearly ruined by the revocation of the Edict of Nantes, which dispersed most of its best workmen to Spitalfields, Amsterdam, Crefeld, &c.

The events which occurred at Lyons during the first Revolution have been detailed at p. 379.

In 1815 Lyons threw open its gates to Napoleon on his return from Elba; the troops intended to defend it having at once deserted the standard of the Bourbons, to gather round the tricolor, in spite of the exertions of the Comte d'Artois and Marshal MacDonald to keep them to their duty.

## ROUTE 106.

PARIS TO LYONS—ROUTE DE BOURGOGNE BY SENS, AUXERRE, ARNAY-LE-DUC, CHÂLONS-SUR-SAÔNE, AND MACON.—DESCENT OF THE SAÔNE.—CHÂLONS TO LYONS.

466 kilom. = 289 Eng. m.

*Malleposte* (4 places) daily in 33 hours, returning in 37 hours.

*Diligences* daily in 41 hours to Châlons, and 8 or 10 thence to Lyons.

This route has the advantage over that by Moulins, that, by taking the diligence no farther than Châlons, you may enjoy a night's rest there, perform the rest of the journey by water, and yet reach Lyons as soon.

The traveller desirous of visiting Fontainebleau on his way to Lyons may follow R. 105 as far as that place, and then strike off into this road at Fossard.

The best point to quit Paris on this route is by the Barrière de la Gare, and the road along the S. or l. bank of the Seine, crossing that river just above the confluence of the Marne.

7 Charenton, a village of 1900 inhab., where the road to Troyes (R. 144) strikes off to the l. Two of the detached forts intended to defend Paris, guard the passage of the Seine here, one on each bank. At Alfort, through which our road passes, is a large Veterinary College.

The large building at Charenton is a lunatic asylum.

11 Villeneuve St. George.

The road passes through the forest of Senars, consisting chiefly of plantations of copse, cut down in rotation for fuel. In the midst stands an obelisk which led to a château of Louis XVIII., now pulled down.

13 Lieusaint.

13 Melun (*Inn*: H. de France), a town of 6622 inhab., chef-lieu of the Dépt. Seine et Marne. It is mentioned in Cæsar's Commentaries under the name Melodunum. In 1520 it was besieged and taken by the armies of Henry V. and the Duke of

Burgundy, but the English were ejected 1530.

11 Châtelet.

8 Panfou.

“The traveller who approaches Montereau from the side of Paris involuntarily halts on the summit of the heights of Surville, which overhang the town on the N., to gaze on the lovely scene which lies spread out, like a map, beneath his feet: he would do well to remember that there, beside the little cross adjacent to the château, stood Napoleon during the last and not the least of his many victories, on Feb. 18th, 1814. On the evening of the 17th the French troops assembled in imposing masses on these heights (which they had gained only after a severe conflict), and which commanded the bridge and town beneath. The artillery of the Guard was placed on either side of the road near the cross, and the Emperor took his station, in person, amidst the guns, to direct their fire, for the enemy still held the town. Such was his eagerness to annihilate the dense masses of the enemy crowding over the bridge, that he himself, resuming his old occupation of a gunner, with his own hand, as at Toulon, levelled and pointed a cannon upon them.”—*Alison*. The allies were so hotly pursued by the French cuirassiers, that they were driven over the Seine, and out of Montereau, having barely time to blow up the bridge over the Yonne, which checked the pursuit in the direction of Sens.

Montereau is a town of 4153 inhab., occupying a pleasing situation, and one most advantageous for commerce, at the junction of the two navigable rivers the Seine and Yonne. The most considerable part lies on the l. bank of the Yonne. Both rivers are crossed by bridges, and the one over the Seine (or rather an older bridge in the same situation) was the scene of the murder of Jean-Sans-Peur, Duke of Burgundy, in the presence and by orders of the Dauphin (afterwards Charles VII.), during a conference between them, and in spite

of the precautions which had been resorted to of erecting double barricades to divide the persons of the 2 princes. The blow was struck by Tanneguy du Chastel. The conference was designed to bring about a reconciliation, in order that the two parties might combine to resist the invasion of France by Henry V.

*Steamers* ply on the Seine, between Montereau and Paris.

14 Fossard.—*Inn*: Poste, good. The road ascends the pleasant and fertile valley of the Yonne.

9 Villeneuve-la-Guiard.—*Inn*: H. de la Souche, tolerable. Landlord a wheelwright.

12 Pont-sur-Yonne, pleasantly situated on green banks fringed with tall poplars and silvery willows. The country is full of vineyards; and a larger proportion than ordinary of the châteaux of the old noblesse seem to be in existence near the churches of the villages, or peeping over the trees.

12 Sens.—*Inn*: H. de l'Ecu; very good. This ancient capital of the Sennones is now but a small city, containing 9279 inhab., partly surrounded by its original ramparts. It is remarkably clean, with little *becks* of water running through the streets, supplied from a stream called the Vanne, which falls into the Yonne hard by. The *Cathedral*, dedicated to St. Stephen, is one of the finest of its style, early and pure Gothic, resembling Canterbury; it has undergone a thorough repair. The tracery in front of the transepts is the perfection of flamboyant detail. The painted glass deserves peculiar attention. It was executed by Jean Cousin, a native of Soucy, a village near Sens, who attained great excellence in this as well as in other branches of art. The colouring is extremely harmonious. The tomb of the Chancellor Duprat has partly escaped the general destruction; the bas-reliefs around it are very curious. (Temp. Francis I.) There is also a monument to the dauphin, son of Louis XV., and his



wife by Coustou. In the *Treasury*, among other curious relics, are shown the vests and mitre of Thomas à Becket, his alb, girdle, stole, manipule, and chasuble, to all appearance genuine; they have been repaired. He fled to Sens 1164, when he escaped out of England from the wrath of Henry II.

The altar of *St. Thomas* is said to be the same at which Becket performed his devotions, and is very ancient. He resided, while in this city, in the *Abbey of St. Columbe*, now occupied by the *Sœurs de l'Enfance de Jésus*. Three of the old town gates, the *Portes Notre Dame*, *St. Antoine*, and *St. Remy*, still remain: they are probably as old as the 14th century.

The *walls* of Sens, which, on the south side, extend in a straight unbroken line, exhibit in the lower portions magnificent remains of Roman, some say Gaulish, masonry.

At Vallery, 12 m. to the W. of Sens, the Grand Condé is buried in the *Church*, which contains a costly monument of marble. The *Château* was designed by Philibert Delorme.

An open chalky country follows Sens, till you reach

14 Villeneuve-le-Roi, a remarkably pretty and peculiar town, with much scope for the use of the pencil and sketch-book. The principal street is terminated by a gate at each end, of feudal times, yet apparently more for ornament than defence. The church, in the style of the Renaissance, is richly ornamented.

8 Ville-Vallier.

9 Joigny.—*Inn*: Duc de Bourgogne; dear. This town (pop. 5800) is also pleasantly situated on the Yonne. It derives its ancient name (*Joviniacum*) from Jovinian (see Rheims).—*H.* A fine quay, closed at either end by an iron gate, runs along the side of the Yonne, from one end of the town to the other. The old town, scarcely accessible, owing to its steep and numerous streets, contains 3 Gothic churches.—*St. Jean*, which stood within the castle; *St. André*, attached to the *France*.

priory; and *St. Thibault*. The road to Dijon (R. 145) issues out at the farther end; ours, turning to the rt., crosses the Yonne by a stone bridge. The Abbey of Pontigny, the retreat of Thomas à Becket, is about 20 m. from Joigny. (See R. 145.)

12 Bassou.

15 Auxerre.—*Inn*: Léopard, on the quai, next the Poste; civil people. This city, of 12,300 inhab., very prettily situated on the l. bank of the Yonne, and chef-lieu of that Dept., is seen to great advantage from the hill above it, from which you descend. The grand mass of the cathedral, and two or three other large churches, and a fine ruined spire, all rise finely above the houses, looking very much like the cities in the background of pictures by old German masters: within, it is not of a common-place character. The *Cathedral* has a splendid though unfinished façade, in the *Flamboyant Gothic* style, which prevails throughout the edifice, except in the choir, in the early Gothic, of the end of the 12th, or beginning of the 13th cent. "The transepts are covered externally with the boldest flowing tracery, occasionally standing free from the wall. The doors and rose windows are magnificent."—*Petit*. Within, it is beautifully proportioned; and the painted glass, principally in mosaic patterns, is splendid. Here is the tomb of Jacques Amyot, whilome bishop of this see, and celebrated for his racy translation of Plutarch, so excellent in its style as almost to form an era in the history of the French language. The chapter of Auxerre was at one time one of the richest in France, but they freed themselves from most of their superfluous possessions by indulging in the luxury of litigation.

*St. Germain*, now attached to the Hôtel Dieu, on the height, is in a plainer style than the cathedral; it has lost part of its nave, but possesses a lofty choir, and transepts. Underneath are curious *crypts*, one below another; in the lower are some tombs

of early counts of Auxerre. It has an ancient tower, which belonged to the W. front, but is now detached.

*St. Pierre* is a large and handsome specimen of Italianised Gothic, begun at the end of the 16th cent., and finished 1672. *St. Eusèbe* is a Romanesque church, in its nave, and detached tower, with a choir in the florid style, begun 1530.

There is a curious old *clock tower* over a gate-house, "with an ugly skeleton spire of iron bars," in the Place du Marché.

"The *Boulevards*, in the place of the ancient walls which surround the town on 3 sides, are unique in the charming variety of prospects they present; the moats are filled with plantations of acacia, gardens, and vines; the fine old towers are covered with festoons of ivy."—*Miss Costello*.

A considerable quantity of wines (chiefly ordinaires), the growth of La Basse Bourgogne, are sent down the Yonne hence to Paris. *Châblis*, about 12 miles to the E. of this, on the road to Tonnerre, gives its name to a wine of superior quality, prized for drinking at breakfast or with oysters. About 12 miles to the N.E. is *Pontigny*, whose once celebrated Cistercian Abbey, suppressed at the Revolution, served as an asylum for 2 years to Thomas à Becket. The *church* is still the finest ecclesiastical structure in Burgundy, after the Cathedrals of Sens and Auxerre.

10 St. Bris.

13 Vermanton. [A new and good road, avoiding the hills and St. Bris, leads from Auxerre to Semur, keeping along the banks of the Yonne, through the pretty villages of Champs (10 kil.), Vincelles, and Cravaut-Vermanton, 15 kil.]

"Near Auxerre the vine is much cultivated, but in France its stunted stumps give no charm to scenery. Further on the soil is worse, but prodigiously manured, and they grow oats and rye in what appears a stiff red clay. Nothing to relieve the eye; not a bush, not a speck of green, not

an habitation for miles on either side of the glaring white road; we travelled for ever up the steep rise, and down the sharp descent, which succeeded, as like each other and uninteresting as if all had been cast in the same mould."—*Ride to Florence*.

19 Lucy-le-Bois (a homely inn) stands in a sheltered and rather pretty valley. The rocks around, and the stone heaps at the road-side derived from them, abound in fossils of the lias and gryphite limestone.

About 6 m. from Vermanton, and 9 from Lucy-le-Bois, to the S., are the *Grottes d'Arcy*, a series of natural caverns in the limestone, many of vast extent, abounding in stalactites, and in bats, separated from one another by natural divisions, through which it is often necessary to crawl on hands and knees. The entrance to them is by a door inserted in an opening in the rock of a wooded dell, on the borders of the Cure. A guide, with candles, can be obtained at the village; the best time to visit them is during dry weather. The largest cavern is about 25 ft. high, 30 wide, and 400 long.

9 Avallon (*Inn: Poste*), a pleasantly situated town, nearly surrounded by a ravine. Around it runs a broad terrace walk, under lime-trees, about 500 ft. above the bed of the Cousin. The *church* is ancient, and has a curious Romanesque portal. Parts of its interior are singular.

[8 m. off the road, to the E., is *Vezelay*, a decayed town, containing a very remarkable *abbey church*, dedicated to the Madeleine, finely seated on the summit of a hill. The ruinous W. front lost one of its towers by the attack of the Huguenots in 1569; the lower part of it is Romanesque, the upper a late Pointed restoration, poor in effect. Another tower rises from the angle between the nave and S. transept. The W. doors lead into a sort of porch, destined, like the Galilees



in some English cathedrals, for catechumens: 3 other doorways open out of this vestibule into the nave; that in the centre is very rich in sculpture, and supported by an ornamental shaft, on which rests a transom covered with a procession of figures, in relief. The tympanum of the arch above it is filled with a large bas-relief: the figure of the Saviour forms the centre, attended by groups of saints reading or writing. One of the archivolts above is carved with a zodiac, the signs of which are intermingled with monsters forming 29 medallions. The interior of the nave is very impressive from "its great length, its gloom, and the simplicity of design which pervades its Norman features." It has no triforium, and is surmounted by a cradle roof. These walls doubtless echoed to the voice of Becket in 1168, when he repaired to Vezelay on Ascension day, when the church was crowded, and mounting the pulpit cursed, by bell, book, and candle, all those who maintained in England "the Customs of their Elders." This proceeding so enraged Henry II. that he threatened to confiscate all the Benedictine abbeys in England, if the Order continued to shelter Becket in France. A flight of steps leads up into the choir, which, with the transepts, is a fine specimen of early complete Pointed Gothic. It is surrounded by 8 round pillars, each of a single stone, and it is lighted by lancet windows. The axis of the choir differs from that of the nave, inclining a little to the l.

Attached to the S. transept is the *Chapter-house*, a low vaulted chamber, its roof resting on 2 clumsy central piers in the Romanesque style. Here, it is said, the monks assembled, with tears in their eyes, before their expulsion in 1154, through the rebellion of their vassals, the townsfolk, aided by the forces of the Comte de Nevers. The oldest part of the existing church is the nave, from the porch E., and the

crypt; and they probably date from 1050, the previous church having been destroyed, "prope ad nihilum redactum," in the middle of the 10th cent., and its restoration begun 1008. The W. front is probably of the 12th cent., and the choir of the early part of the 13th. Scarcely any remains exist of the domestic buildings of the abbey, which were so vast that kings, with their suite, could be lodged in them without discomfort to their monkish inmates. The entire length of the building is 404 ft.; the height of the choir 70 ft.

Vezelay is now a poor wretched town; its church is dropping to pieces, the roof and walls being cracked and crumbling, yet it possesses interesting historical associations. Here, on March 31, 1145, St. Bernard assembled a solemn Council of the Church, and preached in the presence of Louis VII. to a multitude assembled in the open field (the church being too small to hold them) the necessity of a new Crusade, with such impressive eloquence, that the universal cry for the Cross burst from the crowd around; and the supply of crosses not being sufficient, the Abbot of Clairvaux tore his own red robe to pieces to distribute among his willing hearers. The king, on his knees, first received the sacred symbol from him; the nobles followed his example; and the year following he set out from hence, with his army, for the Holy Land. In 1190 Richard Cœur de Lion, and Philippe-Auguste, repaired hither to assume the pilgrim's cross at the head of their armies.

Theodore Beza, the Reformer and Calvinist theologian, was born at Vezelay, of noble parents, 1519. On the way to Vezelay you pass the church of *St. Père*, whose tower is "an almost unique specimen of transition, or very early complete Gothic. The detached shafts, and canopies at its angles, and its several stages of open windows, give it an air of lightness and elegance such as I have

never seen surpassed in later buildings.”—*Petit.*]

To the S.W. of Avallon stretches the extensive tract of woodland called Forêt de Morvan, which supplies Paris with fuel, the wood being cut every 10 or 15 years, by portions at a time, and transported down the Yonne and Seine in rafts of faggots.

15 St. Magnance. Beyond this we enter the Dépt. de la Côte d’Or.

11 La Roche-en-Breuil.

13 Saulieu (*Inns*: La Poste, very good and clean;—H. d’Angleterre, also good) has a Romanesque *Church*: some of the columns and mouldings are very beautiful.

Here a road branches off, through the interesting city of Autun (Rte. 107), to Châlons; it is  $5\frac{1}{2}$  m. longer than the following line.

13 Maupas.

15 Arnay-le-Duc (*Inn*: Poste; very decent), rather prettily situated on the Arroux.

17 Ivry.

A fine view over the valley of the Saône, the distant Jura, and Mont Blanc is presented a little short of

10 La Rochepot (no good inn), a poor village, surmounted by a ruined *Castle*, flanked by watch-towers.

11 Chagny. Horses bad.

The road runs near the Canal du Centre nearly all the way to

16 *Châlons-sur-Saône*.—(*Inns*: H. du Parc, very good;—~~Trois Faisans.~~)

The Saône, which runs through this town of 12,200 inhab., and which, from this point, becomes an important river, navigable for steam-boats, gives it much water-side activity. The *Canal du Centre*, which joins the Saône to the Loire, commences here, and affords an outlet for a considerable traffic and transit of goods to the Mediterranean and Atlantic from the *central* departments of France. Châlons is the Cabillonum of Cæsar, whose Commentaries should be one of the hand-books of every traveller through the districts of Gaul. A fine granite column, standing, or rather

raised, on one of the places, is unquestionably a relic of the Roman age.

The town is dull, but clean, for France; and there is little worth seeing. But the quai, facing the river, is lined by good houses, and is the most lively portion. The *Cathedral* (St. Vincent), lately restored, in tolerably good taste, with the addition of 2 new towers, is in the early Gothic, when the peculiarities of that style were beginning to mix themselves with the older Romanesque. The *Hospital of St. Laurent*, on the island in the Saône, has some good painted glass, which, it has been suggested, should be removed to the cathedral. At present it is necessary to traverse the sick ward in order to see it. The date of this vaulted dormitory, and of the hospital itself, is 1528.

*Diligences* daily to Paris; to Lyons; to Dijon.

Abélard died (1142) at the Abbey of St. Marcel, about 2 m. from Châlons, now destroyed, except the church; he was buried there, but afterwards removed to the Paraclet.

### *Descent of the Saône.—Châlons to Lyons.*

From Châlons the traveller may proceed to Lyons either by land or by water. *Steam-boats* start every day, and if the traveller avails himself of them, he may complete his journey to Marseilles (or, if he chooses, to Civita Vecchia) entirely by water. “The captain of the steamer will take charge of the carriage, embarking and landing it, and the luggage, and will forward them to and from the hotel. The voyage is far preferable to the land journey, and is performed in 8 hours descending — 10 or 12 ascending. Meals are served on board. Some of the steam-boats are not large enough to convey carriages on board. The *expense with* a carriage ought not to exceed that of posting, including the passenger’s fare, but the charges vary.



The steamers are liable to be arrested by too much water in the river, in which case there is not room for the vessel to pass under the bridges, as well as by too little, and to be delayed by fogs.

The post-road is good and picturesque. *Diligences* run daily to and fro, but take 16 hours, double the time of the steamer. The distance by the river is about 100 m. (35 lieux).

The *post-road* runs along the rt. side of the Saône, sometimes close to it, at others out of sight of it, but so little removed from it that the course by water or land may, without inconvenience, be described together.\*

Rt. immediately below Châlons is the mouth of the *Canal du Centre*, and a basin or dock (see p. 388) for barges entering or quitting it.

The banks of the Saône are at first tame, but improve as you approach Lyons.

Rt.† Tournus (*Inns: Sauvage; H. de l'Europe*; both tolerable), a town of 5311 inhab., possessing a wooden bridge of 5 arches over the Saône. Its *Church*, formerly attached to a venerable abbey, now destroyed, is a very plain edifice, in the Romanesque style, but interesting to the student for its architecture and antiquity. It is surmounted by a central tower, flanked with Corinthian pilasters at the angles, and has 2 other towers at the W. end. Its nave, preceded by a narthex or vestibule supported on 2 rows of short thick pillars without capitals, is probably of the 10th century. The nave is roofed with a series of cradle-vaults, placed trans-

\* *Post Road.*—18 Sennecy. First relay from Châlons.

From some of the eminences surmounted by the road, towards the East, you see the chain of the Jura, and, in favourable weather, the white snow of Mont Blanc, which may at first easily be mistaken for a cloud, distant as the crow flies about 100 miles.

† There is a pretty view of the winding Saône and the town of Tournus from a hill at a short distance from

10 Tournus.

versely, separated by cross arches, so as to divide it into compartments.

In the Place de l'Hôtel de Ville is a granite column, reputed an antique.

The charming painter *Greuze* was a native of Tournus: the house where he was born is marked by an inscription: he died at Paris, 1805.

L. Fleurville, a bridge over the Saône.

L. St. Albin\* has a curious, early pointed Gothic church; the windows lancet. The costume of the villagers is picturesque.

Near the river vineyards cover the slopes, which are a prolongation of the distant range of the hills of Charolois.

Rt. Mâcon†.—*Inns:* Le Sauvage, from which there is a view of the river; tolerably good; H. de l'Europe. Mâcon was heretofore the capital of the country of the Mâconnais, and ruled by its own sovereigns from the time of Louis le Débonnaire until it passed to the house of Burgundy. The country was often settled as an apanage upon the younger branches of the family. The present population of the town, which is not flourishing, is 11,994: it is chef-lieu of the Dépt. Saône et Loire. The conjoint devastations of the Huguenots, who exercised the greatest cruelties and atrocities here, and of the Revolutionists, have nearly denuded Mâcon of all its ancient religious structures; hence the necessity of erecting a new church, which, until recently, was an unheard of event in France. The towers of the *cathedral* are standing, but mutilated, together with a very small portion of the body of the building, now turned into a blacksmith's forge. The river is crossed by a *Bridge* of 13 arches. From it, but still better from a little *Esplanade* planted with poplar trees beyond it, a view of Mont Blanc may be obtained. In the neighbourhood of Mâcon are many very fine pro-

\* *Post Road.*—16 St. Albin.

† 14 Mâcon.

spects of the ranges of the hills of the Bourbonnois and Charolois, the latter being a continuation of the Côte d'Or.

Mâcon is thus mentioned by Cæsar: "Tullium Ciceronem Matiscone, rei frumentariæ causa, collocat." It is the birth-place of the distinguished living poet and deputy M. Alphonse de Lamartine. His Château, St. Point, is not far off.

Mâcon is the centre of a great trade in the *wine* grown in its arrondissement, though at some distance from the town itself, and from our road; at the foot of the hills on the W. The best sorts are the growths of Thorins and Moulin à Vent, which are red, and the Pouilly, a white wine. Romanèche, situated in the midst of this wine district, 12 m. from Mâcon, possesses an important mine of manganese, which gives activity to many manufactures.

[15 m. N. W. of Mâcon is *Cluny* (*Inn*: H. de Bourgogne), once famous for its ancient and wealthy *abbey*, of the order of St. Benedict, which, before the Revolution, had 600 religious houses dependent upon it, and enjoyed a revenue of 300,000 fr. a year. It was so utterly destroyed in 1789, that of its noble Gothic church, which had 5 aisles and double transepts, only the 2 towers remain, with some fragment of wall, and the *chapelle de Bourbon*, 15th centy. The town, which has a population of 4152, and carries on some manufactures, is built on the site and with the materials of the abbatial buildings. The *cloisters* form a sort of public square, and a fragment of the Abbot's Palace is converted into a private dwelling.]

The country on the l. bank of the Saône formed part of the ancient divisions of La Bresse and Dombes; its inhabitants are a primitive race, by no means enlightened.

The banks of the Saône acquire some elevation and picturesqueness below Mâcon; the Jura mountains being all along a feature in the view

to the E.; the nearer hills studded with white châteaux and villages. The Château de Corielles, flanked by 4 round towers, stands at some distance off the road to the W.

Rt. At St. Romain, a suspension-bridge.

L. Toissey, an ancient town of the principality de Dombes, partly hid by poplars and willows.

Rt. Belleville.\* A bridge.

About 13 m. to the W. is Beaujeu, capital of the province of Beaujolais, in the midst of a district famed for its wines.

L. Montmerle, a village situated below a considerable island, has a suspension-bridge: other bridges are thrown across at Fléchère, Beauregard, and at Frans, opposite to

Rt. Villefranche.† "A small town: has rather a cheerful aspect. The *church* has been a beautiful specimen of the florid Gothic, though small."

There is a bridge at St. Bernard.

Rt. Anse is the port of Villefranche.

L. Trévoux is an ancient town of 2239 inhab., on the slope of a concave hill, surmounted by the ruins of its old *castle*. It possesses now no interest beyond that connected with the recollection of its having once been capital of the principality of Dombes, and the place where the Jesuits compiled and printed the very learned works called the "Journal de Trévoux," 1701, and "Dictionnaire de Trévoux," 1704, a sort of Encyclopædia. Their house remains, marked by the shield of arms of the Order of St. Ignatius.

Dombes was acknowledged as an independent state by the French kings (except Francis I.) from Philippe-Auguste down to Louis XIV., owing them only allegiance and aids of men in case of war. It had a

\* *Post Road*.—13 Pontaneveaux.

11 La Croissée.

† 14 Villefranche. Here the road turns away from the river, avoiding its windings, and following a nearly straight line by

13 Limonest to

11 LYONS. (Route 105.)



parliament of its own, which met at Trévoux, and the right of striking money down to 1762. It is supposed to have been the Roman Triviæ, near which Septimius Severus beat the army of his rival Albinus, and thus secured the empire for himself.

Through pretty scenery, between banks thickly scattered with habitations, the Saône, considerably contracted in width, passes under the richly-wooded heights called Mont d'Or, rising 1000 ft. above the river, on the rt., by Belle Ile,

L. Neuville, with its suspension-bridge, and

Rt. Couson, opposite to

L. *La Roche Taillée*, so called from the cutting which Agrippa caused to be made through it, to allow the passage of one of the great Roman highways.

Lower down is *L'Ile Barbe*, the favourite retreat of Charlemagne, linked to either bank by a suspension-bridge. (See p. 382.)

The valley of *Roche-corbon*, with its wood and fountain of *Roset*, was a favourite haunt of Rousseau.

L. La Tour de la Belle Allemande (described p. 378), and

Rt. Pierre Scise. (See p. 378.)

The entrance to Lyons has been compared to the "approach to Bristol under the slopes of Durdham, and King's Down, and the rocks of Clifton Hot Wells; but the river Saône is larger, and the cliffs not so high."

LYONS, in R. 105.

## ROUTE 107.

PARIS TO CHÂLONS-SUR-SAÔNE, BY  
AUXERRE AND AUTUN.

470 kilom. = 291 Eng. m., or  $5\frac{1}{2}$  m. longer than R. 106.

The road is the same as R. 106 as far as

258 Saulieu, p. 388.

10 "Pierre Ecrite, so called from an inscribed stone just beyond the village: that is to say, the stone remains, but the inscription is invisible. Antiquaries, however, maintain that

it was in the Celtic language. This is the highest land between Paris and Lyons, and it is curious to observe the effect produced by this elevation, and its corresponding alteration of character, upon the aspect of the country. It might be Yorkshire. Trees and hedge-rows, so rare in other parts of France, are here universal: oak, hawthorn, and briar not only skirting the road, but dividing the fields."—*F. P.*

11 Chissy. "The road continues descending, winding round by a species of *corniche*, from which the views are often extended."

21 Autun.—Inns: La Poste;—La Cloche. "Let no one approach Autun in September; a fair is then held which lasts the whole month: the inns are then intolerable, and the town one scene of bustle and confusion."—

*W. M.* The first view of this interesting city is very pleasing. It is supposed to have been the ancient *Bibracte*, capital of the *Ædui*, mentioned by Cæsar as "oppidum maximæ auctoritatis apud eos," but its name was changed, in the time of Augustus, into *Augustodunum*, modernised into Autun. Tacitus describes its importance as a fortress and great city, and states that the most illustrious of the youth of Gaul were educated here. "Autun, now a town of 10,000 inhab., stands at the foot of a range of well-wooded hills. The Roman ruins, heavy-grey, situated low down near the river, distinguish themselves by their fine and peculiar forms. Amongst the masses of buildings, crowned by the cathedral and its lofty spire, is the *Temple of Janus*, as it is called, though without any sufficient authority, a square building, of which 3 sides are standing. It is denuded of ornaments, but imposing, from its proportions and its solidity. It probably dates from the time of the Lower Empire. *The Two Roman Gates* are beautiful and very perfect. They are both nearly on the same plan: double arches below, and ranges of smaller arches above, ornamented

with pilasters. The *Porte d'Arroux* is Corinthian, the *Porte Saint André* Ionic. They are evidently of the Lower Empire, and the *purist* will find fault with the details; but if you will put away criticism, and enjoy the objects, the effect is most satisfactory. Nothing can be more charming than the appearance of the delicately-cut arches, coming off against the blue sky."—*F. P.* The *Roman walls of Augustodunum*, within which the present city has shrunk, are very massive and curious, and large fragments still very perfect exist.

Just without Autun, upon the Dijon road, is a singular pyramidal mass of masonry, called the *Pierre de Couars*. It is about 50 ft. in height, and was probably originally much more lofty. The facing is entirely destroyed. It is quite solid, and is probably sepulchral: antiquaries suppose it to be the tomb of Diviciacus (?).

Autun had a noble *amphitheatre*. The ruins are now encircled by other buildings, but the general site of the Roman city is a perfect mine of antiquities. Many were collected by the late *M. Jovet*, whose house covers a mosaic, representing the combat between Bellerophon and the Chimæra. "Here also is a fragment of the tomb of the wicked Brunchault, who was buried at the abbey of St. Martin, a curious structure, now razed to the ground."

"The *Cathedral of St. Lazare* exhibits a great and interesting variety in its style of architecture. The lofty spire, covered with foliated crockets, is a masterpiece of Gothic: so also is the rood-loft, composed of delicate and elaborate filagree-work. But a large proportion of the building is in the Romanesque style, and exhibiting the closest imitation of Roman art."—*F. P.* The elegant flamboyant decorations of the chapels in the nave, and especially the door of the sacristy, a charming bas-relief of Christ and the Magdalene, in the chapel which serves as baptistery, the painted glass in the Chapelle St. Nazare, representing the

genealogy of the Virgin, and the Martyrdom of St. Symphorien, by *Ingres*, deserve also particular attention.

In all parts of the city you may see the disjointed and lamentable fragments of the ancient edifices by which Autun was once adorned. There is a good collection of the *geology* of the district in the Petit Séminaire, of which the Abbé Landriot is superior.

St. Symphorien suffered martyrdom here for refusing to join a procession in honour of Cybele.

Autun, it will be remembered, was the see of *Bishop Talleyrand*.

Not far from Autun are the two valuable coal-basins of Epinac (to the N.) and of Creuzot, which are worked by pits, in some cases more than 650 ft. deep, and employ about 1900 workmen. Mineral oil for lighting the mines is obtained by a distillation from the bituminous schists accompanying the coal. The Romans used these very schists to line the walls of their houses at Autun.

At Creuzot are extensive iron furnaces, but the iron-ore requires to be brought from a distance. From Epinac (where are considerable glass works for making wine-bottles) the coal is transported on a tramway to the Canal de Bourgogne, and thence, by water, to Paris and Alsace. The Canal du Centre traverses the coal-field of Creuzot (see p. 388).

"Soon after quitting Autun, you enter the forest of Morvan (p. 388). The road ascends, but with frequent dips. It is richly wooded, and some of the little glens are lovely. The sides of the road are clad with alder and beech, with here and there a fine oak tree lifting up his head above his compeers. The rocks show between and amongst the verdure, and you see and hear the rushing of the little rills, dashing by or in the road."

17 St. Emiland. "Beyond St. Emiland you begin to find yourself in another climate. Vines re-appear in great luxuriance, and, unlike other parts of France, they are often trained



in festoons and arcades; a mode equally disadvantageous to the produce, and advantageous to the beauty of the scenery.”—*F. P.*

14 St. Leger.

8 Bourgneuf.

12 *Châlons-sur-Saône*. (Rte. 106.)

There is a new road from Autun to Mâcon, 104 kilom., by Marmagne, 21 kilom., Mont Cénis, Blazy.

### ROUTE 109.

MOULINS TO CLERMONT AND LE PUY.  
VOLCANOES OF AUVERGNE.

To Clermont 95 kilom. = 59 Eng. m. *Malleposte* in 6 hours, daily to Clermont, and in 36 to Montpellier.

Clermont to Le Puy 122 kilom. = 75 Eng. m. *Diligences* daily.

Moulins is described in R. 105. This road contrasts agreeably with the monotonous dulness of that from Paris to Lyons, and is interesting from the natural beauties and rich cultivation of the country which it traverses; but more than all, for the phenomena of the extinct volcanic mountains of Auvergne, through the midst of which it passes. It proceeds nearly due S. from Moulins, up the valley-plain of the Allier, the chief tributary of the Loire, first crossing by a bridge to its l. bank. The upper part of this valley above Aigueperse was anciently called *La Limagne*, and is believed to have been once a lake basin, in which were deposited the freshwater marls, sands, &c. which now contribute so much to its fertility.

18 Châtel Neuve, or de Neuve. The mountains of Forez, which divide the waters of the Allier from those of the Loire, are seen on the E.

12 St. Pourçain.—*Inn*: Poste. A town of 4,000 inhab., on the Sioule. An *Ecce Homo*, carved in the stone, in the church here, is praised.

The road, leaving the Allier on the l. at St. Pourçain, ascends the vale of the Sioule. It is a flat and uninteresting stage to

16 Mayet d'Ecole.

8 Gannat. There is a road hence to the Baths of Vichy (R. 105). Our route is shaded by luxuriant walnut avenues.

The hill rising on the l. of the road, about 1 m. N. E. of Aigueperse, is called *La Butte de Montpensier*, and is composed of yellow marly limestones. There is a fine view from its top. Between it and the road is a *hole* which exhales carbonic acid nearly pure, so that small animals which come to drink from the pool of water which often collects at the bottom are apt to be suffocated. The common people, attributing this to the water, called it *La Fontaine empoisonnée*.

9 Aigueperse (*Inn*: Poste, comfortable) is the first town in the Dépt. Puy de Dôme, and is celebrated as the birth-place of the Chancellor d'Aguesseau, born at the Château de la Roche: his statue may be seen in the *Hôtel de Ville*. Its name is derived from “acqua sparsa,” from the streams around it. The *choir* of the principal church, attached to an ugly modern nave, deserves notice as a pure specimen of the Gothic of the 13th century; its lofty roof is sustained by long graceful columns. Here is a painting of the Nativity, attributed to *Ghirlandajo*, in a stiff style (the figures said to be portraits of princes and lords of the Bourbonnais), and a St. Sebastian (?), locked up. There is also a *Sainte Chapelle* here, founded, 1475, by Louis, Dauphin d'Auvergne, inferior to one at Riom.

The Abbé Delille, author of “*Les Jardins*,” was born here 1738.

“O champs de la Limagne, ô fortuné séjour,  
J'ai revu les beaux lieux qui m'ont donné  
le jour.”

The hill of Chaptuzat, on the rt. of the road, is quarried for building stone; the rock is an oolite. Above it, and on many other eminences throughout the Limagne, beds of a tertiary limestone occur, entirely formed of the cases of insects resembling the caddis-worm, or May-fly, incrustated by carbonate of lime and formed into

a hard travertine, called "calcaire à friganes," or indusial limestone. The cases, or tubes, are coated over with shells of *Paludina*, often to the number of 100 around one tube, and 10 or 12 tubes are packed within the space of a cubic inch. These insects must have inhabited the lake which once covered the valley of the Limagne.

Near Riom the country becomes interesting, and exhibits the characteristic features of the scenery of Auvergne, a rich vegetation and beautiful verdure, produced by the abundant irrigation; a varied outline of country, with towns, castles, and villages perched on the tops of eminences commanding the Limagne.

16 Riom (*Inns*: Colonne; Ecu de France) is a town of 12,500 inhab., the second in the Dépt. Puy de Dôme, in a cheerful situation, but built of dark lava from the quarries of Volvic, and paved with volcanic stones. It is encircled by boulevards planted with trees, in one part widening out into a platform called *Pré-Madame*, where a monument of granite has been raised to the memory of General Désaix.

The *Sainte Chapelle*, attached to the Palais de Justice, is, like that of Paris, a light and lofty lantern of stone, built 1382, the piers which support the roof forming the separations between the windows. It has, however, suffered material injury from being divided horizontally, by a floor, into two stories: the lower one is converted into a law court (Cour Royale), and is stripped of its painted glass in order to throw a light upon the proceedings; the upper one, turned into a record office, is filled with old musty deeds, so that its really beautiful stained windows can scarcely be seen.

*St. Amable* is a curious church, which will interest the architect and antiquary. The date of the nave, the oldest part, seems uncertain. The lower arches are pointed, and rest on piers, having engaged pillars on three

sides, but plain on the inner face; above them runs a gallery of circular arches roofed with a demi-vault, which serves the purpose of a range of flying buttresses to support the roof of the central aisle. The little sculpture employed is very rude. The choir is in the Gothic style of the 13th century, the arches alternately pinched up and expanding. The W. front and cupola above the cross are tasteless additions of the 17th century.

About a mile from Riom, on the W., is the village of Mosac or Mosat, whose church has been attributed to Pepin; but the only part which can be referred to the 8th or 9th centuries is the W. porch, now walled up. The nave, in the Romanesque style, seems to belong to the early part of the 12th century, and is remarkable for the beautifully executed capitals of its columns: the only windows are in the aisle. The choir and rest of the church are of the 15th century, and uninteresting. In the sacristy is preserved a silver gilt *shrine*, in the shape of a sarcophagus, ornamented with enamels in the Romanesque style, made in the middle of the 10th century. It contained the relics of Saints Calmidius and Numadia.

At *Volvic*, a few miles farther to the W. of Riom, are the vast *quarries* of lava which have furnished the stones for building that town and Clermont. The lava current in which they are excavated has issued out of the extinct crater called Puy de la Nugère. They are partly subterranean, partly open to the sky; they have been worked since the 13th century, and give employment to the whole neighbouring population. The stone is porous, resembling trachyte, and contains specular iron in its cells; it is easily worked, and the bed furnishes blocks 20 ft. by 6 ft. in size. When first extracted, it is of a grey or slate colour, but darkens by exposure to the air; it is used for rude works of sculpture. The church of Volvic is ancient.



Volvic is built at the foot of the volcanic cone called Puy de la Ban-  
nière, on the lava current which has  
flowed from it, and appears to have  
crossed and covered that from Puy  
de la Nugère.

On an eminence near Volvic stands  
the very romantic ruined *Castle* of  
*Tournoëlle*, in ancient times one of  
the strongest in Auvergne, so that  
it resisted long and stoutly a besieg-  
ing army under Guy Dampierre and  
Renauld de Forez, Archbishop of  
Lyons, in 1213, and again 1590, when  
it was defended against the forces  
of the League by Charles d'Apchon.  
The remains are accessible by a  
steep path, and part of them are  
tolerably perfect: the oubliettes, or  
dungeon entered only by a small  
hole from above, still exist under  
the round tower.

There is a foot-path or horse road  
direct from Volvic to Clermont.

About a mile before entering Cler-  
mont, the suburb of Montferrand,  
a cluster of narrow streets con-  
spicuously seated on a limestone  
eminence, crowned by an old *church*  
dedicated to Notre Dame de Pros-  
périté, is passed. It was anciently  
an independent town and fortress, and  
was called Montferrand le Fort. It  
was surprised and pillaged by the Eng-  
lish, under Perrot the Béarnais, 1388.  
Froissart, in his *Chronicles*, recounts  
at length the story of its capture.

An avenue of trees, nearly a mile  
long, leads into

15 CLERMONT, or Clermont-Fer-  
rand.—*Inns*: H. de l'Ecu, kept by  
M. Dessat; very good;—H. de l'Ecu-  
rope;—H. de la Paix (Boyer's), good  
and tolerably clean.—*F. T.*

Clermont, once capital of Lower  
Auvergne, now of the Dépt. du Puy  
de Dôme, is a cheerful town, which,  
in consequence of recent improve-  
ments, has lost the gloomy character  
which once distinguished it, its houses,  
built of dull grey lava, being now  
whitewashed. Its principal interest  
is derived from its situation on a  
hill, composed chiefly of volcanic

tuff, in the fertile Limagne, in the  
midst of a mountainous country, at  
the foot of that extraordinary range  
of extinct volcanoes which rear their  
conic or crater-shaped forms around,  
surmounted by the mountain of the  
*Puy* (i. e. Pic) *de Dôme*, whence the  
department is named, which, though  
apparently overhanging Clermont, is  
nearly 5 m. distant. The population  
amounts to 32,427, including the  
suburbs.

On the outskirts of the town, nearly  
all round its circuit, except on the  
N. W., runs a line of boulevards, or  
“places,” the chief of which are the  
*Place de Jaude*, a wide oblong dusty  
space on which fairs are held, sur-  
rounded by houses; the *Place de*  
*Taureau*, on which a monument has  
been raised to Gen. Désaix, a native  
of Clermont; and the *Place Delille*,  
by which the Paris road enters the  
town, named after the poet, who was  
also an Auvergnat.

Clermont is destitute of fine public  
buildings: the principal edifice is the  
*Cathedral*, externally an irregular pile  
of dark lugubrious hue, from the  
black lava of Volvic, of which it is  
built; it suffered serious injury from  
the phrenzy of the Revolution, being  
stripped of its ornaments and monu-  
ments, and condemned by the mob to  
be levelled with the ground, but was  
saved by the exertions of a citizen and  
magistrate, M. Verdier Latour, under  
the pretext that it would be useful to  
hold popular meetings in. It is, not-  
withstanding, an interesting example  
of the mature pointed Gothic, begun  
1248, and carried on till 1265, by the  
architect Jean Deschamps (J. de  
Campis), but never completed. The  
interior, therefore, is all of a piece,  
presenting one harmonious whole, re-  
markable for its lightness and lofti-  
ness, the vaulted roof (of tufa) being  
more than 100 ft. above the pavement.  
There are fine rose windows in the  
transepts. The painted glass is very  
beautiful; that in the choir is of the  
age of St. Louis (13th cent.), and  
displays his arms quartered with those

of Spain: the glass in the large window of the nave is of the 15th and 16th centuries, and inferior; it has, besides, suffered from a hailstorm in 1835.

In one of the side chapels of the choir is an ancient *sarcophagus* of white marble, adorned with sculptures well executed.

The *N. portal* suffered least at the Revolution, is very richly adorned with sculptures, and deserves notice.

From the top of the tower the stranger may survey to advantage the town, and the volcanic mountains, the valley of the Limagne, and the plateau of Gergovia, the scene of Cæsar's discomfiture. (See p. 401.)

The most ancient and interesting church, in an architectural point of view, is *Notre Dame du Port*, a Romanesque edifice of the 10th or 11th century, judging from the evidence of style, but said to date from 870, and perhaps portions of the very curious *crypt* may be of that age. It is encrusted externally with rude mosaics. The tower above the W. door is modern (1823), but in tolerable taste: the S. doorway is surmounted by curious bas-reliefs, much mutilated, and partly hidden behind woodwork; yet Christ between two six-winged cherubims, and the Adoration of the Magi, and the Baptism of Christ, may be distinguished below. The interior possesses some modern painted glass by a native artist, M. Thévenot; and in the crypt is a black image of the Virgin, said to have been found at the bottom of the well, which is supposed to work miracles, and is resorted to by pilgrims on the 15th May.

In the N.E. corner of the town, not far from the last-named church, is the Place Delille, in the midst of which has been placed a fountain of elegant design in the style of the *Renaissance*, with some mixture of Gothic, executed 1515, for the Bishop Jacques d'Amboise. In the same quarter, on the l. of the road to Montferrand, is the *Cimetière de la Ville*,

in whose chapel a curious antique sarcophagus, richly sculptured, has been converted into an altar.

In the Faubourg St. Alyre, to the N.W. of Clermont, and at the foot of the eminence on which it is built, rises a remarkable calcareous spring, called *Fontaine pétrifiante*, issuing out of a volcanic peperino resting upon granite. It resembles that of Matlock, except that its deposits are more copious and quickly formed, from the larger quantity of calcareous matter suspended by the carbonic acid with which it is impregnated. It has deposited in the course of ages a mass of travertine or limestone, 240 ft. long, 16 ft. high, and 12 ft. wide at its termination. It has formed over the rivulet a sort of natural bridge, *Pont de Pierre*, which is in fact nothing more than a huge stalactite, while a second bridge is in progress, and gradually increasing. So abundant is the quantity of lime held in solution in the water, that the pipes and troughs through which it passes would be choked up with stone, were they not cleared out every 2 or 3 months. By breaking the fall of a jet of the water, and allowing its spray to descend upon any article subjected to it, such as bunches of grapes, baskets, nests, eggs, hedgehogs, &c., they become encrusted with the calcareous sediment, or petrified, as it is vulgarly called; and in this way even very fine casts are obtained from medals, &c.

The fountain and bridge are situated in a garden, within which is a bathing-house supplied from its waters.

The *Musée*, or Etablissement Scientifique, a building situated on the S. side of the town within the ill-kept but beautifully-situated botanic garden, contains—1. a collection of *Natural History*, particularly rich in the mineral products of Auvergne, which may be studied with advantage by the geological traveller previous to travelling through the country, as the specimens are arranged topographically. 2. The *Public Library* of 15,000



vols., including some curious ancient MSS., and a folio bible of the 12th centy., illuminated with vignettes.

Here is a statue of Blaize Pascal (b. 1623), and a bust of Delille, both Auvergnats.

In a corner of the Jardin Botanique, a number of antiquities, inscriptions, fragments of columns, &c., and a head in relief of the Gallic Mercury(?), dug up in the vicinity, have been deposited here, but are very little cared for, being exposed to the weather in the open air.

The terraced walks called Place du Taureau and Place de la Pôterne command fine views of the surrounding mountains.

Clermont has been the seat of several ecclesiastical *Councils*: the most remarkable was that held in 1095, which may be said to have lighted the spark of the crusades in Europe, the train having been laid by Peter the Hermit. It was convoked by Pope Urban II., who presided in person over the vast assembly at the head of his cardinals, of 13 archbishops, and 205 bishops. The place of meeting is supposed to have been an open space to the rear of the church of Notre Dame du Port. Here, from a throne raised in the midst, around which were grouped the tents of tens of thousands of enthusiastic hearers, the pope pronounced that eloquent discourse which melted all to tears, and was followed by the universal shout of "*Diex le volt*" (Dieu le veut); when the cloaks of red cloth worn by the noble bystanders were torn into shreds, to form the badge of the cross, then first adopted and laid on the breast of all who took the vow.

Clermont is supposed to be the ancient *Augustonemetum*.

*Conveyances.*—*Mallepostes* to Paris by Moulins; to Montpellier, by St. Flour, St. Chely, Marvejols, and Lodève, in 56 to 60 hours.

*Diligences* daily to Paris, by Moulins; to Lyons; to Le Puy and St.

Etienne; to Montpellier, to Aurillac, to Alby and Toulouse, to Tulle, Limoges, and Bordeaux to Bourges.

Several persons in the town let for hire, at a moderate rate, small carriages and saddle-horses, by aid of which numerous interesting excursions may be made in the

*Environs*, the beauties of which can be reached only by passing over a dreary intervening space of dusty road between high walls. It is not therefore advisable to make these excursions on foot.

The ascent of the *Puy de Dôme*, the highest mountain in the neighbourhood, 4846 ft. above the sea level, is very interesting on account of the insight it affords into the geological phenomena of the district. It may be performed in the following manner:—you may hire a char-à-banc at Clermont for 8 or 10 fr. to go and return. No carriage can advance farther than to the foot of the cone, the rest of the ascent must be performed on foot; it is practicable on horseback if the beast be sure of foot: the distance is about 6 m. A steep, but well engineered road, commencing at the barrier, passing at first over black basalt, and afterwards over the more modern lava, scoriæ, and calcined stones, which have issued from the Puy de Pariou, leads, in about 1½ hour, to the hamlet and cabaret of la Barraque, where the road divides, the l. hand branch leading to the Puy de Dôme and Mont Dore, the rt. hand to the Puy de Pariou and Pont Gibaud, and passing on the l. the ruined Castle of Montrodeix. A guide may be hired at la Barraque, and the carriage may proceed nearly to the base of the Dôme, beyond which is a very steep ascent, partly over coarse grass, mixed with bilberry bushes, partly over the bare crumbling rock of which the mountain is composed; a variety of trachyte, called Domite by the French geologists, because peculiar to this locality. It is so porous, that it retains no water on its surface, and the moun-

tain in consequence does not possess a single spring. The summit is most easily accessible from the S., where a sort of zigzag path has been carried up its side. The Puy (pic) de Dôme rises to a height of 1600 ft. above the table land around; it is the largest in mass and the most central of the group of volcanoes of Clermont. Viewed from the W. only has it the form of a dome, but its name is said to come from *dumum*, the thickets which once covered its sides. From the top, the eye surveys the singular range of igneous mountains, craters, domes, lava currents (called *cheires* in the dialect of the country), and heaps of scorix, the produce of volcanoes, which, though extinct within the period of all human tradition, were once as active as *Ætna* or *Vesuvius*, and converted the surrounding district into the Phlegræan Fields of France. In many instances the vast lava currents, flowing across the country for miles, may be traced up to the funnel-shaped craters which poured them forth. The fertile Limagne lies expanded to view, traversed by the winding Allier. On the S.W. rises the rival group of volcanoes of the Monts Dore; the remainder of the panorama is somewhat uninteresting over a monotonous country. The range of hills of the Monts Dôme rises from a granitic platform, and stretches "18 m. in length by 2 in breadth. They are usually truncated at the summit, where the crater is often preserved entire, the lava having issued from the base of the hill; but frequently the crater is broken down on one side, where the lava has flowed out. Had these cones of loose sand and ashes been in existence previous to the Deluge, they must have been swept away, or greatly altered, by the power of a current of water. Had these volcanoes, again, been in activity in the time of Cæsar, he would scarcely have failed to observe them when encamped on the neighbouring plateau of Gergovia (p. 401), or to have mentioned them in his

Commentaries."—*Lyell's Geology*. See *Scrope* and *Daubeny* on *Volcanoes*.

The experiments instituted by the philosopher B. Pascal, to determine the weight or pressure of the atmosphere, were made on the Puy de Dôme within view of his native town.

A chapel, dedicated to St. Barnabe, formerly stood on the summit; and the blocks of basalt, brought from a distance to build it, still strew the mountain side.

In descending from the summit, every one should visit the crater called the *Hen's Nest*, *Nid de la Poule*, at the base of the Petit Puy de Dôme, a regular bowl-shaped hollow, 294 ft. deep, and nearly the same in diameter.

Still farther to the N., the *Puy de Pariou* deserves to be ascended, because it is one of the most beautifully regular and perfect volcanic cones and craters existing in Auvergne. The sides of this bowl-shaped hollow are composed of scorix and pozzolana, thrown up so regularly from below, that they taper upwards into a narrow ridge so little degraded by time or by the weather, that in many places it is barely wide enough for one person to walk along it. The crater is 300 ft. deep, and 3000 in circumference, measured along the brim of the bowl. It has the figure of an inverted cone. "It is clothed to the bottom with grass; and it is a somewhat singular spectacle to see a herd of cattle quietly grazing above the orifice whence such furious explosions once broke forth. Their foot tracks, round the shelving side of the basin, in steps rising one above the other, like the seats of an amphitheatre, make the excessive regularity of its circular basin more remarkable."—*Scrope*.

The lava from this crater flowed down in one undivided stream, bristling and rugged on its surface, like that of a river blocked up by floating masses of ice. After descending as far as la Barraque it encountered a



small knoll of granite. The lava has accumulated against this impediment into a long and elevated ridge, "which still bears the appearance of a huge wave about to break over the seemingly insignificant obstacle; but an easier issue offered itself in two lateral valleys." The rt. hand branch "entered the valley of Villar, a steep and sinuous gorge, which it threaded, exactly in the manner of a watery torrent, turning all the projecting rocks, dashing in cascades through the narrowest parts, and widening its current where the space permitted, till, on reaching the Limagne, it stopped at a spot called Fontmore, where its termination constitutes a rock, 50 ft. high, still quarried for building-stone. From the base of this rock gushes a plentiful spring, the waters of which still find their way from Villar, beneath the lava, which usurped their ancient channel."—*Scrope*.

The left-hand branch "plunged down a steep bank into the valley of Gresinier, replacing the rivulet which flowed there with a black and shagged torrent of lava; entered the limits of the Limagne at the village of Durtol, and, following the course of the stream, did not stop till it reached the site of the village of Nohanent. Here, as at Fontmore, an abundant spring bursts forth from the extremity of the lava current. The springs of the valley of Durtol find a passage beneath the lava concealed among the scoriæ, which always form the lowest part of a bed of lava, and flow on in these subterranean channels, till they burst forth at the limits of the lava, in the same manner that the Arveiron and other Swiss rivers issue from beneath, under the termination of a glacier. Above Nohanent, consequently, is seen the anomaly of a valley without any visible stream; and the inhabitants of Durtol are condemned, in seasons of drought, to the strange necessity of seeking at Nohanent, a distance of 2 m., the water which flows below their own

houses. A similar phenomenon is common throughout Auvergne, wherever a current of recent lava has occupied the bed of a mountain rivulet not sufficiently copious or violent to undermine the lava above, or open a new side channel through its former bank."—*P. Scrope*.

"A little to the N.W. of the Puy de Pariou is the *Puy de Cliersou*, whose 'figure is most precisely that of a bell,' and which is curious from the numerous perforations made in it for the purpose of obtaining trachyte for sarcophagi."—*T. J. T.*

Instead of returning from the Puy de Dôme by la Barraque and the high road, you may strike down into the Val de Fontanat to *Royat*, a poor and filthily dirty village, 8 m. from Clermont, which has twice been nearly swept away by inundations of the torrent which flows past it. It is built on one of the branches of the lava-current which has issued from the Puy de Gravenoire. The torrent, flowing through the valley, has cut through the bed of basaltic lava to a depth of 65 feet, exposing, at the bottom, a sort of grotto, out of which gush numerous copious springs, some of which, conducted in an aqueduct to Clermont, supply the town with fresh water. There are many other sources higher up the valley, issuing out at intervals from the rocky sides. The scenery of the vale of Royat is overpraised by the French; but a fine view is gained of the Puy de Dôme from some part of it. The *church* is remarkable for its antiquity (anterior to the 11th century); it has a curious crypt supported by low columns, and a spring rises in the midst of it; it is in a very dilapidated state.

The *Puy de Gravenoire* is composed of scoriæ and pozzolana; the latter is used in the country to make mortar, and is commonly called "*gravier noire*," whence the name of this hill.

"The conical basaltic summit of the *Puy de Girou*, 3 or 4 m. to the S. of Clermont, is an excellent point

for obtaining an extensive view over a considerable portion of Auvergne.” — *T. J. T.*

At *Pontgibaud*, 13 m. from Clermont, on the road to Limoges, may be seen a feudal castle of the 14th cent., which once belonged to the family Lafayette, and was visited by Montaigne; and the smelting-houses, where the argentiferous lead from mines in this neighbourhood is refined and separated. The village and castle stand on a lava current, which has issued from the base of the very perfect and regularly-conical crater called *Puy de Come*. The course of this current deserves observation: descending the granite slope, it has covered the ground on which Pontgibaud now stands; then, pouring in a broad sheet down a steep granite hill into the valley of the Sioule, it has usurped the ancient bed of that river for more than a mile, and crossing the more ancient stream of Louchadière, near Pichadoire, terminates there. The river has, in consequence, worked out for itself a fresh bed between the lava and the granite of its W. bank, and in one place has laid bare a singular basaltic colonnade, formed of jointed pillars, partly vertical, partly twisted. “In the ravine between the smelting house and the castle is a small isolated knob of granite which separates the two great lava currents of Louchadière and Come. The former continues a short way down the rt. bank of the river, and then crosses it.” — *T. J. T.*

At some little distance to the N.W. of Pontgibaud are the ruins of the *Chartreuse de Port Sainte Marie*, while in an opposite direction, a little to the S., near the margin of the lava current from the Puy de Come, is the *Fontaine d'Oule*, a grotto whence issues a streamlet which is partly frozen in the hottest weather of summer, but in winter preserves a temperature considerably higher than that of the outer air. “Several of the more interesting Puy's are easily accessible from the road between

Clermont and Pontgibaud; and of these two may be particularly specified, viz. the *Puy du Grand Sarcouy*, 3,799 ft. above the sea level, composed of domite, of a striking, flattened hemispherical form, and having on its S.E. side a large artificial excavation, about 70 ft. long, 30 wide, and 35 high, from which the trachyte was quarried in ancient times for sarcophagi; and the conical *Puy de Chopine*, 3,910 ft. above the sea, of a singularly complicated and confused geological structure, and composed chiefly of domite, granite, and basalt: the view from it is very fine.” — *T. J. T.*

The *Puy de Louchadière* may be visited from Pontgibaud by the cross-road leading to Volvic.

The excursion to the volcanoes and *baths of Mont Dore* is described in R. 110.

The *Puy de la Poix*, about 3 m. from Clermont on the Lyons road, is mentioned in R. 112.

The Limagne, or valley of the Allier, is far more interesting above Clermont, on the way to Le Puy, than below it. Here it is truly a luxuriant garden, teeming with the most varied productions.

Soon after quitting Clermont, by the road to Issoire, we skirt a lava current from the mountain Grave-noire, called Plateau de Beaumont, a very characteristic specimen of a lava stream, which, although partly covered with vines, exhibits, even to the unscientific eye, in a manner not to be mistaken, compact and porous lava, ashes (*scoriæ*), and volcanic dust (*pozzolana*). Beyond rises the singular peak of *Montrognon*, a basaltic dyke bursting through fresh-water strata, crowned by an old *castle*, built by the 1st dauphin of Auvergne (not by Cæsar), and demolished, like so many other feudal fortresses, by the Card. Richelieu. The basaltic prisms on which it is founded are the most regular which occur in this district. Our road next passes, within a short distance on the rt., the *Hill of Ger-*



*govia* ( $4\frac{1}{2}$  m. from Clermont), memorable as the site of the chief city of the *Arverni* (whence Auvergne), so nobly defended by the Gauls and their chief Vercingetorix against Cæsar, who was more seriously worsted here than in any other of his numerous campaigns, having run great risk of being made prisoner, and having left his sword in the enemy's hands. The hill of Gergovia is as interesting for its geology as for its history: it is a table-land, composed of a base of fresh-water marls, capped by a sheet of basalt, surrounded by steep escarpments, absolutely inaccessible on the N. and W., while on the S. and E. it presents a slope in the form of steps, occasioned by the horizontal strata of rock composing it. At the base of the eminence flows a small stream, the Auzun, whence the Gaulish garrison are supposed to have drawn water, there being no springs upon the plateau itself; and one of Cæsar's first objects was to cut them off from this supply. The hill called La Roche Blanche, surmounted by a tower of the middle ages, though called Tour de César, is conjectured to be the Gaulish post seized by two Roman Legions in order to effect that object. Cæsar's camp is supposed to have been formed on a detached and lower eminence, called Le Crest. The only traces of human habitation on the top of the table-land of Gergovia are some scanty foundations of walls, some Roman coins and Gaulish axes of flint, found from time to time, and a rampart or agger of loose stones, which may be traced near the margin of the plateau. In the ravine above the village of Merdogne, a section of the strata composing the hill is exhibited, consisting of beds of white and greenish marls, nearly 300 ft. thick, intersected by a basaltic dyke, which has greatly altered the marl in contact with it. In the flanks of this hill also are found extensive deposits of the limestone formed of the cases of insects mentioned before (p. 393).

The road to Le Puy, unlike the monotonous chaussées of most other parts of France, winds and undulates between and over varied heights, sometimes crossing a lava current or basaltic dyke, and is generally shaded from the sun by luxuriant walnut trees. Scarcely an eminence but possesses some interest, either from its volcanic origin, or from its picturesquely-placed castle in ruins, or village, which, in this district, is almost invariably perched on the hill-top. The country is very populous as well as fertile, and intersected by numerous roads.

"The *Puy de Marman*, a little to the N. of Vayre, is celebrated among mineralogists for the beautiful crystallized specimens of mezo-type contained in the volcanic tuff and basalt of which it is composed. In the same neighbourhood interesting fragments of charred wood, whose bark has been converted into mezo-type, are met with in the tufa of the Puy de la Pignette, situated a little to the N. of Mouton."—*T. J. T.*

After passing the populous village Vayre, we reach, by a steep descent, the post station

24 Coudes, situated on the bank of the Allier. The *castle* of Montpeyrour, on an adjoining eminence, now reduced to a round tower, and some fragments of walls, belonged to Philip Augustus. "Near Coudes a variety of sandstone termed *Arkose* is quarried for millstones. Between Coudes and Montpeyrour veins of fibrous arragonite occur in travertine, and farther down the river Allier at Cœrent there are gypsum quarries which afford fine specimens of fibrous gypsum."—*T. J. T.* From Coudes through a lovely country, which keeps the attention constantly alive.

In the ravine des Etouaires, near the village of Perrier, an interesting geological section is presented. Here fossil remains of extinct quadrupeds, mastodon, tapir, rhinoceros, elephant, &c., have been found in alluvial beds, covered by volcanic breccias, and alternating with them. Near Vayre

and at Perrier the rock has been excavated to form cave-dwellings; above Perrier rises the tower of Maurifolet.

A view of the Monts Dores rising on the W. may be obtained near

11 Issoire (*Inn*: Chez Roussard, Poste), an ancient town of 5,990 inhab., situated on the Couze, a short way above its exit into the Allier. The church of *St. Paul* will interest the architect and antiquary, as a characteristic specimen of Auvergnat architecture, as it prevailed in the 10th and 11th centuries. It is in the Romanesque style, ending in 5 apses at the E., surmounted at the cross by a tower, the upper part of which, and also the W. front, are modern. The exterior of the wall at the E. end is singularly decorated with rude mosaics, and with 12 medallions, representing the signs of the zodiac, let into the wall under the cornice. Under the window of the N. transept are 2 bas-reliefs, representing the Angel appearing to Abraham, and the Sacrifice of Isaac. In the interior the arches are semicircular, the side aisles and transepts being covered with a stone roof, forming the quarter of a circle, and thus serving as a buttress to support the tower and central walls of the nave. There is an extensive crypt under the choir.

The chancellor Duprat was born here. The chief manufacture is that of copper kettles.

After passing through St. Germain Lembron, and leaving a little on the l. the coal mines and steam engines of St. Florine beyond the Allier, we quit the volcanic country, and the Dépt. du Puy de Dôme, to enter that of la Haute Loire, shortly before reaching

20 Lempde (*Inn*: Poste), situated on the rt. bank of the Alagnon. Here the road to St. Flour, Montpellier, and Aurillac (R. 114) branches off. It is the line of a malleposte.

15 Brioude.—*Inn*: H. du Commerce. The very fine Romanesque church of *St. Julien* is curious for its semicircular E. end, with chequered

patterns in a coarse mosaic of parti-coloured stones on the outer walls, and round its 5 projecting apsidal chapels, of elegant design. The interior is lofty; the arches of the choir are pointed, and the capitals of the columns adorned with foliage: the arches of the nave are round, and the capitals of the columns supporting them are partly very grotesque, partly display a nearly pure classic character. At the W. end, which is almost bare externally, is a sort of inner vestibule, or narthex, supporting, on low arches, 3 chambers, one of which, the chapel of St. Michel, is decorated with curious antique *frescoes* of the 13th century. The canons of the church of St. Julien the Martyr anciently bore the title of counts.

[The very curious Church of *La Chaise Dieu* is distant 18 m. from Brioude, nearly due E. The monastery of the Casa Dei, now ruined, and attached to a dilapidated little village (Cheval Blanc is the inn), is situated at a considerable elevation, on a high mountain. It was founded in the 11th century by St. Robert, a canon of Brioude, and became the most opulent convent in Auvergne. Of this original structure nothing exists, except perhaps an external gateway. The monastic buildings were destroyed at the Revolution. The Church alone remains, and is a noble edifice in the pointed Gothic style, begun 1343, chiefly at the expense of Pope Clement VI., a native of Chaise Dieu, who laid the first stone, and is buried under a mutilated monument, surmounted by his effigy, wearing the triple crown. The carved woodwork of the 156 stalls in the choir is much admired, and deservedly. On the N. wall, which encloses the choir, are traces, now nearly defaced, and obliterated by moisture, of a Dance of Death, painted in fresco, probably in the 15th century. Here are preserved some of the most curious ancient *tapestries* remaining in France, executed probably at the beginning of the 16th century, woven



partly with gold thread. The tomb of another pope, Gregory XI., and of an abbot, in the S. choir aisle, deserve notice. Two sides of the *cloisters* remain tolerably perfect, and are of a good style. Contiguous to the church rises a tall square *donjon tower*, the only remains of the ancient fortifications which surrounded the monastery. It is surmounted by a bold cornice.]

2 m. beyond Brioude, on the road to Le Puy, at the wretched village of La Vieille Brioude, the Allier, here running in a deep and rocky bed, is crossed by a *Bridge* of a *single arch of stone*, which was long celebrated as being the widest in span of any known, measuring 181 English ft. and 90½ ft. in height, but now surpassed by the stone arches of Turin and of Chester (200 ft. span). It is a very noble arch, and constructed of Volvic lava. It replaces a more ancient bridge (b. 1451), of equal dimensions, which fell down in 1822. Immediately beyond the bridge, the road begins to ascend, and continues over a hilly and uninteresting country, almost constantly mounting higher, for many leagues. A little beyond the poor village of—

21 St. George d'Aurat, the château de Chavagnac is passed, at the distance of 1½ m. on the l. of the road: it is remarkable as being the birth-place of Gen. Lafayette.

By a long, though gradual ascent, which the diligence takes 3 hours to surmount “au pas,” the Montagne de Fix, separating the valley of the Allier from that of the Loire, is passed. Measured at the village of Fix, this road is 3197 ft. above the sea level, and one of the highest carriage roads in France.

18 Limandre.

We are now again upon volcanic rocks, belonging to the basin of Le Puy. The small river Borne, which runs into the Loire below Le Puy, is crossed, and the road is carried down its valley, passing, at a distance of 4 m. from Le Puy, under the black

rock of basaltic breccia, escarped and inaccessible on all sides but the N., which bears the ruined *castle of Polignac*, seat and cradle of that ancient family, the *branche aînée* of the name, whence sprang the Cardinal, a diplomatic servant of Louis XIV., and the well-known minister of Charles X. It was pulled to pieces during the fury of the Revolution, and all the lands sold; but the mouldering and picturesque ruins, which still bristle on the top of the rock, were repurchased by the family. They consist of rude but strongly built walls, often double and treble, with flanking towers at intervals, surmounted by a square donjon tower. Part of the pile of buildings which served as dwellings may be as old as the 12th century. There is little to be seen except an enormous *mask*, rudely carved in granite, of a bearded human face, with a wide orifice for the mouth. According to the tradition, a Temple of Apollo occupied the summit of the rock before the castle, and from this mouth-piece (somewhat after the fashion of the Bocca della Verità at Rome) oracles were delivered: hence some have gone so far as to derive Polignac from “Apollinis Arx.” (?) Sunk in the platform of the castle is a well, called *Puit de l'Oracle*, from a tradition that the oracles were delivered from it through the mask, which is said to have covered the well. At a depth of 20 ft. this well communicates with a vaulted chamber, supported on circular arches, resting on square piers, designed doubtless as a cistern, into which rain water was conducted by pipes, now stopped up. About 25 paces from the well is the *abyme*, a hole about 40 ft. deep, and 15 wide, cut in the rock, probably designed as a storehouse. The *church* of Polignac, at the foot of the castle rock, is an ancient Romanesque edifice.

Upon a sudden turn of the road, here bordered by basaltic columns, a very striking view is presented of Le Puy and its volcanic rocks; the

“spiry pinnacle” of St. Michel’s, resembling more an artificial obelisk than a natural eminence, and Corneille, starting up from amidst the masses of buildings, while on the rt. appears Espailly (p. 406).

19 LE PUY.—*Inns*: H. des Ambassadeurs; best and good;—Palais Royal;—H. du Commerce. Le Puy, anciently capital of the Velay, and now of the Dépt. de la Haute Loire, with 14,924 inhab., is, at a distance, one of the most striking, uncommon, and picturesque towns in France. Excepting the broad modern Boulevard, through which the high roads from Clermont and St. Etienne pass, which stands on level ground, the buildings and narrow streets of the old town are carried up a steep slope, surmounted by a towering, table-topped mass, called *Rocher de Corneille*, whose summit, vertically escarped and mouldering in the form of turrets, is surmounted by the ruins of an old *castle*, the stronghold and place of retreat from danger of the former bishops. This rock is a volcanic breccia, resting on a calcareous base.

Far more remarkable, though less lofty, is the *Rocher de St. Michel*, an isolated rock of basaltic tufa, which, from its needle shape, gives the name *de l’Aiguille* to the suburb in which it stands. It rises from the margin of the stream of the Borne to a height of 265 ft., with a thickness of 500 ft. at its base, and 45 or 50 on its top. It is a fragment of the vast bed of volcanic rock once covering the country around. The rocks of Corneille and Polignac are also relics of it, and, because harder than the rest, have resisted the erosive processes of rivers and the atmosphere, which have scooped out into valleys the intervening portions, and have washed away the débris. Faujas de St. Fond absurdly supposes the Aiguille of St. Michel to have been projected by a volcanic eruption from below, and consolidated in its actual form. The sides of this truncated cone, or sugar-loaf, are nearly vertical, and its top is

surmounted by a small *chapel*, which just fills the platform, dedicated to Michael, the saint who loves such airy sites. This building, rendered accessible by a winding stair partly cut in the rock, is in the Romanesque style, and was constructed at the cost of a dean of the cathedral in the 10th cent. Its Moresque portal, a circular arch under a trefoiled arch, is ornamented with curious sculptured mermen, bas-reliefs, and chequered stone work, composed of black scoriæ, white sandstone, and red tile, in the style of marqueterie. The interior presents a low irregular choir, supported by short pillars with carved capitals.

From the top of the rock a good view is obtained of the vine-clad hills covering the slopes of the valley, dotted over with white country-houses, boxes, and pavilions, built in the midst of the vines, also of the white escarpments of the tertiary strata, laid bare here and there.

Near the foot of this rock stands an octagonal building which has long passed for a heathen *temple of Diana*, though destitute of any pretensions to such a title, being, in fact, a Christian edifice in the Romanesque style, and perhaps originally a *baptistery*: some say a chapel of St. Claire. A small apse projects from its eastern side, and it is entered by doors on the N. and W. It has an octagonal roof, with a hole in the centre, resting on columns placed in the angles. It may have been built by the Templars, who had property in this suburb.

A road slopes upwards from St. Michel, under the Rock of Corneille, past the Hospital, and the little turning box, in which enfans trouvés are deposited after ringing a bell to announce their arrival, through the “Rue de la Raison,” to

The *Cathedral*, which rears its singularly streaked W. front high over the other buildings. The regular approach to it is up the steep streets leading from the market-place to the



long flight of steps under the huge cavernous vaulted portal, which is prolonged in a sort of corridor beneath the church. As the slope of the hill denied to the architect level ground sufficient to extend his church to the W., he was forced to raise an artificial platform for it upon these vast substructions. The doorway is flanked by 2 pillars of Egyptian porphyry. It is a heavy ungainly building in the Romanesque style; its interior not improved by the repairs and stucco applied at the expense of Louis XVIII. The oldest parts of the church are the choir, including 4 compartments of arches on either side, and the transepts; each compartment is cross-vaulted; the probable date is the 10th or 11th century. This church is chiefly remarkable for a miracle-working image of *Nôtre Dame du Puy*, which for many centuries has attracted thousands of devout pilgrims, who still repair hither, though in less number than formerly. Among its visitors in former times are numbered several popes, and the following kings: Louis VII., Philippe Auguste, Philippe le Hardi, Charles VI. and VII., Louis XI., Charles VIII., and François I.: its visitors at present do not exceed 4000 annually, and are chiefly of the lower order of peasants. One cause for this falling off may be, that the existing image deposited over the high-altar, a black group of the Virgin and Child with shining faces, is a modern work, executed by a sculptor in the town, whose name is well known, from recollection of the original, which was destroyed at the Revolution. The original *Nôtre Dame du Puy*, believed to have been made by the Christians of Mount Lebanon, or, according to some accounts, by the prophet Jeremiah himself, and brought to Europe at the time of the Crusades, was of cedar-wood, singularly swathed round with bands of papyrus glued to it, and partly inscribed. Upon this the features of the face, of negro tint, the flesh of

hands and feet, and the draperies, were painted in distemper, in a rude style, probably by some artist who copied from Egyptian models.

A marble tablet on one side of the church records the names of 20 priests of the diocese slaughtered in the Revolution, 1793-4 and 8.

The *monument* raised to the Constable Du Guesclin, whose body reposed some time at Le Puy, after his death at Châteauneuf de Randon, and whose entrails were buried here, has recently been restored in a chapel on the N. side of the Gothic *Church of St. Laurent*, in the lower part of the town. His effigy represents him in armour, except the helmet, lying on his back, his hands raised in prayer. The head is modern, but copied from a cast of the original, destroyed by the Baron des Adrets and his followers, and is considered to have some claim to be looked on as a portrait.

The collections in the *Musée*, not far from the cathedral, are of considerable interest as local curiosities in art and nature. Besides some mediocre paintings (among them Henrietta Maria, queen of Charles I., a copy from *Vandyke*; a faint, but curious portrait of Henri II., in the style of *Janet*, and a good landscape by *Huysman*), are some Roman antiquities, a bas-relief of a Stag and Boar Hunt, found on digging the foundations of the Evêché; also 3 Genii or Cupids fishing (one with 2 dolphins of very fair execution), from Margeaix; a cippus hollowed out into a sarcophagus, bearing figures of arms, cut in relief, among them a cross-bow (?); cast of a bronze hand, with a Greek inscription, recording a treaty of peace; a cast from the so-called Mask of Apollo, at Polignac (see p. 403); one or two groups of Gothic sculpture, nuns, female saints, &c.; carvings in ivory, in Byzantine and Gothic styles; a portion of the inscribed *papyrus* in which the image of N. D. de Puy was swathed, preserved at the time

the image was burnt, at the Revolution; some old furniture; an abbot's seat, carved in the style of the Renaissance; and an arm-chair of Gothic work, bearing the arms of Polignac. Those who take interest in the *geology* and *mineralogy* of the district will find the collections here not only the best part of the whole museum, but one of the best arranged and best named cabinets which any provincial museum in France possesses, under the inspection of M. Bertrand de Doué, the able expositor of the geology of Velay. The formations of La Puy en Velay, the Vivarais, and the Ardèche may be studied in distinct series of specimens, topographically arranged, side by side with a series of the volcanic rocks of Vesuvius, for the sake of comparison.

Here are preserved the bones of rhinoceros, hyæna, deer, &c., found by Dr. Hibbert, a Scotch geologist, at St. Privat d'Allier, in a matrix of scorïæ, between two layers of basaltic lava; a discovery of great interest, as proving the recent date at which the volcanoes of the Velay were in activity; also fossil bones of Palæotherium, of Anthracotherium Velauum, so named by Cuvier from Le Puy, the locality where it was found; of hippopotamus, found in the terrain du transport near Polignac; and fossil fruits from the coal measures at Longeac.

The manufacture of *cotton lace* gives employment to the females of the lower classes in and about the town; and some specimens are shown at the museum of great beauty.

About 1 m. W. of the town is the village of *Espailly*, surmounted by another castle-crowned *rock* of volcanic breccia. Charles VII. was residing here during the occupation of France by the English (1422), when news was brought of the death of his father, and his scanty train of followers proclaimed him King of France in the ancient fashion, by raising him aloft on a shield, at the same moment that the infant Henry VI. of England

was proclaimed, with all pomp, at Paris, the successor to the French throne. There are good displays of basaltic columns here, called *Les Orgues d'Espailly*; and on the opposite side of the river, in the eminence of Denise, several coarse varieties of precious stones, sapphires, zircons, and garnets, are found in the basalt, and in the sands of the neighbouring streamlet of Riou Pezzouliou. Fossil remains of Anthracotherium and other extinct animals have been found in the marly limestone near Espailly.

The *Castle of Polignac* is a walk of about an hour, not far from the road to Clermont (p. 403).

The *Roche Rouge*, an isolated mass of basalt, rising abruptly out of the granite rock to a height of 60 ft., about 3 m. to the E. of Le Puy, will interest the geologist. Its name is probably derived from the colour of the lichens which grow on it. It is nothing more than the expanded portion (*renflement*) of a basaltic dyke, which, from superior hardness, has resisted the action of the weather, while the softer granite around has been disintegrated. The dyke is continued on either side in a vein often not more than a foot wide.

*Diligences* twice a day to St. Etienne; daily to Clermont, and to Langogne.

The views of the town from the surrounding heights from the roads to Espailly, Polignac, St. Etienne, are very striking. Mr. Scrope prefers the extensive *panorama* from the more distant *Mont d'Ours*, and observes, with some geological enthusiasm,—“There are, perhaps, few spots on the globe which offer a more extraordinary prospect than this. To the eye of a geologist it is superlatively interesting, exhibiting in one view a vast theatre of volcanic formation, containing igneous products of various natures belonging to different epochs, and exhibited under a great diversity of aspect.”

“The traveller bound from Le Puy



to the Volcanic District of the Vivarais and Ardèche may take the diligence to Pradelles, and thence strike across the country, by bad cross roads, to Aubenas, by Thueyts (R. 118, 121), or, more directly, by a mule-road to Montpezat; in the course of which he may visit the *Mt. Mezène*, the highest volcanic mountain in Central France, presenting some wild and singular views. He may also pass the curious mountain called *Gerbier des Jones*, at the foot of which rises the Loire. There is scarcely any accommodation on this route, which can hardly be performed in a day; and the people are rude and forbidding.”—*P. F.*

### ROUTE 110.

#### CLERMONT TO MONT DORE LES BAINS.

I. Grande Route, 53 $\frac{1}{4}$  kilom. = 33 Eng. m.

II. Petite Route, hilly and not good for carriages, 42 kilom. = 27 Eng. m.

I. *Diligences* run daily in summer.

It is a hilly journey by either of these routes, beginning to ascend from the Barrier of Clermont to La Barraque (see p. 397), then leaving the Cone of the Puy de Dôme on the rt. and the ruined castle of Montrodeix on the l.; its walls formed of basaltic prisms.

The road reaches the summit level of the chain of the Monts Dôme, at a spot called Moréneau, between the Puys de Leschamps, covered with wood, and de Montchié, a volcano, furnished with 4 craters, which has been cut away at the base to give passage to the road; and trunks of trees charred have been disclosed by the section of the trachytic rock. Descending the opposite slope it crosses the stream of the Sioule, here in its infancy. At St. Bonnet, near Pont des Eaux, a basaltic clinkstone is quarried, to serve as roofing slate, as bridges, fences, &c.: the thin slabs ring like a bell when struck.

20 Rochefort.

The ruined *castle*, on the summit

of a basaltic rock, once belonged to the Dauphins of Auvergne.

The road continues to ascend through a hilly and bleak country, often blocked up by snow in winter. About 3 m. beyond the village of Laqueuille the road to Mont Dore branches off to the l., out of that to Aurillac by Muriac, and crossing another ridge, descends upon the village Murat le Queire, in the valley of the Dordogne, and proceeds up the rt. bank of that stream to

24 *Mont Dore les Bains* (p. 407).

No. II. *La Petite Route* is the same as No. I., until reaching the village Laschamp, 3 m. beyond La Barraque; “or, on foot, more directly and agreeably by Thadde. As there are few villages, the route may most conveniently be traced by the Puys which are passed, viz. Gravenoire and Charade on the rt.: La Bache and Lasolas, also on the rt., are extremely well preserved, and are completely thrown open on the S.W. side, towards which they have diverted their lava streams. There is here quite a circle of craters, among which Mont Jughat and Mont Chat are conspicuous.”—*P. F.*

21 Randanne (a tolerable road-side Inn). In the vicinity, at the foot of the Puy de Montchal, is the residence of the patriotic philosopher Le Comte de Montlosier, who settled himself down here, after his return from exile in 1816, in the midst of an unproductive wilderness, the home of his fathers having been destroyed in the Revolution, and by the enlightened agricultural improvements which he introduced, redeemed a large tract from unproductive barrenness, and “bid the desert smile.” He is buried in a small Gothic chapel, erected on a pretty spot within his estate; the priests having refused interment to his remains within consecrated ground, on account of his writings against the Jesuits.

About 3 m. on the l. is the sheet of water called *Lac d'Aidat*, formed by

the volcanic current from the Puy de la Vache, damming up the course of 2 rivulets. On its borders Sidonius Apollinaris is said to have lived, and an inscription on the wall of the church has been supposed (?) to mark it as the place of his interment. "To the rt. is the *Puy de la Rodde*, a fine crater opening to the S., and commanding an extensive view of the Puys, the streams of lava, and the mountains of Mont Dore. Abundance of fine crystals of Augite are found in it."—*T. J. T.*

After attaining the table-land of Baladaud, which commands an extensive view, but is itself bleak and uninteresting, it is an uninterrupted and steep descent into the vale of the Dordogne. It is clothed with wood, and interesting. At Quereilh the traveller turns abruptly to the l., and enters the valley enclosing

21 *Mont Dore les Bains*. "Many hotels: Chez Chatancy is thought the best;—chez Baraduc, very comfortable."—*L.* There is a daily table-d'hôte at most of them. The rivers and lakes furnish trout, and the mountains roe venison. This small watering-place is a village at a height of 3,411 ft. above the sea-level, in an upland valley, the cradle of the river *Dor-dogne*, surrounded by an amphitheatre of volcanic hills, their sides clothed with verdant meadows or black pine forests, but torn and gashed at intervals by ravines and gullies, down which numerous streams dash in small cascades from the bare table-land above. The village lies at the distance of about 2 m from the Pic du Sancy, the highest summit in central France, 6,217 ft. above the sea level, and the culminating point of the Mont Dore, that vast volcanic excrescence which has broken through the fundamental granite rock, and stretching from this point to a distance of 8 or 10 m. measures 18 leagues in circumference. It is seamed and fissured by deep valleys radiating in all directions from the common centre, the chief of them on the N. side

being the valley of the Dordogne, or of Mont Dore. The crater from which this eruption burst forth is not distinctly marked, owing to the dilapidations in its sides caused by volcanic convulsions, by the wearing down of torrents, and even by the effects of the weather; but there can be no doubt that we see the traces and remains of the lava walls which surrounded it in "the elevated peaks which still bristle over the circus-like gorge occupying the very heart of the mountain. This was probably the site of its central crater, but now branching off into deep and short recesses, it forms the upper basin of the principal valley, and the recipient into which 2 mountain rills, the Dor and the Dogne, unite, at the source of the noble river which henceforward bears their joint names."—*Scrope*, 98.

The mineral springs, on account of which Mont Dore is resorted to from June to the end of September, are 8 in number, 2 being cold, the rest of a temperature of 106° to 113° Fahrenheit; they issue out of the trachytic rock, at the foot of the eminence called Plateau de l'Angle. They are alkaline, and are efficacious in complaints of the lungs, when unattended with inflammation, in disorders of the stomach, and in rheumatism. They are conducted into a very handsome *bathing establishment*, built, like the rest of the houses, of a trachytic lava, resembling that of Volvic, but obtained from a neighbouring quarry. The most copious source, *La Madeleine*, is also used for drinking, and large quantities are exported in bottles. It, as well as that called Le Bain de César, is enclosed in *Roman masonry*, proving that bath-loving people to have made use of these warm springs. Numerous architectural fragments, columns, &c. have been discovered here, supposed to have belonged to a temple whose foundations exist, and go by the name of *Le Panthéon*.

Horses may be hired at the rate of 3 f. a day; also guides, and chaises-à-porteurs with bearers for ladies, for



the numerous interesting excursions in the vicinity of these baths. In front of the bath-house is a pretty green promenade, encircled by the windings of the Dordogne, over which a suspension bridge has been thrown, conducting to a path which leads to the base of the *Capucin*, the isolated, cowl-shaped rock, conspicuous from all parts of the valley, named from a detached pinnacle, jutting forward on one side, said to resemble a monk in a hood.

The direction of the valley of the Dor from its head, at the base of the Pic de Sancy, to a short distance below the baths, is nearly due N. and S. In its E. side, not more than  $\frac{1}{2}$  an hour's walk above the baths, a singular breach or fissure is perceptible, worn away by the descent of a stream called *La Grande Cascade*, which has cut through the rock, and exhibits, in the face of the precipice, an instructive geological section of a series of beds of trachyte, tufa, and basalt. Vast blocks have been detached and hurled below, so that the stream, after its leap of nearly 80 ft., is almost hidden from view.

The Valley of Mont Dore is a region of woods and waterfalls; the latter, though not of any great elevation or grandeur, add an interest to the many pretty scenes around; the principal falls are the *Cascade de Quereilh* and *de Vernière*.

On the W. side of the valley, opposite to the Grande Cascade, is the gorge called *Vallée d'Enfer*, excavated out of a volcanic rock, consisting of scorix and other fragments, bearing the marks of fire, over which rise the naked summits of the Pic d'Aiguiller. The breccia is in many places penetrated by vertical dykes of dark porphyritic trachyte; and such a dyke forms the separation, called Les Fernes, between the gorges of Enfer and La Cour. Similar dykes are seen traversing the precipices of the Pic d'Aiguiller exposed to view at the end of the Val d'Enfer.

The ascent of the *Pic de Sancy* may  
France.

be made in 2 hours from the baths, on horseback, or in a chair; proceeding to the head of the valley, past the gorges d'Enfer and de la Cour, and turning to the l., near the ravine of La Craie, where a steep ascent begins, through a fir wood, in the depths of which lies the Cascade du Serpent, passing the marsh in which the Dore rises. The Pic is reached by passing the high Col between it and the Puy Ferrand. The distant objects seen from it are the volcanic group of the Cantal to the S., and the Monts Dôme to the N., while near at hand yawns a labyrinth of valleys and gorges, with peaks bristling around on all sides; and numerous small lakes glitter in the depths, among them the crater Lakes de Pavin and that de Chambon.

Another very interesting excursion is to the *castle of Murol*, situated to the E. of the baths, crossing the mountains by the Puy de Diane and the pretty little Lac Chambon. There is a road thither directly over the Mont Dore by la Croix Morand, but as it requires to be repaired every spring after the melting of the snow, inquiry should be made whether it is passable. Murol, the village, is built at the base of the red scoriaceous volcanic hill called Puy de Tartaret, upon a lava current which has issued from it, at a period long after the formation of the volcanic rocks of the Mont Dore. Murol is nearly surrounded by a dense forest, one of the finest in Auvergne. Homely and rustic accommodation at the public house kept by Morin.

The *castle*, one of the largest relics of feudal times in France, and a most picturesque object, crowns the summit of a detached eminence topped with basalt, affording a platform just large enough to hold the fortress, whose walls rise up, as it were, in continuation of the vertical precipices beneath them. It consists of a double enclosure, an outer wall flanked with bastions, dating from the 16th cent., and an inner circular wall, sur-

mounted by machicolations, of the 15th. In the midst rises a round tower, or *donjon*, commanding the country far and near, and affording a most interesting view of the plain and valley around, covered with lava vomited forth from the Tartaret. Some of the existing constructions of the castle are as late as the 18th cent., and none appear older than the 15th; the first mention of it occurs in 1223, when its seigneur was named Jean Chambre Chevarier.

The *Puy de Tartaret* deserves the attention of the geologist; it consists of loose scoriæ, lapilli, and fragments of granite, which have been forced up through the fundamental granite rock. "It has 2 deep and regular bowl-shaped craters, separated by a high ridge, and each broken down on one side:" the lava current which they have furnished first spreads over the plain, then, contracting, confines itself to the valley, whose sinuosities it follows as far as Neschers, a distance of 13 m., occupying the channel of the former river. Near Neschers and Champeix it assumes a regular columnar form. Neschers is a picturesque village, and the curé, the Abbé Croizet, has a collection of fossils.

Rather more than an hour's walk ( $4\frac{1}{2}$  m.) from Murol, passing partly over the lava from the Puy de Tartaret, and near the waterfall Des Granges, one of the prettiest in Auvergne, lies *St. Nectaire*, a village possessing *hot Baths* and an *incrusting spring*, much more remarkable than that at Clermont, which issues from the granite, and deposits large quantities of lime. The curious Romanesque church is a very ancient and unaltered but much dilapidated specimen of the style, no part of it apparently older than the 12th century. It is surmounted at the cross by an octagonal tower, and terminates at the E. end in 3 apses. The capitals of the pillars in the choir, carved with bas-reliefs of Scriptural and legendary subjects, are curious. In this church are preserved a curious Byzantine

crucifix of copper gilt, and a reliquary, in the form of a bust, of embossed copper gilt, also Byzantine, and probably of the 11th cent. The Castle of St. Nectaire, the cradle of a noble family, whence sprang 2 marshals of France, has been destroyed. On the rt. of the road to Neschers, a little way out of St. Nectaire, is the arch of a Roman bridge, the piers of which stand on the lava of Tartaret.

On the heights above the Bains de Boite, not far from St. Nectaire, are, some *Druidical remains*, consisting of a dolmen or altar formed of the unhewn blocks of the granite found in the country. On the summit of the hill of *Cornadore* are extensive excavations, supposed to be of great antiquity, formed, perhaps, by the Gauls as store-houses, or places of refuge: they are now used as sheep-sheds.

"Another interesting excursion, especially for the geologist, may be made to the rocks of La Thuillière and la Sanadoire,  $1\frac{1}{2}$  hour from Mont d'Or. The columnar feldspar or phonolite of the Roche Sanadoire is curious, and the view fine.  $1\frac{1}{2}$  hour more takes the traveller to the Lake of Servières, from which he may gain the great road to Clermont by descending the valley of the Sioule by Vernines (old castle) and St. Bonnet."—*P. F.*

The above is but a very imperfect enumeration of the curiosities and excursions of the neighbourhood of Mont Dore, which affords many other objects of interest, well calculated to repay the traveller for exploring. A full and excellent description of them will be found in the work of M. Lecocq, "*Le Mont Dore et ses Environs*.\*"

#### ROUTE 112.

CLERMONT TO LYONS, BY THIERS:—  
MONTBRISON.

177 kilom.=109 Eng. m.

*Diligence* daily.

\* For any corrections and additions to the above Route, derived from personal knowledge, the Editor will be much obliged.



The road out of Clermont runs nearly due W., passing on the l. the *Puy de la Poix*, an eminence of basaltic tufa, having on the N. side a spring of bitumen, or mineral pitch, which issues out of the earth along with a source of water.

15 Pont du Château, a prettily situated town, named from a bridge over the Allier, by which our road crosses it. "About  $\frac{1}{2}$  m. above the bridge, on the rt. bank of the river, there is an interesting geological display of fossiliferous freshwater limestone strata, alternating with calcareous beds containing volcanic substances."—*T. J. T.*

The *Château of Beauregard*, a little on the l. of the road, was formerly the country seat of the bishops of Clermont, and the residence of Massillon as such.

13 Lezoux, a small town on the verge of the Limagne, has an ancient church.

The *Castle of Ravel* belonged to Philippe le Bel. Our road is hilly, threading a part of the chain of the mountains of Forez, which separate the Allier from the Loire.

12 *Thiers* (*Inns*: Poste;—H. de l'Europe; new and good), an industrious manufacturing town, built on the top and slope of a peaked granitic hill, at whose base the Durole flows in a deep rocky bed, turning many paper-mills and forges, where various articles of *cutlery* are wrought, the staple manufacture of the town, giving employment to a large portion of its 9830 inhabitants. The town, so picturesque at a distance, with its houses rising one above another, on nearer approach is found to consist of dirty lanes; but from the upper part of it, especially from the high *terrace*, fine views are obtained over the Limagne, and the distant chain of the Monts Dôme. Here also is situated the antique church of *St. Genes*, a Romanesque building, chiefly of the 12th centy., though the vaults of the roof are newer: the end of the S. transept is ornamented with coarse

mosaics. More curious to the antiquary is the church *Du Moutier*, in the lower part of the town; the E. extremity of the choir has been referred to the 8th century.

A portion of the old *castle* remains.

The road for about 4 m. is carried along the edge of a precipice, and is called *Le Cordon*. The views over the rich plain of the Limagne, to the range of the Monts Dôme in one direction, and of the chain of the Forez in the other, are very fine.

14 *La Bergière*.

13 Noiretable, a village at the foot of the high Montagne de l'Hermitage.

12 *St. Thurin*.

15 Boën (*Inn*: Poste; tolerable, clean beds), a dirty village. It is about 11 m. distant from *Montbrison*, chef-lieu of the Dept. of the Loire, though inferior in extent and population (7,000) both to Roanne and *St. Etienne*. It stands at the base of a lofty and precipitous rock, from the top of which, or from the tower of the neighbouring church, as some say, the ferocious leader of the Calvinists, Le Baron des Adrets, compelled his Roman Catholic prisoners to leap, to their certain destruction. When one of the condemned, after twice approaching the brink, faltered in taking the leap, the tyrant exclaimed, "Two chances are too much." "I'll wager that *you* will not do it in ten" was the ready reply; and, it is said, saved the waverer's life. The *Cathedral* is a Gothic building (1205), and contains the tomb of its founder, Guy IV., Comte de Forez. (*Inns*: H. du Nord;—Du Centre.)

From Boën the road to Lyons crosses the flat and marshy plain of the Loire, and runs parallel with the Lignon, which is seen on the rt.; it is crossed, and at a short distance the river Loire also, before entering

18 Feurs, which occupies the site of one of the most important cities of the Gauls—*Forum Segusianorum*. In this name may be traced the modern one of Forez, given to the district of

which it was the capital, during the middle ages. Extensive fragments of Roman walls, aqueducts, inscribed stones, &c., attest its ancient consequence. Population 2,250.

The *railroad* from Roanne to St. Etienne (R. 119) runs past the town on the E., directly across our line of route.

Soon after, the road ascends out of the fertile valley of the Loire.

10 St. Barthélemy l'Estrà.

13 Sainte Eoy l'Argentière.

6 Duerne.

A high mountain ridge, a continuation of the hill of Tarare, described in R. 105, commanding an extensive view over the valley of the Rhône. and extending even, it is said, as far as Mont Blanc, is traversed in this stage.

11 La Braly.

14 Grand Buisson.

LYON. (Route 105, p. 372.)

#### ROUTE 114.

CLERMONT TO TOULOUSE BY THE CANTAL AND AURILLAC.

322 kilom. = 199½ Eng. miles.

Those who wish to avail themselves of a public conveyance must take the Montpellier diligence as far as St. Flour, whence a private vehicle may be procured to Aurillac.

The most direct road from Clermont to Aurillac is by Rochefort (R. 110) and Mauriac, but it is not provided with post-horses, and it avoids the picturesque district of *Cantal*, so interesting to geologists, through the heart of which the following road through Murat is carried.

It is the same as Route 109 as far as

55 Lempde, where it turns to the l., ascending a long hill as it quits the town. By another hill, du Grenier, you descend in zigzags to

18 Massiac (Dépt. Cantal), where you turn to the left out of the St. Flour road, by a very pretty branch line carried up the vale of the Alag-

non. This new road lies through scenery of uninterrupted beauty and interest, passing the picturesque castle of Merdogne, perched on a crag of basalt.

14 Ferrières (Cantal).

22 Murat.—*Inn*: Chez Dolly; tolerable, excepting the dirt. Fine trout here and elsewhere in the Cantal.

Murat is a dirty and antiquated town of 2,941 inhab., in the upland valley of the Alagnon, here bare of trees, but surrounded by hills of uncommon appearance, capped by basalt. One of these rises immediately behind Murat, in a tall cliff called *Roche Bonnevie*, composed of lofty and regular basaltic pillars, 30 to 50 ft. long. The castle on its summit was razed by Louis XI., after he had put to death its owner, Jacques d'Armagnac, 1477.

Opposite the town is another remarkable hill, also topped with basalt, on which stands the pilgrimage chapel of N. D. de Bredom.

Soon after quitting the town, the convent of St. Gal, now an hospital, is passed on the l., and the Castle of Anterroches on the rt. An excellent road is carried up the valley of the Alagnon, constantly ascending, amidst cliffs and precipices of granite. Near the Pont de Pierre Taillée, a bridge thrown over a stream which falls in a pretty cascade, a good geological section of the trachyte and tufa has been exposed. Above this, the fine fir forest of Lioran, which clothes the upper part of the valley, commences. The additional steepness of the valley near its head has hitherto been surmounted by a series of tourniquets or zigzags; but in order to avoid this, as well as the snow which blocks up the highest part of the road, frequently for weeks and months in winter and spring, a *Tunnel* is carried through a saddle-shaped ridge, which divides the waters of the Alagnon from those of the Cère, a little to the E. of the highest point of the old road, and about 400 or 500 ft. below it. This



Tunnel is driven through the trachytic rock for a distance of about 4,593 ft. (1,400 mètres); it is nearly 18 ft. high, ascends slightly in the centre, and terminates a little below the village of les Chazes. On emerging from it, the *Puy de Griou*, a pointed, wedge-shaped peak of white rock, with a stream of débris descending from it, is seen on the rt.; and the *Plomb de Cantal*, a boss like a camel's hump surmounting a precipice, rises on the l. Those, however, who are content merely to pass through the tunnel, will miss altogether the grand and striking scenery of the vast volcanic amphitheatre, through the midst of which the old road is carried, in proximity to the sources of the Alagnon and Cère.

The traveller, whether geologist or merely a lover of picturesque, will be well rewarded by making the ascent of the *Puy de Griou*, which may be effected in about an hour from the hamlet of les Chazes, even without a guide. It is fatiguing from the extreme steepness of the slope; but the only difficulty is in surmounting the bare crest of white clinkstone, covered with loose fallen masses, which rattle down under your feet into the depths below. But even here a sort of path has been formed, over the scanty grass tufts springing up between the stones. The summit itself is a mere crest only 3 or 4 ft. wide and 20 yds. long, plunging precipitously down on all sides. The Puy de Griou rises in the midst of an irregular circle of precipices, supposed by geologists to have been the fiery mouth or crater whence the volcanic rocks of the Cantal were erupted, and whence they spread for 15 or 20 m. around, from this centre as far as Aurillac, Murat, and St. Flour. It is also supposed, that, at a later period, the volcanic forces acting from below, at the same point, burst through these deposits of trachyte, tufa, and basalt, fracturing the strata, with radiating cracks like those in a starred pane of glass, and that these cracks gradually widening,

became the valleys of the Alagnon, Cère, Jourdanne, Dienne, &c. The circuit of precipices which composed the walls of this crater is broken by gaps formed by the openings of the different valleys radiating from this point like the spokes of a wheel. These walls are most perfect on the E. below the basaltic hump called Plomb de Cantal, the highest summit in the district, 6,095 ft. above the sea level; on the N. in the Puy Mary, 5,459 ft.; and on the W. in the Puy Chavaroché. Through the gaps between them, the eye ranges down the vistas of the valleys over an extensive horizon of plain and distant hills. The dimensions of this crater greatly exceed those of any in Auvergne, as it is more than 6 Eng. miles in diameter. Within and beneath its bounding walls are rounded slopes, wooded or covered with turf, forming the lining of the crater, and presenting a pleasing picture. Quite at the foot of the Puy de Griou is a remarkable kettle-shaped hollow, covered with the brightest verdure, and dotted over with 2 or 3 cabins, and with herds, for it is the best piece of pasturage in the district. From its shape it might be mistaken for a minor crater, hemmed in by wooded eminences. It is called *le Font du Vacher*.

Quitting the volcanic amphitheatre at les Chazes, we commence the descent of the valley of the Cère, which is far more picturesque in its scenery than that of the Alagnon, but is best seen in ascending, as the forms of the mountains at its head lend to the views their most striking features. The first village, St. Jacques des Blats, produces excellent cheeses of goat's milk, called *cabeçons*. The numerous projections on either side of the valley conceal the villages from view until you are close upon them. The river cuts through a rocky bed, and the road, skilfully engineered, is carried in terraces hewn out of the trachytic rock, along the edge of deep precipices, the most remarkable of which,

called *Pas de Compain*, terminates within a few hundred yards of the village of

26 *Thiézac*, where the *Poste* (*Tête Noire*), though most forbidding externally, by reason of its dirt, can afford 2 clean beds and a tolerable supper, with trout; for which and a breakfast only 5 fr. are charged. Below *Thiézac* calcined flints shattered by heat, like unannealed glass, may be seen embedded in the trachyte rock at the road side.

The most strikingly picturesque scene in the whole valley is at a spot called *Pas de la Cère*, a little way above the solitary projecting rock (*Rocher de Murat*), rendered conspicuous by the single round-headed lime tree which crowns its summit. Here the valley at once expands considerably, and makes a deep descent or step, and the river has forced for itself a passage, at a great depth below the road, in a fissure lined by smooth walls of rock, and nearly shrouded by a luxuriant growth of trees. The rocks towering above the road imitate the forms of old castles. The little town of *Vic* (*Vic-en-Carladés*, or *Vic-Sur-Cère*) is the chief place in the very picturesque valley. (*Inn*: *Chez Vialette*.) Close to it there are mineral *springs* of acidulous water, received into a *bathing establishment*. 1 m. out of the town, at the roadside, stands the *Château de Comblat*, belonging to an ancient and loyal family settled here for ages, the present owner being the *Comte Charles de la Baume*. At *Polminhac* is a far more picturesque *castle*, towering over the road, a fit subject for the artist's pencil. The valley of *Vic*, here widening out into a small plain, covered with meadows and corn fields, is yet enlivened by a pretty distribution of wood and hedgerows, amidst which rise numerous *châteaux* and modern country houses, indicating that the proprietors reside on their estates. At this point our road quits the vale of the *Cère*, gradually ascending in a sloping terrace cut

through the white tertiary limestone, containing flints, in appearance closely resembling the upper chalk of England, though of a very different age, which has been disturbed and baked by the trachytic rocks. Turning the shoulders of the hills, we enter the valley of the *Jourdanne*, a tributary of the *Cère*, at the mouth of which stands

27 *Aurillac* (*Inn*: *Trois Frères*; best and good), *chef-lieu* of the *Dépt. du Cantal*, and anciently one of the 6 good towns of *la Haute Auvergne*, is a dull town of 11,000 inhab., without objects of interest, in a tame and bare valley watered by the *Jourdanne*. The churches, convents, and palace of the abbot were destroyed by the Huguenots, who took the town, 1569, by assault, and kept it for a year: the existing public buildings are modern and common-place. The *Castle of St. Etienne*, rising on a rock above the town to the W., is said to have belonged to the ancestors of *St. Géraud* (d. 918), the patron of the town: it was held by the abbots, and now belongs to the bishop of *Clermont*, but is not worth visiting.

The chief manufactures carried on here are of copper kettles and coarse lace.

The infamous *J. B. Carrier*, the author and inventor of the *Noyades* at *Nantes* (p. 169), was born, 1756, in the village of *Yolet*, close to *Aurillac*.

*Diligences* daily to *Paris*, to *Rodez*, 3 times a week to *Toulouse*, by *Figeac*. The road to *Figeac*, after crossing the level verdant valley of the *Cère*, and the river itself, mounts into a hilly district of gneiss and mica slate rocks, barely covered with heath. From the high ground fine views are obtained of the volcanic group of the *Cantal*.

27 *Cayrols*.

A very long and winding descent doubling the shoulders of the hills, and diving deep into the recesses of the glens, leads down a wooded valley to



Page. 415. at Villefranche.

(note 1) It is one of the Bastides or Free-towns built in the 14<sup>th</sup> century. and retains its regular plan.

(note 2) In the suburbs on the other side of the river is the public Hospital formerly a Carthusian Monastery the buildings of which are preserved nearly entire including a good Flamboyant Church, and the Refectory with its rich pulpit and tower.

Page 415 (note 3) at Caylus ~~The~~  
Opposite the north door, is a remarkable  
~~well preserved~~ house of the 14<sup>th</sup> century the  
house of which is very perfect & curious.

the poem of the sugar loaf.

Cordes. Hotel du Berg - (on the top of the Hill) Good.

H. de Commerce at the bottom bad and cheating!

A very curious little ~~fort~~ house on the top of  
a sugar loaf hill, remarkably steep - The old  
fortifications and gate still remain. and within

The Walls are a number of stories of the 13 & 14<sup>th</sup>

centuries the ~~front~~ of which are very elaborate

and in most perfect preservation. The Antiquary

should by no means pass by this house as the arduous  
ascent of the Hill, will be well repaid. (J.H.P.)



Page 415.

(note 4)

On a cross road to Alby are

St. Antoin. - ~~a small~~ to H. de Commerce - ~~Attenly~~ but clean

" de Ville "

A small town with a very pretty Hotel, the greater


part of the 12<sup>th</sup> century, lately ~~restored~~ well restored

by under the direction of M. Rollé - de - Doue. There

are a number of old houses of the 13<sup>th</sup> & 14<sup>th</sup> centuries (and

much mutilated). And others of later date, in line of

which are very fine. Laundry and iron place. (J. H. P.)





18 Maurs. Another hilly tract intervenes before we reach

24 Figeac—(Inn: Poste)—a town of 6400 inhab., in the Dépt. of Lot, lying snugly at the bottom of a small valley, so shut in by steep hills that the high roads are obliged to make the most singular and circuitous contortions in order to reach it. The town, whose naturally obscure name has become familiar through its illustrious citizen Champollion, who was born here, and to whom a monumental *obelisk* has been erected at the water side, contains a great number of antique houses, and 2 curious churches. The abbey *Church of St. Sauveur*, in the lower part of the town, consists of a Romanesque basement, with a later pointed superstructure of the 15th cent., and a modern front of the 19th. The choir, however, seems almost entirely of the 11th cent. Attached to the S. transept is a small chapter house, resting on pointed arches.

On an eminence, above the town, stands *Nôtre Dame de Puy*, a church of the 11th cent., though much altered, in the form of a basilica, ending towards the E. in 3 apses. At the bottom of the choir is a very fine *altar screen* of wood richly carved and ornamented, a masterly work of the early part of the 17th cent., judging from its style.

The *Château de la Baleine*, now Palais de Justice, fortified and moated, also deserves attention.

A high table-land of limestone, bounded by very abrupt slopes, separates Figeac from the valley of the Lot. After reaching its summit by a steep ascent, the road to Villefranche passes near a singular stone *pillar*, or obelisk, rising on the brow of the hill above Figeac. Its use and age are equally unknown. Some consider it to have been a beacon: it was more probably a landmark to designate the boundary of some jurisdiction. There is a similar pillar on the other side of Figeac.

From the high ground a view is

obtained, on the l. of the town, of Capdenac, on the rt. bank of the Lot, supposed by Champollion to be the ancient "*Uxellodunum*," besieged by Cæsar, and mentioned in his Commentaries.

The Lot is crossed by a wire suspension bridge: the hills bordering on the river sides are very steep.

18 La Remise.

17 Villefranche (Inn: Grand Soleil). This is a town of 9540 inhab., on the Aveyron. Its principal building is the large *Collegiate Church*, in the pointed Gothic style of the 15th and 16th centuries, standing in Place surrounded by arcades. Its W. façade, though bare of ornament, is imposing from its proportions, and is surmounted by a lofty tower, supported by obliquely set buttresses, at the base of which a porch, furnished with triple arches, gives entrance to the interior.

There are many ancient houses of the 15th and 16th centuries, very picturesque in their architecture, in the principal street.

Steep hills lead into and out of

29 Caylus, a town of most picturesque character, both in itself and in its situation, buried as it were in the deep recess of a valley. In the midst its *castle*, rising on a rock, towers above the houses clustering round its base; and by its side rises the church spire.

The road emerges from this bowl-shaped hollow, by being carried in bends round its nearly vertical sides.

22 Caussade } described in R.  
23 Montauban } 70.  
51 TOULOUSE }

## ROUTE 116.

CLERMONT TO TOULOUSE BY ST. FLOUR  
—THE BATHS OF CHAUDES AIGUES,  
RODEZ, AND ALBY.

385 kilom. = 238½ Eng. m.

*Malleposte* as far as St. Flour, and thence to Montpellier, in 31 hours.

The route is identical with R. 109 as far as

54 Lempde (*Inn*: la Poste). At.

18 Massiac (Cantal) it turns to the l., away from the road to Aurillac, and reaches, by an ascent requiring  $1\frac{1}{2}$  hour to surmount, an elevated plain called la Fageole, formed by a great basaltic plateau.

10 La Barraque is a solitary post house, surrounded by a few farm buildings, in a desolate spot.

About 5 m. short of St. Flour, a good view of it, and of the volcanic group of the Cantal beyond, is obtained.

19 St. Flour (*Inns*: chez Aubertot, tolerable; supper, bed, and coffee cost 3 fr. 5 sous;—H. de France).

St. Flour, the 2nd town in importance of the Cantal, is strikingly conspicuous at a distance, owing to its elevated position on the top of a table mount, whose platform is of basalt. The high road from Clermont to Montpellier passes through a suburb at its base; but the upper town is rendered accessible for carriages by a road carried in winding terraces cut into the basaltic rock, and laying bare a regular natural colonnade near the crest of the hill. Excepting its singular and picturesque situation, bounded on 3 sides by escarped precipices, the town, consisting of narrow streets and houses built of basalt, and containing 6464 inhab., is deficient in attraction. Its *Cathedral*, the chief edifice, is a Gothic structure, not remarkable, dedicated 1496, but not finished till 1566; its towers, demolished in 1593, have been recently rebuilt. The roof is finely groined, and rests on piers without capitals.

From a little terrace behind the Cathedral, from another behind the Séminaire, and from the *Promenade*, or *Cours Chazeret*, occupying the neck of land by which the town is alone connected with the adjoining high ground of the Planèse, views may be obtained over the country and distant hills, but they are arid and bare, and over the contiguous valley watered by the Arder, on

whose banks the suburb, the most busy part of the town, is planted. The basaltic rocks in the neighbouring mountains are covered with the lichen archil (orseille) used in dyeing, which is collected and largely exported hence.

St. Flour was anciently a very strong fortress, and withstood many sieges from the English in the 14th century.

At this point the road to Chaudes Aigues and Rodez separates from that to Montpellier; a *malleposte* from Clermont follows the latter through St. Chely, Marvejols, and Milhau.

The road to Chaudes Aigues traverses for a considerable distance the elevated basaltic plateau called la Planèse. The volcanic group of the Cantal mountains is visible for a long time on the W.

On the way to Chaudes Aigues, but considerably to the l. of the road, lies Alleuzes, mentioned by Froissart under the name Louise, a castle which belonged to the celebrated robber-chief of the 14th century, Aymerigot Marcel, whence his band used to sally forth to pillage on the highways. A little further in the same direction is *Montbrun*, another castle, which was taken and held for the English, 1357, by John Chandos, constable of Guienne.

The approach to Chaudes Aigues is by the steep hill called Côte de Laneau, where the road has been terraced through rocks of gneiss and mica-schist, whose contortions are laid open in sections, at the edge of ravines and precipices. After passing the ravine called Saut du Loup, from a fanciful resemblance in the rock to a wolf's head, it descends into the valley or gorge of the Truyère, a tributary of the Lot. That river is passed on a handsome stone bridge.

33 *Chaudes Aigues*.—*Inns*: the best is Chez Fabre, recently rebuilt;—H. Felgère, furnished with baths.

This is an old but rustic-looking town of 2351 inhab., planted in a narrow and picturesque gorge, which



about 3 m. below opens into that of the Truyère. The *mineral waters* from which it has obtained some resort as a watering-place are almost pure warm water: they issue out of the slate-rock, and are 4 in number. That called *Source du Par* is the hottest spring in Europe, except the Geysers in Iceland, having a temperature of 177° Fahrenheit, and is one of the most copious sources in France; the others, *de Felgère, du Ban*, and *de la Grotte*, vary in heat between 135° and 162° Fahr. The waters are taken in baths, and are drunk, being considered efficacious in rheumatism, swellings of the joints, and some cutaneous disorders, though by no means richly impregnated with mineral particles. They are also turned to various domestic and economic purposes: they have the property of discharging most rapidly the grease from sheep's wool, and a vast number of fleeces are sent hither from the Dépt. Aveyron to be washed. From the month of Nov. to April the hot water is used for warming the town, being conducted in pipes into some of the houses, called in the patois of the country *Maison Caoudo*; and it thus saves the inhabitants the cost of many tons of coal or whole forests of firewood: the equal distribution of the waters is watched over by the police. The hot streams are also partly employed for cookery, for boiling eggs, preparing soups, and scalding pigs. They have also been turned to the artificial incubation of chickens with considerable success.

There is no object of interest in or near the town except the waters. A ruin at a short distance, near the chapel, is called *le Fort des Anglais*; indeed the English are said to have captured the town in the 14th century, in the two incursions which they made, in 1357, under the command of Robert Knollys, and in 1387. A large portion of the inhabitants of Chaudes Aigues migrate every winter to Paris, to obtain employment in various menial offices,

as water-carriers, *décrotteurs*, &c.—a practice common among the lower orders throughout Auvergne. From Chaudes Aigues it is possible to ascend on foot the Plomb de Cantal and descend on Thiézac (p. 414), but this cannot be accomplished in a single day.

Scarcely a human habitation occurs on the long stage from Chaudes Aigues, except the poor hamlet of Lecalm, where the road enters the Dépt. Aveyron; a hilly road.

32 Laguiole, built on the slope of a basaltic hill, trades in the excellent cheese made in this district.

The road skirts on the l. a valley, in whose recesses, once shrouded by forests, stood the venerable and wealthy Bernardine Monastery of Bonneval, now entirely swept away. The descent into the fertile and verdant valley of the Lot is very pleasing. Above the winding course of the river, which is bordered with wooded and vine-clad slopes, rise the escarped peaks crowned with the ruined *castles* of Caumont and of Roquelaure.

24 Espalion (*Inn*: Chez Aigalenz, tolerable) is a prettily-situated small town, residence of a sous-préfet, on the Lot. There is nothing of interest in the town itself, but in its vicinity the two castles already mentioned, and a curious *chapel* in the cemetery of the village of Perse.

The road to Rodez ascends out of the valley of the Lot after crossing it, under the castle-crowned height of Caumont. From a distance of many miles the traveller discerns the picturesque towers of

31 Rodez (*Inns*: Ville de Paris, good;—H. des Voyageurs;—Des Princes), chef-lieu of the Dépt. Aveyron, is a town of 9685 inhab., and occupies a commanding site on an escarped peninsula, surrounded on three sides by a curve of the Aveyron, which flows at a depth of 150 ft. below. The tongue of land, which alone connects it with the neighbouring plain, is traversed by the road from Paris and Espalion; from all

other sides the town is accessible only by steep ascents.

The *Cathedral*, so imposing and conspicuous at a distance, will probably not altogether justify the impression it has produced on a near approach, though it is of large size and possesses some elegant details. It was founded 1274, but carried on slowly through the two following centuries, and never finished. The W. end is destitute of entrance, because fitted up internally with a high altar as well as the E. end. The entrances are at the sides, and, though mutilated, display some rich ornaments; near the N. transept rises the *belfry*, the pride and boast of Rodez, 265 ft. high, consisting of a square base supporting an octagonal summit, richly ornamented in the upper part with florid tracery. It is surmounted by a statue of the Virgin, and was finished 1531.

The interior of the church, 110 ft. high, rests on piers without capitals, and the style of its decorations resembles the perpendicular of English Gothic. At the entrance of the choir is a fine *Jube* (rood-loft), which, though mutilated, exhibits workmanship of surprising beauty, in the delicate sculpture of its curled foliage. A part of the *screen* intended to surround the choir is of like beauty. The wood-work of the *stalls* and bishop's throne in the choir are of good execution, and were well preserved until painted recently. One of the side-chapels contains a fine *altar-screen* of wood, elaborately carved with bas-reliefs, arabesques, and ornaments partly Gothic, partly classic, in the style of the 16th centy. The whole is painted and illuminated. The partition *screen* to this chapel is of rich open work in stone, flamboyant in its style. The wood-work of the organ-loft, a tomb in the form of a sarcophagus, adorned with bas-reliefs of the 9th centy.; another tomb of Bishop Guirbert, 14th centy.; an altar-table of white marble, 6 ft. long, with Byzantine

ornaments, 10th centy., now used as an altar-screen, and painted with a figure of the Virgin,—also deserve attention.

The town abounds in antique houses of the 15th and 16th centuries, and contains some of perhaps a still older date. In the *Place d'Omet*, there is a house charmingly decorated, in the style of the Renaissance, with arabesques, medallions richly framed, and in the upper story with a range of fantastic consoles.—(See Merimée, 157—169.)

Terraces run round the town upon the line of the old fortifications, and afford agreeable views, though the country round Rodez is not particularly attractive, the valley of the Aveyron being bare and not very fertile.

Rodez was the *Segodunum* of the Romans, and capital of the Gaulish tribe the Ruteni, whence comes its present name.

*Fromage de Roquefort*, the choicest cheese which France produces, which was sent to ancient Rome, and was enthusiastically praised by Pliny, is made with ewe milk, in the mountains of La Lozère, about 28 m. E. and S. of Rodez, in the district around St. Rome, St. Afrique, St. Georges, and Milhau. It is kept in cellars, belonging to the cheesemongers, to ripen. About 10,000 cheeses are made annually. The village of Roquefort, where are the principal cellars, is situated near St. Afrique, in the midst of the pastures of Larza, which support more than 100,000 sheep.

*Diligences* go to Toulouse and Montauban.

The *Valley of Marcillac*, beginning at Salles Compteaux, about 5 m. N. of Rodez, forms an agreeable contrast to the barren district immediately around that town. This beautiful green dell, gushing with springs and waterfalls, covered with trees and orchards, is excavated out of a high plain destitute of vegetation, which must be crossed to reach it. At the



head of the valley rises an old castle, near which a copious spring bursts forth. Following this valley past Marcillac (5 m.) along the banks of the Dourdou for about 12 m. below that town, you reach *Conques*, a small town half hidden in a rocky ravine, in the midst of the wildest mountains of the Rouergue, scarcely accessible at some seasons, owing to the badness of the roads. It owes its origin to an ancient abbey, whose site it occupies, but the buildings of which have all disappeared except the *Church of St. Foy*, constructed to all appearance at the beginning of the 11th century by Abbot Odalric. It is entirely in the Romanesque style, with semicircular vaults and arches; it terminates at the E. in 3 apses, and is surmounted at the cross by an octagonal tower more modern than the rest (14th century). The W. end is flanked by 2 towers; the central portal is ornamented with a curious bas-relief in the tympanum, representing the Last Judgment, divided into 3 horizontal friezes; in the centre, Christ within the *Vesica piscis*; on his rt. the good, on his l. the wicked; above, angels; below, on one side, the gates of Paradise, with bolts and a huge lock, and the dead rising from beneath their grave-stones; in the centre, below Christ, an angel and devil weighing souls; on the other side, the gate of hell, an enormous open jaw, into which the devil is thrusting the condemned. Each group and portion of the relief is designated by inscriptions in Leonine verses. The figures are coloured.

The *Trésor* of the church contains the following curious and valuable relics of ancient art, which at the Revolution were intrusted to the care of different inhabitants of the town, and were most carefully preserved, and religiously restored by them when the political storm had passed away. An ancient *reliquiary*, called Charlemagne's A, from its triangular form, and the tradition that it was given by that monarch to the abbey;

it is of silver gilt and partly enamelled, and set with polished gems and some antiques; at the base are 2 little figures of gilt bronze, supposed to be less ancient than the upper portion. A statue of St. Foy, 18 inches high, of silver gilt, and studded with precious stones and antique gems, cameos, &c.; a Byzantine enamel of the figure of a saint, on a plate of copper; a silver crucifix of beautiful workmanship; a square slab of red porphyry in a frame of silver, covered with heads of Christ, the Virgin, and Saints in niello. There are also some tapestries of the 16th century.

About 3 m. below Conques the Dourdou falls into the Lot.

The high road from Rodez runs through

26 La Motte. *Inn*: Chez Nave.

30 Farguette.

At Carmeaux a coal-field is worked, which furnishes good fuel.

22 *Alby*—(*Inns*: H. des Ambassadeurs; de l'Europe; du Nord, good)—an ancient city, chef-lieu of the Dépt. of the Tarn, in the midst of the flat but fertile plain of Languedoc, watered by the river Tarn, has 11,662 inhab. Its buildings are of brick, as is the case throughout the plain of Languedoc; the ramparts are thrown down and planted, and especially on the side next the new Quartier de Vigan, there are extensive walks, avenues, and gardens, partly on the site of the ancient lists (les Lices), where tournaments were held.

The *Cathedral of St. Cecile* is the chief building in the town; it is a noble Gothic edifice of brick, founded 1282, and not completed till 1512. The tower at the W. end, raised by Louis d'Amboise, 1475, is 290 ft. high and of curious construction. The nave, without transepts, and unsupported by pillars, is 88 ft. wide and 98 ft. high. The choir is separated from the nave by a *rood-loft* (*jube*) of extreme beauty of design, and elaborate delicacy of execution in its Gothic tracery, foliage, &c.; the enclosure of the choir is of equally rich workmanship. But

the most striking feature of interest is the profusion of *fresco paintings* on the roof and walls, which escaped destruction at the Revolution; portions in the vaults are untouched, and of the utmost freshness and beauty, on an azure ground, the work of Italian artists, 1505. In some of the side chapels, and near the entrance, are paintings of a still earlier date (14th century), and in a style resembling that of the German schools. The stone carvings of the choir, consisting of elaborate tabernacle work with a profusion of statues, were executed for Cardinal d'Amboise by a company of itinerant masons from Strasburg.

The *Préfecture*, formerly the Episcopal Palace, but at a still earlier period the residence of the counts of the Albigeois, is, in part, a heavy castellated edifice of brick, at the margin of the Tarn, on its l. bank. Its terraced garden, overlooking the river, is pleasing.

The *Church of St. Salvi* presents some architectural features of interest.

Some manufactures are carried on here of coarse linen cloths, candles, and tools, files, scythes, also of *woad* (pastel), which has been made here from a very early period. The chief commerce is in grain; the plain of Alby being one of the richest corn countries in France.

Alby has given its name to the sect of dissenters from the Church of Rome, the *Albigeois*, who abounded in the district during the 12th and beginning of the 13th centuries, and who were condemned as heretics by a council held here, 1254, and soon after nearly exterminated at the siege of Beziers. (Route 126.)

Alby is the birth-place of the unfortunate sea captain and circumnavigator of the globe, La Peyrouse.

At *Saut de Sabot*, about 3 m. off, the course of the Tarn is intercepted by rapids of considerable descent, by the side of which a furnace and forge for the manufacture of steel is established.

The *Castle of Castenau de Levi*, on the rt. bank of the Tarn, is a picturesque object. The Tarn is crossed at the village of Marsac.

21 Gaillac stands on the rt. bank of the Tarn, in a country producing abundance of wine. Its population exceeds 7000.

23 Pointe-Sainte-Sulpice.

16 Montbert.

15 TOULOUSE. Route 70.

## ROUTE 118.

LYONS TO LE PUY, AUBENAS, AND MENDE, BY ST. ETIENNE.—RAILWAY TO ST. ETIENNE. — ARDÈCHE, AND CEVENNES.

220 kilom. = 134 Eng. m.

Railroad from Lyons to St. Etienne,  $14\frac{1}{2}$  leagues =  $35\frac{1}{2}$  Eng. m. Trains go 3 times a day in 4 hours, returning in  $3\frac{1}{2}$ ; the line is not well made, the jolting is great, and the carriages, except the first-class (*coupés*), are large and dirty, and filled with workmen and market-people; stoppages are frequent at the numerous villages near the line. It was opened 1837. It is carried through more than a dozen tunnels. Its chief use is to supply Lyons with coal from St. Etienne. The *terminus*, or *depôt*, is situated outside the town of Lyons, in the *Faubourg de Perrache*, between the Saône and Rhône, but passengers are conveyed thither in huge omnibuses, which start from the Place Bellecour. The railway is carried over the Gare, or safety dock for barges, opening into the Saône, and crosses the Saône itself just above its junction with the Rhône, by the suspension *Pont de la Mulatière*, and thenceforth skirts the rt. bank of the Rhône as far as Givors, sometimes close to the river, sometimes separated from it by low meadows and rows of plantations of willows, which intercept much of the view.


The course of the Rhône is described in R. 125.

Rt. The first village is Oullins, surrounded by country seats of Lyonese



Page. 420

On the opposite side the river stands the little church  
of <sup>Lescures</sup> ~~Lescures~~, quite a model of the Byzantine style of the  
11<sup>th</sup> century in this part of France. -





manufacturers; in its churchyard Jacquard, the inventor of the loom named after him, is buried. The line is carried through several small tunnels and cuttings past the villages Irigny, Vernaison, and Grigny, before reaching Givors.

13 Brignais, the first post station on the high road, is about 5 m. to the W. of the railway. At Irigny the high road crosses a hilly range between Brignais and Rive de Gier.

Givors, a dirty and smoky town, abounding in manufactories, especially of glass bottles, on the rt. bank of the Rhône, at the point where it receives the stream of the Gier, and the *Canal de Givors*, which transports much coal and ironstone. Population about 5000.

Omnibuses go hence to Vienne (R. 125), 5 m., in about an hour, corresponding with the railway trains.

The railroad here quits the side of the Rhône, and ascends the valley of the Gier, keeping that stream and the canal on the rt. hand. Industry prevails everywhere; manufactories occur at every step, and envelope the country with their dense smoke.

A tunnel about  $\frac{3}{4}$  m. (1500 mètres) long is driven through a hill of the coal measures, near Terre Noire, before reaching

17 La Rousillière.

22 Rive de Gier, a very flourishing and increasing manufacturing town of 12,000 inhab., on the rt. bank of the Gier, at the commencement of the Canal de Givors, situated in a productive coal-field, which is the chief source of its prosperity. More than 40 coal mines in the vicinity are provided with steam-engines. There are very large glass works here, and a manufactory of steel carried on by Englishmen, Messrs. Jackson, which produces the best steel in France.

Here are also manufactories of steam-engines and other machinery, and some silk mills. Lyons is chiefly supplied hence with fuel; but Mar-seilles, Mulhausen, Paris, and Nantes also receive fuel in large quantities

from this coal-field, the most important in France, from its extent and position. Above this, owing to the steep inclination of the railway, horse power has hitherto been alone employed; but a new and more level line is being cut (1843) to admit of the use of locomotives. The railroad and post road run side by side to

15 St. Chamond, another manufacturing town, where ribbons and stay-laces are made. More than 1200 frames (*métiers à la poupée*) are employed in weaving stay-laces, which are largely exported. Here are besides numerous iron furnaces, founderies, and forges, and several silk mills. Population, 8246. This place has been much injured by the railway not passing through it. Between St. Chamond and St. Etienne runs the ridge separating the waters flowing into the Mediterranean through the Rhône, from those which go to the Atlantic through the Loire.

Another *tunnel*, about 1 m. long, traverses a hill under a considerable village, immediately before reaching St. Etienne. It is very narrow and low, affording space for only one line of rails. The latter part of the line is an inclined plane, which the train descends by its own impetus in going to Lyons.

12 ST. ETIENNE, in Route 119.

The diligence takes 12 hours to make the journey from St. Etienne to Le Puy. The road is very hilly and varied: crossing a long ridge out of the valley of the Furens, it continues to traverse a district very populous, and abounding in manufactures as far as the coal measures extend. At Le Chambon are manufactures of cutlery, nails, saws, &c. At

12 Firmigny there are many coal mines, some of them worked after the fashion of quarries, open to the sky, in a coal bed more than 32 feet thick; also glass works, ribbon and silk mills. The valley is bristling with chimneys, coal heaps, manufactories; but they cease before you reach St. Ferreol, just within the

borders of the Dépt. de la Haute Loire. The road is admirably engineered, and partly cut through the granite rock in a terrace winding round the shoulders of the hills.

17 Monistrol: the château, formerly a country seat of the Bishop of Le Puy, is now a ribbon manufactory. Some ribbons are woven here, but the manufacture extends no farther. 4 m. beyond Monistrol our road approaches the Loire, and crosses, by a very long and steep descent and ascent, the deep and picturesque gorge of the Langon, which falls into the Loire about  $\frac{1}{2}$  m. below the bridge. The course of that river and its deep and wide valley may be traced for a considerable distance on the rt. from the heights beyond the Langon.

20 Yssingaux. — *Inn*: H. de l'Europe; not good. A town of no particular interest; pop. 6700.

Near this we enter the volcanic district of the Velay: on either side of the road rise hills of basalt and trachyte, and from the summit of the trachytic ridge of the Montagne de Pertuis, which it traverses by a long ascent, an excellent panorama is presented of the country. A part of Le Puy itself is visible. The hills generally assume a conic form, and are frequently capped with basalt. The top of the Mt. Pertuis is of slaty clinkstone, which is used for roofing houses.

On the rt. of the road is passed the ruined Castle Lardeyrolles, perched on the top of such a volcanic eminence.

Within 3 m. of Le Puy the Loire is crossed, here an insignificant stream descending from its source at Gerbier des Jones, at the base of the Mont Mezène in the Dépt. de l'Ardèche. The pedestrian may proceed direct from Le Puy to Montpezat and Aubenas by the Source of the Loire. See page 406, col. ii.

A good view is obtained of the town of Le Puy in approaching it, though it is partly concealed by the Rocher de Corneille.

23 *Le Puy*, in Route 109.

The road to Mende is now furnished with post horses; it is very hilly, being carried over part of the range of the Cevennes, in which some of the principal rivers of France take their rise. At first it ascends the valley of the Dolaison. From that stream as far as Pradelles the country is all volcanic.

19 Castaros.

About 3 m. W. of this is the Lac de Bouchet, a mountain tarn occupying the basin of an ancient crater, 91 ft. deep in the centre, without visible outlet.

At the small and elevated town of Pradelles, near which the granite rock shows itself, a cross road strikes off to Aubenas, by Savilatte, over the mountains into the valley of the Ardèche, near its source, and follows its course downwards, by Mayras, to Thueyts. (*Inn*: chez Burine.) Thueyts is built on a current of basaltic lava, which has flowed from a crater a little to the E. of it, and has occupied the bed of the Ardèche; but the river has cut for itself a passage on one side, laying bare a majestic colonnade of basalt 150 ft. high, stretching with a few interruptions  $1\frac{1}{2}$  m. down the valley. Its situation and environs are most picturesque and interesting (see p. 433). About 4 m. below Thueyts, the river Alignon enters the Ardèche from the S. The course of that stream for about 3 m. up lies at the base of vertical cliffs formed of columns of basalt 150 ft. high, the section of another lava current, made by the Alignon, which has gnawed for itself a channel between the granite and the basalt. This lava current is traced up to a large volcanic crater, called, from its regular cup shape, *La Coupe de Jaujac*. It has been breached and broken down on one side. Its cone and slopes are covered with Spanish chestnut trees, which grow in the greatest luxuriance on volcanic soils, as is especially seen on the slopes of Mount Etna. This crater of Jaujac has burst forth through a coal formation, which lines



the bottom of a triangular-shaped valley, bounded by mountains of granite and gneiss. The village of Jaujac stands in a very striking and singular position, on the edge of the basaltic precipice, on the rt. bank of the Alignon, near the base of the crater, whence a mineral spring and copious jets of carbonic acid gas issue. Another lava current enters the Alignon about 300 yards above its junction with the Ardèche; its origin is to be sought in another volcanic cone, the *Gravenne de Souillols*. It has spread for a considerable distance down the valley of the Ardèche. Numerous picturesque ranges of columnar basalt are presented on the river banks from time to time. Some of the most striking occur near *Pont de la Beaume*, at the junction of the Fontaulier, which flows from Montpezat, with the Ardèche. The excursion to Montpezat and the rest of the road to *Aubenais* are described in Route 121.

The road from Pradelles descends into the valley of the Allier, which it crosses before entering

21 Langogne, a town of 2720 inhab., in the Dépt. de la Lozère. It has an ancient church, which belonged to a monastery founded in the 10th century.

20 La Vitarelle. About 6 m. to the S. and E. of this the rivers Allier and Lot take their rise. A stone has been set up here to commemorate the death of the chivalrous Du Guesclin, who breathed his last while besieging a company of marauding mercenaries of the bands called "compagnies" in the petty fortress of Châteauneuf le Randon, a little on the rt. of the road, which still retains the ruins of its castle. The commander had promised to yield the place to Du Guesclin in a fortnight, provided no succour arrived; but the constable, who was adored by the compagnies as their father, who had spent his own fortune in ransoms for them when taken prisoners, died in the interval.

The governor of the fortress nevertheless kept his word by placing the keys on the dead warrior's coffin on the appointed day.

The road is carried over a very high pass in the granitic range, a part of the Mont Margaride, often blocked up with snow, called in irony *Le Palais du Roi*.

29 Mende (*Inn: H. de Pavillon*), *Comm.* chef-lieu of the Dépt. de la Lozère, anciently of the province of Gévaudan, is a feudal and monastic town of 5909 inhab., in a hollow, surrounded by mountains, on the Lot. It has a fine *cathedral*, surmounted by 2 spires.

The ancient *Bishop's Palace* is now the *préfecture*. On the slope of the Mont Mimat, above the town, is perched the *Hermitage de St. Privast*, over the grotto of that saint, the apostle of the Gévaudan.

Some considerable manufactures of serges and other coarse cloths are carried on here.

The direct road from Paris to Montpellier runs through Marvijois, about 12 m. W. of Mende.

About 6 m. S. E. of Mende rises the *Mont Lozère*, whence the department is named, whose summit, 1,490 mètres above the sea level, is covered with extensive pastures occupied in summer by large flocks of sheep, to the number, it is said, of 200,000, which migrate in the winter to the plains of Languedoc; and its base is girt round with large forests, which still abound in wolves.

At 3 m. from Mende our road quits the valley of the Lot, and crossing a calcareous table-land, utterly bare and arid, destitute of habitation, cultivation, and almost of soil, called *Causse de Sauveterre*, descends into the valley of the Tarn, and the country of the Cevennes. (Introduction, Sect. V.)

26 Molines.

The principal source of the Tarn is in the plateau de l'Hôpital: on its borders lies Grisac, birth-place of Pope Urban V., and about 6 m. from its source the Pont de Montvert, a

small village, deep sunk between the Mont Lozère and Bougès, the scene of some remarkable events in the war of the Cevennes. The insurrection in fact commenced here by the murder of the archdeacon Chayla, a cruel persecutor of the Calvinists, who had scoured the country, backed by a troop of dragoons, seizing, imprisoning, and torturing women and men. On the night of July 24, 1702, the house, still standing at the N. end of the bridge, at that time occupied by Chayla and a party of priests and soldiers, was beset by a band of armed Camisards, headed by one of their prophets, Seguiet, who, after breaking down the door with the trunk of a tree and releasing the prisoners, set fire to it, and slew those who attempted to escape.

A few of its inmates were allowed quarter, but Chayla, whose death was the motive for the assault, having broken his leg in letting himself down from a window, was discovered and killed without mercy. He fell, pierced with 52 wounds, 24 of which were mortal. The prophet and his companions, having perpetrated this act of vengeance, passed the night on their knees around the corpses singing psalms, and did not withdraw before the morning. Seguiet was captured shortly after, and expiated his crime by being *burned alive* on the 10th August, 1702. As Pont de Montvert was the cradle, so was it also the tomb of the insurrection: the last bold act of the Camisard chief Roland before his death was an assault upon the Miguelets or Spanish soldiers posted in the village, from which he was repulsed. Joani, one of the last of the Camisard leaders, having been made prisoner near this (1710), slipped off from behind the horse of the "archer" or policeman who was conveying him to a dungeon, as he was passing the bridge, like Rob Roy in Scott's novel, and leaped down into the Tarn, a height of 20 ft. He was shot, however, by the captain of the archers, and perished in the river.

Our road quits the Tarn to follow its tributary, the Tarnon, shortly before reaching

11 Florac, a town of 2200 inhab., situated under a hill, whose bare cleft ridge rises in the form of castellated towers on the Tarnon, close to the influx of the Mimente. The 3 valleys of the 3 head waters of the Tarn lead into the inextricable labyrinth of defiles composing the mountainous district of the Hautes Cevennes. The Mimente rises in the mountain of Bougès, whose N. summit is crowned by the forest *Altefage*, in the depths of which the murderers of the archpriest Chayla had their rendezvous under 3 huge beech trees, one of which was standing in 1837, reduced to a shattered trunk. At Cassagnas, a village near the source of the Mimente, 13 m. from Florac, many of the *caverns* which were converted into storehouses and arsenals by the Camisards still exist and serve as habitations. They were filled with corn, wine, oil, chestnuts, and other provisions taken from convents and Romish villages, or contributed by the Protestants to their leaders. The provisions were conveyed thence to the spots where the insurgents met, either in conventicle for prayer, or in battle array, and there distributed in rations. The corn was for the most part ground in hand-mills, the water-mills having been destroyed by the military commander of Languedoc, who, at the same time, laid waste and burned all the villages in the Upper Cevennes, to the number of nearly 400, driving away their inhabitants. Other caves were filled with living flocks and herds or with meat salted, while others again were used as powder magazines and mills; for the Camisards made powder for themselves from the saltpetre collected in their caverns, and the ashes of the willows growing on all the streams. Their principal supply, however, was purchased at Papal Avignon; so that the papists were shot chiefly by the pope's own powder. The most airy



and wholesome caverns were transformed into hospitals for the wounded, and stored with drugs from Montpellier—to such an extent was the commissariat organised by Roland and other leaders of that fearful civil strife. The mountains skirted by the road on the l., from Molinez down to Ledignan, may be regarded as the citadel of the Camisard insurgents; but their ravages and incursions extended S. of the Gardon, and as far as the sea. Among these desolate solitudes they met, like the Cameronians of Scotland, with arms in their hands, in secret conventicles, where the harangues of their prophets and their hymns and prayers were often interrupted by an onset of the royal troops, and the congregation arose from their knees to do battle. After some miles we ascend out of the valley of the Tarnon, leaving it and the road to Montpellier on the rt., and, crossing the high land of Hospitalet, enter the valley of the Gardon, in which lies

23 Pompidou.

The road runs along a sort of hog's back or ridge, dividing the Dépt. de la Lozère from that of Gard, and traverses a sterile and dreary country.

30 St. Jean du Gard, on the l. bank of the Gardon, contains silk mills: 4128 inhab.

Within this canton, 6 or 8 m. to the N.E., among the mountains, lies Mialet, a village of 1358 inhab., the stronghold and head quarters of Roland, chief of the Camisards, who was born at Massoubeyran, close to Mialet. It is also remarkable for the caves and grottoes around it, converted by him into arsenals and store-houses during the war of the Cevennes. Another position of strength held by him was Durfort, among the mountains on the rt. of the Gardon and considerably to the S. of Anduze.

To the S.W. of St. Jean rise the mountains of the Basses Cevennes, the chief of which is the Aigoal, at whose base the river Herault rises.

Anduze (no post) is a town of

5554 inhab., on the rt. bank of the Gardon, and protected from its furious inundations by a strong dyke forming a terrace and promenade. It is overhung by escarped rocks of the Monts Peyremale and St. Julien. It was the centre of the religious wars which followed the death of Henri IV., and the head quarters of the Calvinist leader Rohan. A large portion of its inhab. are still Calvinists. During the Camisard insurrection this town as well as Alais was constantly beset by the Camisards up to its very walls.

Florian, the author of "*Gonzalvo de Cordova*," was born in the castle of Florian, between Anduze and St. Hyppolite. The valley of the Gardon below Anduze, between Fornac and Ners, is called *Vallée de Beauvige*, and is described in his pastoral romances *Estelle* and *Némorin*, but with so much exaggeration as scarcely to be distinguished.

Near Lezan our road quits the valley of the Gardon.

27 Ledignan.

Ribaute, a village situated among the hills to the N. of this, was the birth-place of Cavalier, who, having been bred a shepherd, and afterwards apprenticed to a baker at Anduze, was elected, at the age of 17, second in command of the Camisard insurgents, and proved himself a most able general, as well as powerful prophet or preacher. He died a pensioner in Chelsea Hospital.

13 Les Barragues de Fons.

18 NISMES, in Route 126.

### ROUTE 119.

ROANNE TO VALENCE ON THE RHÔNE, BY ST. ETIENNE AND ANNONAY.—RAILWAY FROM ROANNE TO ST. ETIENNE.

179 kilom. = 110 $\frac{3}{4}$  Eng. m.

The *malleposte* from Paris to Marseilles takes this route, thus avoiding the long détour by Lyons.

*Diligences* go daily.

Roanne is described in Route 105.

A *Railroad*, 42 $\frac{1}{2}$  m. long, has been carried from Roanne to St. Etienne;

the branch from Andresieux to St. Etienne was the first railway constructed in France: horses and not locomotives are used on it, and, though passenger trains traverse it in about 6 hours, it is chiefly used for the conveyance of coals and merchandise: its construction is very imperfect, and it is *not* recommended to English travellers.

From Roanne it is carried up the valley of the Rhins, a small tributary of the Loire, parallel with the post road to Lyons, as far as St. Symphorien de Lay, where it turns S. The post road to St. Etienne turns off previously at L'Hôpital to

20 Neulise (Stat.), beyond which it meets the railway, and the two proceed side by side up the valley of the Loire along its rt. bank. Near the village Pouilly the Loire is confined between huge *dykes*, faced with stones cemented and clamped together, called *Mole de Piné*, the original construction of which is attributed to the Romans. The rapids thus produced in the river prevent the ascent of boats.

20 Feurs (Stat.), in R. 112.

11 Montrond (Stat.), a village on the rt. bank of the Loire,  $1\frac{1}{2}$  m. W. of the railway. Above it rise the majestic ruins of its old *castle*, burned at the Revolution by order of an itinerant representative of the people.

Montbrison (R. 112) is 10 m. distant from Montrond.

14 La Gouyonnière.

The railway reaches the banks of the Loire at Andresieux, to which place large quantities of coal are conveyed from St. Etienne, to be embarked on the Loire for the supply of the centre and W. of France. Beyond Andresieux the line quits the side of the Loire, and ascends the industrious valley of its tributary the Furens, which, in the course of 9 m., sets in motion more than 100 forges and mills. The line from Roanne meets that from St. Etienne at a place called Quérillière, near La Fouillouse.

14 ST. ETIENNE. — *Inns*: H. du Nord; large, and comfortable, in the Rue Royale; — *Poste*, also good.

St. Etienne, the largest and most populous town in the Dépt. de la Loire, although not its chef-lieu, now numbering with its suburbs about 72,000 inhab., is a remarkable example of a sudden rise, and of still increasing prosperity, owing to two very dissimilar but flourishing branches of manufacture—the making of fire-arms and the weaving of ribbons. To use the words of a French topographer, “ce sont les ateliers de Mars à côté de ceux de Vénus.” The town is advantageously situated on the banks of the Furens, which furnishes water-power to move its machinery, in the midst of one of the most productive coal-fields of France. It may be called a French Birmingham, and, like that of England, it is “the child of coal,” surrounded by mines, and even seated on coal deposits, so that some galleries are driven beneath its very streets, though under strict superintendence of the authorities. It is by no means an inviting place to tarry in: little regularity is preserved in the building of streets so suddenly thrown up; and the fine white sandstone of its houses, many of them 5 and 6 stories high, is soon tarnished and blackened by the coal-smoke which constantly hangs in clouds over it. It has one fine broad street, divided into 2 “Places,” planted with trees, by the *Hôtel de Ville*, which stands in the centre of it and of the town. It is a building of no great merit, but of large size. It contains the *Bourse* and the commercial tribunal called *Conseil des Prudhommes* (see p. 382).

Within its walls is an incipient *Museum* (*Musée industriel*), containing specimens of the staple manufactures of the town, ribbons of all kinds, gun-barrels, locks, and stocks, engraved and carved by local workmen; also a collection of the minerals of the neighbourhood, and of the fossils of its coal-field, &c.



There are more than 200 master-manufacturers of *ribbons* here. The number of persons in the town and neighbouring communes employed in this branch of industry has been estimated at 40,000, and the number of looms at about 20,000. The weavers live chiefly on the outskirts of the town and in the adjoining villages, where they avoid the smoke, and live cheaper, by escaping the octroi.

The beauty and varied invention shown in the patterns, and the delicate combinations of colours, are admirable. An English traveller should not omit to visit a ribbon-weaver's atelier. About 60 artists are employed in designing and drawing patterns. The total annual value of ribbons made here is estimated at 45 millions of francs.

The *gunsmiths' shops* may be better seen at Birmingham, or even at Liege, both which places produce a larger quantity of arms. About 30,000 or 40,000 stand of arms are made here annually in time of peace, besides 30,000 fowling-pieces, and 1500 pair of pistols; and during the sway of Napoleon not less than from 60,000 to 100,000 were turned out; but it is stated that at a push 300,000 muskets might be produced in 12 months. A musket may be bought for 12 or even 10 fr.; but the price paid by government is from 24 fr. to 35 fr. a-piece. About 500 men are employed in the *Manufacture Royale des Armes*, which is carried on by contractors, under the superintendence of artillery-officers; but many more out-labourers are employed. All the barrels made must pass through a trial at the proof-house (*Maison d'Épreuve*), open twice a-week. There are also considerable manufactures of quincaille, hardware, and cutlery.

The making of bayonets, gun-locks, gun-stocks of walnut-wood seasoned by steam, employs a great number of hands.

St. Etienne is lighted with gas. Its *Cathedral* exhibits in its choir an

ancient specimen of Romanesque architecture.

There is a *Theatre* here.

*Chemins de Fer.*—Two short railways branch off from St. Etienne—*I.* to Lyons: the terminus is at the end of the Rue Royale, on the E. of the town, and there are 3 trains daily (see Rte. 118); *II.* to Roanne. The station is also about  $\frac{1}{4}$  hour's walk from the centre of the town. Trains go once a-day. (See p. 421.)

*Diligences* daily to Lyons (3 times); to Le Puy; to Annonay and Valence; to Clermont; to Roanne.

*Malleposte* in 37 hours to Paris;—ditto to Marseilles, in 22 hours, by the following route.

The road to Annonay, almost immediately on quitting the town, passes out of the coal-basin, and commences a long but gradual ascent through a rugged valley, over the high mountain-ridge separating the waters flowing into the Atlantic from those which run into the Mediterranean, and the valley of the Loire from that of the Rhône. These two rivers run parallel to each other, but in an opposite direction, for not less than 120 m. A short way below the summit stands

12 La République, the first relay, a solitary cabaret, which will furnish a tolerable meal and glass of wine. The ridge which our road crosses is a continuation of the granitic range of the Mont Pilas (pileatus), so conspicuous from the banks of the Rhône, near Vienne (R. 125), whose peak is visible on the l. near La République. The summit of the pass, and country around, is occupied by a vast forest of firs, le Grand Bois, on emerging from which, and beginning to descend, a fine view opens out, at the end of the valley, of the Alps of Dauphiné stretching along the horizon, of the minor chain running from them down the valley of the Isère, and more near, on the rt., of the mountains of the Ardèche.

The road is finely engineered, carried gradually down along the

flanks of the mountains, following their sinuosities. It passes above the ruined *Castle d'Argental*, planted on a sort of promontory, where the rocks are naked and inaccessible. The Bourg, once attached to it, has prudently descended from this feudal platform,

(16 Bourg d'Argental), and now occupies a more genial and sunny site lower down, in a part of the valley where the vine grows and the white mulberry flourishes. The white silk produced here is the best in France for the manufacture of blonde lace, and bears a high price.

A little below this town, the road passes out of the Dépt. of the Loire into that of the Ardèche.

The valley of the Dieune, in which lie both Bourg d'Argental and Annonay, has no very striking features of beauty; naked rocks intermixed with formal mulberry plantations, with green meadows, aspens, and willows, are the components of its scenery. Lower down, the river is bestridden by several large paper mills, chiefly belonging to the respected family Montgolfier. The road, carried high up, looks over slopes occupied by vineyards, beyond which rises the Alpine chain, and between which, in a deep ravine, runs the river. Numerous country houses, or boxes, among the vines announce the approach to Annonay.

15 Annonay. *Inns*: H. du Midi; H. du Nord.

This active and increasing manufacturing town, the largest in the Dépt. de l'Ardèche, containing a population of 10,000 souls, is situated in the rocky gorges of the Dieune and the Cance, which join their streams in the very centre of the town. The houses are either crammed in between the rocks, or carried up their sides in tiers, or in ranges along their tops, so that its ground plan is very irregular, and from no point can the whole town be seen at once. It has no public buildings of the least interest, merit, or good taste. The

*Grande Place* includes in its centre the *Bascule*, and on one side an *Obelisk* to the memory of the ingenious brothers Joseph and Etienne Montgolfier, natives of Annonay, the inventors of the air balloon, and founders of the celebrated paper mills near this; it was erected "*par leurs concitoyens*." Their first ascent into the air was made from this spot, June 1783, in the presence of the Estates of the province. The descendants of the brothers still reside in the neighbourhood, where the family is distinguished by its well-earned opulence and intelligence. Boissy d'Anglas, the firm and unbending president of the Convention, was also born here.

The chief manufacture of Annonay is that of *paper*, celebrated all over France, produced in 8 paper mills on the neighbouring streams. The preparation of kid and other *glove leather* occupies 65 master manufacturers, and 600 men: 350,000 dozen of skins are prepared annually, of which half are sent to England. The cultivation of the silk-worm, and the production of silk, chiefly the white kind, prized for blondes, is rapidly advancing in the neighbourhood. Vast quantities of mulberries have been planted within a few years, and numerous silk mills (*filatures*) established.

The name Annonay is said to come from the Latin *annonia*, corn magazines, established by the Romans on this spot (?).

12 *Diligences* daily; to St. Etienne; to Paris; to Lyons; to Grenoble; to Valence and Marseilles.

A steep ascent leads out of Annonay: from the heights above it, and nearly all the way to the Rhône, the Alps form a fine feature in the view.

The borders of the Rhône are reached a little below la Tour des Martyrs, near Andance, picturesquely situated among granitic hills, on whose sides every inch of space opening to the sun is occupied by vines.



A crag rising above the village is surmounted by a Calvary. Near this the sad effects of the inundations of the Rhône, in 1840–41–46, meet the traveller's sight, in fields and vineyards overwhelmed with sand, broken bridges, and ruined houses, until the Rhône is crossed, by a wire bridge, at

21 St. Vallier, }  
32 *Valence* (Inn: } described in  
Poste), } Route 125.

### ROUTE 121.

VALENCE TO NISMES, BY PRIVAS.—  
AUBENAS AND ALAIS.—VOLCANOES  
OF THE ARDÈCHE.

184 kilom. = 115 Eng. m.

A post road, but not good in places, and very hilly. A *diligence* goes daily to Aubenas, but it takes 12 hours, owing to the defects of the road, which, while it continues along the Rhône, is carried through several rivers by fords, and beyond is very hilly. Throughout it is interrupted by numerous villages, the passage of whose narrow and ill-paved streets is very difficult and tedious.

The Rhône is crossed by the wire bridge at Valence to the rt. bank: and the Eyrieu by another wire bridge to

19 La Voulte; all which is described in Route 125.

The Valley of La Payre, up which the road turns on quitting the Rhône, is not remarkable for beauty; owing to the extreme aridity of the hills, which are of bare limestone, with a drapery of vines too scanty to cover their nakedness. There is some pasture in the low ground; but the district must properly be considered one vast grove of mulberries, for rearing the silkworm,—the source of wealth to the Ardèche. (See R. 125.)

The large white buildings which line the banks of the useful stream traversing the valley are, for the most part, silk mills, for the moulinage (reeling) and filature (throwing) of the silk. They are very numerous

near Chomerac, the most considerable place in this valley. A low ridge separates it from that in which is situated

20 *Privas*.—*Inns*: La Croix d'Or; tolerable, but dear; H. du Commerce. Avoid stopping here for the night if possible, in autumn, on account of the mosquitoes.

Privas, chef-lieu of the Dépt. de l'Ardèche, 4219 inhab., and one of the smallest chef-lieux in France, is situated on a steep ridge, a root of the range of the Coiron, projecting between the valley of the Ouvèze, and that of a smaller stream falling into it, within an amphitheatre of rugged and arid hills. Its principal street running along this back-bone is prolonged, at either end, into terraces planted with trees, whence a good view is obtained of the valleys around, their slopes clad with vines, and dotted with country houses; their depths, along the line of the streams, studded with silk mills.

The town has an aspect of some pretension at a distance, with the Greek portico of its Palais de Justice, but contains nothing worth notice except its establishments for the reeling and throwing of silk. It was in the 16th and 17th centuries a fortress, and stronghold of Protestantism, so that in 1612 a synod of all the Reformed Churches of France was held here; and in the reign of Henri IV. there was not a single Roman Catholic in the town or its territory. It has now quite a modern appearance, owing to its having been burned to the ground, and levelled with the dust, by Louis XIII., who assisted in person to besiege it, in the train of Card. Richelieu. The defence was conducted by the brave St. André de Montbrun, and a garrison of 1200 men, assisted by the inhabitants. At the end of 2 months a general assault was made by the royal forces, who were repulsed with a loss of 500 men; but the place being no longer tenable was abandoned by Montbrun, who retired to the Fort de Toulon, where

the want of provisions compelled him soon after to surrender. The king caused him and all his companions to be hung; he confiscated the property of all the inhabitants of the town who were in it during the siege, and forbade, by an edict, any person living there without letters issued under the great seal. The site of this fort is marked by a conical hill, surmounted by 3 crosses, and a Protestant temple near the Esplanade marks the position of the old castle, which was razed to the ground. Privas had, in a previous war of Religion, 1574, successfully resisted the royal forces, under the Duc de Montpensier, and had become a sort of metropolitan church to the Protestants: hence the exasperation of the Roman Catholic party against it.

The road to Aubenas surmounts the chain of the Coiron mountains, which traverse the Dépt. Ardèche, from N.W. to S.E., by a steep ascent, requiring 2 hours to climb to the summit of the pass. It passes through large plantations of sweet chestnuts. The famed "*Marrons de Lyon*" come chiefly from the Ardèche. The country is not interesting, the extreme nakedness of the hills being a great drawback. The mountains on either side of the gap or col over which the road passes are capped by basalt. From the slope and top of the pass the mountains of the Dépt. of the Drome beyond the Rhône are well seen. On the opposite slope, a little way down, stands

16 Les Moulins, a single house. On the descent towards Aubenas, the hills are not less parched and naked, nor more picturesque, than on the side of Privas. The vine grows very high up, and it is curious to see it flourishing upon the dry disintegrated débris of rock fallen from the tops of the mountains, streaking their whitened flanks with the faintest tinge of verdure. The descent is very long, and the road towards the bottom of the valley as bad as possible; not properly made.

The river Ardèche is crossed immediately before reaching Aubenas, in a suburb of that town composed chiefly of silk mills. A series of zig-zags carried up the face of the hill are surmounted in order to enter

14 Aubenas.—*Inn*: H. de l'Union, kept by Barry; good, and tolerably comfortable, with capital cuisine, and not expensive. Truffles abound here: chestnuts, figs, ortolans are to be had in perfection. The house being situated on the brow of the hill, commands a fine view from its terrace.

Aubenas (4685 inhab.) is a town of very striking appearance at a distance, from the commanding height on which it stands, and the picturesque forms of its old Gothic castle, feudal walls, and other chief buildings. From this elevated platform, the foot of which is washed by the Ardèche, you command a view of some interest over its industrious and productive vale, clothed in its lower slopes with vines, fig-trees, and mulberry groves, surmounted, in the distance, by the usual bare arid mountains. You trace the river's course upwards to the point where it issues out of the more confined gorge of Vals, and as it were rejoicing in riotous liberty, widens its bed, and overspreads the valley with gravel, bare at most seasons but winter, and after autumnal storms, when the whole channel is covered by its muddy stream. It is nevertheless useful; serving to irrigate the fields, and turn the machinery of a long array of silk mills which line its banks.

Aubenas is of importance as a place of trade, having become the staple for the silks of the Ardèche, Drome, Gard, and L'Hérault, which are deposited here in commission houses, sometimes to the value of 3 millions of francs, to be disposed of and distributed to the consumers in Lyons, St. Etienne, &c., who find here an assortment of all the different qualities of silk, suited to the exigence of the various manufactures. The canton of Aubenas furnishes about



the 30th part of the silks sold in its market : in 1838 it possessed 60 mills for reeling and throwing the silk, which employed 1600 persons, chiefly females ; the number has since greatly increased.

The *Collège Royal* was originally placed under the care of the Jesuits, established here in the 16th century, for the conversion of the Protestants, who abounded in the Vivarais, as well as for the dissemination of learning. Neither the building nor its church merit notice.

The *castle*, an ancient and picturesque edifice, flanked by round and square towers, was occupied alternately by Romanists and Huguenots during the wars of Religion : it is now converted into municipal and police offices ; and the public *scales* for weighing all the silk brought to market are deposited in it.

*Diligences* daily to Privas and Valence ; a courier to Bourg St. Andeol ; and 3 times a week to Montelimart.

Although there is little worth seeing in Aubenas itself, it makes capital head-quarters (more especially considering the goodness of its Inn) for exploring the surrounding district of the Vivarais, so interesting in a geological point of view.

The course of the river Ardèche and its tributaries, above Aubenas, and within a range of 15 or 20 m., exhibits a series of interesting volcanic phenomena, which the geologist will not fail to explore, and which may be visited with interest even by the ordinary traveller, merely on account of the picturesqueness and singularity of the scenery.

Some of the valleys of the Bas Vivarais present an exquisite combination of beauty and magnificence. Their scenery has been compared by Mr. Scrope, in his excellent geological description of this district, to that of the Apennines, but with a more luxuriant vegetation. The rich glow of the chestnut forests, tinted by a soft and brilliant atmosphere, are admirably adapted to painting.

*Excursions.*—1. *Antraigues* and the *Coupe d'Ayzac* are distant about 8 m. above Aubenas. A good road leads thither, turning out of that to Le Puy at La Begude, and crossing the river Ardèche, by a wire bridge, to the village of Vals (H. de l'Europe ; a good inn, and convenient head-quarters for geological excursions), resorted to on account of its mineral baths, supplied by a spring of cold acidulo-ferruginous water. Vals lies on the l. bank of the Volane, a tributary of the Ardèche ; and for nearly 6 m. above Vals the valley, which is very picturesque, and alternately well wooded or bounded by rocks of gneiss and granite, is studded at intervals by patches of basalt, forming platforms and regular colonnades, like those of the Giant's Causeway, but on a much smaller scale, although at times 100 or 150 ft. high. These fragments are all that remain of a lava current which once, undoubtedly, filled the bottom of the valley, but was cut away by the Volane, in forcing a passage for its waters. They appear to be composed of 3 beds, or stories, of which the lower one presents the most regular columns, and the upper is nearly amorphous. In places the current of the river, or of some minor rivulet, still saws through or undermines the basalt, and strews the bed of the Volane with detached pillars, mostly regular prisms of 5 or 6 sides. In some places you look down on the top of the lava stream, which presents the appearance of a gigantic tessellated pavement. The origin of this eruption is to be traced in a volcanic cone, called *La Coupe d'Ayzac*, rising on the l. bank of the Volane, opposite Antraigues, a picturesque village, which occupies a commanding platform on the top of a high rock of gneiss near the head of the valley. Around the base of this rock still cluster numerous groups of columns, corresponding with a much finer colonnade, on the opposite or rt. bank of the river, at the same level, which were doubtless originally united.

Antraigues affords no accommodation but a miserable cabaret. To reach the Coupe d'Ayzac is a walk of  $\frac{3}{4}$  hour from the bridge over the Volane, leaving on the rt. hand the road up to Antraigues. It is a very regular crater, but slightly broken down on the N.W. side, facing the Col d'Ayzac; and from this breach the stream of basaltic lava which has flowed down the course of the Volane may be seen to issue.

The stout pedestrian may find his way over the mountains from this to Burzet and Montpezat, but the aid of a guide may be desirable; otherwise he must retrace his steps down the Volane to Vals.

2. To *Montpezat, Thueyts, Jaujac.* It is a long day's excursion to Montpezat alone, which is probably 16 m. from Aubenas—a ride of nearly 4 hours by a bad road. The road to Le Puy, up the valley of the Ardèche, is followed; but instead of crossing the bridge at La Begude, you continue along the rt. bank, leaving on one side the dirty village of Prades, where coal in small quantity is found, and proceeding to La Baume ( $6\frac{1}{2}$  miles from Aubenas), a village picturesquely situated, under a mass of basalt, exhibiting in the face of its cliffs a fine architectural façade of columns, and occupying an angle in the valley, nearly opposite to the junction of the Fontaulier with the Ardèche. The top of this platform of basalt, called *Chaussée du Pont la Baume*, is covered with vines, and its mass is penetrated by a sort of grotto, lined and vaulted with natural pillars. This chaussée is probably the production of no less than 4 or 5 extinct volcanoes situated in the side valleys opening into the Ardèche, above this, whose lava streams united at this point, just as the waters flowing out of them now do. Between the two rivers, on the top of a domineering rock, its shattered towers and walls picturesquely draped with ivy, rises an old *Castle*, which once belonged to the Ducs de Ventadour: it is one

of the finest feudal relics in the district.

The road to Montpezat (a bridle or cart road only) here quits that to Thueyts and Le Puy (see R. 118), crosses the Ardèche by the Pont de la Baume, and ascends the valley of the Fontaulier, having the castle on the l., and commanding a fine view of it and the 2 valleys. Ranges of basalt appear from time to time on either side of the valley.

On the rt., a little beyond the village of Meyras, the valley of Burzet opens out on the rt.; a bed of basalt occupies the bottom of it, and the river frequently flows over the tops of its columns, instead of cutting through them. About 6 m. up this valley is a village.

The vale of the Fontaulier expands as you ascend it; its lower slopes are covered with one vast forest of sweet *chestnut*, which flourishes in the congenial soil, composed of volcanic ashes, many of the trees being centuries old. The roads are strewn with their fruit in September, yet, productive as they are, and valuable to the peasant, who exports the best to Lyons or Paris, and feeds on the inferior fruit himself, in winter, they are gradually giving place to the still more profitable mulberry trees and the culture of silk. The higher slopes, nearly to the tops of the hills, are terraced to plant vines. The red ashes, or scoriæ, which compose the soil of the valley, have issued from a volcanic crater near its head, easily distinguished for some distance below by its red hue, called *La Gravenne de Montpezat*. It is a regular bowl-shaped orifice, composed of porous scoriæ, roasted like the slag of a furnace, or of puzzolana (here called *gravier*). The crater is slightly inclined on one side; and from the lowest edge of its rim the lava current which occupies the valley below Montpezat has been discharged, filling the beds of the streams to a depth of 130 ft., and for the width of nearly  $\frac{1}{2}$  a mile. The road to and from the bridge leading to Montpezat passes



under cliffs cut through this eruption of lava, and showing on their face columns of considerable regularity. A branch of the lava current from the Gravenne has descended, on the opposite side of the crater, towards Thueyts, into the Ardèche. Volcanic tears, bombs, black and white cinders, are among the productions of its lava.

Montpezat (*Inn*: a dirty, miserable cabaret, de France) is a poor and dirty town, composed of singular gloomy houses, in a narrow street, at the foot of the granitic range of the Coiron mountains. A carriage road has recently been made from the town up the valley, and over the bridge behind, as far as the village Pal ( $1\frac{1}{4}$  hour's walk), beyond which, on the opposite slope, is the very perfect volcano of Pal, in the midst of which rise 3 cones.

About 15 m. N. of Montpezat, near Gerbier des Jones, at the base of the Mount Mezène, is the *source of the Loire*, 4711 ft. above the sea level. There is a bridle path by it to Le Puy (p. 407).

It is possible to cross the mountain from the Gravenne of Montpezat direct to Thueyts: the only other way is to return to Pont de la Baume.

A short way above La Baume, the Ardèche is joined by the river Alignon, in whose valley are situated the singular *craters* of *Jaujac* and *Souillols*. (See Route 118.) There is a road from Jaujac down the valley of the Liane to L'Argentière.

Thueyts (*Inn*: Chez Burine; far better than that at Montpezat) lies on the l. bank of the Ardèche, surrounded by the most splendid volcanic scenery, about 4 m. above La Baume (see Route 118); it stands on a volcanic current, which has issued from the same ridge as the Gravenne de Montpezat, if not from that very crater. For nearly 1 m. below Thueyts the river is lined by the majestic colonnade of basalt proceeding from it. A stair, the steps of which are basaltic prisms, has been

formed up the rock, and is called *Escalier du Roi*.\* A stream dashing down into a tremendous ravine called *La Gueule d'Enfer*, forms a remarkable waterfall.

The road from Aubenas to Nismes is that by which the silk produced in the S. is transported to the market of Aubenas, and thence transferred to the manufactories of Lyons and St. Etienne. It leaves the town of L'Argentière a little on the rt. before reaching

23 Joyeuse, a small town on the Baume, at the foot of the Cevennes. An excursion might be made hence by Ruoms and Vallons (famed for the caves in its vicinity) to the *Pont de l'Arc*, a natural bridge of limestone spanning the river Ardèche, open to a height of 90 ft. above it, and 160 ft. wide. It was once the common line of passage from the Vivarais into the Cevennes, and was fortified in the religious wars.

29 St. Ambroix, in the Dépt. Gard, a town of 3000 inhab., on the Cèze, surmounted by an old castle.

The coal mines of Bessège, near which the road passes, are remarkable for the quantity and size of the fossil vegetables occurring in them.

The rivers Cèze and the 2 Gardons take their rise in the mountains of the *Hautes Cevennes*,—the wild theatre of the insurrection of the Protestant mountaineers, known as Camisards, or “*Enfans de Dieu*,” as they called themselves; while they distinguished their native mountains, whose roots our road may be said to skirt on the rt. from St. Ambroix to Ners, by the name “*le Désert*.” Their desolating irruptions and bloody contests with the forces of Louis XIV. spread far and wide over the country we are about to traverse, on both sides of our route, up to the very gates of Nismes and Alais; and almost every step will recall to those familiar with the his-

\* Additional information respecting the valley of the Ardèche is desired by the Editor.

tory of that fearful contest some melancholy memorial of bloodshed and violence.

19 Alais (*Inns*: H. du Commerce; —Lion d'Or), an important manufacturing town, containing 15,884 inhab., in the midst of a productive coal-field, which has only recently begun to be worked to any extent, and which furnishes iron as well as coal. The chief collieries are at Grande Combe on the railway. There are in the vicinity of Alais numerous iron furnaces, silk mills, glass works, and many steam-engines hard at work.

The Place de la Maréchale is surrounded by low porticoes or arcades.

The town contains no fine buildings. It was taken by Louis XIII., as a stronghold of Protestantism, and its fortifications destroyed.

A *railroad* connects Alais with Nismes; trains go twice a day. Distance 49 kilom. = 30 Eng. m. A branch extends from Alais to Grande Combe, 10 m.

At la Tour de Bellot, a deserted sheep-farm and watch-tower to the W. of Alais, between it and Anduze, a band of 1500 Camisards, betrayed by a miller on the Gardon, who had supplied them with provisions, were surprised at night by the troops of Louis XIV., 1704. The Camisard outposts had barely time to sound an alarm, when they were cut to pieces, so that only the leader and a part of the band were able to issue forth from the tower before it was invested. The Camisard chief, Cavalier, made furious efforts to drive back the soldiery, and relieve his brethren in the tower, but in vain. Its garrison, however, blocked up every entry, pouring a deadly fire from every window and cranny, and were only subdued, after an obstinate resistance of 8 hours, by fire being set to the building, in which 298 of them perished, besides 100 left dead outside the walls. The loss of the king's troops was estimated at 1200 killed and wounded. Wild justice was soon after done by the Camisards on the

traitorous miller; he was seized, condemned to death, and led out to execution in front of the insurgents, who, as was their custom, knelt around him the while, offering up prayers for his soul. His two sons, who served in their ranks, refused his parting embrace, and looked on unmoved during his punishment.

Vezenobre, through which the road passes, is frequently mentioned in the history of the Cevenol war; and the inhabitants of Euzet, a village a few miles to the E., were put to the sword, 1704, by a king's officer, Lalande. Entering the town suddenly, he found great store of provisions, heaps of bread, hams, sausages, and a bullock skinned, evidently destined for the Camisards, whom a brief search disclosed concealed in the neighbourhood. They were the remains of the force of Cavalier, defeated at Nages (R. 126), and were here again routed with a loss of 170 killed, including several prophetesses. Further evidence that the inhabitants of Euzet were aiding and abetting the rebels was furnished by the discovery in their vicinity of one of those caverns which the Camisards converted into hospitals and arsenals. It was filled with wounded, medicines, arms, and ammunition. This sealed their fate; they were all slaughtered, including the patients in the cavern, and Euzet was destroyed. Such was the system on which this exterminating war was carried on. The Camisard commissariat was supplied by requisitions upon towns and villages, both Catholic and Protestant: when not furnished with good will, a mis-sive of this sort preceded their appearance, addressed to the chief men of the place:—"M.M., vous ne manquerez point de nous préparer demain le dîner, sous peine d'être assiégé et mis à feu et à sang.—CAVALIER."

14 Ners is a village on the l. bank of the Gardon, at the angle formed by the junction of its two branches, the Gardon d'Anduze and d'Alais.



The river in winter rolls down a flood of water with the force of a torrent, but in summer is dried up to a few rills or threads. Owing to its impetuosity and sudden rising, no attempt to throw a bridge across it has succeeded.

Not far from Ners, on the W., is the Castle of *Castelnau* (8 m. S. of Uzès). It is remarkable as the spot where Roland, the chief and generalissimo of the Cevenol insurgents, ended his career, Aug. 13, 1704. His presence on the spot had probably been betrayed to Marshal Villars, for in the middle of the night, when Roland and his companions (including a female called *Mademoiselle de Cornelli*) were fast asleep, their sentinel on the tower heard the noise of horses' feet approaching at a gallop. He gave the alarm just as the cavalry were about to enter. The Camisards started up half naked, rushed to the stable, and mounting the bare backs of their horses, galloped off for their lives, but without saddles, belt, or spurs. They were soon overtaken, compelled to

dismount, and, having been discovered trying to conceal themselves in a hollow way, were forced to face about. Roland, planting his back against the trunk of an old olive tree, made a desperate resistance; answering to the summons, "Rendez-vous! Bas les armes!" by killing 3 of the dragoons with 3 successive shots of his blunderbuss, and he was drawing his pistols, of which he carried a row at his girdle, when a musket-shot brought him down. The wound was mortal, and his companions, seeing his fall, at once threw themselves on his body, and allowed themselves to be seized and bound like lambs. The body of Roland was publicly burned at Nismes.

Near Ners rises the tall tower of the modernized Castle of Boucoiron, on a rock.

16 La Calmette.

The road passes near the limestone quarries, whence the Romans obtained the material for the amphitheatre of Nismes.

14 NISMES. (Route 126.)

## SECTION VI.

## PROVENCE AND LANGUEDOC.

ROUTE	PAGE	ROUTE	PAGE
125 THE RHÔNE, (B.)—Lyons to <i>Avignon</i> and <i>Arles</i> , by <i>Vienne</i> , <i>Valence</i> , <i>Orange</i> ( <i>Vaucluse</i> ), <i>Tarascon</i> , <i>Beaucaire</i> , and <i>St. Remy</i> . . .	440	127 Nismes to <i>Marseilles</i> and <i>Nice</i> , by <i>Beaucaire</i> ( <i>Railway</i> ), <i>Arles</i> , <i>The Crau</i> , <i>Toulon</i> , and <i>Hyères</i> . . .	482
126 <i>Avignon</i> to <i>Narbonne</i> by the <i>Pont du Gard</i> , <i>Nismes</i> , <i>Montpellier</i> , and <i>Beziers</i> .— <i>St. Gilles</i> and <i>Aigues Mortes</i> ( <i>Rail. Nismes to Cette</i> ) . . .	469	128 <i>Avignon</i> to <i>Marseilles</i> and <i>Nice</i> , by <i>Aix</i> , <i>Fréjus</i> , and <i>Cannes</i> . . .	494
		129 <i>Railway</i> — <i>Avignon</i> to <i>Marseilles</i> , by <i>Arles</i> , <i>St. Chamas</i> , and the <i>Etang de Berre</i> . . .	499

## PRELIMINARY INFORMATION.

1. Features of Provence.—Climate, People.—2. Mistral.—3. Mosquitoes.—4. Fertility and Varied Productions.—5. The True Garden of Provence.—6. The Roman Antiquities.—7. Gothic Architecture.—8. The Rhône.

§ 1. THE Englishman who knows the S. of France only from books—who there finds Provence described as the cradle of Poetry and Romance, the paradise of the Troubadours, a land teeming with oil, wine, silk, and perfumes, has probably formed in his mind a picture of a region beautiful to behold, and charming to inhabit. These anticipations may probably be strengthened by Mrs. Radcliffe's well-known, but perfectly unfounded, descriptions of scenery in the "*Mysteries of Udolpho*." Nothing, however, can differ more widely from the reality; and at least it is not from this quarter that France deserves the epithet "*La Belle*." Nature has altogether an arid character;—in summer a sky of copper, an atmosphere loaded with dust, the earth scorched rather than parched by the unmitigated rays of the sun, which overspread every thing with a lurid glare. The hills rise above the surface in masses of bare rock, without any covering of soil, like the dry bones of a wasted skeleton. Only on the low grounds, which can be reached by irrigation, does any verdure appear. There is a sombre, melancholy sternness in the landscape of the South. The aching eye in vain seeks to repose on a patch of green, and the inhabitant of the North would not readily purchase the clear cloudless sky of Provence with the verdure of misty England. Neither the bush-like vine nor the mop-headed mulberry, stripped of its leaves for a great part of the summer, nor the tawny green olive, whose foliage looks as though powdered with dust, will at all compensate in a picturesque point of view for forests of oak, ash, and beech.

"After Nice, the *austere* South of France, silent, burnt up, shadeless, and glaring, with houses all closed, showed the misery of a hot climate, while in Italy its *luxury* had struck us. The sun had bleached every thing, and the atmosphere was thickened with the perpetual dust of habitual drought, for here it is said not to rain for seven months together in summer. The



roads were of a dusky buffy white; the farm-houses, built of the materials nearest at hand, of the same colour; roads, soil, houses, men, trees, animals, all partaking of the same hue of universal dust, as the caterpillar does of the leaf on which it feeds. Now and then parched and scanty grass sprang up among the clodded earth, and long-legged sheep were feeding anxiously upon it, in the scorching sun, without a single tree of shelter. All the inns, however miserable, have large *remises*, to afford coolness and shade, during the middle of the day, for travellers and horses.”—*P*:

The character of the people appears influenced by the fiery sun, and soil which looks as though it never cooled. Their fervid temperament knows no control or moderation; hasty and headstrong in disposition, they are led by very slight religious or political excitement, on sudden impulses, to the committal of acts of violence unknown in the North. They are rude in manner, coarse in aspect, and harsh in speech, their patois being unintelligible, even to the French themselves, not unlike the Spanish dialect of Catalonia. From the loudness of tone and energy of gesture, they appear always as though going to fight when merely carrying on an ordinary conversation. The traveller who happens to fall into the hands of the ruffianly porters at Avignon will be able to judge if this be an exaggerated picture.

Those who are prone to complain of the climate of England should be sent to try that of the South of France. If they expect an unvarying serene sky and warm temperature, they will be wofully disappointed. The variations between summer and winter are marked by the dead olive, and vine trees killed by the frost; and the torrid influence of summer by the naked beds of torrents left without water. In many years not a drop of rain falls in June, July, and August, and the quantity is commonly very small: the great heats occur between the middle of July and the end of September, yet even in summer scorching heat alternates with the most piercing cold; and the vicissitudes are so sudden and severe, that strong persons, much more invalids, should beware how they yield to the temptation of wearing thin clothing, and of abandoning cloaks and great coats.

§ 2. The cause of these sudden changes in temperature is the *Mistral* or N. W. wind, one of the scourges of Provence, from the occurrence of which no season is exempt. It is a most violent, bitterly cold, and drying wind, which fills the atmosphere with a yellow haze, and is very painful to the eyes and face. It prevails chiefly in spring all along the coast, and up the Rhône as far as Valence.

“Voilà le vent, le tourbillon, l’ouragan, les diables déchaînés qui veulent emporter votre château; quel ébranlement universel!” are the words in which *Madame de Sévigné* describes it: it overthrows at times the largest trees; their branches generally grow in a direction contrary to its cutting blasts, and while it rages vessels are not unfrequently prevented putting out to sea in the teeth of it. It was well known to the ancients, and is supposed to be the *Melamborias* of Strabo, which he describes as sweeping stones and gravel from the ground. It is sufficient to blow a man from his horse. “In the winter months, December, January, February, the weather is truly charming, with the mistral very rarely.”

§ 3. Another plague of the South of France is the *mosquitoes*, cousins, or moucherons, which, to an inhabitant of the North, unaccustomed to their venomous bite, will alone suffice to destroy all pleasure in travelling. They appear in May, and last sometimes to November; and the only good which the mistral effects is that it modifies the intensely hot air of summer, and represses, momentarily, these pestilential insects. They are not idle by day, but it is at night that the worn-out traveller needing repose is most exposed to the excruciating torments inflicted by this cruel insect. Woe to him who

for the sake of coolness leaves his window open for a minute; attracted by the light they will pour in by myriads. It is better to be stifled by the most oppressive heat than to go mad. Even closed shutters and a mosquito curtain (*cousinière*), with which all beds in good inns are provided, are ineffectual in protecting the sleeper. A scrutiny of the walls, and a butchery of all that appear, may lessen the number of enemies; but a single one effecting an entry, after closing the curtains and tucking up the bed-clothes with the utmost care, does all the mischief. The sufferer awakes in the middle of the night in a state of fever, and adieu to all further prospect of rest. The pain inflicted by the bites is bad enough, but it is the air of triumph with which the enemy blows his trumpet, the tingling, agonising buzzing which fills the air, gradually advancing nearer and nearer, announcing the certainty of a fresh attack, which carries the irritation to the highest pitch.

The pain and swellings usually last for several days, and there is no remedy but patience. The state of the blood at the time, however, considerably modifies or increases the amount and duration of suffering. It is said to be the female only which inflicts the sting. Mosquitoes, of course, are not peculiar to the S. of France, but there the traveller from the N. will probably first encounter them; and it is necessary that he should be prepared.

The *scorpion* is not uncommon in Languedoc and Provence, and even now and then makes his entrance into the houses, being brought in along with fire-wood; and it is even not uncommon to discover it in the folds of the bed-curtains or sheets. Instances, however, of persons being bitten by this foul insect are very rare indeed: from its nature it is fearful, and, when discovered, endeavours to run away and hide itself.

§ 4. The foregoing description of Provence and Bas Languedoc has been limited to the dark side of the picture: it remains to examine the resources, fertility, and curiosities of the country.

Its valleys, and lowlands accessible to irrigation, are most fertile; and the earth, where it can be sufficiently supplied with moisture, teems with varied productions all the year round. Before the spring is over, the mulberry-trees, which line the roads and cross the fields, in ugly cabbage-headed rows, are stripped of their juicy foliage to feed the silk-worm—silk alone being a source of immense and increasing wealth in the S. provinces of France. Early in summer comes the corn-harvest, the crops having grown, for the most part, under the boughs of the mulberry, olive, or vine; sunshine and soil sufficing for both. Autumn is the season of the vintage; and the wines of Lunel and Frontignan have a widely established reputation, though the bulk of the produce is used in the *manufacture* of wines and for mixing with other sorts. Chestnuts are another crop collected in the same season, and furnishing a store of wholesome food for the peasant during winter. The winter has set in before the olives are gathered and pressed. A visit to the market-place in every town will show with what abundance the earth brings forth fruits and vegetables of endless variety—grapes, figs, melons, almonds, citrons, mushrooms, tomatas, truffles, &c. The drying and preserving of fruits of various kinds is a great source of mercantile wealth to Provence.

§ 5. There is one little corner of Provence which combines remarkable picturesque beauty with a climate so serene and warm, and well protected from injurious blasts, that its productions are almost tropical in their nature. This is a narrow strip in the Department of the Var, bordering on the blue Mediterranean, extending from Toulon to Nice, stretching inland to Grasse and Draguignan. In this favoured region, the true garden of Provence, the real paradise of the Troubadours, in the valleys, and on the



S. slopes of the small mountain-chains of Les Maures and Les Estrelles, sheltered from the injurious mistral, and open only to the S., the aloe, the cactus, the pine of Aleppo, the umbrella-pine, the pomegranate, the orange, and even the palm-tree, may be seen flourishing in the open air. This is especially the case at St. Maxime, Hyères, Antibes, and Cannes, whose gardens, luxuriant with aromatic herbs, heliotropes, orange-flowers, jasmines, &c., supply the perfume-distilleries of Grasse, where more scents, pomades, essences, &c. are made than in any town in Europe, save Paris.

§ 6. The chief attraction, however, of these southern provinces is their *Roman remains*, not surpassed in beauty and preservation by any in Italy. The *Pont du Gard*, between Avignon and Nîmes, and the walls of the *Theatre at Orange*, are stupendous and most impressive structures, perfectly characteristic of the great people that raised them; the *Amphitheatres of Nîmes and Arles*, though far less enormous than the Colossæum, are more interesting on account of their better preservation. The *Maison Carrée* is a gem of architecture: the *monuments at St. Rémy*, and the *arch at Orange*, are also of great excellence, besides many other curious relics, which are described in their proper place.

§ 7. The student of *Christian architecture* will find much to interest him in the churches of Arles and its vicinity, of St. Gilles, of Aix, of Avignon (the cathedral), where the stupendous Papal palace is also a very interesting historical monument, and many more.

In these and other mediæval monuments of S. E. France the traveller will not fail to observe the long-perpetuated influence of Roman architecture on the ecclesiastical edifices of the district, which still retains its Roman name of *THE Province*, par excellence. "A marked difference of character prevails between the church architecture of the S. of France and that of the N., in the smallness of the windows, designed no doubt to exclude the glare and heat. This gives the southern churches a much greater solemnity than those immense lantern-structures of the N.: unless where the windows are entirely filled with stained glass, it is difficult to produce the same effect. The influence of climate evidently gave rise to the distinctions in the two styles."—*E. o. S.*

§ 8. The *Rhône*, the great highway to Provence and to Italy, since the establishment of steamers, is not of commercial utility proportioned to its length and volume, owing to its turbulence and shifting sand-banks. Yet it is a noble river, and its scenery very striking, and some have preferred it to the Rhine; but, in truth, the two have a totally different character, and each its own excellences: the writer of this, however, cannot conceal his preference for the German stream. The traffic upon the Rhine is at least fourfold greater than that on the Rhône. The Rhine is navigated by 42 steamers, and, although there are 23 at present on the Rhône, they make on an average only 50 passages in the year, while a great part of the Rhenish steamers are, with the exception of a few weeks, in action all the year through.

The works which will best afford detailed information respecting Provence and the South of France are—Millin, "*Voyage dans le Midi de la France*;" Frossard, "*Tableau de Nîmes*;" Merimée, "*Rapport sur les Monumens du Midi de la France*" (for architecture); and Hughes' "*Itinerary of Provence and the Rhône*."

## ROUTE 125.

THE RHÔNE, (B.)—LYONS TO AVIGNON  
AND ARLES, BY VIENNE, VALENCE,  
ORANGE.

By land, 263 kilom. = 163 Eng. m.  
By water to Arles, 285 kilom.

*Steamers*, belonging to several companies, but almost without exception managed by English engineers, start every morning from the Quai on the rt. bank of the Rhône, except when the river is too high to allow them to pass under the bridges, or too low, which sometimes happens. The hour of departure varies, according to the season, from 5 to 7 A.M. They make the voyage to Avignon, a distance of at least 135 Eng. m., in 11 hours; and to Arles in 13. They take carriages at a charge varying from 60 fr. for a light calèche, to 160 for a Berline. The captain manages the embarkation and landing of carriages; transporting them to and from the hotel. The passenger's fare varies from 10 to 20 or 30 fr., so that it is cheaper than posting for a party in a light carriage (?). They are by no means clean, and are often crowded with merchandise. There is a capital and cheap restaurant on board. They touch at Vienne, Tournon, Valence, Avignon, Beaucaille, Arles. Steamers also run between Lyons and Valence. It is very advisable to go by water *down* the Rhône, as the road is bad. It scarcely answers for passengers *to ascend* the river, as the vessels take as long as the diligences, requiring 40 or 50 hours from Arles, and at least 2 days from Avignon to Lyons.

4 *diligences*\* run daily, along the l. bank, to Marseilles, and many more between the intermediate towns.

There is little interest at first in

\* By land, 263 kilom. = 163 Eng. m.

The *Post Road* quits Lyons, after traversing the Rhône, by the Faubourg Guillotière, passes on the l. the detached *Fort de la Motte*, one of the modern defences of Lyons, named after an old castle occupied by Henri IV., at his marriage with Marie de Medicis, and shortly before reaching

8 St. Fons, enters the Dépt. de l'Isère.

the banks of the Rhône, after getting clear of Lyons, its bustling quays and tall stately houses, and passing,

Rt., the junction of the Saône with the Rhône,—

"Ubi Rhodanus ingens amne prærapido fluit,  
Ararque dubitans quo suos cursus agat  
Tacitus quietis alluit ripas vadis,"—*Seneca*.


under the new wire suspension bridge of La Mulatière, which carries the railway to St. Etienne over the Saône (R. 118). The junction of the Rhodanus and Arar originally took place nearly 2 m. higher up, until 1770, when the architect Perrache constructed dykes between the rivers, and gained from the water the long tongue of land now partly occupied by an important suburb of Lyons. Cæsar appears to have visited the junction from his description of it: "Arar in Rhodanum influit incredibili lenitate, ita ut oculis in utram partem fluat, judicari non possit." (See p. 379.)

The united waters form a broad majestic flood; the banks are studded with small villages, scattered among willow and poplar avenues.

L. The high road along the l. bank of the Rhône is one of the worst in France; a series of ups and downs, liable to constant injury from the torrents descending from the hills across it; but, above all, tremendously cut up by the immense number of broad-wheeled waggons which traverse it at all seasons. Even though the Rhône, the largest river in France, runs parallel with it, such is the *rapidity* of the current, and the perversity of the navigation, from shifting sand-banks, that the transport up its valley of most of the bulky articles the produce of Provence, soap, oils, silk, dried fruits, &c., and of the colonial imports of Marseilles, is made on the axle. Every mile or two the road is studded with enormous barn-like Remises, whose open portals yawn invitingly to receive in their shade the loaded waggon and its 6 or 8 horses. They have a cabaret or carter's hostel attached to them.

The traveller "journeys onwards





THE RIVER RHONE

FROM LYONS TO THE SEA

French Post Leagues

English Miles

Reims

St. Denis

Paris

Orleans

Amboise

Chartres

Le Mans

Angers

Nantes

St. Nazaire

La Rochelle

Marseille

Arles

Nîmes

Montpellier

Perpignan

Barcelona

Valencia

Malaga

Seville

Cadix

Algeciras

Tangier

Morocco

Algeria

Tunisia

Syria

Lebanon

Palestine

Jerusalem

Baghdad

Constantinople

Istanbul

Sofia

Belgrade

Vienna

Budapest

Prague

Warsaw

St. Petersburg

Moscow

London

Paris

Brussels

Amsterdam

Rotterdam

Antwerp

Brussels

Paris





in the dazzling dreariness of the sunshine, amidst clouds of intolerable dust, crossed ever and anon by long caravans of roulage, drawn by tall mules."

Rt. The railway to St. Etienne (R. 118) continues near the water's edge as far as the dirty manufacturing town of

Rt. Givors, distinguished at a distance by the smoke of its glass-houses. It is a place of some importance from its position on the railway, and at the mouth of the canal, which brings down coal, iron, &c. from Rive de Gier (see R. 118). Its population is 4,900. Omnibuses run between Givors and Vienne corresponding with the railway trains.

Along the banks of the Rhône, from Lyons to Valence, a "poste aux ânes," or relays of donkeys, for the convenience of bargemen and such persons, was at one time established. The cultivation of the vine is very general in the neighbourhood of Vienne: vineyards here cover all the slopes.

L.\* *Vienne.* (Inn: Table Ronde: best, but charges high—L. F.; and not clean.) Vienne, a town of 17,000 inhab., stretches its buildings along the l. bank of the Rhône, faced by a tolerably handsome quay, at the foot of precipitous hills, and runs up a small valley between 2 heights: the one, *Mont Salomon*, crowned by a ruined castle of the middle ages; the other, *Mont Pipet*, originally a fortified camp of the Romans. The *Castle of Salomon* passes with the common people for the prison of Pilate, who was banished to Vienne in Gaul, according to Eusebius and others, after his return from Judæa to Rome.

From the valley behind Vienne, the Gère issues out into the Rhône, turning in its passage many mill wheels, and giving activity to manufactures of

coarse cloth, pasteboard, iron forges, &c.

Vienne is one of the most ancient towns in France, having been already a flourishing place before Lyons is known to have existed. It is mentioned by Cæsar, by Ausonius, in the line,

"Accolit Alpinis opulenta Vienna colonis,"

and by Martial, who calls it "opulenta Vienna," and it is natural to expect to find some remains of its Roman possessors. Besides numerous water conduits and substructions of masonry, the chief Roman building is a *Temple*, supposed to have been dedicated to Augustus, in form somewhat like the *Maison Carrée* at Nîmes, but much injured during the middle ages by having the interstices of its columns built up with masonry, and the columns themselves rasped to bring them to a level with the walls, in order to convert it into a church. It is now a *museum*, and contains a number of sculptured and architectural fragments found in and about the town, a very rich frieze, capitals of columns, &c. A Greyhound, in marble, two Boys quarrelling about a Bird (a common subject of antique sculpture), and 2 copper Dolphins found in the Rhône, are worth notice.

Behind the Place du Pilori is a lofty double arch and vault, with pillars inside, called *Arche de Triomphe*, but in reality part of the portico of the ancient Forum. It now leads to the modern theatre, and is unimportant.

On the slopes of Mont Pipet the remains of the seats of a *Roman theatre* may, it is said, be traced among the vineyards, but they are very inconsiderable. Lastly, outside the town, below it, is the Roman obelisk, or *Aiguille*, described p. 442.

The *Cathedral of St. Maurice* is a stately edifice in the lower part of the town, raised upon an elevated basement or parvis, facing the river, on a line with the bridge, and approached by a broad flight of steps.

\* The post road continues through  
8 St. Symphorien, at a considerable distance from the river, but it approaches it at  
13 Vienne.

Its W. front, flanked by 2 massive towers, is rich in flamboyant ornaments, but they are clumsy and without delicacy; and it was much mutilated, like all the churches on the Rhône, by the fanatic Huguenot soldiery (1562), less than 30 years after its completion. The interior wants height. The pointed roof, painted blue, and sprinkled with stars, and the 4 compartments nearest to the W. end, seem of the same age, viz. 15th or 16th century. The pillars of the choir, and the apses at the E. end, are said to be of the 12th century. There are no transepts. A marble monument of an Archbishop Montmorin, on the rt. of the altar, though much vaunted, seems a heavy piece of work; its artist was called Michel Angelo Slodtz. The N. porch retains some statues in a stiff style.

The Romanesque tower of *St. André le Bas* will be admired by the architect, for its composition and proportions; but the cloister, so interesting for the varied sculpture of its capitals, is now included in a private garden, and its pillars built up in a wall.

In the suburb Pont l'Evêque, in a hill on the l. bank of the Gère, there is a lead mine.

Many who have occupied themselves in tracing the route of *Hannibal* over the Alps suppose that he quitted the l. bank of the Rhône at Vienne (which was one of the chief towns of the Allobroges), proceeding hence, by Bourgoin and Yenne, to the Little St. Bernard.

Vienne is interesting as the cradle of Christianity in the W.: the Epistle of its early Martyrs to their brethren in the E. is a very instructive and perfectly authentic document.

Vienne was capital of the 1st kingdom of Burgundy in the 5th century, and at a later period was the capital and residence of the Dauphins. A celebrated ecclesiastical council held here 1307, and presided over by Pope Clement V. and Philippe le Bel, condemned the Order of the Templars

The archbishops long enjoyed considerable temporal sway: they had the privilege of naming the governor of the forts Salomon and Pipet, who was always a canon of the cathedral, but had a military deputy under him.

A *suspension bridge*, reconstructed since 1840, the previous one having been washed down by the inundation, connects Vienne with,

Rt., its suburb, St. Colombe, where stands by the water side an old square tower, sometimes called "Tour de Mauconseil," from a tradition that Pilate threw himself off from the top of it. In reality it was built by Philippe de Valois as a tête du pont to the original stone bridge, destroyed by the Rhône, 1651, except the trunks of some of its piers, still visible when the water is low.

*Diligences* daily to Grenoble (Rte. 131) and Lyons, and omnibuses along the rt. bank of the Rhône to Givors, to meet the trains on the railway to St. Etienne and Lyons. (Rte. 118.)

L. Immediately below Vienne, in the midst of a field, on the rt. of the road to Avignon, stands a Roman obelisk, called *L'Aiguille*, 76 feet high, rising from a square base, pierced by a double arch and supported at the angles by pillars of clumsy proportions. The whole is of excellent masonry, the stones being fastened together, not by mortar, but by iron clamps. Its destination is unknown, and it bears no trace of an inscription, but was probably a sepulchral monument.

Rt. The uniformity of the vine-clad slopes which border the river is relieved by the lofty irregular ridge and picturesque outline of *Mont Pilas*, 3516 ft. above the sea level, a member of the chain of hills which divides the Rhône from the Loire.

Rt. Ampuis.\* At its base is a small

\* The *Post Road* continues near to the Rhône, until almost opposite Ampuis, where it turns away to the station.

13 Auberive, situated outside the village, which it leaves on the rt.

6 Péage de Roussillon.



village, from the flat behind which rise the sunny slopes of *Côte Rotie*; called "the burnt side," from their happy exposure to the sun, which, striking full on them, as on a forcing wall, matures the excellent wine named after them. 3 m. below the hills of *Côte Rotie* is

Rt. Condrieux, a town of 4000 inhab., famed for its wines; it has a suspension bridge over the Rhône.

The soil of the valley of the Rhône abounds with rolled pebbles, which in places almost exclusively compose it; yet upon this grows the mulberry tree in vast quantities, planted in rows across the fields, while beneath, and in spite of its shade, luxuriant crops of corn are produced.

Rt. There is another suspension bridge at Serrières, and hence a road strikes off to Annonay. (R. 119.)

Rt. The church of Champagne is a Romanesque edifice of the 13th century, well worth the attention of the antiquary, on account of the singular bas-reliefs with which its outer walls are incrustated, consisting of heads of animals, monsters, &c., and for the sculptured cornice running under the roof. Some of these carvings have been conjectured to belong to a more ancient structure. Two of them represent David and Goliath, and Judith and Holofernes. The interior ends in an apse at the E. The grand portal is decorated above with 6 bas-reliefs in medallions, representing, 1. a satyr; 2. a lion couchant; 3 and 4. 2 young fauns; 5. a tiger; 6. a group of 2 genii embracing. The meaning of these sculptures seems difficult to explain.

Before the Revolution the towns of Andance, Champagne, Annonay, though on the rt. bank of the Rhône, belonged to Dauphiné, having been ancient possessions of the Dauphins of Vienne.

L.\* St. Rambert. Just below this the Rhône passes from the Dépt. de l'Isère into that of La Drôme.

Rt. The direct road from Paris to

\* *Post Road.*—? St. Rambert.

Marseilles, by Annonay, descends through a gap in the vine-clad granite hills near

Rt. Andance (R. 119), and crosses the Rhône, a little lower down, by the *suspension bridge* of

L. St. Vallier\* (*Inn*: Poste or Grand Sauvage), a town of 2455 inhab., consisting of a long street, extending on a terrace above the Rhône. It has a large modern château. There are numerous silk mills here.

Behind the town, in the gorge of the Galaure, rise the picturesque ruins of the *castle of Vals*; and near it is the *Roche Taillée*, a passage cut in the rock, through which a small road is carried.

L. The Château de Ponsas (derived, by the vulgar, from Pontius Pilate, who, according to the tradition, ended his days here by throwing himself from the rock) is a fine object, frowning with towers and battlements over river and village from the summit of a lofty precipice.

The valley of the Rhône is narrowed to a pass, by rocks projecting on either side, on approaching Tain. Nearly opposite the mouth of the considerable river Doux, which is crossed by a wire bridge,

(L.) a lofty round-topped hill, with a scanty scarf of black bushes round its shoulder, pushes forward its naked and almost precipitous sides into the river, which, along with the road, winds closely round its base. On doubling the sort of cape which it forms, its southern side will be found to consist of a more gradual slope, descending in a succession of steps, or terraces, formed by the natural divisions of the slaty beds of gneiss rock, all covered from top to bottom with vines. This is the celebrated vineyard of *L'Hermitage*, named from the ruin on its summit, once, perhaps, a hermit's cell. On its favoured slopes the sun plays all day long, maturing the juices of its grapes, which produce the Hermitage wine, one of the finest which grows on the Rhône.

\* 12 St. Vallier.

The white sort will keep for half a century; the red, of the best quality, is sent to Bordeaux, to be mixed with clarets of first growth, principally the kinds exported to England, which derive from it, and not from brandy, as is commonly supposed, that body which fits them for exportation, and adapts them to the English palate. The whole extent of the vineyard does not, perhaps, exceed 300 acres, and of this only a part near the centre, where a calcareous band traverses the gneiss rock, produces first-rate wines; the soil below is too rich, and above is too cold. The hill is divided among numerous proprietors; it is cultivated with vast labour, and at great expense; the vines are manured with sheep or horse dung. The grape grown for the red wine is called *Ceras*, and is said to have been brought from Shiraz, in Persia, by one of the hermits of the mountain.

L.\* Tain (*Inn*: L'Assurance; mid-*dling*), a town of 2,338 inhab., connected by a wire suspension bridge, the first, on a large scale, erected in France, with

Rt. Tournon, one of the chief towns of the Dépt. de l'Ardèche, 3,971 inhab. Above the bridge, the picturesque towers of the old *castle* of the Counts of Tournon and Ducs de Soubise rise on a precipitous rock, at the foot of the hills; it is now converted into the purposes of a mairie, tribunal, and a prison. Below the bridge, at the water side, stands the *Collège Royal*, originally founded by the Cardinal de Tournon, a favourite of Francis I. (1542), and a few years after, 1561, delivered over to the care of the Jesuits, in order to extirpate the seeds of Protestantism, and they maintained their post here until the suppression of the Order in 1766. It next became an *Ecole Militaire*.

*Diligences* run from Tain to Romans on the Isère, on the way to Grenoble. (R. 132.)

L. The valley of the river Isère, one of the chief tributaries of the

\* *Post road*.—14 Tain.

Rhône, rising at the foot of the Little St. Bernard, now opens out into a wide and monotonous plain, after traversing which, and being crossed itself by the high road, on a handsome bridge of 7 arches, the river falls into the Rhône. Its waters have usually a black tint contrasting with the white muddy Rhône. Hannibal is supposed by some to have reached the foot of the Alps by ascending this valley, having passed the Rhône lower down, perhaps near Rochemaure.

L. The vista, opening out through the valley of the Isère, is terminated by the majestic snowy mass of *Mont Blanc*, clearly distinguished from among the Alps of Dauphiné; a magnificent object, although 70 or 80 m. distant as the crow flies. The deck of the *steamer* is too low to command it, but it is well seen from the road, or rt. bank.

Rt. Mr. L. Giraud, the owner of the picturesque white feudal castle, the *Châteaubourg*, perched on a pedestal of rock, projecting into the Rhône, with a little hamlet at its foot, is much to be envied: his dwelling stands in the eye of Mont Blanc, and the everlasting snows of the monarch of mountains add magnificence to the distant horizon of a view, in which the exulting and abounding Rhône forms the foreground.

Rt. Cornas, at the foot of limestone hills of considerable elevation, produces a tolerable red wine.

Rt. On approaching Valence, the bare limestone precipices, rising behind the village of St. Peray, and crowned by the picturesque *castle* of *Crussol*, arrest the attention. (See p. 447.)

L. *Valence*.\*—*Inn*: Poste, outside the walls; not at all bad, with some pretensions to English comforts, but rather dear. Try here the sparkling St. Peray, an excellent wine, not inferior to Champagne.

The *steamer* passes the town and the Citadel, which is conspicuous from

\* *Post road*.—18 Valence.



the Rhône, but is separated from it by a considerable space of garden ground, and comes to her moorings below the *wire Suspension Bridge*, one of the handsomest on the Rhône, supported in the centre by a fine lofty arch of classical architecture.

The high road from Lyons to Avignon skirts the outside of the town, which lies between it and the river, through a faubourg, in which the *Poste aux Chevaux* and other inns are situated.

Valence is an ancient town of 10,967 inhab., still surrounded by its feudal ramparts, battlemented, flanked by towers, and entered by arched gates. It is chef-lieu of the Dépt. de la Drôme, and was formerly capital of the Valentinois, created a dukedom for the infamous Cæsar Borgia, by Louis XII.

The *Cathedral*, a Romanesque building, small in size and very plain, is yet interesting to the architect for its age and constructive peculiarities. It is a cross with long transepts. Outside the nave, above the aisle roof, runs a small arcade of arches, alternately round and straight-sided. The interior is simple; the piers, surmounted by nearly pure Corinthian capitals, support round arches, from which rises the cylindrical roof, without triforium or clerestory. The E. end is an apse, roofed with a semi-dome. The Church contains a bust and bas-relief, by Canova, to the memory of the unfortunate Pope Pius VI., who, after having been carried off a prisoner from the Vatican, and loaded with insults by the French, which he bore with resignation, died here, 1799.

On the S. side of the church is a singular building, known as *Le Pendentif*, of classical architecture, erected 1548, as a monument to the family Mistral, whose arms are still visible on it. It is square in form, consisting of 4 piers, with pillars in the angles, and arches between them, supporting a vault, the first of its kind erected, and regarded as a type in

architecture. In the rusticated space occupying the sides, carvings of monstrous birds may be discovered.

The ancient *Evêché*, now subdivided, and partly destroyed, was often visited by Madame de Sévigné.

The semicircular E. end of the cathedral adjoins the *Place aux Clercs*, a small square, about to be ornamented with a statue of the Napoleonist General Championnet, a native of Valence.

In the "Grande Rue," leading out of this Place, will be found a very rich and interesting specimen of domestic architecture, in a *Mansion* of the 16th century, now converted into a bookseller's shop. Its origin and destination are not clearly known. It has a Gothic front, covered with elegant Florid tracery, now sadly mutilated, combined with a certain mixture of classic ornament, such as rows of heads and statues, the upper heads representing the 4 Seasons. The doorway is an elegant flattened arch; the transoms of the windows have unfortunately been knocked out. The front of the house is not in one plane, but projects forward; only one part of it is ornamented, and that which is unadorned retreats backward at a slight angle, so as to be partly concealed from view as you approach it from the Place aux Clercs, probably with design on the part of the architect. The groined and vaulted passage, and the walls towards the inner court, also deserve notice. In the same street, at No. 4, on the 1st floor, *Napoleon* lodged, while yet a poor and obscure sous-lieutenant of artillery; and some of his first essays in the art of war were made in the Champs de Mars here. The *staircase* at the back of the house of Madame Duprè, Rue Perolierie, is a good specimen of the Renaissance in architecture, enriched with sculpture.

The *Citadelle*, begun by Francis I., and bastioned only on the side facing the town, but of no use now as a fortress, is converted into a Caserne

du Génie. From the finished bastion there is a good view over the river, of St. Peray, and the Castle of Crussol on its arid rock beyond the Rhône.

Valence is the seat of an *École d'Artillerie*, and the practice of gunnery is taught on the *polygone*, a large sandy area on the outskirts of the town, bordering on the Lyons road.

The reeling (filature) and throwing (moulinage) of silk affords employment to a large number of persons at Valence. (See p. 449.)

*Steamers* up and down the Rhône daily. The ascent to Lyons is made in one day.

*Malleposte*, by Annonay, to Paris and to Marseilles.

*Diligences* daily (4) to Lyons and Marseilles; 2 to Grenoble (R. 132); 1 to Aubenas and Privas (R. 121); to St. Etienne and Annonay.

Rt. *St. Peray*, famed for one of the best wines of the Rhône, is 2 Eng. m. from Valence, on the opposite side of the Rhône, within the Dépt. of the Ardèche: an omnibus goes thither several times a day.

The little village of St. Peray lies snugly in the quiet nook of a sheltered valley running down to the Rhône opposite Valence. Its most conspicuous buildings are the house of M. Faure, the chief proprietor of the *vineyards* around; and on the height, a little above it, the *Château de Beauregard*, a singular mansion on the plan of a mimic fortress, bastioned and curtained, with loopholed walls, portcullis, &c., built, it is said, by Marshal Vauban, as a freak, reminding one of Uncle Toby and Corporal Trim, now converted into a dépôt for the wine of the district, for which it is better suited than for a dwelling, being constructed over cellars of vast extent.

The slopes of the hills around St. Peray are covered with one uninterrupted vineyard, and wherever they present an aspect to the S.E., so as to receive the sun's rays during nearly

the whole day, the best wines grow: such are the Côte de Hongrie, Chapelle de Crussol, and the Prieuré vineyards. The soil is a decomposed granite, and the vine seems to flourish most on this mere dry gravel. Great pains are taken in digging about the roots, but the only manure employed is the leaves of the box, cut small. The grape, when ripe, assumes a beautiful golden hue; its taste is cloyingly sweet, and the saccharine matter exuding often covers the bunches with a brown stain.

The sparkling *St. Peray wine* is distinguished from Champagne in this respect, that its sweetness arises from the natural juice of the grape, and not from the addition of sugar to the grape juice; and it is consequently a far more wholesome and not less palatable wine. The red St. Peray derives its colour, a delicate rose tint, from the hue of the skins of the grapes. The vintage takes place about the middle or end of September, and the juice is at once transferred to the cask before the fermentation has begun, and rests there for 6 or 7 months, during which time it is fined. In March or April it is bottled, and remains 2 or 3 years to mature, and allow the dregs to deposit. The bottles are piled up in stacks, each row separated by laths, to allow of the bottles which burst (and they form 14 or 15 per cent. of the whole) to be withdrawn. After this the wine is racked, i.e. every bottle is taken out, and is thrust, with its neck downwards, into a hole cut in a board. By this means the dregs sink down gradually into the neck, and, as they descend, day by day, the bottle is tilted more and more until its position becomes nearly vertical. To expedite the falling of the sediment the bottles are lifted and set down with a jerk once or twice a day; and after receiving 200 or 300 of these jerks, the bottle is taken up, and the sediment is discharged by cutting the string and letting the cork fly, and with it the lees at the



neck of the bottle, but as little as possible of the wine. This is called "disgorging." The vacancy thus caused is filled with clear wine; and this process of corking and uncorking is repeated 2 or 3 times, until no more sediment is deposited. The wine is then fit for use, and an excellent wine it is, the "St. Peray grand Mousseux" of M. Faure being at least equal to a first-class Champagne.

Rt. A very conspicuous but unsightly line of cliffs of limestone, naked, arid, and partly stained black and yellow, bounds the W. side of the Rhône valley, opposite to and below Valence. Quarries of building stone are worked in these rocks. The highest peak of all, a castled crag rising above the entrance of the valley in which lies St. Peray, is crowned by the ruins of the *Castle of Crussol*, called, from its 2 projecting and roofless gables, *Les Cornes de Crussol*, and conspicuous from a great distance. It belonged to the ancient family of the Crussols, Ducs d'Uzès, and once enclosed within its fortifications, which may be seen running down the rock, a small village long since deserted. Owing to the precipice, from whose very edges its walls start up, it must have been impregnable in the olden time.

Rt. Lower down, on the top of the same escarpment of limestone, stands *Soyons Castle*, now an utter ruin, conspicuous from its leaning tower, on the verge of the precipice, once a stronghold of the Calvinists, who by means of it held the key of the Rhône, intercepting the communication between Lyons and the S. in 1627, under their chief, Brisson: it was taken and demolished the same year by the Prince de Condé. A flight of steps cut in the rock leads to the summit.

L. Among the Dauphiné mountains the *Roche Courbe* becomes a conspicuous feature in the landscape, from its precipitous sides and horned brow. A little further down it changes its aspect, presenting a series of peaks as seen from the river.

L. L'Etoile, a pretty village.

Rt. The river Eyrieu pours itself into the Rhône, a little below Charmes, at Beauchastel, where a new wire bridge shortens the way to Lavoulte by more than 2 m. Formerly it was necessary to ascend as high as St. Laurent du Pape to cross the Eyrieu.

Rt. Lavoulte, a little town, piled up in a heap against a rock, is distinguished by the large *castle* on the summit of the height above it, and the clouds of smoke rising from the 4 large iron furnaces at its base. The *Castle*, an ancient possession of the house of Ventadour, and residence of Louis XIII. in 1629, is now occupied by an iron company, and partly serves as a fire-brick kiln: 1 or 2 picturesque towers remain of its older feudal part. The furnaces at its base are supplied with a very rich ore (red carbonate or hæmatite), from mines a short way up the valley. More than 300 persons are employed in them and in the iron works; and the red tinge from the ore pervades the hideously filthy streets, and its dirty inhabitants, whose flesh, clothes, and even hair, acquire the same ruddy stain. The coal comes from St. Etienne, and the metal is sent hence in barges, for whose reception a little basin has been formed here at the water side.

A little below Lavoulte, on the opposite side of the Rhône,

L. the river Drôme, which gives its name to a Dépt., pours itself into the Rhône.

L. On either side of the Drôme, about 2 m. above its confluence, stand the towns of Livrons (half of whose 3457 inhab. are Protestants) and Loriol\* (*Inn*: Chariot d'Or). A fine bridge over the Drôme connects them, and the high road passes through both. On the l., in the valley, is the Château of Crest, well placed. Loriol was the birth-place and residence of Faujas de St. Fond, who wrote a bulky tome on the extinct Volcanoes of Central France in his own neighbourhood, which, as the

\* *Post Road* —11 Paillasse. 11 Loriol.

author had never seen an *active* volcano, abounds in fallacies, and is now little valued.

The road to the volcanic district of the Ardèche, by Privas and Aubenas (Route 121), turns away from the Rhône near Pouzin.

L. Cruas, a curious fortified Abbey on a hill, in ruins, but retaining its antique ramparts, gates, and donjon, which stood sieges in 1584 and 1585, from the Calvinists, who were repulsed by the Monks. The church, below the road and half buried under the deposits brought down by a neighbouring torrent, is a curious specimen of Romanesque architecture: beneath it are crypts. It contains the monument of Count Adhemar, founder of Montélimart and Rochemaure.

One of the most striking scenes on the banks of the Rhône is

Rt. Rochemaure, a small village, at the base of a hill from which project 3 peaked masses of black basalt, contrasting vividly with the light-coloured limestone around. The middle peak, rising precipitously 300 ft. above the river, is surmounted by the ruins of a feudal *castle*, which belonged to the families of Ventadour and Soubise. The donjon, crowning a now isolated peak, was formerly joined to the rest of the fortress by bridges thrown across the abyss. In these precipices of Rochemaure you behold the last root or limb of the Coiron chain of hills, which, after traversing the whole of the Ardèche, terminates here, on the margin of the Rhône. The black rocks are 3 dykes of basalt, branches of the vast lava current which caps that mountain plateau. The basalt assumes in places a columnar form, and some of the houses and a part of the castle are built of regular prisms. From the top of the rock of Rochemaure there is a fine view over the course of the Rhône, the Alps of Dauphiné, &c.

About 3 m. lower down, but  $1\frac{1}{2}$  from the river-side, stands

L. Montélimart\* (*Inn*: Poste), an  
\* *Post road*.—13 Derbières. 10 Montélimart.

ancient town of 7,956 inhab., entirely surrounded by Gothic ramparts flanked with watch towers, and entered by 4 gates. On a rising ground within it stands the *castle* or citadelle. It obtained its name, Monteil d'Adhemar, from a powerful family of magnates, who held possession here from the days of Charlemagne, and from whom many of the old noblesse of the province traced their lineage. Some morocco leather is made here, and the manufacture is mentioned by Rabelais. The almond cakes (*nougat*), in texture resembling a piece of soap, enjoy some celebrity. Near this the olive is first seen, though it cannot be said to flourish farther to the N. than Avignon: black truffles abound; and the mulberry tree is cultivated to a very great extent for the silk-worm.

At a small village called Allan, about 9 m. S.E. of Montélimart, and the same from the Rhône, there existed, down to 1802, the first white mulberry planted in France. It was brought thither from Naples, by Guy Pope de St. Auban, seigneur of Allan; one of the soldiers who accompanied Charles VIII. on his Italian campaign, 1494. It spread hence all over the S. of France, where the culture of the silk-worm is now one of the chief sources of industry and prosperity to the people. The silk-worm is here called *magnan*, and the establishments in which it is reared *magnaneries*. A single tree will furnish 5 or 6 quintaux of leaves, and not unfrequently as much as 9 or 10 quintaux.

At the time when the eggs (*la graine*) are beginning to be hatched, sheets of paper pierced with holes are laid upon them, and through these the worms, extricating themselves from the shells, climb to reach the mulberry leaves hung over them, whence they are transferred to hurdles formed of reeds, arranged like shelves, for their future habitation. The worms live in that state (as *larvæ*) about 34 days, and in the course of that period change their skin 4 times. Before each of



these sloughings, called "*ages*" by the peasant, they become torpid, and cease to eat, but, having changed their skin, their appetite increases enormously. The periods of appetite preceding the 4 first changes are called *petites frèzes*, and that before the 5th change, *grande frèze*. The consumption of leaves increases with each age. The worms produced by an ounce of eggs devour 7 lbs. of leaves during the 1st age, and as much as 200 to 300 lbs. of leaves during the final period. At that time they make a noise in eating which resembles that of a heavy shower falling. On the 10th day of this 5th age they cease to eat, and try to climb up to the small twigs of heath or other plants purposely hung over the shelves, in order to spin their cocoon, which they complete in 3 or 4 days. Formerly it was usual to bake the cocoons in an oven, in order to kill the worm and prevent its biting through the silk; a more effectual method, unattended by risk of burning the silk, is to enclose the cocoon in a copper filled with steam, and hermetically sealed, and thus to stifle the worm. It is then fit for reeling (*filature*).

17 m. S. E. of Montélimart is *Château Grignan*, celebrated in the letters of Madame de Sévigné, and the residence of her son-in-law. It was originally a stately pile, "*un château vraiment royal*," as Madame de S. calls it, seated on a commanding height above the town, fronted with a terrace raised partly on a rock, partly on masonry, 100 ft. high, commanding an extensive view, bounded by the Mont Ventoux. But it was burnt and gutted at the Revolution by a band of robbers composed of the scum of Orange and the neighbouring towns, and now stands a mere shell; yet the window of the bed-chamber and boudoir of the Sévigné is still pointed out. In the *church*, whose tower adjoins the castle terrace, and rises to a level with it, Madame de Sévigné (who died at Grignan) is buried. A black stone in the pave-

ment marks the entrance of the family vault, which was saved from desecration at the hands of the Revolutionist pillagers of the church by the removal of this stone, so as to conceal the position of the vault.

The traveller may regain the banks of the Rhône from Grignan by a different road, leading direct to La Palud, near Pont St. Esprit. The cross-roads, however, to and from Grignan are very bad indeed.

A considerable hill occurs on quitting Montélimart.

Rt. The inundation of 1840 carried off the suspension-bridge across the Rhône at Le Theil, nearly opposite Montélimart.

The superior transparency of a southern atmosphere becomes perceptible hereabouts, in the remarkable blueness of the distant hills, approximating in intensity to ultramarine. The inhabitant of a northern climate, who has, perhaps, regarded as exaggerations the azure mountains in the backgrounds of the paintings of Titian, will be surprised to find them here realised in nature.

The Rhône is confined between high but arid limestone cliffs abreast of

Rt. Viviers, a town of only 2,500 inhab., yet a bishop's see, and anciently the capital of the province of Vivarais, which is named after it. The town, inclosed within its old walls, is a complicated labyrinth of narrow streets, partly crossed by arches, not unlike the interior of a hive. On an eminence, near the verge of the cliff, rising abruptly from the Rhône, stands the *Cathedral*, overtopping the other buildings: it is small, and not very remarkable; the nave modern, surmounted by a tower. Near it is the Evêché. At the upper end of the town stands the *Séminaire*, a huge modern edifice of 6 stories, for the education of priests. A private house in the principal Place presents in its richly ornamented front a good specimen of domestic architecture. Viviers suffered

much during the wars of Religion, having been one of the first towns to declare against the king in favour of the Prince de Condé and the Protestant party, 1562. It was several times besieged and captured by both parties.

There is a road from Viviers to Aubenas, by Villeneuve de Berg, the birth-place of Olivier de Serres; near which is a curious volcanic mountain, known as les Rampes de Montbrul, pierced with grottoes.

L. The majestic summit of the *Mont Ventoux*, the extreme buttress or root pushed forth from the French Alps towards the Rhône, continues in view, a noble object and landmark from this as far as Avignon.

Below Viviers\* the river expands, and its current is divided by numerous willowy islands. A fine suspension-bridge of 3 curves, rebuilt since 1840, when the inundation destroyed it, crosses the Rhône at

Rt. Bourg St. Andeol, a town of 4,300 inhab., built on a slope. Close to it is a copious source rising from the base of a rock, on the face of which, about 20 ft. from the ground, is a rudely-sculptured group, representing the Sacrifice of a Bull to the god Mithras, to whom the source seems to have been dedicated. It is now nearly effaced.

Those who intend to visit the antiquities of Orange, on their way to Avignon, must quit the steamer at the bridge of Bourg St. Andeol.

L. Opposite to St. Andeol, but removed  $1\frac{1}{2}$  m. from the river, is Pierrelatte, so called from the broad isolated mass of rock rising out of the plain behind it, to a height of 300 or 400 ft. For many miles beyond this, nearly as far as Avignon, the road runs at such a distance from the Rhône that it is rarely seen at all.

L. La Palud,† the first place in the Dépt. Vaucluse, is about 2 m. distant from the Rhône, but the

crocketed stone spire of its Gothic church may be distinguished. A few miles to the E. of the road is St. Paul Trois Châteaux, the Roman Augusta Tricastinorum.

Rt. The river Ardèche pours its waters into the Rhône nearly opposite La Palud, and its deposits seem to have formed the numerous islands occurring near its mouth.

Rt. About 2 m. lower down, at *Pont St. Esprit*, a town of 4,500 inhab., whose citadel was built by Louis XIII. to keep in awe the Protestants, the Rhône is crossed by a *bridge* of 26 arches, the longest stone bridge in the world, and down to 1806 the only one over the Rhône. It was built 1310 by an associated brotherhood formed in the town, then called St. Saturnin, and 45 years were occupied in its construction, the first stone having been laid 1265 by the prior of the convent. The cost of this great public work was defrayed by subscriptions raised among the inhabitants of both banks of the Rhône, and by offerings made by the pious at a little chapel dedicated to the Holy Ghost at the end of the bridge, whence its actual name. The stones for it were brought by water from the quarries of St. Andeol, and a company of monks and nuns was established on the bank, the one to superintend the works, the other to attend the sick or wounded workmen. It is 2,550 Fr. ft., or 2,717 Eng. ft. long, more than three times as long as London Bridge, and 17 ft. wide: the arches are irregular in size; the widest have an opening of 108 ft.; the piers are pierced with small, round-headed, flood-water arches. It is not straight, but makes an angle against the stream. The passage under the Pont St. Esprit used to be thought an achievement like that of shooting old London Bridge, owing to the rapidity of the current; but the experience of the pilots is a guarantee from all danger, and the steamers pass in perfect safety,

\* *Post road*.—14 Donzère.

† *Post road*.—16 La Palud.



although the eddying river, rushing through the low arches, has an alarming look, increased by the sudden twist which the steersman is obliged to give to the vessel the moment it has passed through. The bridge is about 2 m. distant from the high road to Avignon. Roads branch off from it E. to Gap, and S.W. to Nîmes, by the Pont du Gard. (R. 126.)

L. The Avignon road, having crossed that from Pont St. Esprit to Gap, skirts the towns of Montdragon and Mornas, both seated at the foot of precipitous cliffs crowned by ruined castles. From that of Mornas, as the story goes, the ferocious Huguenot leader, the Baron des Adrets, forced his prisoners to leap down on the pikes of his soldiers below.

L. After passing a small stream, the Aigues, a glimpse may be obtained from the river of a huge structure surmounting the town of Orange, 3 m. inland from the Rhône: it is the wall of its Roman theatre. (See below.) The post-road, just before it reaches Orange, flanked by poplars, is carried in a double sweep round the antique Roman Arch.

L. *Orange.\*—Inns:* H. des Princes; Griffin d'Or; both dear: mosquitoes are to be much dreaded here. (§ 3.) This town of 9,223 inhab., situated about 3 m. E. of the Rhône, was the ancient Arausio, and is remarkable for the interesting Roman remains which it possesses. Its name has been rendered familiar and illustrious by having been borne by the noble family of Nassau. It was the chief town of a small but independent principality which had existed from the 11th cent., and on the death of Philibert de Châlons, Prince of Orange, 1531, without children, became the inheritance of his sister, who was married to the Prince of Nassau Dillingen. The family of Nassau was confirmed in the possession by the Treaty of Ryswick; but upon the death of William III. of England the King of Prussia claimed

it, as a descendant of the princes of Nassau-Orange, and in spite of other, rightful perhaps, but weaker claimants, he was allowed by the Treaty of Utrecht to make over the principality, in exchange for other possessions, to the King of France, from whose dominions it has never since been separated. The house of Nassau consequently retains at present no more than the title of Prince of Orange, which is borne by the heir to the throne of Holland.

The principal Roman remains are, 1. The *Triumphal Arch*, situated about  $\frac{1}{4}$  m. outside the town, on the road to Valence. It is a handsome structure, in a good, if not in the best style of Roman architecture: its preservation is remarkable, considering that it was incorporated in the palace of the Princes of Orange; and the deep yellow tints of the stone (a tertiary limestone abounding in fossils) of which it is composed have a rich effect. The bas-reliefs with which it is adorned represent chiefly naval trophies,—rostra, masts, yards, shrouds, anchors, and a number of barbaric shields skilfully disposed; others consist of groups of figures, but the subjects are not satisfactorily explained: one female holds her finger to her ear. The sunken panels (caissons) in the vault of the central archway are very elegant. The date and destination of this arch are unknown; no inscription is visible, excepting certain names inscribed on the shields, among which the most distinct is MARIO, and some have, in consequence, supposed that it was raised in commemoration of Marius' victory over the Cimbri near Aix. But arches of triumph were not known, it appears, until the time of the emperors, and the generally-received opinion at present refers it to the reign of Marcus Aurelius, and to his successes on the Danube and in Germany.

The building has been very judiciously repaired.

Quite at the other end of the dirty

\* *Post road* —12 Mornas. 11 Orange.

little town stands, 2. The *Roman Theatre*, at the foot of a hill, whose side, with skilful economy, was excavated into semicircular ranges of seats for the spectators, and whose top was crowned by the citadel of the Romans first, and afterwards of the Princes of Orange, finally razed by Louis XIV. The colossal wall forming the scena, the chord of the semicircle, built over against the hill, overtops all the puny edifices of modern times, and is conspicuous for miles around. Few such walls, it may safely be asserted, exist in any part of the world: its dimensions are, 34 mèt. = 121 ft. high, 102 mèt. = 334½ ft. long, and 4 mèt. = 13 ft. thick. It is formed of huge blocks, fitted accurately together without cement. It had 3 doorways below, and near the top ran 2 rows of projecting corbel stones, those nearest the extremities being pierced with holes for the masts, by which an awning was stretched over the scene. Owing, however, to the projection of the crowning cornice, the masts must have inclined outwards. The inner face of the wall is denuded of ornament; in its centre is an arch, and on either side a curious and lofty recess. The interior has recently been cleared of the miserable hovels which filled it, and whose tenants, in some instances, burrowing like moles, had formed cellars in the thickness of the wall, regardless of the risk of undermining it, and of being buried in its ruins. The removal of 100 of these cabins now enables the spectator to judge, to a certain extent, of the arrangement of the scene on its inner face. It is still accessible by stone stairs nearly to the top. Some of the corridors are vaulted with long stone beams. Near the top the stone is calcined and reddened by the action of fire. The apartments at the side were destined for the actors, scenery, and other accessories of a theatre. A few seats remain on the slope, formed by excavating the limestone rock: on one may be seen the letters Eq. C. III.,

(Knights' 3rd row).—Round the semicircle run 3 passages, lined with masonry of small stones. A great many fragments of architecture and sculpture, slabs of marble, pillars of granite, &c., dug up within the enclosure, are preserved here.

Side by side with this theatre ran a *circus*, or hippodrome, the greater part of which has disappeared, quarried out to build the houses of the town, except a few arches of the portico, which joined it to the theatre.

The ancient *Arausio*, which could construct and maintain edifices of such splendour and magnitude as these, far exceeded in extent the present provincial town; and, judging from the range of the Roman walls, part of whose circuit still remains, they may have enclosed a population of 40,000. A good survey of it may be made from the heights above the theatre, where the citadel, now reduced to fragments of masonry, and the base of a round tower, once stood.

The people of Orange have a character for ferocity, of which they certainly displayed a sample during the Revolution; 378 persons perished here by the guillotine, in the space of 3 months, in compliance with the decree of the revolutionary tribunal.

At Vaison, 15 m. N. E. of Orange, are some scanty ancient remains, 2 arches of a *theatre*, and a *Roman bridge*, of a single arch, over the torrent Lou Vèze, beyond which, in the modern town, are 2 old Romanesque churches, *St. Quinin*, partly of the 8th centy., and the *cathedral*, calculated to interest the antiquarian architect.

The most curious of the bas-reliefs and other antiquities, built into the walls of the house called Château Maraudy, have been removed to Avignon.

The Rhône, below Orange, traverses a wide plain, with little variety of surface.

Rt. Roquemaure, distinguished by its tower, perched on the edge of a



cliff, excavated below by stone quarries, is fixed on by various authors as the spot where Hannibal passed the Rhône with his army and elephants, 4 days' march below the junction of the Isère, on his way to the Little St. Bernard, where he crossed the Alps.

L. Nearly opposite is Château-neuf des Papes, where the Popes had a country residence.

L. The stony plain on the E. of the Rhône is nearly barren, but supports a few olives and willows. The road passes by Courthezon, near which is a salt lake, the only one in France; in its bed salt is collected when the waters dry up. There is greater fertility near Bédarrides (Biturritæ, from 2 towers which it possessed), and Sorgues, a village named from the clear stream flowing through it, which rises at Vaucluse. At its junction with the Rhône, that river divides into 2 branches, separated by broad islands.

The spires of Avignon, and the gigantic towers of the Papal palace, now rise conspicuously to view, whether we approach by land or water.

The steamers stop at the quay, outside the lofty battlemented city wall, just above the broken *stone bridge* of *St. Benezet*, and its little chapel, which is about a mile from the Inns. Passengers are left in the hands of the *porters* of Avignon, who are notoriously a brutal set, and whose exactions and insolence ought to be repressed by the police.

L. AVIGNON.\*—*Inns*: Hôtel de l'Europe, very good; a most attentive landlord;—H. du Palais Royal, also very good and moderate. There are few better inns in France than these.

This ancient city of the Popes is seated on the l. bank of the Rhône, a little above the influx of the Durance into it, and is still enclosed by the lofty *walls*, surmounted by a cornice of machicolations, battlemented, and flanked by watch-towers, which were

constructed for its defence by Clement VI. in the middle of the 14th centy. They are very perfect and picturesque, interrupted only on the side towards the Rhône by the cliffs of the *Rocher des Dons*, which, starting up abruptly, nearly from the water's edge, is let into the wall, serves as a rampart, and renders other defence needless. Within the circuit of these fortifications, however, will be found large spaces, now vacant, once covered with habitations; for Avignon, though now numbering only 31,786 inhabitants, possessed down to the time of Louis XIV. a population of 80,000. It has indeed several thriving suburbs outside its walls. A new suspension-bridge is thrown over the branches of the Rhône, from the Port d'Oulle to Villeneuve-les-Avignon, on the rt. bank of the river. In the Place d'Oulle, just within this gate, stand the two principal hotels, and a small *theatre*, designed by the architect Mignard, now a warehouse. On this Place Marshal Brune, in passing through Avignon, 1815, was murdered by an infuriated mob of Provençal royalists, who, upon the news of the battle of Waterloo, and instigated by hatred of Buonaparte, rose upon their adversaries, and committed all sorts of excesses and massacres. The Marshal, though furnished with Lord Exmouth's passport, was shot by the pistol of an assassin in his chamber at the Hôtel du Palais Royal, his body was thrown into the Rhône, and his murderers escaped justice.

To obtain an idea of the leading features of Avignon and its vicinity, the traveller must penetrate through its ill-paved and dirty streets, so narrow that an awning is often stretched across, from house to house, to keep off the sun, to the *height of the Dons*. On reaching its platform of bare rock, close to the telegraph, he will find himself on the brink of a precipice, looking over the Rhône, here divided by an island, towards the

\* *Post road*.—18 Sorgues. 10 Avignon.

towers of Villeneuve, which was long a frontier fortress of France, on the opposite bank. In the S. appears the barren range bordering the valley of the Durance, and the Durance itself hurrying on to join the Rhône. On the N. E. rise the Mont Ventoux, and the blue hills at whose feet lies Vaucluse; and close at hand the buildings of the city are spread out, surmounted by the cathedral, the palace of the popes, and its ill-omened tower of the Glacière planted side by side.

The *Cathedral*, called *Notre Dame des Dons* (de Dominis), is founded on the rock, and approached by a long flight of steps. It is entered by a projecting porch, calculated to interest and puzzle the architect and antiquary, consisting of a circular arch, flanked by 2 Corinthian columns at the corners, so completely Roman in character that some have supposed it to have formed the porch of a Roman building, a temple of Hercules; and, judging from a juncture perceptible in the masonry behind, it is probably of a different date from the body of the church. The pediment surmounting it is rather higher pitched than is usual in classic buildings; its tympanum is pierced with a circular opening, and over the doorway are the remains of frescoes of the 14th centy. Behind this rises a massy W. tower, and the cross is surmounted by an octagon, supported at the angles and flanked externally by fluted Corinthian columns. The roof is Pointed; the side chapels date from the 14th centy.; that of St. Joseph was once a passage leading into the papal palace. The *tomb of Pope Jean XXII.* is a florid Gothic canopy, richly carved, but mutilated, and its niches emptied since the Revolution; beneath it reclines his broken effigy. Benedict XII. is also buried here under a plainer monument. Here is preserved a very ancient *altar*, a slab of marble supported on 5 pillars with classic capitals. In the choir is placed the *papal throne*, now the seat

of the archbishop, of marble, carved with the Winged Bull of St. Luke, and the Lion of St. Mark. 4 or 5 popes were consecrated in this church.\*

Besides what it suffered at the Revolution, this edifice was, in 1814, made the receptacle for some hundred Spanish prisoners. It has lately undergone repairs, and has been modernised with bad effect. One chapel is decorated with frescoes by *Deveria*; in one a statue of the Virgin, by *Pradier*, has been placed.

The ancient *Palace of the Popes*, now degraded into a barrack and prison, is magnificent from its colossal vastness, and very impressive in spite of its present degradation and mutilations. It partakes of the mixed character of a feudal castle and convent. Its walls are 100 ft. high, and some of its towers 150 ft., with a proportionate thickness of masonry. But above all, how rich is it in associations! It was founded by Clement V., 1319, and during the greater part of the 14th centy., the period of its con-

\* The Popes gained possession of Avignon on the strength of a grant made by Joanna of Naples, while yet a minor, 1348: she was to receive for it 80,000 gold crowns, which were never paid.

*List of the Popes who reigned at Avignon—all Frenchmen.*

- 1305. Clement V. Born near Bordeaux.
- 1316. John XXII. Born at Cahors.
- 1334. Benedict XII. Born at Verdun, Comté de Foix.
- 1342. Clement VI. Born near Limoges.
- 1352. Innocent VI. Born near Limoges.
- 1362. Urban V. Born in diocese of Mende.
- 1370. Gregory XI. Born in Limousin. Quit-  
ted Avignon for Rome, 1376. Thus  
ended the Babylonish Captivity of  
the Romish Church, as it is called,  
"L'Empia Babilonia" of *Petrarch's*  
*Sonn.* 91.

Afterwards the following schismatic Popes set up their throne at Avignon, and resided there 40 years:

- 1278. Clement VII.
- 1394. Benedict XIII. (Pierre de Luna.)
- 1424. Clement VIII.

On the termination of the Schism, Avignon became the residence of a papal Legate. Louis XIV., "the eldest son of the Church," seized Avignon to revenge a pretended affront on his ambassador at Rome. Louis XV. held possession of it for 10 years. It was not united with France until 1791.



struction by successive rulers, it was the seat of the Papal court, which had become a by-word for its luxury, profligacy, and venality. In those halls, now echoing to the blasphemous oaths of prisoners, or subdivided and filled with soldiers' cribs and accoutrements, the conclave of cardinals sate by whom the pope was elected: here *Petrarch* was a guest. Giotto and his scholars adorned its walls, and in its dungeons *Rienzi* was a prisoner. Here the once formidable Tribune of Rome, who had ruled from the Capitol with the sway of the Cæsars, now humble and despicable, owed his life to the intercession of his friend the poet. He was imprisoned in the tower *des Oubliettes*, and fettered with a single chain, fastened into the vault of the dungeon; in other respects kept in honourable custody, and had his meals from the remnants of the papal table, which were distributed to the poor. He could pursue his beloved studies: the Bible, and the history of the ancient Romans, particularly the books of Livy, were his companions in his prison, as formerly at the height of his prosperity. These battlemented walls and towers defied for several years a French army under Marshal Boucicault, who in vain besieged within them the anti-pope Benedict XIII. (Pierre de Luna), who finally escaped by a postern.

Above the entrance, originally defended by drawbridges, portcullis, and iron gates, now removed, is the *balcony* whence the popes bestowed their benediction upon the people. The first court is disfigured by new buildings. A wide stone staircase, under a depressed arch, on the rt. hand, leads up to what was once the great *hall* of the palace, called *Salle Brûlée*, ever since Pierre de Lude, papal legate in 1441, caused it to be blown up, with the guests assembled in it, consisting of the nobles of Avignon, in revenge for the murder of his nephew, a young libertine, who had outraged them by his excesses! Attached to it are side

chapels, and the *Salle du Consistoire*, having traces of *frescoes* executed in the 14th centy.; but they are partly effaced or concealed from view by the modern division of this lofty range of halls by floors, into 3 stories, to convert them into dormitories.

Another stair, on the opposite side of the building, leads to the chamber occupied by the *Inquisition*, which was established here in the 13th centy. The *Chapelle du Saint Office*, vaulted and groined, retains scarcely any traces of the frescoes with which it was decorated by Giotto, 1324-27. Christ's Baptism, and Interview with the Woman of Samaria; Theodosius repulsed by St. Ambrose, and St. Louis in Egypt, the Pyramids in the background, may still be distinguished. A large portion, including the Last Judgment, are effaced. Here the Jews inhabiting Avignon were assembled at stated times to hear a sermon, designed to promote their conversion to Christianity. The *chamber of torture* (*salle de la question*) adjoining is built with funnel-shaped walls, contracting upwards, in the manner of a glass-house; a form devised, it is said, to stifle the cries of the miserable victims. In the thickness of the wall, in one corner, are the remains of a furnace for heating torturing irons, according to the tradition. Near it are the holes to which was attached the instrument called *La Veille*, a pointed stake upon which the condemned was seated, suspended by cords from above, so as only to prevent his falling, but allowing his whole weight to bear upon the point. These are the associations of the dark ages, and they are dismal enough; but this building has beheld events in modern and enlightened times which far distance them in their horrors and atrocities. The crimes accumulated during a few hours of the French Revolution exceed those dispersed through previous ages. Who has not heard of the *Glacière* of Avignon? The tower so called, from an ice-house in a garden near it,

stands close to the tower of the Inquisition. The stranger is invited to gaze into it, through an aperture in its walls, and he will discern near the bottom long black stains; they are streaks of human blood; and into those dark depths below were hurled from above no less than 60 unfortunate and innocent persons, females as well as men, massacred by a band of democrats more savage than wild beasts, in Oct. 1791. The prisoners were dragged from their cells, and poignarded or struck down in the door; but in the blind haste of the ruffians, it is believed that some of their victims were precipitated from above before life was yet extinct; but to finish the deed of infamy, quicklime in large quantities was thrown down over them upon the mangled heap of dead and dying.

In the narrow passage, shut up within lofty walls, by which you approach this part of the castle, some of the prisoners of the revolutionary executioner Jourdan, called *Coupe-tête*, from his butcheries, were thrust, and cannon being brought to the gate, were despatched by grape-shot, the marks of which still indent the walls.

The modern building facing the Papal palace, now *Hôtel de Ville*, fantastically ornamented in front with large garlands, carved in stone, was the *papal mint*.

A little way behind the castle, passing into the *Rue Peirollerie*, under a huge flying buttress, which supports the castle wall, and leaving on the rt. an ancient building, once the residence of the Podestat or Governor of Avignon, we reach the *church of St. Pierre*, having a richly florid front, built 1512, nearly in the Perpendicular style, but mutilated. It contains a stone pulpit, carved and surrounded by little statues, in canopied niches. Scarcely any other of the numerous churches here deserve notice; but to give an idea how completely ecclesiastical Avignon was before the Revolution, we may mention that it

contained 8 chapters, 35 convents of both sexes, 10 hospitals, 7 fraternities of penitents, 3 seminaries, a university, and 60 churches, of which 18 now remain:  $\frac{1}{3}$  of its population were dedicated to the church, and it possessed between 200 and 300 towers and spires. Rabelais, in consequence of the number of bells, called it "*La Ville sonnante*."

The *Place de l'Horloge* is overlooked by the clock-tower, or belfry, called *Jacquemart*, from the figure in armour, who strikes the hours, attached to a semi-Gothic edifice, originally a palace of the Colonna family. Here are situated the principal cafés and the theatre.

In the *Rue Calade* is situated the *Musée*, founded by Calvet, a native of Avignon. Its collections are of considerable interest. The Roman antiquities found in the neighbourhood are numerous, though few are derived from Avignon itself, the ancient *Avenio*. Several large monuments, carved in high relief, have been brought from *Vaison* near Orange (p. 452), among them a chariot carrying 2 persons, and a driver drawn by Horses harnessed with Traces, and shod (this use of horse-shoes has been attributed to later times); another represents the Sacrifice of a Bull (? Mithraic). They are overladen with ornament, and in the debased style of the Lower Empire. An amphora or wine jar, 5 ft. high, and 8 or 10 in circumference, deserves notice for its size.

In the upper rooms are a large collection of antique bronzes, arms, utensils, &c., found in Provence and the *Comtat Venaissin*, in fine preservation: some of them have a Greek character. Among them is the Head of a Roman Standard (the Eagle of a Legion?), and a Head of Jupiter, cut in agate. The collection of Roman glass is large and perfect. Many of these objects were obtained from the Roman town *Vaison* by excavations in 1838—1840. There are 2 perfect Egyptian paintings on papyrus, and



other Egyptian antiquities. The coins and medals amount to 14,000 : among them is a suit of Papal medals struck at Avignon ; also the seals of the Popes and their Legates, and the last seal used by the *Inquisition* here.

In the *Picture Gallery*, besides many early paintings of the 15th and 16th centuries, which seem to have been retouched, there are 2 portraits attributed to *Holbein* ; another head, like John Knox, 1535, in an oval ; and a Holy Family of the Milanese school. A Crucifixion, by *Eckhout*, is not unworthy of Rembrandt, and is, perhaps, the best picture in the gallery. There are paintings by the 3 *Vernets* : by *Joseph*, who was a native of Avignon, one of his best landscapes ; by *Carl*, several landscapes ; and by *Horace* (whose bust, by Thorwaldsen, is placed in the room), Mazeppa on the Wild Horse. Many of old *Vernet's* sketches for the views of French sea-ports in the Louvre exist here.

The *library* amounts to 42,000 vols. derived from suppressed convents in the town ; it includes 700 MSS. and many early printed editions of the 15th century.

In the same street, further on, is the Gothic church of *St. Martial*, remarkable for the elegant florid windows at its E. end, in one of which the tracery assumes the form of the fleur-de-lis.

The large Benedictine convent adjoining it has been converted into a *Museum of Natural History*. In this collection may be seen specimens of the *flamingo* caught in the delta of the Rhône, where it frequents the ponds (étangs) of the Camargue. (See p. 468.) It is stated to be a permanent inhabitant of that part of France, forming a nest of mud, in the form of a truncated cone, on which it sits over its eggs, with its long legs dangling down on the outside. The bird does not assume its red plumage until it is 2 years old.

Here is the *beaver* of the Rhône, an animal now nearly exterminated, since the late inundations drove most *France*.

of them from their retired haunts. Its colour is tawny, and its hair harsh compared with the American beaver. It does not build houses, nor lay up stores in Europe, but burrows in the dykes or river bed, and feeds on willows or other brushwood, whole plantations of which are often laid prostrate by its sharp teeth. Here are collections of the minerals and fossils of the Dépt. de Vaucluse ; also of fossil insects and fishes from Aix. The museum has been enriched by the splendid bequest of M. Riquet, and the whole appears well arranged. Behind is the *botanic garden*.

Continuing in the same direction, as far as Rue des Lices (No. 8), a street abounding with dyers and tanners, at the back of the Maison des Orphelins, a charitable institution for the education of 50 poor children, we shall find the last relic of the *church of the Cordeliers*, in which Petrarch's Laura, a married lady of the family De Sade in Avignon, was buried. The church, destroyed at the Revolution, is now reduced to a fragment of the tower and side walls, sold probably for the value of the materials, but not worth pulling down.

*Laura's tomb*, described by Arthur Young as " nothing but a stone in the pavement, with a figure engraved on it, partly effaced, surrounded by an inscription in Gothic letters, and another on the wall adjoining, with the armorial bearings of the family de Sade," has entirely disappeared, having been broken open, and the contents of the tomb, as well as that of the brave Crillon, scattered by the Revolutionists. In a sort of tea-garden behind the fragment of the church, a vulgar, tasteless monument has been raised to Laura, bearing the pompous inscription, " Hunc cippum posuit Carolus Kelsall Anglicus." Petrarch has recorded that he first saw Laura in the church of St. Claire, 1327, in the time of his early youth.

In this church of the Cordeliers, June 1791, the mob of Avignon, irritated at the tyranny, spoliations, and

sacrilegious acts of the democratic municipality, put to death its agent and secretary Lescuyère: the chief actors in this deed of blood were women, who actually tore out his eyes with their scissors.

Behind the church and convent of St. Martial is the *Hôtel des Invalides*, subordinate to, and dependent on, that of Paris, founded for old soldiers, after the expulsion of the French from Egypt. It occupies the buildings of 2 suppressed convents, between which a park extends. The upper part of a *chapel*, in the roof of which are traces of fresco, serves as the *Lingerie*. The establishment is furnished with a good library for the use of the inmates.

A *crucifix* of ivory, 26 inches high, executed by one Guillermin, according to the story, to save his nephew from execution, and preserved in the chapel of the Hospice des Insensés, is much vaunted in the guide-books; but is not, after all, of high merit.

*Steamers*, 2 daily to Lyons in the morning; 2 to Arles in the afternoon.

*Railway* to Marseilles. (Rte. 129.)

*Diligences*, daily, 3 or 4 to Marseilles; to Nismes 3 (in 4 hours); to Arles twice a-day; to Lyons and Paris 4 daily; to Narbonne and Toulouse.

Rt. Opposite to Avignon, on the rt. bank of the Rhône, at the extremity of the wooden bridge, stands Villeneuve-lès-Avignon, an ancient town of 4000 inhab., which was much encouraged by the kings of France, as a border-fortress, on the frontier of Languedoc, confronting the foreign territory of the Pope, on the opposite shore of Provence. It contains several objects of curiosity. In the chapel of the *Hôpital* is placed the elegant Gothic *tomb of Pope Innocent VI.*, composed of tabernacle work, and niches beautifully carved, though much mutilated. It has recently been removed from the ruined convent of the Chartreuse, and carefully restored. In the same hospital is preserved a curious painting of the *Last*

*Judgment*, an ancient work of the 15th century, of good design; the heads of careful execution, but much injured. It is in water-colours (? distemper), varnished, and is attributed, but with slight probability, to *King René, Duc d'Anjou*.

In the *Gothic Ch.*, a heavy building of the 14th cent., there is a Descent from the Cross, attributed to *Bellini*.

The ruins of the Gothic *Church* of the *Chartreuse*, and the tower which formed the *Tête du Pont* of the broken bridge of St. Benazet, faced with stones cut in diamond facettes, built by Philippe le Bel, also merit notice. The *Fort St. André*, on an elevated platform above the town, is a nearly unaltered citadel of feudal times.

The climate of Avignon is described in the proverbial line, "Avenio ventosa, sine vento venenosa, cum vento fastidiosa."

The following very interesting *excursions* may be made from Avignon:—a. To Vaucluse; b. To the Pont du Gard, on the way to Nismes (R. 126); on no account to be omitted: either of these may be seen in one day from Avignon. The traveller should not return to Avignon from the P. du G., but by all means go on to Nismes. c. To Orange, on the way to Lyons (p. 451); d. To St. Remy (p. 463); e. To Carpentras. The Roman remains of Nismes (p. 470) and Arles (p. 464), more distant from Avignon, are scarcely inferior in interest to any in Italy.

a. To *Vaucluse*. 29 kilom. = 18 Eng. m.

A carriage with 2 horses costs 18 or 20 fr. to go and return; the excursion will take about 8 or 10 hours.

It is incumbent upon all travellers to perform this "sentimental journey," not only on account of Petrarch and Laura, but because Vaucluse itself is a striking scene. You quit Avignon by the *Porte St. Lazare*, traverse long avenues of willows and poplars, leaving on either hand nu-



merous country-houses, each fronted with an avenue of planes; and, after crossing the *Canal de Crillon*, which conducts the waters of the Durance to fertilise the fields of madder around Avignon (R. 128), reach the village of Le Thor, so named from a *bull*, which, by constantly falling on its knees, when brought to water on the margin of a pond, led to the discovery of a miraculous image of the Virgin, which was fished out of the mud, and deposited in the *Church of St. Marie du Lac*! This is an ancient and curious Romanesque building; its W. doorway resembles that of Nôtre Dame des Don's, and is probably of the 11th cent.; an ornamented portal at the E. end is rather later. The country is dreary as far as

22 L'Isle (*Inns*: H. du Petrarque et Laure; not very good, and dear; —Poste; better), a town of 5000 inhab., 12 m. from Avignon, on an *island* surrounded by branches of the Sorgues, whose waters, employed in irrigation, spread fertility and verdure around. This is a green oasis in the desert, affording bubbling streams and grateful shade. There is a road from L'Isle to Carpentras. (See p. 460.)

The valley of the Sorgues, whose course we trace hence upwards, is excavated in a mountain-chain, branching from the lofty Mont Ventoux. Near its head lies the little village

7 *Vaucluse*.—*Inn*: H. de Laure; small, and not very clean. The landlord is a capital cook, and, judging from the Strangers' Book—a singular record of frivolous sentiment and selfish “gourmandise,”—his fried trout and eels, soupe à la bisque, and coquille d'écrevisse, have made a far deeper and more lasting impression on his visitors than the souvenir of Laura; and indeed they are not to be despised; even Petrarch himself has mentioned the fish of the Sorgues with praise. Close to the village stands a tasteless *monument* to Petrarch, which the Academy of Avignon planted at the mouth of the

grotto itself, whence it was judiciously removed by order of the Duchesse d'Angoulême, when she visited the spot. A path leads from the village to the fountain by the side of the Sorgues, whose exquisitely limpid waters are dried up near the head, in summer, and, instead of bursting out exuberantly from the cavern, filtrate underground, and issue out, some hundred yards lower down, in numerous streamlets, out of holes in the limestone rock.

The *valley of Vaucluse* (vallis clausa) is a complete cul de sac, a semicircular excavation in the side of a mountain, which seems to have been split from top to bottom, so as to disclose the secret storehouse of water within it, whence the sparkling Sorgues derives its supplies. All around rise walls of rock from 500 to 600 ft. high, intermixed with bristling pyramids, arid, destitute of verdure, and glaringly white. The sides and bottom are strewn with broken fragments of stone, which, where the Sorgues rolls over them, are covered with a luxuriant mantle of green moss. It is a desolate and arid scene. On a ledge half-way up, to the rt., is perched a ruined *castle*, which belonged to the bishops of Cavaillon, one of whom, the Cardinal de Cabassole, was Petrarch's friend. Though popularly known as Petrarch's Castle, it never belonged either to him or to Laura; but the site of his house is pointed out between the castle and the village. Here, beside a natural grotto in the rock, mentioned in his letters, one of the gardens which he formed with so much care was probably situated.

At the extremity of this majestic recess, at the base of the precipice, yawns the cavern which contains the *fountain of Vaucluse*. According to the season, and the abundance of the water, it presents alternately a gushing cataract, tumbling over the moss-clad stones, from step to step, or a quiet, pellucid, dark-blue pool, sunken within its grotto, so that you may

enter under the vault beside it, and, gazing into its funnel-shaped basin, watch the stones which are thrown in gradually descend into its fathomless depths. A wild fig-tree, springing from a crevice in the face of the rock, above the natural vault, marks, with its roots, the height which the waters attain when they fill the cave.

Around this spot must have been the other garden mentioned by Petrarch in his letters; that consecrated to Apollo, adapted to study, "where art surpasses nature."

It is more agreeable to contemplate Petrarch in these haunts, as the laborious student retired from the world, than as the mawkish lover, sighing for a married mistress, and converted, as in the sentimental verses of Delille, into a sort of Italian Werther. Listen to his own account of his occupations at Vaucluse.

"The Sorgues, transparent as crystal, rolls over its emerald bed; and by its bank I cultivate a little sterile and stony spot, which I have destined to the Muses; but the jealous Nymphs dispute the possession of it with me; they destroy, in the spring, the labours of my summer. I had conquered from them a little meadow, and had not enjoyed it long, when, upon my return from a journey into Italy, I found that they had robbed me of all my possession. But I was not to be discouraged; I collected the labourers, the fishermen, and the shepherds, and raised a rampart against the Nymphs; and there we raised an altar to the Muses; but, alas! experience has proved that it is in vain to battle with the elements. I no longer dispute with the Sorgues a part of its bed; the Nymphs have gained the victory.

"Here I please myself with my little gardens and my narrow dwelling. I want nothing, and look for no favours from fortune. If you come to me, you will see a solitary, who wanders in the meadows, the fields, the forests, and the mountains, resting on the mossy grottoes, or beneath the shady trees. Your friend detests the

intrigues of court, the tumult of cities, and flies from the abodes of pageantry and pride.—Equally removed from joy or sadness, he passes his days in the most profound calm, happy to have the Muses for his companions, and the song of birds and the murmur of the stream for his serenade. . . . I have few servants, but many books. Sometimes you will find me seated upon the bank of the river, sometimes stretched upon the yielding grass: and, enviable power! I have all my hours at my own disposal, for it is rarely that I see any one. Above all things, I delight to taste the sweets of leisure."

e. *Carpentras*. 23 kilom. = 14 Eng. m., and the *Mont Ventoux*.

The road thither from Avignon lies through Entraigues and Monteux, crossing the Sorgues, here as limpid as at Vaucluse, between the two villages. The country around Carpentras is a fertile plain, which, by means of irrigation, and of a southern sun, produces crops of all kinds in abundance.

23 Carpentras is a flourishing town of 10,000 inhab., still retaining, like most of those in the old Papal territory (the Comtat Venaissin), its feudal walls, towers, and gates; the *Porte d'Orange* being particularly perfect and stately. It was an important Roman station; but almost the only relic of that people remaining is an *Arch of Triumph*, formerly built up into the bishop's palace, and serving as his kitchen, but recently set free from that degradation, and detached from the buildings surrounding it. It is a ruin, reduced to the mere stone vault, without the attic, resting on the side piers. Upon these are curious sculptures in relief, representing Barbarian Captives, their hands bound behind their backs to trophies. Nothing is known of the date or destination of this arch; but it is doubtless a work of the Lower Empire.

The *cathedral*, rebuilt 1405, has a



tower attached to it of the 10th century, and contains a nail of the Cross, made into a bit, and used for that purpose by Constantine, if we may believe the tradition.

There is a *musée* here containing antiquities, and a public library of 12,000 volumes and 700 MSS.

The *aqueduct* of Carpentras, a massive structure of 48 arches, was finished 1734.

The ascent of the *Mont Ventoux* may be made from Carpentras by way of Malaucène, whence it is 6 m. distant. Its top, reached by Petrarch in 1345, is 6,427 ft. above the sea level, and is covered for half the year with snow, which supplies the Dépt. with ice in summer. The view from it includes a portion of the chain of the Alps, the Cevennes, the Coiron, the course of the Rhône and Durance, and, it is said, extends to the Mediterranean. At the foot of the mountain stands *Bedouin*, a miserable village rising from amidst the blackened ruins of a former village destroyed at the Revolution. There is no darker spot in the black history of that period than the burning of Bedouin and the massacre of its inhabitants by the revolutionary committee. Their agent, the apostate priest Maignet, directed this atrocious crime, and Suchet, afterwards so eminent a general, with his soldiers, carried it into execution, setting fire to the houses, blowing up the public buildings, hurrying the peaceful inhabitants to the scaffold, and picking off with musketry those who tried to escape, until 180 had perished. And these horrors were enacted, not in a hostile country and in time of war, but upon fellow-countrymen, women, and children, Frenchmen being the executioners; and all because a tree of liberty planted within the parish had been sawn through in the night.

*Descent of the Rhône continued:—  
Avignon to Arles.*

The Rhône opposite Avignon always belonged to the King of France,

even when its l. bank formed the territory of the Pope, and, in consequence, during an inundation of the river, which had laid a quarter of the town under water, the royal bailiff entered the streets in a boat, and claimed all those parts which the river had occupied, for his master.

L. Within  $2\frac{1}{2}$  m. of Avignon, the Rhône is joined by the Durance, a turbulent and injurious stream, part of whose course is described in R. 128.

The course of the Rhône below this possesses very little interest. The high road to Arles is equally uninteresting, but more direct than the river: traversing at first a country rendered fertile by irrigation, it crosses the Durance, at a distance of  $1\frac{1}{2}$  m. from Avignon, by a very long suspension bridge, rendered necessary by the broad bed of gravel, not half of which is occupied by the wild river, except in times of flood.

L. At Barbantane there are extensive quarries.

L. A low ridge of hills, called *Alpines*, remarkable for their utter nakedness, now approaches the Rhône, running from E. to W. In the distance, upon their flanks, the white houses of St. Remy, and its 2 Roman monuments, may be distinguished.

Rt. Aramon is a town of 2800 inhab.: and a little below it the river Gardon, which gives its name to the Dépt., flows into the Rhône.

A wire bridge, suspended from 4 piers, 1,446 ft. long, over which the high road from Marseilles to Nismes and Narbonne passes (R. 126, 127), connects

L. Tarascon, whose massive square castle at the water-side is overtopped by the spire of its Gothic church behind, with

Rt. Beaucaire, lying at the base of cliffs of bare rock, one of them surmounted by a Calvary, the other by a ruined castle. The bridge was erected in 6 months in 1829 by M. Seguin, of Lyons, at a cost of 600,000*l*.

Passengers disembark or go on

board the steamer from a pier descending from the bridge.

L.\* *Tarascon* (*Inn*: H. des Empereurs, close to the bridge; not recommended—*G. B.*) is a town of about 11,000 inhab. Etymologists have been bold enough to derive its name from the Greek *ταράσσω*, disturb, connecting it with the tradition of a dragon called *Tarasque*, which, once upon a time, infested the borders of the Rhône, preying upon human flesh, to the great terror and disturbance of the inhabitants. They were at length delivered from the pest by St. Martha, sister of Lazarus, since adopted as the patron saint of the town, who conquered the monster with no other weapon than the Cross, and made him a prisoner with her girdle. This deliverance was commemorated until within a few years by a procession of mummers, attended by the clergy, who paraded the town, escorting the figure of a dragon, made of canvas, and wielding a huge beam of wood by way of a tail, to the imminent danger of the legs of all who approached. The ceremony was attended by numerous practical jokes, and led to acts of violence, in consequence of which it has been suppressed. The effigy of the dragon now slumbers in the lumber-room of the playhouse.

The *Ch. of St. Martha* is a pointed Gothic building of the 14th century, with the exception of the S. portal, which is circular and recessed with deep mouldings; between these the dog-tooth ornament appears: it dates from 1187. In a crypt beneath the nave of the church is the shrine and tomb of St. Martha, ornamented with her reclining effigy of white marble, not badly executed, but modern. Against the walls the history of Martha is represented in a series of bas-reliefs. Here also is the tomb of a Neapolitan knight, a follower of Roi René, and a well in the floor, the water of which is said to rise and fall with the Rhône.

\* *Post road.*—23 Tarascon.

The picturesque *Castle*, remarkable for its massive construction and perfect preservation, was begun by Henri II. in 1400, and finished by King René of Anjou, who frequently resided here, spending his time in festivities and fêtes, during one of which he and his queen appeared in the attire of shepherd and shepherdess: it is now a prison, and contains nothing remarkable.

The road from Tarascon to Marseilles and Nismes is in R. 127 and 129.

Rt. *Beaucaire* (*Inn*: H. du Luxembourg), though it contains only 9967 inhabit., is a town of more life than its opposite neighbour Tarascon. It stands at the mouth of the Canal de Beaucaire, which joins the Canal du Midi, and thus unites the Rhône and Garonne, and it is the terminus of the Railway to Nismes and Alais (R. 127). It is, besides, the locality of the celebrated fair, held here every year between the 1st and 28th of July, on the wide space of ground, planted with rows of trees, extending between the Rhône and the castle rock. This space is then covered with booths and sheds, arranged in streets, forming a sort of supplemental town of wood and canvas, within which the various kinds of merchandise are deposited, each classed by itself. The shore is lined by a flotilla of barges, the roads are choked with waggons, and the inns are filled to overflowing. Though somewhat fallen off of late, this fair collects together about 100,000 persons, and is attended by merchants not only from all parts of France, Spain, Italy, Portugal, but by many Jews, Turks, Armenians, Greeks, and even Moors from Barbary, who sell dates, &c. It terminates July 28, at midnight. It is said to date as far back as 1168.

The *Castle*, standing on the top of an escarped rock, was an ancient possession of the Counts of Toulouse, and was recovered by Count Raymond VII., when only 19 years of age, from the usurping Simon de



Montfort and his sons, after a long and memorable siege (1216), in which he, besieging the garrison, was himself surrounded by an army from without. It is now reduced to a complete ruin; one stately triangular tower, and a curious Romanesque *chapel* of great antiquity, in which St. Louis is said to have heard mass before he embarked for the Crusade, alone surmounting the crumbling walls. There is a good view, from the castle rock, of the Rhône, the bridge, the scene of the fair, the distant arid range of the Alpines on the opposite side of the river, and the equally naked hills of the Calvary and gallows (*fourche patibulaire*) on this side; but verdure is wanting. The rock, which serves as the pedestal to the castle, is being cut through, to allow the passage of a road to the Rhône.

Beaucaire is the scene of the old Provençal romance of Aucassin and Nicolette.

St. Gilles (see p. 475) is about 15 m. distant.

From Tarascon an excursion may be made to *St. Remy* (10 m.), a deserted town, remarkable only for two well-preserved Roman buildings, detached from all others, and about  $\frac{3}{4}$  m. from the town: the one is a funereal *Monument*, of most elegant design, about 50 ft. high, ornamented on its square base with bas-reliefs. On the N. side is a Skirmish of Cavalry; on the W. a Combat of Infantry; on the S. the Sacrifices and Erection of Trophies after a Battle; on the E. a winged Victory supporting a wounded Soldier: above this rises a double arch with engaged columns in the angles, and the whole is surmounted by a circular temple enclosing 2 statues. It bears this inscription, which throws no light on its date:—

SEX.L.M.JVLIEL.C.F.PARENTIBVS.SVEIS.

The *Arch of Triumph*, standing within a few yards of it, is less perfect, having lost its upper story, but the stones of its vaults remain, beautifully

carved in hexagonal compartments, or sunk panels. Much of the sculpture has perished; the bas-reliefs remaining represent captives, bound, with women beside them. The date of this monument is as little known as that of the former: it has been supposed to commemorate the victories of Marc Aurelius. St. Remy was the ancient *Glanum*: it stands on the slope of the naked Alpines, and one of the limestone crests near the town is pierced through and through by a natural orifice. St. Remy was the birth-place of Nostradamus (1503), the astrologer and fortune-teller.

Orgon, on the road to Marseilles, is about 10 m. from St. Remy (R. 128).

Rt., close to the bridge of Beaucaire, is the mouth of the canal joining the Rhône to the Canal du Midi. The plain around was overwhelmed by débris, brought down by the Rhône, which broke its banks hereabouts during the inundation of 1840. This irruption, covering the low grounds, destroyed the crops, but has left behind a deep deposit of mud over much waste land, which it is hoped may produce permanent fertility.

L. The country between Tarascon and Arles is a flat and uninteresting alluvial marshy plain, intersected by ditches, and the olive here gives place to the willow.

L. A little on the l. of the road, about 2 m. from Arles, a singular rock rises, like an island, above a marshy pond, crowned with the ruins of the once celebrated *abbey of Montmajeur*, founded in the 10th century, and continued down to the 18th. Of the latter period are the vast palatial constructions of Italian architecture, which formed the convent, now rapidly falling to pieces. The *church* is partly Romanesque, partly Pointed; but beneath it is a vast *crypt*, of the 11th century, running under nearly the whole upper church. Behind the altar of this crypt stretches a

semicircular wall, pierced with windows so as to render the altar visible from the side-chapels. Attached to the church is a ruined *cloister*, in which 2 mutilated monumental effigies remain of princes of the house of Anjou.

At the foot of the rock, on the N. E., is the very curious *chapel of Sainte Croix*, consisting of a central square tower, from which project 4 equal semicircular apses, that on the W. having a porch attached. It is in the Romanesque style, but destitute of all ornament. It is proved by records to have been dedicated by Pons de Marignan, Bishop of Arles, in 1019. An *inscription*, forged by the monks of Montmajour at a comparatively late period, attributed its origin to Charlemagne, to commemorate a victory here gained over the Saracens. Down to 1789 this chapel was resorted to every year, on the festival of the Discovery of the True Cross, by infinite multitudes of pilgrims, anxious to reap the advantages promised by papal indulgence to all who then flocked hither. The rock on which the chapel is built is honey-combed with tombs of all sizes excavated in it: some are said to have been the last resting place of early Christians.

L. The Rhône first forks off into 2 branches, forming the head of its delta, about a mile to the N. of Arles. The branch which it sends off to the W., called Petit Rhône, is crossed by a wire suspension bridge at the village Fourques.

L.\*ARLES.—*Inns*: H. du Nord, in the Place du Forum; improved (E. o. S.) and tolerably comfortable; —H. du Forum, good; Gauthier, who keeps it, was cook to Lord Salisbury; —H. du Commerce, on the Quai; kept by the wife of one of the English engineers on the steamboats.

Arles, one of the most ancient, and once the most important city in France, the Rome of Gaul ("Gal-

lula Roma Arelas," as Ausonius calls it), the residence of a Roman Prefect, and, after the fall of the Roman Empire (A. D. 876), the capital of the kingdom of Arles, or of Trans-Jurane Burgundy, is now shrunk up into a dull provincial town. It is, however, rich in ancient remains of the period of its greatness; and the stranger who succeeds in threading its labyrinth of dirty narrow streets, more intricate than any other perhaps in France, will be duly rewarded, if he takes an interest in antiquities. Arles is justly celebrated for the beauty of its women.

It is a sea-port town of 19,406 inhab. (but its population is on the decrease), standing on the l. bank of the Rhône, near the apex of its delta, about 23 m. from the sea. The river bank is lined by a quay, at which may be seen moored a number of heavy barges, with one mast and a very long yard, and a prow not unlike that of the antique galleys. A *bridge of boats* unites the town with its suburb

Rt. Trinquetaille, and supplies the place of an old bridge, over which passed the Aurelian Way, extending from Rome to Cadiz,

Per quem Romani commercia suscipis orbis, to use the words of Ausonius, in his description of Arles.

The most interesting ancient monuments existing at Arles are,

1. *The Amphitheatre*, a magnificent and most interesting relic of former days, larger than that of Nîmes (measuring 459 feet by 338 feet, having 5 corridors and 43 rows of seats, and capable of holding 25,000 spectators), but by no means so well preserved, owing to the devastations of human hands, rather than those of time. It consists of 2 stories of 60 arches, the lower Doric, the upper Corinthian, both rude in style, and of most massive construction, formed of enormous blocks, very exactly fitted together. Owing to the unevenness of the ground, it is supported on one,

\* Post road.—15 Arles.



side by vast substructions. The outer wall is now nearly separated from the second by the removal of the vaults, and the interior is completely gutted. Yet the lower portion, including the podium, or parapet surrounding the arena, faced with marble slabs, is even more perfect than at Nismes, having been covered up with earth until within a few years. Scarcely 12 years have elapsed since this building was entirely filled within and choked up without by an accumulation of mean hovels, occupied by the poorest and worst part of the population of the town, to the number of 2000, part of whom burrowed under the vaults, or nestled in its recesses, reminding one of the fungi and parasites springing up over the trunk of some venerable monarch of the forest. One of these houses is still allowed to remain, to give an idea of the former condition of the amphitheatre. Another excrescence, not forming part of the original structure, are the two *square towers* surmounting the entire edifice. But they are interesting historical relics, having been raised in the 8th century, either by the Saracens, who, under Jussouf-Ben-Abdelrahman, Wali of Narbonne, then obtained possession of Arles, or by Charles Martel, who expelled them from the city, 739. At all events the amphitheatre, like the Coliseum of Rome, was at that period converted into a fortress, and withstood sieges and assaults, while 4 towers of defence were erected at the 4 cardinal points. From the top of the loftiest remaining tower the best view is obtained of the amphitheatre, and of the city of Arles, of the course of the Rhône upwards to Beaucaire, of the distant outline of the Alpines, and Mont Ventoux, and of the plain of the Crau: the sea is not visible.

The stranger will not fail to remark the beauty of the masonry of the amphitheatre, the arches sometimes turned flat, of small stones, sometimes replaced by huge single beams of

stone. The vaulted chambers communicating with the arena are supposed to have been the dens for wild beasts. The very scanty traces of inscriptions remaining on this building throw no light on its date, but it is supposed to be older than the arènes of Nismes, and is attributed to the age of Titus.

The *Roman Theatre*, more recently disinterred from the earth than even the amphitheatre, has suffered equal if not greater dilapidations in the course of ages. It is said to have been demolished by order of the early Christian bishops, who regarded it as the focus of idolatry and vice. Although reduced to a mere fragment, the costly marbles, the columns, the sculptured friezes (some preserved in the museum), and the statues found in it, one of which, called the *Vénus d'Arles*, forms an ornament to the Louvre, attest its ancient magnificence. The portions remaining are two Corinthian columns, surmounted by part of their entablature, which stand isolated like those in the forum of Rome; they formed part of the Proscenium, the rest of which is reduced to the pedestals of other pillars on a line with these, to truncated walls pierced by openings for doors, by which the actors made their entrance and exit, and furnished with niches for statues. Opposite to this wall is the semicircular space destined for the audience, scooped out of the rock, and still retaining some of its stone seats, rising in steps one above the other. In the middle are some very curious substructions, attached apparently to the orchestra, consisting of 3 parallel walls, 6 or 8 feet high, stretching quite across the building, leaving a space of about 1 foot between them, which is set with grooved ridges projecting alternately from either wall at regular distances. Within these was probably placed the wooden support of the proscenium or pulpitum, the stage in fact. It is difficult to explain the uses of this

very peculiar construction. Near the theatre there is a very beautiful *Doric gateway*, or arch, with both frieze and architrave richly sculptured.

In the midst of the *Place Royale*, or de l'Hôtel de Ville, in which are situated the church of St. Trophime, the Hôtel de Ville, and the museum, rises an *Obelisk* of a single shaft of grey granite, antique, but not Egyptian, since it is ascertained to have been brought from a quarry in the Estrelle mountains, near Fréjus: and it differs in shape from those of Egypt, tapering more rapidly from its base to its summit. After having been for centuries prostrate in the mud of the Rhône, it was elevated in its present position in 1676. It is supported on 4 lions, and surmounted by a very tasteless gilt sun, set off with eyes, cheeks, and mouth. It is supposed to have stood upon the spina in an ancient circus, all traces of which are gone; it is 47 ft. high (the Luxor obelisk is 72 ft.), and is destitute of inscription or hieroglyph.

The *Museum* occupies the suppressed church of St. Anne; it is filled with an interesting collection of ancient remains discovered in or near Arles, a large proportion in the theatre, including a very rich marble frieze, and numerous statues, whose merit as works of art is small, except a head of a female (? Diana, or the Empress Livia) without a nose, and a head of Augustus found in 1834, belonging to a torso previously sent to the Louvre, both very fine. An altar to Apollo bears representations of the Delphic Tripod and of Marsyas flayed alive. A leaden pipe, more than 40 ft. long, stamped with the name of the Roman plumber, was discovered in the bed of the Rhône, and is supposed to have conveyed fresh water to the opposite bank. The cemetery called Aliscamps (p. 467) has furnished a great number of sarcophagi, some pagan, but the majority Christian,

ornamented with bas-reliefs of good design and execution, showing that Roman art survived long after the extinction of paganism, though the subjects on which it was exercised were taken from the Bible. Those most commonly represented are Adam and Eve, the Deluge, the Passage of the Red Sea, Moses striking the Rock, Jonah and the Whale, the Sacrifice of Isaac, &c. On one is seen the Oil Press and Olive Harvest. A mutilated statue of the god Mithras, wanting the feet and head, is very curious. It is a human body entwined by a serpent, between whose folds the signs of the zodiac are sculptured.

The *cathedral of St. Trophimus*, who is said to have been a disciple of St. Paul, and to have first planted the Cross here, is entered from the Place by a very curious projecting porch, constructed in the 12th or early in the 13th centy. It consists of a deeply recessed semicircular arch, with mouldings not unlike our late Norman, resting upon a horizontal sculptured frieze which forms the lintel of the door, and is continued from beneath the arch on the rt. and l. of the façade, supported on pillars. There are 6 of these pillars, round, square, and octagonal, on either side of the door, of stone, resembling metal in colour, and one in the middle of the door forms the support of the lintel. They are based upon carved lions, some of them devouring men. Between the pillars are statues of Apostles and Saints, those in the angles being St. Trophimus and St. Stephen. The tympanum over the door is occupied by the figure of the Saviour as Judge of the World with the attributes of the 4 Evangelists; and the sculptured frieze below represents in the centre the 12 Apostles, and on the sides the Last Judgment; the Good being on the l. of the spectator, the Bad, bound by a rope and dragged by devils, on the rt. The



arehivolt is filled with the Heavenly Host in the shape of rows of cherubims.

The interior is modernized, and less interesting; it contains 3 antique sculptured sarcophagi, one of which serves as a font.

The *cloisters* on the S. side are very curious; two of the sides have round arches, and two pointed, resting on double shafts, or square piers carved on the sides with figures of saints, and projecting towards the courtyard in the form of fluted Corinthian pilasters. The capitals of the pillars are very curiously but rudely sculptured, in part with Scripture groups.

The square tower is also ancient, and in its upper story Corinthian pilasters again appear.

The *Hôtel de Ville* was built 1673, from designs of *Mansard*, contiguous to the clock-tower, which is somewhat older. It contains a collection of natural history.

Besides the more important Roman remains already described, there are, within the town, in the *Place du Forum*, 2 granite pillars and part of a Corinthian pediment, let into the wall in front of the *Hôtel du Nord*; they are supposed to have been moved, from some building now destroyed, into their present position. Other constructions, which may have belonged to the *forum*, are known to exist beneath the houses. In a narrow street near the *Rhône* is a tower of brick, called *Tour de la Trouille*, supposed to have been built by Constantine the Great, who resided much at Arles, and whose eldest son was born here.

Beyond the walls, to the E. of the town, is situated the ancient Cemetery of Arles, still called *Aliscamps*, a slight variation from the original name (*Elisii Campi*) by which it was known 18 centuries ago. It was of vast extent, a complete Necropolis, and the dead were brought hither from other cities, as far distant as Lyons, for interment. *Dante* mentions it in the *Inferno*, IX. 112:

“ Si come ad Arli ove 'l Rodano stagna,  
Fanno i sepolcri tutto 'l loco varo.”

And Ariosto alludes to it in the *Orlando Furioso*:

“ Piena di sepolture è la campagna.”

One portion of the ground was used for burials in pagan times; another, marked off with crosses, was afterwards designated for the interment of Christians. The ground teems with gravestones, sepulchral memorials, and sarcophagi, but the most curious have been removed to the museums of Arles, Toulouse, Marseilles, &c. In the neighbouring farms the cattle drink out of stone troughs which are nothing but empty coffins; and with their lids the ditches are bridged. Several chapels were erected within the area of this vast churchyard: the most remarkable is that of *St. Honorat* or of *Nôtre Dame de Grace*, now falling to ruin. It is surmounted by an elegant octagonal tower, of two stories, having 2 circular-headed windows in each face; the interior, except the crypt, is not older than the 14th century.

The ecclesiastical constructions of the middle ages on the *Montmajeur* are described at p. 464.

Although, in the days of the Romans, Arles was plentifully supplied with spring water, conveyed to it from the chain of the Alpines in aqueducts of masonry many miles long, the modern town is destitute of this important commodity, and the inhabitants suffer severely from the want of drinking water. Owing to the marshes and pools in the vicinity, the town and the district around Arles are unhealthy at certain seasons; and intermitting fevers are very prevalent, but less so now than formerly, in consequence of the extended drainage.

A *Canal* has been formed from Arles to Boue, on the sea-coast, at the mouth of the salt lake called *Etang de Berre*, which opens a more direct communication to Marseilles

than the course of the Rhône. This canal, begun 1802, with the double object of draining the marshes on the l. bank of the Rhône, and of facilitating traffic by avoiding the bars and sandbanks at the mouth of the river, was not completed until 1835. It is about 30 m. long. It was traversed regularly by barges until 1840, when the great inundation of the Rhône overwhelmed a part of it with sand.

A *steamboat* plies between Arles and Marseilles; but the navigation at the mouth of the Rhône is intricate, and there is little accommodation for passengers on board. Another account says that the voyage is very agreeable. *Steamers* daily to Avignon and Lyons, but the ascent to Lyons takes 3 or 4 days.

*Diligences* daily to Marseilles, to Nismes, to Narbonne, and to Avignon.

*Railway* to Marseilles, Rte. 129.

The wide uninterrupted plain stretching from Arles to the sea, S. and E., nearly as far as Marseilles, including the *delta* of the Rhône, or the island of *Camargue* (derived from *Καμαζ*, marsh, and *αγρος*, field?), presents some singular phenomena not unworthy of attention. Indeed, both its climate and its soil of mud banks, arid sand, or vast bare gravel beds, alternating with salt marshes and lagoons, raised from 2 to 7 feet above the sea, assimilate it rather to Africa and the borders of the Nile than to France. Even some of the animals which resort to it, the ibis, the pelican, and the flamingo, properly belong to the African continent. (See p. 457.) The ground is so impregnated with salt, that the water is brackish; the surface of the soil is, in summer, covered with a white saline efflorescence, like a coating of snow, and, when the pools are dried up, the salt forms in a cake 2 inches thick. Here, as in the deserts of Asia and Africa, the *mirage* constantly occurs during the heats, transforming the arid plain in appearance into a wide lake. Cultivation can only be pursued by excluding the sea by dykes, which entirely

surround the Camargue, and the saline influence is counteracted by covering the surface with the muddy deposits brought down by the Rhône. In this manner the district produces extensive pastures, on which large flocks of sheep are fed, together with herds of small cattle, and wild horses or rather ponies, said to be of a stock originally brought from Africa by the Arabs, in their frequent invasions of this part of France. At stated times the young bulls are chased and separated from the herd by horsemen armed with tridents, in order to be branded, and receive the marks of their different proprietors; this is called *La Ferrade*. A considerable portion of the district is ploughed land, furnishing crops of corn, madder, &c., which are produced in abundance, and the culture of rice has lately been introduced: but this fertility, as well as the rich pasturages, arises entirely from irrigation, and the distribution in all directions of the waters of the Rhône, derived from the river in cuts and canals. The salt marshes and lagoons are unprofitable except in producing salt. There is only one village in the Camargue, that of Saintes Maries, but many isolated farms are scattered over it. At harvest time, in the month of July, the corn is threshed in the Oriental fashion, by driving 10 or 12 young horses, held with a long rein by a man in the centre of the threshing floor, over the sheaves laid in heaps around, but this practice exists throughout Provence. The winnowing is performed by tossing the straw, chaff, and grain into the air, and allowing the wind to separate them.

The *Crau*, or stony plain to the E. of the Camargue, is described in R. 127.

The very curious church of St. Gilles is described in Route 126.

It has been calculated that the Rhône discharges into the sea, in 24 hours, more than 5 million cubic mètres of earthy matter, similar to the deposits composing the Camargue.



Its banks are in consequence extending daily, and the *Tower of St. Louis*, built 1737, at a distance of 2600 mètres (1 m. 3 furl.) from the sea, is now 7200 mètres (4 m. 3 furl.) from it. In consequence the mouths of the Rhône are beset by sand-banks, so as to be pronounced by Vauban "incorrigibles," and their navigation is dangerous.

## ROUTE 126.

AVIGNON TO NARBONNE BY THE PONT DU GARD, NISMES, MONTPELLIER, AND BÉZIERS.—EXCURSIONS TO ST. GILLES, CETTE, AND AIGUES MORTES.

200 kilom. = 124 Eng. m.

*Malleposte* from Nismes to Narbonne daily, in 12 hours.

*Diligences* from Avignon to Nismes, in 4 hours, daily, and thence to Narbonne. The Pont du Gard may be seen on the way to Nismes.

9 kilom. extra are charged by the postmaster for making the *détour* by the Pont du Gard.

You quit Avignon by the new suspension bridge which crosses the Rhône. From the slope and summit of the steep ascent which carries the road over the hills which form the rt. bank of the Rhône, you have a fine view of it, and of Avignon, and then a dreary country succeeds, hills bare as dry bones; but in the low ground olives, mulberries, and vines.

12 Begude de Saze.

The point where our road approaches nearest to the Pont du Gard is at Remoulins ( $1\frac{1}{4}$  m. distant from it), a small town on the l. bank of the Gardon, now at length connected by a bridge of wire with

11 La Foux (Fabre's restaurant), a village and post station on the rt. bank. 9 kilom. extra are charged if the traveller posting chooses to be driven round by the *Pont du Gard* ( $1\frac{3}{4}$  m. distant). The sight of this noble edifice, one of the grandest monuments which the Romans have left behind them, in France or any

other country, would well repay for a very long *détour*. Like Stonehenge, it is the monument of a people's greatness, a standard by which to measure their power and intellect. It consists of 3 rows of arches, raised one above the other, each smaller than the one below it; the lowest of 6 arches, the central tier of 11, and the uppermost of 35; the whole in a simple, if not stern style of architecture, destitute of ornament. It is by its magnitude, and the skilful fitting of its enormous blocks, that it makes an impression upon the mind. It is the more striking from the utter solitude in which it stands, a rocky valley, partly covered with brushwood and greensward, with scarcely a human habitation in sight, only a few goats browsing. After the lapse of 16 centuries, this colossal monument still spans the valley, joining hill to hill, in a nearly perfect state, only the upper part, at the N. extremity, being broken away. The highest range of arches carries a small canal about 5 ft. high, and 2 ft. wide, shaped like the letter U, just large enough for a man to creep through, still retaining a thick lining of Roman cement. It is covered with stone slabs, along which it is possible to walk from one end to the other, and to overlook the valley of the Gardon. The arches of the middle tier are formed of 3 distinct ribs or bands, apparently unconnected. The height of the Pont du Gard is 180 ft., and the length of the highest arcade 873 ft. Its use was to convey to the town of Nismes the water of 2 springs, 25 m. distant, the Airan rising near St. Quentin, and the Ure near Uzès. It forms only a small portion of the conduit constructed for this purpose, whose course, partly raised on low arches, some of which exist on the N. of the Pont du Gard, partly cut in the rock round the shoulders of the hills, may be traced at the village of St. Maximin, near Uzès, and above that of Vers, to the Pont du Gard; thence, by St. Bonnet and Sernhac, to the hill of the Tour

Magne, and Bassin des Thermes at Nismes.

The conveyance of this small stream was the sole object and use of this gigantic structure, an end which would now be attained by a few iron water-pipes. Its date and builder are alike lost in oblivion, but it is attributed to M. Agrippa, son-in-law of Augustus, B.C. 19. The quarry whence the stone was obtained is a little way down the Gardon, on its l. bank. The bridge by which the road crosses the Gardon, on a level with the lower tier of arches, and formed by merely widening them, is a modern addition to the ancient structure, having been erected in 1743 by the States of Languedoc.

A little below La Foux, the road to Nismes turns rt. out of the valley of the Gardon, and traverses a more fertile and productive, but uninteresting country, by

10 St. Gervasy, to

10 *Nismes* (*Inns*: H. du Luxembourg; good; tolerably clean; the best, but much frequented by commis voyageurs; tolerable cuisine;—H. du Midi.

Nismes, chef-lieu of the Dépt. du Gard, a flourishing manufacturing town of 44,240 inhab., consists of a central nucleus of narrow intricate streets and old houses, encircled by a girdle of open *boulevard*, which separates it from its modern faubourgs, composed of wide streets and new houses. The boulevard is itself a fine broad street, planted with trees, lined with handsome buildings; and there is little need for the passing traveller to penetrate into the old town, as the chief curiosities and objects of interest are situated on the edge of this boulevard, or at a short distance from it. They consist almost exclusively of Roman monuments, relics of the ancient city of *Nemausus*, which, though passed over in oblivion by classic authors, so that its origin is unknown, and merely mentioned in the geographical catalogues of Strabo and Ptolemy, yet affords more pal-

pable testimony of its ancient extent and splendour than most cities celebrated in classic page. While the renowned cities of Marseilles and Narbonne have few relics and no existing edifices of the ancient masters of the world, the obscure Nismes is richer in well-preserved antiquities than any town in France or Northern Europe.

A walk along the boulevard, starting from the H. du Luxembourg, and keeping to the l., will bring you first to the *Esplanade*, a square terraced platform, planted with trees, furnishing a promenade of considerable extent. Facing it is the new *Palais de Justice*, fronted with an imposing portico, and a little further on stands

The *Amphitheatre*, *Les Arènes*, now isolated by the removal of the buildings which obstructed it within and without, in the middle of a wide place, allowing unimpeded view of its very perfect oval circuit. It consists of 2 stories, each of 60 arcades, 70 ft. high; the lower arches serving as so many doors: the arches of the upper arcade are double, but the inner arches are not concentric with the lower. It is far better preserved, externally, than the Coliseum at Rome, although like it converted into a fortress during the middle ages, and retains even its projecting stones, pierced with holes, for inserting the masts to which the awnings (*valeria*) were attached.

The interior, though less perfect, retains some of the original seats, especially of the lower and upper rows. The modern French architect employed on the building, not content with preserving and protecting the parts which remain, has committed the fault of restoring, or rather reconstructing, in a somewhat clumsy manner, part of them and some of the arcades. There were originally 32 rows of seats, and the number of spectators which it is supposed the building may have contained is estimated at from 17,000 to 23,000.

A long corridor, surrounding the



building, runs within the arches on the ground story, and a smaller corridor encircles the upper story. It is worth while to make the circuit of these, and, indeed, to penetrate every part of this extraordinary structure. The vaults of the lower corridor or portico are like some vast natural cavern; the upper one is roofed with huge stone beams, 18 ft. long, reaching from side to side, many of them cracked, either by an earthquake, or by the conflagration which consumed the Arènes in the time of Charles Martel. It is interesting to penetrate the wedge-shaped passages, radiating from the centre, and widening outwards, so contrived as to facilitate the egress of the hastening crowds, and allow them to depart without any check; to ascend the stairs, by which ready access was given to every part of the huge structure; to clamber over the broken seats, some still marked with the line indicating the space allotted to each spectator, scaring the frightened lizard, which starts away from under your foot, out of the sunshine in which it has been basking, to the shelter of the tufts of grass or weeds springing up among the crevices of the masonry; and, finally, to stand on the topmost stone, the rim of this huge oval basin, surveying its whole interior, dismantled, and almost gutted. Here you may examine the round holes cut in the projecting stones, and corresponding with hollows in the exterior cornice below, into which the poles were put, in order to fasten the awnings stretched over the spectators. A very narrow stair in the thickness of the wall, near the N. side, was destined, it is supposed, for the men who had charge of the awning. The zones of seats, as is well known, were divided into 4 tiers (*præcinctiones*) by spaces wider than the seats themselves, and were destined for spectators of different rank; the patricians occupied the lower, equivalent to the dress circle, the plebeians the upper, corresponding with the gallery. These spaces,

or landing-places, were each reached by 10 passages or vomitories. The 3 uppermost rows of seats rest upon a half arch, whose only support is the outer wall.

The *dimensions* are, length 437 ft., width 332 ft., height 70 ft.

The founder of this building and its date are unknown: it is attributed to Antoninus Pius, whose ancestors came from Nismes, but by others to Titus and Adrian.

The Visigoths converted it into a fortress, and it was known as the "*Castrum Arenarum.*" The Saracens occupied it as such in the beginning of the 8th century, until expelled by Charles Martel, who endeavoured to destroy the building altogether, by filling its vaults and passages with wood, and setting fire to it; finally, down to the middle of the 18th century, it was occupied by mean hovels, all of which are now swept away. The people of Nismes use the Arènes for an entertainment called *Ferrade*, which consists in teasing a number of wild bulls from the Camargue (p. 468), previous to branding them with hot *iron*. The sport is but a poor imitation of a Spanish bull-fight; nearly as cruel, without being so exciting, and it has properly been prohibited.

Continuing through the boulevard, from the Arènes, and passing on the l. the Great Hospital, you reach the modern *Theatre*, remarkable only for its tasteless portico, contrasting very unfavourably with a neighbouring building, which, though of an age deemed barbarous, shows yet a far greater refinement in taste.

The *Maison Carrée*, the vulgar name given to a beautiful Corinthian temple, a gem of architecture, which has come down to the present time in a state of wonderful preservation, considering its various fortunes, and the purposes to which it has been converted. Originally a temple, consecrated in the reign of Augustus, according to some; of Antoninus Pius, according to others: it became

afterwards a Christian church, and in the 11th century the Hôtel de Ville; still later it was converted into a stable, and its owner, to extend his space, built walls between the pillars of the portico, and pared away the flutings of the central columns to allow his carts to pass; it then became attached to the Augustine convent, and was used as a tomb-house for burial; its next changes were into a Revolutionary Tribunal and corn warehouse; and finally, at present it is converted into a *museum*.

It is surrounded by 30 elegant Corinthian columns, 10 of them detached, forming the portico, and 20 engaged: their height is equal to  $10\frac{1}{4}$  diameters; and learned architects will tell you that these proportions are contrary to Vitruvian rules, and that the building is debased and defective in consequence. This, however, appears a case in which ignorance is bliss; the ordinary and unlearned spectator will scarcely fail to be impressed with the elegance of its general effect, as well as with the simplicity of its form, the beauty of its fluted Corinthian columns, and the richness of the capitals, frieze, and cornice which they support.

M. Séguier, an antiquary of Nismes, first hit upon the ingenious idea of restoring the inscription on the frieze above the portico from the holes left in it, by which the bronze letters composing it were attached, the letters themselves having long since disappeared. "According to his reading, it ran thus:—C. CAESARI. AVGVSTI. F. COS. L. CAESARI. AVGVSTI. F. COS. DESIGNATO. PRINCIPIBUS. JVENTVTIS.; thus attributing the dedication of this temple to "Marcus and Julius Cæsar, grandsons of Augustus, Consuls Elect, Princes of Youth." The style, however, of the building, and the profusion of ornament, indicate a period much later than Augustus; and another antiquary, on examining the original state of the holes in the frieze, discovers 3 holes preceding the 2 to which M. Séguier's first

letter C was fastened, and thus converts the C into an M. This slight alteration shifts the date of the Maison Carrée from the era of Augustus to that of Antoninus, for it appears that the only 2 princes bearing such names who enjoyed together the title *Principes Juventutis*, after the sons of Agrippa, were Marcus Aurelius and Lucius Verus, adopted sons of Antoninus. It is evident, however, that the determination of the letters from such data must, in a great degree, be a mere piece of guess-work, owing to the confusion and number of the holes. Excavations have laid bare the foundations of walls, extending on either side of the temple, showing that it was only the centre of a larger edifice, from which two long colonnades extended, in the manner of wings, on either hand, and it is supposed that it occupied one end of the ancient *forum* of Nemausus.

The whole is now enclosed by an iron railing, within which are deposited numerous antique fragments found in and about the town.

The contents of the *Museum* (into which the temple is now turned) consist of other antiquities, including a bronze head (of Apollo?); a marble bust of Venus, and a quantity of *pictures*, very poor and common-place for the most part, excepting *Paul Delaroche's* master-piece, Cromwell opening the Coffin of Charles I., and Nero trying upon a Slave the Poison destined for his Brother Britannicus, by *Sigalon*.

"Opposite the entrance to the Maison Carrée is the small though very rich Museum of Antiquities, formed by M. Perrot. Ask for his exquisite head of Sappho."—*J. D. H.*

Returning to the boulevard, and continuing along it as far as the irregular Place de la Bouquerie, you come upon a handsome canal, supplied with water from the ancient *Fountain of the Nymphs*. It must not, however, be judged of at first sight, for at this point nothing can be more unclassical; its limpid rills are



stained with soap-suds, and in the place of nymphs a swarm of blanchisseuses convert it into a public washing tub. Trace it upwards, however, and you will find its source within a fine *Public Garden*, planted with trees, in the midst of which it bursts forth in exuberant copiousness from the foot of a hill, and is received into a large reservoir, originally a Roman bath for women. It is surrounded by a large colonnade below the level of the ground, and is conducted through a formal canal lined with masonry like the ditch of a fortification, and bordered with a handsome stone balustrade. A part of this enclosure is of antique masonry, but the whole has been restored in modern times. It is a very handsome, but formal construction, and it and the garden which it traverses form a principal ornament of the town. On one side of it is a *ruined Roman building*, supposed at one time to have been a *temple of Diana*, but now regarded as a *Nymphæum* (or fane dedicated to the Nymphs), and connected with the neighbouring baths. It appears to have had a semi-cylindrical roof rising from an entablature, supported by columns. It is proved by inscriptions to have been built, along with the baths, by Augustus. It was reduced to ruin 1577. The ancient aqueduct which the Pont du Gard carried across the valley of the Gardon (p. 469) terminated near the fountain at Nismes, in a basin or reservoir 16 ft. diameter, and about 5 ft. deep, recently discovered.

The hill rising behind the fountain, planted with trees, and rendered accessible by zigzag walks, is surmounted by another singular ancient monument, known as *La Tourmagne*, a dismantled tomb of rough ashlar, not unlike several still existing in the vicinity of Rome, but which has passed at different times with learned antiquaries for a lighthouse (50 m. inland, and remote from any river!), a Gallic temple, and a treasury. It is hollow within, having a rude conical

shape, resembling that of a glass-house. The walls are very thick below, but taper upwards; externally it was an octagon, but the surface-stonework is for the most part removed. It is, perhaps, the oldest building in the town. Some have referred its origin to times preceding the Romans: in their time it was included in the defences of the town, and connected with the walls. It was originally filled with earth, and it seems not unlikely that it was built upon a nucleus of earth, for its cone is not properly vaulted, but consists of small stones, held together by the strength of the cement alone. It was cleared out by a gardener, who obtained leave from Henri IV. to search the building for treasure, a scheme which turned out eminently unprofitable.

A staircase is now erected to the top, whence the *view* is very fine. The situation of the Tourmagne is very commanding; at the foot of the heights, on which it stands, the whole city is displayed, and the distant horizon includes the bifurcation of the Rhône, and, perhaps, the site of Aigues Mortes on the Mediterranean.

Nismes retains two of its original Roman gates, the *Porte d'Auguste*, founded in the reign of that Emperor, B.C. 16, consisting of a double arch with two side doors for foot passengers, flanked by 2 towers, and the *Porte de France*.

In the heart of the old town stands the *Cathedral*, an ancient building, but so injured during the wars of religion of the 16th and 17th centuries, and now so much modernised, as to possess little interest. High up, on the W. front, above a circular window, a curious sculptured frieze, representing events from the book of Genesis, is introduced; it is very ancient.

The cabinet of *antiquities of M. Pelet*, and the cork models made by him of the ancient buildings in Nismes, are well worth seeing.

There are 12,000 Protestants at Nismes, who have 2 churches (*temples*) and a chapel: they have endured

severe persecutions at different times. So little even now do the Protestants and Catholics coalesce, that each party frequents distinct cafés.

The *Maison centrale de Détention* was originally a citadel, erected by Louis XIV. to keep down the Protestants.

The *manufactures* of Nismes consist of various articles of silk and cotton, which change with the fashion and the demand; it has large printing and dyeing works; but cotton handkerchiefs seem the staple production at present.

The want of water is severely felt for 3 months of the year, the town being dependent for the supply required by its inhabitants and its manufactories on the single source already described. A considerable trade in the wines and spirits of Languedoc, in raw silks, and in oil, is carried on here.

In the garden of the Convent of Recollets, now occupied by the Theatre, Marshal Villars had an interview in 1704 with the celebrated chief of the Camisards, Cavalier, who, originally a baker's boy, and at that time a mere youth, had raised himself by his talents for command and his fanatic eloquence to be the head of the formidable rebellion of the Cevennes. He appeared on that occasion magnificently mounted, and attired in laced coat, cocked hat, and plume of white feathers, escorted by a body-guard on horseback. The result of this memorable conference was to detach him from the insurgents by flattery and promises of rank and reward in the service of Louis XIV., as the price of his defection, coupled with assurances of justice and tolerance in religion to the persecuted Protestants of the Cevennes. Neither the one nor the other was destined to be kept or fulfilled. Villars, however, thus dealt a death-blow to the insurrection, by depriving it of one of its heads; and Cavalier, despised and hated for his desertion by his own party, and neglected by

the court, was soon driven into exile, and died a pensioner at Chelsea.

On the Place de Boucairie in 1705 were erected the gibbet, the wheel, and the stake, at which a vast number of the Camisards concerned in the rebellion of the Cevennes perished miserably, after suffering horrid tortures in the prison of the fortress. The most memorable execution was that of the chiefs (April 22) Catenat and Ravenel, who were burnt alive, almost within sight of the battle field where 2 years before they had defeated the royal forces under the Comte de Broglie; while their companions, Jonquet and Villas, were broken on the wheel and then burnt. On the 16th August, 1704, the body of Roland Laporte, general of the Camisards (see p. 435), was dragged into Nismes at the tail of a cart and burnt, while 5 of his companions were broken on the wheel around his funeral pyre.

Nismes is the birthplace of Nicot, a physician who first introduced from Portugal into France *tobacco* (called after him *Nicotiana*). Some one proposed to raise a monument to him in the form of a snuff-box, bearing the inscription, "Dieu vous bénisse." M. Guizot, Minister of France, also comes from Nismes, "where his father, an avocat, was guillotined during the Reign of Terror."—G.

*Railroads* to Alais and its coal-field (R. 121), trains twice a day; to Beaucaire (R. 127), trains 4 times a day. To Montpellier and Cette. (The *Railway* to Marseilles will be finished 1848.)

*Mallepostes* to Marseilles and Narbonne.

*Diligences* daily to Marseilles; to Narbonne, and Toulouse; to Avignon, 3 times; to Alais (railway); to Lyons; to Mende, St. Flour, and Clermont; to St. Gilles and Aigues Mortes; to Uzès, by Alais.

Mons. E. B. D. Frossard's "Nismes et ses Environs" is a charming book: the author is a Protestant clergyman.



The *Pont du Gard* (p. 469), distant about 15 m. from Nîmes, on the way to Avignon, ought to be visited expressly by those whose route does not lead them past it. It is about 2 hours' drive; a carriage may be hired for 12 fr. to go and return. About 13 m. nearly due S. of Nîmes is *St. Gilles*, a town of great antiquity, originally *Rhoda Rhodiorum*, a colony founded by the Rhodians according to Pliny, situated on the Petit Rhône, chiefly remarkable at present for its magnificent *abbey church*, which will interest the antiquary. The upper church was begun 1116, on a scale of great magnificence, by Alphonso, son of Raymond IV., Count of St. Gilles, called Jourdain, because baptised in the Jordan, but was destroyed during the wars of religion, having been turned into a fortress by the Huguenots in 1562, and demolished, when no longer tenable as such, by the Duc de Rohan, 1622. It has been replaced by a temporary structure of late date and inferior architecture.

The *lower church*, however, which is not subterranean, but on a level with the cloister, is, perhaps, of the 11th century, having been dedicated, 1096, by Pope Urban II.; and the *West Front* is a master-piece of the Romanesque style, upon which every species of ornamental decoration and rich sculpture seems to have been lavished. It has been described as one immense bas-relief, crowded with pillars, statues, panelling, foliage, &c., combined with a strange infusion of the elements of classical architecture, columns, capitals, entablatures, and friezes. Sculptured lions are frequently introduced as supports to the pillars, and in other parts; and as the abbots of St. Gilles, powerful seigneurs in ancient days, used to sit at the gate of the church to dispense justice, many of the old charters begin with the words "*Domino NN. sedente inter leones.*" In the vestibule of this church, Raymond VI., Comte

de Toulouse, accused of favouring the persecuted Albigenses, underwent, in 1209, the ignominious penance of being scourged on his naked back, in the presence of the papal legate and of 12 French bishops. The lower church is supposed to be a little older than the porch.

[A detached pile of ruin, behind the actual church, is the only relic of the old priory which escaped being destroyed in the 16th century; it contains a corkscrew *staircase*, called *Le Vis de St. Gilles*, and is celebrated for its masterly construction as a piece of masonry. It was again saved from destruction at the Revolution by the influence of M. Michel, a lawyer of St. Gilles. In a narrow street facing the church is a curious old house, deserving attention as a remarkable specimen of the civil architecture of the middle ages.]

A *Railway*, finished 1844, joins Nîmes to Montpellier (52 kilom.), and is carried thence to the sea-port of Cette, 27 kilom. = total 45 Eng. m. 4 trains daily, in 2 hours. Fare, 1st class, 2 frs. 10 sous, carriage 32 frs. Its chief work is a viaduct of 96 arches. It passes by Lunel.

The road from Nîmes to Montpellier lies across an extensive plain, reaching from a range of low rocky limestone hills on the N., the extreme roots of the Cevennes, to the salt marshes bordering on the Mediterranean, S.

The fertile district to the W. of Nîmes is called the *Vaunage* or Valley of Nages, from a small and reduced town of that name, a little to the N. of our road. It was the scene of one of the most remarkable engagements in the war of the Cevennes (April 6, 1704), in which Cavalier, at the head of 900 foot and 300 horse, well equipped, intending to waylay the Maréchal de Montreval on his way to Montpellier, was himself betrayed into a vast ambuscade, surrounded on all sides by the royal troops (among whom were 100 Irish

from the Boyne), and caught as in a trap. Undismayed by numbers 6 times exceeding his own, the Camisard chief, perceiving the design of the enemy to outflank him, wheeled his column rapidly round under the hottest fire, and in the face of a charge of bayonets, and drew off his men, retreating en échelon—a masterly manœuvre of the baker's boy, which drew forth the admiration of Marshal Villars. Cavalier's retreat, however, was cut off; the royal army occupied every pass, every height; not an opening remained; and his only course was to cut his way through. Throwing aside his magnificent uniform and white plume, he put on a common dress, and, bidding his followers close their ranks, dashed forward directly against the enemy. With the fiercest struggle he broke through the first line, but was soon singled out and discovered: at one time a soldier caught his horse's bridle, but a Camisard behind cut off the hand; another dragoon who had seized him he shot with his pistol. But in front now appeared a second rank barring his way, and a squadron of dragoons occupying the Pont de Rosni, the only issue. The fugitive cavalry poured down upon it, forced their way through, forgetful of their leader, who was in the rear, and would probably have been cut off after all but for his brother, a boy 10 years old, who drew up his horse across the bridge, and with a pistol presented to the fugitives, summoned them to defend their chief, and not abandon him. Cavalier, with the rest of his infantry, escaped into the wood of Cannes. This battle, or series of combats, extended from the mill of Langlade to the village of Nages; 1,000 dead were left on the field, half of whom were Camisards.

At the commencement of the fight one of the Prophets of the Enfants de Dieu, named Daniel Gui, planted on the top of a rock, surrounded by 5 or 6 prophetesses, 3 of whom were afterwards found among the slain,

called on the God of battles to favour their cause.

12 Uchau, anciently *Ad Octavum Lapidem* (the 8th milestone).

The turbulent torrent Vidourle, which separates the Dépt. du Gard from that of L'Herault, is crossed shortly before reaching

14 Lunel, a town of 6,385 inhab., owing its celebrity and prosperity to the sweet wine and brandy which form its chief articles of commerce. The best Lunel wine is grown on the Côte de Mazet. The lower ground in which the town is situated is often inundated in winter and spring, is infested with mosquitoes in summer, and with fevers in autumn. Human bones, with pottery, have been found in caves in the tertiary limestone at Pondres, 6 m. N. of Lunel.

About 5 m. S. of Lunel is *Aigues Mortes*, singularly situated in the midst of salt marshes and lagoons, whose exhalations render it very unhealthy. It is approached by a causeway raised above the marsh and spanned midway by an ancient gate tower, *La Carbonnière*. Aigues Mortes, itself a miserable and deserted town, is of interest only as a perfect example of a feudal fortress; its walls and gates, more entire and less altered than even those of Avignon, give a perfect idea of the art of fortification in the 13th century. Its foss has been filled up, on account of the malaria produced by its stagnant water. In advance of the place, to the N., is a single round tower, which served as a citadel, 90 ft. high, 65 in diameter, surmounted by an old lighthouse turret of 34 ft. In the centre of each floor is a hole communicating with a reservoir for water below. Some of its chambers served as a prison, in which Protestants, chiefly females, who refused to abjure their faith, were confined after the Revocation of the Edict of Nantes. Some of them had been shut up here for 35 years, when they were released in 1769. From the upper story of this tower, the Camisard chief Abraham, with 17 companions,



made a wonderful escape, letting themselves down from a height of 80 ft. by their blankets tied together. This tower is called *Tour de Constance*, for what reason is unknown. It is proved to have been built by St. Louis, who embarked here on his unsuccessful Crusade in 1270, having assembled at this spot a fleet of 800 galleys, and an army of 40,000 men. As Aigues Mortes lies nearly 3 m. inland, some have supposed from this that the sea must have retired since the 13th centy.; modern investigations have proved, however, the existence of a small port close to the town, in whose walls the ancient mooring rings still remain; and of a canal, now filled with sand, extending thence to the harbour of Grau du Roi, on the sea, doubtless the place of rendezvous for the royal fleet. The walls of the town were built after the death of St. Louis, in Africa, by his son Philippe le Hardy, on the plan, it is said, of those of Damietta. Salt is the chief article of commerce produced in the vicinity; and after the massacre by the royal forces, aided by the townsfolk, of the Burgundian troops, who had obtained possession of the town in 1421, the bodies of the slain were thrown into the tower still called *Tour des Bourguignons*, between layers of salt, it is said, in order to prevent their putrefying and breeding miasma in the town. In 1538 an interview took place here between the Emperor Charles V. and Francis I.; and in 1542 the Turkish corsair Barbarossa, the ally of the French king against the emperor, moored his fleet in the harbour.

There is little to observe on the road between Lunel and Montpellier; the country rich and monotonously flat.

10 Columbier, a land of oil and wine.

13 *Montpellier*. — *Inns*: Hôtel Nevet, a splendid, new, and large edifice, 200 bed-rooms—one of the best hotels in France—*L. Y.*;—*H. du Midi*; best, very good, but insects;

—*H. de Londres*; good;—*H. des Ambassadeurs*. The name of Montpellier, familiar to every one who has been in an English watering-place, as the type of salubrity and mildness of climate, will not in reality answer the expectations of those who anticipate either a soft air or a beautiful position. Indeed it is difficult to understand how it came to be chosen by the physicians of the North as a retreat for consumptive patients; since nothing can be more trying to weak lungs than its variable climate, its blazing sunshine alternating with the piercingly cold blasts of the *mistral*. Though its sky be clear, its atmosphere is filled with dust, which must be hurtful to the lungs; and the glare from the chalky ground and white houses, unmodified by shade, is exceedingly painful to the eyes. The town is chef-lieu of the Dépt. de l'Hérault, and a place of importance, since it contains 40,746 inhab.; in its streets and buildings it is not much distinguished.

The *Promenade du Peyrou* (a provincial form for pierreux, stony, the spot having been originally a bare rock), an elevated platform, reached by flights of stairs, and surrounded by balustrades in the style of the time of Louis XIV., whose equestrian statue is in the centre, was constructed 1766, and is referred to as the ne plus ultra of a public walk. It has, it is true, shady avenues and neat parterres. At the extremity of it rises the Château d'Eau, a sort of fountain-temple, which receives and distributes through the town the waters conveyed across the fertile valley from the opposite hill by the *Aqueduct*, a very noble construction, though modern, begun 1753, consisting of 53 large arches, surmounted by 183 smaller, measuring 2,896 ft. The source whence the water is derived is about 2 m. distant. The beauty of the view from the Peyrou has been somewhat exaggerated; the Pyrenees are too distant to give it interest, though the peak of the Canigou is said to be sometimes

visible; the Mediterranean is ill represented in its border of marshes and lagoons, and the Alps (in spite of what the guide-books say) are out of the scope of vision. The chief feature is the bare Pic de St. Loup, a buttress of the Cevennes projecting from the N., visible from the road to Nismes. On the S. is seen the church tower of Maguelonne.

The town *gate* on one side of the Peyrou was erected to commemorate the *glories* of the reign of Louis XIV. The bas-reliefs towards the town are meant to represent the union of the Mediterranean to the Atlantic by the Canal du Midi, and the Revocation of the Edict of Nantes; the one a benefit, the other a curse to France. There are, indeed, mournful recollections connected with the Peyrou: here were raised, during the reigns of Louis XIV. and XV., the scaffolds on which perished, by being burnt alive or broken alive on the wheel, not only many of the fanatic Camisards, among others their chief Castanet, but also many "Pastors of the Desert," Protestant ministers whose only crime was praying to God according to the impulse of their own conscience.

The *Jardin des Plantes* was the first established in France, in the reign of Henri IV., and it is well kept up. Here may be seen the Galactodendron, the cow or milk tree of S. America, mentioned by Humboldt. In one corner of the garden, shaded by cypress, is an arched recess, fenced with a trellis rail, within which a simple tablet bears these words, "*Placandis Narcissæ manibus.*" This is pointed out as the tomb of Mrs. Temple, the adopted daughter of Young, the poet, who died suddenly here, at a time when the atrocious laws which accompanied the revocation of the Edict of Nantes, backed by the superstition of a fanatic populace, denied Christian burial to Protestants. Such a refusal gave rise to the following passage in the "Night Thoughts:"—

"Snatch'd ere thy prime! and in thy bridal hour!  
And when kind fortune, with thy lover, smiled!  
And when high-flavour'd thy fresh opening joys!  
And when blind man pronounced thy bliss complete!  
And on a foreign shore, where strangers wept!  
Strangers to thee; and, more surprising still,  
Strangers to kindness, wept: their eyes let fall  
Inhuman tears! strange tears! that trickled down  
From marbled hearts! obdurate tenderness!  
A tenderness that call'd them more severe;  
In spite of nature's soft persuasion steel'd;  
While nature melted, superstition raved;  
That mourn'd the dead, and this denied a grave—  
Denied the charity of dust to spread  
O'er dust! a charity their dogs enjoy.  
What could I do? What succour? What resource?  
With pious sacrilege a grave I stole;  
With impious piety, that grave I wrong'd;  
Short in my duty; coward in my grief!  
More like her murderer than friend, I crept,  
With soft suspended step, and muffled deep,  
In midnight darkness, whisper'd my last sigh.  
I whisper'd what should echo through their realms;  
Nor writ her name whose tomb should pierce the skies."

Evidence has been brought forward to prove that Narcissa (Mrs. Temple) was, in reality, buried at Lyons.

The student of medicine should not fail to see the *Ecole de Médecine*, situated in the old building, formerly the bishop's palace. It contains valuable anatomical collections, and the doctor's *robe* with which Rabelais was here installed, and which is employed for the same purpose at present, but so much patched and mended that scarcely a thread of the original garment remains. The school of medicine here is of great antiquity, having been founded, it is said, by Arab physicians, driven out of Spain, and patronised by the Comtes de Montpellier. Adjoining this building is the *Cathedral*, modernised, and of no interest. It has a singular porch, projecting from the wall, and resting on 2 round piers or turrets. The building suffered much from the Huguenots. It contains an altarpiece by *Sebastian Bourdon*, a native of Montpellier, the Fall of Simon Magus.



The principal object of curiosity here, however, is the *Musée Fabre*, named from its founder, a native of Montpellier, an artist, and the friend of Alfieri and his mistress the Countess of Albany. It comprises a collection of paintings, of an excellence rarely found away from the capital; among them a portrait of Lorenzo de' Medici, father of Catherine de' Medici (d. 1519), by *Raphael*, probably genuine, and good; and a head of a Young Man with a Beard, also attributed to *Raphael*, brought from a villa near Sienna; and at least a good copy by his scholars, if not original. There are also many other pictures of the Italian schools, and a number by artists of the modern French school.

The *library of Alfieri*, 15,000 vols., including many works on art, is also deposited in this museum. The Marquis de Montcalm has a good collection of *Paintings* by the old masters, which is shown.—*H. N.*

Cambacères, Grand Chamberlain of Napoleon, Seb. Bourdon, the painter, and Chaptal, the chemist, were born here.

Montpellier has some considerable *manufactures* of cottons, dye-works, &c.; and some which are nearly peculiar to itself and its neighbourhood, such as the making of *verdigris*, which is obtained by laying plates of copper between layers of grape husks, and allowing them to remain in cellars for 18 or 20 days, after which the coating of green rust (acetate of copper), produced by the oxidizing of the metal plates by the grape juice, is scraped off. There are extensive *chemical works* here, founded by the Comte de Chaptal, consisting of alum, Prussian blue, sulphuric and nitric acids; also a considerable quantity of perfumes, essences, and liqueurs. The distilleries of brandy from the wines of the district are very numerous.

The excellent Roquefort cheese is made about 15 m. to the N. of this,

in the Dépt. de la Lozère. (See Index.)

*Diligences* daily, to Nismes and Marseilles; to Toulouse; to Perpignan.

The *railway*, 17 m. long, from Montpellier to Cette, passes through Villeneuve, whose *church* is in part as old, probably, as the 8th century, and *Frontignan*, celebrated for its sweet wine, the best being of the kind called Muscat.

The flourishing town and sea-port of *Cette* (*Inns*: Poste;—H. du Grand Galion; dear) contains a population of 13,413, and is situated on a tongue of land running between the sea and the salt lake called Etang de Thau: it stands at the foot of an eminence, surmounted by a fort. The town is entered by a causeway elevated above the lagoon, and by a bridge of 52 arches. The town was founded by Louis XIV.; and the works of the harbour, piers, &c. were executed by Riquet, the engineer of the *Canal du Midi*. There is an extensive *manufacture* here of the *wines of all countries*, port, sherry, claret, champagne, for the English and other markets, produced by the mixture of various kinds of French and Spanish wine and brandy; Benicarlo wine being imported from Spain to mix with inferior claret. The salt works on the lagoon are numerous. In 1710 a descent was made here from the fleet of Commodore Norris by a small British force designed to cause a diversion on the side of Spain, and effect a junction with the insurgents of the Cevennes. They took possession of Cette, but after holding it for a few days were driven back to their ships with some loss.

*Steamers* to Marseilles, in 10 or 12 hours; to Onglous, near Agde, at the mouth of the Canal du Midi, crossing the Etang de Thau: 36 hours are required to reach Toulouse from Cette by the canal, owing to the number of locks; so that this mode of conveyance is not to be recommended.

A canal passes through the series of lagoons from Cette to Aigues Mortes, fenced in by dykes of stone or mud, and thence to Beaucaire. The Canal du Midi opens out also into the Etang de Thau, and thus Cette communicates both with the Rhône and Garonne.

The ruined church of *Maguelonne*, on an island between the sea and the lagoons, beyond the Canal du Grave, will interest the antiquary, but he will require a guide to it across the heath and marsh, though the distance is only 6 m. from Montpellier. It appears more like a castle than a church, little ornament being expended on its exterior. Its W. doorway is curious, consisting of a pointed arch of coloured marble, resting on a sculptured frieze, with a bas-relief of the Saviour in the tympanum, and a triangular bas-relief on either side of the door, representing St. Peter with the Keys, and St. Paul with the Sword. The body of the church, a nave ending in an apse, contains some ancient tombs of bishops, but is filled with hay. The building dates from 1110 to 1180. It is the sole relic of a populous town which existed on this spot down to the 16th century.

The road from Montpellier to Narbonne passes through a country abounding in vineyards, which cover all the low ground, while olives occupy the hills: it is very thickly inhabited.

11 Fabrègues.

8 Gigan; from this the town of Cette, rising on a promontory out of the sea, is well seen. Skirting the margin of the lagoon of Thau, we proceed to

12 Mèze. (*Inn*: Couronne, tolerable.) Near this are the baths of Balarue, supplied by a hot salt spring: they are good for rheumatism, paralysis, &c. There is a very bad road (1846) from Mèze to Béziers, by Agde (20 kil. *Inn*: Poste), a small sea-port, Béziers (22 kil.)

Beyond Mèze the road turns away

from the sea; the country is very pretty, especially in the vicinity of

18 Pezenas, a town of 7,800 inhab., agreeably situated on the l. bank of the Hérault, at the confluence of the Peine. It was anciently called *Pisecanum*. Molière wrote here his comedy *Les Précieuses Ridicules*, while director of a troop of strolling players. The chair in which he used to sit to be shaved by the barber is still preserved in the town. Pezenas is one of the chief brandy markets in Europe.

10 La Begude de Jordy. A very steep ascent, for which an extra horse is required, leads into

12 Béziers.—*Inns*: H. du Nord, filthy in the extreme and exorbitant—W. W. L.;—Poste; dirty also;—Croix Blanche.

Béziers, an ancient town of 16,779 inhab., has an imposing appearance at a distance, seated as it is upon a commanding eminence, its topmost building being its *Cathedral*. The interior, however, is confined, gloomy, and filthy; but some improvements have lately been made, including a new bridge to lead into the town. The view from the *Terrace*, in front of the cathedral and évêché, is fine, extending over the course of the Orbe, and of the Canal du Midi, both of which pass near the foot of the hill, and pursue their way to the sea in different directions. The Cathedral of *St. Nazaire* is a Gothic building, surmounted by battlements, so as somewhat to resemble a castle externally, and contains some old painted glass. It was the chief scene of the horrible slaughter of 1209, with which the name of Béziers is always associated, at that terrible siege by the crusading army raised at the call of the church of Rome to exterminate the unfortunate Albigenses, who were numerous in this devoted city. The inhabitants refusing to yield, the crusaders forced their way into the town, their leaders being its bishop and the abbé of Citeaux, who had prepared a list of the proscribed per-



sons. In the confusion of the assault, however, the soldiers were perplexed to distinguish the heretics from the orthodox; "Kill all," exclaimed the abbot; "the Lord will recognise his own" (*Cædite eos, novit enim Dominus qui sunt ejus*). The result was the massacre of every living soul, to the number of 60,000, according to some historians, though the abbot of Citeaux himself, in his letter to Innocent III., humbly avows that he could only slay 20,000.

The chief trade here is in Eau de Vie, produced in the numerous distilleries. On the Promenade is a *Statue* in bronze of Paul Riquet, Baron de Bonrepos, a native of Béziers, the projector of the *Canal du Midi*, which is carried through 9 locks close to the town. (See Route 93.) It opens into the sea, 13 m. S. of this, at Agde, called "Ville Noire," from the black volcanic basalt of which it is built. Agde (*Inn*: Poste; 8,230 inhab.) has a curious *cathedral*, and a cloister, whose arcades are perfect, though walled up. The Herault is here crossed by a suspension bridge.

Hence to Narbonne the country is very uninteresting.

10 Nissan. The Etang de Capetang is passed on the rt., and the river Aude (Atax), which gives its name to the Dépt., is crossed between this and

17 Narbonne. *Inns*: H. de la Dau-rade, good—*E. o. S.*; H. de France.

This very ancient town was the Narbo Martius of the Romans, one of the first colonies established by them beyond the Alps, and capital of the vast province of Gallia Narbonnensis, which extended from the Alps to the Pyrenees. It was the spot where Julius Cæsar settled the remains of his 10th Legion, at the termination of the civil wars, and the "pulcherrima Narbo" of Martial; yet it retains surprisingly scanty vestiges of its ancient masters compared with the importance and celebrity which it maintains in history. Not one Roman

building remains; and the chief traces of its former splendour are the numerous bas-reliefs, friezes, inscriptions, &c., built into the town walls, erected by Francis I., who fortified the place with the ruins of Roman buildings. The ramparts may consequently be looked upon as a museum of antiquities. A local antiquarian society, however, has collected together in a *Museum* within the ancient Archevêché a number of fragments, and several antique tombs of the 3rd and 4th centuries, a bas-relief of 2 Eagles supporting a Garland, &c.

Attached to the *Archevêché*, a heavy castellated building, rises a square tower, the lower part of which, of large cubical stones, dates probably from the time of the Lower Empire, and the upper part from the 8th century. This building retains one curious doorway. Within it Louis XIII. signed the order for the delivery of Cinq Mars and De Thou to a commission named by their enemy the Cardinal Richelieu for trial.

The *Cathedral of St. Just* is a fine Gothic edifice, of which the choir only is finished. It was founded in 1272; the height of the roof is 40 mètres (? 131 ft.). The side chapels were added during the 13th century; and some of the windows having flamboyant tracery are of the 15th. There is a good deal of painted glass in them. The high altar is rich in marble of the country. The magnificent white marble monument of Bishop de la Jugie (1272) is a model of Gothic art of the 13th century, and well worth study. The statues of saints and bishops are admirably executed, "but in the revolutionary frenzy the head of every statue was knocked off, and the Bishop's effigy removed. A monument in the style of the Renaissance, having figures of weepers instead of saints, was left untouched by the infidel devastators." —*E. o. S.* There are other tombs of the 16th cent., and a fine organ of the age of Louis XIII. Repairs and

additions are being made to the building, and the completion of the nave is intended.

Behind the altar are some curious iron seats, in the form of an X, of considerable antiquity. Sebastian del Piombo's "Raising of Lazarus," now in the National Gallery, was painted for this church: there is a copy of it here. The *Church of St. Paul*, founded 1229, may interest the architect. The carved capitals of the columns "on the outside represent monsters, devils, and other objects designed to disgust men with vice, and to remind them of the punishment of the wicked."—*E. o. S.*

Narbonne is a city of 10,792 inhab., but, though once so important, it is now not even chef-lieu of the department. It is about 8 m. from the sea; and a branch of the Canal du Midi, called *La Robine*, runs through it to the Mediterranean. The principal Promenade is an avenue of trees, which lines its side, called *Allée des Soupirs*. Narbonne is an intricate, curious, but lifeless town, though it possesses some manufactures. The *honey* of Narbonne is the best in France; it is very white, and has a highly aromatic flavour. A distant view of the Pyrenees is obtained from hence.

The two great roads, to Perpignan (R. 94) and to Toulouse (R. 93), branch off from this. *Diligences* traverse both daily.

The *Canal du Midi* is shortly described in R. 93.

### ROUTE 127.

NISMES TO MARSEILLES AND NICE, BY  
BEUCAIRE, ARLES, TOULON, AND  
HYÈRES.

*Railway* from Nismes to Beaucaire and Marseilles (1848); trains 4 times a-day, and 10 or 12 times during the fair of Beaucaire; it takes carriages; the journey to Beaucaire is performed in 35 min.; the distance 24 kilom. = 15 m. This railroad is carried through

olive-grounds and vineyards, and, on approaching Beaucaire, is terraced along the shoulder of a hill overlooking the muddy Rhône, and the canal leading to Cette. It passes one or two small tunnels and cuttings.

A *post-road*, which saves 16 m., has been made direct from Nismes to Arles, crossing the Canal de Beaucaire and the Rhône, by

17 Bellegarde (about 7 m. S. of this lies St. Gilles, see p. 475).

15 ARLES, and avoiding Beaucaire altogether.

[The old and longer post-road from Nismes is carried through

11 Curbussot to

Beucaire (*Inn*: H. du Grand Jardin, tolerable), where there are no post-horses; and it is therefore necessary to cross the Rhône to

15 Tarascon, described in R. 125.

There are 2 roads hence to Marseilles, either by St. Remy (16 kilom.), whose 2 Roman buildings are described (R. 125, p. 463), and Orgon, 18 kilom. (in R. 128), or along the l. bank of the Rhône to

17 ARLES (in R. 125), and by the Railway (R. 129).

The road on issuing out of Arles passes the antique Necropolis of Aliscamp (p. 467), and near an aqueduct, comprising part of the line of a Roman one, which conveyed the waters of the Durance by St. Remy to Arles. Between Arles and Salon our road traverses the *Crau*, a singular stony plain extending S. to the Mediterranean, covered all over with rolled boulders and pebbles, deposited doubtless by the Rhône and its tributaries, especially the Durance, under circumstances differing from their present physical condition. This "campus lapideus" was well known to the ancients; not only is it described by Strabo, Pliny, and Mela, but Æschylus, in a fragment preserved by Pomponius Mela, lays on it the scene of the combat between Hercules and the Ligurians, when the son of Jove, having exhausted his arrows, was supplied with artillery from heaven



by a discharge of stones from the sky, sent for his use by Jupiter.

Ἰδὼν δ' ἀμυχανοῦντα σ' ὁ Ζεὺς οἴκτερεῖ,  
νεφέλην δ' ὑποσχών νιφάδι στρογγύλων  
πέτρων

ὑπόσκιον θήσει χθόνα, οἷς ἔπειτα συμ-  
βαλῶν δηώσει ραδίως λίγυν στρατόν.

One ancient writer remarks that the assistance of Jupiter would have been more effectual had he showered down the stones at once on the heads of the Ligurians. Such is the mythological history of the Crau. Its modern name is traced by some to the Celtic *craig*, a rock (?). "It is composed entirely of shingle, being so uniform a mass of round stones, some to the size of a man's head, but of all sizes less, that the newly thrown up shingle of a sea-shore is hardly less free from soil; beneath these surface-stones is not so much a sand as a cemented rubble, a small mixture of loam. Vegetation is rare and miserable; some of the absinthium and lavender so low and poor as scarcely to be recognised, and 2 or 3 miserable grasses, with *Centaurea calycitropes* and *solstitialis*, were the principal plants I could find."—A. Young.

Through the greater portion of its extent its condition is that of a semi-desert; but under the stones which cover it grows a short sweet herbage, which the sheep accustomed to the locality obtain by turning over the stones. It is consequently covered over in the winter months with flocks driven hither from the French Alps, where they spend the summer, passing annually to and fro like the merino flocks of the Mesta in Spain. There the practice of migrating from the plains to the Pyrenees, and *vice versa*, is as old as the 7th century. Here, however, it must be traced to a far earlier period, since it is mentioned by Pliny, "e longinquis regionibus pecudum millibus convenientibus ut vescantur."

The small portion of the Crau which can be reached by irrigation

is exceedingly fertile, producing vines, olives, mulberries, and corn. Arthur Young says, "The meadows I viewed are among the most extraordinary spectacles the world can afford, in respect to the amazing contrast between the soil in its natural and in its watered state, covered richly and luxuriantly with clover, chicory, rib-grass, and avena elatior." The chief means by which this useful purpose is effected is the *Canal de Craponne*, so called from its projector, who began it in 1554; it is cut from the Durance at a place called La Roque, and extends to the Rhône at Arles, a distance of 33 m., sending out branches to Salon and elsewhere. The whole agriculture of the district depends upon this canal, as Egypt does upon the Nile: it is besides of no small use in turning oil and corn mills. It is followed for a considerable distance, and crossed, by our road. Previous to its construction the stony desert reached up to the very outskirts of Arles and Salon. In the remoter and uncultivated parts of the Crau, the *Mirage*, which so often in the African deserts cheats the parched traveller with the appearance of inland lakes in spots most destitute of water, is of frequent occurrence. The irrigation and evaporation from a vast body of stagnant water renders this district very unhealthy, and the funereal cypresses, thickly planted around all the houses, are symbolic of the fate of their inhabitants, worn out with fever and ague.

17 St. Martin is a solitary post-house. The plain ends and hills are reached near

23 Salon.—*Inns*: Poste;—Croix de Malte. Avoid stopping here; the accommodation is very bad.—*G. B.* This is a rather considerable town of 6000 inhab., carrying on an important trade in olive-oil. The high road is carried through a sort of Boulevard, in the neat modern quarter enclosing the old town; and passes the *Castle*, said to be that of Nostradamus, now a barrack. That celebrated astrologer

died here 1566, and is buried in the parish church, a handsome Gothic building.

The road hence to Aix is billy; it passes on the l. the Château de Labarben, a striking edifice of large size, part modern, but flanked by feudal towers, belonging to le Marquis de Forbin. At

18 St. Canuat (H. au Berceau de l'Amiral Suffrein—execrable, J. O.) we enter R. 128, and follow it to

16 Aix, described R. 128. A road, shorter by 18 kilom., but very bad, runs from Salon to Marseilles by Tête Noire, 21; l'Assassin, 14; Marseilles, 14—some fine views of the sea.

A considerable range of hills intervenes between Aix and the sea-coast; the sandy and dusty road, cut up by carts, is generally in bad order; it passes on the rt. the Château of Albertas, and on the l. the older feudal tower, belonging to its former owners; and, constantly mounting higher and higher, reaches the relay of

14 Le Pin. At the hamlet of Les Tours, 3 m. from Marseilles, it reaches the brow of a hill called *la Vista*, from its beautiful view of the Mediterranean, whose deep blue compensates in part for the want of verdure on the land. From this height the city of Marseilles, and its countless *Bastides*, or country-houses (see p. 488), and the islands off the harbour-mouth, are well seen, while a clump of umbrella-pines forms a pleasing foreground. Down this hill the road proceeds by an uninterrupted descent into the suburbs of

15 MARSEILLES.—*Inns*: H. des Empereurs, on the Cannebière, newly fitted up;—H. de Noailles, clean and select;—H. d'Orient, *M.*;—H. Beauveau, improved;—H. de Paradis, Place Royale, good.

Marseilles, capital of the Dépt. des Bouches-du-Rhône, is a busy and flourishing city, and the most important sea-port of France, having a population of 183,186 souls; but it has few fine public buildings or sights

for strangers. The entrance from the side of Aix is by an *Arch of Triumph*, not remarkable for elegance of design, originality of elevation, or elegance of decoration. It was intended to commemorate the campaign of the French in Spain in 1823, but its destination is now changed to that of celebrating "all the glories of France." From this arch a fine broad street, called the Cours and Rue de Rome, stretches entirely across the town to the Porte de Rome. Near the centre of it another wide street, called Rue de la Cannebière (Κάνναβις, *flax*), strikes off from it at right angles, down to the *Port* or *Harbour*, a natural oblong basin 1000 yards long by 330 broad, extending into the heart of the town, occupying an area of 45,000 mètres (nearly 70 acres), about equal to two of the docks at Liverpool. The depth of water varies from 18 ft. at its mouth to 24 ft., and it is capable of holding 1000 or 1200 merchant vessels. This is the focus of that extensive commerce which renders Marseilles the first sea-port of France and of the Mediterranean. The number of vessels entering and quitting in a year amounts to 18,000, and their tonnage exceeds 2,000,000 tons, about one-fourth of that of Liverpool: 633 vessels, of 53,973 tons, belong to the port. To this harbour Marseilles is indebted for her commercial consequence, which dates nearly 3000 years back, from the days when the Phocæans first set foot on her shore, inoculating the barbarous realms of W. Europe with the civilization of the East. The connexion of France with Algiers has given a great impetus to the prosperity of Marseilles, as it engrosses nearly the whole trade with the new colony in Africa. It has risen also to considerable importance within the last 12 years as a steam-packet station (see p. 489). A *new Harbour* (le nouveau Port) is being constructed a little to the N. of the old works, and it is a stupendous undertaking. It is formed by a break-



water, 1224 yards long, thrown into the sea parallel to the shore, and at a distance of 1312 feet from it: 2 moles or piers stretch from the shore towards it, at a distance of 550 yards from each other, but leaving openings for the entrance of vessels. This will form an inner basin and 2 outer harbours, and they will be connected by a canal, running behind Fort St. Jean, with the old Port.

From the margin of the old harbour, lined with quays, the ground rises on all sides, covered with houses, forming a basin or amphitheatre, terminating only with the encircling chain of hills. From this disposition of the ground, the port becomes the sewer of the city—the receptacle of all its filth, stagnating in a tideless sea and under a burning sun, until a S. E. wind produces that circulation in its waters which the tide would do on other seas. The stench emanating from it at times is consequently intolerable, except for natives; and dredging-machines require to be constantly employed to cleanse it. Were it not for this, its *Quais* would be an agreeable walk, presenting as they do an amusing scene of bustle and variety, Greek, Turkish, and Neapolitan costumes; among its shipping, the picturesque latteen sails of the Mediterranean are very common.

The direction of the old harbour is from E. to W. On its N. side, and within the angle formed by the Rue Cannebière and the Cours, lies the old town of narrow dirty streets, scarce worth entering. In the line of the quay, on this side, stands the *Hôtel de Ville*, a heavy building, and overloaded with tasteless ornaments, attributed to Puget, but not by him, his really beautiful design having been rejected. Farther on, near the harbour mouth, is the *Consigne*, or health office, where everything relating to quarantine is transacted, and whence the permission for vessels to enter the harbour is issued. To this office the captains of vessels come to give an account of themselves (*raison-*

*ner*), and to show their bill of health. The council-room contains a few paintings, chiefly having reference to the plague: by *Girard*, the Plague at Marseilles, in which Bishop Belzunce is introduced; and another showing the self-devotion of the Chevalier Rose in burying the dead, when even the galley-slaves had refused; by *David*, St. Roch healing the Sick; a bas-relief, by *Puget*, of the Plague at Milan; the Cholera at Marseilles by *Vernet*; the Yellow Fever at Barcelona, 1822. The subjects are all horrible, and the execution not good enough to compensate.

The mouth of the old port is narrow, and was once closed by a chain. It is defended by two forts: on the N. by the old castle and tower of St. Jean, built in the 15th century, in which Philippe Egalité was imprisoned with his youngest son, and whence they after a time escaped; on the S. the *Fort St. Nicolas*, recently repaired and extended, guards the entrance. It was founded by Louis XIV., who, after capturing the disobedient city, and entering it by a breach in the walls, observed that “he also would have a Bastide at Marseilles;” and forthwith laid the foundation of this fort, of which the first stone bore the inscription—“*Ne fidelis Massilia, aliquorum motibus concitata vel audaciorum petulantia, vel unicâ libertatis cupiditate tandem ruerit, Ludovic. XIV. optimatum populique securitate hâc arce prodixit.*” Close beside Fort St. Nicolas a new wet dock, Bassin de Carénage, has been formed, by costly excavations out of the rock, on the site of an ancient cemetery.

Not far from this is *St. Victor*, the most ancient church of Marseilles, though its crypts and substructures alone are of the 11th century. The upper part dates from 1200, except the two battlemented towers, which give it the air of a castle, erected, 1350, by Pope Urban V., who had been abbot of St. Victor. The entrance under the tower is by a round

arch: near it is a curious pointed arch, its mouldings relieved with the dog-tooth ornament. St. Victor was one of the most celebrated abbeys in Christendom, and possessed a host of other abbeys and religious houses dependent on it.

Above St. Victor, to the S. of the town and harbour, rises the bare rocky hill of *Nôtre Dame de la Garde*, so called from the curious *chapel* situated within a small fort on its summit, a spot exposed to all the winds that blow. An image of the Virgin, carved in olive-wood, and of great antiquity, is enclosed within this humble shrine; it is held in the highest veneration throughout the Mediterranean by the sailors and fishermen and their wives, and its walls and roof are hung with ex-votos, chiefly paintings representing moving accidents by flood and field—all the veriest daubs, but very curious, as illustrating the religious feeling of the people. Besides a vast number of shipwrecks, storms, steam-boat explosions, escapes from British vessels of war, there is a whole host of surgical operations, sick-beds, road-side accidents, &c. The cholera panic produced numerous offerings; among them a silver tunny-fish, presented by the Marseillaise fishwives. Many ostrich-eggs and models of ships are suspended from the roof, and one corner is filled with cast-off crutches, the gifts of grateful cripples now no longer lame, and with ropes' ends by which men have been saved from drowning! The silver statue of the Virgin, 4 ft. high, over the altar, is modern.

The view from the top of the hill, beside the chapel, is perhaps the best that can be had of Marseilles itself, spread over a gradually-sloping basin, surrounded by hills which are covered with vineyards and olive-gardens, and speckled with white country houses, called *Bastides*, to the number of 5000 or 6000, belonging to the citizens and shopkeepers. It is an arid prospect of dazzling white, in-

terspersed, but unrelieved, by dark streaks of dusky green. From this the eye is delighted to turn and repose upon the deep blue of the Mediterranean, the graceful curves of the coast of the gulf of Lyons, and the little group of islands, *If*, crowned by a *castle*, once a state prison, in which Mirabeau was shut up, and Pomègue and Ratoneau, behind which a fleet of vessels in quarantine find shelter. The stripe of blue sea is prolonged into the heart of the city in the harbour, partly hidden from view by its forest of masts.

The Fort de la Garde was built by Francis I., and was never of great importance as a defence: hence the verses,

“Gouvernement commode et beau,  
Où l'on ne voit, pour toute garde,  
Qu'un Suisse, avec sa hallebarde,  
Peint sur la porte du château.”

Along the lower slope of the same hill, within the town, stretches a wide promenade planted with trees called *Cours Bonaparte*; and lower down, at the water-side, stands the *Custom-house*, with its piles of warehouses, isolated by a canal cut round it from the port.

The *Prado* is a handsome and very agreeable public walk and drive, a prolongation of the Rue de Rome by the sea-side, 3 Eng. m. It commands a fine sea view.

The *Museum*, situated beyond the Marché aux Capucins, contains the few relics of antiquity which alone remain of the time-honoured city *Massilia*, founded (B.C. 578) by Phocæan exiles flying from Asia Minor. In spite of its wealth, power, and progress in civilisation, the ancient city has left no remains of buildings, nor any traces of its existence beyond inscriptions (some in Greek), sarcophagi, mostly of the 5th, 6th, and 7th centuries, and a few fragments of sculpture. Among the antiques is a draped torso of a female with a child, wearing a peaked cap, of Greek workmanship; a marble sarcophagus (No. 13) brought from Arles, sculp-



tured with a combat between centaurs and lions: several Christian tombs, brought, for the most part, from the crypt of St. Victor; one (No. 27) of marble, designed for a child, contained the relics of St. Victor, and seems to be the most curious; another of Abbot Isarn (d. 1048), whose effigy is covered with his epitaph in Latin verse, allowing only his head, which exhibits the tonsure, and the feet to appear. None are so old as the capture of the city by Julius Cæsar.

The *Picture Gallery* in the same building contains about 150 very badly lighted pictures, of which the following seem the best:—St. John carried up on the Eagle, inspired to write the Revelations; a portion of the isle of Patmos appearing below: a copy after *Raphael*. The 3 Maries, as mothers, with St. Joseph, St. Cleophas, St. Simeon, &c., by *Perugino*: a very pleasing and genuine picture, though faded; very like Raphael's early manner. *Rubens* (perhaps by Jordaens): a boar hunt; spirited, but the figures rather huddled together. A Prince of Orange with his family, attributed to Rubens. Lord Strafford, a copy from Vandyk. One or two small paintings by *Puget* merit notice, as he was a native of Marseilles, and architect and sculptor as well as painter.

It is remarkable that so extensive and wealthy a mercantile community as that of Marseilles should not possess a permanent *Exchange*, yet the bourse is a mere temporary structure of wood and canvas, not much better than a show-booth in a fair. In front of it is a fountain of heavy design, basins resting on griffins. Some wag wrote upon them, when the fountain was first erected, "N'approchez pas, ils sont mauvais."

Another fountain surmounted by a bust of Homer bears this inscription: "Les descendants des Phocéens à Homère, 1803." !!

The *Lazaret*, to the W. of the port, is a well-regulated establishment; one of the first placed on a sound footing

in Europe, and so large that it held the entire French army on its return from Egypt. It covers an area of 50 acres, is enclosed within a double wall, and is of course not accessible to any persons but such as enter it for quarantine.

A Breakwater has been thrown between the islands of Pomègue and Ratonneau, connecting them together so as to form a quarantine roadstead, called *Port du Frioul* (fretum Julii). At this spot Cæsar's squadron, under the command of D. Brutus, was stationed during the siege of Marseilles.

If a case of plague shows itself, the vessel is sunk and the goods burned. Merchandise is released from quarantine after exposure to the air, and especially to the dew. The Lazaret owes its foundation to the fearful ravages of the *plague at Marseilles* in 1720, which destroyed between 40,000 and 50,000 persons, *i. e.* half the population of the town. Amidst the general despair, selfishness, and depravity, which accompanied this dire calamity, many individuals distinguished themselves by their noble self-devotion. One of them has been commemorated by Pope:—

"Why drew Marseilles' good bishop purer  
breath  
When nature sicken'd, and each gale was  
death?"

The name of the good bishop was *Belzunce*, who offered a rare example of courage and piety by his intrepid intercourse with the sick in the hospitals, where, aided by pious nuns, he constantly ministered to the support and consolation of the plague-stricken inmates. The 2 *échevins* of the town, Estelle and Moustier, likewise exposed their lives. The streets soon became choked with dead, and of the galley-slaves, supplied at the rate of 80 a-week to conduct the dead-carts, none survived. The Chevalier Rose with his own hands then helped to bury the dead, when the very galley-slaves refused the dangerous duty. 3 physicians, also, from Montpellier, repaired to the city of death to aid

the sick and dying, when all the native doctors were dead or had fled. The pestilence, which had broken out in the spring, continued with dreadful fury till September, but abated after a violent storm, and disappeared in November.

One of the chief *manufactures* here is that of *soap*, which is said to employ 700 men. The process is worth seeing, and, as it is made exclusively of vegetable oil, it is not so unsavoury as in England. The manufacture of *Coral*, celebrated in the earliest times, has greatly fallen off, and has been transferred to Leghorn, Genoa, and Naples. Shipbuilding is a very important branch of trade. The manufactory of steam-engines, belonging to Mr. Philip Taylor and Sons, is one of the most considerable in France.

The fish-market displays a number of the finny inhabitants of the Mediterranean unknown in the seas of the N.; among others, the tunny is abundant at certain seasons.

The *climate* of *Marseilles* for a large portion of the year is delightful, but in summer and autumn the heat is at times intense—the streets like an oven, so that it is scarcely possible to move abroad during the daytime, and all rest during the night is liable to be destroyed by the *mosquitoes*. To this not unfrequently succeeds the *Mistral*, or cutting dry N. E. wind, whose effects are described p. 437. The N. W. wind, called *le Libech* (Ital. Libeccio), exercises a terrific force over the Mediterranean.

*Consuls* reside here from the principal states of Europe and America. Mr. Turnbull is the worthy representative of England.

The *English Church Service* is sometimes performed at the French Protestant Church, in the Rue Grignan, on Sundays, but there is no resident clergyman. “Dr. de Chargé is a very clever homœopathic physician.” —*E. o. S.*

Baths. The *Bains de la Méditerranée*, about 1½ m. out of the town, on the S. of the road to Aix, in an agree-

able situation, commanding a view of the bay, and receiving the sea-breeze, is a well-conducted establishment. There are other baths, even superior, at the extremity of the Prado.

With this exception the *Environs of Marseilles* possess but slight attractions—nothing but dust, scorched rocks, and bare high walls, amidst which the eye in vain seeks for some verdure to rest on. The *Bastides* already mentioned are little country boxes, which entirely dot the slopes around the town, prolonging it apparently to the tops of the surrounding hills. Some of them are handsome, and surrounded by gardens, but the greater part stand in mere bare enclosures, between 4 walls, destitute of shade and water, their only recommendation being that they are out of town. Every merchant, citizen, or shopkeeper must have one, and their number is said to exceed 6000. The stupendous *Canal* to supply *Marseilles* with *water from the Durance* will entirely alter the aspect of the country around the town, by the irrigation which it will furnish. Travellers should visit the *aqueduct of Roquefavour* (see p. 495). It will take a day to go and return.

A common excursion is a “promenade sur eau,” from the harbour’s mouth to the islands of If, &c. (p. 486). Courty’s Restaurant, “La Muette de Portici,” at the *Prado*, on the beach, 2 m. out of *Marseilles*, affords a good specimen of la Cuisine Provençale.

Some of the best shops are in the Rues St. Ferréol, Beauvau, and Paradis, and the *Post Office* is in a street running out of it, Rue Jeune Anacharsis. Letters reach this from England on the 6th day.

*Railway* to Avignon (Rte. 129). Terminus not far from the Arc de Triomphe.

*Malleposte* daily to Paris by St. Etienne in 59 hours (3 days); to Lyons in 24 hours; to Nismes and Toulouse in 29 hours.

*Diligences* daily to Lyons (5 or 6)



in 34 hours, and to Paris in 66 hours ; to Aix, Avignon, Nismes ; to Arles and Tarascon ; to Toulon and Nice ; to Grenoble in 38 hours.

#### *Steamers.*

To *Italy* 12 to 15 times a-month ; Government mail, and several Companies, touching at Genoa, Leghorn, Civita Vecchia, Naples, and Sicily.

To Leghorn, Civita Vecchia, and Naples (Gov.), 3 times a-month.

To Malta, Piræus, Smyrna, Constantinople, 3 times a-month.

To Malta, Alexandria, and Beyrout, 3 times a-month.

To *Spain*, Barcelona, Valencia, Malaga, Gibraltar, 3 or 4 times a-month ; to Cadiz 3 times a-month.

To *Algiers* (Gov.) 6 times a-month.

To *Corsica*, Ajaccio and Bastia, once a-week.

To *Cette* twice a-week.

To *Malta* and *Alexandria* (British Gov., with India mail and overland passengers) the 11th of every month. Takes the mail despatched from London on the 7th of the month, and reaches Malta in about 70 hours, or 3 days, *i. e.* on the 15th of the month. Fare, 1st class 9*l.*, 2nd class 5*l.*

To *Arles* and the *Rhône*, several times a-week.

To Cannes and Nice weekly.

*History.* Classical tradition assigns the foundation of *Massilia* to a colony of Phocæans, who left their native country, Asia Minor, with their wives and children, rather than submit to Cyrus, and sought for liberty on the then barbarous shores of Gaul. Their emigration (B. C. 5) is described by Herodotus, and alluded to by Horace :—

“ Phocæorum

Velut profugit execrata civitas,

Agros atque lares patrios, habitandaque rura

Apris reliquit et rapacibus lupis :

Ire pedes quocunque ferent, quocunque per undas

Notus vocabit, aut protervus Africanus.”

Favourably received by the inhabitants of the country, the settlement increased and prospered ; became

great in commerce and navigation, eminent in the arts and literature ; was sought and esteemed by Rome as an ally, until, wishing to remain neutral in the wars between Cæsar and Pompey, and finally siding with the latter, she was besieged, taken, and reduced to great distress by his successful antagonist, who records that he preserved it “ magis pro nomine et vetustate quam pro meritis in se.”—*Cæsar*. Lucan has described the siege, but evidently without local knowledge. Cicero says, in his Oration for Flaccus, that Greece alone could compete with Marseilles as a seat of learning ; Tacitus calls her “ magistrum studiorum.” Her importance continued during the middle ages ; she formed a sort of independent state, electing her own magistrates, and forming alliances with other states. She furnished alone all the galleys required by St. Louis to transport his army on the Crusade. The famous commercial code *Le Consulat de la Mer* is supposed to have been drawn up here. At length, conquered by Charles d’Anjou, Comte de Provence, she yielded to the rising superiority on the sea of Pisa, Genoa, and Venice.

Marseilles held out against Henri IV. long after Paris had submitted ; when at length he was informed of its surrender, he exclaimed, “ C’est maintenant que je suis Roi.” Yet was its turbulent spirit of independence not subdued, since, in consequence of an outbreak against Louis XIV., that monarch entered the city by a breach in its wall (see above, p. 485).

At the Revolution, which inflamed to madness the fiery spirits of the people of the south, among whom moderation and restraint are unknown or little practised, Marseilles furnished, from the dregs of its own population, and the outcasts of other lands, the bands of assassins who perpetrated the greater portion of the September massacres in Paris. The Reign of Terror at Marseilles itself,

under the rule of the infamous Fréron and Barras, produced more than its usual proportion of atrocities and follies. The usual wholesale murders were committed, amounting to 400 persons, attended by confiscation of their property.

But not satisfied with this, it was proposed by one of the Représentants du Peuple to fill up its harbour. The name of Marseilles was absolutely abolished by a decree, which enacted that it should pass under the denomination of "la Commune sans Nom!" Even the death of Robespierre, which, for the most part, put an end to the Reign of Terror in other places, was here and elsewhere in the south the signal for fresh assassinations. Vengeance against those who had been the instruments of the revolutionary massacres was now the cry; the Fort St. Jean, in which about 200 of them had been confined, was broken open, and they were all murdered by an irritated mob of insurgents, employing cannon loaded with grape, to finish their victims in their cells.

Marseilles is the birth-place of Mascaron the preacher, of Bishop Belzunce, and of Puget, the architect who built the old British Museum.

It takes about 5 hours to post from Marseilles to Toulon (40 m.). The first part of the road is dreary so long as it runs between white stone walls which enclose Bastides and intercept all view and fresh air. "The most dusty road I ever saw; the vines for 20 rods on each side like a dressed (powdered) head: the country all mountains of rock with poor pines." —*A. Young.*

17 Aubagne. Near this a little verdure is visible in the pretty vale of Gemenos. The Abbé Barthélemy, author of the "Voyages du Jeune Anacharsis," was born at Aubagne.

The caper, a pretty flowering plant, is cultivated near

12 Cujes, a miserable-looking town (like most of those on the road) of 3000 inhab., but the country

around most productive and well cultivated.

A hilly road leads to the poor town of

13 Beausset, in the Dépt. du Var. The sea is now and then seen through breaks on the rt.

About 3 m. farther the road penetrates the mountains, through a deep chasm or defile of wild and savage features, called the *Pass of Ollioules*. Bare, bleached, and nearly precipitous rocks of limestone, surmounted by a ruined *Castle*, which once guarded the passage, hem in on either side, for a distance of nearly 3 m., a scene of desolation, nakedness, and solitude. On emerging from it, the landscape is more cheerful; the orange-tree is first seen; the pomegranate grows in the hedges; the olive-trees, the cactus, and palm occur at intervals in the favoured region, sheltered from the N. by the Estrelle, extending hence to the Var.

17 *Toulon.*—*Inns:* Croix de Malte, improved, civil people and good cuisine; Croix d'Or, very good, table-d'hôte 3 francs at 5; Hôtel de France.

Toulon is the Plymouth of France, the seat of her naval power in the Mediterranean, and one of her chief naval arsenals, inferior only in some respects to Brest. It is a strongly fortified town, situated at the bottom of a deep double bay, which forms the roads. Behind it runs an amphitheatre of hills rising on the N. into the heights of Mount Pharon, too bare to be picturesque, which stretch their arms as it were round the bay, so as nearly to landlock it, rendering it a safe anchorage, except from the S. and E., where it is somewhat unprotected. 6 forts on the land side defend the town, while the mouth of the harbour and hills commanding it are studded with forts and redoubts.

The *Port* is divided into the old and new, separated from the roadstead by moles, hollow and bomb-



proof, begun in the reign of Henri IV., formed externally into batteries on a level with the water's edge,—very formidable against ships. The Port du Commerce, or *Darse Vieille*, on the E., is appropriated to merchant vessels, and is bordered by a quay. The *Darse Neuve*, on the W., is surrounded by the dockyard, slips, the arsenal, the storehouses for provisions, &c., equipments, cannon foundry, park of artillery, &c.

The town itself contains 39,243 inhab., exclusive of the garrison; but, confined within ramparts, its streets are narrow, its shops inferior, and its buildings (exclusive of those of the dockyard) unimportant.

The *Hôtel de Ville*, facing the harbour, is ornamented in front with two colossal thermæ, serving as caryatides to support a balcony, executed by *Puget*, and of good design. Behind the *Hôtel de Ville*, at the corner of the Rue d'Orléans, is a house built by that variously accomplished artist.

The dockyard and fleet of Toulon were destroyed by a British force under Sir Sidney Smith, detached from the fleet of Lord Hood, in November, 1793, previously to the evacuation of the town by the British. It was a work of danger, as the republicans, having already gained possession of the surrounding forts and heights, poured in a merciless hail of shot and shells; and the work was but imperfectly performed, that is to say, the great magazine and several vessels on the stocks escaped. 27 vessels were destroyed, being ignited in the harbour by a fire-ship, 2 of them blowing up; 15 ships were brought away. It must be remembered that the English gained possession of Toulon not by force of arms, but by convention with the royalist portion of its inhabitants, on condition of their being protected from the cruel vengeance of the republicans. But the means at the disposal of Admiral Hood, a fleet of 21 ships, aided by a Spanish squa-

dron of 17, were totally inadequate to effect this; 5000 British troops, the amount of his land force, were far too few to garrison so vast an extent of works, and little good was done by our 8000 Neapolitan and Spanish allies. Although the surrounding forts were manned and put into a state of defence as far as possible, the important pass of Ollioules, commanding the only approach to Toulon from the W., was left unguarded, and the republican forces, reeking from the massacres of Lyons and Marseilles, marched in and speedily invested the town to the number of 50,000, breathing vengeance against the inhabitants of Toulon for the defection of a place so important. When at length, at the end of 3 months, the harbour became no longer tenable, and the British fleet was obliged to weigh anchor, nearly 15,000 of the inhabitants were embarked on board the British fleet, by the light of the burning ships and dockyards, amidst the cries and groans of the multitude that remained behind, praying for the means of escape from the hands of the merciless republicans. Nor were their worst anticipations unfounded: more than 6000 miserable victims were sacrificed to the vengeance of the agents of the Committee of Public Safety, in spite of the remonstrances of Dugommier, the French general, and his lieutenant Buonaparte. With such blind rage did the besieging soldiery rush into the town, that they murdered, without question, 200 Jacobins who had gone forth to meet them. The horrors of the fusillades and the butcheries of the guillotine were then exercised against the inhabitants with a blind rage, which did not wait to distinguish those who had opposed from those who had favoured the English. Fréron and the other members of the Committee of Public Safety, including the younger Robespierre, presided in person over the fusillades (thank God, the word has no equivalent in English). They sent orders for 1200 masons to raze

the town of Toulon, but their commands were only partly carried into execution, and they decreed that its name should be abolished, and that it should in future be known only as Port de la Montagne.

The *Dockyard* (Port Militaire), entered from the town by a handsome and appropriate gateway, is not readily shown to foreigners; the introduction of the English consul will, generally, obtain admission for Englishmen. Excepting, however, the *Bagne*, or prison for the *forçats* (convicts), they will see nothing here that they may not see as well at home, at Portsmouth or Plymouth, &c. The description already given of Brest (Route 36) renders a further detailed account of a French dockyard unnecessary. This arsenal covers a space of 55 acres, of which 35 are occupied by the Basin, which has a depth of water throughout for the largest ships fully equipped. In 1841, 13 vessels were building here; only 2 of the slips (cales) are roofed; but there are nearly twice as many vessels laid up in ordinary here as in any other French port. The store of oak timber is very large. The rope-house (*corderie*) is nearly 1200 ft. long, of 3 vaulted aisles of masonry, fire-proof, except the floor. In the centre of the surface of the yard is an opening out into the Petite Rade, and a line-of-battle ship fully armed and stored may sail at once from the basin or port right out to sea. Immediately after crossing this opening on the rt. is *Le Bagne*, a large airy building. The number of *forçats* here varies from 3000 to 3500; they are most rigidly superintended, chained each night to their beds, as at Brest, and there are loopholes for guns in the walls at the extremity of the dormitory, which would sweep it from end to end in the event of a mutiny. The number of free workmen, in 1841, was about 4500.

The *Musée de la Marine* contains a large collection of models of inventions, ship-building, &c.

“2 first-rate Docks have been constructed at the S. angle of the Basin. They are not excavations from the land, but formed by quays carried into the port. A large frame of wood (*caisse*) was sunk with ballast at the spot and of the size of the dock, and the masonry was built in around it.” — *W.*

A new or supplemental dockyard has been formed at Mourillon, in the S. of the town, between it and Fort la Malgue; here are 5 large slips.

The *Roadstead* and *Harbour* is the most picturesque and interesting feature about Toulon, and the views of it from the neighbouring heights are very pleasing. A small *steamer* plies across to the village of la Seyne. The inner road is divided from the outer by 2 capes or headlands; that on the E. is defended at its point by an advanced fort, called Grosse Tour, and on its neck or root, between the little and great “Rade,” stands the strong *Fort la Malgue*, surrounded by ramparts 30 ft. high, capable of holding 800 men, and defended by 200 pieces of cannon. Opposite to this, from the W. side of the bay, stretches forth a two-horned hilly promontory, the two points of which are occupied by the strong forts of *Eguillette* and *Ballaguer*, at the water's edge, while the commanding heights, de Caire, above them are crowned by the Fort Napoleon, which replaces the field-works of 1793, styled *le Petit Gibraltar*, and which is the key of the whole defences. *Eguillette* was regarded as the key of the British position in 1793, but was occupied by a garrison of which unfortunately only a small part were British, the rest Spaniards and Neapolitans. After keeping possession of it between 3 and 4 months, in spite of the besieging French force from without, on the 16th of December a range of batteries, which had been formed secretly by the French and concealed behind the olive-gardens, suddenly opened their fire upon le Petit Gibraltar and the Fort Eguil-



lette from the heights behind, throwing, in the course of 36 hours, 8000 shot and shells. Early the next morning the French, led by Dugommier, their commander-in-chief, advanced to the attack, but were so warmly received that, at first, there seemed no hope of success, until the brave Muiron, followed by his men, entering by an embrasure on the side of the line intrusted to the Spaniards, overpowered them, and cut to pieces the British detachment of 300 men.

The planner of this attack, the constructor of the concealed batteries which now opened by hundreds of fiery mouths from the crests of all the hills upon the detachment of the allies below, was a young officer of artillery, aged 23, named Buonaparte, who for the first time received a command and enjoyed an opportunity of displaying his vast military genius on the heights above Toulon. On arriving 2 or 3 months previously to take the subordinate command, he found that the incapables who had preceded him had raised their batteries at a distance of 2 gun-shots from Toulon, and were directing vain efforts against the place itself. His quick eye at once perceived the defect, and singled out the points where an impression was to be made. In 5 or 6 weeks, under his directions, batteries were constructed, mounting 200 pieces of cannon, on the heights of Brégaillon, Evesca, and Lambert, commanding the forts held by the British. While awaiting the time when all should be ready to make his great effort, the Representatives of the People, discovering so many guns lying idle, would have caused an immediate cannonade, and would in their ignorance thus have spoiled all. Then it was that the young officer had the boldness to reply to one of them, Barras, "Tenez-vous à votre métier de Représentant, et laissez-moi faire le mien d'artilleur. Cette batterie restera là, et je répons du succès sur ma tête." He promised that, in 2 days after gaining the fort, Toulon

would fall, nor was he wrong: the morning after the capture of Petit Gibraltar, Eguillette, and Fort Pharon (an important work on the heights to the N. of the town), whose guns together swept the roadstead from end to end, the British and Spanish fleets had weighed anchor, and were standing out to sea.

A previous attempt was made upon Toulon, in 1707, by the Austrian and Sardinian army, under Prince Eugene and the Duke of Savoy, aided by an English and Dutch fleet, under Sir Cloudesley Shovel; but after an ineffectual bombardment of the town, they found it so stoutly defended that they were compelled to retire.

Messrs. Taylor, English engineers, have contracted to deepen the roadstead by the removal of  $8\frac{1}{2}$  million tons of gravel and mud.

The *Outer Road* is formed by a hilly peninsula, stretching from W. to E., terminating in Cap Sepet, corresponding with Cap Brun on the opposite side of the bay.

There is an extensive *Naval Hospital* at St. Mandrier, on the S. side of the roadstead, farthest from the town, a splendid building with 2000 beds. Near it is the Lazaret.

A *Government Steamer* every week to Algiers, but takes no passengers except French officers.

*Steamers* twice every week to Corsica, touching at Ajaccio (22 hours' passage) and Bastia (24 hours) alternately.

The *view* from the hill to the S.E. of Toulon, on which stands Fort la Malgue, is one of the finest in the S. of France.

The *Botanic Garden*, outside the town, is worth a visit, on account of the number of plants of tropical or southern countries which here first begin to flourish in the open air; among others, the date-palm. Several palms may also be seen in the neighbourhood of

18 *Hyères* (*Inns*: H. des Ambassadeurs, civility and comfort—C. S.; H. de l'Europe), a town of 4591

inhab., on the slope of a hill, crowned by ruins, sheltered from the mistral by the chain of Les Maures, so that it enjoys a temperature nearly as mild as that of Nice. It faces the Mediterranean, but is separated from it by an intervening space, partly common, partly marsh, 3 m. broad: hence it enjoys little view of the sea.

The mildness of its climate causes Hyères to be chosen as a winter residence for invalids, but the exhalation from the marshes and lagunes, in which the sea-water mixes with the fresh, in summer renders it unwholesome. The place has certainly been too much cried up in other respects: there is little beauty in its situation, and its vaunted orange-groves, where alone in France the orange bears fruit, though a novelty to strangers from the N., are not an agreeable feature in the landscape, the trees being shut up in walled gardens. The palm-tree, of which there are 4 or 5 in the neighbourhood, produces no fruit in this latitude. The old or upper town, composed of narrow streets, steep and dirty, retains a fragment of its old *Castle*, and part of the line of the former fortifications still climbing up the steep. It is the birth-place of Massillon, the preacher, to whom a marble *pillar* and *bust* have been raised in the Place Royale.

The low ground is richly cultivated: olives, vines, figs, mulberries abound; the pomegranate, pistachio, caper, myrtle, jessamine flourish; but the hills are bare. On the shore, about 3 m. to the E., are large salt-works, and off the coast is the group of islands called

*Iles d'Hyères* (anciently Stœchades), named Ile du Levant or Titan, Port Gros, Porquerolles, and Bagneau. They are barren and rocky, with a few pine-trees, thinly inhabited and fortified, and enclose a roadstead. There is a manufactory of soda here. These islands, though several m. farther S. than Hyères, do not enjoy the same favoured climate, being

withdrawn from the protection of the hills.

*Diligences* run daily between Toulon and Hyères.

The road hence to Nice passes through

23 Cuers.

15 Pignan.

15 Le Luc (*Inn: Poste*), where it falls into R. 128.

## ROUTE 128.

AVIGNON TO NICE BY AIX (MARSEILLES),  
FRÉJUS, AND CANNES.

274 kilom. = 170 Eng. m.

*Diligences* several times a-day. When the railway (Avignon to Marseilles, 120 kilom.) is completed (1847) by Arles (Rtes. 127 and 129), the first part of this road will be deserted.

The road on quitting Avignon runs along the rt. bank of the Durance (*Druentia*), a turbulent and ill-conducted stream, whose wide and desolate bed of gravel, laid bare in summer, bears so large a proportion to the reduced stream flowing in threads towards the Rhône, that a passing traveller has no idea of the considerable volume of water poured down by it even at that season from the supplies furnished by the melting snows of the Alps. In winter, swollen in a few hours to a torrent, it not only fills its channel, but often inundates its banks. Its waters are employed in irrigating the neighbouring land. One considerable *Canal*, called *de Crillon*, from the grandson of le Brave Crillon, who caused it to be made, is passed by our road near Bonpas. Here we cross the Durance by a long wooden bridge. A road runs hence to l'Isle, by which the traveller visiting *Vaucluse* (p. 459) may gain the route to Marseilles without returning from Avignon.

Near Bonpas is the village Noves, reputed the birth-place of Petrarch's Laura.

Higher up the Durance, on its rt. bank, is Cavaillon (7000 inhab.), where are some mutilated Roman



remains, an *Arch of Triumph*, half buried in the ground, attributed to the Emperor Constantine, and a curious Romanesque *Cathedral* (St. Véran) of the 13th cent., with an apse of the 12th; attached to it is a curious *Cloister*.

The Durance separates the Dépt. of Vaucluse from that of Bouches du Rhône.

18 St. Andéol. There is a cross-road from this to St. Remy, whose Roman monuments are described at p. 465. It lies at the foot of the low chain of bare limestone hills, visible to the S., extending from Tarascon to Orgon, called *Les Alpines*.

10 Orgon (*Inn*: Poste; dear, and not to be recommended). This is a town of 2000 inhab., near the l. bank of the Durance, at the foot of a hill crowned by a ruined castle.

The *Canal de Boisgelin*, a branch of the Canal de Craponne, which conveys the fresh water of the Durance to the Rhône at Arles, fertilising the land on its passage, is here carried through the rock in a *Tunnel*, known as the *Pierre Percée*, of no great length.

Napoleon, on his way from Fontainebleau to Elba, was nearly torn in pieces here by the infuriated populace, and became so much alarmed as to disguise himself as a courier, and ride on before his own carriage.

The Canal de Craponne is crossed at

18 Pont Royal: there is a pretty fountain near the post-house.

*Canal to Marseilles from the Durance.*—"This highly-important hydraulic work has been projected and executed under the able direction of M. de Montricher. It derives its water from the Durance, near to the suspension bridge at Pertuis, and is conducted by open cutting and tunneling for a distance of 51 m., through a mountainous and difficult country, until it reaches the arid territory of Marseilles, where it will be employed for the supply of the city, as well as for irrigation, and giving activity to

various branches of industry, for which it will furnish a water-power equal to that of 6000 horses. The section and fall of this canal is calculated to pass 11 tons of water per second; and its levels are so disposed, that this quantity of water will arrive near to the city at an elevation of 400 ft. above the level of the sea.

"Perhaps no work of this description has been attempted either in ancient or modern times more hardy in its conception, or more really useful in its effects. Three chains of limestone mountains are pierced by the 10 miles of tunnels which are required to conduct this stream; and the *Aqueduct of Roquefavour*, of 3 rows of arches, conveys it across the ravine of the river Arc (about 5 m. from Aix), at an elevation above the river of 262 ft., while its length across the ravine is 1230 ft. The design for this gigantic structure is in excellent taste, and as a work of art it will not suffer from comparison with the famous Pont du Gard, which it surpasses both in altitude and size. The cost of this canal will probably exceed a million sterling, and this sum is raised by the city of Marseilles with aid of a loan from the Government. The revenue arising from this work will be principally from supplying water as a motive power and for irrigation, the value of land in such a climate being quadrupled if water can be so applied to it."—*P. T.*

Lambesc is passed on the way to

14 St. Cannat, where our road is joined by that from Arles and Nismes. (R. 127.)

A hilly country succeeds, bare and bleak, but abounding in olives, and not interesting. A long and steep hill leads down to Aix; on its brow, close to the road, are subterranean *Quarries of Gypsum*, in connection with which a great number of well-preserved fossil fish and insects are found. They occur in a fresh-water shale, whose laminations are so minute as to resemble the leaves of a

book; on splitting them open the fossils are found between.

The Montagne de St. Victor, rising to the E. of Aix, is a conspicuous feature in the landscape (see p. 497).

16 *Aix*. (*Inns*: H. des Princes, the first house as you enter the Cours, good, but very dear; Palais Royal, good.)

Aix is a flourishing town of 22,575 inhab., agreeably situated in a basin surrounded by hills of abundant fertility, amidst almond-groves and plantations of olives, which furnish the much-esteemed *sweet oil of Aix*, the best produced in France.

The broad street called the *Cours*, by which you enter the town, is very striking; it is lined with handsome modern houses, including the chief hotels, closed at one end by an iron rail, and ornamented with 3 fountains, one of which bears a statue, by *David*, of *le Bon Roi René*, who is represented holding a bunch of Muscat grapes, which he introduced into France. During his reign Aix was the scene of gaiety and luxury, and the seat of art and literature. Within the modern and external quarters of the town, which assume somewhat the aspect of boulevards, is the *Old Town*, the ancient capital of Provence, the resort of the troubadours, the home of poetry, gallantry, and politeness; the theatre of the courts of love, and of gay fêtes and tournaments, during the reign of Raymond Berenger IV. as well as of René of Anjou. It still retains in part its feudal walls and gates, and its streets are narrow and foul. Here stands, surmounted by an octagon belfry, without a roof, the *Cathedral of St. Sauveur*, parts of which are very ancient, as the S. aisle of the nave, resting partly on a wall of Roman masonry, entered by a curious portal flanked by 2 Corinthian columns, probably antique, within which is a plain round arch. Attached to the aisle is a *Baptistery* recently restored, around which are arranged a number of antique pillars of polished granite, supporting round

arches. These portions are all Romanesque, of the 12th centy., as well as the *Cloister*, remarkable for the variety of the columns supporting it. The central aisle is later, in the florid Gothic, and the N. aisle shows traces of the Italian style. The main *W. entrance* resembles in character somewhat the perpendicular English Gothic, overloaded with ornaments. The heads of the statues ornamenting it, destroyed at the Revolution, have been restored in the worst manner. The carved cedar-wood doors merit notice; they were executed 1503. The bas-reliefs upon them represent the 12 Theological Virtues (or the Sibyls), and the 4 Greater Prophets, below: the ornaments, a mixture of Gothic and Renaissance, are very delicately executed. These *doors* are covered with a sort of shutter to protect them, which the sacristan will remove for a small fee.

Within the church is a very good *old picture* of the Virgin and Child, on the top of a clump of trees, surrounded by a glory. Below, an angel appears to a shepherd, probably intended to represent Moses and the burning bush. On the outside of the two wings or shutters which cover the picture, painted in black and white, is the angel Gabriel appearing to the Virgin; and within are King René, and his second wife, Jeanne de Laval, both evidently portraits; he, attended by his patron saints, the Magdalen, St. Anthony, and St. Maurice; she, accompanied by St. John, St. Nicholas, and St. Catherine, the last a beauteous and most elevated countenance. This picture is attributed, like many others in different parts of France, to the pencil of King René; it is probably the work of a Flemish artist of the school of Van Eyck: its date must be posterior to 1455, as René did not marry Jeanne de Laval until that year. There are some marble bas-reliefs, which probably belonged to an antique sarcophagus, representing Christ and the Apostles, in the chapel



of *St. Mitre*, and others of the 15th century behind the altar of *St. Maurice*.

The *Ch. of St. John* includes some monuments to the Counts of Provence. The building is Gothic. The sacristy of the modern church of *La Madeleine* contains a curious painting of the Annunciation, attributed to *Alb. Dürer*.

The *Museum* contains numerous fragments of antiquity, inscriptions, mosaics, sculpture, bronzes, chiefly Roman, and found in the neighbourhood; including a torso of a youth, a tripod carved with a dancing female in relief, and a statue, said to be *Hercules*. The *Pictures*, as usual, are for the most part very mediocre; but among the modern works is a sample of *Granet*, a native of Aix.

The *Public Library* in the *H. de Ville* consists of 100,000 volumes, and possesses many letters of *Mary Stuart*.

In the *Place de l'Hôtel de Ville* is an old gateway with a clock bearing the date 1512. "There are many pretty *bits* of carved stone, and other relics of ancient taste and splendour, in the filthy little closes of this most filthy town."—*W. M.*

Aix, the *Aquæ Sextiæ* of the Romans, derives its origin from a Roman colony sent hither to defend the Phocæan colonists of *Marseilles* from the attacks of the *Salyes*, in the year 630 after the building of *Rome*. Its warm *mineral waters* served probably as an inducement for them to select this spot. The hot saline spring still exists, but it is neither very strong nor in high repute.

A *Bath-house* is erected over the source in the suburb, and there are remains of vaults near it, said to be Roman. The water is so weak that the baths may with safety be taken as ordinary warm baths. The chief spring, called *Source de Sextius*, from the founder of the Roman colony, *Caius Sextius Calvinus*, has a temperature of 78° Fahr. At the beginning of last century it diminished

greatly in quantity, in consequence of wells being dug at a place called *Barret*, 2 m. off, which brought to light, at a short distance from the surface, very copious springs, similar in nature to those in the town, but cold. The magistrates, however, ordered these sources to be stopped up; and 22 days after, the warm spring of *Sextius* had regained  $\frac{3}{4}$ ths of its original volume. It would appear, from this remarkable occurrence, that the source of heat must lie between the *Source de Barret* and that of *Sextius*.

Few provincial towns in France have produced a greater number of remarkable men than *Aix*: among them the learned *Peiresc*, the *Marquis d'Argens*, the naturalists *Tournefort* and *Adanson*, the painters *J. B. Vanloo* and *Granet*, and General *Miollis*.

The commerce in the sweet oil of *Aix* has greatly fallen off since 1830, when an unusually severe frost killed a large proportion of the olive-trees in this neighbourhood.

*Diligences* to *Marseilles*, 4 or 5 daily; to *Nice*; to *Avignon*, *Arles*, and *Nismes*; to *Gap*; *Digne*; *Toulon*. *Malleposte* daily to *Paris* (in 58 hours) and to *Marseilles*; to *Nice* in 20 hours.

The road to *Marseilles* and *Toulon* is described in *Route 127*.

The road to *Nice* passes under the precipitous heights of the *Mont St. Victoire*, and not far from the spot where *Marius* is supposed to have defeated the *Cimbri*, B. C. 125. 100,000 of the barbarians are stated to have been slain or taken prisoners, and the battle-field on the banks of the *Arc* was long known by the name "*Campi Putridi*," whence the modern village *Pourrières*.

12 *Châteauneuf-le-Rouge*.

11 *Grande Pugère*.

14 *St. Maximin* (*H. du Var*, indifferent) has a rather fine Gothic Church, very lofty within, but destitute of a W. front, without transepts, but ending in 3 apses. It was founded

by Charles II., King of Naples and Count of Provence, 1279, but seems chiefly of the 15th centy. The wood-work of the pulpit and sacristy is well preserved. Here are treasured up the bones of the Magdalen, over the altar; her skull, with a bit of flesh adhering to the forehead, where our Saviour touched it! her arm gilt, and the coffins of several saints, her servants; also some curious old vestments.

22 Tourves, a wretched town of 2800 inhab., in the Dépt. du Var. No inn. There is a *direct road* from Tourves, by Roquevaire 30 kil., Aubagne 8 kil., to Marseilles 17 kil.

12 Brignolles. (*Inn*: Poste, not very good, J. O.) In this town of 6000 inhab. an extensive trade is carried on in dried fruits. The "prunes de Brignolles," though sold here, are in fact produced in the country around Digne (Basses Alpes).

14 Flassans. *Inn*: La Poste, decent.

9 Le Luc. *Inn*: Poste, very dirty. Here the road from Toulon and Hyères falls in. (See R. 127.)

12 Vidauban. *Inns*: H. de Provence; Poste, good beds. Scenery interesting; the Mediterranean in view; myrtle, stone-pine, and cork trees. An abrupt turn of the road at

13 Le Muy. (H. Jourdan or La Poste, comfortable.)

15 Fréjus. *Inns*: H. du Midi; Poste; both clean and comfortable.

Outside the walls of this small and dirty town (not 3000 inhab.), the once celebrated *Forum Julii* founded by Cæsar, on the W., are the remains of a small *Circus*, recently cleared out, far inferior in size and preservation to those of Nîmes and Arles. The direction of the old Roman town walls may also be traced by existing fragments of them. The ancient harbour, in which Augustus posted the fleet of 300 galleys captured at Actium from Antony, is now sanded up by the deposits of the Argens (Argentius). The mole and tower (? lighthouse), which commanded the entrance to the old port, now rise out of the midst of a grass-

grown plain. The town is now a mile from the sea.

Between the sea and the town is a *Roman arch*, formed of small stones alternating with layers of tiles, called *Porte Dorée*. The *Cathedral of St. Etienne* is neither large nor handsome, but may interest the antiquary as a Romanesque edifice of the 11th or 12th century. Adjoining it is a *Baptistery*, resting on 8 antique columns of grey granite with marble capitals.

The most considerable and interesting Roman remains here are those of an *Aqueduct*, passed on the way to Cannes. It has been traced for more than 24 m. up the valley of the Ciagne, whose clear water it conveyed to the town. Many of the arches and piers remain perfect. It is a picturesque subject for the pencil.

Napoleon landed at the small port of St. Raphael near this, 1799, on his return from Egypt, and embarked hence, 1814, for Elba. This is the birth-place of the Abbé Sièyes, and is said to be that of Julius Agricola.

The French coast between Toulon and Nice is bordered by 2 small hilly chains called *les Maures* (because once occupied by Saracen brigands) and *l'Estrelle*. They are, as it were, the roots or footstool of the Alps, whose higher ridges protect them from the N. Consequently in their recesses and on their S. slopes they seem to enjoy a peculiar and privileged climate. Though their peaks are bare, near their bases the aloe, cactus, and palm flourish in the open air; and the umbrella pine, as in Italy, raises its graceful head close to the sea-shore. This is the true "garden of Provence." The Estrelle mountains are partly of porphyry, and are highly picturesque in their forms, as is invariably the case where that rock occurs. The red porphyry was worked by the Romans, and used by them for the buildings of Fréjus, and was even sent to Rome; the ancient quarry has been discovered about 1½ m. from the shore.



A new and improved line of road has been constructed over the Pass of 14 L'Estrelle. The scenery, varied by the fine foliage of the cork-tree, arbutus, and evergreen oak, is very pleasing, and is diversified by fine sea views.

20 Cannes. *Inns* (none good): H. du Nord; Pinshinat's Hotel, outside the town; La Poste. The fish called St. Pierre is reputed the ortolan of the sea.

This is a neat and cheerful small town, finely situated in a mountainous country at the bottom of a beautiful bay. It is the port of Grasse.

About  $\frac{1}{2}$  a mile off is the villa Louise Eléonore, built by *Lord Brougham*, in one of the most charming situations in the S. of France. Mr. Leader and other English visitors have houses here.

Napoleon landed  $1\frac{1}{2}$  m. E. of Cannes from Elba in March 1815, with an army composed of 500 grenadier guards, 200 dragoons, and 100 lancers without horses. He took the road to Grasse, and bivouacked the first night in an olive-garden there.

Opposite Cannes, about  $2\frac{1}{2}$  m. from the shore, lies the *Ile Ste. Marguerite*, covered with wood, one of the group of 2 isles called Lérins, in whose fort, once a state prison, the Man in the *Iron Mask* long lingered. The dungeon in which he was confined (1686 to 1698) is still pointed out; its walls are 12 ft. thick, and its solitary window is guarded by treble iron bars. The only approach to it was through the governor's rooms. In the midst of a small garden is a curious square building with a door in each face. On the *Ile St. Honorat* are remains of a fortified convent, a church and a baptistery, recently reduced to ruin, and all deserving the attention of the antiquary. On the top of the hill washed by the sea above Cannes is the *Ch. of Notre Dame d'Espérance*, much revered by sailors. The road to Nice merely skirts, and does not enter, the town of

11 Antibes (*Inn*: Poste, not good),

a flourishing little sea-port (5976 inhab.), finely situated on a promontory jutting out into the sea, and looking beautiful at a distance, and commanding views of the Maritime Alps. Here are portions of 2 square Roman towers. "Travellers should stop outside the gates, and send in for horses; they will thus save time, and their carriage will escape the risk of accidents, in being twice dragged through the most odious streets."—*W. M.* A pier thrown out from the shore connects it with some islets in the bay: it was the work of Vauban.

It is a delightful ride hence to Nice. The torrent Var, crossed by a bridge of wood, divides France from the Sardinian states. It is an unmanageable stream, rolling enormous masses of shingle down into the sea, which the current of the Mediterranean pushes constantly to the W., grinding them smaller the further they are carried.

The French custom-house is strict. (See INTRODUCTION.) N.B. "The Douanes on either side of the Var open about 8 A.M., and close at 5 in winter, 6 in summer. The gates on the Pont du Var are locked during the intermediate hours, and are not opened for travellers."—*L. F. M.*

24 NICE (*Inn*: H. des Etrangers; excellent—*L. F.*) is described in *HAND-BOOK FOR NORTH ITALY*.

## ROUTE 129.

AVIGNON TO MARSEILLES, BY ARLES, ST. CHAMAS, ÉTANG DE BERRE—RAILWAY.

120 kilom. =  $74\frac{1}{2}$  Eng. m.

This line will be opened in 1848.

About 3 m. from Avignon the railway will be carried over the Durance.

The valley of the Rhône is flat and uninteresting.

Route 125, p. 461.

Tarascon station. See Route 125, p. 462.

ARLES STATION. See Route 125, p. 464.

The railroad is carried across the

singular plain of the Crau, described p. 482, round the margin of the Etang de Berre, a sort of inland sea, navigable for small vessels, which is about to be connected with the sea by a new canal at Bouc.

St. Chamas St.—a town of 2443 inhab., on the Etang de Berre. It is divided into 2 parts by a narrow marly ridge pierced with caverns, some of them inhabited. On the ridge stands the old *Church* of *St. Amand*.

Part of the ancient ramparts surround the town. There is a Government powder-mill here. 500 paces

out of the town, in the midst of the plain, stands the *Pont Flavien*, a Roman bridge, built over the Touloubre, a single arch of large blocks crossed by an arch of triumph of elegant Corinthian architecture at either end. On the frieze is this inscription:—

L. DONNIVS. C. FLAVOS. FLAMEN.  
ROME ET. AVGVSTI. TESTAMENTO. FIERI  
JVSSIT. ARBITRATV. C DONNII. VENÆ  
ET. CATTEI. RVFI.

MARSEILLES Terminus (R. 127, p. 484).

\*\_\* More detailed information concerning this railway is desired.



## SECTION VII.

## DAUPHINÉ.\*

ROUTE	PAGE	ROUTE	PAGE
131 Lyons to <i>Grenoble</i> by <i>Vienne</i> , or by <i>Bourgoin</i> .— <i>Excursion to the Grande Chartreuse</i> . . . . .	502	136 Lyons to Nice by <i>Grenoble</i> , <i>Digne</i> , and <i>Grasse</i> . . . . .	515
132 Valence on the <i>Rhône</i> to <i>Grenoble</i> and <i>Chambéry</i> , through the <i>Valley of Grésivaudan</i> . . . . .	509	137 <i>Grenoble</i> to <i>Briançon</i> , by <i>Bourg d'Oysans</i> and the <i>Col de Lauteret</i> , and by the <i>Mont Genève</i> to <i>Susa</i> . . . . .	515
134 <i>Grenoble</i> to <i>Marseilles</i> , by <i>Gap</i> and <i>Sisteron</i> .— <i>Protestant Valleys of Dauphiné</i> . . . . .	511	139 <i>Gap</i> to <i>Briançon</i> , by <i>Embrun</i> .— <i>Protestant Valleys</i> (continued): <i>Val Queyras</i> , <i>Val d'Arvioux</i> , and <i>Val Fressinière</i> . . . . .	519
135 <i>Grenoble</i> to <i>Marseilles</i> , by the <i>Croix Haute</i> . . . . .	514		

## INTRODUCTION.—SKETCH OF THE COUNTRY.

THIS province has been as much neglected by travellers as many other parts of France, yet its scenery is of first-rate beauty and grandeur. "I saw nothing among the Alps," says Arthur Young, "that offered such pleasing scenes as the N. parts of Dauphiné." The valley of the Isère is made up of a series of beautiful scenes, and the part of it about Grenoble, the deservedly vaunted Vallée de Grésivaudan, combines with the mountain forms of Switzerland the luxuriant vegetation and umbrageous foliage which usually characterise the S. slope of the Alps.

The *Grande Chartreuse* has been rarely visited by the English since Gray and Horace Walpole first drew their attention to it, yet the approach to it from St. Laurent is by a gorge as fine as any in the Alps. Grenoble itself is a striking city in a very romantic situation. The new carriage-road, begun by Napoleon, and at length nearly finished, from Grenoble to Briançon, by Bourg d'Oysans and the Col of the Lauteret, lays open a magnificent Alpine pass.

In addition to all this, however, Dauphiné includes, in the block of mountains which separate the basin of the Romanche from that of the Durance and the sources of the Drac, the *highest mountain in France*, *Mont Pelvoux*, whose culminating peak, the Pointe des Arcines or des Ecrins, attains an elevation of 13,123 ft. above the sea level. Yet, though the loftiest summit in the Alpine chain between Mont Blanc and the Mediterranean, and considerably higher than Monte Viso, its name rarely appears on maps and in books of geography even published in France. Among the few persons who have visited it, besides engineers employed in the vicinity, are M. Elie de Beau-

\* The name *Dauphin* (Delphinus, whence Dauphiné), borne by the eldest son of the King of France down to 1830, is of unknown origin, but belonged to the Counts of Vienne, who also carried a dolphin as their coat of arms, from the 11th or 12th century down to 1349, when Count Humbert III., the last *native* Dauphin, made over his title and domains to the eldest son of Philip of Valois.

mont, and our own countryman, Prof. Forbes, of Edinburgh, who have examined it geologically. The scenery around Mont Pelvoux will well repay the trouble of a visit: it is of a sublime, but desolate and savage character. It is best approached from Bourg d'Oysans, whence a path runs up Val Christophe to Berarde, a desolate village at its base, buried by snow 7 months of the year, and hemmed in by precipices, with the scantiest vegetation around, and beyond it moraines and the glacier of la Condamine. It is destitute of any accommodation; indeed the traveller who explores the Montagnes d'Oysans must be prepared to rough it; the mere tourist is an animal nearly unknown as yet among them. Mont Pelvoux is surrounded by other lofty peaks, all inclining their heads to him as in homage to the monarch of the French Alps, but presenting sides nearly precipitous, surrounding the desolate valley of Berarde as it were with a colossal circus, 36 miles in circumference, forming an arrangement which has been compared to the petals of a flower.

The *Valleys of the Hautes Alpes*, including the Val Fressinière to the S. of Mont Pelvoux, and the Vals Queyras and Pragelas, running E. from Embrun and Mont Dauphin towards Monte Viso, although destitute of roads and accessible only by the pedestrian, will be explored with a double interest, not only for their noble scenery, but also as the refuge of persecuted Protestants, the kindred of the Albigenes and Vaudois, and also in recent times as the scene of the labours of the virtuous pastor, Felix Neff.

*Bourcet's* "Carte du Haut Dauphiné" is an indispensable travelling companion, and is not to be surpassed for accuracy.

*Gilly's* "Life of Felix Neff," of which there is a pocket edition, will be read with interest amidst the scenes of his ministry.

### ROUTE 131.

LYONS TO GRENOBLE BY VIENNE, OR  
BY BOURGOIN.—EXCURSION TO THE  
GRANDE CHARTREUSE.

*a.* By Vienne 113 kilom. = 70 Eng. m. A diligence daily. The road is the same as R. 125 as far as

27 Vienne.

15 La Detourbe.

14 Chatonay.

17 La Frette.

13 Rives.

13 Voreppe, p. 503.

14 Grenoble, p. 507.

*b.* The route by Bourgoin is shorter than the preceding by 7 kilom.; it is the road to Chambéry and Turin as far as Bourgoin.

4 *Diligences* go daily; and 2 or 3 to Chambéry and Turin follow the road by Bourgoin and Pont de Beauvoisin.

The road quits Lyons by the Pont Guillotière, and the long suburb of

that name, emerging between two of the detached forts. It enters the Dépt. de l'Isère before reaching

10 Bron, a solitary post-house.

8 St. Laurent des Mûres (? so called from the mulberry-trees).

11 La Verpillière.

12 Bourgoin (Poste, good), a neat manufacturing town of about 3750 inhab., whose industry is promoted by the Bourbre and 2 other small streams flowing through it. Here are manufactures of cotton, calico, cloth, and paper. A considerable trade is carried on in flour and wool; and the prosperity of the place is promoted by its position at the point where the roads from Lyons to Chambéry and Grenoble branch off.

The way to Chambéry and Turin runs through

15 La Tour du Pin (Poste; tolerable), a town of 2484 inhab.

8 Gaz (no inn); a road runs hence



by Voiron, a town of 6924 inhab., where great quantities of sailcloth and other coarse cloths are made, to Voreppe and Grenoble.

10 Pont du Beauvoisin (Poste; fallen off), a frontier town on the Guier, which here separates France from Sardinia. The respective custom-houses of the two countries are situated at the two extremities of the bridge over it.

The road runs along up the rt. bank of the Guier, but high above it, through a picturesque and fertile country at first, and afterwards through the grand gorge of La Chaille.

15 (2 posts) Les Echelles, a village situated at the junction of 2 streams, the Guiers Vif and Mort.

About 8 m. S. of this, up the Guiers Mort, is St. Laurent du Pont, the point from which the Grande Chartreuse is visited (see p. 504).

A good road leads from Les Echelles to Grenoble, through St. Laurent.

*Chambéry* is fully described, together with the road thither from Pont Beauvoisin, in the SWISS HANDBOOK.

*Road to Grenoble.*—The direct road from Lyons to Grenoble turns off from the preceding route at

40 Bourgoin.

11 Eclose.

15 La Frette. We here fall into the road *a* to Grenoble by Vienne, p. 502.

The Château of La Frette was the birth-place of the terrible Baron des Adrets, a sort of French Alva, at whose name, and war-cry "Beaumont," squadrons used to turn and fly. At the age of 60 he led on the Huguenots against the Romanists, and especially against the party of the Guises. He died here, after having become himself a Romanist, at the age of 80.

La Côte St. André, a little to the W., is famed for its distilleries of liqueurs.

13 Rives, on a stream called La Fure.

After surmounting a hill the road descends at Moirans into the beautiful valley of the Isère. The portion of it extending upwards from Voreppe to Chapareillan is called the *Valley of Grésivaudan*, and is deservedly celebrated as one of the most productive and beautiful in France. In its culture and its different kinds of produce, it is scarce surpassed by those luxuriant valleys stretching down into Italy on the S. side of the Alps. Up to the point where the mountains rise in bare precipitous rocks, or are girt with dark forests, every portion is constantly subject to tillage, and produces a vast variety of crops. Besides corn and clover, hemp, for which the valley is celebrated, grows often to the height of 15 ft. Orchards, chestnuts, and mulberry-trees rise above these; and the vine also, very abundant, instead of being allowed to crawl along the ground, or being clipped like a currant-bush, slings its graceful festoons from tree to tree, or is trained along wooden trellises. The roads are lined and shaded with trees, and it is difficult to see across the valley for the dense screen of foliage, but it hides the somewhat arid peaks and ridges from view, and thus modifies an unpleasing feature. Industry, abundant irrigation, and manure have brought the whole to the condition of a luxuriant garden, and a great portion of the bottom is carpeted with meadows.

13 Voreppe, a flourishing village abounding in inns, chiefly resorted to by waggoners, of which the Petit Paris seems the best. A tolerably good cross-road, practicable for carriages, strikes off from Voreppe N. to the Grande Chartreuse and Les Echelles.

#### THE GRANDE CHARTREUSE.

"Per invias rupes, fera per juga,  
Clivisque præruptos, sonantes  
Inter aquas, nemorumque noctem."  
GRAY.

"There are certain scenes that would awe an atheist into belief with-

out the help of other argument. I am well persuaded St. Bruno was a man of no common genius to choose such a place for his retirement.”—*Gray's Letters.*

*N. B.*—Those who cannot content themselves with Carthusian fare, viz. soupe maigre, herbs, and an omelet, had better take some cold meat and wine with them on this excursion.

The road from Voreppe to the Grande Chartreuse runs up a side valley shaded by walnut-trees, ascending steeply at first. At a distance of about 6 m., where the valley has widened out, the road from Voiron (*Inn: Poste*) and Le Gaz (p. 503) falls in, and 4 m. farther lies St. Laurent du Pont, a small village, with a poor and not very moderate inn. Here the traveller bound to the Chartreuse must turn out of the carriage-road, which continues on to Les Echelles, and the rest of the way must be performed on horseback or on foot. A mule or horse may be hired here for 5 fr.; a guide to show the way is unnecessary.

St. Laurent lies on the stream called Guiers Mort, up whose valley our way lies: it is at first bounded by gentle slopes covered with pasture below, and above with wood; but it soon contracts into a wooded gorge, not exceeded for picturesque grandeur among the Alps. At Fourvoirie, a little more than a mile from St. Laurent, near an iron forge, now bankrupt and deserted, the mountains close together; the river, hemmed in by vertical precipices of vast height, is spanned by a single-arched bridge, and gushes forth from between the smoothed rocks with the swiftness of a cataract, in one deep sea-green flood. The jaws of the gorge seem barely rent asunder sufficiently to allow the stream to pass. The space cut out for the road between the torrent and the mountain precipice is occupied by a gateway, a pointed arch, faced by a modern and less picturesque one. It originally served for defence, and marked the

limit of the domain of the monastery, or of the “Desert of St. Bruno” as it was styled. The bridge, the forge, the gateway, the river, and the precipices combine to form a most romantic natural picture, which will gratify the artist's eye, and has often employed the pencil. Within this grand portal the sides of the defile, up which the rough mule-path is carried, are rocks and precipices of limestone many hundred feet high; but their savageness is subdued by the dense foliage which lines them, so that it is a ride through a forest the whole way. The varied combinations of rock, tree, and river,—of rocks at a vast height overhead, inclining over the tree-tops and the wayfarer,—of the torrent foaming and rushing in the depths below, now spanned by a bridge, now studded by saw-mills,—its constant roar, as it frets and worms its way, indicating its presence, even when lost to view by the bends of the gorge or the intervention of rocks and trees,—and the varied forms and tints of the foliage, especially in autumn,—redeem the defile from all monotony. The road, though narrow, must have cost the monks much, and could only have been executed in a long time, and with great labour, being cut out of the rock great part of the way. Since the Revolution, however, which ruined the monks, it has gone to decay also, and in places is now barely passable, intersected by holes in which you might bury a mule, filled with mud, in which your animal plunges knee-deep. In places the torrents from the mountains have adopted it as their bed; in others it is no better than a steep staircase of bare rock. Owing to the badness of the road, no wheeled cart can pass, and the timber cut in the surrounding forests, and sawn into planks in the mills on the Guiers, is transported down the valley slung with ropes by the middle to the sides of mules. The deals thus nicely poised “*traverse*” like the needle of a compass, and at every movement of the animal per-



form segments of circles sweeping the road, and all that is upon it. It is by no means agreeable to meet a train of beasts so laden, with a precipice on one side of the narrow path, and a wall of rock on the other; nor are the huge sacks of charcoal more pleasant to encounter, as they at least leave their marks on the clothes, if they do not push you down the abyss, as the loaded animal brushes past. About half-way up, the path is carried by a narrow bridge, destitute of parapet, across the Guiers to its rt. bank, and after a very severe ascent it reaches a *second Gateway*, jammed in as it were between the precipice and a colossal Obelisk of limestone (*pain de sucre*), beyond which, in former times, no female could pass,—such was the rigid regulation of St. Bruno. A guard of soldiers was anciently posted here to keep the pass. The mountains here separate, and from the height you look down upon their sloping sides covered with nearly unbroken forest, stretching over several minor valleys. The path, quitting the defile, turns to the l., still through woods, but slightly thinned, though the charcoal-burners are habitually settled in them. At the end of a ride of  $1\frac{1}{2}$  hour the traveller reaches

*La Grande Chartreuse*, the Escorial of Dauphiné, seated at a height of 1,210 mètr. (4,268 ft.) above the sea, shrouded in umbrageous woods, with only small patches of meadow and little or no level ground about it, being quite hemmed in by wooded heights. The position is not grand, but solitary, desolate, and monotonous, from the confined prospect. The *convent* is a huge unpicturesque pile, having neither age nor architecture to recommend it, since, owing to repeated conflagrations, which destroyed 6 or 8 previous buildings, very little of it is older than the 17th centy. Externally, its tent-like roofs of slate, higher than the body of the building which they cover, are its most conspicuous feature. Various

*France.*

straggling outhouses surround the main edifice: one is a cowhouse, another the infirmary, and one tenement is now set apart for females, who, though no longer restricted to the limits of the gateway, are not permitted to set foot in the convent itself. Male visitors are received by one of the fathers, called *Père procureur*, who is absolved from the obligation of silence, and conducted along its cold corridors, one of which is 660 ft. long, and includes part of a Gothic cloister, perhaps of the 15th century, to the *burial-ground*, a simple inclosure without tomb-stones. The graves of the Generals of the order alone were formerly marked by stone crosses, but these were destroyed at the Revolution. When one of the monks dies, a cross of lath is set up over his head; but it soon disappears. Each father has a small habitation and garden to himself, in which a crucifix and a skull invite him to prayer and the contemplation of death. The cells are lined with plain deals, and furnished with bookshelves. The chapel is a lofty apartment, quite plain, in which service is performed by night and day. The chapter-house has lately been painted with portraits of the Generals of the order, of no great merit, and contains a marble statue of St. Bruno. The number of monks (*pères*) is now reduced to 33, who are dressed in white cloth, and 18 servitors (*frères*), clad in brown. By the rule of the order, the members were originally prohibited from speaking except on Sundays and fêtes; but this seems now not to be rigidly enforced. On certain days the monks walk abroad, and ascend in company to the chapel of St. Bruno; this they call "*le Spaciment*," and they afterwards dine together in the refectory; on other occasions they eat alone, excepting on fête-days. Previous to 1789 the monks were owners of St. Laurent du Pont and of many other villages: their tenants were well off, the ground well tilled, and they gave away much in charity.

They were excellent landlords, managing their estates prudently, and were just to their tenants. The convent was stripped of its vast possessions at the Revolution, and escaped being sold only because no purchaser could be found for it; but the woods around, forfeited at that time, still belong to the government, and all that remains to the monks is a garden, with the right of cutting wood in the forest, and of pasturage for their cows, of which they have about 50. They depend much upon charity, and it is customary for strangers who visit the convent to make a small donation to the alms-box, and, if they remain for the night, to pay for board and lodging. Male visitors are entertained with the humble fare of the convent, eggs, fish, and vegetables, and are lodged in a little cell provided with a small bed. The monks are famed for distilling *liqueurs*; the finest quality, *l'Elixir*, is used as a medicine and cordial.

About  $1\frac{1}{2}$  m. higher up the mountain is the *Chapelle de St. Bruno*, where the founder of the order, descended from an opulent family at Cologne, established himself, 1084, having resolved to abandon the world. He retired to this spot, pointed out to him by Hugues, Bishop of Grenoble, as a desert quite beyond the haunts of man, and named, from a neighbouring hamlet, Cartuse, or Chartreuse, whence the order derives its name. Bruno lived in a cave or cleft of the rock, which is pointed out still higher up, and left no written rule for his order; that was compiled 44 years after his death by Dom Guignes.

At a less elevation than St. Bruno's is the chapel of the Virgin.

From *Le Grand Som* (sommet), the highest neighbouring cliff or peak, many hundred ft. above the convent, marked by a crucifix, an extensive view may be obtained, including part of the Lac de Bourget, on the side of Savoy.

There is only one other outlet from this upland valley, besides the road to St. Laurent du Pont. It is a path leading to the small hamlet of St. Pierre de Chartreuse, and Sapey, 3310 ft. above the sea-level. It is much shorter than the other, and Grenoble may be reached by it in 3 or 4 hours. From the summit of the heights, as you descend towards that city, a beautiful view is obtained of the Vale of Grésivaudan (see R. 132, p. 510).

The foundation of the Grande Chartreuse by St. Bruno is attributed, in the legendary histories of him, to the effect produced on him by the apparition after death of a learned doctor of Paris, who, as the funeral procession was proceeding to the place of burial, burst from his coffin, exclaiming, "I am accused by the just judgment of God." This occurrence sank so deeply on St. Bruno's mind, that he, with 6 friends, determined to quit the world and retire into the wilderness. At first his only habitation was in the clefts of the rock, and the spot was inhabited at that time only by wild beasts. The first cells were higher up than the present convent, near the chapel of St. Bruno. These mere huts were swept away by an avalanche. The first convent, on the actual site of the present one, was built of wood by the 5th prior, Guignes, who died 1137. He first committed to writing the rules of the order, one of which runs thus:—"Nous ne permettons jamais aux femmes d'entrer dans notre enceinte; car nous savons que ni le sage, ni le prophète, ni le juge, ni l'hôte de Dieu, ni ses enfans, ni même le premier modèle sorti de ses mains, n'ont pu échapper aux caresses ou aux tromperies des femmes. Qu'on se rappelle Salomon, David, Samson, Loth, et ceux qui ont pris les femmes qu'ils avoient choisies, et Adam lui-même; et qu'on sache bien que l'homme ne peut cacher du feu dans son sein sans que ses vêtemens soient embrasés, ni marcher sur des char-



bons ardents sans se brûler la plante des pieds.”

Between Voreppe and Grenoble is, perhaps, the most picturesque portion of the *Vale of Grésivaudan*: the valley is here bounded by mountains precipitous as well as lofty. The road winds under such a one near the village of La Buisserade, which is particularly imposing. Under the dark woods and heights on the opposite bank lies Sassenage, and near this the river Drac pours itself into the Isère.

Little is seen of Grenoble, at a distance, in approaching from this side. A tall mountain buttress, nearly precipitous, projects forward to the Isère, leaving barely space for the road at its foot, and hides the town from view. This shoulder of rock has been recently studded with fortifications, rising one above another nearly to the clouds, 918 ft. above the river. They took more than 10 years to construct; the natural strength of the height having been increased by blasting and scarping the rock with gunpowder. The position of this fortress, the citadel of Grenoble, at an angle in the valley where the Isère makes a bend, and opposite the opening of the Vale of the Drac, gives it the command of these valleys, which would be swept by its guns. The chief work is the crowning battery, to defend the place in the rear, where it is surmounted by the superior heights of the Mont Racht. It is called *La Bastille*, from an old feudal castle, a bit of which remains in the midst of modern works. It is worth while to ascend the hill of the Bastille, the Ehrenbreitstein of the Isère, for the sake of the view. It embraces the town of Grenoble at your feet, laid open as on a plan, surrounded by its stellated ramparts, on a flat and fertile tongue of land watered by canals, bounded on one side by the Isère and by the Drac on the other. The courses of both rivers may be traced

from their junction upwards; that of the Isère is very winding, and its valley is terminated by the snowy mass of *Mont Blanc*. In front stretches the straight road leading to Vizille, and pointing to the mouth of the valley of the Romanche, bounded by mountains of very picturesque outline.

*Permission* to enter the fortress must be obtained from the commandant.

At the foot of the rock crowned by the Bastille, stands the narrow suburb of St. Laurent, wedged in between precipices and the river. One side of its confined street has recently been pulled down and converted into a cheerful quay.

St. Laurent occupies the site of the original Gaulish town, called *Cularo*, mentioned in the letters of Plancus to Cicero: it changed its name, out of compliment to the Emperor Gratian, into that of *Gratianopolis*, whence Grenoble.

A handsome *stone bridge*, and a suspension wire bridge, replacing an old one of wood, connect this suburb with

14 GRENOBLE.—*Inns*: H. de Trois Dauphins, Rue Montorge; good, but not very clean, and somewhat dear; excellent table d'hôte at 3 fr.; breakfast à-la-fourchette, 2 fr. In this house Napoleon lodged on his return from Elba: the room he occupied remains nearly in the same state;—H. des Ambassadeurs, “very good; bread excellent.”—*F. R. K.*

Grenoble, formerly capital of Dauphiné, and now of the Dépt. de l'Isère, is a fortified city of 28,967 inhab., pleasingly situated on the Isère, in a basin of great fertility and beauty, surrounded by high mountains, within which the Romanche and the Drac unite with the Isère, joining it a little below Grenoble. The full and rapid flood of the Isère, which is here confined within handsome *quays*, lined with fine houses, contributes much to the beauty of the town. Grenoble has been much improved and enlarged

of late, and it is proposed to extend it considerably, and reconstruct the fortifications around it, so as to enclose a much larger space of ground. It has scarcely any fine public building: its churches are not remarkable: the *Cathedral* is a heavy mixture of ancient and modern masonry, having been ravaged and almost destroyed in the 16th centy. by the ferocious Baron des Adrets, who also destroyed, in the *ch. of St. André*, the monuments of the Dauphins. *St. Laurent* is the oldest church.

One of the most pleasing features of the town is its *Public Garden*, on the l. bank of the *Isère*, shaded with umbrageous trees, planted with flowers, and set out with orange-trees in pots. It was originally laid out by the Duc de Lesdiguières, and attached to his palace, now the *Préfecture*.

In the midst of the neighbouring Place *St. André* is a bronze colossal *Statue of Bayard*, the "chevalier sans peur et sans reproche," who was born in the valley of the *Isère*, and buried in the neighbouring church of the *Minimes*, (?) some say in the cathedral, where there is an inscription to his memory. It is meant to represent him in the moment of death, mortally wounded, kissing the cross formed by the hilt of his sword; but it is theatrical, and unworthy of the hero. It stands opposite the *Palais de Justice*, originally the palace of the dauphin, the most interesting old building in the town, retaining a Gothic oriel, and other portions in the style of the Renaissance. The Place *Grenette* is the largest open space in the town: in it are the chief *cafés* and *diligence offices*.

Attached to the *College* is a *Museum*, in which may be seen some of the old busts of the dauphins, removed from their palace. Here is a large collection of *paintings*, mostly mediocre: the best seem to be a portrait by *Philip de Champagne* of Jean Duvergier de Hauranne, a member of Port-Royal; a Venetian in Velvet,

by *Tintoret* (?); the Entry of the Emp. Sigismond into Mantua; a sketch by *J. Romano*; Pope Julius II. do. (?); *St. Gregory*, with Prudence and Force, by *Rubens* (or one of his school). Here are 2 bronze lions of Byzantine art, brought from an abbey at *St. Marcellin*.

In the *cabinet of natural history* may be seen specimens of the minerals of Dauphiné,—its huge rock crystals, 2 feet long and 1 foot broad, its axinite, anatase, &c., with silver ore from *Allemont*, and gold from *La Gardette*, both mines near *Bourg d'Oysans*, no longer worked: but the collection is dirty and ill-arranged. Here are stuffed specimens of the wild animals from the neighbouring Alps, the bear and wolf.

The *library* contains some books, brought from the *Grande Chartreuse*; also portraits of some of the celebrities of Grenoble—*Vaucanson*, the mechanician, and *Dolomieu*, with busts of *Mably* and *Condillac*.

*Diligences* daily (4 or 5), to Lyons; to Vienne; to Valence; to Chambéry (2); to Marseilles, by Sisteron; to Gap; to *St. Laurent*; to *Bourg d'Oysans*.—*N. B.* The gates of Grenoble are closed at 11 p.m., and there is no means of gaining admittance except an order from the commandant. Those who are shut out must sleep where they are, and there is no inn, outside.

Though Grenoble itself is deficient in objects of curiosity, the country around has great beauty, and many interesting excursions may be made from it: the chief of these are,

1. To the *Grande Chartreuse* (described at p. 503). There are two ways, either *a*, by Voreppe (p. 503) and *St. Laurent du Pont*, practicable as far as that place in carriages, and traversed by a daily diligence in summer, by which one can go in the morning, and return in the evening; or *b*, by *Sapey*, a mule path, the shorter of the two, by which the convent may be reached in 4 hours. The most interesting part of the excursion



sion, however, is the wooded gorge on the other road between St. Laurent du Pont and the convent.

2 To Sassenage, a beautifully situated village on the opposite side of the Drac, in the midst of thick woods and falling waters, and fine pasturages, producing an excellent *cheese*, resembling that of Roquefort. The distance is about 5 m.; a one-horse carriage may be hired in Grenoble to go and return for 5 frs. It is a pleasant drive. A turning to the rt. leads out of La Cours, the long avenue extending from Grenoble to Vizille, and conducts you to the iron suspension-bridge over the Drac. The river is here retained within stout dykes, originally the work of Lesdiguières; the plain is intersected with canals for the sake of irrigation. A small streamlet, a tributary of the Furon, which traverses the valley of Sassenage, bursts out of a hole in the limestone mountain above the village. The rock is pierced by several small caves, rather difficult of access.

3 *Château Bayard*, the birth-place of the model of French chivalry, is about 27 m. up the valley of the Isère, on the left bank. (See Route 132, p. 511.)

4 Six m. from Grenoble, at the mouth of the gorge of the Sonnant, is the fine feudal castle *Uriage*; and near it mineral *baths*, with a large hotel.

5 *La Tour St. Venin*, on the hill of Parisot, on the l. bank of the Drac, classed among the wonders of Dauphiné, from a vulgar belief that no poisonous reptiles can live on it, is a fine point of view, 4 or 5 m. from Grenoble, commanding the junction of the valleys of the Isère and Drac. It appears to have been a chapel or hermitage, attached to a castle now swept away, dedicated to St. Verin; and that a misprint or mispronunciation gave rise to the present name and to the vulgar fable.

The staple manufacture of Grenoble is that of *leather gloves*: it is the

most considerable in France. They are made of the skins of kid, the best sorts of which are obtained from Annonay, of chamois (beaver), and of lamb. Much leather also comes from Romans and Milhau. The gloves are chiefly sewed by the hand by women, between 4,000 and 5,000 being employed, in and about the town, in cutting out and sewing.

Grenoble was the first place which openly received Napoleon on his return from Elba. After having been joined at La Mure by the troops sent out against him (see p. 512), and still nearer at hand by Labedoyère, he approached the walls, which were strongly guarded by troops and cannon. Although the garrison dared not disobey their commandant by opening the gates, yet not a shot was fired on him; he was permitted to come up to the gates and direct against them a howitzer to blow them open. Once within the walls he was received both by citizens and soldiers with the utmost enthusiasm, and borne in triumph, amidst shouts of "Vive l'Empereur!" to the Hôtel des Trois Dauphins. The Bourbonist governor was obliged to decamp, leaving him at the head of a force of 7,000 men. Before the Emperor retired to rest, the gates of the Porte de Bonne, which he had been obliged to burst open, were unhinged and brought before his windows by the young men of the town, instead of the keys, of which they could not obtain possession to present them to him.

## ROUTE 132.

VALENCE ON THE RHÔNE TO GRENOBLE  
AND CHAMBERY, THROUGH THE  
VALLEY OF GRÉSIVAUDAN.

147 kilom. = 92 Eng. m.

*Diligence* daily in 11 hours.

The ascent of the valley of the Isère is a most agreeable journey, the country being alike remarkable for its beauty and fertility. The river is spanned by 12 or 15 iron wire suspension bridges, erected for the most

part within a few years. Our road crosses it at Bourg du Pèage, by a stone bridge, connecting that place with

18 Romans (*Inn*: Coupe d'Or?), a thriving town of 9,972 inhab., in a picturesque situation, still partly surrounded by ramparts and flanking towers, one of which leans considerably out of the perpendicular. The church of *St. Antoine* is said to be a curious Gothic edifice.

At this place the last Dauphin, or native prince of Dauphiné, Humbert II., having lost his only son, who leaped from his nurse's arms out of a window of the castle of Mazard into the Isère, and was drowned, signed his abdication, 1349, by which he resigned his domains to Philippe de Valois, on condition that they should be an apanage of the heir to the French crown, and that he should bear the title of Dauphin.

18 Fauries, in the Dépt. de l'Isère.

At La Sône, where the Isère is crossed by a wire bridge, is an old *castle*, now turned into a silk mill, part of the machinery for which was made by Vaucanson, who was a native of Dauphiné.

14 St. Marcellin. *Inn*: Petit Paris, not good. This little town, of about 2,700 inhab., is situated near the Isère. On the height above it, called Mont Surjeu, is a fine terrace walk, commanding one of the best views of the valley.

11 L'Allegrerie.

From the top of the descent to Tullins, commencing at the inn of Morette, a beautiful view opens out over the valley of the Isère, and the serpentine windings of the river, backed by the chain of Alps, and by the Grand Som, which surmounts the Grande Chartreuse, in front. The charms of the landscape, the diversified nature of the ground, the variety of crops, the number and denseness of the trees, and the luxuriant productiveness of the valley, one of the very finest and richest in France, appear to be constantly increasing as far as

11 Tullins (*Inn*: La Poste), a town of 3,500 inhab., only remarkable for its situation in a spot teeming with fertility, so as to give rise to the saying "Si le Dauphiné étoit un mouton, Tullins en serait le rognon." This is a great market for hemp grown in the vicinity.

The stream of the Fure, crossed a little beyond Tullins, is studded with iron forges.

At Moirans, a town of 2,500 inhab., we enter the high road to Lyons (R. 131, p. 503), and the valley of Grésivaudan at

13 Voreppe, which, with the excursion thence to the *Grande Chartreuse*, and the remainder of the route to

14 GRENOBLE, is described in Route 131, pp. 503, 507.

There are two roads up the valley of the Isère above Grenoble.

a. On the rt. bank of the river is the post road, and the shortest way to Chambéry. It is carried along a sort of terrace at the roots of the mountains, which rise abruptly towards the Grande Chartreuse. The bridle road thither turns off to the l. by Sapey at Montbonot (p. 506). The lower slopes are sprinkled with the country seats of the Grenoblois.

20 Lumbin.

On the opposite side of the Isère rise the ruins of Château Bayard.

A little farther on, our road passes on the rt. *Fort Barraux*, commanding it and the passage up and down the valley; it was built by Charles Emmanuel, Duke of Savoy, in the presence of a French army, commanded by Lesdiguières. That general, on being reproved by Henri IV. for his inertness in allowing this to proceed, replied, "Your Majesty has need of a fortress on the side of Savoy, to hold in check that of Montmeillant; and since the duke is willing to undertake the expense, we may as well permit it, and as soon as it is properly furnished with cannon and provision, I undertake to capture it;" and he kept his word, surprising the fort by moon-



light, March 13, 1598. It was afterwards strengthened by Vauban. It commands a charming view from its elevated position. The country hereabouts is enchanting.

19 Chapareillan. Here is the French custom-house.

Hence to *Chambéry*, described in the HANDBOOK FOR SWITZERLAND, is 15 kilom.

*b. The road on the l. bank of the Isère* is interesting and picturesque, but is not furnished with post-horses.

At St. Domène there is a wire suspension-bridge over the Isère: others have been erected at Brignon and La Gache.

At Tencin, which is about half-way, the traveller, while his horses rest, may explore a pretty shady glen, traversed by a gushing stream, leaping in a miniature fall down the rocks.

Goncelin. A road strikes off to the rt. from hence to the iron mines and works of Allevard, 6 m. distant.

About 27 m. from Grenoble stands

*Château Bayard*; a foot-path leads up to it from the church of Grignan.

Its remains are situated on a height which commands the road, and a fine view of the beautiful valley from its terraces. In the mouldering turrets and shattered walls there is little beauty, but as the birth-place of the "Chevalier sans Peur et sans Reproche," they possess great interest. A gateway with the two flanking towers is the part best preserved. The walls of the castle are, in some places, 6 ft. thick. The situation of the room in which Bayard was born (1476) is pointed out by those who show the place, but without authority for what they state. Nearly opposite, beyond the Isère, is the modern fort Barraux. The conspicuous mountain of La Tuille, remarkable for the contortions of the strata in its limestone precipices, appears to close the valley at its upper end.

Pontcharra, the frontier town of France, is about a mile distant. (Inns very dirty and uncomfortable.) Near

this, Lesdiguières, marshal of France, with a force not exceeding 5,700, beat the Savoyard army, 14,000 strong, in 1591.

Before a hired carriage can cross the frontier, it is necessary that the driver procure from the douaniers a permit, termed in French *caution*, in Savoyard *Bolla* or *Bolletone*. It is a paper containing a description of the horse and carriage, which enables them to pass and repass without paying duty.

### ROUTE 134.

GRENOBLE TO MARSEILLES BY GAP AND SISTERON.—PROTESTANT VALLEYS OF DAUPHINÉ.

282 kilom. = 175 Eng. m.

A *courier* goes daily to Gap in 14 hours, taking passengers:—also a *diligence*.

This is a very hilly and a little more circuitous way to Marseilles than the new road by La Croix Haute. (Rte. 135.)

The road on quitting Grenoble is carried within an avenue of trees across the plain of the Drac, at a short distance from its rt. bank, in a straight line from the Porte de la Graille, as far as Claix, where there is a fine *bridge* of a single arch, built on dry land by Lesdiguières, who afterwards turned the course of the river below it. Here the new road by Croix Haute crosses the river, while ours, turning to the l. along high dykes, passes near the junction of the rivers, the Grèze on the l., and the Romanche on the rt., with the Drac. We here bid adieu for the present to the Drac, and follow up its tributary, the Romanche, as far as

18 Vizille (*Inns* wretched), an ancient town of 2750 inhab., on the rt. bank of the Romanche, carrying on some manufactures of cotton-spinning, calico weaving, &c., chiefly founded by the Périer family, one of whom was the French minister Casimir Périer.

The *Château*, partly destroyed by

fire, 1825, was built, between 1611 and 1620, by Lesdiguières, the Protestant commander, and governor of Dauphiné under Henry IV., "ce fin reynard," as the Duke of Savoy called him, who compelled the peasants on his estate to contribute their unpaid labour in constructing it, conformably with the old tax called *Corvée*. In 1788 the Estates of Dauphiné, assembled by Louis XVI. to appease the discontent and outcries of the people of the province, met in this building, and here prepared the bold remonstrance against aristocratic privileges, and in favour of popular representation by the assembly of the Tiers Etat, which served as a signal for the Revolution. This event occurred a year before the opening of the States General at Versailles; Barnave and Mounier were the leading orators. The actual building is now a calico and silk-printing work, and belongs to the family Périer. One apartment is preserved as it was in the time of Lesdiguières, and a bronze bas-relief of him, on horseback, still exists.

The route to Briançon and the Mont Genève, across the grand mountains of Bourg d'Oysans, here turns to the l. (R. 137.)

The road to Gap crosses the Romanche beyond Vizille, and proceeds by a very steep ascent, requiring 2 hours to surmount. The view from its slope over Vizille and the Romanche, and over an intervening hilly ridge to Grenoble and the valley of the Isère, is very fine.

#### 7 Lafrey.

On the l. of the road 3 small lakes, la Motte, L'Aveillan, and Pierre Châtel, are passed in succession. Napoleon on his way from Elba, with little more than 200 men, was encountered, a little to the S. of Lafrey, by a battalion despatched by the governor of Grenoble, and drawn up across the road to intercept his march, between the hill on one side, and the stream which runs out of the lake on the other. Napoleon, on coming in

sight of them, turned off into a meadow on the rt., and sent forward Bertrand to parley with the commanding officer and soldiers opposed to him. The two parties remained thus an hour in view of each other, when Napoleon, advancing to the battalion, opened his grey riding-coat, and baring his breast, so as to show the Star of the Legion of Honour, exclaimed, "Si quelqu'un de vous veut tuer son Empereur, qu'il tire." They were most of them soldiers of his own armies, and their commanding officer had served under him in Egypt. The command given by their officer to "fire" was unheeded by them; the ranks were broken, and the veterans crowded around him; some, embracing his knees, swore never to quit him; many burst into tears, while the air resounded with the cry of "Vive l'Empereur!" On his way hence to Grenoble, at the head of this reinforcement, he was met by the regiment of Labedoyère, which at once joined his ranks, their colonel at their head.

After leaving behind the 3 lakes, some coal mines are passed on the rt.; they are worked to a considerable extent, and produce the species of coal called anthracite (*charbon-à-pierre*).

14 La Mure (*Inn, Poste, dear*), an industrious town, on the top of a high hill, visible from afar; it abounds in mean cabarets and cafés; the chief occupation of the people is nail-making. Capital honey here.

A long-continued and very circuitous descent leads into the valley of the Drac; the road, however, does not approach it closely, but skirts the shattered and deep gorges of its tributaries until a favourable opportunity occurs for crossing them. It is a hilly stage to

11 Souchons. The mountains of the district are mostly of the Jura limestone formation, and are readily disintegrated by the washing of the rivers and by the weather. One very conspicuous conical summit



rising on the W. is called the Mont Aiguille, or Mont Inaccessible, and was regarded as one of the wonders of Dauphiné. It is 6562 ft. above the sea level. Another mountain, still higher, called L'Obieux, rises above

14 Corps; no good inns.

On the opposite (l.) bank of the Drac are the shapeless and uninteresting ruins of the *château Lesdiguières*, built by the Constable as a resting place after death, for he never inhabited it living. His body, transferred hither from Italy, was torn up at the Revolution, and his monument removed to Gap.

We enter the Dépt. des Hautes Alpes and cross the Drac, before reaching the relay of

14 Guinguette de Boyer.

St. Bonnet, on the rt. bank of the Drac, was the birth-place of Lesdiguières, 1343.

The upper part of the valley of the Drac, which we now leave on the l., is called *Champsaur* (campus aureus); it is fertile and picturesque, and a large portion of its inhabitants are Protestants. They formed part of the flock of Felix Neff, who often resided at St. Laurent. This valley communicates at its upper extremity, by the difficult pass of the *Col d'Or-cières*, with the village of Dormilleuse, and the sterile and dreary Val Fres-sinière (Route 139).

10 Brutinel. In this stage, the high chain which separates the vale of the Drac from that in which Gap is situated is crossed by a long and tedious ascent, requiring 2 hours to surmount.

13 Gap. *Inns*: H. du Nord;—De Provence; only tolerable. This little mountain capital, the chef-lieu of the Dépt. des Hautes Alpes, with 7854 inhab., need scarcely detain the traveller, since it possesses no objects of curiosity, but is pleasingly situated, approached by avenues of walnuts, and surrounded by slopes on which the vine still flourishes, although the height above the sea amounts to

2424 ft. In the *Préfecture*, a modern building, is deposited the monument of the Duc de Lesdiguières, François de Bonne, who, after having been the successful leader and defender of the Protestants in Dauphiné, abjured his faith for the rank of Constable of France, imitating, in his apostacy, the example of his master Henri IV. The monument was originally erected over his grave, in his own castle on the Drac, the spot chosen by himself, but was torn thence by revolutionary spoilers. It is of little merit as a work of sculpture, and consists of a white marble effigy, stiffly reclining on his side, in armour.

Gap was the ancient *Vapincum*: it was burnt 1692, by Victor Amedeus of Savoy.

William Farel, the Reformer, was born in the hamlet of Tareau, just outside of Gap: his first sermon was preached in the mill of Burée, but his followers soon drove out the Roman Catholics from Gap, and he took possession of the pulpit of St. Colomb.

The road from Gap to Briançon is given in R. 139. That to Marseilles descends a tributary valley of the Durance, and reaches the borders of that turbulent river at

17 La Saulce: passing previously, a little on the l., the ruined *castle of Tallard*, once the property of the family d'Auriac, now of that of Bé-ranger: the ruins are extensive and picturesque.

16 Rourebeau.

The considerable river Buech is crossed before entering

14 Sisteron (*Inn*: H. du Vers d'Or, a poor sort of inn). This antiquated fortress, which once commanded the passage from Dauphiné into Provence, is composed of narrow dirty streets, cooped up within useless ramparts. It is built at the foot of a perpendicular rock, which is surmounted by a *citadelle*, once the prison of Casimir, brother of Ladislaus VII. of Poland; but so many attempts were made by his friends for his rescue that he was

removed to Vincennes. The works now in progress to strengthen it will, it is said, render it impregnable. There is a curious ancient *Cathedral* here; and fine remains of a monastery, now turned to lay purposes. Sisteron has a picturesque exterior, and its position in a sort of defile of the Durance, here hemmed in by cliffs, is well worthy of the pencil of the artist.

Here the roads to Grenoble by La Croix Haute (R. 135), and to Nice by Digne (R. 136), diverge from our route.

23 Peyruis.

12 Brillane. The Durance, throughout the greater part of its course, is nothing better than a large devastating torrent, at no time a picturesque object, and in summer so far diminished as to be incapable of covering its bed, so that, though its volume is always considerable, its shrunken rivulets of water seem nearly lost amidst beds of gravel and rolled stones, so broad as in places to appear like a dried lake bed.

15 Manosque (*Inns*: Poste, fair;—Petit Versailles) is a flourishing little town, with double the population of Digne, the chef-lieu of the Dépt. des Basses Alpes. The olive is cultivated to a considerable extent in its vicinity.

20 Mirabeau. About  $\frac{1}{4}$  m. from the post-house, on a height, is the ruined *Château* of the family of the celebrated leader and orator of the French Revolution. He frequently resided here in his early years, but was not born here. It is flanked by 4 round towers; and a group of poor houses form a hamlet about its base.

We are now within the limits of scorched and dreary Provence (Sect. VI.). About a mile from the post-house the Durance, hemmed in between high cliffs, is spanned by a suspension bridge, by which the road is transferred to its l. bank, and is carried along it partly on terraces.

11 Peyrolles.

The road begins to ascend near

Meyrargues; and a little beyond the village, which is surmounted by a stately castle, the remains of an ancient aqueduct of brick, designed by the Romans, it is said, to convey the water of the Durance to Aix, are passed. From the top of the hill which succeeds, the eye wanders for many miles down the vale of the Durance, traversed by two more suspension bridges in this part of its course.

The new and wonderful *Canal* which is to supply Marseilles with water commences on the Durance, near the suspension bridge of Pertuis. (See p. 495.)

A considerable tract of well-cultivated table-land is traversed, commanding a view of Mont St. Victoire on the E. (see p. 497), before descending the long hill which leads into

21 Aix, } in R. 128.  
29 MARSEILLES,

### ROUTE 135.

GRENOBLE TO MARSEILLES, BY THE  
CROIX HAUTE.

277 kilom. = 172 Eng. m.

This road was opened 1841, and is excellent. The *diligences* now follow it, having abandoned the old road. As there are many precipices, and few parapet-walls, the journey was at first attended with danger. No one should attempt this road without being prepared to rough it. It is well to engage post-horses to be in readiness at a fixed time beforehand.

There is *no inn* fit to sleep in before reaching Sisteron, and there only a very bad one.

The relays, after crossing the plain of the Drac, below Vizille (R. 134), are

16 Vif.

18 Monestier de Clermont.

The country near Grenoble is very beautiful; woods of walnut and chestnut abound; in the distance snowy peaks appear.

17 Clelles.

14 Lalley. The mountains assume



a very wild and desolate appearance, and there is scarcely any vegetation, on approaching

11 Lus la Croix Haute.

14 La Faurie.

8 Aspres les Veynes.

15 Serres.

16 Larogne. No inn but a wretched cabaret.

17 Sisteron (*Inn*: Vers d'Or; a poor place: see R. 134).

131 MARSEILLES. (R. 128 and 134.)

N.B. Additional information respecting this road and its inns is requested by the Editor.

### ROUTE 136.

LYONS TO NICE BY GRENOBLE, DIGNE, AND GRASSE.

This is by far the shortest route from Lyons to Nice; but a considerable portion of the road is very hilly, and the distance between Digne and Grasse is just furnished with post-horses; but, though on the whole the shortest, it is by no means the most comfortable as regards accommodation. It is, however, a fine road, well engineered, and passes through mountain-scenery on the grandest scale. From Lyons to Grenoble (see R. 131). Thence to Sisteron (see R. 134). The road is carried hence along the L bank of the Durance, and then alongside one of its tributaries, the Bléone, which over-spreads the valley with débris, to

20 Malijay.

Digne (*Inns*: Petit Paris;—Bras d'Or), a town of 3000 inhab., of narrow, steep, and dirty streets, and mean houses, stands in the midst of a cultivated oasis of this desert, through which the torrent passes, restrained within dykes. It is chef-lieu of the Dépt. des Basses Alpes, and its chief building is the Préfecture, once the Bishop's Palace, a very ordinary building.

The ancient *Cathedral* exists only in a scanty ruined fragment on the road to Barcelonnette, and is very curious.

Pliny mentions the town under the name Dina.

About 1½ m. off are *Warm Baths*, supplied by thermal springs, recommended in cases of rheumatism. The accommodation is very simple.

The philosopher Pierre Gassend, or *Gassendi*, was born at the neighbouring village, Champtercier, of poor parents, 1592.

29 Barrême.

25 Castellane (*Inn*). A small town of 2100 inhab., at the foot of an escarped rock, on the Verdon, surrounded by precipices, and in the midst of scenes of the highest grandeur. The road hence commands magnificent views over the coast of the Mediterranean—Nice, Antibes, Ile Ste. Marguerite, and Sardinia.

24 Logis-du-Pin.

22 Nans.

18 Grasse, 10 m. N. of Cannes (12,888 inhab.), has a comfortable *inn*, where an invalid from Nice might put up with advantage during the month of March, as the place is well sheltered. Grasse has, after Paris, the most extensive manufacture of perfumery in France, made from the flowers, roses, &c. which flourish in its neighbourhood, favoured by the mild climate. Some of the nursery-gardens near Cannes produce annually 200,000 frs. worth of flowers of orange, lemon, heliotrope, hyacinth, which are sent to Grasse to supply its distilleries. The views of the Alps from its *Public Walks* are very striking.

23 k. Antibes. } Route 128, p. 499.  
24 Nice.

### ROUTE 137.

GRENOBLE TO BRIANÇON BY BOURG D'OYSANS AND THE COL DE LAUTERET, AND BY THE MONT GENÈVRE TO SUSA.—EXCURSION UP THE VAL ST. CHRISTOPHE.

To Briançon is about 50 Eng. m.

This magnificent carriage road, begun by Napoleon in 1804, has been many years in progress, under the direction of the meritorious engineer

of Mont Cenis, M. Dausse, but owing to the extent and difficulty of the works to be executed, will, probably, not be completed for some time(?). It is, however, perfect and fit for carriages as far as Bourg d'Oysans, between which place and Grenoble *diligences* run daily; and it is practicable for the whole distance, with a light carriage, when the ground is clear of snow. The accommodation on the way, as yet, is bad. "It abounds with some of the finest scenes in the Alps." As far as Vizille the road is the same as R. 134, but, instead of crossing the Romanche, it adheres to its rt. bank, and enters a narrow and finely-wooded glen, threaded by the river for many miles, called Combe de Gavet.

In 1081 a landslip, or fall of a mountain, washed down by the fury of the torrents, formed such an accumulation of earth at the upper end of this defile as to dam up the river Romanche until it formed a lake, which covered the entire plain of Bourg d'Oysans, and rose to a height of 60 or 80 ft. It lasted for two centuries until 1229, when the dyke burst, and the emancipated flood swept all before it, cultivated lands and villages, as far as the city of Grenoble, part of which it also destroyed.

At the upper end of the combe, where the valley opens out, the river Olle flows into the Romanche from the N.; a few miles up it are the iron foundries of Allemont, and the silver mine of Chalanche. At the head of the valley of Allemont are the *Sept Laux*, 7 small lakes, one of the "wonders" of Dauphiné, abounding in trout. By the Sept Laux a passage may be effected to Allevard in the valley of the Isère, p. 511.

Bourg d'Oysans, 7½ leagues (*Inns*: very bad: Poste, civil;—Chez Manuel, (? Etoile), a town of 3052 inhab., possessing a manufacture of cotton.

"An interesting excursion may be made from Bourg d'Oysans to La Bérarde, in the upper part of the

valley of St. Christophe, between 7 and 8 hours' walk from the Bourg. The only Inn on the whole route is at the finely situated village of Venos, 2½ hours from Bourg d'Oysans, where there are tolerable quarters, but the traveller must carry his own provisions thither. St. Christophe is 2 hours above Venos, and La Bérarde lies at the foot of Mont Pelvoux, the highest mountain in France or in the S. Alps, its loftiest summit, the Point d'Arcines or des Ecrins, being 13,123 ft. above the sea level. The scenery of the whole valley, and especially at and above La Bérarde, may vie in grandeur with any in the Alps. The valley is less known than Chamouni was before the time of Wyndham and Pocock; but a day devoted to visiting it from Bourg d'Oysans will always be remembered with gratification by the lover of sublime scenery."

A coach starts every evening from Bourg d'Oysans for Grenoble. A char might be hired here, to cross the Lauteret to Briançon, for 18 or 20 fr. in 12 or 14 hours. About 3 m. above Bourg d'Oysans, the plain terminates, and the Veneon, coming from the l., pours itself into the Romanche. Between these two streams rises the snowy Mont de Lans. The road is carried along a tremendous gorge called *Les Infernets*, on the N. side of this mountain, through which the Romanche forces its way, by terraces and tunnels cut out of the solid rocks. Two very long galleries have thus been formed for the passage of the road. The first of these, more than 234 yards long, and very wide and high, is one of the finest works of the kind in the Alps.

The gorge of Infernets is succeeded by a sterile upland valley, strewn with rocks. The road is nearly completed, and fit for carriages, with the exception of some cuttings near the mouth of Les Infernets, as far as Le Dauphin (4 leagues), in a bare and dreary situation, with scarce a habitation around. A little above this, on the l., is a



fine waterfall, called *Le Saut de la Pucelle*.

Between Le Dauphin and La Grave a stupendous gorge is traversed by the Romanche, remarkable for the extraordinary grandeur and utter nakedness of the precipices of gneiss which form its sides. It is called *La Combe de Malval*. These precipices are the escarpments of vast mountains covered over with eternal snow and glaciers, which terminate at the edge of the cliff overhanging the combe; and numerous streams descend from them in falls across the road.

Several small torrents, after circulating among the upland pastures, called Prés de Paris, leap down from the N. brow of the gorge, in falls more than 300 ft. high. Beyond, the valley is strewn with blocks of gneiss, fallen from above, some of them as big as a house.

We pass from the Dépt. d'Isère into that of the Hautes Alpes, about a mile before reaching the miserable village of La Grave, grandly situated on a projecting rock, backed on the S. by vast snowy heights. There is a small and tolerably clean cabaret at La Grave. The church is worth looking at, and the *view* from it is splendid. A long day's walk leads hence over the *Col des Infernets*, a wild and high but not difficult pass, to St. Jean Maurienne.

There is a grand scene a little short of Villars d'Arène, where the road is carried through a dark and deep defile, overhung by the precipices above, while the Romanche dashes down in a fine fall into the depths below.

Villars d'Arène (4 leagues), another wretched village, is situated at the foot of the pass of the Lauteret, which the route now ascends, leaving on the rt. the Romanche, whose source is in an upland valley to the S., at the foot of the snowy *Mont Pelvoux*.

The *Col of the Lauteret*, which separates the waters of the Romanche from those of the Guisanne, is 6869 ft. above the sea level, about 500 ft.

higher than the Mont Genève. Its summit is covered with some of the most beautiful pasturages in the Alps. Near the crest of the Col, which is not more than 50 yards broad, is an ancient

Hospice (2 leagues), founded by Humbert II., Count of Dauphiné. The view from the summit is fine: the Montagne d'Oursine is a grand object on the S.W.; from the glacier at its base rises the Guisanne, while in that of Tabouchet, to the S., is one of the sources of the Romanche. The Mont Pelvoux from this point appears lower, because more distant.

A steep descent leads down the valley of the Guisanne by Le Lauzet and Le Casset, near the glacier of Lusciale, to

Monestier (4 leagues), a town of 2,500 inhab., has several indifferent Inns, 12 m. from Briançon, having in its neighbourhood *hot sulphureous springs*, used for baths, and so abundant, that within a short distance of the source they serve to turn a mill. The valley around, and from hence to Briançon, is fertile, well cultivated, and studded with numerous villages; the upper slopes clothed with fir woods, while the view of the course of the Guisanne, backed in the distance by Briançon, and its extraordinary group of forts, piled one over the other, forms a magnificent scene. According to Brockedon the peak of the Monte Viso is visible in clear weather, surmounting the Alps in the extreme back-ground.

From Monestier to Briançon (15 kilom.) the road is completed: and this part of the valley is remarkable for its populousness, there being not less than 22 villages between the foot of the Lauteret and

15 *Briançon*. *Inn*: H. de la Paix, not very clean; but great civility and attention, with tolerable cuisine.

Briançon, a first-class fortress of great strength, a sort of Alpine Gibraltar, commanding the passage from Italy into France by the Mont Genève, is a most picturesque and im-

posing object at a distance. It stands at the meeting of 3 valleys, at the foot of an isolated and escarped rock, whose summit is crowned by the *Fort du Château*, so named from an old castle, now demolished. Many of the streets of the town are so highly inclined that they are impassable for vehicles, and the carriage road makes a circuit, and enters it by a series of zigzags. All the heights around are converted into points of defence; fort rises over fort up to the very clouds, which frequently shroud from view the upper works. Where the position is not inaccessible through natural precipices, it has been rendered so by artificial escarpments. The rivers Guisanne and Clairée, which unite beneath the walls of the town with the infant Durance, run in deep gullies, whose sides are precipices, forming as it were natural ditches to the fortress. The principal works are on the l., or E., bank of the Clairée, whose deep and savage gorge is crossed by a bridge of a single bold arch, 130 ft. span, and 168 ft. above the water, constructed 1734. An excellent road leads, in zigzags, up the abrupt heights from this bridge to the different forts, which communicate with each other by subterraneous ways. The largest fort is called *Les Trois Têtes*, because it occupies a triple-headed crag; on a level with it is *Fort Dauphin*; 330 ft. higher, towards the Durance, is *Fort Randouillet*, whose batteries are partly excavated in the rock: nearly 2,000 ft. above this is the *Donjon*, and finally the *Point du Jour*, commanding all the other defences. The different points, or mamelons of rock on which these forts are built, all belong to the *Mont Infernet*, whose summit still supports the ruins of a fort built in 1814, at a height of 9,350 ft. above the sea level. From its crest the Mont Pelvoux is a magnificent object, and the valley Des Prés or De Neuvache, down which pours the Clairée, and that leading up to the Mont Genève, are well seen.

Permission to visit the forts may be obtained from the commandant in the town. If the weather be clear, it is worth while to ascend to Randouillet, on account of the view up the beautiful valley of Guisanne, studded with villages, and towards the Col de Lauteret (p. 517), otherwise the traveller may content himself with seeing the Fort du Château. The fortifications of Briançon have been greatly strengthened of late, and the improvements are not yet completed.

In the town itself there is nothing to see. The Port d'Embrun bears this inscription: "Aux braves Briançonnais, pour la conservation de cette ville, Louis-Philippe reconnaissant;" alluding to the refusal of the inhabitants, in spite of the orders of the préfet, to deliver up the town, though defended by a weak garrison, to the allies in 1815.

Briançon has 3,455 inhab.; it stands at an elevation of 4,285 ft. above the sea level, and may be said to endure 7 months of winter. It has hitherto been cut off, in a manner, from the rest of the world, being accessible by only one carriage road from the side of Gap; the Sardinian government having refused to render the Mont Genève practicable for 4-wheeled carriages. The carriage-road, however, direct from Grenoble over the Lauteret, has been many years in progress, and may soon be finished. It is even now practicable in a light char.

It takes 12 or 14 hours to reach Bourg d'Oysans by this route, in its present state. A *diligence* goes daily to Embrun and Gap. (R. 139.)

The passage of the Mont Genève leads from Briançon to Susa, a day's journey with a 1-horse char. The road leaves the Val des Prés on the l., traversing thick forests of fir, and at the end of about 2 leagues of ascent, by zigzags, reaches the summit of the pass at Bourg Mont Genève, a hamlet on a plain, 6,476 ft. above the sea level, on which barley ripens. From this plain, at a short distance



from each other, rise the Doira, which flows through the Po into the Adriatic, and the Durance; hence the verses

“ Adieu ma sœur la Durance,  
 Nous nous séparons sur ce mont;  
 Tu vas ravager la Provence,  
 Moi féconder le Piedmont.”

An obelisk erected on the summit commemorates the construction of this road, under Napoleon.

This pass was crossed in 1494 by Charles VIII. of France with the army with which he invaded Italy, dragging with him several hundred pieces of artillery.

The descent into Piedmont lies through

Cesanne	2 leagues.
Oulx	2 —
Salabertrand	2 —
Fort Exiles	1 —

*Susa* (22 m. from Cesanne) described in the *HAND-BOOKS* for SWITZERLAND AND N. ITALY.

### ROUTE 139.

GAP TO BRIANÇON, BY EMBRUN, AND  
 EXCURSION INTO THE VAL DE QUEY-  
 RAS, VAL D'ARVIEUX, AND VAL FRES-  
 SINIÈRE.

91 kilom. = 56 Eng. m. to Briançon.

A *diligence* (very slow) daily.

The valley above Gap is stony and dreary.

17 Chorges appears to have preserved traces of the name of the ancient inhabitants of this district, the “Caturigæ.”

After crossing a high ridge the road descends in a gradual sweep into the valley of the Durance, which it reaches at the foot of a precipitous mountain. The valley hereabouts is a scene of unmitigated desolation: the turbulent river rolls along a furious flood of dirty water, undermining the loose shaley rocks (? Jura limestone) composing its sides, strewing the bottom with rubbish, and constantly forcing its banks. The road is frequently swept away by

inundations, and for some distance is carried along temporary causeways. The Durance is crossed by a wooden bridge at

14 Savines, and again before reaching

10 Embrun. *Inn*: the best is indifferent. Embrun (anciently *Ebrodunum*), an old-fashioned fortress, surrounded by loop-holed ramparts, overlooks the valley from the top of a singular platform or table of pudding-stone rock, escarped on the side facing the river, and separated by a ditch from the mountain behind it. The *Cathedral* has a fine lofty Romanesque tower ornamented with circular arches, and a N. portal, whose round mouldings rest on pillars of the red marble of the country, the two outer ones being supported on rudely-carved lions. The W. end is chequered with slabs of yellow limestone and black shale. It has a tolerable wheel window, filled with stained glass. The interior is not otherwise remarkable: the roof is Pointed. Against the N. door is nailed a horse-shoe, said to have been thrown by the horse of Lesdiguières, the Protestant leader, which is reported to have stumbled and thrown its master in the porch as he was spurring on his steed to enter the church, and thus saved it from desecration. Such is the Romanist legend. The image of Nôtre Dame d'Embrun was held in great reverence by Louis XI., who, as dauphin, resided long in Dauphiné. (See “*Quentin Durward*.”)

Beside the cathedral stands the building formerly the archbishop's palace, now a barrack; and near it rises a curious tower of ancient masonry called *Tour Brune*.

The first church at Embrun is said to have been built by Constantine the Great. The line of its archbishops is traced back, uninterruptedly, to his time: they were made princes, and endowed with the sovereignty of a large part of Dauphiné, by the emperor Conrad II. A portion of their archives, captured with the town by

Lesdiguières in 1585, are now in the public library of Cambridge.

Embrun is a poor town of narrow dirty streets; the view from its ramparts is striking, but the mountains around are bare in the extreme.

Little occurs worthy of remark in pursuing the course of the Durance upwards, until, after crossing the river to its l. bank, we approach the very picturesque and strong fortress of *Mont Dauphin*, the key of the pass into Italy, standing conspicuous on an elevated platform of rock, appearing to close the mouth of the lateral valley of the Guil, which here enters the Durance from the N. E. It was fortified by Vauban, who constructed its bastions of the rough pink marble of Eygliers, a neighbouring village, and completely commands the 2 valleys—presenting escarped precipices on either side, so as to be almost impregnable. Our road is carried under the base of the rock of pudding-stone, crowned by the fortress, 500 or 600 ft. above the river, and near it is the post-house,

16 Plan de Phazy.

The river *Guil* rises at the base of the Monte Viso, on the Piedmontese frontier: its valley, called *Val de Queyras*, consists chiefly of a series of narrow defiles, through which the river seems to have forced its passage. About  $1\frac{1}{2}$  m. up, on its l. bank, is Guillestre, which was one of the stations for English prisoners during the war. Above this the valley is rent by an extraordinary fissure, called *Gorge de Chapelue*, bounded by precipices from 700 to 800 ft. high, described by Brockedon as “one of the *finest in the Alps*.” Nearly 2 hours are required to traverse it. In places the rocks almost meet over-head, and the road crosses the depths, in which the Guil flows far below, from side to side, as the rocks present a shelf for its passage; but at times they are so completely precipitous that it is necessary to ascend the heights, and go over their summits. At the upper end of the defile, about 4 hours’ walk

from Mont Dauphin, is the *castle of Queyras*, an ancient feudal stronghold of the seigneurs of Château-Ville-Vieille, perched on the top of a monstrous rock, which seems to have been detached from the neighbouring peak in order to guard the passage. It is now converted into a military post, and is occupied by a company of infantry. A tolerable inn here, chez Bosi.

Two passes, the Col des Hayes and Col d’Isoard, lead N. over the mountains to Briançon.

In the remote valleys around Queyras the Protestants are very numerous, especially in the *Val d’Arvieux*, reached by a rough road branching off on the l. about  $1\frac{1}{2}$  m. below Château Queyras; as well as in the Commune of Molines, and its hamlets, St. Veran, Pierre Grosse, and Fousillarde. They have churches at Arvieux, St. Veran, and Fousillarde, in all of which service is performed once in 3 weeks by a minister who resides for a week in each parish alternately.

Felix Neff’s residence was at La Chalp, in the Val d’Arvieux, above the village of that name; a foot-path runs thence over the mountains to Briançon. *St. Veran*, where he had also a small Protestant flock, is situated in another valley, 8 or 10 m. to the S. of Château Queyras, on the very verge of vegetation: it is the loftiest human habitation in France, 6692 ft. above the sea-level, and the nearest towards the snowy summits of the Viso. Neff said of it that it was “the highest, and consequently the most pious village in the Val Queyras.”

About 2 m. above Queyras is Abries, where the Guil bends to the S. E. towards the Monte Viso, whose unscaled peak forms a striking object amidst the wild and savage scenery of this upland valley, here contracted and strewn with rocks. It is very grand, and well worth exploring, not only on its own account, but because through the two passes issuing out



over the mountains at its head most interesting excursions may be made into Piedmont.

*a.* The *Col de la Croix* leads from the village Ristolas and Monta (French custom-house) to the Protestant valleys of the Vaudois, and their capital La Tour.

*b.* The *Col de Viso* conducts from La Chalp, a hamlet  $1\frac{1}{2}$  m. above Monta, along the rt. bank of the Guil, by a path only practicable on foot, in 5 hours, from Abries to the summit of the Pass, 10,150 ft. above the sea-level, whence the view over the valley of the Po and plains of Piedmont, comprising an horizon of 100 m., "is one of the most magnificent in the world."—*B.* The traveller may enter Italy by the Col de Viso, and return by La Tour and Col de la Croix. The routes are described in the *HAND-BOOK for SWITZERLAND*.

From Mont Dauphin to Briançon the road constantly follows the course of the Durance, sometimes on a level with it, at others at an elevation of many hundred feet above it. The river runs for a long distance at the bottom of a deep gash, whose sides, rarely susceptible of cultivation, slope at a very high angle. About 6 m. above Mont Dauphin, near the village of La Roche, prettily situated beside a small lake, a long timber bridge crosses the Durance, and an abrupt shepherd's path, scaling the mountain, leads up into the Val Fressinière, the poor Alpine valley once blessed by the ministering care of Felix Neff, and which now serves as his last resting-place. "The path creeps up the mountain in an oblique direction, and then over some rugged ground leads to a defile through which a torrent rushes, bordered on each side by groups of cottages, crossed by an Alpine bridge, below which is a cascade. This hamlet is Palons, and the torrent, called the Rimasse, is the guide which conducts to the Val Fressinière. There

is no mistaking the way. The villages passed are Fressinière, whence the valley is named (1 league), in a lovely fertile vale, producing grain of several kinds and fruit-trees: Vio-lins (1 league); here is a Protestant church, built by Neff, to which a tower has lately been added: Min-sas (2 m.). Then comes the toilsome, rough, and clambering path, through a country perfectly savage and appalling, to Dormilleuse (3 m., or 5 leagues from La Roche), a miserable village at the very foot of the glaciers, constructed like an eagle's nest upon the side of a mountain, the most repulsive, perhaps, of all the habitable spots of Europe. Nature is here stern and terrible, offering nothing to repay the traveller, but the satisfaction of planting his foot on the rock which has been hallowed as the asylum of Christians of whom the world was not worthy. It consists of a few poor detached huts, from which fresh air, comfort, and cleanliness are all banished; some without chimneys or glazed windows, others consisting of a mere miserable kitchen and stable, seldom cleaned out more than once a year, where the inhabitants spend the greater part of the winter along with their cattle, for the sake of the warmth. Their few sterile fields hang over precipices, and are partly covered with blocks of granite. In some seasons even rye will not ripen. Many of the pasturages are inaccessible to cattle, and scarcely safe for sheep. Yet in this gloomy spot did the virtuous Protestant pastor, Felix Neff, sit himself down, because his services seemed here to be most required, where he had every thing to teach, even to the planting of a potato."—*Gilly's Memoir of Neff*.

A mountain pass leads over the *Col d'Orcière*, at the head of the Val Fressinière, into the valley of Champ-saur, traversed by the Drac. (R. 134.)

Near Palons are several caves in the rocks, which served the inhabitants in time of persecution as places of refuge

and of worship: one of them is called Glesia (L'Eglise).

17 La Bessée. Near this a step or rise occurs in the valley of the Durance, which seems barred by a high bank or natural dam. Up this the road to Briançon toils in zigzags. A little above La Bessée, the ruins of an embattled wall are visible, running across the valley from either bank of the Durance to the summit of the heights commanding it on the rt. and l., evidently designed to close the passage up, and check the incursions of a people from the S.

Nearly opposite La Bessée to the N.W. opens out the Val Louise, which terminates in the *glaciers* and peaks of the *Mont Pelvoux*, whose top rises 13,440 ft. above the sea level. "The poor village called *La Ville de Val Louise* is the chief place. Its environs are very picturesque. The valley branches into two; that on the rt. leads to Mt. Pelvoux; through it 2 French engineers most nearly attained the summit, but not quite. By the other branch there is a difficult pass into the Val Godemar, called Col de Celar."—*Pr. F.*

Within this valley is a cavern called Baume des Vaudois, from a number of those unfortunate professors of an ancient faith who concealed themselves within it in 1488, carrying with them their children, and as much food as they could collect, relying on its inaccessible position, and the snows around, for their defence. When the officer despatched by Charles VIII. arrived with his soldiers in the valley, none of its inhabitants were found; but at length tracing out their hiding-place, he commanded a great quantity of wood to be set fire to at the mouth of the cave to burn or smoke them out. "Some were slain in attempting to escape, others threw themselves headlong on the rocks below, others were smothered; there were afterwards found within the caverns 400 infants stifled in the arms of their dead mothers. It is believed as a certain fact that 3000 persons perished on that occasion in this valley."—*Gilly's Mem. of Neff.*

Above this the valley is more wooded, while low down little patches are cleared of stones to allow the grass to grow.

17 Briançon, in R. 137, p. 577.



## SECTION VIII.

## BURGUNDY.—FRANCHE-COMTÉ.

ROUTE	PAGE	ROUTE	PAGE
144 Paris to <i>Dijon</i> , by <i>Troyes</i> .	523	155 <i>Descent of the Haut Rhône.</i>	
145 Paris to <i>Dijon</i> , by <i>Sens</i> and <i>Tonnerre</i> . . . . .	531	— <i>Aix</i> in <i>Savoy</i> to <i>Lyons</i> .	539
148 <i>Dijon</i> to <i>Geneva</i> , by <i>Dôle</i> .	533	156 <i>Lyons</i> to <i>Geneva</i> , by <i>Nan-</i> <i>tua</i> and <i>Bellegarde</i> . . . . .	540
150 <i>Dôle</i> to <i>Lausanne</i> , by <i>Pont-</i> <i>arlier</i> . . . . .	535	159 <i>Lyons</i> to <i>Besançon</i> , by <i>Bourg</i> and <i>Lons-le-Saulnier</i> . . . . .	541
152 <i>Dijon</i> to <i>Châlons-sur-Saône</i> , by <i>Beaune</i> and the <i>Wine Dis-</i> <i>trict of the Côte d'Or</i> . . . . .	536		

## ROUTE 144.

## PARIS TO DIJON, BY TROYES.

310 kilom. = 192 Eng. m.

*Malleposte* (3 places) in 24 hours.

*Diligences* daily, in 33 hours.

A Railway is in progress by way of Melun, Montereau, and Nogent. Thence to Troyes will be finished 1847.

The road turns out of Route 106 beyond

7 Charenton.

14 Grosbois. The *Château* was the property of Monsieur, afterwards Louis XVIII., and now belongs to the Prince de Wagram.

8 Brie Comte Robert. The name of this little town comes from its situation in the district of Brie, an ancient dependence of the province of Champagne, and from Robert Comte de Dreux, and seigneur of Brie, its founder or benefactor. The parish church is Gothic of different periods from the 13th to 16th century. It contains some painted glass. The old castle is an utter ruin. The ruined chapel attached to the Hôtel Dieu merits notice.

16 Guignes.

Near this is the *château La Grange*, the residence of Lafayette, a moated mansion, whither he retired during

the rule of Napoleon, occupying himself with agricultural pursuits; here he was visited by Fox, who planted the ivy which covers one of the towers.

8 Mormant.

11 Nangis.—*Inns*: Lion d'Or;—Sauvage. There is an ancient church and ruined castle here. (?)

11 Maison Rouge.

11 Provins.—*Inn*, H. de la Fontaine. The ancient walls, flanked by watch towers, of this venerable but decayed town, enclose, besides the houses, a wide open space now occupied by gardens and vineyards. It lies between 2 hills, the old town on the highest ground, the new town on the lower slopes.

In the upper town, which abounds in ruins, rises, conspicuous far and wide, an ancient tower of great size and solid masonry, known as the *Grosse Tour de César*, though undoubtedly a work of the middle ages. It is square at the base; but in its upper story 4 turrets detach themselves from the centre, which becomes octagonal, and is connected by flying buttresses with the turrets. This building, containing 2 curious halls and dungeons, now serves as bell-tower to the neighbouring church of *St. Quiriace*, remarkable for its early

date and plain massive architecture; it is surmounted in the centre by a cupola, and beneath is a curious *crypt*.

Under various buildings in the high town run extensive *vaults* and *caves*, arched over and partly sustained on pillars: they appear to have been formed out of ancient stone quarries, and may have served as places of refuge, or for warehouses and cellars in former times. The 2 old gates of St. Jean and Jouy still lead through the bastioned antique fortifications to the upper town.

In the *lower town*, which is also surrounded by ramparts and boulevards, stands the church of *Ste. Croix*, completed in 1538, but it includes a more ancient chapel of *St. Laurent*, of the 15th cent., containing delicate sculptures. This church is much modernised, but supported in the interior by piers of primitive form, two of them twisted, and contains fine carved wood. The church of *St. Ayoul*, a simple nave without transepts or apse, in the Round style, may reward the notice of the antiquary.

The *chapel of the hospital* contains the monument in which was deposited the heart of Thibault VII., Comte de Champagne, who founded here, 1050, an hospital for pilgrims.

Provins has for centuries been celebrated for *Roses* (improperly called Provence roses); and though the cultivation of them for purposes of commerce has now nearly ceased, they are still partially grown to make "conserve," and to colour bonbons. The Provins rose has a rich crimson hue, and is said to have been brought by the Crusaders from the Holy Land.

The two small rivers, the Durtin and Vouzie, above whose confluence Provins is built, turn no less than 50 or 60 corn-mills; their waters are thought to be well fitted for dyeing, and there are consequently numerous dye-works on their banks. Population 6009.

The road affords little subject for remark until you reach

18 Nogent-sur-Seine (*Inns*: Cygne d'Or;—Cygne de la Croix), a thriving town (3365 inhab.), prettily situated on the l. bank of the Seine, at the point where it becomes navigable. It is intersected in the middle by the *Ile des Ecluses*, which is connected with either bank by stone bridges, one of which was blown up on February 11, 1814; when Nogent was bravely defended, step by step, and house by house, by a small body of French, under Bourmont, against the Allies, who finally carried the place by storm.

Here is a handsome *church*, in the late Gothic of the 15th century, surmounted by a fine tower, constructed between 1521 and 1542; also *agreeable walks* round the town.

Nogent is famous for soft cheese.

*Railway* from Nogent to Troyes.

At St. Aubin, about 4 m. beyond Nogent, the road passes within view of the chimneys and roofs of an iron-forge now abandoned, which occupies the site of the famous monastery of the *Paraclete*, founded by Abélard, 1123. It afterwards became the retreat of Heloise, and the final resting place of both. In 1792, when the abbey was sold, the coffin containing their bodies was removed to Nogent, and afterwards transferred to Paris, where it is now deposited in Père la Chaise, under a Gothic monument, originally erected at the monastery of St. Marcel, near Châlons, over the remains of Abélard. The monument raised over the two lovers at the *Paraclete*, ornamented with a figure of the Trinity, was destroyed at the Revolution, 1794. A marble *pillar* was placed over the mouth of their burial vault, within the area once occupied by the church of the *Paraclete*, by the late Gen. Pajol, the owner of the ground, and within it still remains the stone sarcophagus which once enclosed their leaden coffin. The abbot's house is now inhabited by a peasant.

8 Pont le Roi, a town of 2000 in-



hab., at the junction of the Aube with the Seine: the *Château* was built by Casimir Périer in 1830.

14 Granges. (Aube.)

15 Grès. The country possesses slight interest.

19 TROYES (*Inn*: Grand Mulet; good, clean, and cheap) is chef-lieu of the Dépt. de l'Aube (population 25,563), and is seated on the l. bank of the Seine, branches of which, conducted through the town in canals, contribute to its industry and cleanliness. In the reign of Henri IV. Troyes had 60,000 inhabs., so that it will be perceived its present state is one of decay; many of its most industrious citizens having been banished by the revocation of the Edict of Nantes. "This ancient capital of Champagne, in which the peculiar provincial character of the 'Francs Champenois' is thought to be exhibited in its most genuine aspect, still contains much that is interesting. The greater part is of timber and plaster, or pargeting, exactly in the old English style, though, as in England, the number of these venerable buildings diminish day by day.

"The *Cathedral*, dedicated to St. Peter, is a splendid specimen of the *flamboyant* Gothic, full of bold inverted curves, open borders of festooned pendants, and all those luxuries which preceded the abandonment of the style. The church is 374 ft. long, 96 ft. high to the point of the roof, and has 5 aisles, producing beautiful combinations of perspective. Those who are fond of painted glass will here have much enjoyment, for the windows are most brilliant and elegant. They exhibit the finest and most delicate mosaic patterns, which are more rare than other styles in this species of art. The clerestory is here really a *clear story* from the size of its windows, filled with as fine painted glass as the rest. In this church, and before the high altar, May 20, 1420, was our Henry V.

affianced to the Princess Katherine; and on the following day was signed the memorable *Treaty of Troyes*,—that treaty so full of disaster, by which the victor of Azincour was declared to be the heir of Charles VI., and his successor in the kingdom. Charles VI. was present, together with very many magnates and nobles, English and French; but, above all, Philip Duke of Burgundy, by whose intervention the treaty was negotiated and concluded.

"The *Ch. of St. Urbain* is unfinished. It contains a great deal of open tracery, such as is found at Cologne, but of which there are very few examples on this side of the Rhine. Maréchal Vauban, who studied Gothic architecture attentively, used to say of this church that it was built of *coupons*."—*F. P.*

The marriage of Henry V. took place June 2, 1420, in the *Church of St. Jean*, now much mutilated externally. It encloses a well, which furnishes water to the neighbouring quarter of the town, and possesses an altar-piece, painted and given by *Mignard*, who was born in the parish.

The *Sainte Madeleine* possesses a stone *rood-loft* (jubé) of great beauty and richness of decoration, the work of John Gualdo, an Italian, 1518. Most of the statues have been destroyed, and some replaced by wood. Those which remain are good. In this church, at *St. Nicholas*, and at *St. Nazaire*, are painted glass windows.

*St. Pantaleon* is ornamented internally with statues, the best of which are attributed to an artist named François Gentil.

In *St. Remi* there is a bronze statue of Christ by *Girardon*.

The *H. de Ville* was built 1624-70 from a design of Mansard.

The *Public Library* is said to contain 50,000 vols. and 5000 MSS.: the hall in which they are deposited is decorated with painted windows representing events in the life of Henri IV.

"The ancient *Boucheries* consist of several long low ranges of timber buildings, evidently quite as old as the time of our Henry V. It used to be an article of popular belief that flies never entered this building, which some writers ascribed to a property of the wood, others to the construction of the edifice, and others to a spell or charm of St. Loup. The immunity, however, like all other privileges, has disappeared.

"Troyes would delight an architect. The houses are generally old and picturesque, and there are several churches besides those which we have noticed, Troyes having suffered less than many places during the Revolution."—*F. P.*

The *Hôtel Megrigny* is a good specimen of the architecture of the Renaissance, flanked by 2 turrets.

The name of Troyes will always be familiar to us from our *Troy-weight*, which obtains its name from the standard of this town.

The city has little commercial activity; it is evidently the centre of an agricultural community. A new *Canal*, however, is in progress to form a communication from Troyes to the navigable part of the Seine, and also to the Canal of Burgundy; it will doubtless contribute to the prosperity of the town.

The chief manufacture carried on in and around Troyes is that of *night-caps*.

Troyes is a very important place in a military point of view, being the centre where various roads meet on the l. of the Seine, in the midst of a plain cut up by streams and woody morasses. As a proof of this, in the course of the wonderful campaign of 1814, when Napoleon kept at bay so many enemies pressing on him from all sides, it was twice taken by the Allies and once by the French. In the month of February the portion of the Allied armies encamped round the walls amounted to 100,000 men, and they required 12 hours to march

through it. Here the first steps for the Restoration of the Bourbons were taken, and the white cockade was publicly displayed in France for the first time after a lapse of more than 20 years.

*Railway* to Nogent and Montereau.

At Troyes the high road from Paris to Basle (Route 162) branches off from that to Besançon and Dijon. *Mallepostes* run on both.

19 St. Parre-les-Vaudes.

14 Bar-sur-Seine. Pleasantly situated on the banks of the infant Seine, here a clear rivulet. A quiet country town. *The Church* has great elegance.

19 Mussy.—"The *wine* character of the country now becomes very apparent. The vineyards are, however, principally in strips, alternating with corn, potatoes, haricots, hemp, clover, altogether conveying a cheerful impression. This country begins again to vary from its hitherto swelling or undulating monotonous level. Towards the west, hills of a tabular shape appear, which continue increasing until they form almost a connected chain. This is the commencement of the well-known *Côte d'Or*, of which more hereafter."—*F. P.*

15 Châtillon-sur-Seine. (*Inns: Poste?; H. de la Côte d'Or*; dirty, and barely tolerable), a neat small town. A Congress of representatives of the allied sovereigns, at which Lord Castlereagh appeared on behalf of England, was held here, February 1814, to offer to Napoleon the throne of France, provided he would be content with its limits previous to the Revolution; he rejected these terms, and, emboldened by the successes he gained in the course of the campaign, broke off the negotiations, and the result was his dethronement. Marshal Marmont was born here, and has built on the spot a fine *château*.

"The road now becomes more hilly, masses of grey rock, coloured



and stained with iron hues, starting abruptly from the sides of the hills. The fields and soil generally stony, yet pleasantly watered by sparkling streams. On the hill sides many little ancient towns or *bourgades* are seen, even now strongly bearing the impress of feudality. Surrounded by walls and gates, it seems as if not a house could venture to stray out of the protecting circuit, indicating the ancient unsettled state of the country, or, at least, of the habits which arose from its insecurity.”—*F. P.*

14 Aisey-le-Duc.

15 Ampilly-le-Sec.

15 Chanceaux, celebrated for the manufacture of preserved barberries (*épinettes*). Here is a comfortable little inn, where a good stock of the preserve is kept.

The Seine takes its rise in the high land of the Côte d’Or, within about 1 m. of Chanceaux.

The road from Paris to Dijon, by Tonnerre (R. 145), falls into our road here.

“The country now begins to assume a picturesque character; you begin, as it were, to cross the fibres of the roots of the Jura, and the beauty of the scene gains as you advance.

“12 St. Seyne, beautifully situated amongst a ridge of bold hills, almost of a mountainous character. The town, which contains about 1000 inhab., is at the bottom of the valley. Above, on the brow of the hill, are the remains of a celebrated *Abbey* of Benedictines, founded by St. Seguanus before 580. The church, whose construction dates from the beginning of the 15th century, is yet standing, and contains much that is remarkable; amongst other things, a series of ancient frescoes representing the life of the patron founder. This church has some peculiarities in its architecture, and the stalls of the monks continue undisturbed.”—*F. P.*

10 Val de Suzon, so called from the torrent Suzon, which flows through the very pretty valley. “The ge-

neral aspect of the village, which you reach by a steep descent, continues to remind the traveller of his gradual approach to Switzerland; and indeed, throughout the whole of this district, he will observe how overcharged is the opinion of the monotony of French scenery, even in the provinces which are not professedly mountainous.”—*F. P.*

17 DIJON.—Hôtel de la Cloche; good, and well situated, near the Cathedral, close to the Paris gate:—H. du Parc. “The ancient capital of the Duchy of Burgundy, now the chef-lieu of the Dépt. de la Côte d’Or, contains 26,000 inhab. The first view of this once important and opulent city is peculiarly agreeable and striking. It bursts upon you after the long ascent of the Val de Suzon, when you reach a species of tableland. The Jura faintly bounds the horizon. Dijon lies outspread on the plain below. The great fortress-like masses of the churches, and the Palace of the Dukes of Burgundy, standing out boldly from the buildings of the town, mark themselves forcibly on the landscape, quite as advantageously as the greater richness of battlemented turrets and of open spires. All the ecclesiastical buildings of Dijon are more or less remarkable for their castle-like solidity; and even the *Flèche* of *St. Benigne* (now the *Cathedral*) is scarcely an exception to the rule. This spire, by the way, though it enjoys a species of celebrity, is merely an elongated pyramid or obelisk of wood, and possesses no beauty, except from its height and its general harmony with the rest of the structure. *St. Benigne* before the Revolution was conventual, but it became the cathedral when the hierarchy was restored; the original cathedral having been destroyed during the Revolution. *St. Benigne* also suffered much. The present cathedral is upon a grand scale, particularly the front, but in every part it shows the ravages it has sustained.

*Nôtre Dame* is a singularly fine church in the purest Gothic, somewhat like Ely, and remarkable for the boldness of its construction. This also was one of the churches which were studied by Vauban, as affording lessons in vaulting, and for the best employment of materials. The front exhibits a beautiful play of light and shade; but its effect is impaired by the absence of the towers, which were intended to complete the elevation. At one corner of this façade, where it was intended a tower should rise, still stands the clock brought in 1382 by *Philip le Hardi*, an epithet which his general conduct deserved, though, in this achievement, *le Cruel* would have suited him better, for he plundered and burnt the town, and massacred the inhabitants. Jacques Marques, a Flemish mathematician, was the maker of this clock, which, in the opinion of Froissart, was the most curious existing, whether in Christendom or in the heathen lands, and hence selected by the duke as his trophy. The bells are struck by two hammer-men (the ancestors of our defunct black men at St. Dunstan's, as well as of those whom we still find at Venice), and who are called *Jacquemars* by the badaud of Dijon—a corruption of their maker's name.

“Amongst other churches, and fragments of churches, *St. Michael* deserves attention. It is a splendid example of the style which in France is now called ‘*La Renaissance*,’ less Gothic than the schools at Oxford, and less Italian than the Castle of Heidelberg. The portal is composed of three circular arches, with a very fine frieze above. The ornaments of this front are generally Italian or Roman in their details, yet so put together that the whole becomes a perfect Gothic cathedral.”—*F. P.*

There are a great many desecrated churches here, degraded into stables, coach-houses, warehouses, &c., though in tolerable repair, and worthy the attention of the architect; such are

St. Jean, remarkable for the span of its roof; St. Etienne, a covered market; St. Philibert, cavalry stables.

“The ancient *Palace* of the dukes of Burgundy, which, after the union of the Duchy to the crown of France, became the *Palais des Etats*, has been so completely modernised in its principal front, that the great interest possessed by the building would hardly be anticipated. But the front is merely a mask, and within, as well in the quadrangles as in other aspects, it retains very many of the features which distinguished it when it was the residence of the premier dukes of Christendom. This was the rank possessed by these powerful sovereigns, who, as such, ranked immediately after royalty.

“The style prevailing in this and the other buildings of the 15th century in Dijon, and which may be properly called the Burgundian style, has many of the features which we afterwards find in our Tudor architecture, and the aspect of the building softens down from the castle to the palace or mansion; not that strength was neglected, the ducal palace being surmounted by a large and very massy tower, and all the lower stories of the building being vaulted, but still the castellated character is no longer retained. The building is now used for public offices. A portion of it is employed as a

“*Museum*, and the ancient halls and chambers have been very judiciously chosen as the place of deposit for the very rich and important monuments of the middle ages which are there preserved. Most of the articles have *certificates of origin*; and they form a collection second only to that which existed in the now dispersed museum ‘*des Monumens Français*’ in the Petits Augustins. They are extremely valuable as illustrations of the progress of the arts in what was one of the most opulent and civilised portions of the European commonwealth. The following articles may be particularly noticed.



The crozier of St. Robert, the first abbot of the Cistercian order (ob. 1098). The wooden eup of St. Bernard, undoubted relic of this truly great and pious man, whose memory cannot be, however, relieved from the atrocities occasioned by the Crusades. The ornaments were probably added after his canonization. Toilet furniture of the Duchesses of Burgundy; caskets and boxes of ivory, beautifully carved. A purse supposed to have belonged to Isabella of Portugal, third wife of Philip the Good, of leather richly embroidered, and apparently of oriental workmanship. The chief ornaments of the collection are the magnificent *Tombs* of Philippe le Hardi, the founder of the second race of the Dukes of Burgundy (1342—1404), and of Jean-sans-peur, his son and successor (1371—1419). These tombs, the sculptures on which are perhaps the finest specimens existing of mediæval art on this side of the Alps, have suffered strange vicissitudes. Both were erected in the Chartreuse of Dijon, founded and endowed by Philip, and selected by him. Upon the suppression of the Chartreuse, they were removed to St. Benigne, where they rested but a short time, as in 1793 the Council of the Commune decreed their destruction. The bases remained at St. Benigne, but the figures were dispersed: some were placed in the Museum, others in private cabinets, and some abandoned in a lumber-room. In 1818 the department determined upon their restoration. This labour, though very costly, was comparatively easy, for the agents who executed the orders at the Revolution evidently contemplated the possibility of a restoration of the monuments, because, although pulled to pieces, these pieces were as little defaced as possible. The statues and architectural ornaments were disjoined, but not broken or mutilated. After the labours of nine years, we see them in a state very little different from the original splendour. The tomb of Philippe le

*France.*

Hardi represents him in a recumbent posture, in his full ducal robes. He is crowned with the ducal coronet (and it may be remarked that this ornament is a plain eirele without flowers), and his hand grasps the ducal sceptre. Two angels are placed below the head of the figure, holding the helmet, which has for its crest the fleur-de-lys of France. By the side is a space for the statue of his consort, but it never was filled. The sides of the tomb are ornamented with singular beauty. Instead of niches or panels filled with statues in basso-relievo, the dado is here surrounded by a miniature cloister, worked most delicately and elaborately in the finest alabaster. The little pillars, which stand quite free, sustain canopies and finials of the richest pattern, and in each division are the statues of one or two friars. All are represented as mourners, but with the most skilful variety of feeling: one, in all the anguish of grief; a second, equally afflicted, but tranquilly resigned; a third, stupified with sorrow; all as true as if you had the convent before you. The draperies are admirable; and whether we consider the goodness of the drawing or the skill of the execution, we must confess that it would be hardly possible to rival the skill of Claus Sluter, the Dutchman, for he was the artist, at the present day.

“The tomb of *Jean-sans-peur* matches entirely with that of his father both in material and in design. His ducal robe is *semé* with the device which he adopted, the *rabot*, or carpenter’s plane, assumed by him in opposition to the ragged staff of his political adversary, the Duke of Orleans. By his side is his consort, Margaret of Bavaria. Her robe is white, *semé* with the well-known little flower which bears her name. The coronets of both these personages are, like those of Philippe le Hardi, circles of gold richly studded with gems, but destitute of crosses and flowers. In general design, the miniature cloister,

which surrounds the base of the tomb, resembles that of its prototype, but the canopies and pinnacles and finials are even more delicate and elaborate. The mourners within are the exact fellows of the other company, and are executed with equal taste and skill, and the groups are equally true to nature. One monk is telling his brother the sad news of the Duke's death. Another, with his cowl drawn down, and his hands clasped, evidently displays, though his face be concealed, the deepest sorrow. The satisfaction at seeing these truly exquisite specimens of ancient art will be enhanced by the remembrance of those at Bruges, equally splendid in their kind. If the traveller has visited those, containing the remains of the sovereigns in whose persons the line of Philippe le Hardi became extinct, he will have seen the dynasty beginning and closing with the tomb.

"Jean-sans-peur was slain on the bridge of Montereau, 10th September, 1419, in the presence of the Dauphin, afterwards Charles VII. (R. 106.) The first blow came from an unknown hand, but he was struck down by the battle-axe of Tanneguy du Chastel. When Francis I. visited the Chartreuse the bodies were shown to him; and, pointing to the gash in the skull, he said, 'Through that the English entered France.'

"The chimney-piece of the Great Hall is said to have been built in 1504, after a fire which destroyed the roof in 1502; but it was probably only restored. It is perhaps 30 ft. in height by 20 in breadth, and it is a most magnificent specimen of Gothic art. The general outline resembles that of some of our English pedimented tombs, but the ornaments are on the boldest scale, and in the richest style. Here is preserved a model of the beautiful Sainte Chapelle, the chief Gothic ornament of Dijon: desecrated at the Revolution; pulled down and sold, 1807.

"The *paintings* in the Museum are

numerous, but much of the usual kind found in provincial collections: some of the portraits are interesting, especially those of the Duchess of Burgundy. A head of John the Baptist on a Charger is attributed to A. Dürer.

"The cabinet of M. Baudot still contains some very curious articles, though he has, with much spirit, placed several which he had in the Museum. The most curious are, the *marotte*, or bauble, of *La Mère Sotte*, under whose auspices whilome existed one of the farcical festivities of the middle ages. It is of carved wood, and represents La Mère at the top, with a bottle and a drinking glass in her hand, and groups of little fools creeping up, about and around her. Here are tablets covered with wax, according to the ancient Roman custom, upon which Philippe le Hardi noted his expenses: the book (if it can be so called) upon which the Dukes of Burgundy took their inauguration oath: it is composed of leaves of wood, upon which are painted the symbols of the Evangelists, and the first verse of the Gospel according to St. John in four languages—Hebrew, Greek, Latin, and French."—F. P.

Some curious relics of domestic architecture and early art are to be met with in the town; the *wells*, for instance, especially the *Puits de Moïse*, executed by Claus Slater (the sculptor of the ducal monuments), situated in the old Chartreuse, lately rebuilt as an Hospital for the Insane. It consists of figures of Moses, David, Jeremiah, Zachariah, Daniel, and Isaiah, hexagonally placed under rich canopies, and upon elaborate pedestals. The figures are admirable in expression. In a street near St. Michael's is a very elegant stone seat or sofa. "In a house entered through a shop, not far from Notre Dame, is a Gothic staircase, on the top of which stands the figure of a man with a basket on his shoulder, whence spring, in the form of a plant or tree, the vaulting ribs of the roof; these are



foliated in a very bold manner. The whole is of good execution, though evidently late in the style.

"The artist may pass several days here pleasantly as well as profitably, as it is a clean, cheerful, and handsome town, and the park or pleasure grounds will always form a delightful walk." —*Petit.*

The *Public Walks* are, indeed, a leading feature in Dijon, surrounding the walls as with a belt of foliage, and there is perhaps no other provincial town in France so well provided. They run partly in the form of *Boulevards* outside of and parallel to the old ramparts, which themselves form elevated terraces. The *Parc*, about a mile out of the town, reached by the Cours du Parc, was laid out by Le Nôtre for the Princes de Condé, its owners, who gave free admission to the public.

Dijon has the renown of being the native place of Bossuet, the divine, born in the house No. 12, Place St. Jean;—of Crebillon; of Guyton Morveau the chemist, and of the Duc de Bassano. St. Bernard was born in the village *Fontaines*, about a mile beyond the wall, and his father's castle is still in existence beside the curious church.

The *trade* in the *wines of Burgundy* is concentrated at Dijon; the district which produces the most celebrated wines lies to the S. of the town, and is traversed by the road to Châlons-sur-Saône, passing Clos de Vougeot, Nuits, and Beaune. (R. 152.)

*Conveyances.*—*Mallepostes* to Paris, to Besançon, to Bâle, and to Strasbourg, daily.

*Diligences* to Paris, morning and evening, by Tonnerre (R. 145); and by Troyes (R. 144); and to Châlons and Lyons (starting in the evening you reach Châlons in time for the steamer next morning); to Nancy and Strasbourg; to Dôle and Geneva; to Besançon.

*Railroad* to Châlons-sur-Saône in progress.

## ROUTE 145.

### PARIS TO DIJON BY SENS AND TONNERRE..

303 kilom. = 188 Eng. m.

*Diligences* daily.

The road is the same as R. 106 as far as

110 Sens (see R. 106), where our road turns E.

11 Theil.

18 Arces.

16 St. Florentin. A pretty town at the junction of the Armanche and Armançon. Its *Church*, founded 1376, is said to possess fine painted glass, and a curious double staircase. The walk of the Prieuré commands a view. About 16 m. S. of St. Florentin lies the *Abbey of Pontigny*, remarkable as having been the residence of many English prelates, and the retreat of Thomas-à-Becket during his exile, 1164-66. While here he carried the practice of the austerities of the Cistercian order to the very extreme, and while in prayer before one of the altars of the church had a divine vision, accompanied by the words, "Thomas, Thomas, my church shall be glorified by thy blood:" such, at least, is the Romish legend. The Abbey was devastated by the Huguenots, who unroofed and burnt the church and Abbey, and broke open the tombs, 1567; and the destruction of the conventual buildings and confiscation of the revenues were effected at the Revolution. The *Church*, however, still remains, and, though dilapidated, is a grand edifice, in a severe style of early Gothic, erected 1150. It is 351 ft. long and 68 ft. high, and is lighted by narrow lancet windows. Behind the high altar is the Shrine of the English Saint Edmund, Archbishop of Canterbury, an ark or chest of wood, carved and gilt, with a top in the form of a roof, and statues of saints around it, supported by 4 stone statues of angels as large as life.

Attached to the S. transept is a chapel, now in ruins, dedicated to St.

Thomas the Martyr, who was driven from Pontigny by the threat of Henry II. to banish the Cistercians from England, if they sheltered him in France. It retains some traces of frescoes, executed 1520. Among the English refugees who found shelter here was Stephen Langton, archbishop of Canterbury, when banished from England by King John, together with his suffragans. The church of Pontigny is about to be repaired by the Government.

The high road from St. Florentin follows the valley of the Armançon, and the line of the Canal de Bourgogne upwards, through

13 Flogny, where is a wire bridge, to

15 Tonnerre.—(*Imm*: Poste.) This is an old and dull town, of 4,247 inhab., on a steep slope, on the summit of which stands the *Ch. of St. Pierre*, commanding a fine view of the town from its rocky platform, and containing the interesting monument, in marble, of Marguerite de Bourgogne, Queen of Sicily, who founded the noble *Hospital* in this town, endowing it with large revenues, which it still enjoys. Her effigy, finely sculptured in the costume of the time, reclines upon the tomb. Here is also buried, under an imposing monument, Michel le Tellier, Marquis de Louvois, Minister of War to Louis XIV. It is the work of Girardon. *St. Pierre* and *Nôtre Dame* possess some architectural interest as Gothic churches.

The gnomon traced on the walls of the hospital, in 1786, is interesting as a scientific memorial.

About 6 m. E. of Tonnerre is *Tanlay*, one of the finest châteaux in Burgundy, and tolerably well kept up by its owner. It is a good specimen of the style of the Renaissance, the oldest part having been begun, 1559, by Coligny d'Andelot, brother of the Admiral Coligny, the leader of the Protestants, and the chief victim of

the St. Bartholomew's night. A chamber in the *Tour de la Ligue* is pointed out as the place where he and the other leaders of the party, the Prince de Condé, &c., were in the habit of meeting; and it is still covered with faded frescoes, representing, under the disguise of the gods of Olympus, the leading characters of the time; Catherine de Medicis as Juno (but with a double face?), and her son, Charles IX., as Pluto; Condé as Mars. The larger and more splendid portion of the château, including numerous additions to the original plan, was built between 1643 and 1648 by Particelli d'Emery, Surintendant de Finance under Mazarin, from designs of Le Muet, except the Petit Château at the entrance of the great building, which is a beautiful specimen of the Renaissance of the 16th centy. At the extremity of the grand *Canal*, flanked by avenues, beneath which Coligny and Condé may have walked, is the Château d'Eau, from which artificial streams burst forth.

The first stage on the road to Dijon is

18 Ancy le Franc.

The *Château* was begun in 1555, from designs, it is said, of Primaticcio, and decorated with frescoes still existing. In 1688 it became the property and residence of Louvois, minister of the Grand Monarque, who owned besides the Comté of Tonnerre, and other vast neighbouring possessions brought to him by his wife, Anne de Souvré, the richest heiress in France. The Marquis de Louvois established iron forges here. The château is well kept up, and surrounded by park and woods.

16 Aisy-sur-Armançon. Soon after quitting this place, you enter the department of the Côte d'Or, so famous for its vineyards.

11 Montbard. *Imm*: Point du Jour. This unimportant and dirty town was the residence of the naturalist Buffon, who was born 1707, and lived in the *Château*, which still



exists. The *gardens* attached to it are arranged in terraces along the slope of the hill, and decorated with orange trees. In an isolated antique tower, rising in a corner of them, now going to decay, and stripped of its furniture, Buffon formed his study, and composed most of his works. Nothing but bare walls now remains. The gardens, now open to the public, were laid waste and destroyed by the Revolutionists, but one relic of their ancient condition was preserved in a small pillar of marble raised by the son of Buffon in front of the lofty tower which contained his father's study, and bearing this inscription,

"Excelsæ turris humilis columna,  
Parenti suo filius Buffon, 1785."

"The *Château*, now occupied by the widow of Buffon's son, who was one of the first victims of the guillotine at the Revolution, contains portraits of Buffon and his assistant Daubenton. Two of the rooms are lined with coloured prints from the Natural History of its great owner. *His tomb*, in the parish church, was destroyed at the Revolution, the lead of his coffin melted, and his bones scattered."—*Costello*.

*Fontenay* is a sequestered abbey, a few miles from Montbard, whose founder was one Evrard, bishop of Norwich. It was devoted to monks of the Cistercian order. Its ruined buildings are now converted into a paper manufactory, belonging to the highly respectable family of Montgolfier. The chapter-house and cloisters are still fine specimens of Gothic architecture. The church, converted into every-day purposes, is less striking; but it contains several mutilated ecclesiastical monuments.

From Montbard there are 2 roads.  
*Route A.*—

A very hilly stage leads to

17 Semur, on the Armançon, here a small stream running in a deep ravine, overhung by picturesque crags, crossed by a high bold bridge. Above it rise the towers of the Donjon.

Over an elevated and undulating plain of arable land, crossing the Canal de Bourgogne, the road reaches  
23 Vitteaux.

Ascend a steep valley.

15 La Chaleur.

At the head of the valley, on the high ridge forming the watershed, is perched the town of Lombernion.

12 Pont de Pany. Hereabouts the road approaches the Canal de B. It descends the valley of the Ouche, hemmed in by bold hills, alternately craggy and wooded. On issuing from the hills, you find yourself on the outskirts of

DIJON. (Rte. 144.)

*Route B.*—by

22 Villeneuve-les-Convers.

14 Chanceaux.

Here our road falls into R. 144.

39 DIJON (p. 528).

## ROUTE 148.

### DIJON TO GENEVA BY DÔLE.

195 kilom.=120 Eng. m.

Diligences: 2 or 3 daily.

The journey may be divided into 2 days' posting: 1st day to Champagnole, 8 or 9 hours; 2nd day, Geneva, 10 hours.

For some distance along the road there is little worth description or notice; the country fertile, but flat and monotonous. As you advance, the distant blue outline of the Jura mountains is discovered on the horizon.

17 Genlis must not be confounded with the place of the same name in Picardy, whence Madame de Genlis derived her title.

A causeway  $1\frac{1}{2}$  m. long, pierced with 23 arches, to allow the escape of the water of the Saône during inundations, leads into

14 Auxonne (*Inn*: Grand Cerf), a second-class fortress of minor importance, owing to its distance from the frontier, in the rear of Besançon. It stands on the l. bank of the Saône,

here crossed by a bridge. The fortifications were planned by Vauban. It was taken by the Austrians 1815. The population 5,150.

From the heights above Dôle the snowy mass of the Mont Blanc, more than 100 m. distant as the crow flies, is apparent in clear weather.

16 Dôle (*Inns*: H. de France;—Ville de Lyon;—H. de Paris; said to be good) is a town of 10,137 inhab., in the Dépt. of the Jura, seated on the Doubs. It belonged for a long time to Spain, having been the capital of Franche-Comté, which was not united to France until the reign of Louis XIV. The Emperor Charles V. fortified it; but the works were destroyed by Louis.

The *Parish Church* is Gothic, and the *Tour de Vergy*, which now serves as a prison, is one of the few ancient edifices.

The *Canal* which joins the Rhine to the Rhône passes near the town.

[The road to Besançon turns off here, passing through

14 Orchamps.

13 St. Wit.

18 Besançon. (R. 159.)]

18 Mont-sous-Vaudrey, a town of 1000 inhab.

A road branches off here to Lausanne, by Salins and Pontarlier. (R. 150.)

19 Poligny (*Inn*: H. de Genève) is a town of 6,492 inhab., situated at the extremity of the plain, at the foot of the Jura, the first ascent of which commences on quitting Poligny. The road was made by Napoleon, and commands from the summits, after an hour's march, a good view into the valley called Culée de Vaux, and over the plains of Franche-Comté and Burgundy, as far as the Côte d'Or.

12 Montrond.

The Mont Blanc appears over the top of a saddle-backed hill.

10 Champagnole. (*Poste*; a very fair inn.) A town of 3,150 inhab., on the Ain, here crossed by a high bridge

A picturesque road, passing Billaude on the first platform or step of the Jura at the base of the second, to 12 Maisonneuve.

10 St. Laurent. (*Inn*: *Poste*.) French custom-house on entering France. The staple productions of the Jura are cheese (resembling Gruyère) and timber; saw-mills stud all the streams.

In this stage we reach the culminating point in the ascent of the Jura, and soon after begin to descend by a fine road, recently completed, to Morbier, and

12 Morez (*Inn*: *Poste*; comfortable), an industrious and rapidly increasing bourg of 2,508 inhab., seated at the bottom of a defile, on the Bienne, which turns the machinery of numerous mills and works, where clockwork, jacks, nails, &c. are made.

8 Les Rousses (*Inns*: not good; *Poste* best), a hideous village on the Swiss frontier, in a cold, arid, upland country. It is proposed to convert Les Rousses into a fortress for the defence of the French frontier.

Here is the first French custom-house encountered by travellers coming from Switzerland. Geneva trinkets, boxes, &c. must be declared; watches are admitted on paying a duty of 5 fr. each.

Those who wish to ascend the *Dôle*, one of the highest summits of the Jura, on account of its surprising view, must turn out of the high road at Les Rousses, and proceed to St. Cergue (12 kilom.), whence the top may be attained in 3 hours. See SWISS HAND-BOOK.

The descent of the Jura to Gex is now made safe and easy by an excellent new road. About a mile beyond the douane you pass out of France, but re-enter it before

15 La Vattay.

A little beyond La Faucille, at the extremity of a narrow gorge, on a sudden turn in the road, opens out the celebrated and sublime view over the Lake of Geneva, the Mont Blanc,



and the range of the Alps; a view not to be forgotten in a lifetime.

15 Gex (*Inn*: La Poste), through Ferney Voltaire, to

17 GENEVA (described in SWISS HAND-BOOK).

### ROUTE 150.

#### DÔLE TO LAUSANNE BY PONTARLIER.

100 kilom. = 62 Eng. m. to Jougne, *i. e.* the French frontier.

A journey of 2 days, stopping the first night at Pontarlier, 8 hours; thence to Lausanne, 10 hours.

A very agreeable road, through a romantic and beautiful country, quitting that to Geneva by Morez at

18 Mont-sous-Vaudrey (p. 534).

16 Mouchard.

9 Salins (*Inns*: Poste; — Tête Noir; tolerable), a town of 9000 inhab., which had the misfortune to be almost entirely consumed by a fire, which lasted for 3 days, in 1825. It is romantically situated in a narrow rocky gorge, and owes its name to the salt-works, *Salines Royales*, a vast edifice, 918 ft. long, surrounded by walls, in the midst of the valley. The salt is obtained from brine-springs rising below vaults of ancient construction. The weaker springs are conducted in pipes to the forest of Chaux, 15 m. off, where, after being evaporated in "maisons de graduation," they are boiled.

The Church of *St. Anatole* is an interesting edifice, and contains some good woodwork in the stalls of the choir.

There are quarries of gypsum here.

The road ascends, on quitting Salins, through a country having much of the Swiss character, abounding in rocks and dark fir-woods.

21 Levier.

21 Pontarlier. *Inns*: Poste; very good;—Croix Blanche;—Lion d'Or. This is the frontier town of France, a place of considerable antiquity and interest, containing 4,890 inhab., seated at a height of 2,716 ft. above

the sea level, at the foot of the second ridge of the Jura, and at the débouché of the principal routes leading through that chain. It is the loftiest town in France.

The road hence first ascends by the side of the river Doubs, and through the pass of La Cluse, which may be called a mountain gateway between France and Switzerland, to St. Pierre de Joux. The defile is commanded by the *Château de Joux*, situated on the summit of a precipitous and nearly inaccessible rock, at the foot of which the roads from Pontarlier, Neufchâtel, and Lausanne unite. This frontier-fort was the prison of the unfortunate Toussaint L'Ouverture, when treacherously carried off from St. Domingo by command of Napoleon. He ended his days here, some say by violent means; but the sudden transition from the climate of the tropics to a dark dungeon, so dank and cold that the water drops from the roof in summer, and icicles congeal on the walls in winter, in the elevated region and biting atmosphere of the Jura, sufficiently explains the cause of his death, without the need of violence. His miserable cell still exists, and has been described by Miss Martineau. He was buried in the prison church, with nothing to mark the grave, but it was bricked over, and is included in the new wall of the church. Here also was confined previously, "dans ce nid de hibous, égayé par une compagnie d'invalides," as he termed it, another remarkable prisoner, *Mirabeau*. He was sent hither (1776) by virtue of a lettre de cachet obtained by his father, "L'Ami des Hommes," as he called himself, and the tyrant of his own family, as he proved himself. Mirabeau, having by his insinuating manners obtained leave from the governor to visit the town of Pontarlier on parole, made love to Sophie Monnier, the wife of a magistrate there, and eloped with her to Holland. She was the Sophie

to whom he addressed some of his obscene writings, the "Lettres datées du donjon de Vincennes."

A desolate country, chiefly of forest, inhabited by charcoal-burners, succeeds.

19 Jougne, in a narrow pass, between high mountains. Here is the French custom-house.

2½ Orbe.

1¾ Cossonay.

2 Lausanne.

} Distances in posts.

The routes from the Fort de Joux to Neufchâtel by Val Travers, and to Lausanne by Orbe, are described in the HAND-BOOK for SWITZERLAND.

### ROUTE 152.

DIJON TO CHÂLONS-SUR-SAÔNE BY BEAUNE, AND THE WINE DISTRICT OF THE CÔTE D'OR, CHAMBERTIN, CLOS-VOUGEOT, NUITS, ETC.

67 kilom. = 41½ Eng. m. A railway is begun, 45 m. in length: it will form part of the line from Paris to Lyons.

This road carries the traveller along the skirts of the vineyards, producing the finest *Burgundy wines*, which rank amongst the best and most famous in France. The country, wherever it presents an advantageous slope, is entirely laid out in vines, and what it loses in picturesqueness it gains in richness. It is besides very populous; there are said to be 40 or 50 villages between Dijon and Beaune, a distance of 26 m.

"About a mile to the S.W. of Dijon begin those hills which form the celebrated *Côte d'Or*, which, judging by the eye, average from about 800 to 1000 ft. in height, continuing to range at the distance of about a mile from the carriage-road. It is a wall of hills, covered with vineyards, which ascend in terraces their sunny sides, and then spread along the table-land on the summit. The colour of the soil, as seen through the well-trimmed tufty vines, is of yellowish red; and it may be asked whether the name of the range arises

from this prevailing colour of the ground, or from the richness of the product. The tract from the road nearly to the summit of the hills is covered with vineyards. Here the best Burgundy is grown, and here, as in almost all other vine countries, we find the singular and perplexing phenomenon (but perhaps nowhere so forcibly apparent as here), that whilst one tract of small extent produces the finest and "most particular" quality, another hard by, enjoying the same aspect, and, as far as we can judge, either by our unaided senses or by chemical tests, the same soil, can never be made to bring forth a wine of equal flavour. In richness of flavour, and in perfume, and all the more delicate qualities of the juice of the grape, they unquestionably rank as the finest in the world; and it was not without reason that the Dukes of Burgundy were designated as the "princes des bons vins." The soils on which these valuable wines are grown consist, in general, of a light black or red loam, mixed with the *débris* of the calcareous rocks upon which they repose. The principal vineyards of the *Côte d'Or* are all situated between Dijon and Chagny, and describe an *arc* of a large circle exposed to the S.E. and protected from the N.W. by the range of hills that stretches behind them. The vines are planted in trenches, at the distance of about 2 ft. apart, and are trained on poles to the height of 30 to 40 inches. In the best vineyards they are extremely old, and when old vines are replaced by others, a larger crop, but of an inferior quality, is obtained. The choice red growths of the *Côte d'Or* are the Clos-Vougeot, Nuits, Beaune, Volnay, Pomard, Chambertin, Richebourg, Romanée, and St. George. They are all distinguished by their beautiful colour and exquisite flavour and aroma, combining, in a greater degree than any other wines, the qualities of lightness and delicacy with richness and fulness of body. Many other



crops are intermixed with the vineyards, — potatoes, clover, and maize, — whilst cherry, almond, and walnut trees are dotted over the fields. One need not wonder that the Kings of France should have coveted this rich Burgundian territory. This is about the highest latitude N. where maize can be grown to any advantage.”—*F. P.*

12 La Baraque. At Givray, a little to the rt. of the road after quitting this relay, lies the vineyard of *Chambertin*, about 7 m. from Dijon. It is about 15 or 20 acres in extent, but divided among numerous proprietors.

Farther on, the road passes under the wall of the enclosure (*Clos*) de *Vougeot*, the prince of Burgundy wines. It originally belonged to the monks of the neighbouring Abbey of Citeaux, who carried its culture to the highest perfection, never selling it, but making presents of what they did not consume themselves. At the Revolution it was bought by MM. Tournalon et Revol, and still later was resold to M. Ouvrard(?) and Aguado, the loan contractor. Its recent proprietors have enlarged it by taking in some of the neighbouring land; but the present extent of the vineyard is only 112½ English acres (48 hectares): the average annual produce is about 200 hogsheads. The soil near the top of the hill consists of small fragments of whitish limestone, mixed with shells, of which the hill is composed: in the lowest part of the vineyard it merges into a nearly pure clay. The vines nearest the top, in the dry soil, produce the best wine; on reaching the clay it falls off, and becomes the mere vin du pays.

“The vintage is in general soon over, the proprietor employing often from 400 to 450 vintagers at the same time. For the red wine, the grapes as they are brought in are thrown into large cases or troughs, and there trodden by a number of men, with large wooden shoes, till the grapes are nearly all broken. They are then taken up in baskets, with interstices

wide enough to allow the grapes to pass through, when a portion of the stalks, generally about two-thirds, are taken out. If the whole of the stalks were taken out, the quality of the wine, as has been repeatedly proved, would be inferior. The whole is then put into the vat into which the *must*, as it ran from the treading, had been previously carried. With the number of people employed, it requires a very short period to fill a vat. A space of about 12 inches is left unfilled at the top, and a sliding lid is then put over, which floats upon the surface. As soon as the fermentation becomes violent, the swelling of the mass lifts the lid to the height of six inches above the mouth of the vat. As, however, the skins and the stalks had previously risen to the surface, none of the liquor escapes. A very small space, formed by the looseness of the lid, is considered sufficient to allow the gas to escape, until the rising of the lid allows a greater space; and it is perhaps owing to the confinement of the gas that the lid is raised to such a height. If the weather had been very warm when the grapes were gathered, and still continues warm while the fermentation is going forward, the wine is soon made. The fermentation is sometimes over in 30 hours, at other times it continues 10, 12, and even 15 days. The best wine is always produced from the most rapid fermentation. When the fermentation slackens, the liquor begins to subside, and when it is entirely over, sinks within the top of the vat, but not so low as when the vat was first filled, for the *marc*, or in other words, the stalks and skins, are completely separated from the liquor, and float upon the top.

“As soon as it is known by the subsiding of the head, and by the taste and examination of the wine, that the fermentation has ceased, the wine is drawn off into large vats, which contain about 700 gallons each. Every 3 or 4 months it is pumped by

means of the syphon and bellows into another vat of the same dimensions, when a man enters by the small opening left in the end of the vats, and washes out, with a brush and cold water, any lees which may have been deposited. The Burgundy of the Clos-Vougeot receives no other preparation, and it is treated in this manner as often as may be judged requisite, till it is disposed of. They commence selling it when 3 and 4 years old, but the wine of very favourable seasons is retained by the proprietor till it is 10 or 12 years old, when it is bottled, and sold at the rate of 6 frs. a bottle. The price of the wine of ordinary vintages, from 3 to 4 years old, is from 500 to 600 frs. the hogshead, but seasons occasionally occur when the wine is not better than the *Vin Ordinaire* of the country. The wine of 1824 was given to the labourers as their ordinary drink; that of 1825, after ripening in the large vats 3 or 4 years, will be worth 6 fr. a bottle.”—*Busby*.

11 *Nuits*, a town of 2700 inhab., in the midst of the celebrated vineyards Romanée, Richebourg, La Tache, &c.

The *vins de Nuits* were brought into fashion, 1680, by Louis XIV., for whom they were exclusively prescribed by the chief physician Fagon, as a means of restoring his strength.

6 or 7 m. E. of *Nuits* is the celebrated *Abbey of Cîteaux*, founded 1090 by Robert de Molesme, in which St. Bernard assumed the cowl 1113, which sent forth to assume the keys of St. Peter no less than 4 popes, and which numbered 3,600 tributary convents of the Cistercian order, of which it was the head. Remains of the abbatial buildings still exist. [Information respecting their present condition is desired by the Editor.]

15 *Beaune* (*Inns*: Poste; — H. d'Angleterre) contains 10,000 inhab., and owes its prosperity to its being the chief seat of the *wine trade in Burgundy*, about 80 mercantile houses being engaged in it; the annual

exportation amounts to 30,000 or 40,000 butts.

The *Hospital*, founded by Nic. Rolin, chancellor of Philip, duke of Burgundy, 1443, presents in its court some good bits of Gothic, and there is a fine Gothic hall. There is a remarkable early painting, a Last Judgment, by *Albert van Ouwater*, in the Hôtel Dieu. The Bouzeoise, a limpid stream full of green weeds floating with its current, traverses the town.

Beaune is the birth-place of the senator Monge, the savant, and favourite of Napoleon.

At *Cussy la Colonne*, 12 m. S. W. of Beaune, is a Roman pillar or monument, bearing bas-reliefs; but it is accessible with difficulty by cross roads. At *Nolay*, near it, Carnot, the republican general and engineer, was born.

“The country immediately about Beaune has much amenity, and in its neighbourhood are produced the celebrated wines of Volnay and Pomard, the former being characterised by its light and grateful aroma and delicate tint, the latter having more body and colour: they are sometimes mixed with the red wines to give them fire. Savigny, Beaune, Meursault, and several other vineyards in the neighbourhood, all produce excellent wines, and, generally speaking, all the growths of that district are remarkable for the purity of their flavour.”

15 Chagny. “This town is full of interesting subjects for the sketch-book, particularly of domestic architecture; one house in the principal street, with a row of trefoil windows, is particularly striking. The tower of the *church* is also curious; it is a perfect specimen of the transition into the Pointed from the Norman style.

“From Chagny, the spot where the range of the Côte d'Or, properly so called, ceases, there is still a scattered line of lower hills, but the slopes are less rich and the plains less fertile.” — *F. P.*

16 *Châlons-sur-Saône*. (R. 106.)



## ROUTE 155.

DESCENT OF THE HAUT RHÔNE.—AIX  
IN SAVOY TO LYONS.

*N.B.* — A diligence runs several times a week from Geneva to Seyssel, to meet the steamer to Lyons.

The Upper Rhône is navigated, in summer, by a steamer, which performs the voyage, descending from Aix to Lyons, in 9 hours, but requires  $1\frac{1}{2}$  day, or 22 hours, for the ascent, which is somewhat tedious. A vexatious delay also of 2 or 3 hours takes place at the custom-houses of France and Savoy.

The voyage across the Lac de Bourget from Aix, passing the Abbey of Haute-Combe, at the foot of the Mont du Chat, is described in the SWISS HAND-BOOK, and is very delightful. The outlet from the lake is a narrow winding channel, called Canal de Savières, traversing the flat meadows in a serpentine course, which some have supposed artificial, but which has, probably, only been enlarged by art. By this issue the Lac de Bourget disgorges its waters into the Rhône, near the Savoyard village of Chana. The course of the Rhône hereabouts is nearly due N. and S., and parallel with the lake, from which it is separated by the mass of the *Mont du Chat*, whose ridges are called Dents, and over whose shoulder Hannibal is supposed to have led his army to the foot of the high Alps. On entering the Rhône we have this mountain on the l.

The Rhône has been navigated by steam above this, as high as Seyssel, a small town on both banks of the river, one part belonging to France, the other to Savoy.

Except at one or two points, the scenery of the Upper Rhône is not very remarkable. It runs through a series of basins, terminated at either end by gorges (*étranglemens*, i. e. throttlings, as the French expressively term them), caused by the ap-

proximation of the hills on either side. Below Seyssel

L. the Fièvre, a turbid river, which drains the Lake of Annecy, enters the Rhône.

L. At Yenne, opposite Belley, is a suspension bridge, traversed by the high road from Chambéry to Châlons. A monotonous sandy plain extends thence to Chana, across which the navigation is difficult, on account of sand-banks in its bed.

The Rhône, however, narrowed within a reduced channel, traverses a contracted defile, abreast of

Rt. Pierre Châtel, a fort of imposing appearance, belonging to France, built on the summit of a rock 400 or 500 ft. high. The river rushes through the gorge at its base with a furious speed; but the steamer, steered by a skilful pilot, passes safely over the rapids, which, at the point of greatest fury, are crossed by a wire suspension bridge.

The river below alters its course; turning to the N. W., and emerging upon an open country, it is intersected by numerous low islands, the resort of smugglers. Between St. Genis and (l.) St. Didier the river Guiers, which descends from the Grande Chartreuse (R. 131), joins the Rhône: it is the boundary of Savoy, separating it from the Dépt. de l'Isère; below this, therefore, both banks of the Rhône are French. Above the junction of the Guiers there is a suspension bridge, and a castle on the height near it.

Rt. the ruined *Castle of Groslée*.

L. Castle of Quinsonas.

To this succeeds the defile of St. Albin, where the channel is contracted to a width of 60 ft.; it is walled in by bare rocks, destitute of verdure.

The Rhône is traversed from side to side by a reef of rocks a little above the (rt.) village of Le Sault, so called from the leap, or *rapid*, formed by the river over them. They are smooth, and not very dangerous, but the steamer in ascending has diffi-

culty in stemming the torrent which sweeps over this inclined plane. Here the river is crossed by a handsome stone bridge, the central arch being 105 ft. span. On either side are extensive quarries of limestone, furnishing building materials for Lyons and other towns on the banks of the Rhône below.

Rt. St. Sorlin, with the remains of ancient fortifications.

L. Vertrieux, a modern château in the foreground, near the river; and behind it, on an isolated rock, its ancient castle rises in picturesque ruins.

Rt. at Lagnieux, where a suspension bridge of wire spans the Rhône, the hills subside into a monotonous plain, stretching away to Lyons.

L. The entry of the cave called Grotte de la Balme is about 10 minutes' walk from the river.

Rt. We pass the embouchure of the Ain, which gives its name to the Department extending along the rt. bank of the Rhône from Fort l'Ecluse nearly to Lyons. The Rhône below this assumes a very tortuous course between islands and sand-banks, unrelieved by objects of interest. Nothing announces the approach to a vast city, the borders of the river are so desolate and lonely. The steamer at length brings to, under the fortress-crowned heights of La Croix Rousse, at the quai in the Faubourg of Bresse, on the outskirts of

Rt. LYONS, described in R. 105.

#### ROUTE 156.

LYONS TO GENEVA, BY NANTUA AND BELLEGARDE.

151 kilom.—93½ Eng. m.

*Diligences* daily: a beautiful and interesting drive.

The road for some distance, after quitting Lyons, runs parallel with the Rhône, up its rt. bank. The river, left to its own wayward impulse, straggles onward, overspreading the plain with wrecks of sterile sand and

stones. The slope of La Pape, whence there is a good view of the river and the distant Alps of Dauphiné, is next ascended.

13 Miribel.

9 Montluel is a small town, of about 3,000 inhab., on the Seraine, which is crossed on quitting the place.

13 Meximieux. We reach the borders of the river Ain at Mollon.

11 Bublanne.

11 Pont d'Ain (*Inn*: H. Zacharie), a town of 1,266 inhab., on the rt. bank of the Ain, at the foot of a height crowned by a *castle*, built by the dukes of Savoy. Here the road to Bourg strikes off (R. 159).

The Ain is crossed by a stone bridge at Neuville, and its valley is quitted by the road at Poncin, remarkable for the ruins of a feudal castle, in order to reach

13 Cerdon.

From this the road ascends along the flank of a mountain, forming one side of a gorge, varied by the pretty fall of St. Marcellin, and by the ruined castles of Labatie and St. Julien.

The approach to Nantua, along the borders of its lake, is very pleasing, surrounded by mountains. It is about 1½ m. long.

19 Nantua (*Inns*: H. du Nord;—L'Ecu de France) is a town of 3,700 inhab., finely situated in the midst of the Jura mountains, at the extremity of its lake, hemmed in by bare precipices and dark woods. It possesses some considerable manufactures.

The *Parish Church*, originally attached to an abbey, is a "venerable and picturesque edifice, in the Romanesque style." The entrance, a round-headed arch, is surmounted by a circular window, and nearly all the rest of the building is early Pointed. The centre is surmounted by an octagonal lantern. Charles le Chauve, who died at Briord, 877, was buried here.

The lake produces capital trout and craw-fish.



The scenery of the Jura mountains, through which the road winds, continues very interesting for the rest of the way. A little beyond Neyrolles we attain the summit of the pass, and, descending, skirt the shore of the Lake Sylant, about 2 m. long.

13 St. Germain de Joux. *Inn:* H. de la Paix, clean and good.

At Châtillon de Michaille we cross the Valserine, and leave on the rt. the road leading to Seyssel (R. 155). We reach the valley of the Rhône at

12 *Bellegarde* (*Inn:* Poste), the frontier town of France, placed at the junction of the Valserine with the Rhône. Passports are here called for, and baggage examined likewise, on entering France. Ten minutes' walk from the inn is the *Perte du Rhône*, a contracted portion of the channel, encumbered with rocks, where the river plunges into the earth, and continues its subterranean course through caverns neither explored nor fathomed, which it has probably excavated by its own torrent in the limestone rocks, for about 120 yards. This phenomenon, however, is seen to perfection only when the river is low. At other times, when its volume exceeds that which the subterranean passage is able to contain, it flows along its upper bed, open to day, as well as below ground. At such times, says M. Simond, "*la Perte du Rhône est perdue pour les voyageurs.*" The vault of rock which covers the subterranean canal has of late been partly removed by blasting, to facilitate the flottage of timber in detached trunks down the Rhône at high water; this tends to diminish the wonder of the Perte.

The width of the Rhône, which, on quitting the Lake of Geneva, is about 115 ft., is contracted at the Pont de Grezin, in the neighbourhood of the Perte, to 15 or 16 ft.

"The bed of the Valserine is more picturesque and scarcely less curious than the Perte. It is worth while to descend from the garden of the inn

into the worn channel of this little river, which is almost dry in summer time, except when a rivulet of its water burrows into the clefts and fantastic bends of its calcareous rock."—*H. R.*

The wild and narrowly contracted gorge through which the Rhône forces its way between Bellegarde and Collonges, formed by the Mont Vouache on the side of Savoy, and the Mont Credo, the extremity of the Jura, on that of France, is thus described by Cæsar:—"Angustum et difficile inter Montem Juram, et flumen Rhodanum, quâ vix singuli currus ducerentur; mons autem altissimus impendebat, ut facile perpauci prohibere possent." Near the upper end of this defile, commanding the entrance into France, stands the very strong and picturesque fortress *Fort de l'Ecluse*, originally planned by Vauban, but ruined by the Austrians, and repaired since 1824 by the French government, who have used infinite labour and expense to strengthen this position. Additional batteries have been cut in the rock above the lower fortress, and these communicate with the barracks below by a broad staircase, 100 ft. high, hewn inside the solid mountain."—*H. R.* The high road is carried through the fortress. Permission to see it in detail may generally be obtained from the governor.

12 Collonges. Here the defile opens out. On quitting

16 St. Genix, you enter Switzerland.

12 GENEVA (2 postes royales extra charged) in *HAND-BOOK FOR SWITZERLAND.*

## ROUTE 159.

LYONS TO BESANÇON, BY BOURG AND LONS-LE-SAULNIER.

217 kilom. = 134½ Eng. m.

*A malleposte* daily in 18 hours.

*Diligences* daily.

The road from Lyons is the same as R. 156, as far as

58 Pont d'Ain.

20 *Bourg.*—*Inns*: H. de l'Europe (?);—du Nord (?). This place was capital of the ancient division of La Bresse, and is now chef-lieu of the Dépt. de l'Ain; its population is 8,996. It belonged to the Dukes of Savoy from the 11th to the 17th centy., and was not finally gained by the French until 1600. It has neither trade nor manufactures, and the only object of interest is the *Church of Notre Dame de Brou*, outside the walls, a very remarkable edifice in the latest style of Gothic, verging into the Renaissance, constructed between 1511 and 1536 by Margaret of Austria, who was created by her father, the Emperor Maximilian, and confirmed by her nephew, Charles V., governor of the Netherlands. Her motto, *fortune—infortune—fortune*, is repeated in various parts of the building. The architect was “Maistre Loys Van Boglem,” and the sculptor “Maistre Conrad.” The W. front is surmounted by 3 gables, that in the centre being the most lofty; under it is a *portal*, consisting of a flattened arch, highly enriched with carvings, arabesques, and other ornaments. The decorations of the interior are concentrated upon the *choir*: rich and varied marbles, and peculiarly fine painted windows, contribute to the splendour of the shrine, which contains the superb monuments of Margaret, the founder of the church, of her mother-in-law, Margaret de Bourbon (wife of Philip II. prince of Savoy), who made the vow, which her daughter accomplished, of building this church; and in the centre that of her husband, Philibert le Beau, which is the finest of all. The prince is represented above as dead, and below as dying. These tombs, all of white marble, are the work of an artist of Dijon named *Colomban*. The carving and decoration of the *rood screen*, the wood-work of the choir, and the altar-piece delicately sculptured out of alabaster, all deserve minute at-

tention. The sun-dial in front of the portal, originally made in the 16th century, was reconstructed by the celebrated astronomer *Joseph de Lalande*, who was born at Bourg, 1732.

The district of La Bresse is famed for its poultry, honey, &c.

11 St. Etienne du Bois.

Coligny, a little beyond this relay, is the cradle of the illustrious family which sent forth the leader of the Protestants, the Admiral Coligny. He was born at Châtillon-sur-Loing.

18 St. Amours.

18 Beaufort.

15 Lons-le-Saulnier (*Inn*: Chapeau Rouge) is situated in a basin nearly surrounded by the mountains of the Jura, whose lower slopes are covered with vines. It is chef-lieu of the Dépt. of the Jura, and a flourishing town of nearly 8000 inhab.

At one end of the town is the *brine spring*, or *well*, 60 ft. deep, supplying the salt-works, *Salines* (whence the town received its ancient name, *Ledo Salinarius*), situated about a mile from the town, including vast evaporating houses for sparing fuel, by strengthening the brine before it is boiled.

Above the salt well rise the ruins of the *Castle Montmorot*.

This is the birth-place of the revolutionary general Lecourbe.

14 Mauffans.

15 Poligny, on the high road from Dijon to Geneva, R. 148.

11 Arbois. A good sparkling wine is grown here. It is the native place of General Pichegru.

9 Mouchard.

17 Quingey, in the Dépt. of the Doubs.

12 Larnod.

10 *Besançon.* *Inns*: H. du Nord; H. de France.

This ancient and interesting city, and first-rate fortress, originally capital of Franche-Comté, and a free city of the empire, now chef-lieu of the Dépt. of the Doubs, is seated on



the Doubs, which divides it into 2 parts, and nearly surrounds the ville haute, the larger and older portion. Its population is not less than 30,000. It is defended by a *Citadel*, built by Vauban, on an inaccessible rock, occupying the isthmus of the peninsula on which the town stands, and by several detached forts. There is a fine view from the citadel.

Besançon was the ancient *Vesontio* mentioned by Cæsar, and his description of it is so exact that no other will better portray its position. He tells us that it was the largest town of the Sequani, and so strong by nature as to form an excellent basis for a campaign, because nearly surrounded by the river Dubis (Doubs), making a curve like a horse-shoe about it, except for the space of about 600 ft., occupied by an eminence washed by the river on either side. A wall which surrounds this height converts it into a citadel, and unites it with the town. "Oppidum maximum Sequanorum; naturâ loci sic muniebatur ut magnum ad ducendum bellum daret facultatem: propterea quod flumen Dubis ut circino circumductum, pene totum oppidum cingit: reliquum spatium quod non est amplius pedum DC quâ flumen intermittit; mons continet magnâ altitudine, ita ut radices montis ejus ex utrâque parte ripæ fluminis contingant."—L. i. It is interesting to find the classical description backed as it were by still existing remains of the Roman city, which are both numerous and curious, consisting, not only of inscriptions, mosaics, pillars, and other fragments, but of buildings, the chief and oldest of which is a *Triumphal Arch*, still tolerably perfect, ornamented with niches, statues, and reliefs, called *la Porte Noire*.

The old and narrow bridge over the Doubs is said also to rest on Roman foundations.

The *Porte Taillée* is an ancient gateway of solid masonry, built in a cleft of the rock, which was cut

through by the Romans to give passage to an *aqueduct*, constructed by them, to convey water to the city from the village Arcier, 7 m. distant, considerable fragments of which are still visible along the road leading to that village from the Porte Rivotte. Outside the walls are the remains of an *Amphitheatre*.

The extensive promenade of *Chamars*, traversed by two branches of the Doubs, is said to occupy the site, as well as retain in part the name, of the Roman "Campus Martius."

The *Cathedral* of *St. Jean* has a fine Gothic nave.

The other churches are comparatively modern. The *Palais de Justice* was built 1749 to receive the court of the parliament of the province, removed hither from Dôle by Louis XIV.

The Cardinal Granvelle, the able minister of the Emperor Charles V. and of Philip II., in the Low Countries, himself a native of Franche-Comté, born at Ornans, spent many years here, when disgraced through the intrigues of his enemies, occupying himself with literary pursuits. He contributed to the enlargement of the *College* founded by his father, and he built the *Palais Granvelle*, in the style of the Renaissance, uniting (like the schools at Oxford) the various orders of architecture, one above another. The library contains 60 folio vols. of his letters.

The Hôpital St. Jacques is an extensive edifice, containing 500 beds.

In the *Musée*, partly the bequest of a native named Paris, are assembled objects of art and antiquity of various degrees of interest.

*Watch-making*, introduced from Switzerland about 40 years ago, is the most important manufacture here, employing 2000 persons, who work at home for large houses.

Besançon stands on the important line of inland navigation formed to connect the Rhine with the Rhône, partly by making the Doubs navi-

gable: it was originally called *Canal du Monsieur*, now *Canal du Rhône au Rhin*.

*History.*—In the vicinity of this city Cæsar defeated Ariovistus. Besançon was taken by Louis XIV. in person 1660, and the possession of

it was confirmed to France at the peace of Nimeguen. It was fruitlessly besieged by the Allies in 1814.

*Conveyances.* *Malleposte* daily to Paris by Dôle and Dijon.

*Diligences* daily to Paris; to Strasbourg; to Lyons.

---



## SECTION IX.

## CHAMPAGNE.—LORRAINE.—ALSACE.—THE VOSGES MOUNTAINS.

ROUTE	PAGE	ROUTE	PAGE
162 Paris to Mühlhausen and Bâle, by Troyes, <i>Bar-sur-Aube</i> , <i>Chaumont</i> , <i>Langres</i> , and <i>Vesoul</i> , and the Baths of <i>Bourbonne-les-Bains</i> .	545	171 Strasburg to Besançon, by Colmar, <i>Thann</i> , <i>Belfort</i> , and <i>Montbelliard</i> . . . . .	564
164 Paris to Strasburg, by <i>Sézanne</i> , <i>Bar-le-Duc</i> , and <i>Nancy</i> or <i>Lunéville</i> . . . . .	548	175 Paris to <i>Metz</i> and <i>Forbach</i> , by <i>Meaux</i> , <i>Château Thierry</i> , <i>Epernay</i> , <i>Châlons-sur-Marne</i> , and <i>Verdun</i> .	565
166 Paris to the Baths of <i>Plombières</i> , by <i>Ligny</i> , <i>Domrémy</i> , and <i>Epinal</i> . . . . .	557	178 Paris to <i>Mezières</i> and <i>Sédan</i> , by <i>Soissons</i> and <i>Rheims</i> .	573
168 The <i>Vosges Mountains</i> .—Strasburg to <i>Epinal</i> , by <i>Mutzig</i> and <i>St. Diey</i> .—Excursion to the <i>Ban de la Roche</i> . . . . .	559	180 Rheims to Luxembourg, by <i>Stenay</i> and <i>Longwy</i> . . . . .	580
170 Strasburg to Bâle.—RAIL-ROAD by <i>Schlestadt</i> , <i>Colmar</i> , and <i>Mühlhausen</i> . . . . .	560	181 Nancy to <i>Trèves</i> , by <i>Metz</i> and <i>Thionville</i> .—Descent of the <i>Moselle</i> . . . . .	581
		182 Metz to Luxembourg, or <i>Arlon</i> , by <i>Longwy</i> . . . . .	582

## ROUTE 162.

PARIS TO MÜHLHAUSEN AND BÂLE, BY TROYES, BAR-SUR-AUBE, CHAUMONT, LANGRES, AND VESOUL, AND THE BATHS OF BOURBONNE-LES-BAINS.

'To Troyes, 160 kilom. = 99 Eng. m. *Malleposte*, 12 hours.

Troyes to Bâle, 329 kilom. = 204 Eng. m.

The road is the same as R. 144 as far as

158 *Troyes* (see p. 525).

A *malleposte* runs daily hence to Belfort and Mühlhausen, in 24 hours. *Diligences* daily.

The road ascends the valley of the Barse, traversing the theatre of the memorable campaign of 1814. The bridge of La Guilottière over the Barse was stormed and carried by the Bavarians, March 4, after a stout resistance from the French. Lusigny,

a little farther on, was the scene of a conference, followed by an armistice, Feb. 24.

19 Montiéramey.

13 Vendeuvre.

The Barse rises at the very foot of the old *castle*, built, it is supposed, in the 13th century.

A ridge of high land is now surmounted, and the road descends into the valley of the Aube, whence the Dépt. gets its name.

That river is crossed, and the road carried up its rt. bank as far as

21 Bar-sur-Aube.—*Inn*: La Poste.

Bar is a town of 4133 inhab., at the foot of Mont St. Germaine, on the rt. bank of the Aube, here crossed by a stone bridge, upon which a chapel was erected to mark the spot where Charles VII. caused the Bastard de Bourbon, who had revolted against him, to be broken on the wheel, and

his body, sewn up in a sack, to be cast into the river, 1440.

There are 2 churches here: *St. Pierre* is very ancient, and its pavement sunk considerably below the level of the ground; and *St. Maclou*, which has a curious altar-piece of wood, carved and gilt.

An important and hard-contested action was fought here, Feb. 27, 1814, when the Allies, under Schwartzberg, retreating before the French general Oudinot, turned round and made a stand, the result of which was that the French were obliged to retire across the river, having lost 3000 men, the Allies 2000. Schwartzberg and Wittgenstein were both wounded here. On the preceding 25th of February a conference of the ministers of the allied sovereigns was held here, in which the firmness of Lord Castlereagh in refusing the English subsidies to Bernadotte, who was hanging on the French frontier unwilling to take a part in the invasion of France, unless he detached 2 corps of his army in support of Blücher, contributed in no slight degree to decide the wavering policy of the Allies, and to bring the war to an end. These reinforcements, thus extorted from the Swedish army, enabled the Allies to fight the battle of Laon, and put a stop to Napoleon's successful efforts to arrest the march of the Allies on Paris.

At *Brienne le Château*, 19 m. lower down the Aube, Napoleon went to school—a poor friendless Corsican boy, not 10 years old, able to speak no language but Italian, 1779. The military college which he attended was suppressed, 1790, and the building sold and pulled down. At this spot, 25 years after, he attempted the masterly manœuvre of cutting the army of Silesia in two, by marching suddenly from Châlons and interposing his forces between Blücher and Schwartzberg, so as to prevent their junction.

The town is named after its handsome *Château*, built by Louis de

Lomenie, last Comte de Brienne, with the fortune obtained by his marriage with the daughter of a fermier général. It was the head-quarters of Blücher during the memorable engagement of Jan. 29, 1814, alluded to above. After resisting the assaults and bombardments of the French during the whole day, by which the town had been set on fire, and nearly destroyed, the Prussian commander was very nearly surprised and made prisoner by a party of French grenadiers, who burst into the town at night through the park. He escaped, it is said, by leading his horse down a stair. Almost at the same spot, and at the same time, the career of Buonaparte, who was advancing to enter the town, was nearly cut short by a Cossack, one of a band who had dashed unawares upon the Emperor's staff, and, singling him out from the rest, charged him with his lance in rest, and was only arrested by a bullet from the pistol of Gourgaud, which brought the daring lancer to the ground, when so near to the Emperor that he fell at his feet. Napoleon took up his head-quarters in the *Château*, which he promised to make an imperial residence or military school, to compensate to the inhabitants for the losses his cannon had caused them. But his promises were not destined to be fulfilled. However, he left by his will a million of francs to the town, where he received the first rudiments of his military education.

About 10 m. from Bar-sur-Aube, in an opposite direction, up the valley, is (or rather was) the *Abbey of Clairvaux*, founded 1114, in a savage glen, previously known as the *vallée d'Absinthe*, by St. Bernard, then only 24 years old. It is now converted into a very capacious prison, or *Maison Centrale de Détention*.

Its noble *church*, in which kings and princes were interred, not inferior to *Nôtre Dame* of Paris, no longer exists. After withstanding the storm of the Revolution, it was pulled down



in the first year of the Restoration, without leaving one stone upon another, not even St. Bernard's monument, in order to make room for a prison-yard!

We quit the valley of the Aube on leaving Bar, and soon after enter the Dépt. Haute Marne.

15 Colombey les Deux Eglises. About 15 m. to the N. is the *Château de Cirey*, where Voltaire passed 5 years of his life in a degrading retirement, in the company of the Marquise de Châtelet. He composed in this retreat, "Mahomet," "Merope," "L'Enfant Prodigue," and the "Discours Philosophique sur l'Homme."

8 Juzennecourt.

In the midst of a country destitute of picturesqueness, but abounding in iron furnaces, works, forges, &c., stands

17 Chaumont (*Inn*: Ecu de France?), chef-lieu of the Dépt. de la Haute Marne, a dull town of 6318 inhab., planted on a sort of elevated platform on the l. bank of the Marne, and retaining some fragments of old fortifications. A square tower alone remains of the *Castle of Haute Feuille*, which belonged to the Comtes de Champagne. Here is a sort of *Triumphal Arch*, begun by Napoleon, finished by Louis XVIII.

The *Treaty of Chaumont*, signed here by the ministers of the allied sovereigns, March 1st, 1814, stipulated that in case Napoleon should refuse to agree to the reduction of the territory of France to the limits existing previous to the Revolution, the four allied powers, Austria, Russia, Prussia, and England, should each maintain an army of 150,000 men in the field, and that Great Britain should contribute a subsidy of 5 millions a year towards their support; it also provided for the reorganization of the other states of Europe.

There are some manufactures in the town, and it has a large trade in the iron made in the neighbouring

iron-works: iron is the staple manufacture of the Dept. Charcoal is chiefly employed in smelting the ore. From Chaumont a road strikes off to Bourbonne-les-Bains.

The country from Chaumont to Langres is such as one would wish to pass in the dark, so few attractions has it for the eye. The road runs up the valley of the Marne.

17 Vesaignes.

A steep ascent leads into

18 Langres (*Inns*: H. de l'Europe, exceedingly good;—Poste?), situated on the slope of a hill skirted by the Marne, at a considerable elevation: 8303 inhab. It is of military importance, as commanding the passage from the basin of the Saône into that of the Seine, and the Government has consequently decided on making a fortress of it. It is mentioned by Cæsar as capital of the Lingones, and its antiquity is undoubted. The *Cathedral* (St. Mamée) is its finest edifice: it is built chiefly in the Romanesque style, with ornaments, such as rams' heads, borrowed apparently from classic architecture; some portion, however, is Gothic. The portal, a work of the last century, is quite inappropriate, and the choir-screen, resembling an arch of triumph, built 1555, is not much better. *St. Didier*, the oldest church, is degraded into a receptacle for fire-engines.

The only vestige of a Roman building is an *arch* built into the town wall, raised in honour of the 2 Gordians A.D. 240.

Diderot was born at Langres: he was the son of a cutler.

Langres is a sort of French Sheffield, and produces the best fine cutlery.

About 30 m. N. E. of Langres lies the watering-place *Bourbonne-les-Bains* (*Inns*: H. du Commerce;—Vosges;—Tête du Bœuf), resorted to on account of its saline hot springs, which have a temperature of 131° Fahr., and are efficacious in rheumatism, scrofula, and paralysis. The

bathing establishment contains about 50 baths, and there is accommodation for more than 1000 visitors. The number usually exceeds 800, exclusive of military, who are received in a Government hospital.

The situation is elevated, the climate rainy, and the resources are said to be few.

13 Griffonotes.

11 Fayl-Billot (*Inn*: Lion d'Or?), 2411 inhab.

From the heights surmounted by the road views are obtained of the Vosges mountains.

13 Cintrey (Dépt. Haute Saône).

12 Combeau Fontaine.

12 Port-sur-Saône, 2067 inhab., is situated on the Saône, here crossed by a bridge, over which our road is carried. The Romans called it Portus Abucinus. The Saône becomes navigable at Gray, 30 m. lower down; but a canal has been undertaken to extend the water-way up to this point. It is a hilly country.

13 Vesoul (*Inns*: Cigogne;—Madeleine). Although chef-lieu of the Dépt. Haute Saône, this is a dull but considerable town of 16,738 inhab., possessing absolutely no interest, but seated in a fertile country.

11 Calmoutier, a dirty village.

A tolerably level road through a country diversified with woodland of oak, birch, and hazels.

18 Lure (*Inn*: H. de France, clean), a town of 3058 inhab., in the midst of a marshy plain.

The road reaches the hills at

18 Champagne, near which there are coal-mines employing many hands.

The Dépt. of the Haut Rhin is entered at Essort, a little short of

14 Belfort, described in Route 171.

Here the road to Mühlhausen turns off on the l. (R. 171). The distance hence is 18 kilom. The road lies through a hilly country, passing the iron-mines of Perouse; and from the high hill, surmounted on quitting

15 Chavannes, commands a fine view of the Swiss mountains. Here

the Canal du Rhône au Rhin is crossed (see p. 543).

19 Altkirch is a manufacturing town of 3028 inhab., and a place of some antiquity. Its old *castle*, in ruins, was occupied by the archdukes of Austria when they visited Alsace. It is seated on the Ill.

15 Lochwürrh.

13 St. Louis, the last French town.

A little to the l. of the road lies *Huningen*, once an important fortress, built by Vauban for Louis XIV., 1681, close to the l. bank of the Rhine and to the Swiss frontier, but now a heap of ruins, having been captured by the Austrians in 1815, and blown up pursuant to treaty.

4 BÂLE, in the SWISS HAND-BOOK.

#### ROUTE 164.

PARIS TO STRASBURG, BY SÉZANNE, BAR-LE-DUC, AND NANCY, AND BY LUNÉVILLE.

455 kilom. = 282 Eng. m.

A *Railway* is in progress through Lagny, Meaux, Château Thierry, Epervay, Châlons-sur-Marne, Vitry-le-Français, Bar-le-Duc, Nancy, Sarrebourg, Saverne, to Strasburg.

*Malleposte* (3 places) daily in 33-35 hours.

*Diligences* daily in 43 hours.—*N.B.* That which goes by Metz is 10 hours longer on the road.

*For those who travel post* the journey may be divided into 3 days from Paris: thus—1st night, Vitry; 2nd, Lunéville; 3rd, Strasburg: and returning, 1st, Nancy; 2nd, Sézanne; 3rd, Paris. Or, more leisurely, starting from Strasburg,

1st day, Lunéville, 12 hours.

2nd day, Toul, 5 hours, exclusive of the time spent in seeing Nancy.

3rd, Vitry-le-Français, 10 hours.

4th, Coulommiers, 10 hours.

5th, Paris, 7 hours.

The inns on this road, generally speaking, are dirty and bad, except that at Nancy.

A new post-road has been opened



from Paris to Sézanne, which saves 8 kilomètres, by

14 Champigny.

13 Ozouer la Ferrière.

17 Fontenay.

16 Vauday.

17 Courtacon.

20 Retourneloup.

13 Sézanne.

The other road, followed by the mail, on quitting the fortifications of Paris, leaves on the rt. the Bois de Vincennes, described in Galignani's Paris Guide, and ascends the valley of the Marne by

15\* Neuilly-sur-Marne (Seine et Oise) to

14 Pomponne (Seine et Marne).

13 Couilly and Creci are almost one town, separated only by the river.

"The village La Chapelle has a beautiful old Church, and a ci-devant château."—*R. I.*

20 Coulommiers (*Inn*: L'Ours, tolerable) is an unimportant town of 3373 inhab., in the pretty valley of the Morin, which turns several mills.

18 La Ferté Gaucher, also on the Morin, studded with paper-mills, near this.

22 Retourneloup.

13 Sézanne (*Inn*: H. de France; very decent) (Dépt. de la Marne), a town of 4016 inhab. The church is curious; it is pewed and contains some painted glass. The Boulevards are good. Sézanne was taken and burnt by the Earl of Salisbury, 1423.

About 15 m. N. W. of this is *Montmirail*, the scene of one of the most decisive of Napoleon's victories during his so-called "expedition of the Marne," when his arms were 3 times successful in the course of 5 days (February 9—14, 1814), beating Blücher, and taking 7,000 Prussian prisoners, besides cannon and standards.

Montmirail was the birth-place of the Cardinal de Retz, 1614.

"The solitariness of the road from Sézanne to Vitry is most striking and

\* Adding 8 kilom. de faveur, charged 23 kilom.

unusual to one fresh from well-peopled England. It crosses a vast, upland, arable plain, whose entire population must exist in towns and villages widely separated from one another, since there are no hamlets or single cottages: the consequence of which must be a loss of time and labour to every cultivator, who must go 3 or 4 miles, or perhaps more, to and from his labour field every morning and evening."—*R. I.*

21 Fère Champenoise.

On the 24th of March, 1814, this town of 2049 inhab. witnessed the decisive defeat of the French, under Marmont and Mortier, by the allied army, vastly superior to them in numbers, but consisting of 20,000 cavalry and artillery alone. Nearly at the same time, and only a short distance off, another French corps, conveying guns and bread, was surrounded by Russian and Prussian cavalry, and having, in spite of the superiority of numbers opposed to them, bravely refused to yield, was cut to pieces. 3000 French fell here, many of them National Guards. By this victory Paris was laid open to the Allies; 7000 prisoners, 80 guns, 200 baggage waggons, fell into their hands. It is said not a musket was fired on their side, the day having been decided by charges, by the sabre, and by artillery.

16 Sommesous, a hamlet made apparently by the passage of the new road.

14 Coole. "A new hamlet, smaller than Sommesous. Between Coole and Vitry not one house occurs: it is one immense open plain, without a tree or a village in sight."—*R. I.*

15 Vitry-le-Français (*Inn*: La Cloche; landlady English) is a town of modern origin, on the Marne (Matrona), which is here navigable, built 1545 by Francis I., and fortified, to supply the place of Vitry-le-Brûlé, 2 m. off, which had been taken and destroyed by Charles V.: 6976 inhab. Here is a good Gothic church, of the age of Francis I.

## 16 Longchamp.

At the point where the Marne first becomes navigable stands

12 St. Dizier (*Inn*: Soleil; tolerable), a very long and very narrow town, with 6400 inhab., of a modern aspect, having been almost entirely burnt down 1775 through the carelessness of a baker. The *Church*, at the N. end, has a pretty and singular variety of Gothic windows. A portion remains of the old *Castle*, which must have witnessed the siege of the place, in 1544, by the Spanish army of Charles V., commanded by Ferdinand de Gonzaga, assisted by Maurice of Saxony, Albert of Brandenburg, and the Prince of Orange (killed at a spot marked by a cross), who served under him. The town, commanded by the Comte de Sancerre and the Seigneur de Lalande, resisted for a month; and, by thus delaying the march of the Spaniards on Paris, enabled Francis I. to collect his forces to oppose them. St. Dizier is now no longer a fortress. The produce of the forges and forests of the Dépt. of the Haute Marne, which is more abundantly supplied with wood and iron than almost any other in France, is embarked here on the river.

About 14 m. S. E. of St. Dizier is Joinville (*Inn*: Soleil d'Or), an interesting town, prettily situated on the Marne, surrounded by vineyards. The ancient and noble castle of the Prince de Joinville, the cradle of the Ducs de Guise, in which the famous "Ligue du Bien Public" was signed, 1585, was sold, in order to be pulled down, by Philippe Égalité, Duc d'Orléans, 1790, and no vestiges of it exist. The building called *Petit Château* was a country seat of the Duc de Guise, the owner of the town. The domain was created a principality by Henri II., in behalf of François, Duc de Guise, who was assassinated by Poltrot. The Sire de Joinville, the faithful servant and biographer of St. Louis, was born here. There are many iron-works on the borders of

the river, the supply of ore being very abundant.

12 Sandrupt (Dépt. de la Meuse).

12 Bar-le-Duc.—(*Inn*: Le Cygne). This town, the chef-lieu of the Dépt. of La Meuse, has 12,496 inhab., and stands on the Ornain. It was for several centuries the seat of the line of Dukes of Bar, whose castle is destroyed all but a small fragment.

In the *Church of St. Pierre*, in the upper town, is the monument of René de Châlons, Prince of Orange, who was killed before the walls of St. Dizier. It bears an emaciated effigy or skeleton of white marble on a black altar tomb.

There is some trade here in timber, iron, and vins de Bar, which resemble champagne. Marshal Oudinot and General Excelmans were born here.

*Diligences* to Châlons-sur-Marne, Verdun, and Metz.

16 Ligny (*Inn*: Sauvage?) is a town of 3012 inhab. It has pretty walks, formed in what was the park of the old château.

The road to the Baths of Plombières, by Domrémy, turns off here. (See R. 166.)

9 St. Aubin.

14 Void.—*Inn*: Aigle Noir; not recommended.

About 24 m. S. of Void, in the Dépt. des Vosges, is the village of Domrémy, the birth-place of Joan of Arc. (R. 166.)

About 16 m. N. of Void is St. Mihiel en Lorraine, where De Retz wrote his Memoirs.

In the stage beyond Void we cross the infant Meuse, and afterwards traverse the mountain ridge separating that river from the Moselle.

11 Lay St. Remy.

11 Toul (*Inn*: H. de l'Europe) is a fourth-rate fortress, irregularly bastioned, seated on the Moselle, and containing 7314 inhab. It was not definitively added to France until 1552, having previously maintained a sort of independence as a free city of the German empire, under the no-



minimal control of a long line of bishops.

The chief edifice is the *Gothic Cathedral*, a fine structure, founded in the 10th centy. Its portal and W. front were designed and raised by Jacquemin de Commercy (1447), and are much admired; the façade is 227 ft. high. The *Ch. of St. Genoul* is said also to deserve notice. The H. de Ville, a modern building, was originally the Bishop's palace.

Toul is the birth-place of Marshal Gouvion St. Cyr.

11 Velaine.

11 NANCY.—*Inn*: H. de France; very good; the best on the road.

Nancy, formerly capital of Lorraine, now chef-lieu of the Dépt. de la Meurthe, is a city of 35,900 inhab., seated on a fertile plain, not far from the Meurthe. It has been styled the prettiest town in France, and it has perhaps some claim to the epithet from the regularity and uniformity of its buildings and breadth of its streets. "Bordeaux is far more magnificent; Rouen and Nantes are more lively; but there is more equality in Nancy: it is almost all good, and the public buildings are numerous. The *Place Royale* is superb." It is surrounded by 6 or 7 fine public buildings, including the H. de Ville and theatre, and ornamented with a *statue of Stanislas Leszcynski*, ex-king of Poland, to whom Nancy is indebted for its modern aspect and architectural embellishments. After abdicating the throne of Poland (1735), he resided here many years as Duke of Lorraine and Bar until his death (1766), when these domains fell to the crown of France. The Place Royale communicates by a triumphal arch, also erected by Stanislas, with the Place Carrière, which is prolonged into the Cours d'Orléans, terminating in the gateway called *Porte Neuve*, erected 1785 to celebrate the birth of the Dauphin, the victories of France, and her alliance with the United States.

In the old town, a network of lanes, except the Cours d'Orléans and Place de Grève, stands a portion of the old *Palace* of the Dukes of Lorraine, now a barrack of gendarmerie. The portal also is admired.

The *Ch. of St. Epore*: from its tower the Burgundian officers of Charles the Bold, to the number of nearly 100, were hanged in revenge for the death of Suffron du Bachier, chamberlain of René II., Duke of Lorraine, whom Charles had seized and put to death while besieging Nancy (1477). Under the tower is a fine portal, and behind the altar a bas-relief of the Last Supper, by *Drouin*, a sculptor of Nancy. In the Chapel of the Conception are ancient frescoes, much injured by repainting. Here are tombs of the Cardl. de Vaudémont, consisting of a kneeling statue, by *Drouin*; of *Callot*, the artist and clever etcher, a native of Nancy; of Antoine de Vaudémont and his lady, 1447; of Philippa of Gueldres, much praised as a work of art, by the sculptor *Ligier-Richier*, and others. From the nave you enter the *Chapelle Ducale* or *Rotonde*, an octagonal structure, rich in marbles, prefaced by the arms of Lorraine and Austria, erected as a funeral chapel for the Dukes of Lorraine. The coffins were taken up at the Revolution, and thrown into a public cemetery; but in 1815 the Empr. of Austria, in company with Louis XVIII., having visited the chapel, then degraded and dilapidated, caused it to be restored, and the coffins to be replaced.

The *Cathedral* is a modern Italian edifice in the new town. The *H. de l'Université* contains the Public Library.

Nancy is well furnished with *Gates* of modern Italian architecture: that of St. Jean leads out of the town to the *Croix du Duc de Bourgogne*, raised to mark the spot where the lifeless body of Charles the Bold was discovered in a pond, near what was then the Marais de St. Jean, two days

after the battle of 1477, when the might of Burgundy was laid prostrate by hireling Swiss and German landsknechts engaged to support Duke René of Lorraine, whose domains Charles had unjustly invaded. He rushed on certain destruction with a dispirited army, inferior to that of his opponents, and betrayed by his Neapolitan favourite, Campo Basso.

At the extremity of the Faubourg St. Pierre stands the *Ch. of Bon Secours*, occupying the site of one raised by the Duc René to commemorate this victory. Having fallen to ruin, it was rebuilt 1738 by the ex-king of Poland, Stanislas, and contains the *Tombs*, in white marble, of himself and his queen. He was burned to death by his clothes accidentally catching fire as he sat at the fire-side. Here are or were preserved several standards taken from the Turks by various Princes of Lorraine in 1664, 1687, and 1716.

The *Cotton* manufacture is carried on to a considerable extent at Nancy, as well as that of Cloth; but *embroidery*, of the kind called “plumetis,” upon cambric, muslin, and jaconots, employs the greatest number of hands, amounting in and about the town to 20,000 or 25,000 persons, but only one-third of the number receive constant employment.

*Malleposte* to Paris and Strasburg daily.

*Diligences*, ditto; to Strasburg in 16½ hours; to Metz (36 m.) in 6 hours; to Lunéville and Lyons; to Langres, Besançon, Colmar; to Châlons-sur-Marne, &c.

*Steamers* down the Moselle to Trèves, starting from Nancy.

There are 2 roads from Nancy to Sarrebourg—a. by Lunéville, 72 kilom.; b. by Bourdonnay, 65 kilom. On quitting Nancy, the former road traverses the faubourg St. Pierre, passing the Church of Bon Secours, and crosses the Meurthe at St. Nicholas, where is a very fine Gothic Church, begun 1494 and finished 1544: the vault of its roof, more

than 100 ft. above the pavement, is supported on very slender piers.

15 Dombasle (Meurthe): here are remains of an old castle.

12 *Lunéville* (*Inn*: Sauvage; good), a town of 12,636 inhab., near the junction of the Vezouse with the Meurthe, consists chiefly of straight streets and regular buildings, but is scarcely otherwise remarkable than for the *Treaty of Peace* signed here 1801 between France and Austria, by which the frontier of the Rhine was conceded to France, as a consequence of the campaign of Marengo. The *Palace* built by Leopold, Duke of Lorraine, at the beginning of the last century, and sometime occupied by the ex-king of Poland, Stanislas, has long been turned into a Caserne de cavalerie. Its gardens are become a *public* walk. Here is a very large riding-school.

This is one of the chief stations for *cavalry* in France.

15 Bénaménil.

15 Blamont.

16 Heming, where we fall into the other road,

*Route b.*, by

14 Champenoux.

17 Moyenvic, a town of 1,295 inhab., which formerly possessed salt-works, abandoned 1831, since the discovery of a mine of rock-salt at Dieuze (3,892 inhab.), about 9 m. off, where the most extensive *salt-works* in France have been established, producing annually 145,000 quintals, supplied chiefly from very copious brine springs as well as rock salt, and employing 400 men. There is also a considerable manufacture of soda and other chemical products.

6 m. N. of Moyenvic is the town of Château Salins.

“From Moyenvic, or even farther W., the country traversed is a vast uninclosed arable plain, uninhabited, save in the towns or villages; scarcely one hamlet or farm-house, hardly a solitary cabaret at the road side.”  
—*R. I.*



14 Bourdonnay.

20 Heming.

8 Sarrebourg (*Inns*: Le Sauvage; —Grand Hôtel), a town of 2164 inhab., on the rt. bank of the Sarre, or Saar.

Hommarting.

9 Phalsbourg (*Inn*: H. de la Ville de Metz) is one of Louis XIV.'s fortresses, planned by Vauban in the place of older works: it is of importance from its position, under the crest of the Vosges, as commanding the defiles of those mountains, and is itself built on the living rock.

On the next stage the road crosses the hill of Saverne, the dorsal ridge of the Vosges, the ascent and descent of which are not much less than 8 m. The spire of Strasburg may be seen in clear weather from the top. We now enter the Dépt. du Bas Rhin. The steep slope is traversed by the road in circuitous windings, by which it is brought gradually down. The entrance into Alsace is very picturesque, presenting a pleasing picture of fertility. The people differ much in customs, dress, and language from the French.

9 Saverne (Germ. Zabern), (*Inn*: Poste), a town of 5106 inhab., on the Zorn, once residence of the Bishops of Strasburg. It suffered severely in the 30 Years' War, but has ceased to be fortified since 1696.

Near the town are the ruined castles of Greifenstein and Hoch Barr. About 21 m. N. of Saverne is the fortress of Bitche, where many English were confined prisoners of war.

You now enter the level plain of Alsace, inhabited by people of the German race. The way to Strasburg is described as through one of the richest scenes, as far as regards soil and cultivation, to be met with in France.

15 Wasselonne, pop. 4192, a manufacturing town, with numerous cotton-mills.

12 Ittenheim.

The road now enters the valley of *France*.

the Rhine. Not one gentleman's place occurs between Bourdonnay and

13 STRASBURG. — *Inns*: H. de Paris; the best and good; table d'hôte at 1 and 5, 3 fr.; breakfast 1¼ fr.; rooms from 2 to 4 fr. Omnibuses run from the inns to the steamers on the Rhine and to the railway;—Maison Rouge (Roth's house);—La Fleur; in a central situation, near the diligences and the cathedral; the landlord speaks English;—Rebstock (the Vine); a 2nd-class German inn, but good.

Strasburg, capital of the ancient province of Alsace (Elsass), is a very strong frontier fortress, with 70,298 inhab., and a garrison of 6000 men, even in time of peace; situated at the distance of about 1½ m. from the Rhine, on the Ill, which, on its way to join that important river, intersects the town in all directions by canals. Strasburg is the *Argentoratum* of the Romans.

Though it has now for a long time been united to France, and forms at present the chief town of the Dépt. du Bas Rhin, yet it bears all the external aspect of a German town in the appearance of the streets and houses, and in the costume and language of its inhabitants. German is generally spoken by the lower orders, though French is taught in the schools. Louis XIV. got possession of Strasburg, which was an imperial city of the German empire, in 1681, by an unwarrantable attack during the time of peace.

The principal and most interesting building in the town is the *Cathedral*, or *Münster*, one of the noblest Gothic edifices in Europe, remarkable for its spire, the highest in the world, rising 474 ft. above the pavement; 24 ft. higher than the great Pyramid of Egypt, and 140 ft. higher than St. Paul's. The artist who designed this admirable masterpiece of airy open-work was *Erwin of Steinbach*: his plans are still preserved in the town. He died in 1318, when the work was

only half finished: it was continued by his son, and afterwards by his daughter Sabina. The remains of this family of architects are interred within the cathedral. The tower, begun 1277, was not completed till 1439, long after their deaths, and 424 years after the church was commenced, by John Hültz of Cologne, who was summoned to Strasburg for this end. Had the original design been carried into execution, both the towers would have been raised to the same height. A doorway, in the south side of the truncated tower, leads to the summit of the spire. On the platform, about  $\frac{2}{3}$ ds of the way up, is a telegraph, and a station for the watchmen, who are set to look out for fires. One of them will accompany those who wish to mount the upper spire, and will unlock the iron gate which closes the passage. There is no difficulty or danger in the ascent to a person of ordinary nerve or steadiness of head; but the stonework of the steeple is so completely open, and the pillars which support it are so wide apart, and cut so thin, that they more nearly resemble a collection of bars of iron or wood; so that at such a height one might almost fancy one's self suspended in a cage over the city; and, if the foot were to slip, the body might possibly drop through the open fret-work. At the same time, the elaborateness of the tracery, and the sharpness of the angles and ornaments, are proofs of the skill of the architect, and the excellent materials he had chosen; and it is only by a close inspection that the delicacy of the workmanship can be truly appreciated. Within a few feet of the top, the winding stair terminates, under a species of carved rosette. Several instances are recorded of persons who have either fallen, or have thrown themselves, off the top. The upper part of the spire, within and without, is covered with neatly carved names, chiefly of freemasons (?), who have visited it;

among them may be read Stolberg, Göthe, Schlosser, Herder.

The view of the multitude of rusty-coloured tiled roofs of the town is not very pleasing; nor is it the bird's-eye panorama of the rich district around of the Rhine and Black Forest in Germany, and of the Vosges Mountains on the side of France, that will reward the adventurous climber; but rather the exploit, the great elevation, and the near view which it affords of the steeple.

Now to descend to the body of the church. The exterior of the west end deserves the most minute examination.

"The gigantic mass, over the solid part of which is thrown a netting of detached arcades and pillars, which, notwithstanding their delicacy, from the hardness and excellent preservation of the stone, are so true and sharp as to look like a veil of the finest cast-iron, contains a circular window 48 ft. in diameter, and rises to the height of 230 ft.: *i. e.* higher than the TOWERS of York Minster."—*Hope's Architecture*.

"The building," says Mr. Whewell, "looks as though it were placed behind a rich open screen, or in a case of woven stone. The effect of the combination is very gorgeous, but with a sacrifice of distinctness from the multiplicity and intersections of the lines." The *triple portal* in the W. front deserves minute examination, on account of its sculptures, statues, and bas-reliefs; as does also the porch on the S. side, executed by *Sabina*, the daughter of Erwin. Although the greater portion of these carvings are modern, the originals having been destroyed by the democrats of the Revolution, who melted down the great doors of brass into sous-pieces, yet they have been restored with a perfect exactness, with great truth of sentiment, and good taste, by MM. Kirstein et Haumack. The group of the Death of the Virgin is executed in a masterly manner.



The nave was begun in 1015, and finished in 1275. The choir, far inferior to it in size and proportion, is part of an older building, attributed to the time of Charlemagne. The most remarkable things in the interior are the vast and beautiful marigold window, the rich painted *glass*, executed partly in 1348, partly in the 15th century, the pulpit of carved stone (date 1487), and the famous *clock*, in the south transept, made in 1571, which, after standing still for more than 50 years, has at length been repaired by a watchmaker of Strasburg. At 12, all its clockwork, puppets, and images are set in motion. The part of the church where it is now placed is supported by a beautiful single pillar, ornamented with statues: above the Gothic border, which runs along the wall, appears a figure of the architect of the minster, Erwin of Steinbach, carved by himself: he is interred here; and in 1835 the tombstone was discovered in the little court behind the chapel of St. John. A statue of him has lately been erected in the porch on the S. side of the nave.

The *Guild of Freemasons* has existed at Strasburg since the foundation of the minster, and is the parent of the lodges throughout Germany.

*Two ancient Gothic houses* near the Palais have been repaired, and deserve notice.

The *Church of St. Thomas*, appropriated to the use of a Protestant congregation, contains the *Monument of Marshal Saxe*, erected to his memory by Louis XV., the masterpiece of the sculptor Pigalle, and the result of 25 years' labour. It represents the General descending with a calm mien to the grave, while France, personified in a beautiful female figure, endeavours to detain him, and at the same time to stay the threatening advance of death. It is looked upon as a very successful effort of the chisel: though somewhat theatrical, there is a tenderness of expression about the

female figure which is truly charming. This monument was saved from destruction at the Revolution by a citizen of Strasburg, named Mangelschott, who covered it up with bundles of hay and straw, the church having been turned into a straw warehouse. Schöpflin, and a brother of the pastor Oberlin, are buried in this church; and there are one or two other small monuments. Two bodies, said to be of a Count of Nassau Saarwerden and his daughter, are shown, on account of the wonderfully perfect state in which flesh and clothes have been preserved after the lapse of more than a century. This is truly a disgusting spectacle.

Some curious portions of a "Dance of Death" were discovered in 1823, painted on the walls of the *new Church*.

The *Mairie*, in the Brandgasse, contains a museum of bad or second-rate *pictures*.

The *Académie Royale*, originally a Protestant school, founded 1538, raised to the dignity of an University in 1621, but suppressed at the Revolution, has produced several remarkable scholars, as Schöpflin, Oberlin, Schweighäuser, &c.: here also Göthe completed his studies, and took his degree of Doctor in Laws, 1772. His residence at Strasburg is admirably described in his autobiography. The Academy possesses a *Museum of Natural History*, which ranks far higher than the common average of provincial collections. It is very complete in the productions of Alsace, and especially in the fossils of the grès bigarré; and there is a large series of the fossil plants discovered at Sulz-les-Bains and Mühlhausen. The botanical collection contains the section of the trunk of a silver fir, from the Hochwald, near Barr; its diameter was 8 ft. close to the ground, its height 150 ft. There are many other specimens of woods, preserved in such a manner as not only to interest the botanist, but to be useful to the practical man, to the carpenter

and the like, by showing the texture and quality of the timber.

The *Public Library*, near the new Church, boasts of many literary curiosities: the principal are, the "Landsberg Missal," or "Hortus Deliciarum," of Herrade, Abbess of Hohenberg, richly and copiously decorated with illuminations and miniatures in the early Byzantine style, executed in 1180; many early-printed books; Cicero, printed by Faust, 1465; a Bible, printed at Strasburg, 1466, by Eggestein; Mentelin's Bible, printed here in the same year.

Here also is deposited a collection of antiquities, chiefly Roman, and found in Alsace; also some monuments of the middle ages; a statue of Rudolph of Habsburg; and the town standard (carroccio) of Strasburg, and some painted glass from Molsheim.

The earliest attempt at printing was made at Strasburg (about 1436) by John Guttenburg, who finally brought his invention to perfection at Mayence. Peter Schöffer, who assisted him, and made many improvements, particularly in the casting of metallic letters, was a citizen of Strasburg. The total number of volumes in the Strasburg library exceeds 100,000. The *statue of Guttenburg*, on the *Marché aux Herbes*, now called *Place Guttenburg*, was modelled by *David*, and it appears, on the whole, not inferior to the one at Mayence.

Strasburg is regarded as one of the strongest fortresses in France or in Europe; its fortifications, including the *citadel* of 5 bastions, whose outer works extend to the arm of the Rhine, were laid out by Vauban, 1682–84. Persons interested in military matters will be disposed to visit the *arsenal* of a fortress so important as Strasburg: it contains fire-arms for 155,000 men, and 952 pieces of cannon, 412 of which are required for the defence of the town and the citadel. There is a *cannon foundry* here, and one of the largest depôts of

artillery in France. By means of large sluices, constructed in the time of Louis XV., by Vauban, at the spot where the Ill enters the town, the country around Strasburg, between the Rhine and the Ill, can be laid under water, and the city rendered unapproachable by an army, and almost impregnable.

The *Palais du Roi* is a handsome edifice, close to the cathedral: it was originally the Bishop's palace.

There is a good provincial *Theatre* here, near the square called Broglie, from a governor of Alsace of that name. A very splendid *Synagogue* was erected in 1834 by the Jews. It is curious to contrast the present with the former condition of that people in this city. Nowhere did they suffer more cruel or tyrannical persecutions. The street called Brand Strasse (Fire-street) was so named because on the spot where the Préfecture now stands a bonfire was made, in 1348, to burn the Hebrews; and 2,000 of that devoted race, accused of having poisoned the wells and fountains, and thus caused the plague which desolated the city about that time, were consumed in the flames. From henceforth no Jew was allowed to live within the walls; and the summons of a horn, blown every evening from the Minster tower, compelled them all to depart.

The body of General Kleber (a native of Strasburg), originally interred in the Minster, has been removed to a vault in the centre of the *Place Kleber*, and a monument has been erected over it.

Strasburg is famous for its *Pâtés de foie gras*, made of the livers of geese, which are enlarged to an unnatural size by the simple process of shutting the birds up singly in coops, too narrow to allow them to turn, and stuffing them twice a day with maize. They are generally kept in a dark cellar, and the winter is the season for fattening them, coolness being essential. There is such a coop in almost every house in the town. Sulphur or



garlic is steeped in the water given to the birds, to increase their appetite. Instances are known of a goose's liver having attained the weight of 2 or even 3 lbs. Hummel, No. 9, Rue des Serruriers, is said to make good pâtés. A heavy duty is charged on them in England.

The gates of Strasburg are shut at 10 o'clock, but ingress or egress is allowed after that time for diligences, and for travellers by poste and by steam-boat; and some of the gates remain longer open in summer.

The principal *Promenade* is the *Ruprechtsau*, an extensive space, laid out in walks and gardens, beyond the walls.

*Conveyances* to Paris daily—*Malleposte* in 36 hours: 3 *diligences* in 43 hours.—*N.B.* Do not book a place to Paris unless you are *assured* that you will not be turned out of it at Nancy in favour of passengers from that place, which it is the practice of some messengeries to do.

*Diligences* also to Besançon and Lyons; to Metz; to Freyburg and Schaffhausen; to Haguenau (several); to Epinal; to Mutzig and Bischweiler.

*Railway* from Strasburg to Bâle (Rte. 170). Trains go 4 times a day. Starting from Bâle by the early train (7 A.M.) you may reach Mayence at 10 the same night.

*Railway* to Baden-Baden, Carlsruhe, Heidelberg, and Frankfurth.

*Steamers* descend the Rhine to Mannheim and Mayence twice a day, starting at 6 from the Canal of the Ill, in the middle of the city, and at 10½ or 11 from Kehl bridge, on the French bank of the Rhine; they reach Mayence in 11 hours: but take 2 long days to mount upwards from Mayence.

The distance from Strasburg to the boat bridge over the Rhine at Kehl, near which some of the steamers set out, is rather more than 1½ m. On the way thither you pass, on the rt., in the middle of an island formed by a branch of the Rhine, a monumental cenotaph, inscribed "Au Général

Desaix—l'Armée du Rhin—1801," bearing a medallion portrait of him; and bas-reliefs representing the Passage of the Rhine, the Battle of the Pyramids, and the Death of Desaix at Marengo. His body lies on the summit of the Great St. Bernard.

Kehl and the Rhine are described in the *HAND-BOOK FOR NORTH GERMANY*.

The Ban de la Roche, or Steinthal (Stone Valley), the scene of the Pastor Oberlin's beneficent life and labours, is about 30 m. S.W. of Strasburg. It is described in R. 168.

Strasburg communicates with Provence and the Mediterranean by the *Canal du Rhin au Rhône*, and with the Loire and Atlantic by the Canals de Bourgogne and du Centre, which supply the manufacturers of Alsace with fuel from the coal basin of the Loire, just at the time when their own coal mines had been exhausted.

## ROUTE 166.

PARIS TO THE BATHS OF PLOMBIÈRES, BY LIGNY, DOMRÉMY, AND EPINAL.

396 kilom. = 246 Eng. m.

The road is the same as Rte. 164 as far as

249 Ligny (p. 550), where it turns to the S.E. and ascends the valley of the Ormain to

23 Houdelaincourt: thence crosses the hills to

22 Domrémy (*la Pucelle*). This retired and insignificant village, on the Meuse, has been rendered celebrated as the birth-place (1410) of *Jeanne d'Arc*, the simple untaught peasant girl who quitted her flocks to rescue her country from foreign invaders, and to place the crown of France on the rightful sovereign's head. Here, in the deep shade of the neighbouring haunted wood, Bois Chénus (*Nemus Canutum*), she heard the mysterious voices of her guardian saints, St. Margaret and St. Catherine, urging her to the enterprise, and counselling her how to act; and here in the village chapel dedicated to them, now in

ruins, she would spend whole days in prayer, avoiding the pastimes of her companions. After the accomplishment of her mission, by the coronation at Rheims of Charles VII., Jeanne d'Arc entreated to be allowed to return hither to join her parents, and become a shepherd girl again, an intention she was persuaded to abandon to her own destruction. The only favour that she asked from the king, for whom she had effected so much, was that her native village should be exempt from every tax. This privilege was conceded, and remained in force down to the Revolution. In the registry-book of taxes the space opposite the name Domrémy was filled up with the words, "Néant, à cause de la Pucelle," instead of the amount of contribution. The humble *cottage* in which she was born, having always been treated with a sort of veneration, is still preserved. A *monument* and a girls' school have also been raised in her honour; and King Louis-Philippe has presented to the village a cast of the beautiful statue of the Pucelle by his own daughter, "another inspired Maid of Orleans."

At Vaucouleurs, about midway between Void and Domrémy, the maid first disclosed her mission to the Sire de Baudricourt, and hence she set forth on a journey of nearly 300 miles, to declare to the king at Chinon, in Touraine, the assistance which Heaven destined in support of his cause.

11 Neufchâteau (*Inns*: Couronne (?);—La Providence (?), a town of 3650 inhab., on a stream which runs into the Meuse not far off.

19 Houécourt.

19 Mirecourt.

24 Darnieulles.

9 *Epinal* (*Inn*: La Poste), chef-lieu of the Dépt. des Vosges, is a town of 9526 inhab. It stands on the W. declivity of the Vosges mountains, on the infant Moselle, which makes several small falls in passing through it, and it is surmounted by the ruins of an old *castle*. It has a large Gothic *church*.

*Diligences* to Nancy; to Thann and Mühlhausen; to Strasburg.

16 Xertigny. The Saône rises a few miles to the W. of this.

11 *Plombières* (*Inn*: Ours; poor accommodation). There is no lack of lodgings in the town; 10 frs. a day is charged for a double-bedded room, a sitting and servants'-room, with linen and its washing.

Plombières is a town of 1500 permanent inhab., situated on the Eau-ronne, at a height of 1382 ft. above the sea level. It possesses celebrated mineral springs, and may be regarded as one of the most fashionable watering places in France. The *waters* are chiefly saline and thermal; but there are some cold springs, one of them ferruginous, *La Bourdeille*. They are very numerous; the principal are the Sources du Romains, du Crucifix, de l'Enfer, du Grand Bain (147° Fahr.), des Capucins (127° Fahr.), du Bain des Dames. They are used chiefly for baths; but some, as the Crucifix, Bains des Dames, are taken internally.

The bath-houses belong to Government; the principal ones are *Bain Royal*, containing 2 public baths (piscines), one for male, the other for female bathers, each capable of holding 25 persons, besides private baths. The building also contains a reading-room, which serves for balls and concerts. The others are the Bain des Capucins, Bain Tempéré, Bain des Dames (so called from the Nuns of Remiremont, to whom it belonged), and Grand Bain, or Bain des Pauvres. In all there is a public as well as private bath, and in some are douche and vapour baths.

The waters are considered beneficial in chronic diseases of the digestive organs, dyspepsia, &c. The season lasts from May till October.

In the neighbourhood of Plombières are some agreeable *walks*, through the vast forests of oak, beech, and fir, which cover the surrounding mountains.

One of the *walks* nearest to the town leads to the *Fontaine Stanislas*,



a well on the side of an eminence overhung by rocks, carved with inscriptions recording the benefactions of the Polish king, who also founded a hospital here (see p. 551). The avenues planted along the sides of the road leading to Remiremont form another frequented promenade. The eminence called *La Feuillée* commands a fine view over the fertile Val d'Ajol.

### ROUTE 168.

THE VOSGES MOUNTAINS.—STRASBURG TO EPINAL, BY MUTZIG AND ST. DIEY.—EXCURSION TO THE BAN DE LA ROCHE.

139 kilom. = 86 Eng. m.

*Diligences* daily to Epinal, and to Mutzig.

This road through the heart of the Vosges mountains will possess an interest with many English travellers from its leading them close to the country of the estimable pastor Oberlin. The following account is derived from the journal of an English traveller:—"We left Strasburg by the Porte de Nancy, and crossing the Ill, passed over a country whose chief productions seemed to be tobacco, flax, and potatoes.

11 "Entzheim. In several villages the houses were hung with double rows of tobacco-leaves drying in the sun. 3 m. on rt. is the château of M. Humann, late Minister of Finance. At Altorf, the near undulating hills are covered with vineyards; in the distance the mountains of the Vosges show themselves with great beauty. At Molzheim, a prettily situated village, is a large manufactory of saws, files, and other edge tools." Near this are the saline thermal springs of Sulz-les-Bains, little frequented at present.

"At Darlesheim we cross the river Bruche, and entering a defile of the mountains lose sight of Strasburg spire, hitherto visible far above the level plain."

14 Mutzig, a small walled town of

3551 inhab., prettily situated on the Bruche. The *Château* of the bishops of Strasburg is turned into a manufactory of fire-arms. Behind the wooded hills to the W. rises the bald head of the Donon, 3314 ft.

"At Diersheim, 2 m. farther, a fine view of mountain scenery: the valley only  $\frac{1}{2}$  m. broad; on l. a level greensward from which the hills rise precipitously about 500 ft., covered with young oak, beeches, fir, &c.; before us the mountain stream, the narrow but fresh-looking valley shut up by the mountains of the Vosges, of which we trace 7 ridges rising one above another in the distance.

22 "Schirmeck, a village prettily situated at the junction of another small stream with the Bruche, has 2 large ribbon manufactories. We are now in the Dépt. of the Vosges. 5 m. farther, at Rothau, a village situated at the N. E. extremity of the Ban de la Roche, we turn to the l. out of the road to St. Diey, and crossing the Bruche by a road for which we are indebted to the labour of Oberlin's own hands, reach the quiet village of *Fouday*, within the Dépt. Bas Rhin, at the entrance of the valley of Waldersbach, which, though naturally sterile, enclosed by schistose hills, rising 1000 ft. above it, is much improved by cultivation and irrigation. A cotton ribbon factory has been established here by M. Légrand, which, unlike most other establishments of the kind, has proved a blessing instead of a curse. The children who are chiefly employed work at home under their parents' eyes, and thus reap all the benefits of industry without the risk of health or morals attendant upon a crowded room."—C. W.

In the churchyard is the *grave of Oberlin*, a plain stone with his name engraved on it, and the words, "Il fut 60 ans Père de ce Canton," and round the edge, "La mémoire du juste sera en bénédiction."—"His memory is indeed blessed: no cottager in this valley ever mentions his name

without the affectionate addition of Father. Look around; every smiling field, every cultivated spot, every tree bearing fruit, reminds them of their lost benefactor: the education of their children, the comforts they enjoy in their cottages, the very roads by which they communicate, and, of infinitely more importance, the knowledge of the road that leads to heaven, which was constantly and faithfully taught them both by precept and example,—all forcibly recall the memory of their ‘Father Oberlin.’” — *Capt. W.*

At Waldbach, a few miles farther, is Oberlin’s parsonage, where his study, books, MSS., specimens of natural history, and drawings remain nearly as he left them; the walls and doors decorated by him with texts from Scripture.

In the plain village church is a monument to him, a medallion head by *Ohmacht*. The school established by him, which in one generation redeemed the inhabitants of this district nearly from barbarism, will not be looked on without interest.

There is no inn at Fouday or Waldbach. There is a road from Fouday by St. Blaise and Villy to Schlestadt (see p. 561).

The principal mass of the *Vosges* mountains lies between Giromagny and the valley of the Breusch; they are about 120 m. in extent, running parallel to the Rhine, and separating its basin from that of the Moselle. They consist chiefly of rounded dome-shaped hills abounding in forests and often turfed on the top. The name “ballon” applied to several of them is doubtless derived from this swelling rounded form. Les Chaumes (Calvi montes), so called from their bareness, form the highest ground in the Ban de la Roche. The bulk, or thickest mass of the *Vosges*, rises between the Ballon d’Alsace (4124 ft.), the Donon (3314), and the Ballon de Sultz, the highest of all (4693).

The rivers Seine, Saône, Moselle, and Saar rise in the Vosges.

The road from Schirmeck to St. Diey runs by

20 Saales.

19 St. -Diey or Dié (*Inn: La Poste*). The name of this town of 7707 inhab. comes from St. Dieu Donné (Deodatus), to whom it and the valley were given by Childeric II. It stands on the Meurthe, here a mere torrent. Having been burnt down 1756, it was rebuilt, chiefly by the ex-king of Poland, Stanislas.

11 L’Hôte du Bois.

16 Rambervillars.

13 Girecourt.

15 *Epinal*, in Route 166, p. 558.

The *Baths of Plombières* are about 36 m. to the S. of this, p. 558.

#### ROUTE 170.

STRASBURG TO BÂLE.—RAILROAD, BY SCHLESTADT, COLMAR, AND MÜHLHAUSEN.

140 kilom. = 86 Eng. m.\*

Trains go 4 times a day: the stoppages by the slow trains are very numerous, 28 in all, and the journey in consequence tedious, occupying 5 hours.

Inquire if there be not one fast train daily from Strasburg at 5 P.M. and from Bâle at 1 A.M., which makes the journey in 4 hours. Passengers by this train pass the Douane without examination, if on their way to the Lower Rhine. Carriages and baggage may be plombé at either end of the line, in order that the search may be deferred till the end of the journey; or if you are going out of France, the plompage will relieve you from all search.

“The transit by the railroad from Basle to the steam-packet at Strasburg is, *on the whole*, well managed,

\* By the *post road* (147 kilom. = 88 Eng. m.) the stations and distances are:

15 St. Ludan.	19 Meyenheim.
12 Benfeld.	22 Mühlhausen.
17 Schlestadt.	17 Sierentz.
13 Ostheim.	12 St. Louis.
10 Colmar.	4 Bâle.



and yet rather puzzling to those who make it for the first time. At the office they give you three sets of tickets, for—1. omnibus to railroad (yellow); 2. railroad (white); 3. omnibus from Strasburg terminus to water-side (green); 4. steam-boat (white): these tickets clear all your luggage. The railroad ticket which was given to you at Basle must be produced to the booking-clerk. All the luggage must be taken to the examination room; and upon your stating that it is for the *Cologne Company's* steamer, it is registered accordingly, and you receive a ticket in the usual manner. All the steam-boat luggage is put into a separate van, and being plombé is driven to the water-side, in charge of a douanier; and the van being opened, you must select your luggage, and see it on board. The conductor of the omnibus takes your steam-boat ticket from you, and you must go for it to the office at the river side, where it is re-delivered to you, having been countersigned.”—*F. P.*

The transport of a carriage costs 50 fr.

The construction of this railway is chiefly due to the enterprise of MM. Koechlin and Brothers, of Mülhausen.

*Omnibuses* ply to and from almost all the stations on the line; the fare is 30 centimes.

The *terminus*, at present but a temporary one, is on the glacis, close to the Porte de Saverne.

There are no great works on this line, owing to its passing over a dead level country, up the valley of the Ill and parallel with the Canal du Rhône au Rhin, and with the Rhine, though at some distance from them.

It is carried over many hundred small bridges, which allow the streamlets descending from the Vosges to pass. It skirts, as it were, the roots of that mountain chain, and commands some pleasing views of them and of their old castles.

7 Geispolzheim, St.

3 Fegersheim, St.

3½ Limersheim, St.

4½ Erstein, St., a town of 3550 inhab. The Strasburghers destroyed its walls and the neighbouring fort of Schwanaue in the 14th centy. Hence an interesting excursion may be made to the *Odilienberg* (11 m.), commanding one of the finest views in the range of the Vosges; the Convent of St. Odilia, with a church built 1696, with 5 or 6 ancient chapels near it.

3 Matzenheim, St.

3½ Benfeld, St.—*Inn*, Poste. This small town was taken by the Swedes 1632, and fortified by Count Horn.

A little to the W. of Benfeld and Schlestadt lies *Barr*, a town of 4200 inhab., remarkable for the beauties of the surrounding country.

Close to Barr are the 2 castles and Abbey of Andlau, and near Barr are the fine castles of Landsberg on a lofty height, Birkenfeld and Spesburg, also the Heidenmauer or Pagan's Wall. Hüttenheim, on the l. of the railway, is distinguished by one of the finest and loftiest church towers in Alsace.

5½ Kogenheim, St.

4½ Ebersheim, St.

6½ Schlestadt, St. (Germ. *Schlettstadt*) (*Inn*: Le Bouc), seated on the l. bank of the Ill, anciently an Imperial Free City, has now 10,000 inhab. and some manufactures, and is a fortress of fourth class, laid out by Vauban. It was besieged by the Allies in 1815.

The church of *St. George* is rather an elegant Gothic building of the 14th centy., and that of *St. Foy* is remarkable for its antiquity, having been built 1094, on the model of the Holy Sepulchre church. Adjoining it is a large convent, called *Le Pavillon*, occupied in turn by Benedictines and Jesuits, but now a barrack.

The *Tour d'Horloge* or *Fausse-porte* is a fine Gothic gate tower pierced by a Pointed archway. *Martin Bucer*, the Reformer, was born here.

*Diligences* go hence to the indus-

trious town of St. Marie aux Mines, which is entirely engaged in the cotton manufacture.

From the vicinity of Schlestadt, and from other points on the railway between Strasburg and Mühlhausen, good views are obtained of the *Vosges Mountains* (p. 560), stretching nearly parallel to the Rhine on the W. and gradually sinking into the plain traversed by the railway. They have mostly a tame, rounded outline; here and there an escarpment of red sandstone, of which they are chiefly composed, breaks through the green forest, and ever and anon upon some projecting cape stands forth a ruined castle. The beauties of the Val de Villée, near Schlestadt, are extolled.  $2\frac{1}{2}$  m. from Schlestadt is the old castle *Kientzheim*.

About 4m. from Schlestadt is the ruined castle of *Hoher Königsburg*, the most extensive in the Vosges range, and very picturesque. From the top of its massive towers a fine view over Alsace and the Rhine valley is obtained. Its origin is unknown, but it is recorded that it was taken and dismantled (1462) by an army of Strasburghers and of Bâlois, who combined their forces, and placed themselves under the Bishop of Strasburg as general, in order to put down the robber knights, its owners, on account of the depredations they had committed. It was ruined and sacked by the Swedes in the 30 Years' War, 1633. The ruins are 4 m. distant from

$5\frac{1}{2}$  Hyppolite, St., and near this there are coal mines.

$4\frac{1}{2}$  Ribeauvillé, St. The best wine produced in the Vosges is grown here.

The hill rising on the W. of this town of 6568 inhab. is crowned by the castle of *Ribeaupierre*, which was besieged in turn by Rudolph of Habsburg and Adolphus of Nassau. Lower down, on neighbouring heights, are the castles of *Giersburg* and St. Ulrich. Along the crest of the advanced line of hills forming the Vosges range

above Ribeauvillé runs the curious and mysterious bulwark, of unknown antiquity, called *Heidenmauer*, or Pagan Wall. It is composed of unhewn stones, heaped together without cement, from 8 to 10 ft. high.

3 Ostheim, St.

3 Bennwihr, St.

6 Colmar, St.—*Inns*: Deux Clefs; good;—Ange. This is a flourishing town of 12,000 inhab., and chef-lieu of the Dépt. Haut Rhin. It is situated near the foot of the Vosges, at the distance of  $1\frac{1}{2}$  m. from the Ill, on two of its tributaries, which do much service in turning millwheels in their passage through the town. Its chief manufactures are cotton and printed goods. There are many large factories on the outskirts. In the 13th centy. it was made a Free Imperial city, and was joined to France 1697. Louis XIV., who took it in 1673, razed the fortifications, and they are now replaced by agreeable *Boulevards*.

In the *Cathedral* or Minster, built 1363, a respectable Gothic edifice, containing some monuments and painted glass in the choir, is a remarkable painting, of the old German school, by *Martin Schön*, or *Schöngauer*, a native of Colmar. It is placed behind the altar, and represents the Virgin Mary in a bower of Roses with the infant Jesus, attended by Angels. It is remarkable for its size and composition: the figures, rather larger than life, are on a gold ground. In the *public library* (containing 36,000 vols.) are several other paintings by M. Schön; 2 altar-pieces of 6 compartments each, filled with events in the Life of Christ; 6 subjects from the Passion; an Annunciation and Adoration of the Magi, also by M. Schön, with other pictures attributed to *Alb. Dürer* and *Grunewald*.

The *Halle aux Blés* is a desecrated church; the nave is very elegant. In the *Musée* is preserved an *aërolite*, which fell from the sky here in 1492.

The fine choir of the *Protestant*



*Church* is now a warehouse; and several other religious edifices are degraded to similar purposes.

General Rapp, celebrated for his defence of Danzig, was a native of Colmar.

The road to Besançon and Lyons (R. 171) here diverges from that to Bâle.

*Diligences* to Lyons; to Nancy and Paris; to New Breisach (an octagon fortress, built by Vauban, 1699); to Old Breisach and Fribourg, crossing the Rhine; also to *Munster* (15 m.), a manufacturing town, of 4340 inhab., on the Fecht, in a pretty, narrow valley, shut in by hills, where factories and country seats alternate with vineyards and gardens. The principal factory is that of MM. Hartman, for cotton prints, one of the largest in France, employing about 1200 work-people: there are also spinning and paper mills.

*Sulzbad*, in the valley of Munster, 9 m. from Colmar, has mineral springs of acidulous water, sometimes called "bain des fous," because considered to be efficacious in hypochondriac and hysterical complaints.

4 m. W. of Colmar is *Turckheim*, where Turenne gained a victory (1675) over the Imperialists.

$4\frac{1}{2}$  Eguisheim, St. This was the birth-place of Leo IX. Above the town rises the castle, conspicuous for its 3 towers.

$2\frac{1}{2}$  Herrlisheim, St.

$6\frac{1}{2}$  Rouffach (St.) is the birth-place of General Lefèvre, Duke of Danzig.

$5\frac{1}{2}$  Merxheim, St. Here stood the castle of Isemburg, inhabited by the Merovingian kings of France.

7 Bollwiller, St. There is a large nursery garden here, where all the known species of vine are cultivated. Some of the best wines of Alsace are grown near this.

At Guebweiler, a few m. up the valley of the Lauch, is an extensive manufacture of spinning machinery.

The Ballon de Guebweiler, or de

Sultz, the highest of the Vosges mountains, is 4693 ft. above the sea-level, and 10 m. distant from Bollwiller.

$4\frac{1}{2}$  Wittelsheim, St.

7 Lutterbach, St.

$2\frac{1}{2}$  Dornach, St.

3 *Mühlhausen*, St. *Inns*: H. de Paris;—Couronne. This town, containing many large new buildings, but for the most part old and irregular, surrounded by the Ill, and situated close to the Canal du Rhin au Rhône, was formerly capital of a small democratic and independent state, and an ally of the Swiss Confederation from 1466 down to 1798, when it was united to France. Since the beginning of the present centy. it has rapidly risen to be one of the most important manufacturing towns in France. Its population amounts to 20,129 by the last census: and 7000 workmen repair daily to the town from the neighbouring communes. An entirely new quarter has lately sprung into existence. The branch of industry from which this sudden progress is derived is the *manufacture of cotton prints and muslins*. The quantity made here probably exceeds that of any other place in the world; they are particularly distinguished by the perfection and variety of their patterns, and the fineness of the colours. Another manufacture, the *spinning of cotton*, does not flourish to an equal extent, having difficulty in competing with Manchester and Glasgow. There are several extensive manufactories of machinery. Cotton printing was first introduced here, 1746, by Samuel Kœchlin (the Orrel, Marshal, or Cobden of France, whose descendants are still at the head of the manufacturers here), in conjunction with J. Schmalzer and H. Dollfus.

Many of the mills and factories of Mühlhausen are carried on, and set a-going, by the capital of the bankers of Bâle. The condition of the work-

people is not good; they are badly clothed, and lodged generally in cellars. (See Bowring's Report.)

Mühlhausen has to contend against the serious disadvantage of its long distance from the sea (raw cotton being transported hither all the way from Havre and Marseilles), and the want of coal in the neighbourhood. Its supply of fuel is obtained chiefly from St. Etienne and Rive de Gier, through the Canal du Rhin au Rhône.

*Malleposte* daily to Paris (Route 162). *Diligences* to Paris; Lyons. There is a branch railroad from Mühlhausen to Thann (R. 171), by Dornach, Lutterbach, and Cernay. Lutterbach is on the line from Strasburg to Mühlhausen, and here the branch to Thann properly begins.

5½ Rixheim, St. Here are made the *stained papers* for rooms, including those very flashy pictures which commonly decorate the walls of salles-à-manger at inns; and one of the chief establishments employs 200 workmen.

1½ Habsheim, St.

10 Sierentz, St.

3½ Bartenheim, St.

7½ St. Louis, St. Baggage searched in coming from Switzerland. (p. 560, 561.)

3 BÂLE TERMINUS (see SWISS HANDBOOK). The Bâle omnibus meets every train, fare 50 cents.

*N.B.*—Travellers setting out from Bâle by the early train (7 A.M.) find, on their arrival at Strasburg, a steamer ready to start at 11 A.M., and by it they may reach Mayence at 10 P.M. the same night (see p. 557), or they may continue the journey from Strasburg by the Baden Railroad from Kehl to Mannheim, or Frankfurt.

#### ROUTE 171.

STRASBURG TO BESANÇON BY COLMAR, THANN, BELFORT, AND MONTBELLIARD.

228 kilom.=142 Eng. m.

A *malleposte* daily in 12 hours, accelerated by the railroad.

The railroad is the best mode of travelling as far as Colmar, or even Thann. (See Route 170.)

69 Colmar, p. 562.

10 Hattstatt. The road continues along the level plain of the Rhine as far as

14 Isenheim, where the country becomes hilly.

The pretty little town of *Thann* (pop. 3937) has a superb Gothic Church dedicated to *St. Thiebaut*, surmounted by a fine spire of delicate open work more than 300 ft. high. The *doorway* is highly enriched with sculpture, representing saints and Scriptural subjects, of very good execution; it is, in short, a miniature of Strasburg, and has lately been repaired.

On the hill above are the ruins of the Castle of Engelburg. There are manufactories of cotton prints here.

A branch *Railway* connects Thann with Mühlhausen (p. 563), and with the railway from Strasburg to Bâle (Route 170).

19 Aspach. At

14 La Chapelle, the heights which connect the chain of the Vosges with the Jura mountains are crossed; and leaving the fertile and industrious province of Alsace, we enter that of Franche-Comté.

16 Belfort, or Béfort (*Inn*: L'Ancienne Poste), a fortress of first class in strength and importance, commanded by a *Citadel*, defending the entrance into France from the side of Switzerland, by the pass between the Jura and Vosges. It was laid out by Vauban; but, besides its own formidable fortifications, it is protected by an intrenched camp, capable of holding 30,000 men. The town numbers about 6,000 inhab., and is seated on the Savoureuse.

The road from Paris to Bâle (R. 162) passes through Béfort.

Country barren and hilly to

11 Héricourt.

21 L'Île sur le Doubs, a bourg of 1,100 inhab., on the l. bank of the



winding Doubs, and on the Canal du Rhin au Rhône.

A détour from BÉFORT of  $5\frac{1}{2}$  m. will carry the traveller through Montbelliard (Germ. Mümpelgard) (*Inns*: Lion Rouge; Balance), a small walled town of 5,000 inhab., the majority Protestants, and industrious; it is prettily situated in the valley of the Allan and Luzine. The most conspicuous building is the *Château*, on a commanding height; the greater part a modern construction of the last century, flanked by ancient round towers. It is now converted into a prison. This town has to boast of being the birth-place of the distinguished naturalist *Geo. Cuvier* (b. 1769): a bronze statue of him by *David d'Angers* has been raised to his memory by his countrymen, opposite the house in which he was born.

2 m. from Montbelliard the road reaches the Doubs, and continues down its rt. bank at the foot of well-wooded limestone hills to the Ile sur Doubs.

Here the river is crossed by a bridge; the road still following its beautiful clear stream between hills 200 or 300 ft. high, covered with every variety of wild flowers.

The Doubs, a *doubling* stream, rises in the Jura, at the foot of Mont Rixon, 3,122 ft. above the sea-level, and flows for 60 m. to the N.E. as if to join the Rhine, but is turned to the S.W., on approaching Montbelliard, by the spur or ridge which connects the Vosges with the Jura, traversed by our road between Thann and BÉFORT. It descends past BESANÇON and joins the Saône below DÔLE. It has been canalised and made navigable for barges of 20 tons, and forms a limb of the inland water communication connecting the Rhine with the Rhône. At

11 Clerval, a pretty village on its l. bank, at the foot of hills 1,000 ft. high, the Doubs is recrossed. 10 m. farther a mass of naked rock, 500 ft. high, of the most picturesque form,

overhangs the road, which has barely room to pass between it and the river.

A steep hill is now to be surmounted, whose top commands a very extensive view of the mountain scenery of the Jura, to the S.E. Immediately at the foot of this hill lies the retired town of

15 Beaume les Dames, pop. 2,447. It is famous for its pâtés and for its fish.

The Doubs is again crossed, and another steep hill succeeds, from whose slope there is a fine prospect of the valley and of a ruined *castle* on the opposite side, which belonged to Charles the Bold, of Burgundy.

12 Roulans.

The scenery of the Doubs valley in this place is not unlike that of the Meuse between Liege and Namur. A sharp descent brings us to the fortified town of

19 BESANÇON (in Rte. 159).

## ROUTE 175.

PARIS TO METZ AND FORBACH, BY MEAUX, CHÂTEAU-THIERRY, EPERNAY, CHÂLONS-SUR-MARNE, AND VERDUN.

377 kilom. = 234 Eng. m.

The *Strasbourg Railroad* will run this way as far as Châlons.

*Malleposte* daily in 25 hours.

*Diligences* daily.

The road quits Paris through the Faubourg St. Martin, leaves on the l. the road to Senlis (R. 1), and traverses the large village Pantin, with its guinguettes and cabarets, to

12 Bondy. Through the Forest of Bondy, in a direction parallel with the *Canal de l'Ourcq*. This Canal commences at Mareuil on the Ourcq, and terminates near Paris, in the basin of La Villette; it is 57 m. long. It serves to feed the Canal de St. Denis, and furnishes Paris with a supply of fresh water.

19 Claye on the Beuvronne.

The banks of the Marne are reached at

15 Meaux (*Inns*: La Sirène;—Palais Royal), traversed by the Marne and the Canal de l'Ourcq, has a population of 9,000. It is a bishop's see, and its *Cathedral* is a noble Gothic edifice, begun in the 12th and continued until the 16th centy., but not finished; its vaulted roof is more than 100 ft. high. It has been recently restored by its actual bishop, in very good taste. It contains the tombs of several bishops, and the *Monument of Bossuet*, "the Eagle of Meaux," as he has been called, who long time filled the see. His marble statue, erected by the Dépt., is stiff, hard, and by no means successful as a work of art. His grave escaped, by a wonder, violation from the Vandals of the Revolution, and even the pulpit from which he preached remains. Some relics of him are preserved in the *Evêché*; the study in which he wrote, and the avenue of yews in the garden where he used to meditate. A house behind the cathedral is a good specimen of domestic architecture of the 15th century, of stone, flanked by turrets. There is an ancient *Hôtel Dieu* here, and an Hospice, founded by a citizen, Jean Rose, is now turned into a Séminaire. 3 abbeys, numerous convents, and 4 out of its 7 churches, were destroyed at the Revolution, and scanty ruins alone exist. A magnificent *Hôpital Général* has been built here lately, and the *Ch. of St. Nicholas* has been restored. Meaux furnishes Paris with a large supply of corn and flour from the water-mills on the Marne. A sort of *cream cheese* (fromage de Brie), known as Fromage de la Poste aux Chevaux à Meaux, is peculiar to the place, and is considered very delicate.

The Marne is crossed by a wooden bridge: one of stone which preceded it having been blown up by the French in 1814.

10 St. Jean les deux Jumeaux.

9 La Ferté-sous-Jouarre (*Inns*: Epée; France; H. du Grand Condé); a town of 2,907 inhab. (Jovis Ara?),

on the Marne, here varied by islands, in one of which, united to the banks by a bridge of 5 arches, is an old mill. Here is a pretty *Pavillon*, of the time of Louis XIII., which, it is said, once belonged to the Duc de St. Simon. The Château de Laguy, in the Faubourg de Condets, and the castle of La Barre, flanked by turrets, near the rt. bank of the Marne, deserve mention. La Ferté is famed for its *millstones*, the best in the world, quarried in the vicinity out of beds of a siliceous cellular rock, known as Burr stone, almost peculiar to the freshwater basin of Paris, in which it forms nearly the uppermost stratum. The stone is very full of cavities, formed chiefly by shells, which have been turned into flint. The blocks are extracted in cylinders, by driving in wedges of wood and iron. A good millstone, 6½ ft. diameter, costs about 48*l.*; but many of those which are used are composed of small *pièces* (carreaux) bound together with iron hoops. The number of millstones extracted amounts to 1,200 pairs yearly, which are chiefly sent to England and America.

On an island in the Marne stands the ancient and half-ruined Castle of *La Barre*; the height opposite La Ferté is crowned by the antiquated town of Jouarre. La Ferté, as before noticed, means *la fortifiée*. The Marne is again crossed, on quitting this town, by a suspension-bridge.

15 La Ferme de Paris (Dépt. Aisne). N.B. There is another road (not post) by Charly, along the banks of the Marne, which are very prettily varied, to

12 Château-Thierry (*Inns*: Sirène;—Poste), a neat and pretty town of 4,697 inhab., agreeably situated on the Marne. On the summit of the gently sloping hill on which it is built are the fragments of a *Castle*, which has now nearly disappeared, constructed, it is said, by Charles Martel for the young King Thierry IV. The site, and the ground around these mouldering walls, are converted into



a pleasant and well-kept *public walk*, and command a pleasing prospect of the town and river. The most perfect of the towers is turned into a powder magazine. The *Church of St. Crispin*, on the heights, of massive pointed architecture, resembling a fortress, surmounted by a huge tower and entered by high flights of steps, deserves the notice of the antiquary. In the *Rue des Cordeliers* (the name given in France to the Franciscan friars from the knotted *cord* which they wore round the waist) the house is preserved in which the charming poet *Jean de la Fontaine* was born, 1621. A *statue* of him has been erected at the end of the promenade called *La Levée*.

This town suffered much in the campaign of 1814, when the plain of Brie was covered over with uncouth hordes of Calmucks and Lesghian Cossacks, having been taken and retaken several times (Feb. 8—12).

The borders of the Marne, up whose l. bank our road proceeds, are the prettiest part of the ancient province of Champagne, the country of the champagne wine. “The whole drive is exquisite, constantly varied and picturesque, and glowing with abundance: corn, vines, and fruit, gardens of roses and orchards, with here and there pretty villas belonging to wine-merchants peeping from their shrubberies, and prospects of extreme beauty opening from the summit of the hills, with the bright Marne winding at their feet.”—*Miss Costello*.

9 Crézancy.

14 Dormans (*Inn*, Lion d’Or?), a town of 2,000 inhab., in the Dépt. Marne, has a port on the river. The ruins of the Château of Châtillon, on an elevated and apparently intrenched position, have a very picturesque aspect.

9 Port à Binson.

15 *Epernay* (*Inn*, H. de l’Ecu de France), a town of 5,318 inhab., on the l. bank of the Marne. It is the head quarters of *Vins de Champagne*;

the kinds which are grown in the vicinity are distinguished from those produced near Rheims, as “*Vins de la Rivière*.” *Aï*, which gives its name to one of the best sorts, is a hill a little higher up the Marne, on its rt. bank. Almost the only “*lion*” is the *Cellars* cut out in the chalk rock; they are of vast extent; a perfect labyrinth, and always contain several millions of bottles, a great part of which are sold on the spot, wholesale, at 2 or 3 francs the bottle.

“Formerly wines from these particular spots were esteemed for their peculiar qualities; but now that the wine of *Aï* or any celebrated locality is no longer prepared without the admixture of the wine of other places, the general quality of champagne wines is greatly improved. These growths are now of value chiefly for admixture; and a skilful wine preparer gives to his wine a quality and character fitted for different markets and countries by his judicious proportions of the wine grown in different soils or aspects. Thus a light wine is preferred in Russia, and a full-flavoured wine in England; and these depend on the selection of the wine, and the degree of sweetness artificially imparted.

It is a common mistake to suppose that champagne wine is obtained from unripe fruit. The grapes are small, but luxuriously sweet; and fine wine is never produced unless the season be most favourable to the ripening of the fruit. The summer of 1842 was one of the finest ever remembered for quality and quantity. The rains, which destroyed the greatest promise for clarets in that year, only increased the quantity and excellence of the champagne wines, which are later by 3 weeks in the vintage; and 1842 will long be celebrated for the excellence of its champagne.

“When the fruit is gathered and pressed, the juice is exquisitely sweet, but in a few days this is destroyed by fermentation in the casks in which it

is placed. When this subsides the wine is vapid, and very disagreeable; it is then stopped, and fined to as great a degree of brightness as can be obtained before the bottling season, usually in March following the vintage. When it is bottled, a second fermentation is induced, by putting into each bottle a small glass of what is called *liqueur*—sugar-candy dissolved in wine, and fined to brightness. This fermentation produces a fresh deposit of sediment or lees, however bright the wine may be when bottled. In this process the greatest attention is necessary, and the bottles are closely watched, the temperature of the air carefully regulated, to promote or check the fermentation; yet thousands of bottles explode—so many, indeed, that 10 per cent. is always charged as a cost of manufacture: but in seasons of early and great and sudden heat 20 per cent. and even 25 per cent. are broken. It was reported that Madame Cliquot of Rheims, the largest grower in France, lost in the latter proportion 400,000 bottles in the great heat of April, 1843, before the fermentation could be checked by supplies of ice from Paris thrown into the caves.

“The destruction of so large a proportion as 10 per cent. is never considered a loss, for the wine buyers, who go round to the growers and merchants to purchase stock, always inquire the amount of breakage. They despise the wine that has lost only 5 per cent., and expect to pay more for wine that has fermented destructively.

“When the wine, after clouding with fermentation in the bottles, begins to deposit a sediment, the bottles are placed, with the necks downward, in long beds or shelves, having holes obliquely cut in them, so that the bottoms are scarcely raised. Every day the man whose business it is to attend to this process lifts the end of each bottle, and after a slight vibration replaces it a little more upright in the hole, thus detaching the

sediment from the side, and letting it pass towards the neck of the bottle. This is done for some time, until the bottle is placed quite upright, and the sediment is entirely deposited in the neck of the bottle; which is then ready for *disgorging*. In this process, a man holds the bottle steadily, with the mouth downwards, before a recess prepared for the operation, cuts the wire, when the internal force drives out the cork, and with it the foul sediment. The skill of the workman is shown in his preserving all the bright pure wine, and losing only the foul. There is an indescribable manipulation in this. An old cork is ready to replace that blown out, which in its turn serves again; the bottle is filled up from some previously purified wine, and again stacked. A second disgorgement is always necessary when the wine is prepared for sale; sometimes a third: when ready, it is sweetened for the particular market, or taste of customers: this preparation is, in fact, a second disgorgement. But the wine now gets another dose of *liqueur*, which is prepared with great care and purity, by candy dissolved in white wine for ordinary champagne, and in red wine for *pink*; and the colouring thus given is sufficient. The quantity put into each bottle depends upon the market to which it is to be sent,—generally a good wine-glassful: this gives it the requisite sweetness, and aids its sparkling condition when opened. The high price of genuine champagne may be accounted for by the loss from breakage and the cost of preparing. So large is the demand now for this class of wines, that many of the wine districts make *mousseaux* wines in imitation, under the names of sparkling Hock, Burgundy, and Moselle; and even in Hungary they make and send 8 millions of bottles annually to Russia, which country consumes more than 3 times that amount from France. A large quantity of wine is made and sold as champagne in France; and a company



exists in Paris, Cette, and in many other towns for this manufacture. Light, poor wines, such as inferior Chablis, are sweetened with candy, and fined or strained bright: the liquor is then passed through an apparatus, which charges it with carbonic acid gas: in this state it is bottled, and in 10 minutes is ready for the market. There is another establishment of the same sort in London. The English imitation by gooseberries is well known; and lately a patent has been granted, which is worked profitably, for making champagne of the juice of the stalks of rhubarb: but all these imitations fall miserably short of the real article. The genuine productions of France in the champagne districts exceed 50 millions of bottles. Moët was a name long celebrated, but it is now more than rivalled in fame, and surpassed in extent, by several others.”—*W. B.*

Large quantities of coarse *earthenware* are made at Epernay from clay called *Terre de Champagne*, obtained from the neighbouring hill of Montigny.

One of the principal buildings is the house of *M. Moët*, the eminent wine-merchant, in which Napoleon slept at the time of the battle of Montmirail, 1814.

The town was taken by Henri IV., 1592, after an obstinate siege, in which Marshal Biron was killed. In the hideous modern church remain a fragment of a portal in the style of the Renaissance, and 16 windows filled with curious *painted* glass of the 16th centy.

The journey continues up the l. bank of the Marne, through a region of vines; the vineyard of Aï being conspicuous on the opposite bank. The landscape somewhat monotonous, the river appearing only now and then.

18 Jalons.

15 *Châlons-sur-Marne*. (*Inns*: H. Morizot;—La Cloche d’Or;—H. du Palais Royal; not a fine house, but decent and comfortable;—H. de

Nancy.) This is the chef-lieu of the Dépt. Marne; and has a population of 13,163. During the middle ages, and under its Count-Bishops, it enjoyed much greater prosperity as a commercial entrepôt, numbering 60,000 inhab. Its privileges were withdrawn, and its celebrated fairs dwindled away, after the union of Champagne with France in 1284.

The town is old; principally of timber, lath, and plaster. The *Cathedral* was built in the 16th centy.; the front has been modernised, but in other parts it is in a rich and florid style: at the W. end is a bold and elaborate gallery, within which is a pretty chapel in the style of the Renaissance, and some good painted glass, including a rose window. It is 360 ft. long and 96 ft. high. The spires are of a beautiful open work, a style of which the finest example is found at Freyburg, in the Breisgau. The Marne runs through the city; and on the banks is another fine Church, *Notre Dame*, of early Romanesque architecture, and forming a striking object in many points of view. Outside the walls is the *promenade du Jard*, planted with 2000 ash trees (*ormes*).

“The *Champagne cellars* of M. Jaqueson, of Châlons, compose one of the finest establishments in France: his caves now hold, as an ordinary stock, 3 millions of bottles; and yet he is greatly extending them.\* On approaching Châlons his buildings give the appearance of a garrison to the town, as they crown the hill, and line the road; and their extent may be imagined, when one portion only—that which contains his stores in cask, and his sheds for packing, where he keeps his wood and straw—were let for 6 months to the French Government as barracks for 4,000 men; and the ground within the building offered ample space for the parade and manœuvring of the troops. There, are excavations in the chalk rock nearly a mile long,

\* Cutler and Lee are his agents in London.

through which loaded waggons are driven. M. Jaqueson expends 6,000*l.* a-year in corks alone.”—*W. B.*

*Diligences* daily to Nancy and Strasburg (R. 164); to Rheims (R. 178), and Troyes, as well as to Paris and Metz.

One of the routes to Strasburg turns off here up the valley, to Vitry-sur-Marne (R. 164).

An account of the battle of Attila, near Châlons, is given in Route 187.

6 m. from Châlons the road to Ste. Menchould passes the beautiful Gothic Church of *N. D. de l'Epine*, a perfect cathedral in size and beauty, surmounted by a most elegant spire of filagree open work, contrasting forcibly with the hovels of the poor hamlet around it. “The exterior is especially beautiful, full of bold and graceful devices, the whole more like some luxuriant tropical plant than a mass of stone.”—*S. A.* It was constructed towards the end of the 16th centy., partly at the expense of Charles V.; and its present ruinous condition is much to be lamented. Its triple portal at the W. end, richly adorned with sculptures of holy persons and sacred subjects, the fine rose windows surmounting them, the gargoyls round the eaves, quaintly carved, the elegance of the piers and arches, the choir screen, or jubé, delicately carved, a bas-relief of wood over the high altar, and some curious painted glass, all merit examination.

The truncated tower was deprived of its spire at the end of the 18th centy., in order to erect upon it the *Telegraph*, which still holds its place.

18 Somme Vesle.

16 Orbeval.

8 Sainte Menchould.—*Inn*: La Ville de Metz: “c’est une auberge excellente,” and its kitchen is a “cuisine modèle,” says *Victor Hugo*. This town of 3,900 inhab. has nothing worth notice, except its very pleasing aspect and position; it stands on the Aisne.

6 m. off is *Valmy*, where the

French under Kellerman defeated the Prussian army and compelled it to evacuate the territory of France, 1792. Louis-Philippe was present in this battle. The French commander, who became Duke of Valmy, desired at his death (aged 82, in 1820), that his heart should be transported to the battle field, in order that it might rest among the remains of his brave companions in arms who fell there. This wish has been complied with, and a simple monument erected on the spot.

The road to Metz passes through a nearly uninterrupted orchard, as far as the large village of

14 Clermont en Argonne, previously entering the Dépt. of the Meuse, across the very pretty wooded valley of the Brième, and the defile of les Islettes. 11 m. to the N. lies the small town of *Varennnes*, where the unfortunate Louis XVI. and his family were arrested, June 21, 1791, while endeavouring to escape across the frontier, by Drouet, post-master of Ste. Menchould, as the king’s carriage was crossing the little place or square.

The ridge of land called Monts de la Meuse, separating the basin of the Marne from that of the Meuse, is crossed between

10 Dombasle and Verdun. The passes of these hills were the scene of the campaign of 1792, when Dumouriez was opposed to the Prussians; but they have lost their military importance, now that the country of l’Argonne is drained, and its forests cleared.

We now enter the valley of the Meuse and the territory formerly known as Les Trois Evêchés (Metz, Toul, and Verdun).

15 *Verdun* (*Inns*: H. de l’Europe; Trois Maures, dear—*J. L.*) is an ancient and historical town, and a fortress of the fourth class, containing a population of 10,540: it is seated on the Meuse, which here first becomes navigable. It is well known to many Englishmen as the *prison* in which



they spent 11 weary years from 1803, when so cruelly and unjustly seized by Napoleon on the sudden breaking out of the war, and kept until his fall in 1814.

The *citadel*, which is alone of importance as commanding the course of the Meuse, was planned by Vauban. The beautiful Gothic chapel of St. Vannes, in the midst of it, was pulled down in 1825 to give place to a barrack.

The great event which renders Verdun distinguished in history is the dismemberment of the vast empire of Charlemagne in 843, between the 3 brothers—Louis, who received all Germany as far as the Rhine; Charles, who took the Gallic provinces S. of a line formed by the Scheldt, Meuse, Saône, and Rhône; and Lothaire, who kept Italy and the E. part of Gaul. This act is known as the “Treaty of Verdun.”

Verdun was a free city of the Empire down to 1552, and was not finally united to France until the peace of Münster, 1648.

It was taken by the Prussians, 1792, after a bombardment of 15 hours, in spite of the opposition of Marceau, Lemoine, and other brave officers, who wished to hold out still longer. It was, however, soon evacuated by the Prussians in consequence of the victory of Valmy. When the French regained possession, the revolutionary tribunal sent to the guillotine 15 young women, all under 15 years of age, for the *crime* of having danced at a ball given by the Prussian officers.

Verdun is celebrated for its *manufacture of sugar-plums* (*dragées*) and liqueurs.

A voiture may be hired here from Barthélemy to go on to Metz in 10 hours.

Beyond Verdun you pass through a beautifully wooded country.

18 Manheules.

10 Harville.

12 Mars la Tour (Dépt. Moselle).

11 Gravelotte.

Immediately beneath the steep hill and corkscrew road, leading down into the plain where lies Metz, and winds the Moselle, is the beautiful village Roseillyeuse: the banks of the Moselle are flat and uninteresting.

14 METZ. *Inns*: H. de l'Europe; best, but dear;—du Nord;—de France.

Metz is considered the strongest fortress in France, and forms the centre of defence on the frontier of Germany between the Meuse and the Rhine. It is also chef-lieu of the Dépt. of the Moselle; and an important city on the score of its population (44,131), of its trade, and of its manufactures. It is seated on the Moselle, at the junction of a small stream, la Seille. The streets in the centre of the town are narrow, and the houses lofty, but the river is lined with open *quays* and crossed by fine bridges. The situation of Metz, its public gardens and quays, will repay the traveller for a halt of some hours. It possesses a magnificent Gothic *Cathedral*, whose construction was continued from the 14th to the 16th centuries, with some incongruous additions (Portal, 1754) in the style of Louis XIV. It is surmounted at the cross by an elegant spire of open work 373 ft. high (built 1427), but is without towers at the extremities. It is 373 ft. long, and the elevation of the vaulted roof above the pavement is 141 ft. (?). The painted glass of the choir, executed 1526 by Anthon Busch of Strasbourg, is remarkably fine, the design good, and the colours very brilliant. The font, called Cuve de César, is very ancient, probably Roman, and oblong in shape. Here are preserved the ancient stone *throne* of the early bishops; 2 processional crosses, 12th and 14th centuries; a cope of red silk, embroidered, said to be Charlemagne's; mass-books, &c.; and a *dragon* of pasteboard, or canvas, on a wooden frame, which was formerly carried through the streets in pro-

cession, with a man inside of it. It is worth while to ascend to the clestory gallery, to view the stained glass close at hand, and to pass on to the roof, in order to examine the skilful arrangement of the flying buttresses, and the details of sculpture, as well as to enjoy the view over the city.

Another church, *Notre Dame de la Ronde*, has a *choir*, built 1130. Within the citadel is a *Round Church*, which belonged to the Knights Templars, somewhat like the round churches of Cambridge and Northampton. It is wholly Romanesque in style; the nave is externally an octagon: it has a low apsidal E. end. Within it, and in a building near it, probably the Knights' Refectory, are traces of painting of the 13th centy.

Some of the ancient city gates remain, and retain the machinery for raising the portcullis.

The church of St. Ségolène may interest the antiquary.

The *Esplanade*, its shady walks and gardens brilliant with flowers, planted with lofty acacias, and "confided to the care of each citizen," with the river, bridges, and fine buildings, in the neighbourhood, are much to be admired.

Metz has one of the largest *Arsenals* in France, with cannon foundery, &c., the machinery moved by water. It is shown only Monday and Thursday, by order. The immense *Military Hospital* is capable of holding 1500 patients. Metz is abundantly supplied with barracks. There is also a *School* for the application and practice of *Artillery and Engineering*.

The fortifications were planned by Vauban, and continued by Marshal Belleisle. The most important works are the forts of *Belle Croix*, a chef-d'œuvre of military construction, begun 1731; and *la Double Couronne*, surrounded by a triple ditch filled with water. In addition to these, there is a considerable redoubt called *le Paté*, so contrived that it may be

converted into an island, by closing the sluices on the Seille, whose waters may be raised 24 ft., so as to form a lake more than 6 m. in extent.

Metz, for a long time capital of the kingdom of Austrasia, became, under the Emperor Otho II., a free imperial city, and residence of a prince-bishop. At length, in 1552, the Constable Montmorency gained possession of it by stratagem for Henri II. The Emperor Charles V., furious at the loss of so strong a fortress and important a city, containing at that time 60,000 inhabitants, assembled an army of 100,000 men, determined at all risks to regain it. The defence, however, had been undertaken by the youthful and chivalrous François Duc de Guise, the same who afterwards wrested Calais from the English, who threw himself into the place with the *élite* of the French noblesse, among them the Prince de Condé. The Guise, by his address and activity, conciliated the citizens, inducing them to endure patiently the horrors of a siege, and strengthened the walls by new works thrown up in an incredibly short space of time. The details of this hard-contested siege are familiar to all who have read Robertson's *Charles V.* On Jan. 1, 1553, at the end of 10 months, the Emperor, experienced general as he was, was compelled to raise the siege, having lost 30,000 men before the place. "Fortune is a woman," he exclaimed bitterly, "and she favours only the young." The Duc de Guise was at that time only 30 years of age.

There are more *Jews* in Metz than in any other city of France, except Paris.

Metz is the native place of Generals Kellerman, the hero of Valmy, and Custine, who was guillotined.

Though Metz was an important city under the Romans, who called it *Divodurum* and *Metis*, yet there are few traces of their buildings in the



town itself. Without the walls, however, at the village of *Jouy aux Arches*, 6 m. off, on the road to Nancy, are the very interesting remains of a *Roman Aqueduct*, which conveyed the waters of a streamlet from Gorze to Metz, a distance of more than 15 m. Five arches are still standing on the l. bank of the Moselle, and 17 in the village of Jouy on the rt., out of 118: that under which the road passes is 60 ft. high. The *gates* of Metz are shut at 11, some even earlier.

*Steamers*, daily in summer (starting from the Quai de la Préfecture) in 1 day to Trèves; to Pont à Mousson, and Nancy (Route 181). Travellers entering France must here obtain their *passe provisoire* (Introduction, § c), which is attended with some difficulty for those who wish to continue on to Paris with the diligence without detention.

Between Metz and the frontier of Germany, the road passes through

18 Courcelles Chaussy.

8 Fouligny.

17 St. Avold.

18 Forbach, a town of 4,281 inhab. Custom-house.

On the arrival of the Paris malleposte, another starts for Mayence and Frankfurt, which place it reaches in 18 hours.

The road hence to Mayence will be found in **HAND-BOOK FOR NORTH GERMANY.**

## ROUTE 178.

PARIS TO MÉZIÈRES AND SÉDAN, BY  
SOISSONS AND RHEIMS.

257 kilom. = 157 Eng. m.

*Malleposte* in 19½ hours, returns in 24½ hours.

*Diligences* daily.

The road quits Paris by the Faubourg St. Martin, and traverses the village of la Villette, situated on the basin of the Canal de l'Ourcq. At this point the most desperate resistance was made by the French in defence of Paris, against the allied

armies, in March 1814, and several bloody combats were fought here.

11 Le Bourget. Napoleon on his way from Waterloo stopped here some hours, in order not to enter Paris by day-light. At the radiation of roads called *Patte d'Oie* (goose's foot), you leave on the l. the route to Senlis, Lille, and Amiens. (R. 1 and 185).

16 Mesnil Amelot (Seine et Marne).

8 Dammartin. The Church of *Notre Dame* contains the monument of its founder, Antoine de Chabannes, leader of the ferocious brigands called "*Ecorcheurs*," died 1488.

The Castle is pulled down.

A little on the l. of the road lies the village of *Ermenonville*. In the *Château* (which belonged to M. de Girardin) Jean Jacques Rousseau resided 3 or 4 months, and here terminated his miserable existence, it is supposed by poison, if not by the additional aid of a pistol, 1778, aged 66. (See Musset-Pathay, *Vie de J. J. R.*, 1822.) His tomb is in the midst of the *Ile des Peupliers*, in the grounds of his host.

14 Nanteuil-le-Haudouin (Oise).

A tower of the *Château* of the time of Francis I. alone exists.

10 Levignen.

15 Villers-Cotterets, a town of 2,689 inhab. Its magnificent manor-house, belonging to the Duc de Valois, of the age of Francis I., is now degraded into a poor-house (*Dépôt de Mendicité*).

La Ferté Milon, a walled town on the Ourcq, with an old castle, about 9 m. S. of our road, on the way to Château-Thierry, deserves mention as the birth-place of *Racine*.

11 Verte Feuille.

13 Soissons. (*Inns*: Croix d'Or; Couronne; Lion Rouge.)

This is a truly historical city, and one of the oldest in France as regards its foundation. Cæsar found the territory of the Suessones most extensive and fertile, and under the rule of a king not only the most powerful in

the whole of Gaul, but who ruled over part of Britain. *Noviodunum*, at that time the name of this city, is mentioned thus in the Commentaries: "Cæsar in fines Suessionum qui proximi Rhemis erant, exercitum duxit, et ad oppidum Noviodunum contendit." Under its walls, Clovis, by defeating Syagrius, in 486, put an end to the Roman rule in France. He established here the throne of the Franks, and made Soissons his capital. Afterwards, and because some of his successors made it the seat of government, they were called Kings of Soissons. Charles the Simple was here defeated 924.

Its importance, in a military point of view, as commanding a passage over the Aisne, is shown by its fortunes in the campaign of 1814, when it was twice taken and retaken within 4 weeks—first, by the Russian general Chernicheff with his Cossacks, by a coup-de-main, February 13th, when its governor, the brave General Rusca, was killed by a cannon-shot on its walls. The French, however, regained it the same day, Chernicheff being compelled to withdraw. Napoleon laid the greatest stress upon the possession of it, enjoining the garrison to hold it to the last drop of their blood; and, if his injunction had been complied with, Blücher and the Silesian army, pursued by Napoleon across the Marne, and pent up between his army and Soissons, with the army of Marmont and Mortier behind it, would probably have been annihilated. Fortunately for the old Prussian Marshal, he obtained possession of the place by a disgraceful capitulation on the part of the French governor, which deranged all Napoleon's plans, March 3d, and Blücher thus escaped out of the trap which Napoleon had laid for him.

Soissons in 1814 was defended only by antiquated ramparts; it has since been converted into a regular fortress. It is a city of 8,149 inhab., pleasantly situated on the banks of the Aisne.

Owing to what it has suffered from time and from the wars of 1567, when it was sacked by the Huguenots, and that of 1814, Soissons of the present day is a new town, and has a modern air, with few tangible relics to which one may attach the recollections of ancient times. The chief buildings remaining here consist of the *Castle*, occupying only the site of that inhabited by the Merovingian kings.

The *Cathedral*, surmounted by a solitary tower, is a very dilapidated edifice, founded in the 12th century, whose venerable appearance is much injured by injudicious repair. The choir is of the 13th century (1212). The S. transept ends in a semicircle. Soissons is one of the oldest episcopal sees in France; indeed, traditions of the church would refer its origin to the primitive Christians.

Of the once magnificent *Abbey of St. Jean des Vignes*, where Thomas à Becket was received when in exile, which was castellated and moated, and formed a fortress by itself, detached from the town, only the W. end of the church, surmounted by 2 towers, crowned by spires, remains. These are a great ornament to the town, and were spared at the entreaty of the citizens, when the ruthless democrats destroyed the rest. The towers and the portal are probably of the 13th century, the spires are more modern. The *Church of St. Leger* is interesting for its architecture, and tolerably perfect.

Some fragments of antiquities found in and near the town are stored away in a *Museum*. The famous tomb of St. Drausen, and the statues of several abbesses, have been saved from destruction.

A short walk across the fields, along the rt. bank of the Aisne, leads to an institute for *Deaf and Dumb*, occupying the site of the once celebrated *Abbey of St. Médard*, which has been razed to the ground, the only remnant being a subterranean *Crypt*, the date of which is referred



by some to the 11th century (?). It is remarkable for the beauty of the construction, the sharpness of the stone, and the good preservation of the colours upon it. Here were buried the kings Clothaire and Sigebert; and in a dismal dungeon adjoining it, measuring 8 ft. by 3 ft., which is still pointed out, Louis le Débonnaire is supposed to have been confined by his own son, Clothaire, 833. The verses on the wall, apparently referring to him, are not older than the 15th century.

Among the natives of Soissons are kings Caribert, Chilperic, and Clothaire II., and the Duc de Mayenne, chief of the League, the opponent of Henri IV., who died here.

*Diligences* run to Laon (22 E. m.) (see R. 187); to Compiègne, Amiens, &c.

About 10 m. N. of Soissons is the very curious Gothic fortress of *Coucy le Château*, the beau ideal in extent, arrangement, and picturesqueness, of a feudal castle, and, perhaps, the finest in France, though in ruins. It is attached to an old and picturesque walled town (*Inn*: Pomme d'Or), situated on the extremity of a high headland overlooking a deep valley. The castle consists of an outer bail or court, whose walls, garnished with circular towers at the angles about 100 ft. high, and with semi-circular ones, or bastions, along the curtains, were partly blown up by Mazarin, 1652. Within this is the inner bail or ward, out of which rises the majestic circular *Donjon*, the prominent feature of the building—fit emblem of the proud barons that built and held it—whose boastful motto was,—

“Roi je ne suis,  
Prince, ni Comte aussi,  
Je suis le Sire de Coucy.”

Time has made little impression on it, and even the earthquake's shock, though it has cleft its walls vertically from top to bottom in 1692, leaving the cracks still perceptible, has not altered its symmetry, nor caused it to

swerve out of the perpendicular. It is 187 ft. high and 325 ft. in circumference; and its walls, massive in proportion, are 34 ft. thick. Except a row of windows surmounting its circlet of machicolations at the top, almost the only external openings are mere loopholes. It was entered by a narrow bridge now removed; over the door is the fragment of a bas-relief, sculptured with the device of the Coucy, a combat between a man and a lion. The interior, divided into 4 stories originally, is now entirely gutted, but around each stage runs an arcade of pointed recesses. On the ground floor to the rt. as you enter, is a well 200 ft. deep, cut in the rock. Beside it was originally a flour-mill and oven. Excepting the topmost story, the halls of the donjon must have been inconveniently dark. Two of the external round towers are furnished with dungeons, whose only entrance was a hole in their roof, like the mouth of a well. Vast casemates ran under the outer walls.

The construction of Coucy Castle dates from the 13th century: its founder was Enguerrand III. de Coucy.

*La Belle Gabrielle* had a house here, which still exists, where she was visited by Henri IV. Her son, the Duc de Vendôme, was born here.

The road to Rheims follows the course of the Vesle, a small stream, upwards through

18 Braine-sur-Vesle.

13 Fismes.

10 Jonchery.

17 RHEIMS.—(*Inn*: Lion d'Or; good; fronting the Cathedral.) “This city (39,185 inhab.), so inseparably connected with the history of the Frankish monarchy, retains many vestiges of the Roman domination. The 4 gates of the city were called respectively the *Porta Martis*, *Porta Cereris*, *Porta Veneris*, and *Porta Bacchi*; the first two still preserve their appellations. The ancient

*Porta Martis* (for there is a modern one beside it) is a splendid triumphal arch, recently restored. The fragments of the Corinthian columns are most delicately fluted, and acquire additional grace from the Gothic towers and rough walls around them. This noble relic has undergone strange vicissitudes. It was employed as the city gate until 1554, when earthworks were raised against it, and the adjoining gate opened. It was uncovered in 1595, but afterwards walled over again. In 1677 it was uncovered, but the apertures were walled. M. Guizot's commission brought it to its present state.

"*The Cathedral*, built 1241, is one of the most sumptuous Gothic edifices in France. It is, perhaps, the finest shrine of masonry N. of the Alps (for Milan must be reckoned as the finest in the world); and highly as the expectations of the stranger may have been raised, they will not be disappointed. The building, as it now stands, was the work of Robert de Coucy, begun 1212. The towers are unfinished; they were to have been crowned by open-work spires, such as did exist in the now demolished church of St. Nicaise; and by their absence the elevation loses much of its completeness. The great merit of Rheims arises from the unity of the conception. Completely as the portal is covered and filled with ornaments, not one can be considered as an afterthought. Having massed the whole design, the architect then worked out the details, without interfering with the general effect. Many of the 600 statues on the portal are colossal, and generally elegant, both in design and workmanship; those in the transepts are not so good. The rose windows in the W. front, of which there are two, one above and one within the vast portal, are filled with the most brilliant painted glass. The gemmed windows of Aladdin's palace could hardly have been more splendid. Size of the building: its length is 466 ft., its height 121. The

architecture of the interior bears a near resemblance, in the main outlines, to Westminster Abbey, excepting that it is bolder and simpler. It is much less florid and decorated than the exterior, and this has sometimes been considered as a defect; but it is evident that the architect calculated upon the gloom produced by the painted glass. The W. wall is ornamented with tiers of statues, placed, not in arches, but in deep cells, so that each figure is brought out by a back-ground of shade. Almost all the monuments have been swept away; but the sarcophagus of Jovinus, prefect of Rheims, is here, brought from the Abbey of *St. Nicaise*—a curious national monument. It is composed of a single block of pure white marble, about 9 ft. in length and 4 in height. Jovinus is represented in fine bas-relief, on horseback, having just broken his spear in the neck of a lion, which was leaping on a man. Many figures surround Jovinus; some, as well as himself, apparently portraits, beautiful in countenance, and perfectly made out in dress and accoutrements. A dead boar and other animals are in the foreground. The figures are about half the size of life; and on the sides of the tomb, shaped like an altar, the story is continued in very low relief. Much learned controversy has been excited on the subject of the bas-reliefs. Some antiquarians are of opinion that they refer (though *how* it would be difficult to conjecture) to the defeat of the *Alemanni* (A.D. 367) by this consular general. Jovinus was a Christian; but there is no token of his faith upon this very curious monument. Amongst the curiosities of the Cathedral, the clock, standing in the N. transept, must not be omitted, inasmuch as it is probably the oldest moving piece of horology in existence. From the style of the Gothic tracery and carvings, it seems to belong to the 15th cent. When it strikes, a door opens, and the effigy of a man looks



out; other smaller figures sally forth and make the round, as in the common Dutch clocks. This, without doubt, was considered in its time as a masterpiece.

“The *Abbey Church of St. Remi* is the burial-place of St. Remigius, the Apostle of the Franks (d. 545). Clovis and Clotilda founded the Church: the monastery owes its origin to Archbishop Turpin, who will be better recollected from the history which passes under his name, so often quoted in romance, than from any other of his deeds. Amongst its treasures was the *Sainte Ampoule*, employed in the coronation of the kings of France, and of which a fragment, said to have been preserved when the rest of the relics were dispersed, was produced at the consecration of Charles X. The original buildings of the Merovingian dynasty have wholly disappeared. As it now stands, the principal portions were erected between 1048 and 1162: the choir is of the latter period, of a fully developed and beautiful Gothic. The front of the S. transept, in the florid or flamboyant style, was built in 1481; the Church, which was extremely injured during the Revolution, has undergone a thorough repair. The bodies of Carloman, Louis d’Outremer, Lothaire, and of 25 archbishops buried in its walls, were torn up, 1793. The tomb of St. Remi, erected by the Cardinal Abbot Robert de Lenoncourt, about 1533, escaped the iconoclasts; and, though not in accordance with the Church, for it is in a Flemish-Italian style, is grand from its size and sumptuousness. It was reconstructed by a private individual in 1803. It is ornamented with 12 statues, as large as life, of the 12 peers of France, to whom Turpin gave so much chivalrous celebrity: six are the prelates of Rheims, Laon, Langres, Beauvais, Châlons, Noyon; six lay peers, the Dukes of Burgundy, Normandy, and Aquitaine, the Counts of Flanders, Champagne, and Toulouse: the figures are of

*France*.

white marble, finely sculptured, but in the rather theatrical and exaggerated taste of the time.

“Many of the streets of Rheims will remind the traveller of an old English town. In these the houses are low, usually of one story. The smart new portions of the town, in which great improvements are making, are of the usual French character” (*F. P.*); yet, on the whole, the stranger who has heard Rheims described as one of the oldest towns in France will be surprised to find that it has so very little appearance of antiquity. A few examples of picturesque street-architecture remain: in the *Rue du Tambour* is the hotel of the Comtes de Champagne; in the *Marché au Blé*, a house decorated externally with rich and well-preserved oak carving. The inn called *Maison Rouge*, near the Cathedral, is interesting as being the same (or occupying the same site as that) in which Jeanne d’Arc was lodged at the coronation of Charles VII., though it then bore the sign of L’Ane Rayé (*Zebra*). In the *Rue de Cérés* is the house in which Colbert, the enlightened minister of Louis XIV., was born, 1619; his father is supposed to have been a draper, and he to have served as a shopman and traveller. The Abbé Pluche, author of the ‘*Spectacle de la Nature*,’ was also a native of Rheims. Mr. Pitt spent some months here in 1786 with his friend Wilberforce, in order to learn French. Drouet, Comte d’Erlon, is buried in the *Cemetery*; his sword is at the foot of the pedestal bearing his bust.

The ramparts and fosse have been planted and converted into agreeable *public walks* surrounding the town. The promenade is large and well laid out. The *Café Courtois* is handsomely fitted up. *Diligences* to Paris in 15 or 16 hours.

Rheims is the metropolitan see of France, and one of the nuclei of the civilisation of that country; and was the place of *coronation* of the

French kings from the time of Philippe Auguste to that of Charles X., with the two exceptions of Henri IV. and Louis XVIII. It was selected for that distinction, probably, as the place of deposit of the *Sainte Ampoule*, or holy flask of oil, brought by a dove from Heaven to St. Rémy as he was about to baptise Clovis (496). The persuasion of Clothilda, his queen, and a vow made before the decisive battle of Zulpich, had induced the Frankish conqueror to receive the Christian rite from the hands of the bishop; who, as the new convert knelt before him, received him as a member of the church with these haughty words:—"Mitis depone colla Sicamber; incende quod adorâsti, et adora quod incendisti." The story of the Ampoule, however, is said to have been an invention of the Bishop Hincmar, 360 years after Clovis; it is certain that no contemporary records make mention of it. After having been publicly smashed to pieces by a sansculotte named Ruhl, in 1793, it most unaccountably reappeared at the coronation of Charles X.

No celebration of the august ceremony of the "Sacre" in that imposing and well-proportioned pile, the Cathedral, can have exceeded in interest that of Charles VII., the result of the enthusiasm of the Maid of Orleans. "The people looked on with wonder and with awe. Thus had really come to pass the fantastic visions that floated before the eyes of the poor shepherd-girl of Domrémy! Thus did she perform her two-fold promise to the king within three months from the day when she first appeared in arms at Blois. During the coronation of her sovereign—so long the aim of her thoughts and prayers, and reserved to be at length achieved by her own prowess—the Maid stood before the high altar by the side of the king, with her banner unfurled in her hand. 'It had shared the danger,' she answered; 'it had a right to share the glory.'

"The holy rites having been performed, the Maid knelt down before the newly-crowned monarch, her eyes streaming with tears. 'Gentle King,' she said, 'now is fulfilled the pleasure of God, who willed that you should come to Rheims and be anointed, showing that you are the true king, and he to whom the kingdom should belong.' She now regarded her mission as accomplished, and her inspiration as fled. 'I wish,' she said, 'that the gentle king should allow me to return towards my father and mother, keep my flocks and herds, as before, and do all things as I was wont to do.'"—*Quarterly Review*.

In the campaign of 1814 Rheims was surprised and taken by a Russian force under St. Priest, the French garrison being quite inadequate, from their small numbers, to defend the walls; but Napoleon did not allow the Russians to keep it many hours. Hurrying to the spot with an army broken by the defeat of Laon, he nevertheless completely took by surprise St. Priest, who was mortally wounded while endeavouring to stem the torrent and secure his retreat. This was almost the last military success which Buonaparte gained.

The situation of Rheims is agreeable, on the rt. bank of the Vesle, surrounded by slopes covered with vineyards.

CHAMPAGNE WINES.—"The city is thriving: the chief article of commerce is the *wine*, which, in spite of all the powers of revolutionary geography, will perpetually keep the ancient name of the province of *Champagne* in remembrance. These *wines* are divided into 'Vins de la Rivière,' and the 'Vins de la Montagne;' the former being for the most part white, and the latter red. The best *river wines*, strictly so called, are obtained from the vineyards situate in the valleys and on the sides of the hills that border the Marne at Aï, Hautvilliers, Epernay, Dizy, Avenay, &c., and occupy a tract of country of about 5 leagues in extent; but the estate of



Cumières, though in the midst of these vineyards, lying under the same line and with the same exposure, yields red wines only, and of a superior quality to the others that are grown in the same neighbourhood. In general, it may be observed, that the vineyards on the banks of the Marne supply the choicest wines. (See pp. 567, 568.)

The road to Mézières lies through an uninteresting portion of that part of Champagne called "La Pouilleuse," passing

17 Isle, beyond which it enters the Dépt. of the Ardennes, and reaches

20 Rethel, a town of 6800 inhab., prettily seated on the Aisne, whose branches divide it into several parts.

A hilly country succeeds; once forest, now cleared for the most part, and bare and sad of aspect in consequence.

12 Saulces au Bois.

10 Launay.

19 Mézières (*Inn*: H. du Palais Royal; very good), one of Vauban's strong fortresses, and at the same time the chef-lieu of the Dépt. des Ardennes, is seated on the rt. bank of the Meuse, on the isthmus of a promontory formed by the river, which washes its walls on two sides, and separates it from Charleville. It has 4083 inhab.

The *parish Church* is a very fine flamboyant Gothic edifice, of the 16th cent., in which the marriage of Charles IX. with Isabelle d'Autriche was solemnised 1570. Among the good points about it are its lateral portals, in the style of the latter part of the 15th century, and 2 curious bas-reliefs in the choir. There are some bits of painted glass inserted in blank windows, and over the N. aisle is a bomb-shell, one of those thrown by the Allies when they invested the place after the battle of Waterloo, which has remained sticking in the roof ever since the town capitulated.

A more glorious event in the annals of Mézières was the resistance

which it made to the Spanish army of Charles V., 40,000 strong, in 1521. The Chevalier Bayard gallantly took the command of the town at a time when Francis I. had proposed to blow it up and abandon it, as too weak to offer any resistance, and to lay waste the country around, as the only means of stopping the enemy. With a force of only 2000 men Bayard endured a siege of 6 weeks, in the course of which *bombs* were for the first time used, and were most plentifully showered upon the garrison, but with little effect. The *banner of Bayard* is said to be still preserved in the H. de Ville.

Charleville, a town of 7773 inhab., is only a mile distant from Mézières, and is connected with it by an avenue and suspension-bridge. It has become a thriving place since it ceased to be a fortress at the end of the 17th century, and manufactures nails, hardware, fire-arms, &c.

The *Meuse* makes a wide sweep around, and then dives into a narrow trench or *defile* cut by it in the slate rocks, which stretch with the most contorted windings nearly as far as Givet. The depths into which the Meuse enters are a narrow and deep chasm in the chain of the Ardennes; the breach is in places no wider than the river itself, its sides often vertical, sometimes 130 ft. high. It expands suddenly at Fumay, a town most picturesquely planted on a holm on the banks of the river, overhung by precipitous rocks, called *Les Dames de la Meuse*, 130 ft. high, and overlooked by the picturesque ruins of the castle of Hierches. Slate is the chief product of this desolate district; it is sent down the Meuse to Holland from Fumay, where there are extensive quarries. In 1623 slates were sent from the Ardennes to roof the church of St. James of Compostella in Spain.

20 m. N. of Mézières is Rocroy, a small fortress, in front of which *le Grand Condé* gained the greatest of

his victories over the Spaniards, at the age of 22 years. The army opposed to him were veteran bands of Walloons, Spaniards, and Italians, commanded by a mature and experienced general; and it was only after thrice heading the charge against this serried infantry, that Condé at length broke their array. The Spanish general Fuentes, who conducted the battle from a litter, being wounded, was found among the dead. The battle-field is on a plain, at that time (May 19, 1643) surrounded by marshes and dense forests on all sides, but now much changed by clearing and drainage.

The road to Sedan lies through a pretty country.

9 Flize. The Meuse is crossed on quitting Mézières, and again twice before entering

13 Sedan. — *Inns*: Croix d'Or: good; — H. de Turenne (?); — Croix d'Argent: nasty. Sedan, situated on the rt. bank of the Meuse, is both an important frontier fortress, commanding the entrance from Luxembourg into France, and a prosperous manufacturing town of 13,719 inhab., but is a dirty, disagreeable place. It is celebrated for the *fine cloths*, especially the black, which are made here, and not less than 11,000 or 12,000 persons are employed in this branch of industry.

Down to the time of Louis XIII. it was capital of a principality belonging to the family of La Tour d'Auvergne, Ducs de Bouillon; but in 1642 the Duc de B., having engaged in the conspiracy of Cinq-Mars against Richelieu, was too happy to give it up to save his head. Marshal Turenne was born here 1611, in a small pavilion attached to the *château*, which was razed to the ground at the Revolution, and no souvenir of him remains, save a black stone to mark the spot where it stood. An ugly statue of him has been set up in the Place. The *château* itself is also demolished. In fact, Sedan has no

thing of interest to detain the traveller.

At Bazeilles, a neighbouring village, is, or was, the *château* where Turenne was nursed, and an *avenue* planted by him. At this place the Comte de Soissons defeated the army of Richelieu 1641, but perished on the field of battle.

## ROUTE 180.

RHEIMS TO LUXEMBOURG, BY STENAY AND LONGWY.

RHEIMS, in R. 178.

17 Isle (Marne), in R. 178.

23 Pauvres.

16 Vouziers (Ardennes), a town of 2000 inhab.; on the l. bank of the Aisne.

13 Boux aux Bois.

9 Buzaney, a bourg of less than 1000 inhab., retaining portions of its old fortifications, and an entrance gate called Porte St. Germaine. On the site of the Citadel is the *Château de la Cour*, anciently the habitation of St. Remy, Bishop of Rheims. To the N. of the village, and in the upper part of it, stands the singular edifice called *Mahomet*, said to have been a mosque built by Pierre d'Angluré, who, having followed St. Louis to the Holy wars, was taken prisoner by the Saracens, and released after a long captivity, on giving his word of honour that he would himself bring back his ransom. He accordingly sold part of his lands to raise the money, and returned, after many adventures, in the course of which he lost an eye, to the Sultan, who was so pleased with his honourable conduct that he restored the gold to the Christian knight, on the condition that he should build a mosque on his return home. The building is constructed of large stones, and the door on the east was originally the only opening; the windows have been broken out.

The Dépt. of the Meuse is entered shortly before reaching



21 Stenay, an ancient town of 3140 inhab., once an important frontier fortress, but after its capture by Louis XIV. its fortifications were razed, 1654. It belonged to the family of Condé down to 1791, and the Vicomte de Turenne, when in rebellion against the Court and Mazarin, threw himself into it, and was joined by the Duchesse de Longueville, so celebrated in the wars of the Fronde. They here signed a treaty of alliance with Spain.

The country around is flat, and subject to inundations from the Meuse.

15 Montmédy is a fourth-class fortress, consisting of an upper town surrounded by 8 bastions, and a lower one badly fortified. It stands on the Chiers, a tributary of the Meuse, and was taken from the Spaniards 1657. 3169 inhabitants.

28 Longuyon.

18 Longwy (*Inn*: Croix d'Or; very good, and the only tolerable inn on the road). This is another fortress; the works of the upper town were laid out by Vauban, 1682, and Louis XIV. styled it the Iron Gate of France, from its important military position, at an angle of the French territory projecting into Luxembourg. It was taken by the Duke of Brunswick and the Prussians, 1792, and again 1815, when, after a severe bombardment, and a noble resistance on the part of the French General Ducos and a small garrison, it surrendered on honourable terms to the Allies commanded by the Prince of Hesse-Homburg.

Mercy, the Bavarian General, the antagonist of le Grand Condé at Fribourg and Nordlingen, where he fell nobly on the battle-field, 1645, was born here.

We cross the French frontier and enter the Duchy of Luxembourg before reaching

6 Auhange.

3½ posts, *Luxembourg*. See *HANDBOOK FOR NORTH GERMANY*.

## ROUTE 181.

NANCY TO TRÈVES, BY METZ AND THIONVILLE —DESCENT OF THE MOSELLE.

A small steamer navigates the Moselle daily between Nancy (Pont-à-Mousson), Metz, and Trèves: it takes 15 hours to go from Trèves to Metz.

The Moselle flows at a distance of about 7 m. from Nancy, and is crossed by our road.

17 Belleville.

11 Pont-à-Mousson (*Inn*: H. d'Angleterre), a town of 7218 inhab., on the Moselle, here crossed by a bridge. A fine Gothic church, in the style of the latter part of the 13th cent., and in the square or Place, which is surrounded by arcades, an ancient mansion curiously decorated externally with sculptures, called *Maison des 7 Péchés Capitaux*, deserve notice. The buildings of the ancient Abbaye de St. Marie are converted into a Séminaire.

This is the birth-place of Marshal Duroc, the friend of Napoleon, in whose arms he died mortally wounded at the battle of Bautzen, 1813. The high road here crosses the Moselle to its right bank.

11 La Lobe.

The ruined Roman aqueduct, described p. 473, is passed at Jouey aux Arches, 5 or 6 m. before reaching

18 METZ, in R. 175.

17 Mondelange. The correction of the course of the Moselle below Metz has been carried to such an extent, that it resembles a canal running between dykes. In Prussia little has been done: in many places the current is so strong that the steamer, in ascending, stems the rapids only by the aid of a towing-horse.

The small town of Richemont stands prettily on the l. bank of the Moselle, at the confluence of the Orne.

11 Thionville (Germ. Diedenhofen) (*Inns*: H. du Luxembourg; — du Commerce; — Lion d'Or), a town of

5800 inhab., a fortress of third class, constructed by Vauban, consisting of 11 bastions covered by some external works, and by a fort on the rt. bank of the Moselle. It contains 5600 inhab.; many of its houses bear the date of the 16th century.

It was taken from the Spaniards, 1558, by the Duc de Guise, but was restored to Philip II. by the treaty of Cateau Cambresis. The Grand Condé, while yet Duc d'Enghien, captured it, 1643, after 3 months of siege and 40 days of open trenches. The Prussian custom-house on the river is near Serl, the French at . The *cuisines de Charlemagne* are not older than the 16th cent. The *Tour aux Puces* is now Magasin d'Artillerie.

17 Sierck, the last town in France, is agreeably situated on the rt. bank of the Moselle, between the Stromberg and the rocks of the valley of Montenach, surmounted at a considerable height by an old *Castle* in ruins, commanding the course of the Moselle: it is a fine point of view.

A little below Sierck is the camp of Kunsberg, thrown up by Vauban, a series of fortified lines, in which Mar-

shal Villars arrested the march of Marlborough.

26 Sarrebourg (3 Pruss. posts).

TRÈVES. HAND-BOOK FOR NORTH GERMANY.

### ROUTE 182.

METZ TO LUXEMBOURG, OR ARLON, BY LONGWY.

The Inn at Longwy is the best and almost the only good one on these lines.

a. to Metz.

17 Mondelange.

11 Thionville (p. 582).

19 (or 2¼ posts) Frisange in Luxembourg.

1¾ posts, LUXEMBOURG. HAND-BOOK FOR N. GERMANY.

b. to Arlon.

17 Mondelange.

20 Fontoy.

9 Aumetz.

20 Longwy (*Inn*: tolerable), a fortress; the upper town was fortified by Louis XIV., after the treaty of Nymegen (p. 581).

Arlon. HAND-BOOK FOR N. GERMANY.



## SECTION X.

## ILE DE FRANCE.—FLANDRES.—ARTOIS.

ROUTE	PAGE	ROUTE	PAGE
183 Paris to Valenciennes, by <i>St. Quentin</i> and <i>Cambrai</i> .	583	Rheims, Châlons-sur-Marne, and Troyes . . . . .	591
184 <i>Chemin de Fer du Nord</i> . Paris to Brussels, by Amiens, <i>Arras</i> , <i>Douai</i> , and Valen- ciennes . . . . .	587	188 Calais to Lille and Tournay, on the way to Brussels, by <i>Cassel</i> . . . . .	594
185 Paris to Lille, by <i>Peronne</i> and Arras . . . . .	589	189 Calais to <i>Dunkerque</i> and Courtrai, by <i>Gravelines</i> and <i>Bergues</i> . . . . .	595
186 Douai to <i>Lille</i> and Dunkirk —RAILWAY . . . . .	590	190 Calais to Arras, by <i>Haze- brouck</i> —RAILWAY in pro- gress . . . . .	597
187 Calais to Dijon, by Douai, Cambrai, <i>St. Quentin</i> , <i>Laon</i> ,			

## ROUTE 183.

PARIS TO VALENCIENNES, BY ST. QUEN-  
TIN AND CAMBRAI.

210 kilom. = 130 Eng. m.

The *Chemin de Fer du Nord* (Routes 3 and 184) has nearly with-  
drawn the traffic from this road.

The road quits Paris by the Fau-  
bourg St. Martin.

11 Le Bourget.

13 Louvres.

10 La Chapelle en Serval. On the  
l. extends the Forest of Chantilly  
(Route 1, p. 5).

9 Senlis (*Inn*: Grand Cerf), a town  
of 5000 inhab., consists of an old  
town still surrounded by ramparts  
and boulevards, among which are  
traces of Roman constructions, and  
of 3 modern suburbs, in which are  
cotton-mills and other manufactories.  
The *Porte de Meaux*, now in ruins,  
was a fort in itself, approached by  
a bridge; the *Porte Bellon* is also  
curious. In the interior of the Cité  
are remains of the *Castle*, dating from  
the time of St. Louis, in which may  
be distinguished the chapel, the hall  
bearing the initials of Henri II. and

Diana of Poitiers, and the chamber  
of Louis XIII.

The *Cathedral* is composed of por-  
tions in different styles. The lower  
part of the front and side aisles date  
from the time of Louis le Jeune.  
The lateral portals, the façades of the  
transepts, which are very rich, are of  
the age of Francis I. and Louis XII.  
It is surmounted by a fine tower and  
spire 211 ft. high.

Several other desecrated churches  
merit notice, as the *Abbey of St. Vin-  
cent*, well preserved; the *Church of  
St. Pierre*, now a hay-store, with a  
porch rich in sculpture; the Chapel  
of the *Hôtel Dieu*; and the nave of  
*St. Frambourg*.

The ruins of the *Abbey of Chaalis*,  
and the Chapelle du Roi, near Senlis,  
may deserve a visit from those who  
take an interest in Gothic remains.

Here the road to Peronne and  
Arras (R. 185) branches off to the l.

12 Villeneuve-sur-Verberie. The  
river Oise runs parallel with our road  
at some distance on the l.

12 La Croix St. Ouen.

8 Compiègne (*Inns*: La Cloche  
(?);—le Lion), a mean town of 8895

inhab., on the l. bank of the Oise, a little below its junction with the Aisne. The Romans gave it the name *Compendium*, because their military stores and ammunition of all sorts were kept here. It has been a favourite residence of the French monarchs, with few exceptions, from the time of Clovis. They often repaired hither to enjoy the pleasures of the chase in its very extensive park and neighbouring forest.

The *Royal Palace*, as it at present stands, is a building of the time of Louis XV., erected from designs of Gabriel. Napoleon added a splendid hall or gallery: it was here that he received his bride Marie Louise. Charles X. spent much of his time here, in his favourite sport of shooting. The interior of the palace is elegantly furnished. The *Gardens* are prettily laid out, and a sort of arbour, or berceau walk, 4800 ft. long, leads from them to the forest. The façade towards the forest is very grand.

The *Hôtel de Ville* is a curious Gothic edifice, surmounted by a beffroi and turrets.

The *Ch. of St. André* is of the pure Gothic of the 13th centy., except the aisles and side chapels, which date from the end of the 15th. In the *Ch. of St. Anne* is a curious marble font.

The *Forest* occupies an area of nearly 30,000 acres, and contains some fine oak timber.

A camp for military manœuvres is sometimes formed here in the autumn.

Though the fortifications are now entirely razed, Compiègne was once a strong place; and it was before its walls that the dauntless Maid of Orleans was made a prisoner and entered on a captivity which ended only in her miserable and cruel death, 1430. She had thrown herself into the town, then besieged by the Duke of Burgundy, and had courageously headed the garrison in a sally across the bridge, when, in retreating last of the rear-guard, she found the town-gate partly closed,

and choked by the throng eager to escape from the enemy, who closely pursued them. In consequence of this, while endeavouring to protect the fugitives, and before she could obtain an entrance, she was seized by an archer of Picardy, and transferred to John of Luxembourg, from whom she was purchased by the English. The spot of her capture, near the old gateway de Vieux Pont, is still pointed out, although the old bridge, close to which it occurred, has been removed, and replaced by another higher up the stream.

*Steamers* navigate the Seine and Oise from St. Germain up to this town.

The road ascends the valley of the Oise on its rt. bank, by

14 Ribecourt, to

10 Noyon (*Inn*: H. des Chevalets), a very ancient town, on a small stream, the Vorse, about a mile from the right side of the Oise, with 6250 inhab., remarkable as the birth-place of the reformer, John Calvin, son of a cooper, b. 1609. The house still exists at the corner of the Rue Fromenteresse. Noyon was besieged by Julius Cæsar, who calls it *Noviodunum Belgarum*. Charlemagne resided here; and Hugues Capet was elected by his vassals King of France at this place in 987.

The *Cathedral* is of interest to the antiquary and architect. It is a fine Romanesque edifice, begun in the 12th centy., and completed on a uniform plan early in the 13th. The transepts and nave have semicircular terminations. The lower arches and the 9 side-chapels outside the choir are Round; the triforium gallery running above them has Pointed arches. This church presents an interesting example of the transition from the Round to the Pointed style.

It is a hilly stage to

9 Guiscard.

The road crosses the ridge dividing the basin of the Seine from that of the Somme, and enters the Dépt. of the Somme before reaching



10 Ham (*Inns*: H. de France;—Cornet d'Or), a small town on the Somme, surrounded by marshes, with 1663 inhab. Its *Citadel* has been much strengthened by modern works, so as to be now a fortress of importance: it serves as a *state prison*, for which purpose it is well fitted. The central tower or *donjon* is 100 ft. high, 100 ft. wide, and the walls are of masonry, 36 ft. thick. It was built 1470 by the Comte de St. Pol, afterwards beheaded by Louis XI., and bears over the gate his motto, "Mon Mieux." The Prince de Polignac, and 3 other ministers of Charles X., who signed the fatal *Ordonnances* of July 25, 1830, were confined here, and Prince Louis Napoleon some time expiated his folly in its dungeons. Strangers are not admitted.

The *Church* is said to be an interesting building, and contains some curious bas-reliefs.

General Foy was born here.

Between Ham and a village called Nesle, Henry V. crossed the Somme, by a ford which the French had left unguarded, with his brave army, which, 2 days after, fought and gained the battle of Azincour, 1415. (See p. 4.)

12 Roupy.

9 ST. QUENTIN (*Inn*: H. d'Angleterre (?), a flourishing manufacturing town, whose population has more than doubled in 25 years, and now amounts to 25,000. It was the ancient capital of the Vermandois, the "Augusta Viromanduorum" of the Romans, and is situated on the Somme (Samarobriva of Cæsar).

The principal *Church*, once collegiate, is less known than it ought to be. It is one of the finest, boldest, and purest Gothic buildings in this part of Belgic Gaul. The vault of the roof is 127 ft. high. It contains some good painted glass. The King of France was premier canon of this church, and the chapter possessed privileges over the municipal community which kept up constant feuds between *town* and *gown*, and this continued, more

or less, until chapter and community sustained a simultaneous annihilation. The *Hôtel de Ville* is a very fine specimen of these structures, in what may be termed the Flemish-Gothic style; and this and many other portions of the town afford good subjects for the pencil. It probably dates from the 15th century.

The wharfs on the banks of the Somme bear testimony to the increasing consumption of coal in this district. It is brought from the vicinity of Valenciennes, Condé, and Mons, by the Canal de St. Quentin, and is of an inferior quality, but it is extensively employed in the various manufactures which are springing up, and which may hereafter become formidable rivals to those of England.

St. Quentin is the centre of the manufacture of *Linen Cloths* (*toile de fil*), muslins and gauzes (*battistes et gazes*), which spread over the country for 30 m. around, as far as Cambrai, Bapaume, and Peronne. Flanders and Picardy furnish the *flax*: the finest quality comes from Marchiennes; that of St. Quentin is coarse. The weavers are obliged to work below ground and in cellars, by the moist and even temperature of which they are alone enabled to prevent the fine thread breaking. It has been calculated that 100,000 persons are employed in weaving and spinning flax. *Cotton spinning* and weaving also employ a great many hands.

Under the walls of St. Quentin was fought (July 28, 1557) the celebrated *battle* between the Spanish troops, commanded by Emanuel Philibert, Duke of Savoy, and Ferdinand Gonzaga, and the French, headed by Coligny and the Connétable Anne de Montmorency, in which the latter were entirely routed. Queen Mary of England aided her husband Philip II. on this occasion with a considerable levy of English troops, under the command of the Earl of Pembroke, who contributed not a little to the victory. This defeat left Paris unprotected; and, had the victors

profited by their advantage, France and Spain might perhaps have been united into one vast monarchy. But Philip, who joined the army after the battle, hesitated, and occupied himself in the siege of the town, which, just capable of defence, might with safety have been left in the occupation of the French garrison. Commanded by Coligny and Jarnac, the town sustained eleven assaults before it was taken. The inhabitants were treated with great cruelty, the Spaniards revenging themselves upon the burghesses, who had defended the town-walls with great valour. Even the clergy were not spared, and they all quitted the town, and did not return until St. Quentin was restored to France by the treaty of Cateau Cambresis, 1559.

*Diligences* daily to Laon and Rheims (R. 187), to Avesnes.

To Amiens, on the Rail to Paris, and to Brussels.

The *Canal of St. Quentin* is of great importance to the town: it connects the basin of the Somme with that of the Scheldt, and is carried through the intervening hills by tunnels,—one at Tronquoi,  $\frac{1}{2}$  m. long, another at Riqueval,  $3\frac{3}{4}$  m. long, cut through the solid rock: it is 20 ft. high, and 20 ft. broad; it admits only 1 barge to pass at a time, towed by men. By means of this canal a communication is opened between the river Scheldt and the extreme eastern departments of France and the Atlantic, through the rivers Somme, Seine, and Loire; it was completed by Napoleon in 1810; it enters the Oise at Chauny. It runs parallel with our road as far as Cambrai.

14 Bellicourt. The road is hilly to Cambrai. Near the little village of Castelet, traversed by the road, the Scheldt (l'Escaut) rises from behind the gardens of Mont St. Martin; it issues from an arch in the side of a hill.

14 Bonavy.

11 *Cambrai* (*Inn*: H. de l'Europe, formerly au Grand Canard; good) is

an industrious and considerable town and fortress on the Scheldt, with 19,000 inhab., principally remarkable for the fine muslin manufactured here, named by the English, after the place where it is made, *Cambric*. The Revolution stripped it of all its principal ornaments. It was the episcopal see of the venerable Fénélon, author of *Télémaque*, who was buried here. The sacrilegious hands of the revolutionists, in 1793, tore his body from the peaceful grave, and melted the lead of his coffin into bullets. The beautiful *Cathedral* was utterly razed to the ground at the same time. By way of making some atonement for the outrage, a handsome *monument* was erected to his memory in 1825, in the present cathedral, a modern church of indifferent architecture. His statue, "half rising from an altar tomb, apparently ready to obey the sound of the last trumpet, is not ill conceived nor executed." The three bas-reliefs represent memorable events of his life—the education of the Duke of Burgundy, the Archbishop attending the wounded soldier after the battle of Malplaquet, and the cow restored to the peasant. His remains are deposited beneath the monument, which is the work of *David*, the sculptor. An ancient Greek painting of the Virgin, attributed, as is usual with pictures of this class, to St. Luke, is preserved in the cathedral, and is yet carried in procession.

Of the 12 churches which existed before the Revolution, 2 alone remain. The only other public building of consequence is the *Hôtel de Ville*, of modern construction. Cambrai is called Camaracum in the Itinerary of Antonine.

Cambrai is celebrated in the annals of diplomacy for the famous *League* against the republic of Venice concocted here in 1508: a treaty of peace between Charles V. and Francis I. was also signed in 1529. The citadel was raised by Charles V. Cambrai was taken by a detachment of the



British army under Sir Charles Colville, June 24, 1815. It is the native place of the historian Monstrelet, and of General Dumouriez (1739).

*Diligences* daily to Douai and Arras; on the Northern Railway.

The *Canal of St. Quentin* begins at Cambrai, where it issues out of the Scheldt: it joins the Oise at Chauny. It is of the highest utility in promoting the industry and prosperity of the district through which it passes.

15 m. E. of Cambrai lies *Le Cateau Cambresis*, famous for the *treaty* signed there (1595) between Philip II. and Henri II. It was also the birthplace of Marshal Mortier, Duke of Treviso, who perished in Paris by Fieschi's assassination-machine. Cateau was the head-quarters of the Duke of Wellington when he entered France in 1815; hence he issued his order to his troops to abstain from pillage, and to maintain the strictest discipline.

15 Bouchain, a small second-class fortress on the Scheldt.

On quitting Bouchain the road passes on the l. *Denain*, the battlefield where Marshal Villars defeated and made prisoner Lord Albemarle, commander of the allied forces, posted in a strong position, 1712. An Obelisk was erected on the field to commemorate the success, with these lines of Voltaire:—

“Regardez dans Denain l'audacieux Villars  
Disputant le tonnerre à l'aigle des Césars.”

The innermost douane to be passed on entering France is at Douchy. There is a railroad from Denain to Anzin by St. Waast, 16 kilom.

On approaching Valenciennes the road passes the great coal-field of the Dépt. du Nord, the most important in France, discovered about 1736, in a portion of Hainault which was not ceded to France until 1678. It is a prolongation of the Belgian coal-field. The chief collieries are at Anzin, Denain, Louches, Fresnes, Vieux Condé, &c.; 40 mines are worked in this district; some of them are 1640 ft. deep. Paris is supplied with a

large quantity of coal from hence by the canal of St. Quentin, and the fuel derived from hence imparts life to the numerous and varied manufactures scattered over the industrious Dépt. du Nord, including 3000 manufactories around the walls of Valenciennes, within a circle of 10 or 15 m.

## ROUTE 184.

PARIS TO BRUSSELS.—CHEMIN DE FER DU NORD, BY AMIENS, ARRAS, DOUAL, AND VALENCIENNES.

370 kilom. = about 228 Eng. m.

5 Trains daily to Douai in  $8\frac{1}{4}$  h.

2 Trains daily to Brussels in  $12\frac{1}{4}$  h.

This Railway is described in Route 3 as far as

147 AMIENS Stat.

Carbie St.

Albert St.

Achiet St.

Boileux St.

Arras Station.

*Arras.* (*Inns:* H. de l'Europe; dear;—Petit St. Paul; the Diligence-house, and well recommended;—the Post-house is at a considerable distance from both.) Arras is a large and fine city, formerly the capital of the Pays d'Artois, and now of the Dépt. du Pas de Calais; population 23,485. It is a fortress of third class, seated on the Scarpe, and the passport regulations are strictly enforced. The entrance, between and amongst the lofty ramparts, shaded by loftier trees, is grand and imposing. In the interior it has quite the character of a Flemish town, especially in its *Grande Place*, surrounded by gable-faced houses, terminating in scallops and scroll-work supported on open arcades. On one side of it stands the *Hôtel de Ville*, a rather pleasing structure in the latest Gothic, resembling our Elizabethan, built 1510, surmounted by a *Beffroi*. The *Revolution* raged here with exceeding violence, a matter of little surprise when it is remembered that Arras was the birthplace of the monsters *Max*.

*Robespierre* and his brother. They were the sons of an advocate, who abandoned them in their childhood, and went to America, and they were educated at the College here, and maintained by the charity of some of the clergy of St. Waast. It is said that in one street all the inhabitants were guillotined, whence it was called the "Rue sans têtes." One effect of this fury was the desecration of the greater portion of the religious edifices. The Cathedral fell like the rest, and only a fragment of it remains near the Place. The *present Cathedral*, though in the form of a Latin cross, with flying buttresses, is a pure Italian edifice. Its interior, supported on classic columns, with side aisles and transepts, is plain but handsome.

Damiens, who attempted to assassinate Louis XV., was a native of Arras.

The *cotton manufacture* is carried on to a considerable extent here.

From Fampoux, on the outskirts of Arras, a railway runs to Hazebrouck, whence it will branch to Calais and Dunkirk.

*Diligences* to Calais, Dunkerque, Cambrai, Douai, &c.

Roux St.

Vitry St.

DOUAI Station.

*Douai* (*Inns*: H. de Flandres;—du Commerce) is a town of 17,501 inhab., surrounded by old fortifications, seated on the Scarpe, defended by a detached fort, about  $1\frac{1}{2}$  m. distant on the l. bank. It is the least *thriving* place in the Dépt. du Nord, and appears to be falling off in population, and, though it covers more ground than Lille, does not contain half as many inhab. Like the Flemish towns it has a picturesque *Beffroi* in its market-place, rising above the Gothic *H. de Ville*, built at the end of the 15th century. It possesses a *library* of 30,000 vols., a collection of *pictures*, and contains one of the 3 *Royal cannon foundries* in France.

From the 15th cent. the college or seminary of Douai, founded by an Englishman, Cardinal Allen, has edu-

cated *Roman Catholic* priests for England and Ireland. O'Connell studied here. There is a considerable trade in flax here.

The sculptor called John of Bologna is supposed to have been born here.

Every year, in the early part of July, a curious procession parades the streets of Douai, consisting of a giant of osier, who is called *Géant Gayant*, dressed in armour, 30 ft. high, attended by his wife and family, of proportionate size; the giant doll is moved by 8 men enclosed within it.

*Diligence* to Cambrai.

Montigny St.

Somain St.

Wallers St.

Raismes St.

*Valenciennes St.*

VALENCIENNES (*Inns*: La Poste; H. des Princes, very good, comfortable, and newly furnished—*J. M.*; Le Canard; La Biche; La Cour de France), a fortress of the second class, with a strong citadel constructed by the engineer Vauban, is a dark and ill-built town, lying on the Scheldt, and has a population of 22,000 souls. In 1793 it was taken by the Allies under the Duke of York and General Abercromby, after a siege of 84 days and a severe bombardment, which destroyed a part of the town: it was yielded back next year. In the grand square, or Place d'Armes, are situated the *Hôtel de Ville*, a fine building, half Gothic half Italian in style, built 1612, and containing 3 pictures by *Rubens* (?), brought from the abbey of St. Amand; the *Beffroi*, 170 ft. high, built 1237, fell 1843, and caused a serious loss of life; the *Theatre*. The *Church of St. Gery* is the principal one.

The celebrated Valenciennes *Lace* is manufactured here, and a considerable quantity of fine cambric. This is the birth-place of Watteau the painter, of Froissart the historian, and of the minister D'Argenson.

On entering France, passports must be delivered up here; and on quitting



the country, they are strictly examined by the police.

The country around Valenciennes offers no picturesque beauty; the rivers are sluggish, and have flat, uninteresting banks.

There is a triple row of French custom-houses on this frontier; and the repeated searches to which the traveller is subjected are often very annoying, and occasion considerable delay.

*Diligences* to Mézières, Sedan, and Strasburg; to Peronne; Landrecies; to Maubeuge and Avesnes.

The Railway from Valenciennes to the Belgian frontier (14 kilom.), and thence to BRUSSELS (11½ posts), is described in the HANDBOOK FOR NORTH GERMANY.

Blanc Misseron St.

Quièvrain St.

Mons St.

BRUSSELS Terminus. See *Handbook* for BELGIUM and NORTH GERMANY.

#### ROUTE 185.

PARIS TO LILLE BY PERONNE AND ARRAS.

220 kilom. = 134 Eng. m.

The Chemin de Fer du Nord (Routes 3—184 and 186) has removed much of the traffic from this road. *Diligences* daily in 24 hours. The road is uninteresting.

The road as far as

43 Senlis will be found in Route 183.

12 Pont St. Maxence is prettily situated on the Oise, and its *Bridge* was built by the architect Peyronnet.

12 Bois de Lihus.

10 Gournay-sur-Aronde.

7 Cuvilly.

7 Conchy les Pots.

11 Roye.—*Inn*: Grand Cerf.

9 Fonches.

7 Marché le Pot.

12 *Peronne* (*Inns*: H. St. Martin; H. d'Angleterre), a fortress on the N. bank of the Somme. It bore the epithet "la Pucelle," because it never

was captured by an enemy down to 1815, when the Duke of Wellington deprived it of its virgin reputation. He thus describes its capture in his Dispatches: "I attacked Peronne with the first division of British Guards, under Major-Gen. Maitland, on the 26th in the afternoon. The troops took the hornwork which covers the suburb on the l. of the Somme by storm, with but small loss, and the town immediately afterwards surrendered, on the condition that the garrison should lay down their arms and be allowed to return to their homes." — *June 26th*, 1815. The number of the inhabitants in the town exceeds 4000.

It was in the *Castle of Peronne* that Charles the Bold detained the crafty Louis XI. his prisoner, in the way so admirably described in *Quentin Durward*, on receiving intelligence of the revolt of the Liègeois, and restored him to liberty only after he had signed conditions most disadvantageous to himself, and known in history as the "treaty of Peronne." The castle is much dilapidated, and a large part is probably not older than the 16th centy., yet there remain many dismal dungeons on the ground-floor. The chamber occupied by Louis is still pointed out in the Tour Herbert, and beside it the miserable cell, on a level with the moat, where Charles the Simple ended his days, a wretched captive. He was buried in the church of St. Farcy, now destroyed. The *Church of St. John*, near the *Beffroi*, or bell-tower, date 1376, is a handsome Gothic edifice, apparently of the 16th centy.; its lythe piers without capitals spread out into multiplied groinings over the roof, and it has a little painted glass. The situation of Peronne is unwholesome, owing to the marshes which surround it. *Omnibus* to Albert, a station on the *Northern Railway*, Route 184.

The road to Cambrai (p. 586) turns off here. That to Arras traverses a flat open country, through

13 Sailly and Bapeume, a dull and dirty fortress, where, however, a good deal of linen and muslin is made.

15 Ervillers.

15 ARRAS, in Route 184.

A few miles beyond Arras a slight ascent is surmounted, and thence a level plain—most fertile and most carefully cultivated, producing vast quantities of beet-root for sugar, and of colza (*Brassica campestris*), a sort of cabbage, which is crushed for oil—extends all the way to Lille.

17 Lens. Here Condé gained a victory over the Spaniards 1678. A little farther, and the canal of the Deule is crossed, connecting Lille with Douai.

12 Carvin.

About 200 windmills are grouped around the walls of Lille in the vicinity of the road to Paris: they are used for grinding rape-seed and other oleaginous grains for oil. There are, however, not less than 600 windmills in this commune, which has lately taken the name of Moulins in consequence. The entrance to the city is by a sort of triumphal arch, *Porte de Paris*, surmounted by a frontispiece in the fashion of a screen propped up behind, filled with the trophies of the glory of Louis XIV. Erected 1682.

19 LILLE, in Route 186.

#### ROUTE 186.

#### DOUAI TO LILLE AND DUNKIRK— RAILWAY.

31 kiloms. of the “*Chemin de Fer du Nord*” (Routes 3 and 184), = 19 Eng. m. from Douai to Lille: 4 trains daily in one hour.

7 Leforest St.

6 Carvin St.

8 Sulin.

*Lille Station.*

LILLE. (Flem. Ryssel.) — *Inns*: H. de l'Europe, good, but very dear—D. C.; de Bellevue; de Commerce.

This city of 63,693 inhab. is im-

portant both as a fortress of the first order for its strength, forming the central point of the defence of France on her N. frontier, and as a populous and industrious seat of manufacture, ranking seventh among the cities of France. It is chef-lieu of the Dépt. du Nord, and was formerly capital of French Flanders. The streams of the Haute and Basse Deule traverse the town, filling its moats and turning the wheels of its mills, and they are connected by a canal, by means of which the country for 1½ m. around the walls can be laid under water.

There are no fine public buildings proportioned to the size and wealth of the city, its monuments have been levelled by bomb-shells, and its objects of interest for the passing traveller, unless he be a military man, are few, as may be judged of by the following enumeration:—

Its *Citadel* is considered a masterpiece of the skill of Vauban, who was governor of it for many years. It is a regular pentagon, furnished with all the accessories which engineering skill can suggest, especially since the siege of 1792, and so strong, because commanded by no point, and capable of isolation by breaking the canal dykes and filling its wide moats, that it is deemed impregnable. A great deal of misery, however, and enormous destruction of property and injury to agriculture, would follow an inundation. The citadel is separated from the town by the *Esplanade*, a wide drilling-ground, which serves also as a public walk, being planted with trees and traversed by the canal. Lille was captured from the Spaniards by Louis XIV. in 1667. At different periods, and under different masters, it has stood 7 distinct sieges; the one most memorable for an Englishman was that by the allied armies of Marlborough and Eugene in 1708, of 3 months' duration, during which the war was not merely waged above ground, but the most bloody combats were fought below the surface be-



tween the miners of the opposite armies, each endeavouring to sap and undermine the galleries of his opponent. Boufflers, the French commander, after a masterly defence, was compelled to capitulate, but upon the most honourable terms.

The *Hôtel de Ville* was anciently the palace of the Dukes of Burgundy. It was built by Jean-sans-Peur, 1430, and inhabited by the Emp. Charles V. It is a quaint rather than a handsome edifice, in the late Gothic style, but it has a prettily groined staircase in one of its tourelles, and a chapel. One division of the building, appropriated to a *school of art*, contains a most interesting and valuable collection of *Drawings by old masters*, including 44 by *Raphael*! well worthy the inspection of all who take an interest in art.

The town also possesses a *Musée*, where, among a number of bad pictures, is one by *Rubens*, St. Catherine rescued from the Wheel of Martyrdom, painted for a church in the town. St. Cecilia and St. Francis are by *Arnold de Vuez* (a native artist of considerable merit, b. 1642); and there is a series of curious old portraits of the Dukes of Burgundy and Counts of Flanders.

The principal *Church* (St. Maurice) is in the Gothic style of the 16th centy., resting on slender piers, but is not very remarkable.

The huge *storehouses for corn* at the extremity of the Rue Royale, a street nearly a mile long, deserve notice. There are some very handsome shops in the *Rue Esquirmoise*.

The tall chimneys of numerous mills, even within the walls, announce the active industry which is working here, and show the unusual combination of a fortress and manufacturing town, while the country around, and indeed a large part of the Dépt. du Nord, is like a hive, in population and activity not unworthy of being compared with parts of Lancashire and the West Riding. The chief *manufacture* is that of *flax* (which is

cultivated in the vicinity), and is spun into ordinary thread, and twisted to form the kind called *Lille thread*, by old-fashioned machines moved by the hand; besides which much linen is woven here. In the spinning of *cotton*, Lille is a formidable rival of the English. The making of tulles and cotton lace has fallen off. The extraction of *oils* from colza and the *seeds* of rape, poppies, linseed, &c., and the manufacture of *sugar from beet-root*, are very important, having given a great impulse to agriculture, as well as employing many hands and hundreds of windmills.

The *Railway* from Lille to Courtrai in Belgium passes through the industrious towns of Roubaix (24,000 inhab., 11 kilom.), a minor focus of the *cotton manufacture*, and Turcoing (20,000 inhab.), famed for its manufacture of table-linen.

Brussels may be reached in 5 or 6 hours from Lille, by railway. The *terminus* at Lille is in the Faubourg des Fives. (See HAND-BOOK N. GER.)

*Railways* to Paris—to Tournay; Courtrai, Ghent (in 3 hours)—Brussels and Ostende.

*Diligences* daily to Dunkerque and Calais; to Boulogne.

The Road to Dunkerque is the same as that to Calais for the 3 first stages.

16 Armentières,	} Described in
13 Bailleul,	
20 Cassel,	
10 Bergues,	} In Route 189,
20 <i>Dunkerque</i> ,	
	p. 595.

#### ROUTE 187.

CALAIS TO DIJON, BY DOUAI, CAMBRAI, ST. QUENTIN, LAON, RHEIMS, CHÂLONS-SUR-MARNE, AND TROYES.

559 kilom. = 346½ Eng. m.

This is the direct road for travellers to Switzerland or Italy, not wishing to pass through Paris. The saving in distance is not great, only 7 m. less than the route by Paris and Sens, and the road is very inferior to it; but by this route they will pass

through a series of places possessing great interest, and by avoiding Paris, they are allowed to retain possession of their passports. The country is interesting, but the road, as far as Châlons-sur-Marne, is wretched; rough paving worn into holes. Beyond C. s. M. it is excellent. Those who travel by *diligence* will not find a conveyance direct to carry them from one end of the journey to the other without interruption, and may often have to wait at various points; but they will invariably meet with diligences running from one great town to another.

Calais is described in Route 2.

- |                |            |
|----------------|------------|
| - 16 Ardres,   | } Route 1. |
| 8 La Recousse, |            |
| 18 St. Omer,   |            |
| 18 Aire,       |            |

13 Lillers, a town of 4620 inhab. Here the first *Artesian well*, so called from the Province Artois, was bored by the engineer Belidor, in the last century, and hence the practice has extended all over Europe; it had been however previously tried in Italy.

13 Bethune. — *Inn*: H. du Roi, comfortable. The post-house is outside the town, which was formerly considered third in importance in Artois. It has 6890 inhab. In its large market-place rises a singular old *Beffroi*, a heavy square truncated tower, on which a Gothic spire has been engrafted.

Water is scarce here, and wells few and very deep.

There are 2 roads hence to Cambrai.

Branch a. by

18 Souchez, a shady and picturesque village.

“The country, which near Calais is very marshy and bleak, gradually improves. Very few hedges are seen. The crops divide the ownership, and some growths become apparent to which we are not accustomed at home: flax and hemp in great abundance, and large strips of the white poppy, cultivated for the purpose of extracting oil from the seed. The pale petals have a large lilac fleck at their

base, and the crop is handsome when in flower. One unpleasing result of the want of hedges is the absence of their feathered tenants.”—*F. P.*

12 Arras (p. 587). Rail to Paris.

24 Marquion.

11 Cambrai (p. 586).

Branch b. from Bethune to

19 Lens (p. 590).

15 Bac en Bencheul.

11 *Cambrai*, in p. 586.

11 Bonavy,	} in R. 183,
14 Bellicourt,	
13 St. QUENTIN.	

p. 585.

10 Cerisy, a pretty village.

12 La Fère, a fortified town of 2085 inhab., on the Oise, which we here cross. It has a school of artillery.

The country improves in picturesqueness on approaching Laon, which is entered by a long and steep ascent.

23 “*Laon.*—*Inn*: La Hure, *i. e.* the Boar’s Head; not a splendid house, but comfortable. Laon is the chef-lieu of the Dépt. de l’Aisne (9346 inhab.); and it may here be remarked, that in a small town of this class there is as much difficulty in procuring beds during the sitting of the Cour Royale as there would be in an assize town in England.

“Laon is situated upon a lofty and almost isolated hill, crowned by the noble *Cathedral of Notre Dame*. This edifice, which is in a very pure and simple Gothic style, much resembling Salisbury, was dedicated Sept. 6, 1114, having been built from the very ground in the space of the two years preceding; so that it is a century older than any specimen of the same kind in England. It has five towers, of which four have very large, lofty, unglazed windows, through which the light shines. The façade, with its great receding cavern-like portals and arches, is singularly venerable; and the traveller will do well to mark its outline, for he will here see, in its simplest aspect, the type which at Rheims is expanded to the highest



grade of decoration and exuberance. As a matter of taste, however, it may be doubtful whether the simplicity be not as satisfactory. The *choir*, like our English cathedrals, ends square. The circular window is remarkable for its size, and for its painted glass, of which there is more in the choir. The Cathedral is much neglected, and the *cloisters* have been demolished quite recently by the Vandalism of the municipality. The Bishop of Laon was one of the twelve ecclesiastical peers of France; but this dignity did not deter the citizens from violently contesting his authority. In this Cathedral is preserved an ancient painting of St. Veronica, brought from a suppressed monastery, with an inscription which greatly puzzled the savans of the age of Louis Quatorze. It is in the ancient Slavonian dialect and character, merely indicating the object which it represents.”—*F. P.*

The *Church of St. Martin*, on the side of the town opposite to the cathedral, is chiefly remarkable for its 2 fine and lofty towers.

The *Préfecture* is established in the ancient abbey of St. Jean, which also contains the public *library*, and the *Hôtel Dieu* is the former *Abbey of Martin*.

The grand massive tower of Louis d'Outremer, one of the oldest monuments in France, has lately been pulled down to make way for a *Citadelle*, which has been deemed necessary to defend this side of France from invasion. Its massive foundations, however, have hitherto resisted the attempt to remove them. Near the Porte St. Martin is a curious *Leaning Tower*, called Tour Penchée, or de la Dame Eve, inclining nearly 10 degrees out of the perpendicular. Queen Brunehaut, who fixed her court at Laon, gives her name to another tower. “The fine masses of the ancient walls and towers which encircle the town, mixing with the rocks, add much to its picturesque aspect. These walls are said to have been built by Guillaume Harulin, the

physician who attended Charles VI. during his insanity; so that, if this tradition be correct, they give a great idea of his fees. There are many fine points of view here, and perhaps none of them are more pleasing than those gained from the summit of the *ramparts*. The landscape is extensive and varied. Vineyards clothe the slopes of the hills, the plains are covered with cultivation, the earth seems literally teeming.”—*F. P.*

One of the finest views of the town is from the road called “Chemin des Creuttes,” near the Calvary, on the way to the *Abbey of St. Vincent*, of which no part escaped the fury of the democrats, except its outer walls (*creuttes*), moated and embattled like a fortress as it was; they now enclose a private garden.

In March (9 and 10), 1814, a *battle*, which lasted 2 days, was fought between the Allies, commanded by Blücher and Witzingerode, who occupied the town and neighbouring heights, and the French army, much inferior to them in numbers. Here the success of Napoleon was arrested for the first time in the campaign, and he was compelled to retire towards Soissons, with a loss of 6000 men and 46 cannon.

20 Corbény. “Crossing the Aisne, the road enters the ancient province of *Champagne*, which derives its name from the many plains which it contains, and which constitute its great natural features, as soon as you advance beyond the borders.”—*F. P.*

9 Berry au Bac. “From Laon the country continues varied, though less hilly, as you approach Rheims. It is tolerably wooded, and the luxuriance of the wild flowers, French honeysuckle, and many which are cultivated in gardens with us, is very pleasing.”—*F. P.*

19 RHEIMS, in R. 178, p. 575.

“11 Sillery; not the locality which produces the celebrated Sillery Champagne. That wine derives its name from Sillery by a secondary process. Under its name is comprehended the

produce of the vineyards of Verzenay, Mailly, Raunent, &c., situated at the N. E. termination of the chain of hills which separate the Maine from the Verle, and formerly belonging to the Marquis de Sillery, husband of Madame de Genlis. Having been originally brought into vogue by the greater care bestowed upon the manufacture of it by the Maréchale d'Estrées, it was long known by the name of *Vin de la Maréchale*.

“ 19 Les Grandes Loges.

“ The road from Rheims to Châlons passes through plains extending far and wide, in which the course of the Marne may be traced by the long rows of poplars upon its bank, by the Campi Catalaunici, where the *great battle* took place between the combined armies of Rome and Theodoric, and the ‘innumerable host’ of Attila (A. D. 451). Here, as Gibbon observes, were assembled the natives of the various countries from the Volga to the Atlantic. The number of the slain amounted to 162,000, or, according to another account, 300,000. Attila, whose valour was always guided by his prudence, had waited for the enemy in these plains, as being best adapted to the operations of his Scythian cavalry. Great as was the slaughter, the conflict was undecided: Attila retreated into his camp, which he had fortified, according to the Scythian usage, by a vast circle of the waggons in which they dwelt. The allied armies separated at the moment when the magnanimous Barbarian had resolved, if his intrenchments should be forced, to rush headlong into the flames of the funeral pile formed of the saddles and rich furniture of the cavalry, and thus to deprive his enemies of the glory which they might have acquired by his captivity. Attila continued for several days within the circle of his waggons after this defeat, dreading some hostile stratagem; but his ultimate retreat beyond the Rhine ‘confessed the last victory which was achieved in the name of

the Western Empire.’ Near the villages of Chape and Cuperly, about 5 miles from Châlons, there are vestiges of ancient earth-works, traditionally known as the Camps of Attila; and the expositors of the productions of the ancient German bards find the battle of Châlons recorded in the *Nibelungen Lay*.”—*F. P.*

13 Châlons-sur-Marne. (R. 175, p. 569.)

18 Vatry.

10 Sommesous.

“ After leaving Châlons, the country becomes less fertile, the crops generally thin and scanty. The vineyards of Champagne seem to be replaced by plantations of Scotch firs, which add nothing to the beauty and little to the shelter of the scenery. The road continues straight before and behind, marked in white chalk along the yellow and russet fields. At length it begins to undulate; till, after a long ascent and descent, you reach

23 Arcis-sur-Aube (*Inn*: Poste; small but decent), a town of 3000 inhabit., nearly all burnt down March 20, 1814, during a combat between Napoleon and the Allies. Much grain is shipped from its bridge. Danton the Terrorist was born here.

9 Voué.

19 Troyes (Rte. 144, p. 525).

19 St. Parre-les-Vaudes. }

14 Bar-sur-Seine. }

19 Musse-sur-Seine. }

15 Châtillon-sur-Seine. } R. 144.

14 Aisey-le-Duc. }

15 Ampilly-le-Sec. }

15 Chanceaux. }

39 DIJON (p. 527).

## ROUTE 188.

CALAIS TO LILLE AND TOURNAI, ON  
THE WAY TO BRUSSELS BY CASSEL.

110 kilom.=68 Eng. m.

*Diligences*—3 or 4 daily.

Calais, in R. 2, p. 7.

24 La Recousse, } R. 1.

18 St. Omer, }



The stage from St. Omer to Cassel may be travelled in about 2 hours. The latter part is a very steep ascent up a high hill, on whose summit lies the village of

20 Cassel. H. du Sauvage, good, but complaints of bad smells.—*H. T.* It is worth while in fine weather to stop here for a short time to enjoy the view. Cassel is an ancient town of 4234 inhab. Here at length the country becomes more interesting. Cassel is most agreeably situated on a hill commanding one of the most extensive views in Europe. Although it has no striking features, it cannot be contemplated without deep interest, as exhibiting on a clear day an unusually extensive tract of highly cultivated and productive country. Its most remarkable feature is, that the horizon is almost equally distant in every direction, as no rising ground interrupts the sight. It extends over the flat and fertile plains of Flanders, and as far as the white cliffs of England, into 3 different kingdoms; includes 32 towns and 100 villages. St. Omer, Dunkerque, Ypres, Ostend, and the beautiful steeple of Hazebrouck are the most prominent objects: no fresh water is visible in this vast expanse. Mont Cassel is only 800 Eng. ft. high: it was one of the principal signal stations of the great trigonometrical survey carried on during the reign of Napoleon. A small map of the country visible may be purchased on the spot for 20 sous.

The gardens and grounds of the late General Vandamme, who was born here, are commonly shown to strangers, and are very tastefully laid out. The stable is worthy of remark on account of its size.

“Flemish is the general language of the entire population in the northern parts of the Dépt. du Nord: it is spoken at Cassel, and as far as Watel.”—*G. C. L.*

20 Bailleul.—*Inn*: Faucon.

12 Armentières, a town of 7700 inhab., mostly weavers.—The road

here almost touches upon the Belgic frontier.

16 LILLE, in R. 186, p. 590.

The quickest and best mode of reaching Brussels from Lille is to take the railway by Courtrai and Mechlin. (See p. 591.)

11 Pont-à-Tressin is the last post station in France; the custom-house is about 3 m. beyond it.

14 Tournay, BRUSSELS, 9½ posts,	$\left\{ \begin{array}{l} \text{described in} \\ \text{HAND-BOOK} \\ \text{for NORTH} \\ \text{GERMANY.} \end{array} \right.$

### ROUTE 189.

CALAIS TO DUNKERQUE AND COURTRAI  
BY GRAVELINES AND BERGUES.

51 kilom. = 31½ Eng. m. to Bergues, and 8 posts thence to Courtrai.

*Diligences* twice a-day to Dunkerque in 5 hours.

Calais, in R. 2, p. 7.

It is a good road to

20 Gravelines.

A fortress, and desolate-looking small town, with grass growing in its streets; it has 3000 inhab. “It is,” to use the words of an old writer, “very strong, by reason that they can drown it round in 4 hours, so as no land shall be within a mile of it.” It is surrounded by a plain, once a vast marsh, below the level of the sea, nearly 20 m. long by 12 broad; almost all this can be laid under water in case of need, to ward off a hostile invasion on this side of France. At present this district supports a population of 60,000. It is protected from the sea by the dunes or sand-hills, and is gradually being drained by its inhabitants. It would cost the arrondissement 10 millions of frs. to repair the damage caused by admitting the waters upon the land.

The Empr. Charles V. here paid a visit to Henry VIII. on his return from his interview with Francis I. at the Field of the Cloth of Gold, 1520.

Beyond Gravelines the road is paved.

21 DUNKERQUE (*Inns*: H. de Flan-

dres; very good, and not dear; table d'hôte at 6, good, 2½ fr.; breakfast with eggs, 1 fr. 75 c.; — Chaperon Rouge), a considerable fortified town and seaport, with 25,400 inhab. Large sums have been expended in endeavouring to clear the mouth of the harbour from the bar of sand which obstructs it, by means of basins and sluices, which are filled by the flowing of the tide, and discharged at low water, so as to scour a channel through the mud. They are said to have failed in producing the results anticipated. Dunkerque nevertheless is the best harbour which France possesses in the N. Sea, and ranks fourth in the value of its exports and imports of all the seaports in the kingdom. It serves as the outlet for the manufacturing district of the Dépt. du Nord. "It is one of the cleanest towns in France, with wide streets, well paved, living cheap: baths, very good."—*D. C.*

The *Quai*, usually crowded with vessels, and *pier*, extending far into the sea, are worth seeing: so is the Corinthian portico of the *Church of St. Eloi*, a handsome but most incongruous frontispiece to a Gothic building; in front of it is a fine detached Gothic belfry, containing the chimes.

There is an *English Protestant Church*, Rue des Sœurs Blanches—a proof of the number of British residents.

A *Statue* of John Bart, a famous sea-captain, born here (temp. Louis XIV.), stands in the Great Market Place.

Dunkerque owes its origin to a chapel built by St. Eloi in the 7th century among the dunes or sandhills, and thence comes its name, "Church of the Dunes." Here was equipped the Flemish division of the *Spanish Armada*, designed to combine in the invasion of England under the command of the Prince of Parma; but that skilful general, perhaps foreseeing the result, refrained from putting out to sea. Dunkerque,

after having been hardly won by the English under Oliver Cromwell from the Spaniards, 1658, was basely sold by Charles II. to Louis XIV. for 6 millions of livres in 1662.

By the Treaty of Utrecht (1715) the French were compelled to demolish the town and fortifications, and an English commissioner was actually sent hither to ascertain that the stipulations of the treaty were complied with to the letter; a source of deep humiliation to French pride, but of more immediate misery to the poor inhabitants. The port and fortifications were not restored and rebuilt until 1740.

The country around is little better than a dreary waste of sandhills thrown up by the wind. It was in the neighbourhood of them that Turenne defeated, in 1658, the Spanish army under Don John of Austria and the Great Condé, who had sided at that time with the enemies of France, in the *Battle of the Dunes*. The siege of the town had been commenced by Mazarin, at the dictation of Cromwell, whose fleet blockaded it by sea. The Spaniards, unprovided with artillery, advanced to attack the French, by marching close to the sea. Condé remonstrated in vain with Don John against a measure so perilous: "Vous ne connaissez pas M. de Turenne," said he; "on ne fait pas impunément des fautes devant un si grand homme;" and just as the action began, he turned to the young Duke of Gloucester, and asked if he had ever been in a battle before. "No," answered the Duke. "Then you will see one lost in half an hour." The action was commenced by 6000 English soldiers of Cromwell, commanded by Lockhart, his ambassador, who formed the left wing of the French army, and distinguished themselves eminently: their charge carried everything before it, and contributed not a little to the result. The Duke of York (afterwards James II.) fought in the opposite ranks, at the head of a regiment of



Cavaliers, and it was from them that their fellow-countrymen suffered most. The Spaniards lost 4000 men, and Dunkerque surrendered 10 days after, in consequence of this defeat.

A pleasant excursion may be made to the hill of Cassel, about  $18\frac{3}{4}$  m. off (p. 595). *Marchand*, voiturier, is obliging, intelligent, and has a good equipage.

*Diligences* daily to Paris; to Ostend; to Lille.

*Steamers* to Rotterdam; to Hamburg; to Havre. A branch railway is projected from Dunkerque to Hazebrouck, where it will join the lines from Lille to Paris.

There is a *canal* from Dunkerque to Furnes, Ostend, and Bruges, traversed daily by a barge, and another canal to Bergues.

10 Bergues (*Inn*: Poste; small, but cheap), a small and poor fortified town of 6000 inhab., situated on an elevation, surrounded by marshes and salt lakes, called Möere, formerly waste and insalubrious; but having been drained within a few years by the construction of hydraulic works, they are now becoming productive, and less unwholesome. Though only a fortress of the third class, the possession of Bergues has been deemed of such consequence in every war, that it has been 8 times taken and retaken, and 9 times pillaged, in the course of 8 centuries. It has a picturesque *Beffroi*, 150 ft. high. A very important *corn-market* is held here every Monday. The gates are closed at 10, after which neither ingress nor egress is allowed.

The French frontier and custom-house is reached at Oest Kappel: here the "acquit à caution" must be

delivered up. (See INTRODUCTION, § e.)

*Belgian Posts:*

$1\frac{3}{4}$	Rousbrugge, a Belgian village.	} See HAND-BOOK for NORTH GER- MANY.
$2\frac{3}{4}$	YPRES.	
$2\frac{1}{4}$	Menin, on the Lys.	
$1\frac{1}{4}$	COURTRAI.	

ROUTE 190.

CALAIS TO ARRAS, BY HAZEBROUCK—  
RAILWAY.

This line is only in progress, and is not expected to be finished before 1849.

Andruick.

Watten, on the canal of St. Omer.

*St. Omer* (Route 1, p. 3)—18,455 inhab.

The suburbs le Hautpont and le Lyzel are traversed by more than 300 canals, each of which has its distinct name, watering a number of gardens, in which the natives, a primitive and pious race of market-gardeners, cultivate vegetables.

The neighbourhood is very marshy: on the Etangs du Clairmarais are floating islands, which form productive gardens.

Hazebrouck St.

Here the Railway lines from Calais, Lille, Dunkerque, and Arras cross each other.

Hazebrouck is a flourishing town of 7346 inhab.

Its church has a spire, 240 ft. high, of open work, b. 1493—1520.

The Railway hence to Arras (54 kilom.) will be carried through

Bethune (Route 187), and near Merville and Lens (Route 185), to Fampoux, a suburb of Arras (Route 587).

## INDEX.

## A.

- Abbeville, 18  
 Abélard (at St. Gildas), 150, 213; his death at St. Marcel, 388  
 Ablon, 175  
 Abronne, 340  
 Accous, 296  
 Adour, passage of the, 282; cradle of, 320  
 Adrets, Baron des, 503, 508  
 Æschylus, 482  
 st. Afrique, 418  
 Agde, 480, 481  
 Agen, 264  
 Agincourt, 4  
 Agnes Sorel, 54, 57, 200, 202, 223  
 d'Aguesseau, 393  
 Aï, 567  
 Aidat, Lac d', 407  
 st. Aignan, 189  
 Aigrefeuille, 217  
 Aigueperse, 393  
 Aignes Mortes, 476  
 Aiguillon, 265  
 Ailly, 18  
 Ain, 540  
 — river, 540  
 Airaines, 14  
 Aire, 4, 291  
 Aisey-le-Duc, 527  
 Aix, 496  
 — in Savoy to Lyons, 539  
 — Ile d', 219  
 Alagnon, 412  
 Alais, 434. To Nismes, railway, *ib.*  
 Albigeois, 340, 420, 480  
 st. Albin, 389  
 Albret, 280  
 Alby, 419  
 Alençon, 118  
 Alfieri's library, 479  
 Alfort, 383  
 Allan, 448  
 Allemont, 516  
 Allevard, 511, 516  
 Allier, 368, 393, 396, 403  
 Alpines, 461, 495  
 Alsace, 545  
 Altkirch, 548  
 st. Amand, 249  
 ——— Montrond, 360  
 Ambleteuse, 9  
 Amboise, 190  
 st. Ambroix, 433  
 Amiens, 18. Cathedral, 19  
 Amphitheatre at Nismes, 469  
 — Arles, 464  
 Ampilly-le-Sec, 527  
 Ampouille, sainte, 577  
 Ampuis, 442  
 Amyot, Jacques, 385  
 Ancenis, 212  
 Ancy-le-Franc, 532  
 Andance, 428, 443  
 Andaye, 287  
 Andelle, 52  
 les Andelys, 51  
 st. Andéol, 495  
 Andorre, 349  
 st. André de Cubsac, 231  
 — le Bas, 442  
 Andresieux, 426  
 Andresis, 49  
 Anduze, 425  
 Anet, chât. d', 117  
 Angers, 160, 165  
 Angerville, 175, 177  
 Angoulême, 228  
 Anjon, 161  
 Annisy, 79  
 Annonay, 428  
 Antibes, 499, 515  
 Antraigues, 431  
 Anzin, 587  
 Aragnouet, 322  
 Arago, M., 344  
 Aramon, 461  
 Aran, Val d', 330, 332, 336, 337  
 Arbois, 542  
 l'Arboust, Val, 323, 331  
 Arc, Pont de l', 433  
 Arcis-sur-Aube, 594  
 Arcy, les Grottes d', 386  
 Ardèche, 352  
 — river, 422, 450  
 Ardenne, 78  
 Ardevan, 95  
 Ardres, 3  
 Argelez, 304, 306  
 Argental, Bourg, 428  
 Argentan, 102  
 Argenton, 247  
 Ariège, 338, 346  
 ARLES, en Provence, 464  
 Arles-les-Bains, 350  
 Armentières, 595  
 Arnay-le-Duc, 388  
 Arpajon, 174  
 Arques, 26  
 Arras, 587  
 Arreau, 321, 322  
 Arrhune, 286  
 Artenay, 175, 177  
 Artesian wells, 592  
 Artigues, 320  
 — Tellina, 332, 336  
 Artix, 290  
 Artois, 583  
 Arvieux, Val d', 520  
 Asnières, 30  
 Aspe, Val d', 296  
 Aspin, 321  
 Athis, Mont, 175  
 Attila, 594  
 Aubagne, 490, 497  
 Aube, 545  
 Aubenas, 353, 430  
 st. Aubin du Cormier, 104  
 Aubusson,  
*Auch*, 338  
 Aude, 341  
 Aulnay,  
 Aumetz, 582  
 Auray, 147  
 Aure, Val d', 322  
 Auriac, 291  
 Aurigny (Alderney), 90  
 Aurillac, 414  
 Ausonius, 272, 464  
 Auteuil, 115  
 Auterive, 347  
 Autun, 391  
 AUVERGNE, 352, 393, 395  
 Auxerre, 385  
 Auxonne, 533  
 Avalon, 132  
 Avallon, 386  
 Avenières, 119  
 Avesnes, 589  
 AVIGNON, 453  
 — to Marseilles, by Arles, St. Chamas, Etang de Berre (Railway), 499  
 — to Narbonne, by Nismes and Montpellier, 469  
 — to Nice, by Aix, 494  
 Avignonet, 340  
 Avranches, 94  
 Ax, 348  
 st. Ay, 184  
 Azac, Coupe d', 431  
 Azay-le-Rideau, 201



Azincour, 4  
Azun, Val d', 306

## B.

*Bagnères de Bigorre*, 240, 325  
— to Luchon, mountain road, 321  
— *de Luchon*, 240, 331  
Bagnes, the, 127, 220, 492  
Bagnols,  
Bailleul, 595  
Balarue, 480  
Ballons, 560  
Ban de la Roche, 559  
Bapaume, 56, 590  
Bar, 561  
Bar-sur-Aube, 545  
— Seine, 526  
la Baraque, 537  
Barbaste, 290  
st. Barbe, 151  
Barbe Bleu, 211  
— Ile, 382  
Barbeira, 342  
Barbezieu, 231  
Barcelonnette, 515  
Bar-le-Duc, 550  
*Barèges*, 240, 317. Crêpe de, 319, 327  
Barentin, 61  
Barfleur, 84  
Barraux, Fort, 510  
Barre-y-va, 54  
Barrême, 515  
Barsac, 266, 279  
Barse, 545  
Basques, 237, 285  
Bastan valley, 287, 319  
Bastides at Marseilles, 484, 486, 488  
Batignolles, 29  
Batz, 133  
Baud, 147  
Baudéan, 321  
la Baume, 432  
Bayard, 508, 579. Château, 509, 511  
*Bayeux*, 81. Tapestry, *ib.*  
— to St. Lo, 104  
Bayle, 346  
*Bayonne*, 281  
— to Irun in Spain, 284  
— to Pau, 288  
Bayonnette, 284, 286  
Bazas, 279, 290  
Bazeilles, 580  
Baziège, 340  
*Béarn*, 234, 292, 295  
st. Beat, 330, 337  
*Beaucaire*, 461, 462, 482  
— fair of, 462  
la Beauce, 155, 182  
Beaufort, 542  
Beaugency, 185  
Beaujeu, 300  
Beaumanoir, 138  
la Beume, Pont de, 423, 433

Beaumont, 72  
— sur-Oise, 17  
Beaune, 538  
Beauport Abbey, 131  
Beaupreau,  
Beauregard, 356, 411, 446  
Beausoleil, 249  
Beausset, 490  
*Beauvais*, 15  
Beauvoir, 95  
Beaver of the Rhône, 457  
Bec Abbey, 71  
— d'Ambès, 276  
Becket, Thomas à, 74, 385, 386, 531, 574  
Bédarrides, 453  
Bédeillac, 347  
Bedouin, 461  
Bédous, 296  
Béfort, 564  
Begude de Jordy, 480  
— Saze, 469  
Behobia, 286  
Behuard, Ile, 210  
Bellegarde, 482  
— fort, 345  
— (Ain), 541  
Belle Isle, 146  
Belleisle en Terre,  
Bellesme,  
Belley, 539  
Belzunce, Bp., 487  
Benfeld, 561  
la Bérarde, 516  
Bercy,  
Bergerac, 263,  
Bergons, Pic de, 311, 312  
Bergues, 597  
Bernadotte, 294, 546  
Bernay, 14, 70  
Berre, Etang de, 468, 500  
Berri, 352  
— Duchesse de, 167  
st. Bertrand de Comminges, 330  
*Besançon*, 542  
Bétharram, 304  
Bethune, 592  
Beycheville, 277  
Beza, 387  
Béziers, 480  
Bezons, 30  
Biarritz, 234  
Biaudos, 289  
Bicêtre, 362  
Bidart, 285  
Bidassoa, 286  
Bielle, 298  
Bielsa, 322  
Bienne, 534  
Biescas,  
Bignon, 366  
Billière, 290  
Binic, 130  
Bischweiler, 557  
Bitche, 553  
Bize, Vent de,  
Black Prince, 227, 248, 272, 305, 324, 342

Blanchelande, 91  
Blanquefort, 271, 273  
Blaye, 276  
Bléré, 192  
*Blois*, 185  
Blosseville, 42  
Blücher, 546  
le Bocage, 102  
Boën, 411  
Bois de Lihus, 589  
— Robert, 28  
Bolbec, 62  
Bolingbroke's Château, 182  
Bollwiller, 563  
*Bonaparte* at Boulogne, 12  
— at Brienne, 546  
— at Cannes, 499  
— at Fontainebleau, 363  
— at Fréjus, 498  
— at Grenoble, 507, 512  
— at Lyons, 383  
— at Malmaison, 44  
— at Orgon, 495  
— at Rochefort, 221  
— at Surville, 384  
— at Toulon, 491, 493  
— at Valence, 445  
Bonavy, 586  
Bondy, 565  
st. Bonnet, 407, 513  
Bonneval, 199, 417  
Bounières, 32  
Bord'haut, 47  
*BORDEAUX*, 266-273  
— to Auch, 290  
— to Bayonne, 279  
— by the Landes, 287  
— Bridge of, 231, 267  
— to Pau, 288, 291  
— Richard of, 272  
— Wines, 270, 274  
Bore in the Seine, 55  
Boscherville, St. George de, 54, 56  
Bosost, 332, 337  
Bossuet, 531, 566  
Bouc, 467, 499  
Bouchain, 587  
Boucoiron, 435  
*Boulogne-sur-Mer*, 9-14  
— Flotilla, 12  
Boulou, 345  
Bourbon l'Archambault, 369  
— Vendée, 217  
Bourbonnais, 352  
Bourbonne-les-Bains, 547  
Bourdaloue, 360  
Bourdonnay, 553  
Bourgachard, 71  
Bourg, 276  
— (Ain), 542  
— St. Andeol, 450  
— d'Argental, 428  
— Dieu or Deols, 247  
— Dun, 67  
— d'Oysans, 516  
— la-Keine, 174  
*Bourges*, 356, 360

le Bourget, 573, 583  
 Bourget, Lac de, 539  
 Bourgoin, 502, 503  
 Bourgheroude, 71  
 Bouscaut, 266, 279  
 Bout de Bois, 143  
 — de Lande,  
 Brèche de Roland, 313, 315,  
 316  
 — ascent to, 315  
 la Brède, château de la, 271,  
 279  
 Bréhal, 93  
 la Bresse, 390, 542  
 Bressuire, 216  
*Brest*, 125-130. Roadstead  
 of, 128  
 — to Nantes, 143  
 Breteuil, 5  
 Bretigny, 157, 176  
 Bretteville, 80  
*Briançon*, 517  
 — to Susa, 518  
 Briare, 366, 367  
 Bricquebec, 83, 90  
 Brie Comte Robert, 523  
 — Cheese, 566  
 Brienne, 546  
 st. Brieuc, 122  
 — to Brest, 130  
 Brignais, 421  
 Brignolles, 498  
 Brionne, 71  
 Brioude, 402  
 st. Bris, 386  
 Brissac, château, 210  
 BRITTANY, 106-112  
 Brives, 250  
 Brix or Bruis, 85  
 Broglie, 70  
 Broons, 122  
 Brou (Ain), church of, 542  
 Brougham, Lord, 499  
 Bruges, 530  
 Brummel, Beau, 78  
 Brune, Marshal, 453  
 Brunel, Mark Isambart, birth-  
 place of, 48  
 st. Bruno, 505  
 Bruyères,  
 Buffon, 532  
 Buisson, Haut, 9  
*Burgundy*, 523. Wines, 536  
 Burzet, 432  
 la Bussière, 366  
 Bussy,  
 Buzançais, 201  
 Buzaney, 580

## C.

Cacolet, 285  
*Caen*, 74-80. Stone quarries,  
 80  
 — to Cherbourg, 80  
 — to Rennes, 102  
 — to Tours, 101  
 Cæsar at Gergovia, 401  
 Cafés, xxxi

Cagots, 237, 312  
 Cahors, 250  
*Calais*, 7  
 — to Arras, by Haze-  
 brouck (Railway), 597  
 — to Dijon, by Douai,  
 Cambrai, St. Quentin,  
 Laon, Rheims, Châlons-  
 sur-Marne, and Troyes, 591  
 — to Dunkerque and Cour-  
 trai, 595  
 — to Lille and Tournay,  
 594  
 — to Paris by Amiens, 3  
 — to Paris by Boulogne, 7  
 Calas, Jean, 258  
 Calmoutier, 548  
 Calvados, Dept., 75  
 Calvin, 584  
 Calvinet, Mont, 260  
 Camargue, 468  
 Cambacères, 479  
 Cambiel, 322  
 Cambo, 284  
*Cambrai*, 586  
 Cambres, 29, 79  
*Camisards*, 354, 433  
 Campan, Val de, 320, 327  
 Campfranc, 296  
 Canal of Arles, 467  
 — de Beaucaire, 462  
 — de Boissgelin, 495  
 — de Briare, 366, 367  
 — de Brienne, 259  
 — du Centre, 388, 392  
 — du Cher, 360  
 — de Crillon, 459, 494  
 — de Marseilles, 495  
 — du Midi, 252, 259, 339,  
 481  
 — d'Orléans, 184  
 — de l'Ourcq, 565  
 — de St. Quentin, 586  
 — du Rhin au Rhône, 557  
 Cancale, Rochers du, 98, 99  
 Candes, 205  
 Canigou, 344, 350  
 st. Cannat, 484, 495  
 Cannes, 499  
 Cantal, 352, 412  
 Canteleu, 53  
 Cany, 67  
 Capbern, 330  
 Capdenac, 415  
 Captieux, 279  
 Carbon Blanc, 231  
*Carcassonne*, 341  
 Cardillac, 266  
 Carentan, 82  
 Carhaix, 141  
 Carla-le-Comte, 346  
*Carnac*, 150  
 Carnot, 538  
 Carpentras, 460  
 Carriages, duty on, xxii  
 Carrier, the infamous, 168,  
 414  
 Cassagnas, 424  
 Cassel, Mont, 595

st. Cast, 139  
 Castanet, 340  
 Castel Jaloux, 290, 298  
 Castellane, 515  
 Castelnau Castle, 435  
 Castelnau, 340  
 Castelnau de Médoc,  
 Castel Sarrazin, 263  
 Castels, 288  
 Castelton,  
 Castillon, 263  
 Castres, 266, 279  
 Cateau Cambresis, 587  
 ste. Catherine de Fierbois, 223  
 Cauchoise, 61  
 Caudebec, 54, 58  
 Caumont, M. de, 78  
 Caunes, 342  
 Caussade, 251  
*Cauterets*, 240, 307, 314  
 Caux, Pays de, 61  
 Cavaillon, 495  
 Cavalier, 355, 425, 434, 474,  
 475  
 Cavignac, 231  
 Caylus, 415  
 Cazeau, 324  
 Cazères, 302  
 Cère valley, 413  
 Ceret, 350  
 Cerisy, 104, 592  
 Cérons, 266  
 Cette, 479  
 Cevennes, 352, 353, 424, 433  
 Cèze, 433  
 Châblis, 386  
 Chabrol Castle, 261  
 Chagny, 388, 538  
 Chailly, 362  
 Chaise Dieu, 402  
 Chalabre, 346  
 Chalonnès, 211  
 Châlons to Lyons, 388  
 Châlons-sur-Marne, 569  
*Châlons-sur-Saône*, 388  
 Chalut, 261  
 Chalusset, 249  
 Chamalière,  
 st. Chamas, 500  
 Chambertin, 537  
*Chambord*, Château, 187  
 st. Chamond, 421  
*Champagne*, 545, 548, 593  
 — Church of, 443  
 — Vins de, 567, 578  
 Champagny,  
 Champagnole, 534  
 Champaubert,  
 Champigny, 203, 549  
 Champollion's birthplace, 415  
 Champsaur, 513  
 Champtercier, 515  
 Champtocé, 211  
 Champtoceaux, 213  
 Chanceaux, 527  
 Chanteloup, 192  
 Chantilly, 5  
 Chapareillan, 511  
 la Chapelle, 549, 564



Chaptal, 479  
 Chaptès,  
 Chaptuzat, 393  
 Charbonnières,  
 Charente, 220  
 Charenton, 383, 523  
 la Charité, 367  
 Charleville, 579  
 Charmes, 447  
 Charonne,  
 Charroux, 228  
 Chauray, 155. Cathedral, *ib.*  
 — to Tours, 199  
*Chartreuse, la Grande*, 501,  
 503  
 Chasselas grapes, 365  
 Château d'Adam, 85  
 Châteaubourg, 444  
 Châteaubriand, M. de, birth-  
 place and tomb of, 100  
 Châteaubriant, 139  
 Château Chinon, 202  
 Châteaudun, 199  
 Château le Forêt, 125  
 — Gaillard, 50  
 — Gonthier, 120  
 — Lafitte, 277  
 — Latour, 277  
 Châteaulin, 144  
 Château du Loir, 102  
 — Margaux, 276  
 Châteauneuf, 136  
 — des Papes, 453  
 — St. Pierre, 85  
 — le Randon, 423  
 — le-Rouge, 497  
 Château Regnault, 199  
*Châteauroux*, 247  
 Château Salins, 552  
 Château-Thierry, 566  
 Châtelaudren, 123  
 Châtelet, 384  
 Châtellerault, 223  
 Châtenay, 174  
 Châtillon-sur-Indre, 201  
 — sur-Loing, 366  
 — de Michaille, 541  
 — sur-Seine, 526  
 — sur-Sèvre, 216  
 Châtonay, 502  
 Châton, 45  
 Chaudes Aigues, 416  
 Chaumette,  
 Chaumont, 189  
 — Haut Marne, 547  
 Chauvigny, 232  
 Chavagnac, 403  
 Chavannes, 548  
 Chazes, 413  
 st. Chely,  
 Chénonceaux, château of, 192  
*Cherbourg*, 85; Digue, 86  
 — to St. Malo, 90  
 Chessy, 372  
 Chevilly, 175, 177  
 Chevreuse, 154  
 Chêze,  
 Chierzac, 231  
*Chinn*, 202  
*France*.

Chissy, 391  
 Choisy, 175  
 Chollet, 216  
 Chorges, 519  
 la Chouannerie, 112, 120  
 Clouzé, 205  
 Christian architecture, 439  
 st. Christophe, 516  
 Cierp, 330  
 Cinq Mars, la Pile de, 204  
 Cintegabelle, 346  
 Cirey, 547  
 Cirque, 236, 313  
 — de Gavarnie, 313, 314  
 Cîteaux Abbey, 538  
 Civray, 228  
 Clain, 224  
 ste. Claire-sur-Epte, 257  
 Clairvaux, 546  
 Claix, 511  
 Clamart, 113  
 Clamécny,  
 Clarbide, Port de, 323  
*Claret Wine*, 270  
 ste. Claude,  
 Clémence Isaure, 253  
 — de Maillé, 247, 250, 272,  
 360  
 Clermont en Argonne, 570  
 — *Ferrand*, 395  
 — to Mont Dore, 407  
 — to Lyons, by Thiers, 410  
 — sur-Oise, 21  
 — to Toulouse, by the Can-  
 tal, 412  
 — — by St. Flour, Alby,  
 Rodez, 415  
 Clerval, 565  
 Cléry, N. Dame de, 184  
 Clichy, 29  
 Clisson, 171, 213  
 Clos-Vougeot, 537  
 st. Cloud, 114  
 Clovis, 574, 577  
 Cluny, 390  
 Cluse, 535  
 Coarrase, 304  
 Cocherel, 73  
 Cœur, Jacques, 357, 358  
 Cognac, 222  
 Coiron, 429  
 Coligny, 6, 230, 366, 542  
 Collioure, 345  
 Collonges, 541  
 Colmar, 562  
 Colombey, 547  
 Colza, 590  
 Combat des Trente, 142  
 Combe de Malval, 517  
 Comblat, 414  
 st. Cômes, 265  
 Comines, 18  
 la Commanderie, 74  
 Commeny, 360  
 Compiègne, 583  
 Concarneau, 145  
 Conches,  
 Conchez,  
 Conchy les Pots, 589

*Condé*, le Grand, at Chantilly,  
 5; at Havre, 63; at Mont-  
 rond, 360; at Fontaine-  
 bleau, 365; at Montargis,  
 366; at the Dunes, 596; at  
 Rocroy, 580; at Lens, 590  
 Condillac, 185  
 Condom, 291  
 Condrieux, 443  
 Conflans, 49  
 Conqueror, Wm. the, his resi-  
 dence at Lillebonne, 60.  
 His birth, 101. His death  
 and funeral, 39, 76. His  
 grave, 76  
 Conques, 419  
 Conquet, 129  
 Coole, 549  
 Corbeil, 176  
 Corbény, 593  
 Corday, Charlotte, 78  
 Cordouan, Tour de, 278  
 Cormery, 199  
 Cornas, 444  
 Corneille, 41  
 Corps Nuds, 139  
 Corrèze, 250  
 Corseulles, 79  
 Cosne, 367  
 Côte des Deux Amans, 52  
 — d'Or, 526, 536  
 — Rotie, 443  
 Côtentin, 83  
 Coucy le Château, 575  
 Coudes, 401  
 Couësson, river, 98  
 Coulange,  
 Coulommiers, 548, 549  
 Courbassil, 349  
 Courbevoie, 43  
 Courcelles, 573  
 Cournouaille, 111, 141  
 Couronne, Grande, 71  
 Courtenay,  
 Courthezon, 453  
 Courville, 158  
 Coustouges, 350  
 Coutances, 91  
 Coutras, 262  
 Crach, 150  
 Craon, 17  
 Craponne, Canal de, 483  
 Crau, 482  
 Crécy, 14  
 Creil, 21  
 Crépy,  
 Cressensac, 250  
 Crest, 447  
 Creuilly, 80  
 Creuzot, 392  
 Crillon, 494  
 Croissy,  
 Croix Court, 140  
 — Daurade, 522  
 — Haute, 515  
 — Rousse, 373, 540  
 Croquelardit, 264  
 Croutelle, 228, 233  
 Crouy,

Cruas, 448  
 Cruscade,  
 Crussel, 444, 447  
 Culsac, Pont de, 231  
 Cujes, 490  
 Cunault,  
 Cussy la Colonne, 538  
 Cuvier, 66, 565  
 Cuvilly, 589  
 Cylindre, Mt., 315  
 st. Cyr, 116

## D.

Dammartin, 573  
 Dampierre, 206  
 —, Château de, 154  
 Dante, allusion to Arles,  
 467  
 Daoulas, 144  
 Darnetal,  
*Dauphiné*, 501  
 Dax, 280  
 Denain, 587  
 st. Denis, 22  
 Departments of France,  
 xxxvi  
 Diderot, 547  
 Dieppe, 24—27  
 — to Paris, 24  
 — to Rouen, 28  
 Dieppedale, 53  
 Dieu le fit,  
 st. Diey, or Dié, 560  
 Digne, 515  
 Digoin, 368  
*Dijon*, 527—531  
 — to Châlons-sur-Saône,  
 536  
 — to Geneva, by Dôle, 533  
*Diligences*, xxv  
 Dinan, 136  
 Divonne,  
 st. Dizier, 550  
 Dol, 98  
 Dôle, 534  
 — to Pontarlier and Lau-  
 sanne, 535  
 Dolmens, 108, 133, 149, 158,  
 208, 226  
 Dombasle, 552, 570  
 Dombes, 390  
 Domfront,  
 Domrémy la Pucelle, 557  
 Donzenac, 249  
 Dorat,  
 Dordogne, 231, 262, 408  
 Dore les Bains, Mont, 408  
 Dormans, 567  
 Dornilleuse, 513, 521  
*Douai*, 588  
 — to Lille and Dunkirk  
 (Railway), 590  
 Douarnenez,  
 Doubs, river, 543, 565. Dept.,  
 542  
 Doullens, 5  
 Dozullé, 72  
 Drac, river, 507, 509

Dragonnades, 252, 354  
 Draguinan,  
 Dreux, 116; battle of, *ib.*  
 Droiturier, 371  
 Drôme, 447  
 Duclair, 54, 57  
 Duguesclin, 95, 121, 122, 136,  
 137, 147, 148, 405. His  
 death, 423  
 Dumouriez, 587  
 Dunes, battle of the, 596  
*Dunkerque*, 595  
 Dun le Roi,  
 Durance, 453, 461, 494  
 Duretal, 160  
 Durfort, 425  
 Duroc, Marshal, 581

## E.

Eaux-Bonnes, 240, 302  
 Eaux-Chaudes, 240, 299  
 Ebro, rise of, 330  
 les Echelles, 503  
 Ecluse, Fort, 541  
 Ecouen, 6  
 Ecouis, 48  
 Effiat, 371  
 Elbœuf, 52  
 st. Elne, 344  
 Elven, 153  
 Embrun, 519  
 st. Emilion, 262  
 Enghien-les-Bains, 22  
 English abroad, xxxvii  
 Enguerrand de Marigny, 48  
 Entre Deux Mers, 231, 276  
 Entzheim, 559  
 Epernay, 567  
 Epernon, 154  
 Epinac, 392  
 Epinal, 558  
 Epiny, 176  
 Epouville, 66  
 Epte, river, 50  
 Erdevan, 151  
 Ermenonville, 573  
 Ers, 260  
 Erstein, 561  
 Escaladieu, 329  
 Escot, 296  
 Espalion, 417  
 st. Esprit, 138, 449  
 Essonne, 362  
 Essort, 548  
 Estagel,  
 Estrelle, 466, 498  
 Etampes, 176  
 Etaples, 13  
 Etauliers, 222  
 st. *Etienne*, 426  
 — to Lyons, 420  
 Etigny,  
 Etoile, 447  
 Etrécy, 174, 176  
 Etrétat, 67  
 Eu, 67  
 Eure, 52  
 Euzet, 434

*Evreux*, 73  
 Eyrieu, 447

## F.

Falaise, 101  
 Faou, 143  
 Faouet, 141  
 Farel, 513  
 st. Fargeau,  
 le Fay, 247  
 Fayl-Billot, 548  
 Fécamp, 66  
 la Fère, 592  
 — Champenois, 549  
 st. Féréol, 340  
 la Ferrade, 468, 471  
 Ferrières, 412  
 la Ferté, meaning of, 246  
 Ferte-Bernard, 158  
 — Gaucher, 549  
 — sous-Jouarre, 566  
 — Milon, 573  
 Feurs, 411, 426  
 Field of the Cloth of Gold, 3  
 Figeac, 415  
 Finisterre, Dept., 123  
 Fire-arms, manufacture of,  
 426, 427  
 Firmigny, 421  
 Fitou, 343  
*Flamboyant Gothic*, 110, 166,  
 199, 525  
 Flamingo, 457  
 Flanders, 583  
 Flavigny,  
 la Flèche, 160  
 Fleury-sur-Andelle, 48  
 Florac, 424  
 st. Florent, 212  
 st. Florentin, 531  
 Florian, 183, 425  
 st. Flour, 412, 416  
*Foir*, 346  
 Folgoat, church of, 130, 134  
 st. Fons, 440  
*Fontainebleau*, 363  
 — sandstone and grapes, 365  
 Fontaine le Henri, 79  
 Fontaines, 531  
 Fontanelle, 58  
 Fontaulier, 423, 432  
 Fontenay-le-Marmion, 101  
 Fontevault Abbey, 205  
 Forbach, 573  
 Forcalquier,  
 Forez, 393, 411  
 Forges les Eaux, 28  
 Formigny, 82  
 Fors,  
 Fossard, 384  
 Fossat,  
 Fouday, 559  
 Fougères, 104  
 Fourchambault, 367  
 Fourvières, 373  
 la Foux, 469  
 FRANCE, introductory in-  
 formation respecting, ix—



xl. Modes of travelling in,  
 xx. Inns, &c., xxix. A  
 traveller's view of, xxxi.  
 Departments and Pro-  
 vinces, xxxvi  
 Franche-Comté, 523  
 Francs, table of, x  
 Fréjus, 498  
 Fresne Camilly, 80  
 Fresnes, 587  
 Fressinière, 521  
 la Frette, 502, 503  
 la Frey, 512  
 Frillièrre, 193  
 Froissart, 78, 238, 305, 588  
 Fromenteau, 362  
 Fronsac,  
 Frontignan, 479  
 Fruges, 4  
 Fumay, 579  
 Furens, 426

## G.

Gabas, 299, 300  
 Gaillac, 420  
 Gaillard, château, 32, 50  
 Gaillon, 32  
 Galgals, 109, 149  
 Galignani, 17  
 Gan, 297  
 Ganges,  
 Gannat, 393  
 Gap, 513  
 — to Briançon, 519  
 la Garaye, 139  
 Gard, St. Jean du, 425  
 — Pont du (Aqueduct), 469  
 Gardon, 425, 433, 473  
 GARONNE, river, 263  
 — below Bordeaux, 271  
 — sources of, 330, 335, 337  
 Gascony, 234  
 Gassendi, 515  
 Gatteville, 85  
 Gaube, Lac de, 309  
 st. Gaudens, 339  
 — to Foix and Carcassonne,  
 345  
 Gave de Gavarnie, 311—314  
 Gaves, 235  
 Gâvr Innis, 149  
 Gèdre, 313  
 Geloz, 298  
 Gemenos, 490  
 Gendarmes, xviii  
 st. Genes, 411  
 Geneva, 535  
 Geneviève, St., 44  
 st. Genix, 541  
 Genlis (Burgundy), 533  
 Gennes, 209  
 Genouilhac,  
 st. George Boscherville, 56  
 st. Gerard-le-Puy, 370  
 Gerbird des Jones, 407, 422,  
 433  
 Gère, 441

Gergovia, 400  
 st. Germain-en-Laye, 45  
 — Railway, 45  
 — de Calverte,  
 — de Joux, 541  
 Gervais, 39  
 Gex, 535  
 Gibaud, Pont, 400  
 Gien, 183  
 Gigean, 480  
 Gildas de Rhuys, 150  
 st. Gilles, 475  
 Giromagny, 560  
 Gironde, 231, 276  
 Girondins, 78, 273, 276  
 st. Girons, 345  
 Gisors, 28  
 Givors, 421, 441  
 Givray, 537  
 Glacièrre at Avignon, 455  
 Gobelins tapestries, 364  
 Godemar, Val, 522  
 Goderville, 66  
 Goncelin, 511  
 Gournay, 28  
 — sur-Aronde, 28, 589  
 Grande Chartreuse, 501, 503  
 — Combe, 434  
 Grandvilliers, 15  
 la Grange, 523  
 Granges (Anbe), 525  
 Granville, 93  
 Grasse, 515  
 la Grave, 517  
 Gravelines, 595  
 Gravièrs, 222  
 Graville, 62  
 Gray, 548  
 Grenoble, 507—509  
 — to Briançon, by Bourg  
 d'Oysans, 515  
 — to Gap and Marseilles,  
 511  
 — to Marseilles, by Croix  
 Haute, 514  
 Grésivaudan, Val de, 501,  
 503, 507  
 Greuze, 389  
 Grignan, Château, 449  
 Grip, 320  
 Grisac, 423  
 Grolaud, 218  
 Grosbois, 523  
 Guebweiler, 563  
 Guegnon,  
 Guerche, Château de, 223  
 Guiche,  
 Guichen, 322  
 Guienne, 234  
 Guier, 503, 536  
 Guil river, 520  
 Guillestre, 520  
 Guillotière, 373, 545  
 Guingamp, 123  
 Guinguette de Boyer, 513  
 la Guiole, 417  
 Guisanne, Val de, 517  
 Guise, Duc de, 69  
 — Assassination of, 181

Guisnes, 3  
 Guizot, 474  
 Gypsum quarries, 495

## H.

Hacqueville, Brunel's birth-  
 place, 48  
 Hagetmau,  
 Hague, Cap la, 90  
 Ham, 585  
 Hambye, 92  
 Hannibal's route over the  
 Alps, 442, 444, 453, 539  
 Harcourt, 74  
 Harfleur, 62  
 Hautes Pyrénées, 304  
 Hauteville, 105  
 le Havre, 63  
 — to Caen, 72  
 — to Dieppe, 66  
 la Haye, 223  
 — du Puits, 91  
 Hazebrouck, 597  
 Héas, Val d', 313  
 Hectares and Acres, xvi  
 Hébé, 136  
 Heidenmauer, 562  
 Mundaye,  
 Hennebon, 146  
 Henri Quatre, birth of, 292  
 les Herbiers,  
 Herblay, 28  
 st. Herbot, 141  
 Héricourt, 564  
 Hermitage, 443  
 st. Hilaire de Harcourt, 104  
 la Hogue, Cape, battle of, 83,  
 84  
 Hommarting, 553  
 Honfleur, 71  
 Honorat, 467, 499  
 Hôpital, 423, 426  
 Hot springs of the Pyrenees,  
 240  
 Houdan, 116  
 Hourat, 299  
 Hourquettes, 237  
 Hourquette d'Aspin, 321  
 Huelgoat, 140  
 Huguenot, derivation of, 198  
 Huningen, 548  
 Hyères, 493  
 st. Hyppolite, 562

## I.

If, 486  
 Ile des Faisans, 287  
 — de France, 583  
 — Jourdain, 338  
 Indre, 201  
 Indret, 171  
 les Infernets, 516, 517  
 Ingouville, 65  
 Ingrande, 211, 223  
 Inns, xxix  
 Inquisition in France, 257, 455

Iron Mask, the Man in the, 499

Isenheim, 564

Isère, river, 444, 511

Isigny, 323

l'Isle, 459

Isle, 579

— sur-Doubs, 564

Issoire, 402

Issoudun,

Issy, 113

Ivry, 388

— battle, 117

Izard, 238, 298

## J.

Jacquerie, 16

James II. at St. Germain-en-

Laye, 45

st. James, 255

Jargeau, 184

Jarnac, 230

Jaujac, 422, 432

st. Jean d'Angely,

— du Doigt, 132

— du Gard, 425

— de Luz, 285

Jean-sans-peur, 530

Jeanne d'Arc, at Rouen, 40 ;

at Patay, 177 ; souvenirs at

Orleans, 179 ; at Jargeau,

184 ; at Chinon, 203 ; at

Domrémy, 557 ; at Rheims,

578 ; at Compiègne, 584

Jeux Floraux, 253

Joigny, 385

Joinville, 550

Josephine, Empress, 44

Josselin, 142

Jouarre, 566

Jougne, 536

Jougon,

Jonx, Fort de, 535

Jouy aux Arches, 573

Joyeuse, 433

st. Julien, 195, 277, 425

Jumièges Abbey, 57

st. Julien, 249

Jura, 542

Jurançon, 290, 296

st. Just, 481

Juvigny,

Juvisy, 175

## K.

Kellermann, 570

Kersanton stone, 111, 134,  
144

Kilogrammes reduced to Eng-  
lish pounds, xvi

Kilomètres reduced to Eng-  
lish miles, xiv, xx.

Kistvaens, 109

## L.

Labarben, 484

Labadoyère, 509

Labourd, Pays de, 283

Labrit, 280

la Chalp, 521

Lac Bleu, 329

— d'Espingo, 323

— d'Estom, 309

— d'Oncet, 319

Lace, manufacture of, 78,  
406, 588

Lafayette, 403, 523

Lafoux, 470

Lafrey, 512

Lagnieux, 540

Lalande, 542

Lamartine, M. Alphonse de,  
340

Lamballe, 122

Lambert, 493

Lambesc, 495

La Mothe Fénelon, 250

Lanbader, 124

Landerneau, 125

Landes, 271, 274, 288

Landevan, 147

Landivisiau, 124

Landrecies, 589

Langeac,

Langeais, 204

Langogne, 423

Langoiron, 266

Langon, 266, 422

Langres, 547

Languedoc, 234, 251, 436

Lanleff, 111, 131

Lanmeur, 132

Lannemezan, 330

Lannion, 132

Laon, 592. Battle, 593

Laplace, 72

Larochejacquelin, 94, 159,

208, 213 ; his death, 216

Laruns, 298

Lasalle,

La Tour d'Auvergne, 141

Laura's tomb, 457

st. Laurent, 507, 534

— du Pont, 503, 504

Lanteret, Col de, 517

Laval, 119

Lavedan, Val, 305, 306

Lavelanet, 346

Lavoulte, 447

Ledignan, 425

Légué, 122

Lehon, 138

Lempde, 402, 412, 416

Lens, 590

Lescar, 290

Lescun,

Lescure, 104, 216

Lesdiguières, 511, 512

Lesneven, 134

Lesparre, 277

Lesponne, 320, 329

Lessay, 91

Lestelle, 304

st. Leu, 22

Leucate, 343

la Levée de la Loire, 189

Lezardrieux, 131

Libech, 488

Libourne, 262

Lieues de poste, xv

Lieuvin, 74

Liffre, 104

Ligny, 550

Lille, 590

Lillebonne, 55, 59

Lillers, 592

la Limagne, 361, 371, 393

Limetz, 50

Limoges, 247 ; Enamels, 248

— to Bordeaux, 261

Limonest, 390

Limousin, 235

Limoux, 346

le Lion d'Angers,

Lisieux, 74

Livres Tournois, 198

Livrons, 447

st. Lo, 104

Loches, castle of, 199

Locmariaker, 149

Lodève,

la Loge, 246

Loir river, 199

Loire river, 172

— A. Gien to Orleans, 183.

— B. Orleans to Tours, 184

— C. Tours to Nantes, 203

— below Nantes, 171

— source of the, 433

Loiret, 184

Longéac, 406

Longjumeau, 174

Longpont,

Longwy, 581

Lons le-Saulnier, 542

Lorient, 146

Loriol, 447

Lorraine, 545

Lombre,

st. Louis, 30, 221, 477, 548

Louis Napoleon, Prince, 585

Louis XI., 196

Louise Eléonore, Lord

Brougham's villa, near

Cannes, 499

Louise, Val, 522

Lourdes, 305

Louviers, 46

Louvigny,

Louvres, 583

Lowendahl, 246

la Lozère, 423

le Luc, 494, 498

Luchon, 331

Luciennes, 44

Luçon, 218

Lucques, 79

Lucey-le-Bois, 386

Lunel, 476

Lunéville, 548, 552

Lure, 548

Lusignan on the Vonne, 233

Luynes, 204, 252

Luz, 311

— to Gavarnie, 312



*Luz* to Barèges, 317

Luzarches, 6

Lyonnais, 352

LYONS, 372—383; Fourvières, 373; Cathedral, 374; Ainay, 375; Museum, 376; Pierre Scise, 378; P. Bellecour, 378. Siege of, 379. Inundation, 380. Fortifications, 381. Silk trade, 381

— to Avignon and Arles, 440

— to Besançon, by Bourg, 541

— to Geneva, by Nantua, 540

— to Grenoble and Chambéry, 502

— to Nice, by Grenoble, Digne, and Grasse, 515

— to Le Puy, Aubenas, St. Etienne, 420

Lys, Val de, 332

## M.

st. Maclou, Rouen, 36

Mâcon, 389

la Magdeleine, 251

Magistère, 264

Magny, 47, 368

Maguelonne, 480

Mailleraye-sur-Seine, 54

Mailly, 594

Maine, 217

Maintenon and its aqueduct, 155

Maison Carrée, 471

— Neuve, 247, 534

— Rouge, 247, 523, 553

Maisons, 30

st. Maixent, 233

Maladetta, 319, 321, 334, 335, 337

Malijay, 515

*Mallepostes*, xxiii

Malmaison, 44

st. Malo, 99

— to Nantes, 135

Mamet, 332

Manny, Sir Walter de, 147

Manosque, 514

*le Mans*, 158

Mansle, 228

Mantes, 31

Marans, 218

Marbore, 313, 315

Marcadaon, 302, 309

st. Marcellin, 510

Marché le Pot, 589

Marchiennes, 585

Marcillac, 418

Marcoing, 221

Marennas, 221

Mareuil, 218

Margaux, 276

Marguerite, Ile Ste., 499

— de Valois, 229, 264

st. Marie aux Mines, 562

stes. Maries, 468

Marignac,

Marigny, Enguerrand de, 38

Marlborough at Brest, 129

Marly, 44

Marman, Puy de, 401

Marmande, 265, 360

Marmoutiers Abbey, 193

Marot, 78, 251

Marquise, 9

st. Mars-la-Bruyère, 158

MARSEILLES, 484—490

Marseille-sur-Oise, 15

Martinvaast, 90

st. Martory, 339

Martres, 256, 339

Marvejols, 416

Massiac, 412, 416

Massillon, 494

st. Mathurin, 209

st. Matthew, Abbey of, 129

Maubeuge, 589

Mauléon, 244

Maupertuis,

st. Maur, 209

les Maures, 494, 498

st. Maurice, 162, 441

Mauris, 415

Mauves, 213

st. Maximin, 469, 498

Mayenne, river, 119

Mayet d'Ecole, 393

Mazères, 346

Meaux, 566

st. Médard, 262

*Médoc* and its wines, 274, 275, 277

Médous, 321

Mehun, 185

— sur-Yèvre, 356

Meillant, 360

la Meilleraye, 139

Melun, 383

Menars-le-Château, 185

Menat, 361

Mende, 423

ste. Menehould, 570

Menez Arrés hills, 106, 140

Menhirs, 99, 108, 133, 149

ste. Mère l'Eglise, 83

Méreville, 175

Merueys,

st. Merxheim, 563

Mesnil-sous-Jumièges, 54

MÈTRE, the, xii; Table of, reduced to feet, xiv

Mettray, 198

Metz, 571

— to Luxembourg, 582

Meudon, 113

Meulan, 30

Meung, 185

Meuse, river, 579

Meximieux, 540

Mèze, 480

Mezenc, Mt., 407

Mézières, 579

Mialet, 425

st. Michel-aux-Lions, 248

Michel, Mont St., 96

*Midi, Canal du*, 252, 259, 339, 481

Milán, 338

Milhau, 509

Mimat, 423

Mirabeau, 366, 486, 514, 535

Mirage, 468, 483

Mirande, 338

Mire,

Mirecourt, 558

Mistral, 437, 477, 488

Moirans, 510

Moissac, 263

Moisselles, 17

Molesme, 538

Molière, 188, 480

Monaldeschi, 364

Monceaux,

Moncountour,

Monestier, 517

— de Clermont, 514

*Money* of France, x

Monistrol, 422

Montagney,

Montaigne (Michel de), 263

Montaignu, 217, 329, 361

Montargis, 356

Montauban, 251

Montbard, 532

Montbazou, 223

Montbelliard, 565

Montbert, 429

Mont Blanc, 444

Montbrison, 411

Montbrun, 416, 429

Mont Dauphin, 520

Montdidier,

Mont Dol, 99

Mont Dore les Bains, 408

Mont d'Ours, 406

Montdragon, 451

Montélimart, 448

Montereau, 384

Montesquieu's château, 279

Montferrand, 276, 395

Montfort, Jean de, 147

— Simon de, 342, 462, 463

Mont Genève, 518

Montgolier, 428

Montigny, 588

Montivilliers, 66

Mont Jan, 211

Montlhéry, 176

Montlosier, 407

Mont Louis, 193, 351

— sur-Loire, 193

— Lozère, 423

Montluçon, 360

Montluel, 540

Montmajour, 463

Mont de Marsan, 280

Montmédy, 581

Montmirail, 549

Mont Mirat, 102

Montmorency, 22

Montmorillon, 232

*Montpellier*, 477  
*Montpensier*, Butte de, 393  
 — *Perdu*, 313, 317  
 — *Pertuis*, 422  
*Montpeyroux*, 401  
*Montpezat*, 432, 433  
 — *Pilas*, 427, 442  
 — *Pipet*, 441  
*Montpont*, 262  
*Montrejeau*, 330  
*Montrelais*, 212  
*Montreuil*, 115  
 — *sur-Mer*, 14  
*Montreval*, 475  
*Montricher*, 495  
*Montrodeix*, 397  
*Montrognon*, 400  
*Montrond*, 360, 426, 534  
 — *Salomon*, 441  
*Mont St. Michel*, 94, 96  
 — *Valérien*, 43  
*Mont-sous-Vaudrey*, 534  
*Mont St. Victoire*, 497  
*Morbihan*, 148  
*Moreilles*, 218  
*Moret*, 365  
*Morez*, 534  
*Morlaix*, 123  
 — *to Nantes*, 140  
*Mornas*, 451  
*Mortagne*, 118, 278  
 — (*Vendée*), 216  
*Mortain*, 103  
*Mortemer*, Abbey of, 48  
*Mortier*, Marshal, 587  
*Morvan*, 388, 391  
*Mosac*, or *Mosat*, 394  
*Moselle*, 568, 581  
*Mosquitoes*, 437, 451, 488  
*la Mothe Fénélon*, 250  
*Mouchard*, 535, 542  
*Moulineaux*, 53  
*Moulins*, 369, 430, 590  
 — *to Clermont and le Puy*, 393  
*Moyenvic*, 552  
*Münhausen*, 563  
*Mulberry*, 448  
*Munster*, 563  
*Murat*, 250, 412  
*la Mure*, 512  
*Muret*, 288, 339  
*Muriac*, 407  
*Murol*, 409  
*Mutzig*, 559  
*Myriamètre*, xii, xiv

## N.

*Nages*, 475  
*Nampont*, 14  
*Nancy*, 551  
 — *to Trèves*, 581  
*Nangis*, 523  
*Nanterre*, 44  
*NANTES*, 165—171  
 — *to Poitiers*, 213  
 — *to Rochelle and Bordeaux*, 217

*Nanteuil*, 573  
*Nantua*, 540  
*Narbonne*, 481  
 — *to Perpignan*, 343  
*Narcissa*, 478  
*Navarre*, 234  
 —, *château de*, 74  
*Navarreins*,  
*Nay*,  
*st. Nazaire*, 342, 480  
*Neauphle*,  
*st. Nectaire*, 410  
*Neff*, *Felix*, 513, 520, 521  
*Negreplisse*,  
*Nemours*, 366  
*Nérac*, 290  
*Néris-les-Bains*, 361  
*Ners*, 434  
*Neschers*, 410  
*Neufbrisach*, 563  
*Neufchâteau*, 558  
*Neufchâtel*, 28  
*Neuilly*, 43  
 — *sur Marne*, 549  
*Neuvy*, 367  
*Nevers*, 367  
*st. Nicolas*, 38, 552  
*Nicot*, 474  
*Niort*, 233  
*NISMES*, 470  
 — *to Alais and Aubenas*, 433  
 — *to Marseilles*, 482  
*Nivelle*, 285  
*st. Nizier*, 376  
*Noailles*, 250  
*Noè*, 339  
*Nogent-sur-Seine*, 524  
 — *le Rotrou*, 158  
 — *sur Vernisson*, 366  
*Noiretable*, 411  
*Noirlac*, 360  
*Noirmoutiers*, île, 171  
*Noisy*,  
*Nonancourt*, 117  
*Nord*, *Départ. du*, 587  
*NORMANDY*, 1—3. *Routes*, 3  
 — 105  
*Norrey*, 80  
*Nort*, 139  
*Nostradamus*, 463, 483  
*Nouvion*, 14  
*Noyades of the Loire*, 168  
*Noyon*, 584  
*Nuits*, 538

## O.

*Oberlin*, 559  
*Octeville*, 90  
*Odilienberg*, 561  
*Oissel*, 53  
*Oléron*, île d', 219  
*Olette*, 349, 351  
*Olivet*, 246, 327, 328  
*Ollioules*, 490  
*Oloron*, 295  
*st. Omer*, 3, 597

*Omonville*, 29  
*Oo*, *Lac d'*, 323  
*Orange*, 451  
*Orcières*, *Col d'*, 513, 521  
*Orgon*, 463, 495  
*Orival*, 53  
*ORLEANS*, 177  
 — *forest of*, 175  
 — *siege of*, 180  
 — *Maid of*, 179—181, 223  
 — *railroad to Paris*, 174  
 — *to Bourges and Clermont*, 356  
 — *to Gien*, 183  
 — *to Moulins and Lyons*, by *Bourges*, 361  
 — *to Toulouse*, 246  
*d'Orléans*, *Duc*, 43  
*Ornain*, 550  
*Orthez*, 289  
*Ossau*, *Val d'*, 295, 297  
*Ossoue*, 311  
*Ossuary*, 111  
*Oudon*, 213  
*Ouessant*, 9, 130  
*Oule*, 236, 313  
*Oullins*, 420

## P.

*la Pacaudière*, 371  
*Pacy-sur-Eure*, 73  
*Paimbœuf*, 171  
*Paimpol*, 131  
*Pain Bouchain*, 372  
*st. Palais*,  
*Palais du Roi*, 423  
*Palaiseau*,  
*la Palisse*, 371  
*le Pallet*, 213  
*Palons*, 521  
*la Palud*, 450  
*Pamiers*, 346  
*Panfou*, 384  
*Panticosa*, 301  
*Pantin*, 565  
*Paper manufacture*, 428  
*Paraclete*, church of the, 524  
*st. Pardoux*, 361  
*PARIS*, 17  
 — *to Brussels—Chemin de Fer du Nord*, by *Amiens*, *Arras*, *Douai*, and *Valenciennes*, 587  
 — *to Caen and Cherbourg*, 73  
 — *to Châlons*, by *Autun*, 391  
 — *to Dijon*, by *Troyes*, 523  
 — — by *Sens* and *Tonnerre*, 531  
 — *to Lille* by *Peronne* and *Arras*, 589  
 — *to Lyons*, *Route du Bourbonnais*, 362  
 — — *Route de Bourgogne*, 383



Paris to Metz and Forbach, 565  
 — to Mézières and Sedan by Rheims, 573  
 — to Mühlhausen and Bâle, 545  
 — to Nantes, 153  
 — to Orleans, 174. Railway, 175  
 — to Plombières, 557  
 — to Rennes, 113  
 — to Rouen (railway), 29  
 — to Rouen (railway), lower road, 43  
 — —, upper road, 47  
 — to Sceaux (railroad), 182  
 — to Strasburg, by Nancy, 548  
 — to Valenciennes, by St. Quentin and Cambrai, 583  
 — to Versailles (railroad), 113  
 Parthenay, 216  
*Passe Provisoire*, xvii  
 PASSPORTS AND POLICE, xvi, xix  
 Passy, 115  
 Patay, 177  
 st. Patrice,  
*Pau*, 291  
 — to Bagnères de Bigorre and de Luchon, 324  
 — to Campfranc in Spain, by Oloron and Val d'Aspe, 295  
 — to Caunterets and Bagnères, 304  
 — to Eaux-Bonnes and Eaux-Chaudes, 296  
 st. Paul, 263, 320  
 — de Dax, 280  
 Pavilly,  
 st. Pé, 305  
 Péage, 182  
 le Pecq, 44, 45  
 Pedauque, la Reine, 256  
 Pelacoy, 250  
*Pelvoux*, Mont, 501, 522  
 Pendentif, 445  
 st. Peray, 446. Wine, *ib.*  
 Perci, 93, 105  
*Perdu*, Mont, 313, 317  
 st. Père, 387  
 Périers, 91  
*Perigueux*, 261  
 Péronne, 589  
*Perpignan*, 343  
 — to Mont Louis and Puy-  
 cerda, 349  
 Perrache,  
 Perte du Rhône, 541  
 Perthus, 345  
 Petignac, 231  
 Petit Rhône, 464  
 Petrarch, 455, 457, 459, 460,  
 461  
 Peulvens, 108  
 Peyrada, 314

Peyrehorade, 289  
 Peyresourde, 322  
 Peyrolles, 514  
 Peyruis, 514  
 Pezenas, 480  
 Phalsbourg, 553  
 Picade, port de, 333  
 Pic de Bergons, 311, 312  
 — Génos, 323  
 — Gers, 302  
 — du Midi de Bigorre, 292,  
 319  
 — du Midi d'Ossau, 290, 297  
 Picquigny, 18  
 Pierre Châtel, 539  
 — de Couars, 392  
 st. Pierre le Montier, 368  
 — Ecrite, 391  
 — les Eglises, 74, 75  
 Pierrefitte, 306, 322  
 Pierrelatte, 450  
 Pilas, Mont, 427, 442  
 Pimené, 314  
 le Pin, 484  
 Pique, valley of the, 331  
 Pithiviers, 177  
 Plantagenet, 106  
 Plessis les Tours, 196  
 Pleyben, 144  
 Ploërmel, 153  
 Plomb de Cantal, 413  
 Plombières, 558  
 Plouarzel, 129  
 Plougastel, 130  
 Plouha, 131  
 Podensac, 266  
 Poissy, 30  
*Poitiers*, 224. Battle of, 227  
 — to Châteauroux, 232  
 — to Rochefort by Niort,  
 233  
 Poix, 14  
 st. Pol, 4  
 — de Léon, 133  
 Polignac, 403, 585  
 Poligny, 534  
 Polminhac, 414  
 Pomard, 538  
 Pommereau, port de, 336  
 Pommereval, 28  
 Pompadour, 249  
 Pompidou, 425  
 Pompignan,  
 Pons, 222  
 Ponsas, 443  
 Pontacq,  
 Pont-à-Mousson, 581  
 Pontarlier, 535  
 Pont Audemer, 71  
 Pontchâteau, 411  
 Pontcharra, 511  
 Pont d'Ain, 540, 542  
 Pont du Beauvoisin, 503  
 Ponts de Cè, 210  
 Pont Flavien, 500  
 Pont de l'Arc, 433  
 — de l'Arche, 32  
 — du Château, 411  
 — d'Espagne, 309

PONT DU GARD, 469  
 — de Montvert, 423  
 — de Pany, 533  
 Pontgibaud, 400  
 Pontigny, 386, 531  
 Pontius Pilate, 443  
 Pontivy, 141  
 Pont l'Evêque, 72  
 — le Roi, 524  
 Pontoise, 22  
 Pont Orson, 95  
 Pontoux, 228  
 Pont St. Esprit, 450  
 — St. Maxence, 589  
 — Scorff, 146  
 Pontrieux,  
 Pont sans Pareil, 3  
 Pont-sur-Yonne, 384  
*Popes* at Avignon, 454  
 st. Porchaire, 221  
 Pornic, 171  
 Port de Lannay, 143  
 Port-Royal des Champs, 153  
 Port-sur-Saône, 548  
 — Vendres, 345  
 Portets, 343, 266, 338  
 Portillons, 236  
 Ports, 236  
 Poste aux ânes, 441  
*Posting* in France, xx  
 Pouges, 367  
 Pouilly, 367, 426  
 Poulahouan, 141  
 st. Pourgain, 393  
 Poussin, Nicolas, 51  
 Pouy, 280  
 Pradelles, 422  
 Prades, 350, 432  
 Pratz de Mollo, 350  
 Preignac, 266  
 Presigny,  
*Pretender* (the), 133, 168  
*Privas*, 429  
 st. Privast, 423  
 Privat d'Allier,  
 PROVENCE, 436  
 Provins, 523  
 Pugère, 497  
 Puiseux, 17  
 Pujols,  
 Puleaux,  
 Puttelange,  
*le Puy*, 404  
 Puy du Chopine, 400  
 — de Cliersou, 399  
 — Come, 400  
 — de Dôme, 397  
 — Girou, 399  
 — du Grand Sarcouy, 400  
 — Gravenoire, 399  
 — Grion, 413  
 — Marman, 401  
 — Pariou, 398  
 — la Poix, 400, 411  
 — Tartaret, 410  
 Puylaurens,  
 Puymaurins, 319  
 Puyoo, 289  
 PYRENEES, 234, 304, 32', 324

Routes, 80, 82, 83, 85, 86,  
87, 91, 94, 97, 98  
PYRENEES, directions for tra-  
velling, 241, 246  
— *the Eastern*, 346, 351  
— Marbles of the, 327

## Q.

Quélern, 129, 144  
*st. Quentin*, 585  
— in Normandy, 101  
Querqueville, 89  
Quesnoy,  
Quevilly, 53  
Queyras, Val, 520  
Quiberon, 151  
Quilleboënf, 54  
Quimper, 144  
Quimperlé, 145  
Quinéville, 83  
Quinipily, Venus of, 147

## R.

Rabastens, 338  
Rabelais, 113, 203, 478  
Rachet, 507  
Racine, 154, 573  
Raillère, 308  
RAILROADS, xxvii  
— Bordeaux to La Teste,  
271  
— Lille to Courtrai, 591  
— Lyons to St. Etienne,  
420  
— Montpellier to Cette, 479  
— Nismes to Beaucaire, 482  
— Paris to Corbeil, 175  
— to st. Germain, 44  
— to Orleans, 175  
— to Rouen, 29  
— to Versailles, 113  
— Roanne to St. Etienne,  
372, 427  
— Strasburg to Bâle, 560  
Raismes, 588  
*st. Rambert*, 443  
Rambouillet, 154  
la Rance, river, 135  
Rancié, mines de, 347  
Rancogne, Grottes de, 228  
Randan, 371  
Randanne, 407  
Raz, Pointe du, 145  
Ré, Ile de, 219  
Rébenac, 297  
la Recousse, 3  
Redon, 143  
Reignac, 231  
Remiremont, 558, 559  
Remoulius, 469  
*st. Remy*, 463  
Renaissance, style, 166, 179,  
188, 194, 445, 528  
René d'Anjou, 496  
*Rennes*, 121  
— to Brest, 122  
— to Vannes, 153

la Réole, 265  
Rethel, 579  
de Retz at Nantes, 167  
*Rheims*, 575  
— to Luxembourg, 580  
Rhins, 426  
RHÔNE, 439  
— the Haut, Aix to Lyons,  
539  
— Junction with the Saône,  
440  
— Lyons to Avignon and  
Arles, 440  
— Perte du, 541  
Rhuys, 149  
Ribbon manufacture, 426, 427  
*st. Ribeaupillé*, 562  
Richard Cœur-de-Lion, 35 ;  
death of, 261  
Richebourg, 536  
Richelieu, 44, 218  
Rienzi at Avignon, 455  
Riom, 394  
*st. Riquier*, 14  
Rive de Gier, 421  
Rivesaltes, 343  
Roanne, 371  
— to St. Etienne (Rail-  
way) and Valence, 425  
Robert the Devil, 54  
la Roche-sur-Yonne, 217  
la Roche Bernard, 152  
— Guyon, 49  
— Maurice, 124  
Roche Corbon, 193, 391  
— Cotte, 204  
— Courbe, 447  
— Taillée, 391, 443  
Roche fort, 211, 220, 407  
la Rochefoucauld, 228  
*la Rochelle*, 218  
la Roche Jagu, castle, 131  
Rochemaure, 448  
le Rochepot, 388  
les Rochers, 120  
Rocroy, 580  
*Rodez*, 417  
Rohan, 142, 425  
Roland, Camisard chief, 355,  
424, 425, 435, 474  
— the Girondist, 48  
— the Paladin, 313  
Rolleboise, 49  
Rollo, the pirate, 47  
*st. Romain*, 41, 390  
— de Colbosc,  
Roman remains, 439, 442,  
452, 465, 467, 473, 500  
Romanche, Val, 516  
Romanèche, 390  
Romanée, 536  
Romanesque style, 111, 166,  
268, 443, 463, 475  
Romans, 510  
Romilly, copper works, 52  
Romorantin,  
Roncesvalles, 238  
Roquefavour, aqueduct of,  
495

Roquefort, 279, 291 ; Cheese,  
418  
Roquemaure, 452  
Roscoff, 133  
Rosieres,  
les Rosiers, 209  
Rosny, Château, 31  
Rosporden, 145  
Rostrénen,  
Roubaix, 591  
ROUEN, 33, 43  
— to Alençon, 70  
— to Caen, 70  
— to Havre, 53, 56 ; by  
Yvetot, 60  
— to Orleans, 182  
— to Paris (Railroad), 29,  
43  
Rouffach, 563  
Rougemont,  
Rouilly,  
Roupy, 585  
Rousseau, 22, 573  
les Rousses, 534  
Roussillon, 234, 343  
Rouvray, St. Etienne de, 53  
Royan, 278  
Royat, 399  
Ruel, 44  
Ruelle, 228  
Ruffec, 228  
Ruines,  
Rumengol, 143

## S.

Sablé, 160  
les Sables, 218  
le Sage, birth-place of, 150  
— his death, 12  
Saintes, 221  
Salbris, 246  
Salces, 343  
Salins, 535  
Salles Comptaux, 418  
Sallies, 289  
Salon, 483  
Samer, 14  
Sanadoire, 410  
Sancerre, 367  
Sancy, Pic de, 408, 409  
Sandrupt, 550  
SAÔNE, *River*, Châlons to Ly-  
ons, 388 ; junction of, with  
Rhône, 440  
Sapey, 506  
Sarrebouurg, 553  
Sarzeau, 150  
Sassenage, 507, 509  
le Saulce, 513  
Saulieu, 388  
le Sault, 539  
Saumur, 206  
Sauterne, 279  
Sauveterre, 289  
*st. Sauveur les Bains*, 240,  
311, 312  
— le Vicomte, 83, 91



Savenay, 152  
 Savenières, 211  
 Saverdun, 346  
 Saverne, 553  
 Savigny, Abbey, 104; village, 176  
 st. Savin, 232, 306  
 Scarron, 159, 160  
 Sceaux, 183  
 Scheldt, 586  
 Schirmeek, 559  
 Schlestadt, 561  
 Schön, Martin, 562  
 Schwartzenberg, 546  
 Scorpions, 438  
 Seculéjo, 323  
 Sédan, 580  
 Séez, 70  
 Seignelay,  
 la Seilleraie, 213  
 SEINE RIVER, rise of, 527  
 ——— Paris to Rouen, 43  
 ——— Rouen to Havre, 53  
 Selles-sur-Cher, 189  
 Semur, 533  
 Senlis, 583  
*Sens*, 384  
 Sept Laux, 516  
 st. Sernin, 254  
 Serres, 515  
 st. Servan, 99  
 Servières, 410  
 st. Sever, 33, 38  
 Sévignac, 297  
 Sévigné, Mad. de, 120, 154, 167, 213, 449  
 Sèvre Nantaise, 217  
 ——— Niortaise, 218  
 Sèvres china, 115  
 st. Seyne, 527  
 Seyssel, 539  
 Sézanne, 549  
 Sierck, 582  
 Sièyes, 498  
 Sigean, 343  
 Silkworm, 448  
 Silk manufacture, 430, 431  
 Sillery, 593  
 ——— Champagne, 593  
 Sisteron, 513  
 Skeleton Tour of France, xxxix  
 Soap manufacture, 488  
 Soissons, 573  
 Solesmes, 160  
 Soligny, 118  
 la Sologne, 246  
 Sommesous, 549, 594  
 Sommières,  
 la Sône, 510  
 Sorgues, 453, 459  
 Sorigny, 223  
 Sotteville,  
 Souchez, 592  
 Sault, Marshal, 260, 283  
 la Source du Loiret, 182  
 Souvigné, 104  
 Souvigny, 369  
 Souzéc, 206

Soyons, 447  
 Steam boats, xxviii  
 Stenay, 581  
 STRASBURG, 553, 557; Pâtés, 556  
 ——— to Bâle (Railroad), 560  
 ——— to Besançon, by Colmar, 564  
 ——— to Epinal, 559  
 Succinio, 150  
 Suchet, Marshal, 461  
 Sully, 31, 183; his castle, 158; his grave, *ib.*  
 ——— town and castle, 183  
 Sulz les Bains, 559  
 Sulzbad, 563  
 Suzon, Val de, 527  
 Symphorien-en-Lay, 372

## T.

Tables d'hôte, xxix  
 Taillebourg, 221  
 Tain, 444  
 Talbot's death, 263  
 Tallard, 513  
 Talleyrand's residence at  
 Valengay, 189; his tomb, *ib.*  
 Tamarville, 83  
 Tancarville, 55  
 Tanlay, 532  
 Tarare, 372  
 Tarascon, 461, 462  
 ——— (Ariège), 347  
*Tarbes*, 324  
 Tarn, 419, 424  
 Tartas, 280  
 Tencin, 511  
 Teste de Buch (Railway), 271  
 Tet, 343, 350  
 Thau, Etang de, 479  
 Thann (Alsace), 564  
 ——— near Cien, 79  
 Theatres, Roman, 59  
 ——— at Arles, 465  
 ——— at Orange, 452  
 Theil, 531  
 Théogonec, 124  
 Thiers, 411  
 Thiezac, 414  
 Thionville, 581  
 Thorigny,  
 Thouars,  
 Thourie, 139  
 Thueyts, 422, 432, 433  
 Tiffauges, 215  
 Tinchebray, 103  
 Tocqueville, 67, 85  
*Toises* reduced to feet, xv  
 Toissey, 390  
 Tomblaine, 94, 98  
 Tonnay Boulon,  
 ——— Charente, 221  
 Tonneins, 265  
 Tonnerre, 532  
 Tonquedec, 132  
 Torfou, 215

Torigni, 105  
 Torte, 302, 303  
 Tôtes, 29  
 Toul, 548, 550  
*Tou'ou*, 493; siege, 491  
*Toulouse*, 252—261; battle of, 259  
 ——— to Auch and Pau, 337  
 ——— to Bagnères, 338  
 ——— to Bordeaux, 263  
 ——— to Foix, 346  
 ——— to Narbonne, 339  
 Touraine, 172  
 Tour de Bellot, 434  
 ——— en Bessin, 82  
 ——— du Carol, 349  
 ——— de Cordouan, 278  
 ——— du Pin, 502  
 Tourlaville castle, 85  
 Tourmalet, 317, 319, 320  
 Tournay, 595  
 Tournebride, 213  
 Tournoëlle, 395  
 Tournon, 444  
 Tournous, 389  
*Tours*, 193, 198  
 ——— to Chinon and Saumur, 201  
 ——— to Loches, 199  
 ——— to Nantes, 203  
 ——— to Poitiers and Bordeaux, 223  
 Tourves, 497  
 Tourville, 33  
 Toussaint l'Ouverture, 535  
 Tramesaignes (Val d'Aure), 320, 322  
 la Trappe près Soligny, 118  
 Trappist Convents, 90, 118, 139  
 Tréguier, 132  
 Tremblay,  
 Treport, 70  
 Trèves, 209  
 Trévoux, 390  
 Tricherie, 224  
 Triel, 30  
 Troarn, 72  
 Trouille, 467  
 Troumouze, 314  
 Trouville, 72  
*Troyes*, 525; Treaty of, *ib.*; weight, 526  
 Tulle, 249  
 Tullins, 510  
 Turcoing, 591  
 Turenne, 250  
 ——— Marshal, 580, 596  
 Turpin, Archbishop, 577

## U.

Ubaye,  
 Uchau, 476  
 Urdos, 296  
 Uriage, 509  
 Urtubi, 286  
 Urugne, 286  
 Ussat, 348

Ussel,  
 Utrecht, Treaty of, 596  
 Uzerche, 249  
 Uzès, 435

## V.

st. Vaast la Hougue, 84  
 Vaison, 452  
 Val d'Ante, 101  
 — d'Ossau, 295, 297  
 Valengay, 189  
*Valence*, 444  
 — to Aubenas, Privas, and  
 Nismes, 429  
 — to Grenoble, 509  
*Valenciennes*, 588  
 Valérien, Mt., 43  
 st. Valery-sur-Somme, 18  
 Vallery en Caux, 67  
 Vallery, 385  
 st. Vallier, 443  
 Vallière, Mad. de la, 45  
 Valliquerville,  
 Vallons, 433  
 Valmy, 570  
 Valognes, 83  
 Vals, 353, 430, 431, 443  
 Vandamme, General, 595  
 Vannes, 152  
 Vanvres, 113  
 Var, 499  
 Varades, 212  
 Varennes, 370, 570  
 la Vattay, 534  
 Vaubadon, 104  
 Vauban, Marshal, 86, 125,  
 281, 556, 590  
 Vaucanson, 510  
 Vaucelles, 77  
*Vaucluse*, 458, 459  
 Vaucouleurs, 558  
 Vaudémont, 551  
 Vaudencourt,  
 Vaudreuil, 47  
 le Vaunage, 475  
 Vaux de Vire, 103  
 Vauxhall, 77  
 Vayres,  
 Velaine, 551  
 le Velay, 406, 422  
*Venasque*, 335; Port de,  
 331, 333, 335  
 Vendéans at Granville, 91  
 — at Laval, 120  
 — at le Mans, 159  
 — at Nantes, 170  
 — at Saumur, 208  
 — at Savenay, 152  
 — at St. Florent, 212  
*la Vendée*, 120, 172, 216  
 Vendôme, 199  
 Vendres, Port, 345

Vénérand,  
 Venin, la Tour, st., 509  
 Venos, 516  
 Ventoux, Mont, 450, 461  
 st. Veran, 520  
 Verberie, 583  
 Verdigris, manufacture of, 479  
 Verdun, 570  
 Veretz, 204  
 Vergy, 534  
 Vermanton, 386  
 Vernet, 351  
 — Ilorace, 457  
 Verneuil, 117  
 Vernon, 32  
 la Verpillière, 502  
 Verrières,  
 Versailles, 116  
 Verteuil,  
 Vertrieux, 540  
 Vervins,  
 Vesaignes, 547  
 Vesoul, 548  
 Vexin, 47  
 Vézelay, 386  
 Vezénobre, 434  
 Vicdessos, 347  
 Vichy Baths, 370  
 Vic-sur-Cère, 414  
 Vic le Comte,  
 Vidauban, 498  
 Vieille-Brioude, 402  
 Vienne, 441  
 — to Grenoble, 502  
 Vierzon, 246, 356  
 Vif, 514  
 Vigan, 419  
 Vignecourt,  
 Vignemale, 310  
 Vigny, 47  
 Vilaine, river, 121  
 Villandraut, 266  
 Villards,  
 Villars, 355, 369, 474, 587  
 — d'Arène, 517  
 — Bocage, 102  
 Villebaudon, 105  
 Villebon, 158  
 Villedieu les Poêles, 105  
 — du Perron, 233  
 Villefranche, 340, 351  
 — sur-Saône, 390  
 — (Aveyron), 415  
 Villejuif, 362  
 Villeneuve lès Avignon, 458  
 — St. George, 383  
 — la Guiard, 384  
 — de Marsan, 291  
 — le-Roi, 175, 385  
 Villers-Cotterets, 573  
 la Villette, 573  
 Ville Vallier, 385  
 Villiquier, 54  
 Viré, 102

Virey,  
 Viroflay,  
 Viry, 175  
 Viso, Monte, 520  
 la Vista, 484  
 la Vitarelle, 263, 423  
 Vitré, 120  
 Vitry le Français, 548, 549  
 Vivarais, 352, 431  
 Viviers, 346, 449  
 Vizille, 511  
 Void, 550  
 Voiron, 503  
 Volane, 431  
 Volcanoes, extinct, of Au-  
 vergne, 352  
 Volnay, 538  
*Voltaire*, 30, 174, 183, 259,  
 547  
 Volvic, 394  
 Voreppe, 503  
*Vosges* mountains (Routes  
 168, 170), 545, 559, 560, 562  
 Voué, 594  
 Vougeot, Clos de, 537  
 la Voulte, 445  
 Vouziers, 580

## W.

Waldbach, 560  
 Waldersbach, 559  
 st. Wandrille, 58  
 Wasselonne, 553  
 Weights and measures, xii—  
 xvi  
 Wellington, Duke of, 161; in  
 the Pyrenees, 239, 260,  
 286; at Bayonne, 281  
 Wimereux,  
 Wimille, 9  
 Wissant,  
 Witsand, 9

## X.

Xantrailles, 290  
 Xertigny, 558

## Y.

Yèvre, 356  
 Yonne, river, 386  
 Young, the poet, 478  
 st. Yrieix, 249  
 Yssingeaux, 422  
 Yvetot, 61; Roi d', *ib.*

## Z.

Zabern, 553

THE END.





# MAP OF FRANCE


to accompany the  
HANDBOOK OF FRANCE

Mallevaste Roads ———  
Fast & Diligence D° ———  
Cross D° ———

✓ NB The figures attached to the names of places  
refer to the Routes in the Handbook under which  
they are described

Railways completed ———  
in progress ———







THE  
HAND-BOOK ADVERTISER,  
1850.

*Printed for those desirous of communicating Information to Travellers, and inserted in*

MURRAY'S HANDBOOKS FOR TRAVELLERS,  
ISSUED DURING THE SEASON.

*\*\* Advertisements are received till the end of May; the Editor is not responsible for any statements made in them.*

SCALE OF CHARGES:—

	£	s.	d.		£	s.	d.
For Eight Lines . . . .	0	8	6	Half a Column . . . .	1	2	0
Every Line additional . .	0	0	9	A Column, or Half-page .	2	2	0
An entire Page . . . . .	£4	0	0				

INDEX TO ADVERTISEMENTS.

GERMANY.

FRANKFORT.—Tacchi's Glass Warehouse 6  
                  Bing's Fancy Warehouse . 7  
MUNICH.—Hermann's Magazine of Fine  
                  Arts . . . . . 8  
                  Steigerwald's Glass Rooms . 9  
COLOGNE.—Farina's Eau de Cologne . . 10  
INNSBRUCK.—Hotel D'Autriche . . . 12  
BONN.—Schmitz's Golden Star Hotel . 13  
LEIPZIG.—Weigel's Old Book Dépôt . 18  
NUREMBERG.—Mr. Schrag, Bookseller . 23

AUSTRIA.

VIENNA.—Stammer's Magasin de Bronze 22

SWITZERLAND.

GENEVA.—Hôtel des Bergues . . . . 11

ITALY.

FLORENCE.—Bianchini's Mosaic Orna-  
                  ments . . . . . 8  
LEGHORN.—Micali's Marble Dépôt . . 11  
GENOA.—Loleo's Fancy Warehouse . . 11  
PISA.—Hotel de la Grande Bretagne . 19  
NICE.—Musso's London Dispensary . 19  
VENICE.—Micheli's Grand Hotel . . . 22  
ROME.—Mr. Bonfigh—Lessons in Italian 22

MALTA.

Steam Communication with India . . 16

ENGLAND.

List of Customs' Duties . . . . . 2  
Custom House Agents—McCracken . . 4  
Union Bank of London . . . . . 14  
Locock's Pulmonic and Female Wafers 15  
Black's Guide Books . . . . . 17  
Hunt—Cure of Stammering . . . . 18  
Graham's Domestic Medicine . . . . 18  
Layard's Nineveh, and its Monuments . 19  
Marryat's Pottery and Porcelain . . . 19  
Handbook for England and Wales . . 20  
                  London and its Environs 20  
Murray's List of Standard Works . . 21  
Le Page's French Prompter . . . . 22  
Del Mar's Spanish Elementary  
                  Works . . . . . 22  
Spiers and Son's Establishment . . . 22  
The London and Westminster Bank . 23  
The Book of Common Prayer . . . . 23  
Lee's Guide-Book Dépôt . . . . . 24

# LIST OF DUTIES

PAYABLE IN LONDON ON WORKS OF ART, CURIOSITIES, ETC.,  
FROM THE CONTINENT,  
ACCORDING TO THE LAST NEW TARIFF.

*There is an Addition of 5 per cent. on those Duties not altered by the last New Tariff*

## The following are all FREE OF DUTY:—

CATTLE, and all Living Animals.	MANUSCRIPTS.
AGATES and CORNELIANS, <i>not</i> being set nor cut.	MAPS and Charts, or parts thereof, plain or coloured.
BRONZE Works of Art.	MINERAL WATER.
BULLION, Coins and Medals of all kinds, and battered Plate.	MODELS of Cork and Wood.
CASTS of Busts, Statues, or Figures.	OLIVE OIL.
COTTON Manufactures, <i>not</i> being articles wholly or in part made up.	PLANTS and Trees, alive.
DIAMONDS and other Precious Stones, <i>not</i> set.	PICTURES, Sketches, Drawings, or Sculpture, on a declaration by the Proprietor (being a British Subject) that they are of his or her performance, and not intended for sale.
FLOWER ROOTS.	SEEDS, Garden, Forest, &c.
FURS and SKINS, <i>not</i> made up.	SPECIMENS of Natural History, Minerals, Fossils, and Ores.
LINEN Manufactures, <i>not</i> being articles wholly or in part made up.	SULPHUR Impressions or Casts.
LAY Figures belonging to British Artists, intended for their own use.	TELESCOPES.
MAGNA GRÆCIA Ware, and Antique Earthen Vases, &c.	VASES, Ancient, not of Stone or Wood.

## On the following the Duty is 10 per cent. ad valorem:—

AGATES, or Cornelians, cut, manufactured, or set.	EGYPTIAN Antiquities, Nubian Spears, &c.
BEADS, Coral, Mock Pearl, and others.	FRAMES for Pictures, &c.
BRASS and BRONZE Manufactures, <i>not</i> being works of Art, such as Inkstands, Candelabra, and Articles of Furniture.	FURNITURE.
BROCADE of Gold and Silver.	FURS and SKINS, all Articles made up.
CARRIAGES of all sorts.	JAPANNED and Lacquered Ware.
CASHMERE SHAWLS, and other Articles and Manufactures of Goats' Wool.	JEWELLERY.
CATLINGS (Violin, Harp Strings, &c.) whether Plain or Silver Strings.	LACE, viz.—Thread Lace, also Lace made by the hand commonly called Cushion or Pillow Lace, whether of Linen, Cotton, or Silken Thread.
CHINA, or Porcelain Ware, painted or plain, gilt or ornamented, and Earthenware.	LINEN Articles, wholly or in part made up.
CLOCKS and WATCHES (must have Maker's name, both on face and on works).	MOSAIC Work, small Ornaments for Jewellery.
COLOURS for Painters, if manufactured, and Crayons.	MUSICAL Instruments.
COPPER PLATES engraved, and Copper Manufactures.	PERFUMERY.
COTTON Articles, wholly or in part made up.	SCAGLIOLA Tables.
	SPA Ware.
	STEEL and IRON Manufactures.
	TILES.
	TOYS.
	TURNERY.
	WOOLLEN Articles, wholly or in part made up.

Plate of Gold or Silver, gilt or ungilt, in addition to 10 per cent., is liable to 1s. 6d. per oz. Stamp Duty.



LIST OF DUTIES—*continued.*

		£	s.	d.
ALABASTER, Sculpture of .....	the cwt.	0	3	0
ANCHOVIES .....	the lb.	0	0	2
ARQUEBUSADE WATER (for the Bottles, see WINE) .....	the gal.	1	10	4
BOOKS, of Editions printed prior to 1801 .....	the cwt.	1	0	0
"          in or since 1801, in Foreign Living Languages.....	ditto	2	10	0
"          in the Dead Languages, or in the English Language, printed out of England in or since 1801 .....	ditto	5	0	0
(N.B.—Pirated Editions of English Works, of which the Copyright exists in England, totally prohibited since 1st April, 1843.)				
BOOKS, English, printed in England (unless declared that no Excise Drawback was received on Exportation) .....	the lb.	0	0	3
BOOTS, Ladies' untrimm'd.....	the doz. pair	0	6	0
"    Men's ditto .....	ditto	0	14	0
SHOES, ditto ditto .....	ditto	0	7	0
"    Ladies' ditto .....	ditto	0	4	6
CAMEOS .....	for every £100 value	5	0	0
CIGARS and TOBACCO, manufactured (3lbs. only allowed for passenger's baggage) .....	the lb.	0	9	0
TOBACCO, unmanufactured .....	ditto	0	3	0
(N.B.—Unmanufactured Tobacco cannot be imported in less Quantity than 300lbs., or Cigars 100lbs. in a package; but small quantities are admitted for Private Use on Declaration and payment of a Fine of 1s. 6d. per lb. in addition to the Duty.)				
COFFEE, Mocha, and other Foreign Coffee .....	the lb.	0	0	6
"    from British Possessions .....	ditto	0	0	4
COINS, of Copper .....	the cwt.	0	10	0
CONFECTIONERY, Sweetmeats, and Succades.....	the lb.	0	0	6
CORDIALS and LIQUEURS (for Bottles, see WINE).....	the gal.	1	10	4
EAU DE COLOGNE, in long Flasks .....	the flask	0	1	0
(N.B.—If other than the ordinary long Flasks, 30s. 4d. the Gallon and the Bottle Duty.)				
EMBROIDERY and NEEDLEWORK .....	for every £100 value	15	0	0
FLOWERS, Artificial.....	ditto	25	0	0
GLASS, Flint or Cut, Coloured and Fancy Ornamental Glass, of whatever kind .....	the lb.	0	0	2 <sup>1</sup>
GLASS, White Flint Bottles, not cut nor ornamented.....	ditto	0	0	0 <sup>1</sup>
"    Wine Glasses, Tumblers, and all other White Flint-Glass Goods, not cut nor ornamented .....	the lb.	0	0	1
GLOVES, Leather (not less than 100 doz. pairs can be imported in one package) .....	the doz. pair	0	3	6
MACCARONI and VERMICELLI .....	the lb.	0	0	1
MARBLE, manufactured .....	the cwt.	0	3	0
Sculptured Stone.....	the ton	0	10	0
NAPLES SOAP .....	the cwt.	1	0	0
OLIVES .....	the gal.	0	2	0
PAINTINGS on GLASS, or Figured Glass.....	the superficial foot	0	0	9
PAPER-HANGINGS, Flock Paper, and Paper printed, painted, or stained .....	the square yard	0	0	2
PICTURES .....	each	0	1	0
"    and further .....	the square foot	0	1	0
"    being 200 square feet and upwards.....	each	10	0	0
PRINTS and DRAWINGS, plain or coloured, single .....	ditto	0	0	1
"          bound or sewn .....	the doz.	0	0	3
SAUSAGES .....	the lb.	0	0	1
SILK, MILLINERY, Turbans or Caps .....	each	0	3	6
"    "    Hats or Bonnets.....	ditto	0	7	0
"    "    Dresses.....	ditto	1	10	0
"    HANGINGS, and other Manufactures of Silk .....	for every £100 value	15	0	0
"    VELVETS, plain or figured .....	the lb.	0	9	0
"    "    Articles thereof .....	ditto	0	10	0
STONE from Malta .....	the ton	0	1	0
TEA.....	the lb.	0	2	1
WINE in Casks, all except Cape Wine.....	the gal.	0	5	6
"    in Bottles, .....	ditto	0	5	6
"    and further on the Bottles .....	the cwt.	0	0	9
SPIRITS in Casks (no Cask can be imported of less contents than Twenty Gallons).....	the gal.	0	15	0
SPIRITS in Bottles (the additional Duty on the Bottles, as on Wine Bottles.)				

# MESSRS. J. & R. M<sup>c</sup>CRACKEN,

7, OLD JEWRY, LONDON,

AGENTS, BY APPOINTMENT, TO THE ROYAL ACADEMY,

*And Agents generally for the Reception and Shipment of Works of Art,  
Baggage, &c.,*

FROM AND TO ALL PARTS OF THE WORLD,

RETURN their sincere acknowledgments to the Nobility and Gentry for the liberal patronage hitherto conferred on them. They hope, by the moderation of their charges, and their unremitting care in passing through the CUSTOM-HOUSE Property confided to them, to merit a continuance of the favours they have heretofore enjoyed. Their establishment comprises dry and spacious Warehouses, where Works of Art and all descriptions of Property can be kept during the Owner's absence, at most moderate rates of rent.

J. & R. M<sup>c</sup>C. undertake to execute Commissions, for the purchase of Pictures, Statuary in Marble and Alabaster, Bronzes, &c., being in direct correspondence with Artists, Agents, and Bankers throughout the Continent.

British Artists resident abroad, having occasion to send home their Works for Exhibition, or to be passed by the Academy, will find it advantageous to address them to the care of Messrs. J. and R. M<sup>c</sup>CRACKEN, whose appointment enables them to offer every facility.

Parties favouring J. & R. M<sup>c</sup>C. with Consignments, are requested to be particular in having the Bills of Lading sent to them direct by post, and also to forward their Keys with the Packages, as all Goods must be examined immediately on arrival.

J. & R. M<sup>c</sup>C. keep Lachrymæ Christi and Marsala Wines of first quality, also Port and Sherry; and are general Importers of French and other Foreign Wines.

## THEIR PRINCIPAL CORRESPONDENTS ARE AT

CALAIS.....	{ Messrs. CHARTIER, MORY, & VOGUE.
	{ Messrs. ISAAC VITAL & fils.
BOULOGNE S. M....	Messrs. CHARTIER, MORY, & VOGUE. Mr. H. SIRE.
	Mr. M. CHENUE, Packer, Rue Croix Petits Champs, No. 24.
	Mr. C. M. STOCK, Wine Merchant, 17, Boulevard de la Madeleine
PARIS .....	Mons. HAVET, Roulagier, 10, Rue Grange Batelière.
	" Petit fils aîné, id., 23, Rue de la Concorde.
	" H. WOOD, 3, Place des Victoires, and at <i>Dunkerque</i> .
	Messrs. H. WATERTON & Co., 36, Rue Basse du Rempart.
HAVRE .....	Mr. A. CHAUMONT, Mr. THOMAS TAYLOR, Messrs. P. DEVOT & Co.
	Messrs. HORACE BOUCHET & Co.
MARSEILLES.....	{ Messrs. BROCHIER & GUILLABERT.
	{ Messrs. ANDRÉ & ABEILLE.
BAGNERES DE BI- GORRE, (Hautes Pyrénées) .....	{ Mr. AINÉ GÉRUZET, Marble Works.
BORDEAUX .....	Mr. AINÉ GÉRUZET, 44, Allées de Tourny.
GIBRALTAR .....	Messrs. ARCHIBOLD, JOHNSTON & POWERS.
NICE .....	Messrs. A. LACROIX & Co., British Consulate.
GENOA .....	Messrs. GIBBS & Co.; Mr. A. G. BARCHI, British Vice-Consulate.
MILAN .....	Messrs. BUFFET & BERUTO, Piazzale di S. Sepolero, No. 3176.
CARRARA .....	Mr. VINCENZO LIVY, Sculptor.
	Messrs. W. MACBEAN & Co. Messrs. G. H. GOWER & Co.
	Messrs. PETER SENN & Co. Messrs. HENDERSON BROTHERS.
	Messrs. MAQUAY, PAKENHAM, & SMYTH.
LEGHORN .....	{ Messrs. GIAC <sup>o</sup> . MICALI & FIG <sup>o</sup> . Sculptors in Alabaster and Marble.
	{ Mr. M. RISTORI. Mr. JOSEPH GUANO. Mr. HENRY DUNN.
	{ Messrs. DELLA VALLE BROTHERS, Artists in Scagliola.
	{ Messrs. GI <sup>o</sup> . GALLIANI & Co.
PISA .....	{ Mr. FERD. PEVERADA.
	{ Messrs. HUGUET & VAN LINT, Sculptors in Alabaster and Marble.
	{ Messrs. EMME <sup>le</sup> . FENZI & Co.
	{ Messrs. PLOWDEN & FRENCH.
	{ Messrs. MAQUAY & PAKENHAM.
FLORENCE .....	{ Mr. GAET <sup>o</sup> . BIANCHINI, Mosaic Worker, opposite the Cappella de' Medici.
	{ Mr. ANTONIO DI LUIGI PIACENTI.
	{ Mr. J. TOUGH.
	{ Messrs. F <sup>lli</sup> . PACETTI, Picture-frame Makers, Via del Palagio.



MESSRS. J. & R. M<sup>c</sup>CRACKEN, AGENTS—*continued.*

FLORENCE .....	{ Messrs. NESTI CIARDI & Co.
VOLTERRA.....	Mr. F. LEOPOLDO PISANI, Sculptor, No. 1, sul Prato.
BOLOGNA .....	Sig. OTT <sup>o</sup> . CALLAJ, and Sig. GIUSE. CHERICI.
ANCONA .....	Mr. FLAVIO PEROTTI, British Vice-Consul.
	Messrs. MOORE, MERELLET & Co.
	Messrs. FREEBORN & Co. Messrs. TORLONIA & Co.
ROME.....	Messrs. MACBEAN & Co. Mr. CARLO TREBBI.
	Messrs. PLOWDEN, CHOLMELEY, & Co.
	Messrs. PAKENHAM, HOOKER, & Co.
	Mr. LUIGI BRANCHINI, at the English College.
CIVITA VECCHIA.	Mr. J. T. LOWE, Junr., British Vice-Consul. Mr. T. ARATA.
NAPLES .....	{ Messrs. IGGULDEN & Co. Messrs. W. J. TURNER & Co. Messrs.
	CUMMING, WOOD, & Co.
PALERMO .....	Messrs. BROWN, FRANCK, & Co.
MESSINA.....	Messrs. CAILLER & Co.
	Mr. EMANUEL ZAMMIT.
	Mr. J. ASPINALL.
	Mr. FERDINAND DIMECH, No. 69, Strada Teatro, Valletta, Sculptor
MALTA .....	in Malta Stone.
	Messrs. JAMES SOLER & Co., Sculptors in Malta Stone.
	Mr. PAOLO DECANDIA, ditto.
	Mr. P. P. DECESARE, ditto. [Workers.
	Messrs. JOS <sup>h</sup> . DARMANIN & SONS, 45, Strada Levante, Mosaic
CORFU .....	Mr. J. W. TAYLOR.
ALEXANDRIA .....	Messrs. BRIGGS & Co.
CONSTANTINOPLE	Messrs. C. HANSON & Co., and Mr. BLACK.
SMYRNA .....	Messrs. HANSON & Co.
BEYROUT .....	Mr. HENRY HEALD.
ATHENS .....	Messrs. O. METIVIER & Co.
	Messrs. FRERES SCHIELIN.
VENICE .....	Messrs. S. & A. BLUMENTHAL & Co.
	Mr. JOHN HARRIS.
TRIESTE .....	Messrs. GEORGE MOORE & Co.
OSTEND .....	Mr. F. A. BELLEROCHÉ. Messrs. BACH & Co.
BRUSSELS .....	Mr. J. J. GIBBS, Bureau du Télégraphe Electrique, Station du Nord
ANTWERP .....	Messrs. F. MACK & Co., Marché de Zéland, No. 2449.
	Messrs. PRESTON & BOSBOOM.
ROTTERDAM.....	Messrs. S. A. LEVINO & Co.
	Messrs. L. MAYER & Co.
	Messrs. C. HEMMANN & Co. Messrs. BOUTMY & Co.
COLOGNE.....	Mr. J. M. FARINA, vis-à-vis la Place Juliers.
	Messrs. G <sup>me</sup> . TILMES & Co.
MAYENCE .....	Mr. JOSEPH THUQUET.
	Mr. P. A. TACCHI'S SUCCESSORS, Glass Manufacturers, Zeil D, 17.
FRANKFORT O. M.	Madame Veuve J. H. STIEBEL, Zeil D, 211.
	Messrs. BING BROTHERS, Zeil D, 212.
MANNHEIM .....	Mr. DINKELSPEIL. Messrs. EYSEN & CLAUS.
	Mr. J. M. DE HERMANN, Printseller.
MUNICH .....	Messrs. MAY & WIDMAYER, Printsellers.
	Mr. F. STEIGERWALD, Glass Manufacturer.
	Messrs. L. NEGRIOLI & Co.
KISSINGEN .....	Mr. E. STEIGERWALD, Glass Manufacturer.
	Messrs. J. BERGMANN & Co.
RATISBON .....	Mr. AUGUSTE KOCH.
NUREMBERG .....	Mr. PAOLO GALIMBERTI.
BASLE.....	Messrs. JEAN PREISWERK & FILS.
BERNE .....	Mr. AUGUSTE BUESCHÉ. Mr. ALBERT TRUMPY.
GENEVA .....	Messrs. RITZCHÉ, PÈRE & FILS, Grand Quai.
INTERLACKEN .....	Mr. J. WYDER.
GRINDELWALD ...	Mr. S. ROTHACHER, Fils.
HAMBURG .....	Messrs. SCHAAR & CLAUS; Mr. C. B. ARNOLD.
PRAGUE .....	Mr. W. HOFMANN, Glass Manufacturer, Kleinen Ring, No. 456.
	Mr. THOMAS WOLF, Glass Manufacturer.
CARLSBAD .....	Mr. CARL KNOLL, au Lion Blanc.
VIENNA .....	Mr. W. HOFMANN, Glass Manufacturer, am Lugeck, No. 768.
	Messrs. G. F. THODE Söhne.
DRESDEN. ....	Madame HELENA WOLFSOHN, Schössergasse, No. 5.
NEW YORK .....	Messrs. WILBUR & SCOTT.

FRANKFORT O. M.

---

P. A. TACCHI'S SUCCESSORS,

(LATE FRANCIS STEIGERWALD,)

ZEIL D, No. 17,

BOHEMIAN FANCY GLASS AND CRYSTAL WAREHOUSE.

---

P. A. TACCHI'S SUCCESSORS beg to acquaint the Public, that they have become the Purchasers of Mr. F. STEIGERWALD'S ESTABLISHMENT in this Town, for the Sale of Bohemian Fancy Cut Glass and Crystals.

They have always an extensive and choice Assortment of the Newest and most Elegant Patterns of

ORNAMENTAL CUT, ENGRAVED, GILT, AND PAINTED GLASS

*Both White and Coloured,*

In Dessert Services, Chandeliers, Articles for the Table and Toilet, and every possible variety of objects in this beautiful branch of manufacture. They solicit, and will endeavour to merit, a continuance of the favours of the Public, which the late well-known House enjoyed in an eminent degree during a considerable number of years.

P. A. TACCHI'S SUCCESSORS have BRANCH ESTABLISHMENTS during the Season at

WIESBADEN AND EMS,

Where will always be found Selections of the newest Articles from their principal Establishment.

---

Their Agents in England, to whom they undertake to forward Purchases made of them, are Messrs. J. & R. M'CRACKEN, 7, Old Jewry, London.



FRANKFORT O. M.

BING BROTHERS,



ZEIL, No. 212,

(OPPOSITE THE HOTEL DE RUSSIE,)

MANUFACTORY OF ARTICLES IN STAG'S HORN,

DEPÔT OF DRESDEN CHINA.

Copy of the Statue of Ariadne.

\*\*\* *All kinds of Parisian Fancy Articles.*

MESSRS. BING BROTHERS beg respectfully to invite the Public to visit their Establishment, where they have always on show, and for sale, a most extensive Assortment of Articles in Stag's Horn, of their own manufacture; consisting of Brooches, Ear-rings, Bracelets, Pen and Pencil-holders, Seals, Ink-stands, Watch-stands, Snuff-boxes, Cigar-boxes, Whips, Walking-sticks, Knives, Card-cases, and every description of article for the Writing and Work Table, besides Vases and other ornamental objects too various to be here enumerated.

Messrs. BING have also the finest Copies, both in Biscuit-China and Bronze, of the Statue of Ariadne, the Chef-d'œuvre of the Sculptor DANNECKER, of which the original is in Bethman's Museum at Frankfort O. M.

Messrs. BING have likewise the *Sole Dépôt* in FRANKFORT of the Porcelain of the Royal Manufactory of Dresden; and at their Establishment may be seen the most splendid assortment of Figures after the Ancient Models, ornamented with Lace-work of the most extraordinary fineness; likewise Dinner, Dessert, and Tea Services; Plates, Vases, Candelabras, Baskets, &c. &c., in the Antique Style, ornamented with flowers in relief, and the finest paintings.

Besides the above-named objects, they have a superb assortment of Clocks, Bronzes, Porcelain, and other Fancy Objects, the productions of Germany, France, and England.

*Dépôt of the veritable Eau de Cologne of Jean Maria Farina, of Cologne.*

 Their Agents in London are J. and R. M'CRACKEN, 7, Old Jewry.

## MUNICH.

---

### J. M. DE HERMANN,

MAGAZINE OF OBJECTS OF FINE ARTS, PICTURES, PRINTS,  
DRAWINGS, AND LITHOGRAPHS.

---

J. M. DE HERMANN has always on Sale a Collection of Pictures by Modern Artists (German and others), of Miniatures and Drawings, Engravings and Lithographs. The latter comprises the Collections of the Pinacothek, of the Galleries of Schleissheim and the Duke of Leuchtenberg at Munich, as well as that of the Royal Gallery of Dresden: also the Collection of the Works of the Old School, better known as the "Collection of the Frères Boisséré;" the Frescoes in the Church of All-Saints, and generally of whatever relates to the Fine Arts.

J. M. DE HERMANN undertakes to forward to England all Purchases made at his Establishment, through his Agents, Messrs. J. & R. M'CRACKEN, 7, Old Jewry.

---

## FLORENCE.

---

### G. BIANCHINI,

MANUFACTURER OF TABLES AND LADIES' ORNAMENTS, OF  
FLORENTINE MOSAIC.

NO. 4844, VIA DE' NELLI, OPPOSITE THE ROYAL CHAPEL OF THE MEDICI,

INVITES the English Nobility and Gentry to visit his Establishment, where may always be seen numerous specimens of this celebrated and beautiful Manufacture, in every description of Rare and Precious Stones. Orders for Tables and other Ornaments executed to any Design.

G. BIANCHINI's Agents in England are Messrs. J. & R. M'CRACKEN, 7, Old Jewry, London.



## MUNICH.



## FRANCIS STEIGERWALD,

MANUFACTURER OF ALL KINDS OF

*Fancy Articles and Services in White and Coloured Crystal Glass,*

CUT, OR ORNAMENTED WITH GILDING, PAINTING, OR ENGRAVING,

BEGS respectfully to inform the Public that his large Stock at MUNICH, the acknowledged seat of the Fine Arts in Germany, is, as it has been for many years, carefully supplied with the NEWEST and CHOICEST PRODUCE of his FACTORY.

FRANCIS STEIGERWALD has also an Establishment at Kissingen during the Season.

Requesting his Customers and Correspondents in ENGLAND to continue to this Establishment the favour and confidence they have been pleased to bestow on his former one at FRANKFORT ON THE MAINE, he begs to state that Purchases or Orders will be transmitted on the shortest notice, and without any further trouble, through the medium of his Agents, Messrs. J. & R. M'CRACKEN, No. 7, Old Jewry, London.

## COLOGNE O. RHINE.

---

# JOHN MARIA FARINA,

(OPPOSITE THE JULICH'S PLACE,)

PURVEYOR TO HER MAJESTY QUEEN VICTORIA, TO HIS MAJESTY  
THE KING OF PRUSSIA, ETC.,

OF THE

## ONLY GENUINE EAU DE COLOGNE.

---

THE frequency of mistakes, which are sometimes accidental, but for the most part the result of deception practised by interested individuals, induces me to request the attention of all English travellers to the following statement :—

Since the first establishment of my house in 1706, there has never been any partner in the business who did not bear the name of FARINA, nor has the manufacture of a second and cheaper quality of EAU DE COLOGNE ever been attempted. Since 1827, however, several inhabitants of Cologne have entered into engagements with Italians of the name of Farina, and, by employing that name, have succeeded to a very great extent in foisting an inferior and spurious article upon the Public.

In the year 1836 a Mrs. Aldenbruck established a manufactory of Eau de Cologne under the firm of “J. M. Farina,” at 2, Frederick Wilhelm Street; and, in order to render the deception more complete, carried on the business for some time under the firm and address of J. M. Farina, opposite the Julich's Place, No. 2. This imposition was speedily put a stop to by the interference of the authorities; but Mrs. Aldenbruck has since taken a shop in the neighbourhood of my house, Unter Goldschmidt, No. 6, and has now opened another, in a small house near the Julich's Place, No. 4. I therefore beg to inform all strangers visiting Cologne that my Establishment, which has existed since 1706, is exactly opposite the Julich's Place, forming the corner of the two streets, Unter Goldschmidt and Oben Marsporten, F. No. 23; and, that it may be the more easily recognised, I have had the Arms of England and Prussia put up in front of the house. By calling the attention of the Public to this notice, I hope to check that system of imposition which has been so long practised towards foreigners, by coachmen, valets de place, and others, who receive bribes from the vendors of the many spurious compounds sold under my name.

J. M. FARINA.

\*\*\* *My Custom-house Agents in London are Messrs. J. & R. M'Cracken, 7, Old Jewry.*



## LEGHORN.

HIACINTH MICALI &amp; SON,

VIA FERDINANDA, No. 1230.

Manufactory of Marble, Alabaster, and Scagliola Tables, and Dépôt of Objects of Fine Arts.

Their extensive Show-rooms are always open to Visitors.

THEIR AGENTS IN ENGLAND ARE

MESSRS. J. AND R. M'CRACKEN,

7, OLD JEWRY, LONDON.

## GENOA.

Silver Filagree Work.

G. LOLEO,

(SUCCESSOR TO FELIX PERNETTI,)

No. 81, IN THE ALBERGO DELLA CROCE DI MALTA,

KEEPS a Magazine which boasts the richest and most complete assortment of every description of objects of the renowned and special production of Genoese industry. He invites Foreigners and Travellers to visit his Establishment, where every article is sold at fixed prices.

His Agents in England are Messrs. J. & R. M'CRACKEN, 7, Old Jewry, London.

## À GENÈVE. AVEC UN BELVÉDÈRE.

## HOTEL DES BERGUES.

A. E. RUFENACHT, qui tient cet établissement depuis son ouverture en 1834, a l'honneur de prévenir Messieurs les Voyageurs, qu'il a pris toutes les dispositions nécessaires, pour leur faciliter le séjour de son Hôtel, tant par une diminution notable dans tous ses prix, qu'en leur offrant la faculté de s'y établir à un prix de pension, à la semaine ou au mois.

Il a destiné une de ses salles à un restaurant où l'on peut se faire servir à la carte à toute heure, lors même qu'on ne loge pas à l'Hôtel. L'on trouvera donc réuni dans son bel établissement, la magnifique position de l'Hôtel d'où l'on jouit de la vue du lac, de la chaîne des Alpes et du Mont Blanc, un service bien organisé, tout le confortable désirable et des prix très-modérés.

La démolition d'une partie des remparts, a été très-favorable pour la vue dont on jouit depuis les appartements de l'Hôtel.

## INNSBRUCK, TYROL.



## HOTEL D'AUTRICHE,

BY

STOTZ AND MAULICK.

---


---

THIS NEW HOTEL, standing in its own Gardens, and in the immediate neighbourhood of the Post Office and other Public Buildings, is delightfully situated, commanding a magnificent view of the surrounding mountain scenery.

It is conducted in a very superior style, and has been so well patronised during the short time of its existence, that the Proprietors have been induced to make extensive alterations, which enable them to offer such accommodation for elegance and comfort as cannot be surpassed.

His GRACE the DUKE OF DEVONSHIRE, the EARL OF LISTOWEL, SIR STRATFORD CANNING, SIR GEORGE NAPIER, and many others of the Nobility and Gentry, have already favoured this Hotel with their patronage.

---

 *Excellent Wines, &c. &c., and all Charges most moderate.*



## BONN ON THE RHINE.

### MR. SCHMITZ,

PROPRIETOR OF THE GOLDEN STAR HOTEL,

BEGS leave to recommend his Hotel to English Travellers. The apartments are furnished throughout in the English style ; the rooms are carpeted, and the attendance, as well as the kitchen and the wine-cellar, is well provided.

The STAR HOTEL has been honoured by the visits of the following Members of the English Royal Family :—

- |       |                 |   |   |
|-------|-----------------|---|---|
| 1846. | June 18.        | { | H. M. ADELAIDE, QUEEN DOWAGER OF GREAT BRITAIN, accompanied by His Highness PRINCE EDWARD OF SAXE WEIMAR, LORD and LADY BARRINGTON, SIR DAVID DAVIS, M.D., Rev. J. R. WOOD, M.A., CAPTAIN TAYLOR, &c. &c., honoured the above establishment with a THREE DAYS' VISIT. |
| 1818. | May             | . | H. R. H. the DUKE OF CAMBRIDGE and Suite.   |
| 1825. | March and Sept. | { | H. R. H. the DUKE and DUCHESS OF CLARENCE and Suite.  |
| 1834. | July            | { | H. M. QUEEN ADELAIDE, accompanied by the EARL and COUNTESS OF ERROL, EARL and COUNTESS OF DENBIGH, EARL and COUNTESS HOWE, &c.  |
| 1836. | Aug.            | . | H. R. H. the DUCHESS OF GLOUCESTER and Suite.   |
| 1837. | July            | . | H. R. H. the DUCHESS OF CAMBRIDGE and Suite.  |
| 1839. | Nov.            | . | H. R. H. the PRINCE GEORGE OF CAMBRIDGE and Suite.  |
| —     | Nov.            | { | H. R. H. PRINCE ALBERT OF SAXE COBURG GOTHA, accompanied by PRINCE ERNEST OF SAXE COBURG GOTHA, and their Suite.  |
| 1840  | . . .           | { | H. R. H. the DUCHESS OF CAMBRIDGE, accompanied by the PRINCESS AUGUSTA OF CAMBRIDGE, and their Suite.   |
| 1841  | . . .           | { | H. R. H. the DUCHESS OF KENT and Suite, accompanied by H. S. H. the PRINCE OF LEININGEN.  |
| 1841  | . . .           | . | H. R. H. the DUCHESS OF CAMBRIDGE and Suite.  |
| —     | . . .           | . | H. R. H. PRINCESS CAROLINA OF CAMBRIDGE.  |
| 1844  | . . .           | . | H. R. H. the DUCHESS OF CAMBRIDGE and Suite.  |
| —     | . . .           | . | H. R. H. PRINCESS MARY OF CAMBRIDGE.  |
| 1845. | June            | { | H. R. H. the DUCHESS OF KENT and Suite, accompanied by H. S. H. the PRINCE OF LEININGEN.  |
| 1847. | July            | { | H. R. H. the DUKE AND DUCHESS OF CAMBRIDGE, with their Family and Suite.  |

MR. SCHMITZ begs to add, that at no Hotel on the Rhine will be found more moderate charges.

# UNION BANK OF LONDON.

## Directors.

SIR PETER LAURIE, *Governor.*

W. M. NURSE, Esq., *Deputy Governor.*

GEORGE WEBSTER, Esq.

PETER LAURIE, Esq.

HENRY HALBERT, Esq.

JOHN BARNES, Esq.

JOHN CONNELL, Esq.

ARCHIBALD BOYD, Esq.

J. W. SUTHERLAND, Esq.

CHARLES LYALL, Esq.

Lient.-Col. MATHESON, M.P.

JAMES FARQUHAR, Esq.

JOHN CHAPMAN, Esq.

JOHN SCOTT, Esq.

WILLIAM WILSON SCRIMGEOUR, *General Manager.*

WALTER LAURIE, *Secretary.*

## CIRCULAR NOTES.

THE Directors give notice that they issue CIRCULAR NOTES of the value of £10 and upwards, *free of expence*, and LETTERS OF CREDIT payable by their Correspondents at the several places indicated below. To be obtained at the HEAD OFFICE, 2, PRINCES STREET, MANSION HOUSE; the REGENT STREET BRANCH, ARGYLE PLACE; and at the CHARING CROSS BRANCH, 4, PALL MALL EAST.

Abbeville	Cairo	Geneva	Mauritius (Port	Rotterdam
Aix-en-Provence	Calais	Genoa	Louis)	Rouen
Aix-la-Chapelle	Calcutta	Ghent	Mayence	Salzburg
Alexandria	Canada (Upper)	Gibraltar	Messina	Santa Cruz,
Aleppo	Canton	Gottenbourg	Milan	Teneriffe
Alicante	Cape Town	Gottingen	Montpellier	Schwalback
Almeira	Carlsbad	Graefenburg	Montreal	Seville
Amiens	Carlsruhe	Granville	Moscow	Shauffausen
Amsterdam	Cephalonia	Gratz	Munich	Siena
Ancona	Cette	Halifax (Nova	Munster	Singapore
Antwerp	Ceylon	Scotia)	Nancy	Smyrna
Athens	Chalon (sur	Hamburg	Nantes	Spa
Augsbourg	Saone)	Hanover	Naples	St. Galle
Avignon	Chambery	Havre	Neuchâtel	St. Malo
Avranches	Chaux de fonds	Hague	New Orleans	St. Omer
Baden-Baden	Christiana	Heidelberg	New York	St. Petersburg
Bagdad	Christiansand	Hermanstadt	Nice	Stockholm
Barcelona	Clermont Fer-	Homburg es	Nismes	Strasbourg
Basle	rand	monts	Nurembourg	Stuttgart
Beirut	Coblenz	Hong Kong	Ditto (Fürth	Tarbes
Benares	Cologne	Innsbruck	near)	Teneriffe
Bergen	Constance	Interlaken	Oleron	Toronto
Berlin	Constantinople	Kissingen	Oporto	Toulon
Berne	Copenhagen	Königsberg	Orleans	Toulouse
Besançon	Cordova	Lausanne	Ostend	Tours
Bilbao	Corfu	Leghorn	Palermo	Treves
Blois	Corunna	Leipsic	Paris	Trieste
Bologna (en	Damascus	Liege	Parma	Turin
Italie)	Dantzic	Lisbon	Patras	Utrecht
Bombay	Darmstadt	Loele	Pau	Valenciennes
Bonn	Delhi	L'Orient	Perpignan	Valencia
Bordeaux	Dieppe	Lubeck	Pest	Venice
Botzen	Dijon	Lucerne	Pisa	Verona
Boulogne (sur	Dresden	Lyon	Port St. Mary	Vevey
Mer)	Drontheim	Lucca (Bains de)	Prague	Vienna
Bremen	Dunkirk	Madeira	Presbourg	Vigo
Breslau	Dusseldorf	Madras	Quebec	Warsaw
Bruges	Elberfeld	Madrid	Rastadt	Weimar
Brünn	Elsinore	Malaga	Ratisbonne	Wiesbaden
Brunswick	Emms	Malta	Rennes	Wurzburg
Brussels	Florence	Mannheim	Rio de Janeiro	Yverdon
Cadiz	Francfort (sur	Marienbad	Rome	Zante
Caen	Maine)	Marseilles	Rostock	Zurich



Under Royal



Patronage.

**Perfect freedom from Coughs in Ten Minutes,**  
 AND INSTANT RELIEF AND A RAPID CURE OF  
**ASTHMA AND CONSUMPTION, COUGHS, COLDS,**  
 AND  
**ALL DISORDERS OF THE BREATH AND LUNGS,**  
 ARE INSURED BY  
**DR. LOCOCK'S PULMONIC WAFERS.**

*\*\* Small books, containing many hundreds of properly authenticated testimonials, may be had from every Agent.*

The following are a few letters which have just been received :

**Cures of Consumption.**

Gentlemen,—I can myself speak of your Wafers with the greatest confidence, having recommended them in many cases of pulmonary consumption, and they have always afforded relief when everything else has failed, and the patients, having been surfeited with medicine, are delighted to meet with so efficient a remedy, having such an agreeable taste.

J. MAWSON,  
 Surgeon.

13, Moseley-street, Newcastle-on-Tyne.

**Important to all who Sing.**

From S. Pearsall, Esq., Her Majesty's Concerts, and Vicar Choral of Lichfield Cathedral.

*Lichfield.*

Gentlemen,—A lady of distinction, having pointed out to me the qualities of Dr. Locock's Wafers, I was induced to make a trial of a box, and from this trial I am happy to give my testimonial in their favour. I find by allowing a few of the Wafers (taken in the course of the day) to gradually dissolve in the mouth, my voice becomes bright and clear, and the tone full and distinct. They are decidedly the most efficacious of any I have ever used.

S. PEARSALL.

**TO SINGERS AND PUBLIC SPEAKERS** they are invaluable, as in a few hours they remove all hoarseness, and wonderfully increase the power and flexibility of the voice.

**THEY HAVE A PLEASANT TASTE.** Price 1s. 1½d., 2s. 9d., and 11s. per box.

Agents: DA SILVA & CO., 1, Bride-lane, Fleet-street, London. Sold by all Medicine Vendors.

**DR. LOCOCK'S FEMALE WAFERS**

HAVE NO TASTE OF MEDICINE,

And are the only remedy recommended to be taken by Ladies. They fortify the constitution at all periods of Life, and in all Nervous Affections act like a Charm. They remove ALL OBSTRUCTIONS, HEAVINESS, FATIGUE ON SLIGHT EXERTION, PALPITATION OF THE HEART, LOWNESS OF SPIRITS, WEAKNESS, AND ALLAY PAIN.

They create APPETITE, and remove INDIGESTION, HEART-BURN, WIND, HEAD-ACHES, GIDDINESS, &c.

In HYSTERICAL DISEASES, a proper perseverance in the use of this Medicine will be found to effect a Cure after all other means have failed.

*\*\* Full directions are given with every box.*

NOTE.—These Wafers do not contain any Mineral, and may be taken either dissolved in water, or whole.

Price 1s. 1½d., 2s. 9d., and 11s. per box.

The 2s. 9d. boxes contain nearly three of the small size, and the 11s. Boxes five of those at 2s. 9d.

**BEWARE OF COUNTERFEITS IN THE FORM OF PILLS.**

MALTA.—EGYPT.—INDIA.—IONIAN ISLES.

By Appointment

OF

THE LORDS COMMISSIONERS OF THE ADMIRALTY.

H. B. Majesty Steam Packets, possessing every requisite accommodation for the comfort of passengers, keep up a regular Communication between England and India, *via* Marseilles, Malta, and Alexandria, twice a Month.

These fine Vessels leave Marseilles for Malta on the 9th and 26th, and Malta for Marseilles about the 12th and 24th, performing the passage in about 68 hours.

On the 13th one of these Packets is despatched to Alexandria with the India Mails and passengers, which place she leaves with the Homeward Mail and passengers about the 21st, occupying about 90 hours in the voyage. The Packet for Marseilles waits her arrival, also one of the Peninsular Company's Boats, to convey passengers to England *via* Gibraltar, to the 26th.

IONIAN ISLES.

On the 1st and 13th of each month one of these Packets is despatched to Corfu, *via* Cephalonia, Zante and Patras, from whence passengers can proceed to Athens. She remains at Corfu four days, and returns (calling at the above ports) to Malta, arriving on the 10th and 23rd, in time to secure passages to England, *via* Gibraltar or Marseilles.

Freights on Specie in accordance with Admiralty regulation; 1 per Cent. on Silver,  $\frac{3}{4}$  on Jewellery.

Freight on Packages and Parcels may be known on application at the Agents'.

*Passages, including Wines, a liberal Table, and every Expense.*

	1st Class.	Female Servants.	2nd Class.	3rd Class, if Victualled.	3rd Class, not Victualled.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
Between Malta and Marseilles	8 2 0	5 8 0	4 10 0	2 14 0	2 0 6
" " Alexandria	12 10 0	8 6 8	7 2 0	3 16 0	2 17 0
" " Corfu . .	9 0 0	6 0 0	5 10 0	2 10 0	1 17 6
" " Patras . .	7 0 0	4 13 4	4 10 0	1 16 0	1 7 0

And the intermediate Ports in proportion.

BOOKING AGENTS.

MARSEILLES—L. BOUVET.  
ALEXANDRIA—MR. DAVIDSON.  
BOMBAY—TIMES OFFICE.  
PARIS—A. & W. GALIGNANI.  
ATHENS—C. MARGARETTA, ESQ.

MALTA—G. MUIR, 247, Strada Reale.  
ZANTE—W. L. REYNOLDS, ESQ.  
CEPHALONIA—CAPTAIN LEFOCHILO.  
SINGAPORE—MR. LOGAN.  
PATRAS—T. WOODLEY.

*Offices will be shortly Established at other Ports.*

G. MUIR,

Booking and Superintending Agent  
to Her Majesty's Packets in the Mediterranean.

N.B.—Passengers leaving England by the P. and O. Company's Steamer from Southampton on the 29th, are conveyed on to Alexandria by H. M.'s Packet leaving Malta on the 13th. Mr. MUIR, the Agent, will be on board to tranship their luggage and give them any information. There is no expense attending it.



## TO TOURISTS.

### BLACK'S GUIDE BOOKS AND TRAVELLING MAPS.

NEW EDITIONS.

"The most valuable series of Picturesque Guide Books issued by Messrs. BLACK of Edinburgh. We have looked carefully through the volumes. They are admirably 'got up;' the descriptions are accurate, and remarkably clear and comprehensive. Altogether, this series of works is of immense value to tourists."—*Art-Journal*.

- BLACK'S PICTURESQUE TOURIST OF SCOTLAND. 8s. 6d.
- ANDERSON'S GUIDE TO THE HIGHLANDS. 10s. 6d.
- BLACK'S PICTURESQUE TOURIST OF ENGLAND. 10s. 6d.
- BLACK'S ECONOMICAL TOURIST OF SCOTLAND. 3s. 6d.
- BLACK'S PICTURESQUE GUIDE TO THE ENGLISH LAKES. 5s.
- BLACK'S GUIDE THROUGH EDINBURGH. 2s. 6d.
- BLACK'S GUIDE THROUGH GLASGOW. 2s.
- BLACK'S TRAVELLING MAP OF ENGLAND. 4s. 6d.
- BLACK'S TRAVELLING MAP OF SCOTLAND. 4s. 6d.
- BLACK'S TRAVELLING MAP OF IRELAND. 2s. 6d.
- BLACK'S MAP OF THE ENGLISH LAKE DISTRICT. 2s. 6d.
- BLACK'S MAP OF NORTH WALES. 1s. 6d.
- BLACK'S MAP OF SOUTH WALES. 1s. 6d.
- BLACK'S COUNTY MAPS OF SCOTLAND. 1s. and 1s. 6d. each.
- BLACK'S PLAN OF EDINBURGH AND ENVIRONS. 1s. 6d.
- BLACK'S TOURIST'S MEMORIAL OF SCOTLAND. 5s.
- BLACK'S MAP OF CENTRAL EUROPE. 4s. 6d.

ADAM & CHARLES BLACK, Edinburgh; and Sold by all Booksellers.

## TOURISTS IN SWITZERLAND.

In a handsome Volume, Imperial 8vo, illustrated by a large Map of the MER DE GLACE of Chamouni, Lithographed Views and Plans, and Engravings on Wood, price 28s., or with the large Map coloured, in a case, 31s. 6d.

### TRAVELS THROUGH THE ALPS OF SAVOY, AND OTHER PARTS OF THE PENNINE CHAIN,

WITH OBSERVATIONS ON THE PHENOMENA OF GLACIERS.

By JAMES D. FORBES, F.R.S.,

Sec. R.S.E., Corresponding Member of the Royal Institute of France, Professor of Natural Philosophy in the University of Edinburgh, &c. &c.

*Second Edition, Revised and Enlarged.*

"This work contains ample and exact details in topography. . . . It abounds with daring and hazardous adventures, contains notices of occasional catastrophes that have befallen less fortunate explorers, presents interesting discoveries with new deductions, and is clothed in a style and diction entirely in keeping with the beauty and grandeur of the subject. . . . We have perused the work with intense pleasure and large instruction."—*Villaman's American Journal of Science and Art*.

"This elaborate and beautifully illustrated work."—*Quarterly Review*.

"Pregnant with interest."—*Edinburgh Review*.

"A truly splendid volume in every sense of the word."—*Church of England Magazine*.

ADAM & CHARLES BLACK, Edinburgh; LONGMAN & Co., London.

## LEIPZIG.

---

### T. O. WEIGEL, BOOKSELLER, LEIPZIG,

Has recently published a complete Catalogue of his very extensive and valuable Stock of Old Books in all Languages. This very choice Collection comprises, amongst other branches of Literature, about 400 Copies of old and rare editions of the Bible, and separate Books of the Old and New Testament, in almost every language of the world; scarce Editions of the Works of the Fathers, Greek and Latin Classics, Oriental Literature, Old Voyages and Travels, History, Numismatics, Philology, Bibliography, &c. &c.

The Books are almost without exception fine copies, and in excellent preservation, and amongst them will be found many extremely rare, and seldom to be met with in Private Libraries. Gentlemen visiting Leipzig are respectfully invited to inspect this Stock, which is well worthy the attention of every amateur and book-collector.

T. O. W., from his long and extensive bibliographic experience and wide-spread connexions, is generally able to procure, at a short notice, such Works as he may not have in Stock, or which are not obtainable through the ordinary channels.

\*\* Catalogues of his Half-Yearly Book Auctions, and occasional Autograph Sales may be had of MESSRS. LONGMAN & Co., London, or will be forwarded direct, by T. O. WEIGEL, to any Gentleman favouring him with his address.

---

### CURE OF STAMMERING WITHOUT SURGICAL OPERATION OR THE USE OF MEDICINE.

---

MR. HUNT may be consulted at 224, REGENT STREET, until the end of June, and for the three following months attends Pupils at Swanage, Dorset, one of the healthiest and most pleasant watering-places in the South of England.

The Royal Victoria Hotel affords economical accommodation of a very superior description, and commands a good view of the Isle of Wight, from which it is distant sixteen miles.

---

In one thick vol., the Tenth Edition, enlarged, price 16s.,

### MODERN DOMESTIC MEDICINE.

A Popular Treatise, exhibiting the Nature, Symptoms, Causes, and most efficacious Treatment of Diseases; with a collection of approved Prescriptions, Directions for Diet and Regimen, the means of affording Assistance in Accidents and other cases of emergency, Management of Children, Doses of Medicines, a clear account of the Hydropathic System, &c. Also a large Appendix on the treatment of Disorders of the Mind and Nerves. Forming a comprehensive Medical Guide for the Clergy, Families, and Invalids, in the absence of their Medical Adviser.

By T. J. GRAHAM, M.D., &c.

"It is evidently the result of great professional talent, experience, and judgment; the author everywhere appears conscientious and candid. One object is prominently evident—a sincere desire to benefit his suffering fellow-creatures." To recommend a work like the present to our readers, is only to manifest a proper regard for their welfare."—*Literary Journal*, Feb. 1843.

"It is altogether deserving of permanent popularity."—*London Weekly Review*.

SIMPKIN & Co., Paternoster Row; HATCHARDS, 187, Piccadilly; and TEGG & Co., 85, Queen Street, Cheapside. Sold by all Booksellers.



## P I S A.

## HOTEL DE LA GRANDE BRETAGNE.

LODOVICO AVOGADRI, PROPRIETOR.

THIS Hotel, new furnished, is situated in the most healthy part of the Town, on the South side of the long Arno, near the English Church; a desirable and comfortable home for Families who would wish to enjoy the fine Italian Climate for a time, at the most moderate Terms, by the Day, Week, or Month.

## TABLE D' HÔTE.

The Proprietor, L. AVOGADRI, hopes, by the convenient arrangements, the punctuality of the service, and his utmost personal attention and civility, to secure him the future Patronage of Families and Travellers.

## N I C E.

## MUSSO'S LONDON DISPENSARY,

NO. 1, RUE DU PONT NEUF,

*(Between the Bridge and the Hôtel des Etrangers.)*

MEDICINES FROM LONDON.

Now ready, *Fifth Edition*. With numerous Plates and Woodcuts. 2 vols. 8vo. 36s.

## NINEVEH AND ITS REMAINS:

WITH AN ENQUIRY INTO THE MANNERS AND ARTS OF THE ANCIENT ASSYRIANS.

By AUSTEN H. LAYARD, D.C.L.

Also, 100 Plates, large folio, £10 10s.

## THE MONUMENTS OF NINEVEH.

ILLUSTRATED FROM DRAWINGS MADE BY MR. LAYARD ON THE SPOT.

"We have had our Bruces and Mungo Parks, as well as our Parrys, Franklins, Backs, and Rosses, but we question whether a more enlightened or a more enterprising traveller than Mr. Layard is to be met with in the annals of our modern English history."—*Times*.

Also, with numerous Coloured Plates and Woodcuts. 8vo. 31s. 6d.

## HISTORY OF POTTERY AND PORCELAIN.

MODERN, EUROPEAN, AND ORIENTAL.

By JOSEPH MARRYAT, ESQ.

JOHN MURRAY, ALBEMARLE STREET.

Nearly ready, with Maps, &c. Post 8vo.

# HANDBOOK FOR ENGLAND AND WALES.

## A GUIDE BOOK FOR THE TOURIST.

The object of this Work is to give an account of the most remarkable *Places* and most frequented Roads in England—enumerating especially the objects calculated to *interest strangers and passing travellers*, the Historical Associations, &c., and furnishing plans for TOURS and SUMMER EXCURSIONS.

### CONTENTS.

BUILDINGS.	ROADS.
MANUFACTURES.	RAILROADS, VIADUCTS, TUNNELS, BRIDGES.
MUSEUMS AND COLLECTIONS OF ART, NATURE, ANTIQUITY.	RIVERS, LAKES, AND CANALS.
PUBLIC WORKS.	CHURCHES, CASTLES, AND RUINS.
PORTS AND HARBOURS.	SEATS, PICTURES, AND STATUES.
DOCKYARDS.	PARKS, GARDENS, AND TREES.
INNS,	VIEWS, WATERFALLS, CAVERNS.
CONVEYANCES, } Expenses.	THE CRADLES AND GRAVES OF REMARK- ABLE PERSONS.
EXCURSIONS, WALKS.	BATTLE FIELDS.
POINTS OF VIEW.	PLANS OF EXCURSIONS, TOURS, ETC.

*The best Lines of Route for seeing these objects with least expenditure of time and money.*

Now Ready, a Revised Edition. With an Index of Names. One Volume. Post 8vo. 16s.

# HANDBOOK FOR LONDON:

BY PETER CUNNINGHAM, F.S.A.

"Very much to be pitied are those who cannot afford the time, or rather fractions of time, necessary to the enjoyment which Mr. Cunningham sets before them. To this Handbook for London the praise of being most instructive as well as entertaining cannot be denied."

"Mr. Cunningham has gathered from hitherto unexplored sources, such a '*multum in parvo*' of novelty and interest as the subject, not by any means new, seemed

scarcely to admit of. It is a dictionary in which any building, street, institution, or other particular of London topography may be looked out and found in its alphabetical place, with its whereabouts, its history, nature, contents, inhabitants, changes and modifications, succinctly given; and subjoined, any passages that contain facts, dates, allusions, or anecdotes illustrative of it."

*Quarterly Review.*

In Preparation, by the same Author. Post 8vo.

# HANDBOOK FOR THE ENVIRONS OF LONDON.

WITH HINTS FOR EXCURSIONS BY RAILWAY, STEAMBOAT, AND ROAD.

JOHN MURRAY, ALBEMARLE STREET.



## STANDARD WORKS.

---

GIBBON'S DECLINE AND FALL OF THE ROMAN EMPIRE.  
 Edited, with Notes, by M. GUIZOT and DEAN MILMAN. *Second Edition.* Maps.  
 6 vols. 8vo. 63s.

GROTE'S HISTORY OF GREECE. From the Earliest Period down to  
 the end of the Peloponnesian War. *Second Edition.* Maps. Vols. 1 to 8. 8vo. 16s. each.

LORD CAMPBELL'S LIVES of the CHIEF JUSTICES of ENGLAND,  
 from the Norman Conquest. 2 vols. 8vo. 30s.

LORD CAMPBELL'S LIVES OF THE LORD CHANCELLORS OF  
 ENGLAND. *Third Edition.* 7 vols. 8vo. 105s.

TICKNOR'S HISTORY OF SPANISH LITERATURE. With  
 Criticisms and Biographical Notices. 3 vols. 8vo. 42s.

HALLAM'S CONSTITUTIONAL HISTORY OF ENGLAND. *Sixth  
 Edition.* 2 vols. 8vo. 24s.

HALLAM'S HISTORY OF EUROPE DURING THE MIDDLE  
 AGES. *Ninth Edition.* 2 vols. 8vo. 24s.

HALLAM'S LITERARY HISTORY OF EUROPE. *Third Edition.*  
 3 vols. 8vo. 36s.

RANKE'S HISTORY OF THE POPES OF ROME. Translated by  
 Mrs. AUSTIN. *Third Edition.* 2 vols. 8vo. 24s.

RANKE'S HISTORY OF PRUSSIA. Translated from the German.  
 3 vols. 8vo. 36s.

ELPHINSTONE'S HISTORY OF INDIA. *Third Edition.* Map. 8vo. 18s.

WILKINSON'S MANNERS AND CUSTOMS OF THE ANCIENT  
 EGYPTIANS. With 600 Illustrations. *Third Edition.* 5 vols. 8vo. 84s.

SOUTHEY'S BOOK OF THE CHURCH. *Sixth Edition.* 8vo. 12s.

BLUNT'S UNDESIGNED SCRIPTURAL COINCIDENCES. A Test  
 of their Veracity. *Third Edition.* 8vo. 9s.

SIR CHARLES LYELL'S PRINCIPLES OF GEOLOGY. *Seventh  
 Edition.* Woodcuts. 8vo. 18s.

SIR CHARLES LYELL'S MANUAL OF ELEMENTARY GEOLOGY.  
*Third Edition.* Woodcuts. 8vo. *Nearly ready.*

MRS. SOMERVILLE ON THE CONNEXION OF THE PHYSICAL  
 SCIENCES. *Eighth Edition.* Portrait and Plates. Fcap. 8vo. 10s. 6d.

MRS. SOMERVILLE'S PHYSICAL GEOGRAPHY. *Second Edition.*  
 Portrait. 2 vols. Fcap. 8vo. 12s.

DR. ABERCROMBIE ON THE INTELLECTUAL POWERS AND  
 THE INVESTIGATION OF TRUTH. *Thirteenth Edition.* Fcap. 8vo. 6s. 6d.

DR. ABERCROMBIE ON THE PHILOSOPHY OF THE MORAL  
 FEELINGS. *Eighth Edition.* Fcap. 8vo. 4s.

---

JOHN MURRAY, ALBEMARLE STREET.

## FOR CONTINENTAL TRAVELLERS, FAMILIES, AND STUDENTS.

This day, 3rd Edition, 5s., neatly bound,

### THE FRENCH PROMPTER:

A complete Handbook of Conversation for the use of Families, Travellers on the Continent, Teachers, and Students.

By **MONS. LE PAGE,**

Author of "L'Echo de Paris," "Petit Musée de Littérature Française," &c.

"The best book of the class published. It is the most complete Handbook of Conversation we have seen, and the best arranged."

*Douglas Jerrold's Weekly Newspaper.*

EFFINGHAM WILSON, 11, Royal Exchange.

*Of whom may be had, gratis, a List of*

MONS. LE PAGE'S SERIES OF FRENCH SCHOOL BOOKS.

## VENICE.

### GRAND HOTEL DE LA VILLE,

*Formerly the well-known Palace of Grassi, on the Great Canal.*

**JOHN MICHELI,**

FORMERLY Courier to their Imperial Majesties the Emperor and Empress of Russia, from whom he has received honourable marks of distinction, begs leave respectfully to announce to the Public that he has opened the above magnificent Hotel, and from his long experience as a Courier, engaged by many of the most distinguished families of England, he hopes to be able to afford every accommodation, comfort, and luxury, on the most moderate terms.

## SPANISH AND ENGLISH ELEMENTARY WORKS.

By **PROFESSOR E. DEL MAR.**

To be had of Messrs. D. NUTT, 270, Strand; DULAU & Co., Soho Square; ACKERMANN & Co., 96, Strand; J. LEE, 440, Strand; and P. ROLANDI, 20, Berners Street; of all of whom the Author's card of address may be obtained.

A GRAMMAR OF THE SPANISH LANGUAGE, WITH EXERCISES AND KEY. 5th Edition. Designed especially for those who have not the access of a master.

AN ENGLISH GRAMMAR FOR THE USE OF SPANIARDS.

A MANUAL OF MOST USEFUL SPANISH AND ENGLISH CONVERSATIONAL DIALOGUES, PROVERBS, AND IDIOMS, &c. &c. 3rd Edition.

These works are well known to the public, and have obtained the most decided approbation.

## VISITORS TO OXFORD

WILL FIND AT

### SPIERS AND SON'S ESTABLISHMENT

A very extensive variety of GOODS suitable for PRESENTS, or for Remembrances of Oxford. Guide-Books and Maps of the University and neighbourhood of every description published; Maps of the Ordnance Survey, and Geological ditto; Engraved Views of Oxford; Ornamental Stationery; Travelling Desks; Envelope Cases; Dressing Cases; PAPIER MACHE GOODS, with paintings of every College and Public Building, by eminent Artists, executed on the premises; Useful and Ornamental China; Glass, Bronze, and Marble Goods; English and Foreign Fancy Manufactures in general, and every description of Furniture for the Writing Table, Mantelpiece, and Toilet.

*The Painting Room and Establishment are always open to Visitors.*

102 AND 103, HIGH STREET, AND 1 AND 2, ORIEL STREET, OXFORD.

### CHARLES STAMMER,

AM KOHLMARKT IN WIEN,

MAGASIN DE BRONZE, PARFUMERIE,  
BIJOUTERIE,

Et haute nouveauté en articles de quincaillerie, se charge de tout article de confection pour voyage, ameublement.

### MR. BONFIGH,

A NATIVE OF ROME,

*(Formerly Tutor in England in a Family of Distinction,)*

Gives Lessons in Italian, through the medium of the English Language.

Address, at MR. PIALE'S English Library, Piazza di Spagna.



## THE LONDON AND WESTMINSTER BANK

### ISSUES CIRCULAR NOTES FOR THE USE OF TRAVELLERS AND RESIDENTS ON THE CONTINENT.

These Notes are payable at every important place in Europe, and thus enable a Traveller to vary his route without inconvenience; no expense is incurred, and when cashed no charge is made for Commission. These Notes may be obtained at the HEAD OFFICE OF THE LONDON AND WESTMINSTER BANK IN LOTHBURY; or at its branches, viz., 1, ST. JAMES'S SQUARE; 214, HIGH HOLBORN; 3, WELLINGTON STREET, BOROUGH; 87, HIGH STREET, WHITECHAPEL; AND 4, STRATFORD PLACE, OXFORD STREET.

J. W. GILBART, GENERAL MANAGER.

Now ready, a New and Smaller Edition, medium Svo, handsomely bound in antique bindings, 21s. cloth, 31s. 6d. calf, 42s. morocco,

## The Book of Common Prayer.

WITH 1000 ILLUSTRATIONS OF ORNAMENTAL BORDERS, INITIALS, TITLE-PAGES, AND HISTORICAL ENGRAVINGS FROM THE OLD MASTERS.

"The Missals of former days, many of them the labour of years of patient toil and misdirected devotion, are here surpassed by the mechanical apparatus which modern science has made applicable to the purposes of decorative printing. The brilliancy of effect, and the permanency of the colours, will be found to have surpassed, with a few

exceptions, anything that antiquity has produced."—*The Times*.

"The work has some admirable woodcuts from pictures by the Old Masters, copied under the direction of Gruner. Typography, indeed, has not produced anything more perfect of its kind."—*Athenæum*.

JOHN MURRAY, ALBEMARLE STREET.

## NUREMBERG.

### MR. SCHRAG, BOOK AND PRINT SELLER,

327, NEAR THE NASSAU HOUSE,

Begs leave to recommend his Repository to the notice of Travellers visiting Nuremberg. They will find the newest English, German, and French publications. Grammars, Dictionaries, Road and Guide Books, Maps, &c. *A rich collection of Engravings and Views of Nuremberg.* He is also the publisher of the well-known

### NURNBERG'S GEDENKBUCH,

a large engraved collection of all the monuments and remarkable remains in this town, comprising 100 sheets.

Prof. Kugler says in the *Stuttgarter-Kunstblatt*:—

"We see extremely well displayed in these little views the characteristic Physiognomy of this old town, as well in the Churches and Buildings as in the Private Houses. Besides being a worthy Souvenir, it contains also much useful information for the purposes of the severer historical study of art, and it therefore possesses a still higher degree of interest and recommendation."




**LEE'S  
Polyglot  
Washing  
Books,**

(To save Travellers  
the trouble of trans-  
lating their Washing  
Bills)

FOR LADIES.

**Ditto**

FOR GENTLEMEN.  
*English & French.*  
*English & Italian.*  
*English & German.*  
*English & Spanish.*  
*English & Portuguese.*  
1s. each.



**PASSPORTS**

Carefully Mounted and inserted in  
morocco cases, with name lettered in  
gold.

---

Ambassador's Signatures obtained  
to British Secretary of State's Pass-  
ports, at one Shilling each.

---

The latest editions of all MURRAY'S  
HAND-BOOKS ; which can generally be  
supplied when out of print and not to  
be obtained elsewhere.

---

COURIERS, or TRAVELLING SERVANTS,  
can be obtained at



**Foreign Letter  
Paper,**  
*Extra Large Size,*  
VERY THIN,  
**1s. per Quire.**

---

**PEDOMETERS.**

---

**PORTABLE  
ALARMS.**

---

**DOOR FASTENERS.**

---

*Pocket Compasses.*

---

**Leather  
Money-Bags.**

**JOHN LEE'S GUIDE DEPÔT,**  
440, WEST STRAND.

TWO DOORS WEST OF LOWTHER ARCADE,

Where an EXTENSIVE COLLECTION of GUIDES, HAND-BOOKS, MAPS, DICTIONARIES in all  
Languages, and INTERPRETERS useful for Travellers upon the Continent or elsewhere, and  
every information concerning PASSPORTS, can be obtained.

---

MURRAY'S HAND-BOOKS, rendered convenient POCKET-BOOKS by J. LEE'S limp  
Morocco binding, at 2s. additional charge.

---

MOROCCO and RUSSIA PORTABLE ROLL-UP CASES containing every essential  
for WRITING.

---

**Moore's German Interpreter,**

With the exact Pronunciation in English on a separate column, price 5s. cloth, 6s. in leather





# RECENT VOYAGES AND TRAVELS.

---

ENGLAND, SCOTLAND, AND IRELAND. Including the CHANNEL ISLANDS AND THE ISLE OF MAN. By Sir GEORGE HEAD. Post 8vo, 12s.

DATES AND DISTANCES. Showing what may be done in a tour of 16 months through various parts of Europe. Post 8vo, 8s. 6d.

FIELD SPORTS OF FRANCE. By RODERICK O'CONNOR. 12mo, 7s. 6d.

GOTHIC ARCHITECTURE IN FRANCE, being an ENQUIRY into the CHRONOLOGICAL SUCCESSION of the ROMANESQUE and POINTED STYLES. By THOS. INKERSLEY. 8vo, 12s.

A RIDE through FRANCE AND SWITZERLAND to FLORENCE. By a LADY. 2 vols. post 8vo, 18s.

A PHYSICIAN'S HOLIDAY, or a Month in Switzerland. By JOHN FORBES, M.D. Post 8vo, 8s. 6d.

PEDESTRIAN WANDERINGS in the PYRENEES. By T. CLIFTON PARIS. Post 8vo, 10s. 6d.

BUBBLES from the BRUNNEN of NASSAU. By AN OLD MAN. 16mo, 5s.

AUSTRIAN LOMBARDY, NORTHERN TYROL, and BAVARIA. By JOHN BARROW. Post 8vo, 10s. 6d.

HUNGARY AND TRANSYLVANIA. By JOHN PAGET. Plates. 2 vols. 8vo, 24s.

DALMATIA AND MONTENEGRO. By SIR J. G. WILKINSON. 2 vols. 8vo, 42s.

ETRURIA; ITS CITIES AND CEMETERIES. By GEORGE DENNIS. Plates. 2 vols. 8vo, 42s.

THE MONASTERIES OF THE LEVANT. By Hon. ROBERT CURZON. Woodcuts. Post 8vo, 15s.

A SHORT VISIT to the IONIAN ISLANDS, ATHENS, and the MOREA. By EDWARD GIFFARD. Post 8vo, 12s.

A CLASSICAL TOUR IN ATTICA. By Rev. Dr. WORDSWORTH, Plates. 8vo, 12s.

A FIRST and SECOND EXCURSION in ASIA MINOR. By SIR CHARLES FELLOWS. Plates. 2 vols. imp. 8vo.

RESEARCHES IN ASIA MINOR. By W. I. HAMILTON. Plates. 2 vols. 8vo, 38s.

NINEVEH AND ITS REMAINS. By A. H. LAYARD. Plates. 2 vols. 8vo, 36s.

ARABIA PETRÆA, MOUNT SINAI, and PETRA. By M. LEON DE LABORDE. Plates, 8vo, 18s.

CAIRO, PETRA, and DAMASCUS. By J. G. KINNEAR. Post 8vo, 9s. 6d.

TRAVELS IN TURKEY: By CHARLES MAC FARLANE. 2 vols. 8vo, 28s.

RUSSIAN LIFE AND MANNERS. By Rev. R. L. VENABLES. 8vo, 9s. 6d.

THE GEOLOGY OF RUSSIA IN EUROPE AND THE URAL MOUNTAINS. By SIR R. MURCHISON. Maps, &c. 2 vols. 4to.

JOHN MURRAY, ALBEMARLE STREET.

June, 1850.



# MURRAY'S TRAVEL

*Books that you may carry to the fire the most useful after all. A man will go on, when he would have been frightened by more erudite appearance.*—DR. JOHNSON

## THE HOME AND CO (COMPLETE

*Forming a compact and portable volume of a single shelf, or of one trunk—of which the interest, value, and popularity will not lapse of time.*

### LIST OF WORKS INCLUDED

BORROW'S BIBLE IN SPAIN.  
HEBER'S JOURNALS IN INDIA.  
IRBY AND MANGLES' HOLY LAND.  
DRINKWATER'S SIEGE OF GIBRALTAR.  
HAY'S MOROCCO AND THE MOORS.  
LETTERS FROM THE BALTIC.  
THE AMBER WITCH.  
SOUTHEY'S CROMWELL AND BUNYAN.  
MEREDITH'S NEW SOUTH WALES.  
LIFE OF SIR FRANCIS DRAKE.  
FATHER RIPA'S COURT OF PEKING.  
LEWIS'S WEST INDIES.  
MALCOLM'S SKETCHES OF PERSIA.  
THE FRENCH IN ALGIERS.  
IRVING'S BRACEBRIDGE HALL.  
DARWIN'S NATURALIST'S VOYAGE.  
THE FALL OF THE JESUITS.  
MAHON'S LIFE OF CONDE.  
BORROW'S GYPSIES OF SPAIN.  
MELVILLE'S MARQUESAS ISLANDS.  
LIVONIAN TALES. BY A LADY.  
MISSIONARY LIFE IN CANADA.  
SALE'S BRIGADE IN AFGHANISTAN.  
LETTERS FROM MADRAS.  
ST. JOHN'S HIGHLAND SPORTS.

## RARE BOOK COLLECTION



## THE LIBRARY OF THE UNIVERSITY OF NORTH CAROLINA AT CHAPEL HILL

Murray

1534

ACLAND'S CUSTOMS OF INDIA.  
GLEIG'S CAMPAIGNS AT WASHINGTON.  
RUXTON'S MEXICAN TRAVELS.  
CARNARVON'S PORTUGAL AND GALICIA.  
GLEIG'S LIFE OF LORD CLIVE.  
HAYGARTH'S BUSH LIFE.  
STEFFENS' PERSONAL ADVENTURES.  
TALES OF A TRAVELLER.  
CAMPBELL'S ESSAY ON POETRY.  
MAHON'S HISTORICAL ESSAYS.  
STOKERS AND POKERS—HIGH-WAYS  
AND DRY-WAYS.  
ST. JOHN'S LIBYAN DESERT.  
SIERRA LEONE. BY A LADY.  
GLEIG'S LIFE OF SIR THOMAS MUNRO.  
SIR FOWELL BUXTON'S MEMOIRS.  
IRVING'S LIFE OF GOLDSMITH.

\* \* \* Volumes may be had separately, Price 6s., in Cloth,

(Vols. 12 & 36, are 8s. 6d. each).

June, 1850.

